creative computing

December 1980
vol 6, no 12
$2.50

the #1 magazine of computer applications and software

Buying Guides to Personal Computers and Electronic Toys and Games

Nuclear Power Plant Simulation

Alvin Toffler: The Electronic Cottage

Comparisons of BASIC's

In-depth Evaluations of Sinclair ZX-80 and Radio Shack Pocket Computer

Superman Game

TRS-80* Model I Computer Owners . . .

Double-density storage. It's really here!

Here at Percom. And your authorized Percom dealers.

And double-density storage is here in a big way. Because now you can choose from *three different levels* of mini-disk systems — all *double-density rated.*

And get the storage that precisely meets your application needs.

Not to mention the service and quality that's made Percom the industry leader.

Although rated for double-density operation, all levels of Percom drives *work equally well in single-density* applications.

You can operate these drives in ordinary single-density format using TRSDOS*, Percom OS-80™ or any other single-density operating system.

Or, you can add a Percom DOUBLER™ to your Tandy Expansion Interface and store data and programs in *either* single- or double-density format.

Under double-density operation, you can store as much as *350 Kbytes* of formatted data — depending on the drive model — on one side of a five-inch minidiskette.

That's *four times* the capacity of standard Model I mini-disks, almost 100 Kbytes *more than* the capacity of the *eight-inch* IBM 3740 format!

Available in 1-, 2- and 3-drive configurations in all three model lines, Percom *burned-in, fully-tested* drives start at only $399.

TFD-40™ Drives

TFD-40 Drives store 180 Kbytes (double-density) or 102 Kbytes (single-density) of **formatted** data on one side of a 40-track minidiskette. Although economically priced, TFD-40 drives receive the same full Percom quality control measures as TFD-100 and TFD-200 drives.

TFD-100™ Drives

TFD-100 drives are "flippy" drives. You store twice the data per minidiskette by using both sides of the disk. TFD-100 drives store 180 Kbytes (double-density) or 102 Kbytes (single-density) **per side.** Under double-density operation, you can store a 70-page document on one minidiskette.

TFD-200™ Drives

TFD-200 drives store 350 Kbytes (double-density) or 197 Kbytes (single-density) on one side of a minidiskette. By comparison, 3740-formatted eight-inch disks store only 256 Kbytes. Enormous on-line storage capacity in a 5" drive, plus proven Percom reliability. That's what you get in a TFD-200.

the DOUBLER™ — This proprietary adapter for the TRS-80* Model I computer packs approximately twice the data on a disk track.



Depending on the type of drive, you can store up to four times as much data — 350 Kbytes — on one side of a minidiskette as you can store using a Tandy standard Model I computer drive.

Easy to install, the DOUBLER merely plugs into the disk controller chip socket of your Expansion Interface. No rewiring. No trace cutting.

And because the DOUBLER reads, writes and formats *either* single- or double-density disks, you can continue to run all of your single-density software, then switch to double-density operation at any convenient time.

Included with the PC card adapter is a TRSDOS*-compatible double-density disk operating system, called DBLDOS™, plus a CONVERT utility that converts files and programs from single- to double-density or double- to single-density format.

Each DOUBLER also includes an on-card high-performance *data separator circuit* which ensures reliable disk read operation.

The DOUBLER works with standard 35-, 40-, 77- and 80-track drives rated for double-density operation.

Note. Opening the Expansion Interface to install the DOUBLER may void Tandy's limited 90-day warranty.

Drive enclosures, power supplies Percom drive enclosures are finished in compatible silver enamel. Three sizes accommodate either 1, 2 or 3 drives. Drive power supplies are heavy duty, cool-running open-frame design. Three-wire ac power cords are safer, have lower noise pickup.

Free software patch This software patch, called PATCH PAK™, upgrades TRSDOS* for operation with improved 40- and 77-track drives. For single-density operation only.

Quality Percom products are available at authorized dealers. Call *toll free 1-800-527-1592* for the address of your nearest dealer or to order directly from Percom. *Prices and specifications subject to change without notice.*

™ trademark of Percom Data Company, Inc.

* trademark of Tandy Radio Shack Corporation which has no relationship to Percom Data Company.

PERCOM

PERCOM DATA COMPANY, INC.
211 N. KIRBY · GARLAND TX · 75042
(214) 272-3421

CIRCLE 177 ON READER SERVICE CARD



Management Information Display

Ultrasonic heart sector scan

High-resolution display with alphanumerics

Get the professional color display that has BASIC/FORTRAN simplicity

LOW-PRICED, TOO

Here's a color display that has everything: professional-level resolution, enormous color range, easy software, NTSC conformance, and low price.

Basically, this new Cromemco Model SDI* is a two-board interface that plugs into any Cromemco computer.

The SDI then maps computer display memory content onto a convenient color monitor to give high-quality, high-resolution displays (756 H x 482 V pixels).

When we say the SDI results in a high-quality professional display, we mean **you can't get higher resolution than this system offers in an** NTSC-conforming display.

The resolution surpasses that of a color TV picture.

BASIC/FORTRAN programming

Besides its high resolution and low price, the new SDI lets you control with optional Cromemco software packages that use simple BASIC- and FORTRAN-like commands.

Pick any of 16 colors (from a 4096-color palette) with instructions like DEFCLR (c, R, G, B). Or obtain a circle of specified size, location, and color with XCIRC (x, y, r, c).

*U.S. Pat. No. 4121283

Model SDI High-Resolution Color Graphics Interface

HIGH RESOLUTION

The SDI's high resolution gives a professional-quality display that strictly meets NTSC requirements. You get 756 pixels on every visible line of the NTSC standard display of 482 image lines. Vertical line spacing is 1 pixel.

To achieve the high-quality display, a separate output signal is produced for each of the three component colors (red, green, blue). This yields a sharper image than is possible using an NTSC-composite video signal and color TV set. Full image quality is readily realized with our high-quality RGB Monitor or any conventional red/green/blue monitor common in TV work.

Model SDI plugs into Z-2H 11-megabyte hard disk computer or any Cromemco computer

DISPLAY MEMORY

Along with the SDI we also offer an optional fast and novel **two-port** memory that gives independent high-speed access to the computer memory. The two-port memory stores one full display, permitting fast computer operation even during display.

CONTACT YOUR REP NOW

The Model SDI has been used in scientific work, engineering, business, TV, color graphics, and other areas. It's a good example of how Cromemco keeps computers in the field up to date, since it turns any Cromemco computer into an up-to-date color display computer.

The SDI has still more features that you should be informed about. So contact your Cromemco representative now and see all that the SDI will do for you.

Cromemco
incorporated
280 BERNARDO AVE., MOUNTAIN VIEW, CA 94040 • (415) 964-7400
Tomorrow's computers today

CIRCLE 130 ON READER SERVICE CARD

ZORK™ is more than an adventure.

Zork™ is a computer fantasy of ultimate challenge. Unearthly creatures guard treasures beyond your imagination. Mazes confound your guest. So quicken your wits and pick your path carefully through the Great Underground Empire. The least likely object may be the only thing that can save your life.

Yet, you can succeed. Discover the 20 treasures of Zork, return them to the Trophy Case and leave alive. But bring all the cunning and courage you can muster. Because in Zork, they take no prisoners . . .

Zork, The Great Underground Empire, was created by Infocom, Inc., and is available for 32K Apple® II and II Plus and 32K TRS-80™ Model I Level II disk systems.



Also new from Personal Software is MONTY™ Plays Monopoly,* which lets an Apple or TRS-80 play America's favorite board game with the family.

Arcade Classics is a new TRS-80 action game featuring Cosmic Raiders, Pinball, Ricochet and Blockade. A great way to have fun without feeding quarters into the machines.

Zork, MONTY Plays Monopoly and Arcade Classics—more fun and games with your computer, now joining our other Strategy Games: Microchess, Gammon Gambler, Checker King, Bridge Partner and Time Trek.

See these great strategy games at your Personal Software computer retailer. For the dealer nearest you, call Personal Software Inc. at 408/745-7841, or write 1330 Bordeaux Drive, Sunnyvale, CA 94086.

When you put your computer to work, use Personal Software™ Productivity Products: VisiCalc,™ DESKTOP/PLAN™ and CCA Data Management System.

PERSONAL SOFTWARE

Zork is a trademark of Infocom, Inc., Apple is a registered trademark of Apple Computer, Inc.; TRS-80 is a trademark of Radio Shack Division of Tandy Corp.; MONTY is a trademark of Ritam Corp.; Monopoly is a trademark of Parker Brothers, Inc.; MONTY is not sponsored or endorsed by Parker Brothers, Inc.

CIRCLE 170 ON READER SERVICE CARD

In This Issue

evaluations & profiles

articles

DECEMBER 1980 VOLUME 6, NUMBER 12

Creative Computing magazine is published monthly by Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. (Editorial office 51 Dumont Place, Morristown, NJ 07960 Phone: (201) 540-0445.)

Domestic Subscriptions: 12 issues $15,24 issues $28,36 issues $40. Send subscription orders or change of address (P.O. Form 3575) to Creative Computing P.O. Box 789-M, Morristown, NJ 07960. Call 800-631-8112 toll-free (in New Jersey call 201-540-0445) to order a subscription (to be charged only to a bank card).

Controlled Circulation pending at Richmond, VA 23228.

applications - games

fiction & foolishness

departments

The cover is an original water color painting done by Alan Kelly of *Creative's* order processing department.

Publisher/Editor-in-chief	David H. Ahl
Editor	Ted Nelson
Managing Editor	Burchenal Green
Associate Editor	David Lubar
Contributing Editors	George Blank Frederick Chesson Charles Carpenter Margot Critchfield Thomas W. Dwyer Stephen B. Gray Richard Kaapke Stephen Kimmel Harold Novick Peter Payack Alvin Toffler C. Barry Townsend Gregory Yob Karl Zinn
Editorial Assistant	Peter Fee
Secretary	Elizabeth Magin
Production Manger	Laura MacKenzie
Art Department	Diana Negri Chris DeMilia Patricia Balinski Joanne Fogarty
Typesetters	Debbie Barbagallo Jean Ann Vokoun
Advertising Sales	Renee Fox Christman Nancy Wood
Marketing Coordinators	Barbara Garris David Rogers
Software Development	Laura McLaughlin John White Chris Vogell Bob Calian Linda Barkaszi
Data Processing Coordinator	Keith Franklin
Software Production	Rita Gerner
Business Manager	Elizabeth Staples
Financial Coordinator	William L. Baumann
Bookkeeper	Patricia Kennelly
Retail Marketing	Jennifer Burr Laura Gibbons Jon Heuer
Circulation	Suzanne Guppy Frances Miskovich Moira Fenton Carol Vita Dorothy Staples
Customer Service	Patricia Brown
Office Assistants	Rosemary Bender Linda McCatharn Maria Petrakis
Order Processing	Jim Zecchin Alan Kelly Dorian Snipes Joan Swihart
Book Service Supervisors	Ronald Antonaccio William Rogalski
Book Service	Scott McLeod Nick Ninni Mark Archambault Mike Gribbon



Advertising Sales

Advertising Coordinator
Renee Christman
Creative Computing
P.O. Box 789-M
Morristown, NJ 07960
(201)540-9168

Western State, Texas
Jules E. Thompson, Inc.
1290 Howard Ave., Suite 303
Burlingame, CA 94010
(415)348-8222

Southern California
Jules E. Thompson, Inc.
2560 Via Tejon
Palos Verdes Estates, CA 90274
(213)378-8361

Mid-Atlantic, Northeast
CEL Associates, Inc.
36 Sohier Street
Cohasset, MA 02025
(617)383-6136

Midwest
Ted Rickard
435 Locust Rd.
Wilmette, IL 60091
(312)251-2541

New York Metropolitan Area
Nelson & Miller Associates, Inc.
55 Scenic Dr.
Hastings-on-Hudson, NY 10706
(914)478-0491

Southeast
Paul McGinnis Co.
60 East 42nd St.
New York, NY 10017
(212)490-1021

Responsibility

Creative Computing will not be responsible for the return of unsolicited manuscripts, cassettes, floppy disks, program listings, etc. not submitted with a self-addressed, stamped envelope.

OK to Reprint

Microform

Creative Computing is available on permanent record microfilm. For complete information contact University microfilms International, Dept. F.A., 300 North Zeeb Road, Ann Arbor, MI 48106 or 18 Bedford Road, London WC1R 4EJ, England.

Foreign Customers

Foreign subscribers in countries listed below may elect to subscribe with our local agents using local currency. Of course, subscriptions may also be entered directly to Creative Computing (USA) in U.S. dollars. (bank draft or American Express card). All foreign subscriptions must be prepaid.

Many foreign agents stock Creative Computing magazines, books, and software. However, please inquire directly to the agent before placing an order. Again, all Creative Computing products may be ordered direct from the USA — be sure to allow for foreign shipping and handling.

CANADA	Surface	Air
1-year	C $28	n/a
2-year	54	
3-year	78	

Micron Distrib.
409 Queen St. W.
Toronto, OT M5V 2A5, Canada

ENGLAND	£	£
1-year	10.00	19.00
2-year	19.50	37.25
3-year	28.50	55.00

CREATIVE COMPUTING
Attn: Hazel Gordon
27 Andrew Close
Stoke Golding, Nuneaton CV13 6EL
England

FRANCE	F	F
1-year	98	183
2-year	188	358
3-year	273	530

SYBEX EUROPE
14/18 Rue Planchat
75020 Paris, France

SWEDEN	kr	kr
1-year	100	188
2-year	193	368
3-year	280	544

HOBBY DATA
Attn: Jan Nilsson
Fack
S-200 12 Malmo 2, Sweden

GERMANY	dm	dm
1-year	42	78
2-year	80	152
3-year	116	225

HOFACKER-VERLAG
Ing. W. Hofacker
8 Munchen 75
Postfach 437, West Germany

HOLLAND, BELGIUM		f
1-year		108
2-year		210
3-year		300

2XF COMPUTERCOLLECTIEF
Attn: F. de Vreeze
Amstel 312A
1017 AP AMSTERDAM, Holland

AUSTRALIA	$A	$A
1-year	23	47
2-year	44	92
3-year	64	136

ELECTRONIC CONCEPTS PTY., LTD.
Attn: Rudi Hoess
Ground Floor 55 Clarence St.
Sydney, NSW 2000, Australia

JAPAN	Y	Y
1-year	5,700	10,700
2-year	10,900	21,000
3-year	15,900	31,000

ASCII PUBLISHING
Aoyama Building 5F
5-16-1 Minami Aoyama, Minato-Ku
Tokyo 107, Japan

HONG KONG	$HK	$HK
1-year	118	222
2-year	227	435
3-year	330	640

COMPUTER PUBLICATIONS, LTD.
22 Wyndham St., 7th Floor
Hong Kong

PHILIPPINES	P	P
1-year	175	330
2-year	338	650
3-year	490	955

INTEGRATED COMPUTER SYSTEMS, INC.
Suite 205, Limketkai Bldg., Ortigas Ave.
Greenhills P.O. Box 483, San Juan
Metro Manila 3113, Philippines

OTHER COUNTRIES		
1-year	$24	$45
2-year	46	88
3-year	67	130

CREATIVE COMPUTING
P.O. Box 789-M
Morristown, N.J. 07960, USA

LOWEST PRICES ON PERSONAL COMPUTERS

buy by mail and $ave

apple computer

Apple II personal computer.
16K
List $1195

ONLY $989

32K, List $1395 ..... $1169
48K, List $1259

DISK II DRIVE $420
Above w/Controller $505
MICROSOFT Z80/CPM
Conversion For Apple II ... ONLY $299
APPLE III
w/96K $2998

CENTRONICS PRINTER INTERFACE
Pascal Language System List $495 $420
Centronics
Printer Card List $225 ..... $191
High Speed
Printer Interface $195 ..... $165

COMPLETE LINE OF CALIFORNIA COMPUTERS
Interface cards available.
We also stock the
DC Hayes Micromodem, Mountain Hardware, and the **SSM combination serial/parallel interfaces.**

Personal Computer Systems

609 Butternut St.,
Syracuse, NY 13208
(315) 475-6800

VISA
master charge

Prices do not include shipping by UPS. All prices and offers subject to change without notice.

HEWLETT PACKARD

HP-85A ONLY $2795

HP-85 ACCESSORIES

5-¼" Dual Master Disc Drive List $2500 ..... **$2125**
5-¼" Single Master Disc Drive List $1500 ..... **$1275**
HP 7225A Graphics Plotter List $2050 **$1845**
HP-85 16K Memory Module List $395 . **$355**
HP-85 Application Pacs Standard List $95 ..... **$85**
Serial (RS-232C) Interface Module List $395 **$355**
GPIO Interface Module List $495 **$445**

IMAGINE A CALCULATOR YOU CAN CUSTOMIZE. IT'S HERE—THE HP-41C.

HP-41C
ONLY $244.95

hp CALCULATORS:

HP-32E Scientific w/Statistics ___ 53.95
HP-33C Scientific Programmable 99.95
HP-34C Advanced Scientific Programmable ___ 123.95
HP-37E Business Calculator ___ 58.95
HP-67 Handheld Fully Advanced Programmable Scientific for Business & Engineering ___ 298.95
HP-97 Desktop w/Built-in Printer. 579.95

TEXAS INSTRUMENTS
INCORPORATED

TI-99/4
home computer



CALL FOR PRICE

Commodore Pet
CALL FOR PRICE

PRINTERS FOR ALL COMPUTERS

ATARI®
A Warner Communications Company

PERSONAL COMPUTER SYSTEMS

List $1080
ATARI® 800™ PERSONAL COMPUTER SYSTEM. $849

ATARI® 810 DISC DRIVE
List $699.95 ..... **$589**

ATARI®
820™ Printer, List $599.95 . . . . **$499**
Atari® 400 List $630 . . . . $499

CIRCLE 240 ON READER SERVICE CARD

et cetera

et cetera

et cetera

Cooperation Games

During the past five years I and my students conceived and developed examples of computer-based cooperation games. As far as I have been able to determine I was the originator of the term "cooperation games" and of the concept it represents in computer-based games. I should be glad to hear from those interested in such games and particularly from those I have missed in my library research.

My discussion of cooperation games, these being ones in which cooperation is rewarded more than is competition among the players, is given in References 1 and 2. Cooperation games should become part of education and of interaction with others. Most computer games are competitive and often violently so. Any society or group in it affords obvious examples of cooperation and the need for it, so let's build it into our games for education and fun!

Those who wish to know more about the best version of LAFIS or Lost and Forgotten island, our most carefully developed game, should write to John Cox, 210 E. Newkirk, Tuscola, IL, 61953. We published the best version in Reference 3.

Creative Computing modified the game and published it in the March 1980 issue, called it "Another New Game from Creative Computing", and made me the author. The authors should have been Joe Taylor and John Cox, my students, with a credit line to Kent Waldrop, another student.

The Editor of *Creative Computing* has acknowledged these errors and kindly permitted me to publish this statement.

— Bruce Hicks*

References

1. Bruce Hicks, "Computer Outreach," *Computers and Society* v.7, no.3, pp. 10-14 (Fall 1976) and added references in v.7, no.4, pp. 1-2 (Winter 1977).
2. Bruce Hicks, "Peace Education: Cooperation Games and Simulations," *Peace and Change*, v.5, no.1, p. 62 (Spring 1978). Also see reprint of this note in "Notes on Recent Educational Applications of Computers," *ISEAC*** no. 15 (March 1978).
3. Joe Taylor and John Cox, "LAFIS — A Cooperation Game," *ISEAC*** no.36 (August 1979).

**Professor Emeritus*, Department of Secondary Education, University of Illinois, Urbana, IL 61801. *Professor*, Department of Electrical Engineering and Computer Science, Polytechnic Institute of New York, 333 Jay Street, Brooklyn, NY 11201.

**ISEAC Illinois Series on Educational Applications of Computers. Individual copies of reports are available from the Department of Secondary Education, University of Illinois, Urbana, IL 61801.

January Small Computer Conference

On January 16-17, 1981, the College of Education at Arizona State University, Tempe, Arizona will host a special small computer conference designed to introduce Educators to the many applications of computers in the classroom.

The overall goal of the conference is to provide an awareness of personal computers and their impact on society. In addition, ways that computers are currently being used in Education at the Elementary and Secondary levels, in the fine arts areas, in career and vocational education, and in special education, will be explored.

For registration materials and further information write to: Dr. Gary G. Bitter, Arizona State University, Payne 203, Tempe, Arizona 85281.



Call for Panelists, National Computer Conference, 1981

Interest is mounting for a panel to discuss Personal Robotics and Artificial Intelligence interests, applications, accomplishments. If you would like to participate in the Personal Computing Festival of NCC '81, and have expertise on a non-professional basis in robotics or AI, please write A. Gelles, 185 W. Houston St., NY, NY 10014. Send description of your area of interest, and content of a brief, 5 minute presentation, which you would be required to present as a panel member.

The conference will be held in Chicago, May 5-7, 1981. Obviously, attendance at the conference is mandatory for panel members, and is at your own expense. However, it is an honor to participate, and should be fun, to boot!

Machine Othello Tournament

The Board of Information Sciences and the Program in Experimental Psychology of the University of California at Santa Cruz have announced a two-day Othello tournament to be held January 17-18, 1981.

The tournament is open to all individuals or teams who register by January 10, 1981. Entries by individuals or teams operating small computer systems located at the tournament site are especially welcome. To register send your name(s), program designation, and equipment description to: Professor Peter W. Frey, 421 Kerr Hall, University of California, Santa Cruz, CA 95064. (408) 429-4005.



400 Pages
Includes Teacher's Manual, 25 Student Workbooks and 143 Transparencies

$159*
Cat. No. 26-2150

Introduce Your Students to Computer Programming Fundamentals Using the TRS-80™ Microcomputer and Radio Shack's New

Computer Education Series

Part I: "Introduction to BASIC"

A Classroom Program Developed by Professional Educators For Professional Educators

Because Radio Shack has built and sold over 200,000 TRS-80 personal computer systems, many to schools and students, we perceive a real need for formal instructional materials in computing. Thus we've created a wholly new Computer Education Series for teachers, and now offer its Part 1, entitled "Introduction to BASIC." As you may know, BASIC is an acronym for Beginner's All-Purpose Symbolic Instruction Code, and is by far the most popular program language.

Designed for classroom use with secondary students who have "hands-on" access to TRS-80, the very professional package includes a 400-page teacher's manual, 25 student workbooks and a set of 143 transparencies for standard overhead projectors. (Additional student workbooks may be ordered separately.)

Developed and field tested in public schools over a two-year period, this material is designed for use by all teachers, regardless of previous knowledge of computers and programming.

We believe that in a few years, people who lack a working knowledge of computers may well be among the educationally disadvantaged portion of the population! Watch for future announcements of additional programs in our new Computer Education Series.

Radio Shack®
The biggest name in little computers™
A DIVISION OF TANDY CORPORATION

*Retail prices may vary at individual stores and dealers

For more information on the Computer Education Series, fill coupon and send to:
Radio Shack Dept. CMA-81-A-162
1300 One Tandy Center, Fort Worth, TX 76102

Name _____

Address _____

City _____ **State** _____ **Zip** _____

Name of School _____

CIRCLE 147 ON READER SERVICE CARD



Input/Output

43 Splats!

Dear Editor:

I refer to *Basic Computer Games - Microcomputer Edition,* and the game "Splat" on pages 151-152.

In this game, line 550 is For J = 0TO42, line 610 is Goto 540. There is no line 540. Having made 43 successful jumps, the game shut down on me! I suspect the author had something like — "Give up, man, you must be wacked!", but I would be much obliged to receive the correct version from you. Being an "expert" jumper now, I can reach 43 in an hour or so!

Apart from this bug, your book has been most enjoyable.

B.D. Heand
85 Holland Road
Kensington, London W.14
England

Just change the DIM in Line 50 to a higher number, replace all references to 42 with the new number, and delete line 610. Then you can jump to your heart's content. But don't put in too large a number — arrays eat memory. — *DL*

The original program allowed for 4000 jumps (it was written on a larger timesharing system. The choice of 42 unsuccessful jumps was totally arbitrary. — *DHA*

Help Wanted

Dear Editor:

It was a disappointment not to find a Basic program included in the article "A Method of Interpolation" which appeared in the July issue of *Creative Computing* on page 54. The article appears to be a very significant contribution to the needs of those of us who use computers professionally.

Would you please advise whether a program for the above article can be obtained and how obtaining one can be accomplished?

Thank you very much.

D.H. Hodgins, President
Merchem Associates
P.O. Box 3610
New Haven, CT 06525

The article was a guideline. It's up to clever readers to put theory into practice. Perhaps one of you who has already done so can send a copy to Mr. Hodgins. — *DL*

Out of the Closet

Dear Editor:

Of all the computer applications journals around, I must say that *Creative Computing* is probably the most diversified in content. Fantastic magazine! Keep it up.

However, I would like to comment on the article "Smart Programs, Dumb Programs" by Michael Potts (September 1980). His article, regarding the use of computer software in Computer-Aided Instruction (CAI), seemed to me to miss the point as to the application of computers to education. In the article, Mr. Potts mentioned what he considered was good and bad in the current crop of CAI programming. Of course, some programs are better than others (and this doesn't just apply to educational/software), but the main point is in how effectively the computers are supported by the teaching staff. The world's greatest program is useless if it isn't properly backed up by classroom lessons and the like. On the other hand, a marginal program, such as one teaching kids the capitals of states, can still be a valuable tool as one facet of instruction, if it is well worked into a lesson. Computers can't be relied on to totally educate kids. I must agree with Mr. Potts on the fact that many schools are not willing to take the time to properly utilize a computer system. It is really a shame to see a valuable item like a computer go unused in many school districts around the country.

Fred Brunner
670 Dunnhill Dr.
Buffalo Grove, IL 60090

Another Conception

Dear Editor:

In facing the challenge put forth in "Self-Reproducing Program Revisited" ("It seems possible to write a shorter Basic version . . . ", July 1980), I wrote two shorter programs which will run on a TRS-80 Level II machine:

```
5 READ A$, B$: PRINT A$; B$; CHR$(34); A$;
CHR$(34); CHR$(44); B$: DATA"5 READ A$, B$: PRINT
A$; B$; CHR$(34); A$; CHR$(34); CHR$(44); B$:", DATA
```

Or using no DATA statement —

```
5 A$="5 A$=: PRINTLEFT $(A$,6); CHR$(34); A$;
CHR$(34); RIGHT$(A$,52)": PRINTLEFT $(A$,6);
CHR$(34); A$; CHR$(34); RIGHT$(A$,52)
```

The second program requires that the command "CLEAR 52" be entered before it can be run successfully.

J.A. Snyder
2406 Washington Ave
Wilmington, DE 19805

At $795*, how tough can these new Tigers be?

Introducing the new Paper Tiger™ 445 with the most rugged printing mechanism ever put in a low-cost matrix printer.

The 445 comes with a reliable ballistic-type print head and an advanced cartridge ribbon that lasts four times longer than many cassette or spool ribbons. Two separate heavy duty motors drive the print head and advance the paper. Plus you get true tractor paper feed.

And the new 445 gives you the performance you expect from the Paper Tiger family of printers. You can software-select character sizes, print 80- and 132-column formats, adjust paper width and length, even generate six-part business forms. All at unidirectional print speeds to 198 characters per second.

Need more stripes? Specify DotPlot™, a sophisticated raster graphics option.

If you've got an Apple**, TRS-80*** or other personal computer, get your paws on the tough new Paper Tiger™ 445 from IDS.

The people who invented low-cost matrix printing just growled.

Call TOLL FREE 800-258-1386 (in New Hampshire, Alaska and Hawaii, call 603-673-9100.)
Or write:
Integral Data Systems, Inc.,
Milford, New Hampshire
03055.

Paper Tiger 445

Integral Data Systems, Inc.

*Suggested U.S. retail price.
**Apple is a trademark of Apple Computer Inc.
***TRS-80 is a trademark of Radio Shack, a division of Tandy Corp.

CIRCLE 207 ON READER SERVICE CARD

You Can Get There From Here

Dear Editor:

In reply to Steve Gray's column in the May issue, I noted that you couldn't find a way to draw a single continuous circle using the Cartesion plotting formula. Actually, it is done quite simply. The new routine (really your old routine with the changes marked in bold) is listed below:

```
100 to 130: no changes
140 FOR X = -R TO 3*R STEP S
150 IF X <= R THEN B = X ELSE B = 2*R-X
160 IF X >R THEN A = 1
170 Y = SQR (R*R - B*B)
180 IF A = 1 THEN Y = -Y
190 SET (7*B + 64, 3*Y + 24)
200 NEXT X
210 GOTO 210
```

Gabor Salamon

Divide and Conquer

Dear Editor:

The May 1980 issue of *Creative Computing* contains an article entitled "In Search of Pi" (p124).

Although lacking in mathematical rigor and elegance, an excellent approximation to the value of Pi is obtained from

Pi = 355/113.

This simple expression provides a value (3.141592920 . . .) which approximates Pi to an accuracy of 0.0000085%!

J. Warshawsky, Ph.D.
Vice President Research and Development
The Fuller Company
2040 Avenue C, P.O. Box 2040
Bethlehem, PA 18001

Babylon

Dear Editor:

I have been following, with interest and approval, Dr. Weiss' series on effective writing. Any efforts to reduce the bafflegab and verbal gookum that increasingly blunt American English are welcome. But yet —

Words are tools. General words and terms are surely better for conveying broad, clear concepts. However, it's a shame to use a hatchet where a scalpel seems to be called for. I admit that the word "facilitate" can be spinecurdling when encountered in every other paragraph of a report or paper. But to yank out "facilitate" and plug in "help" is to shorten at the expense of fullness of transmission of meaning. "Help" means to aid. "Facilitate" means to make easier. We "help" people to find the elevators in buildings, and we "help", for instance, handicapped or elderly people into the elevators. We "facilitate" movement between floors by designing them into the blueprints. As long as I am picking nits, I must say that to substitute "hurt" for the much righer word "inhibit" is really needless pruning. "Hurt" implies damage, diminishment, pain. "Inhibit" speaks of holding back, impeding, keeping (not necessarily negatively) from advance. Example: I built a household robot. My programming skills were not good enough. The robot ran wild and smashed the furniture, also ran over my foot. I reprogrammed the robot to recognize my foot and no longer hurt it. I inhibited the robot. It never inhibited my foot. A couple more of these short sentences and I'm going to inhibit myself.

Sarcasm aside, you can see what I'm getting at. Shakespeare, the translators of the King James Bible, Mark Twain and Loren Eisely didn't bequeath us this rich, lovely language so that we had to choose between polysyllable flak and grunt-and-point.

Or, to put it in a fashion calculated to give Dr. Weiss the itch, Refrain from defenestration of the infant subject during the ejection of the aqueous laundering medium.

Kenneth P. Greene
1692 Haight Street
San Francisco, CA 94117

The Agony and the Exidy

Dear Editor:

What Ben Cushing, in "Dear Humans, Start at Line 10," (September 1980) knows about Basic may be good and useful; but it appears that he doesn't know Basic well enough to teach his Exidy Sorcerer to write English correctly.

According to Mr. Cushing's letter, *should'nt* would be, I suppose, the contraction of *should ont*. Then he talks about *PET's* and *Apple's* as though they possess something, but neglects to explain what they possess. Since he must surely have meant *PETs* and *Apples* as plurals, I can only wonder why he was not at least consistent, constructing the opening sentence as *Many reader's of CC seem to be conscious of the shortcoming's of Basic in the area of control structure's . . .*

Maybe if the technique he suggests "does ont pan out on PET's and Apple's," it is because they know more about English than his poor mistaught Exidy!

T. E. Bailey
Associate Professor
Department of Computing and Information Services
Oklahoma State University
Stillwater, OK 74074

This is one reason we run an Effective Writing column in Creative Computing. —*DHA*

Just Deserts

Dear Editor:

Crossing the hot desert sands is a lot easier than the method hinted at in the solution given (August 1980, page 134). Anyone taking the trouble to go through this entire solution in detail would be awed at the inefficiency of the last few steps. At one point, the truck would be in the middle of the desert, with 50 gallons of gas, plus several 10-gallon caches running back toward the starting point. The solution given would have the truck return to base, gas up, and return to the middle, where 40 gallons would be left, waiting to carry it to the other side. But why not use those 40 gallons immediately to finish the crossing?

This simple change would reduce the gas used to 16 tankfuls. The best strategy can manage with slightly less than 8 tanks!

The technique of "working backwards" is ideal for this problem. The final goal is to be on the other side of the desert. The situation needed to produce this is to be one tankful away from the other side, with a full tank of gas (using numbers as in the problem and solution, this means to be at the 400-mile mark, with 40 gallons of gas). Producing this situation is now the goal we consider.

Clearly we would have to bring some gas forward to the 400-mile mark from a previous point, leave some gas, go back

EXCITING NEWS FOR INVESTORS WITH TRS-80™ 32K DISK-BASED SYSTEMS!

Standard & Poor's proudly announces STOCKPAK, a unique software and data system to help you meet your investment goals like a Wall Street professional.

STOCKPAK not only delivers a "stand-alone" Portfolio Management System but also gives you the software for Standard & Poor's monthly Common Stock Data Service (available to TRS-80 owners on a subscription basis). With STOCKPAK and the Data Service you command one of the most powerful and versatile investment tools available.

Here's How STOCKPAK Will Help You:

A 900 COMPANY DATA BASE SERVICE

Monthly Data Service subscribers receive a diskette containing 30 vital financial items on 900 of the most widely traded stocks (S&P "500" and 400 NYSE, ASE and OTC issues). Accompanying this monthly diskette is an Investor's Newsletter highlighting important financial news and investment strategies, with suggestions for maximizing the usefulness of the system.

STOCKPAK SELECTION SYSTEM

The heart of STOCKPAK is a powerful, analytical stock selection tool which enables investors to choose stocks which meet their investment criteria. For example, you may wish to select only those oil and gas stocks with price/earnings ratios of less than 7 and yields of 6% or more. Once a group of stocks has been selected, you can store it as a separate data file for continuing use.

REPORT WRITER

You can define the report formats you would like to see on those stocks meeting your investment objectives. Hundreds o calculations and ratios that you define can be sorted, averaged or totalled, and displayed on video screen or optional printer.

PORTFOLIO MANAGEMENT SYSTEM

Now you can effectively evaluate and manage your own stock portfolio of up to 100 securities with as many as 30 transactions for each. You can record "buy" and "sell" transactions, price and dividend information and stock splits for instant retrieval, for record keeping and tax purposes. You can measure actual performance or create hypothetical situations to help you make "buy" or "sell" decisions.

HOW TO ORDER STOCKPAK

STOCKPAK is designed exclusively for TRS-80 users with 32K business systems with two mini-disk drives. You can obtain the basic software and sample Data Base, plus a comprehensive User's Manual from your local Radio Shack Store for only $49.95. The STOCKPAK Monthly Data Updating Service can be ordered directly from Standard & Poor's for $200 annually, or from the order form provided in the basic package you purchase from Radio Shack.

Standard & Poor's Corporation

25 BROADWAY, NEW YORK, NY 10004 (212) 248-3994/3374

CIRCLE 254 ON READER SERVICE CARD

And one that costs you a buck.

One: Buy a new TeleLink™ I cartridge for your ATARI 400™ or ATARI 800™ computer and get one free hour of CompuServe Information Service time.

Two: Visit a Radio Shack® computer center. Most are equipped to access the CompuServe Information Service now. Log in and see what you can get. The service is compatible with any TRS-80™ including the new VIDEOTEX™ unit.

Three: Send $1.00 to us and we'll send you the current "menu" of services, including the sophisticated big mainframe power of MicroNET. Send $1.00, name and address to: CompuServe, Information Service Division, 5000 Arlington Centre Boulevard, Columbus, Ohio 43220.

All this is yours to command.

Access to news and entertainment data bases, computer games and art, regional newspapers, newsletters, programs, languages, storage (up to 128k free!) and lots more is yours for 8⅓ cents per minute (between the hours of 6 pm and 5 am weekdays and all day weekends), billed to your charge card. It's a local phone hook-up in more than 260 U.S. cities.

MicroQuote has historical and statistical data on almost every stock, bond or option you can buy. Corporate financial information, commodity prices and financial newsletters are also available.

And, when you're ready for big-time computer action...

You need a computer to use all the MicroNET services which put you in command of our big, fast mainframe computers. But even with the simplest terminal you can send electronic mail to any other user, use the CB simulator, and try to zap the enemy's spaceships in real—and very fast—time. Many networking multi-player games available.

CompuServe is working with 11 major regional newspapers to bring you their electronic editions, as well as the Associated Press news and sports wires.

Simple games and graphics for the beginner. And, when you're ready—try the really tough ones on MicroNET (see MicroNET service). You haven't lived until you discover a player from Los Angeles in *your* dungeon!

See for yourself what a state-of-the-art electronic information service can do. Get a demonstration at a Radio Shack® computer center or send $1.00 for a current menu today.

CompuServe is continually adding new on-line information resources. So, order our current menu and watch for new features such as an electronic encyclopedia, travel information, food preparation and gardening tips, government publication data—and much more!

CompuServe

Information Service Division
5000 Arlington Centre Blvd.
Columbus, Ohio 43220
(614) 457-8600

CIRCLE 134 ON READER SERVICE CARD

I/O, cont'd...

and get more gas, and proceed again to the 400-mile mark. Best efficiency occurs if the truck runs out of gas just as it returns to the previous point where it can get more, and if it takes on a full 40 gallons each time. If so, then 40 of the total 80 gallons are burned in 3 one-way trips, meaning each such trip is 400/3 = 133 1/3 miles.

Thus we can get across, if we reach a point 266 2/3 miles out, with 80 gallons of gas: for then we tank up, drive 133 1/3 miles forward, deposit 13 1/3 gallons, drive back 133 1/3 miles, fill up with the 40 gallons left there, and drive forward 133 1/3 miles — leaving us 400 miles out, with 26 2/3 gallons in the tank and 13 1/3 more that we pick up there.

How do we get 266 2/3 miles out, with 80 gallons? By starting 186 2/3 miles out with 120 gallons: then make two trips out 80 more miles and back, depositing 24 gallons each time, followed by a no-return trip out which leaves us with 32 gallons in the tank.

Et cetera. The distances of the legs between depots, measured in tankfuls of gas, are successively 1, 1/3, 1/5, 1/7, . . . A solution is obtained when we take enough legs so that these sume up to at least 2, which occurs for 8 legs: 1 + 1/3 + 1/5 + 1/7 + 1/9 + 1/11 + 1/13 + 1/15 is about 2.022.

The fact that this sum is slightly greater than 2 means either (a) using 8 full tanks, we could end up on the far side of the desert with about 0.022 tank (0.88 gallons) left; or (b) we could accomplish the task with less than 8 tanks, in fact about 7.673 tanks, starting our trek with 7 1/2 round trips out to a distance of about 17.95 miles.

It is worth noting that since the sum 1 + 1/3 + 1/5 + 1/7 + . . . "diverges to infinity" (i.e. gets as large as you want, if you take enough terms), the problem can be solved no matter how wide the desert is. For instance, if the desert is 10 tankfuls wide, count how many terms of the sequence are required to sum at least 10; that tells how many tankfuls will actually get you across.

Robin Ault
Concolor Allied Technical Services
45 Dexter Road
Newtonville, MA 02160

Pass Go Do Not Return To Basic

Dear Editor:

Before I got my Apple II+ in December 1979, I had been long since using Apple II computers and was just beginning to use assembly-language — wow, how convenient the reset key finally seemed: it interrupted the assembly program and left me in the monitor.

With the Apple II+, though, I was denied of that convenience, because with Autostart-Rom the reset vector goes into Applesoft Basic — terribly inconvenient for a machine user.

Then, after nearly a year of struggling, I've finally solved the problem with five pokes. They are:

115,136	$73:$88
116,24	$74:$18
1010,113 or, from monitor:	$312:$71
6280,105	$1888:$69
6281,255	$1889:$FF

The last two pokes can be set to anything. I've arbitrarily chosen the entry to the monitor. They decide where you end up.

The only drawback of the trick is that it restricts the programmer to 4K of program-space, but, for a machine programmer who grows weary of going in and out of Basic each time he hits reset, it is plenty.

Eric Shirley
89 Southampton Avenue
Berkeley, CA 94707

Out of Sorts

Dear Editor:

Regarding the article on sorting in the September 1980 issue and the Heapsort algorithm, I offer the following observations.

I compared the Heapsort to the Shell/Metzner sort. When the list to be sorted is disordered, the Heapsort appears to be about 10-15 percent faster. However, when the list to be sorted is partially ordered the Shell/Metzner sort is up to 2.25 times faster than the Heapsort.

Not only that but the Shell/Metzner sort is even smaller than the Heapsort and also requires no auxiliary storage. The test I made showed the Heapsort to require 591 bytes (for the program only) whereas the Shell/Metzner sort required only 445 bytes (again for the program only.)

On balance, if one is not sure of the "orderedness" of the list to be sorted, the Shell/Metzner sort is probably the better choice.

Below is a listing of the Shell/Metzner sort.

```
 90 REM SHELL/METZNER SORT
100 LET Y=V
110 LET Y=INT(Y/2)
120 IF Y=0 THEN 250
130 LET K=V-Y
140 LET J=1
150 LET I=J
160 LET B=I+Y
170 IF A(I)<=A(B) THEN 220
180 LET L=A(I)
190 LET A(I)=A(B)
200 LET A(B)=L
210 IF I=>1 THEN 160
220 LET J=J+1
230 IF J>K THEN 110
240 GO TO 150
250 RETURN
```

(array "A" contains the values to be sorted; "V" is the number of elements in the array; i.e., the number of items to be sorted)

Leland C. Sheppard,
Sheppard Software Co.
1523 Coronach Ave.
Sunnyvale, CA 94087

One reason we have run so much material on sorting techniques over the years is that different sorts lend themselves to different jobs. I can find little justification for ever using the popular bubble sort or delayed replacement but other sorts such as Shell/Metzner, Heapsort, Woodrum, etc., all have a place. Five sorting techniques and two shuffling algorithms are described in the 19-page "Sorting, Shuffling and File Structures" reprint available for just 50 cents postpaid from Creative Computing. — *DHA*

NOW THE SOFTCARD™ CAN TAKE YOU BEYOND THE BASICS.

You probably know about the SoftCard — our ingenious circuit card that converts an Apple II® into a Z-80® machine running CP/M®.

You may even know that with the SoftCard, you get Microsoft's powerful BASIC — extended to support Apple graphics and many other features.

Now, whenever you're ready to get beyond the BASICs, the SoftCard can take you into whole new realms. Starting with two advanced language packages from Microsoft.

FORTRAN AND COBOL TO GO.

Now you can run the world's most popular engineering/scientific language and the most popular business language on your Apple. Think what that means: you can choose from literally thousands of "off-the-shelf" applications programs, and have them working with little conversion. Or design your own programs, taking advantage of all the problem-solving power these specialized languages give you.

FORTRAN-80

A complete ANSI-standard FORTRAN (except COMPLEX type), with important enhancements. The extremely fast compiler performs extensive code optimization, and, since it doesn't require a "P-code" interpreter at run time, your programs will typically execute 2-3 times faster than with Apple FORTRAN.

FORTRAN is easy to learn if you know BASIC, and the package includes a huge library of floating point, math, and I/O routines you can use in all your programs.

COBOL-80

Virtually the only choice for serious business data processing. It's ANSI 1974 standard COBOL, with many user-oriented features added: formatted screen support for CRT terminals, simple segmenting of very large programs, powerful file handling capability, trace debugging, and much more. A separate Sort package is coming soon.

FORTRAN-80 and COBOL-80 are just two more reasons why the Apple with SoftCard is the world's most versatile personal computer. Get all the exciting details from your Microsoft dealer today. And start getting beyond the BASICs.

MICROSOFT Consumer Products, 400 108th Ave. N.E., Suite 200, Bellevue, WA 98004. (206) 454-1315.

MICROSOFT

CIRCLE 168 ON READER SERVICE CARD

Mountain Computer makes more peripherals for the Apple Computer than Anybody.

and . . . a place to put them

INTROL X-10

Intelligent Home Controller for lights and appliances. Real-time schedules and energy conservation. Complete applications software package. Home security with random scheduler. Power usage accounting package for home energy cost control. No wiring required.

APPLE CLOCK

Real-time and date information. Interrupts permit Foreground/Background operation of two programs simultaneously. Battery back-up. Crystal-controlled for .001% accuracy. Onboard ROM for easy access from BASICs. Supports PASCAL. Time from one millisecond to one year.

SUPERTALKER SD200

Input/Output Speech Digitizer. Permits talking programs. I/O capability allows interactive programs with speech-prompted inputs. Use output for speech directed activities in business systems: announcements in a control-room, or sound effects in entertainment programs. Easy to use because input as well as output is under user control with special software operating system.

ROMWRITER

Program your own EPROMs. Create your own firmware. Programs 2K 2716 5V EPROMs. Disk software package provides easy EPROM programming. EPROMs are verified after BURN. RUN your programs from on-board socket or install them on ROMPLUS+.

ROMPLUS+

More power for your system through firmware. Six sockets accept 2716 EPROMs or ROM equivalents. Six or any combination can be used at once. Scratch-pad RAM and two TTL connectors. Special 2K ROMs available for powerful system enhancement. Keyboard Filter ROM—COPYROM—Others coming soon.

MusicSystem

Sophistication previously available only on experimental mini and mainframe computer synthesizers. Digital instrumental music synthesizer system. 16 voices in stereo. Instrument definitions simulate the sound of real instruments—and more. Fully programmable waveforms. Envelope Control. Composition system—sheet music input using standard music notation. Chords and multi-part scoring up to 16 voices. A true instrument that anyone with an Apple can play.

A/D+D/A

16 channels analog to digital input. 16 channels digital to analog output. Eight bit resolution. Super-fast 9μsec conversion time. Monitor and output to the real world. All on one card.

EXPANSION CHASSIS

By popular demand! Eight more slots for your Apple. Attractive sturdy enclosure. Its own heavy duty power supply. Easy to use. Address cards in Expansion Chassis the same way as in your Apple. Only one additional command to specify in Apple or in Expansion Chassis. Compatible with all Apple peripherals.

CardReader

At last! An intelligent, high-quality device for data entry from user-marked cards. Implement BASIC programming, examination scoring, inventory maintenance and other applications requiring off-line data preparation for batch entry later. Connects to any computer having RS-232 interface. Software and cards are available for jobs in business, science and education.

MOUNTAIN COMPUTER has the most comprehensive line of Apple peripherals available. Anywere. From anybody. We know the Apple inside and out and are committed to providing the most innovative and unique products to expand and enhance its capabilities and use. After all, we were the first company to make an Apple peripheral—except Apple Computer.

Available at Apple Dealers worldwide

Mountain Computer
INCORPORATED

300 Harvey West Blvd., Santa Cruz, CA 95060
(408) 429-8600 TWX 910 598-4504

Apple is a trademark of Apple Computer Inc.

CIRCLE 191 ON READER SERVICE CARD



To Subscribe, Extend or Renew

creative computing

at the old rate.

Term	Rate until Dec. 31, 1980	New Rate	Single Copy Price
1-year (12 issues)	$15	$20	$30
2-year (24 issues)	$28	$37	$60
3-year (36 issues)	$40	$53	$90

Use the order card in back or the handy form on the back of this flap.

Get the most out of your computer!

Creative Computing, the Number 1 applications and software magazine is packed with pragmatic, well-documented programs for all kinds of computers from small to large.

In-depth Evaluations

Objective, probing evaluations of software and hardware help you make well-informed purchase decisions. More than once, our hard-hitting, honest evaluations have cost us an advertiser, however we feel that our first obligation is to you, our reader.

Programming Techniques

Creative presents innovative and useful programming ideas. For example, six entirely different sort methods appeared in recent issues. We try to make material understandable to the newcomer as well as interesting for the experienced user.

Subscribe Today

Mail this card or call credit card orders toll-free to **800-631-8112** (in NJ, 201-540-0445).

creative computing

Term	*USA*	*Canada and Foreign Surface*	*Foreign Air*
1-yr (12 issues)	☐ $15	☐ $20	☐ $30
2-yr (24 issues)	☐ $28	☐ $37	☐ $60
3-yr (36 issues)	☐ $40	☐ $53	☐ $90

☐ New ☐ Renewal

☐ Payment enclosed

☐ Please bill me ($1 billing fee. Foreign orders must be prepaid.)

☐ Visa ☐ Master Card ☐ American Express

Card No. _____

Expiration date _____

Signature _____

Name _____

Address _____

City _____

State _____ Zip _____

electronic toys and games

Part II

David Lubar

Following is presented a wide selection of toys and games, from the fast paced to the cerebral. There should be something for everyone.

Safari, Basketball, and Bukka-Bukka Bath Toys from Bambino

Safari was a favorite with the staff. The object is to track down and cage wild animals. Four keys are used to move the cage, a fifth key shuts the door. If an animal is inside, you get a point. If you make seven captures in a row without missing, an eighth capture, when made in a corner, will net bonus points. Misses reduce your score. The animals appear at random and hop around the field, evading the cage. There are three skill levels, the third of which seems almost unconquerable.

Basketball, with tiny little players done in remarkable detail, is great fun. It can be played solo or in competition. The player attempts to move past computer-controlled opponents without losing the ball. This is done by changing dribbling heights to high, medium or low, depending on the stance of the opponent. At any point, the player can attempt a shot. The closer he is to the basket, the less the chance that the shot will be blocked. The game is timed with nine-minute quarters. Between turns, the player can press a button and see the score. I've raved enough about Bambino. Rather than say any more about their graphics or games in general, I'll leave it to you to go to the stores and see the games for yourself.

Bukka-Bukka Bath Toys are not electronic, but they are modern and innovative enough to be listed here. These small plastic animals float in the tub. Each has several windows, inside of which a number can appear. The number is the centigrade temperature of the water. This seems to be a step above elbow dipping, both in ease and accuracy.

The Sound Gizmo from Fundimensions

Shaped somewhat like a large safety razor, *The Sound Gizmo,* as the name implies, produces sounds. Each sound is composed of several variables. First, a sliding switch selects the basic sound, such as train, motor, or explosion. Then three knobs can be used to determine volume, pitch, and speed. Finally, two switches can be pressed; one produces constant sound, the other gives fading bursts. With all this potential for experiment, *The Sound Gizmo* is a nice toy with uses limited only by a child's imagination.

Quickfire and Vagabondo from Invicta

Quickfire is a two-player target game with three levels of skill. The players use a gun which shoots a beam of light at three targets. Lights above the targets indicate which target to shoot. Six games are available with the unit. One involves shooting the targets in any order, another requires you to match the pattern that is flashed. The unit, unlike earlier versions of light-gun games, works well even if the room isn't totally dark. Sound effects accompany play, and the time used by each contestant is displayed at the end of a round.

Vagabondo is a board game in which players take turns placing pieces on a board, trying to score points by covering territory and by meeting other pieces. Each player has pieces that are one of several shades, and no two pieces of the same shade can touch. *Vagabondo,* following the lead of other games from Invicta, is a contest of strategy, not luck.

Redline Electronic Drag Race from Kenner

Another winner, *Redline* simulates a drag race. The player selects the type of car he wants to drive, waits for the green light, and burns rubber. A tachometer helps you avoid blowing your engine as you shift through the gears. The sound effects are very realistic. At the end of a race, the elapsed time and speed are shown. Unfortunately, the elapsed time doesn't stay on the screen for long. If you want, two *Redlines* can be attached with a cable, allowing for competitive drag races.

Rubik's Cube from Ideal

This marvelous gadget has received a lot of coverage. A cube of twenty-seven blocks, it can be rotated in segments around any of three cross sections. The object is to obtain six faces of solid color. The cube comes correctly assembled. After a few minutes of experimenting with the unique properties of Rubik's Cube, you'll find it presents a jumble of colors that may never be whole again.

Electron Blaster from Vanity Fair

This game was another favorite with the staff. In *Electron Blaster,* you move a ship back and forth between three columns, trying to shoot down the aliens that are moving toward you. Sound familiar? To win, you have to get 99 points before time runs out. There are three skill levels. If the aliens reach the bottom, or if you are hit three times, you lose. At the top skill level, the aliens move rather rapidly, making the game a real challenge.

The Pothole Game from Cadaco

This one is really electrical, not electronic, but it just seemed different enough to include. Two players steer their cars, trying to avoid the holes, as a beltway moves beneath them. Each car has marbles inside, which drop through the holes. When you lose your marbles, you lose the game. We had a bit of trouble getting the mechanism running since the belt had a tendency to snag. But, once running, the game is fun, though it might be a bit too fast-paced for some children.

WE CAN TAKE YOU FROM WATERLOO TO THE SUPER BOWL. (By way of the North Atlantic.)

In the few short months since we introduced Computer Bismarck™, we've transported over 2500 adventurous minds to the North Atlantic – there to recreate the historic battle between the awesome German warship and the British Home Fleet. The startling realism and excitement of that experience have prompted many well-seasoned travelers to proclaim it "...unique among computer games and board games alike.*" One enthusiast had this to say: "The wealth of detail...is hardly short of fantastic. Only real war rooms...in the Pentagon have ever before been able to simulate a battle in this manner.**" Now we offer two more strategy games to embark you on new flights of the imagination.

COMPUTER NAPOLEONICS™

takes you to the battlefields of Waterloo on the fateful day of June 18, 1815. Here, the greatest battle ever fought is about to begin, awaiting only your commands to set the amassed armies in motion.

You and your friend choose your role – either as the military genius, Napoleon, or as the Duke of Wellington, the iron-willed leader of the Anglo-Allied forces. The video screen displays the map of the Belgian countryside with the artillery, infantry, and cavalry units under your respective commands.

AS NAPOLEON, you must utilize your superior combat strength and numbers to deal Wellington a quick and decisive defeat before his Prussian ally can supply reinforcements. Speed is of the essence. But any tactical blunders in military deployment will result in a repeat of history – Napoleon's ignominious defeat.

AS THE DUKE OF WELLINGTON, you must not only survive the onslaught of the French artillery, cuirassiers, and the dreaded Imperial Guard, you must also inflict sufficient damage to Napoleon's forces to prevent his relentless northward march of conquest.

THE COMPUTER, in our solitaire scenario, plays Wellington while you play Napoleon. Two levels of play are provided by making the entry of Prussian reinforcements variable. This makes the need for French military decisiveness and devastating execution even more critical.

FOR THE NOVICE AND THE ADVANCED. Computer Napoleonics has all the advantages of your basic, traditional wargame –meticulous detail, realism, and playability. Plus one. Because the computer keeps track of all the rules, neither player can make an illegal move. This makes learning it a cinch (mastery is quite another matter), and it will convert the novice wargamer into a fanatic in no time.

The advanced wargamer will find the computer a worthy opponent indeed, and the two levels of play in the solitaire version will challenge the most experienced of strategists.



COMPUTER QUARTERBACK™

propels you onto the playing field of the Super Bowl. From its multiple offensive and defensive plays and its real-time playing conditions to the animated video display of the grid-iron and the halftime statistics, no strategy football game has ever been more complete in detail or as exciting in realism. Three versions are offered: Semi-Pro, Pro, and Computer-as-Opponent.

SEMI-PRO presents you with a choice of 18 offenses and 14 defenses. Here, you will begin to learn the intricacies of football; the thrill of the perfectly executed two-minute drill; the agony of the fumble, interception, and penalty. On offense, you will learn to read the defense and call audibles as needed.

After you have mastered the Semi-Pro version, it's time to move on to the Big Time...the Pro version!

THE PRO VERSION not only gives you every offense (36) and defense (24 plus double-teaming capabilities and special alignments) you could ever want, it also gives you the team you want! With 2.7 million computer dollars, you get to draft a team to your style and specifications. Spend more on your quarterback and receivers and your passing game may very well be unstoppable...but your running game may suffer for lack of funds.

THE COMPUTER eliminates all the organizational drudgery of conventional board games. It plays scorekeeper, referee, umpire, and linesman. As timekeeper, it makes you play in real-time. Take longer than 30 seconds to hike the ball and five yards will be marched off against you for delay-of-game.

"THE ROBOTS" is the team most ably coached by your friendly computer. It's ready to play any time you are. It even "learns" your tendencies and patterns through time, and it will make the necessary tactical adjustments. It plays so well you must be in top form to stand a chance against it.

All you need to start on these mind journeys is an Apple II with Applesoft ROM card, 48K memory, and a mini-floppy disc drive. For $59.95, Computer Napoleonics comes with the game program mini-disc, two mapboard cards, a rule book, and two player-aid charts. Computer Quarterback, for $39.95, gives you the game disc, a rule book, and four play diagram charts.

Credit card holders, call **800-648-5600 (toll free)** and charge your order to your VISA or MASTERCHARGE. In Nevada, call 800-992-5710. For Computer Quarterback, ask for Operator 178; for Computer Napoleonics, Operator 179.

While you're at it, you can also get our other games:

- *Computer Bismarck* for your Apple: $59.95 (Operator 180)
  Computer Bismarck, TRS-80 48K Disc: $59.95;
  32K Cassette: $49.95
- *Computer Ambush* (a tactical simulation of man-to-man combat in World War II) for your Apple: $59.95 (Operator 181)

To order by mail, send your check to Strategic Simulations Inc., Dept. CC, 450 San Antonio Road, Suite 62, Palo Alto, CA 94306. Our 14-day money back guarantee assures your satisfaction.

STRATEGIC SIMULATIONS INC.

*Creative Computing, Aug. 1980.
**Popular Mechanics, Aug. 1980.

CIRCLE 256 ON READER SERVICE CARD

Apple is a registered trademark of Apple Computer Inc.
TRS-80 is a registered trademark of Tandy Corporation.

Melody Madness from GAF

This is a musical version of concentration. The player or players press a button, which produces a tune. Then, a second button must be found which produces the same tune. Once matched, a button will no longer play the tune. There are several skill levels, and the tunes are reassigned to new buttons for each game. Another option allows the unit to be used as a musical instrument. Number-coded songs are included in the instruction manual. All in all, the game is a nice variation on an old concept.

Strobe from Lakeside

The game is composed of a unit with four arms. Each arm has a light on the end and a concealed panel of buttons. In various games, the object is to send the light on to the other player or players by pushing the correct button. One to four can participate. When a player misses, he is out of that round. Unfortunately, this quickly reduces the game to a contest between two players, where each has only one button to press. *Strobe* would be more interesting if it kept a running score and allowed all players to stay in until the end.

Le Game from EDI

Actually, this is Le *Many* Games. The basic version is a board on which "programmed" sheets are placed. These sheets are filled in by the players using an ordinary pencil. Over the sheet goes a game board. The players then take turns touching a portion of the board with a stylus. At certain times, when the stylus is above one of the concealed pencil marks, a light will go on. In different games, this signifies different things. For example, it could indicate the blocked path in a maze, or a free area in a treasure hunt. The game sheets can be saved and reused. *Le Game* is a nice concept, and a variety of games are available. Once the *Le Game* pencil is used up, any soft pencil can be used. Some enterprising children might even try devising their own games and program sheets.

Wildfire, Split Second, and Bank Shot from Parker Brothers

Parker Brothers has come out with some very nice games. *Wildfire* is an electronic pinball game. One to four players can participate, and there are three skill levels. The game has flippers, bumpers, gates, a kicker, and lots of sound. It's fun and challenging, as well as being sturdy and well designed.

Split second comes with five games and three variations; eight ways to play in all. The games are clever and range from simple to difficult. While playing any individual game, the player's best score is kept in memory. If he does better, the game emits a high sound. If he doesn't do better, he gets a low tone. One game involves getting through mazes. Another requires you to shoot down enemy ships. The most difficult game involves manipulating a four-segment line, trying to trap a ball. This is one game that won't become quickly boring.

Bank Shot is a pool game. One or two players can play regular pool, poison, or try trick shots. There are six balls and a cue ball involved. The stroke can be made at different angles, with different speeds. In the trick-shot mode, you can set up the balls anywhere on the table. *Poison* is like regular pool, but has one specific ball that has to be pocketed last. *Bank Shot* is well done.

Playmaker and Owly from Tiger

Playmaker contains three games — hockey, soccer, and basketball — that are similar in design and control to the football game reviewed last month. They use a special button which allows four-way control of the lights on the field. The games are for one or two, and are differentiated by using overlays on the screen.





Owly, for the wee crowd, presents problems in time telling, and number and pattern recognition. Problems are displayed in the center, using seven-segment LED's. The answers are entered in various ways, such as using a clock to match the displayed time, or pressing bars to match the missing segment of a display. Tones and music are used to note correct and incorrect responses.

Sonic Phaser from Kusan

This gun doesn't shoot anything, but it makes a variety of sounds. A sliding switch on the side selects the sound, with choices including "radiate," "anti gravity," and "ion transport." The *Phaser* seems best suited as an adjunct to games as opposed to being a game in itself. Children playing futuristic versions of cowboys and indians (Skywalkers and Vaders?) might enjoy having ready-made sound effects.

Two Player Baseball and Kiddy Computer from Fonas

One or two players can participate in this version of baseball. When played in competition, the pitcher has a choice of throwing a slow or fast ball which can be either straight or curved. There is also a button which allows him to attempt a pick off. All moves made by the pitcher are concealed by a flip-up screen. The batter can attempt to steal whenever he has a man on base. *Two Player Baseball* has all the features of the real game except for unruly crowds and nearsighted umpires. The unit is sturdy and well designed, though the lights show up best in a dimly-lit room.

Kiddy Computer presents math problems in several manners. The player has a choice of two skill levels and two speeds. At this point, ten problems are randomly chosen and presented on the screen. There are two other modes of operation. In one, the problems are presented with one of the factors going in sequence from one to ten. Another mode gives problems with an answer, but one of the factors is missing and has to be supplied. Two *Kiddie Computers* can be linked, allowing competition. Some users found the sound made by the unit to be rather loud.

That wraps things up for this Christmas season, leaving us plenty of time to speculate on what next year will bring. □

Software, Hardware and Otherware for Christmas

David Lubar

Tired of giving and getting clothes, trinkets, and candy? If you are, this list of games, utilities, books, and other goodies should be left open in an appropriate spot with the desired items circled.

Games

Conflict, from Keating Computer Services Pty Ltd, is a war game done in high resolution for a 32K Apple with Applesoft. Combat takes place on a hex grid with varying terrain. The player has tanks, infantry and heavy weapons; each with motion and strength points. At the start, you can choose from five scenarios, or specify your own with such factors as increased enemy strength, decreased enemy movement, or random terrain. The object is to score 100 points before the enemy (Apple). You get points for occupying the city. The enemy gets points for reaching your boarder or keeping you from the city. Enemy pieces are not displaced until they are adjacent to one of your pieces. The computer takes care of combat, drawing results from a table based on the strength of opposing pieces, and taking terrain into account. For those who like war games, this is a great program. For those who don't, this program might change their minds.

Jagdstaffel, from Discovery games, comes with Apple, PET, and TRS-80 versions on one cassette, packaged in a classy container suitable for bookshelves or other niches. All versions require 16K, and the package costs $19.95. The game pits your plane against a group of bombers and escorts, all of which are represented on a text screen. You control the plane with short commands such as "A4" for "Attack and dive 4000 feet." The object is to prevent the bombers from reaching the edge of the screen. The player has a choice of a dozen or so planes, and the enemy planes are also different for each game. The program accurately reflects the characteristics of the planes, and it is up to the player to learn which maneuvers work best for each plane. *Jagdstaffel* is one of a series of similar games, each of which involves a different set of planes. War buffs might want to try several versions, other would probably be satisfied with one.



An early stage of *Conflict*

Adventure International offers *Slag* for 16K TRS-80 ($15.00). Two to twelve players build industries and buy weapons, then try to blow each other up. During the combat phase, the defending country gets to shoot ground-based missiles at the attacking I.C.B.M.'s and bombers. Spy networks can also be created. The game continues until only one player is left. On the lighter side, AI also offers *Frog* ($10.00), another TRS-80 game, with marvelous graphics. The game has a frog on a log. The player moves the frog and tries to catch flies with a darting tongue. The game is fun, though it can get tough when there is only one fly left. *Mountain Shoot* ($7.95), for 16K Atari is a nice version of ballistic-type games. Two players take turns choosing amount of powder and trajectory, trying to blow each

SUPER-TEXT II™

From MUSE, the Leader in Quality Software

With its easy to use key sequences, the ST II **Word Processing** system provides fast editing of letters, manuscripts, books, or other printed material. Automatic column totals, column alignment, and on screen tabbing eliminate tedious formatting and make **Financial and Summary Reporting** a snap. **Data Base Management** is simplified by the most advanced file handling system and makes a world of information instantly available ($150.00).

Completely new documentation designed for first time users and a backup copy of the program disk is included with every program.

TRADE-INS!!

Trade in your present word processor for Super-Text II. Send documentation manual, and proof of purchase.

Trade-in Value:

Super-Text	$100.00
Easy Writer	$50.00
Apple Writer	$50.00
Apple Pie	$50.00

SUPER-TEXT ADD-ON MODULES
For Even More Versatility

Personalize and customize form letters with the ultimate letter writer, the Super-Text **Form Letter Module** ($100.00). Use it with the **Address Book Mailing List Program** ($49.95) or by itself to end repetitious composition of letters, contracts, leases, and other documents. Add the Super-Text **Terminal Module** ($75.00) and a D. C. Hayes Micromodem to communicate with any computer in the world.

Coming soon ... The Super-Text Virtual Memory Assembler—the MUSE in-house development system.

Apple II or Apple II Plus (48K).

For a free catalog or the name of your nearest MUSE Dealer, contact:

MUSE SOFTWARE™

330 N. CHARLES STREET
BALTIMORE, MD 21201
(301) 659-7212

Apple is a TM of Apple Computer Inc.
Easy-Writer is a TM of Cap'n Software.
Apple Writer is a TM of Apple Computer Inc.
Apple Pie is a TM of Programma International Inc.

CIRCLE 226 ON READER SERVICE CARD

Otherware, cont'd...

other up. The wind speed changes each turn, adding challenge to the game. Another Atari Game, *Deflection* ($8.00), puts a moving ball on a screen containing target balls. Whenever the "/" key is pressed, a "/" is placed on the screen, deflecting the ball. The object is to remove all the targets. It is possible to trap yourself in a corner. In this case, the only way out is with the "system reset" button. Still, the game is fun.

The Voice from MUSE, a 48K disk for the Apple II or II Plus ($39.95), allows the computer to speak. No hardware is needed since the internal speaker is used. The program has several parts. A demo persents a low-resolution face with moving mouth and a accompanying speech. Another program allows you to enter words and phrases, using either a microphone or cassette. Once words have been stored on disk, they can be retrieved and combined into sentences. The documentation explains how to combine *The Voice* with other programs. The sound quality can be improved by hooking the output to an external speaker, but, even through the Apple's speaker, the words are understandable. With options for changing the speed of the words, and the ability to build a library of words, you can get some interesting effects from *The Voice*.

Tandy brings the TRS-80 into the space age with their *Astrology* tape ($29.95). You enter your time and date of birth, latitude and longitude of place of birth, then sit back and watch as the computer produces all the information needed to cast charts. Everything concerning rising signs, cusps, and other crucial data is produced. If desired, the output can be sent to a printer. The program comes with a nicely done chart containing the zodiac and lots of other information.

Hayden's *Microsail* for the PET ($11.95) allows you to sail the CRT, racing a path around buoys. The tape requires 8K. There are several skill levels, and the player can control the angle of the sail and rudder, and raise or lower the centerboard. Our resident salt assures me that the game is accurate, with the boat responding just the way a real one would. If you aren't careful, you can tip over, ending the race. Text at the top of the screen keeps you informed of all the essential information, including angle of sail, wind direction, and rudder direction.

Skeet ($19.95), an Apple disk in machine language, from On-Line Systems, lets one to five players compete in a shooting contest. There is a choice of speed, skeet size, and spread of pellets. Players shoot from a number of positions, and the skeets come either singly or in pairs from two points on the high-resolution screen. *Mystery Mansion* ($24.95), in high resolution, should please *Adventure* fans. The game takes place in a large house. The occupants are being murdered. The graphics are very nice, showing the rooms and objects in detail. I wish I could tell you more about the game, but I keep getting lost in the forest outside the kitchen. Both disks require 48K.

Utilities

DOSPLUS 3.1 from Micro Systems Software, Inc. is a disk operating system for the TRS-80, incorporating a lot of nice features. For example, by pushing Shift and Clear, you can send whatever is on the screen to a printer. Unprintable characters will come out as periods. If the printer isn't on, the system won't hang. DOSPLUS offers monitor features, including listing an area of memory as either hex code or ASCII data. Another command displays free disk space. Obviously, the creators of this system knew what they wanted and knew how to achieve their desires. Selling for $99.95, DOSPLUS isn't for everyone. But those who need a friendly operating system with a lot of useful functions might find this item worth considering.

Programmer, a TRS-80 tape utility from Rational Software, provides some useful functions. It loads into high memory and is accessed by hitting shift-break. With it, you can delete lines, move lines, pack programs, append programs, and renumber. Append seems especially useful. A program on tape can be added to one in memory. You specify the starting line number for the program on tape, and the step. Unfortunately, this renumbering of the tape program plays havoc with referenced lines. Still, for adding short subroutines, Append is useful. The Pack function strips REMs and removes all extra spaces. Move allows you to take a line or lines from one section and place them elsewhere. Since Programmer is in machine code, the utilities execute rapidly.

Apple-Doc ($19.95) from Southwestern Data Systems contains three utilities that run in ROM or RAM Applesoft. "Vardoc" produces a list of variables contained in any program in memory. "Linedoc" gives a list of referenced lines and the lines calling them. "Replace" allows you to rename any variable or replace any string. This replacement capability has many uses, such as serving as an aid when converting Integer Basic programs to Applesoft, or for changing the variables in a subroutine which is appended to various programs.

Peripherals

The Musicraft Development System from Newtech Computer systems, Inc. was covered in October, but mention should be made of the Music Box, a peripheral which allows the TRS-80 to produce four-voice music. The box plugs into the keyboard or the expansion interface. It comes with an AC adaptor and a cable for connecting to a speaker. The unit can drive a small speaker, but an amplifier is required if you are using large speakers. The box is attractive; painted to resemble a keyboard, and the manual that comes with the system is comprehensive and well done. The Music Box, with software and hardware, sells for under $200.

For Apple owners who want an easy method of entering graphics, there is the Versa Writer from Peripherals Plus ($252). Thanks to great software, this device does things that bit pads can't do, such as creating shape tables and allowing over 100 colors on the Apple's high resolution screen. The Versa Writer was reviewed in June '79. Since then, the software has been rewritten in machine code, giving much faster operation.

Books

Godël, Escher, Bach almost defies description. The author, Douglas Hofstadt, blends music, art, and mathematics. This $8.95 paperback explores fugues, canons, lithographs, and set theory — to name a few areas touched. Several sections are



A shooter in the act of missing both skeets

devoted to computers and artificial intelligence. The format involves chapters on various matters alternating with fascinating dialogues between Archilles and the Tortoise. This book will delight anyone who is intrigued by the lore of numbers.

Tales of the Marvelous Machine ($7.95) takes 35 stories — some from the pages of *Creative Computing*, many previously unpublished — adds a lot of new artwork, and guarantees a great way to pass those long winter nights. The book starts off with a variety of indexes. You can choose stories by length or content, or by the role played by the computer.

For Science Fiction fans, Creative Computing Press also offers *Masterpieces of Science Fiction* ($7.95), a large-format book filled with color illustrations, and graced with nine classics from such authors as Harlan Ellison, Robert Heinlein, and Issac Asimov. The book is also a great way to hook those who haven't yet become addicted to science fiction. □

Vendor Addresses

Discovery Games
936 W. Highway 36
St. Paul, MN 55113

Muse
330 N. Charles St.
Baltimore, MD 21201

Hayden
50 Essex St.
Rochelle Park, NJ 07662

Tandy
One Tandy Center
Fort Worth, TX 76102

Micro Systems Software
5846 Funston St.
Hollywood, FL 33023

Adventure International
Box 3435
Longwood, FL 32750

Creative Computing Press
P.O. Box 789-M
Morristown, NJ 07960

Newtech Computer Systems, Inc.
230 Clinton St.
Brooklyn, NY 11201

Southwestern Data Systems
P.O. Box 582
Santee, CA 92071

Rational Software
963 E. California Blvd.
Pasadena, CA 91106
Keating Computer Services Pty Ltd
P.O. Box 448
Double Bay, Australia 2028

Peripherals Plus
119 Maple Avenue
Morristown, NJ 07960

On Line Systems
772 N. Holbrook St.
Simi Valley, CA 93065

Christmas Buyers Guide

The computers included in this chart were selected with the aim of giving a wide representation to as many different types of machines as possible. Some of the categories require a few words of explanation. Graphic resolution can be represented in several ways. Effective resolution is the actual number of dots or pixels that can be put on the screen. In some cases, the user has control only over characters composed of a matrix of pixels. Thus, a machine with an effective resolution of, say, 200 X 200 might have a programmable control over only a 40 X 40 grid.

Available peripherals refers to those accessories from the manufacturer of the computer. This is a representative list and is not intended to cover the complete line of peripherals. Outside availability concerns software and hardware from other manufacturers. Again, the examples are representative. The prices given are based on manufacturers suggested list. Most systems can be obtained for a lower price.

	Sinclair ZX80	Commodore PET/CBM	OSI C4P	Heath WH89	Atari 800
Description of System	Compact unit with pressure-sensitive keyboard and CPU	Keyboard, CPU and monitor in a single metal unit	Keyboard and CPU in metal and wood case	Keyboard, CPU, monitor and disk in metal case	Keyboard and CPU in plastic case with metal shielding, cassette in separate unit.
Memory	1-16K RAM 4 or 8K Basic in ROM	8-48K RAM 16K ROM	8-32K RAM, 8K Basic in ROM	16-48K RAM 6K ROM	16-48K RAM up to 26K ROM
Processor	Z-80	6502	6502	Z-80	6502
Basic	Integer Basic	Commodore Basic — a version of Microsoft	OSI Basic	Benton Harbor Basic or Microsoft Basic available through software	Atari Basic — includes extensive commands for graphics, music, and paddles
Monitor Accessibility	Through PEEK and POKE. Z-80 code can be entered as strings	Some user access, assembler programs available	Assembler programs available	Assembler programs available	Assembler cartridge needed
Other Available Languages	None	None	Fortran, Pascal	Pascal	Pascal (1981) Microsoft Basic (1981)
Graphics and Color	B+W with 22 special symbols, 24 X 32	B+W, special graphics symbols 25 X 40 display	256 X 512 effective resolution with 16 colors. Predefined graphics characters available	33 graphics characters available, each composed of an 8 X 10 matrix. B+W	Several modes, from 40 X 24 with 4 colors to 192 X 320 with 2 colors
Text	Upper case 24 X 32	25 X 40 upper and lower case	64 X 32 upper and lower case	24 X 80 upper and lower case	24 X 32 upper and lower case.
Sound Capabilities	None	Through external devices	Built in DAC and tone generator	Through external devices	4 voices plus speaker
External Storage Devices	Cassette (250 baud), disk promised in near future	Cassette, dual disks (360K)	Cassette (300 baud), disk (77.8K)	Cassette (baud rate selectable up to 9600) or disk	Cassette, disk (80 for 1st drive, 86K for drives 2, 3 and 4)
Unincluded Requirements	Cassette and TV	Cassette	Cassette or disk, monitor	Language software	TV
Expansion and Interfacing	Through edge card	IEEE bus, 2nd cassette port, memory expansion bus	4 expansion slots, printer interface, AC remote control, joystick interface	Sockets for memory, two port serial interface	Serial port
Available Peripherals	Plans for printer, disk, and flat-screen TV	Modem, voice synthesizer, disk, cassette, printer	Monitor, joysticks, modem, AC remote control switches, printer	Disks, modem, printer, interface boards	Disk drives, printer, modem, joystick
Outside Software Availability	Some	Good	Some	Little	Fair, getting better
Outside Hardware Availability	None yet	Good, including music boards, S-100 expansion interface, and joysticks	Some	Little	Little
Documentation	Good	Good but not thorough	Good but unorganized	Good	Good, but some decoding required
Dependability	Good	Good	Fair	Good	Good
Service	Return to manufacturer	Available at some dealers or mail in	Available at some dealers, mostly mail in	Through Heath Cervice Centers	From many dealers or Control Data Centers
Price of Basic System	$199.95 for 1K	$995 for 16K	$ 698 for 8K	$1195 for 16K kit without disk	$1080 for 16K
Price of System with Disk	NA	$2590 for 32K with dual disks	$1695 for 24K with disk (C4P MF)	$2895 for 48K with disk, assembled	$2000 for 32K with disk
Comments	Very popular in Europe. Provides a very low cost introduction to programming	A nice unit with some good features, especially popular with educators since it is self contained.	OSI has a history of innovative hardware at a low price, but indifferent factory support.	Heath has an excellent reputation in the electronics field. The use of RAM for languages allows many future applications.	The Atari is growing in popularity. Many vendors will probably be adding Atari products to their lines of software and hardware.

David Lubar

This year, the buyer's guide to personal computers expands, branching in several directions. For quick reference, there is the comparison chart which covers ten computers — both old timers and newcomers. On this chart, you can find machines from under $200 to over $1000, with a wide variety of features and capabilities. Next comes an in-depth look at four of the most popular home computers. Each article was written by someone who has worked extensively with that particular computer; each presents a favorable but balanced view. There are also reviews of two new entries, the TRS-80 Pocket Computer and the Sinclair ZX80. These computers represent a significant step in the evolution of home computing, both in portability and price. For those who want to dig in, there is a comparison of Basics which deals with both available features and speed of execution.

For those who already have a computer, or need a gift idea, there is a review of software, peripherals, and books. That about covers this years buyer's guide. Happy shopping. — DL

	Exidy Sorcerer	Apple II Plus	TRS-80 Level II	TI 99/4	APF Imagination Machine
	Keyboard, CPU, and socket for ROM cartridges in plastic case	Keyboard and CPU in a plastic case with metal bottom	Keyboard and CPU in single black plastic unit, cassette and monitor in separate units	Compact metal and plastic keyboard and CPU, separate monitor	Keyboard, CPU, cassette, and slots for ROM cartridges in a plastic case
	8-48K RAM 12K ROM and ROM cartridges	16-48K RAM, 16K ROM (8K Basic, 4K monitor, 4K hardware switches)	4-48K RAM 16K ROM	16K RAM, 26K ROM, Additional 30K from ROM cartridges	9-17K RAM, 14K Basic in ROM
	Z-80	6502	Z-80	9900	MC6800
	8K Microsoft Basic	Applesoft — Version of Microsoft with extended commands for graphics and paddles	Level II Basic, a version of Microsoft with extensions for graphics	TI Basic with special commands for sound and graphics	APF Basic; similar to Microsoft, but without trig functions or extended string handling.
	Accessible with assembler cartridge	Memory is open to inspection and change, disassembler included.	Special software required for access. PEEK and POKE available from Basic	Not accessible to user	System supports 6800 programming
	Fortran	Integer Basic, Pascal, Pilot	Fortran	None	None
	B+W, special graphics symbols included with effective resolution of 512 X 240. User can define special characters.	40 X 48 with 16 colors, 280 X 192 with 6 colors	B+W 48 X 128 using graphics characters with 3 X 2 blocks, giving programmable control of 16 X 64	192 x 256 with 8 X 8 characters for a programmable control of 24 X 32 with 16 colors	Several modes — 192 X 256 with 4 colors, 192 X 128 with 8 colors, using defined shapes of 4 X 16
	30 X 64 upper and lower case	24 X 40 upper case	16 X 64 upper case	24 X 32 upper case	32 X 16 upper case
	Through external devices	Built in speaker	Through peripherals	Three voices through audio channel of monitor	Built in speaker and Synthesizer
	Cassette or disk (315K)	Cassette (1200 baud), disk (100K, up to 14 drives)	Cassette (500 baud) Disk (55K for 1st drive, 85K for 2, 3, and 4)	Cassette, disk	Cassette (1500 baud), Disk (72K)
	Cassette or disk, monitor	Monitor or TV and RF modulator, cassette or disk	None	Cassette	TV
	S-100 expansion box available, second cassette port and parallel port on board	8 expansion slots for peripheral cards, dip plug for joysticks or paddles	Expansion interface used for additional RAM above 16K and peripherals, edge card for printer on board.	Two ports for TI peripherals and controllers	Optional expansion box
	Disk, monitor	Integer firmware card, language system, disk drive, printer, modem	Printers, disk, speech synthesizer	Speech synthesizer, modem, printer, joysticks, disk (announced)	Disk, expansion box
	Moderate	Excellent	Excellent	Little yet	None
	Excellent if the expansion box is used	Excellent — including boards for speech and music, light pen, printers, bit pads, and joysticks	Excellent, including music, speech, light pens, and printers	Little yet	None
	Fair	Thorough and well done	Good	Good	Fair
	Good	Good	Fair	Good	Too new to tell
	Through some dealers or mail in	Available at all authorized dealers. Quality varies	From 86 service centers across the country	Through some dealers or mail in	Mail in
	$895 for 8K	$1195 for 16K	$649 for 4K, $768 for 16K	$1150	$599 for 9K
	$2250 for 32K with dual disks	$1950 for 32K with disk	$1580	$ 1650 for 16K with disk	$995 for 9K and disk
	A very capable computer suffering from lack of support by Exidy. The recent sale of the computer division might help.	An established machine with continuing support from Apple and other manufacturers. Many active users groups.	A very popular computer with many users groups. Available software and hardware will continue to grow.	The TI has the best speech synthesis available in a small computer	A low-cost way to get started

sinclair ZX80

David Tebbutt

Clive Sinclair has surprised the world with the launch of his attractive, hand-held personal computer. Costing less than $200, and plugging into a TV and cassette recorder, some now suggest the ZX80 to represent the thin edge of a mass consumer market wedge.

Introduction

Sinclair Research set out to build a simple to use personal computer running Basic and capable of breaking the psychological price barrier of $200. Well, they succeeded with their ZX80. Why ZX80? No reason really except that it's based on an NEC copy of the Z80 processor chip . . . and it sounds nice.

The machine is available by mail order only; there are no plans to sell it in stores — yet. The kit version is only available in the U.K.; in the U.S. the assembled version costs $200 and includes an AC power supply.

The ZX80 is amazingly light, twelve ounces in fact, and easily held in one hand. The low weight is achieved through use of a moulded plastic casing just 1mm thick.

It connects quite happily to the television set and the cassette recorder, although it might take a few minutes to find the optimal settings. Once attached to the TV, it gives a rock steady display (more on that later).

Reprinted with the permission of *Personal Computer World*.

Hardware

I have to say that I think it very pretty (our art director would probably beg to differ) — the casing even has go-faster stripes, which look suspiciously like ventilation slots in black and white photographs (coincidence, I'm sure). I would, however, have been happier with something rather more sturdy; ABS plastic might have done the trick, although perhaps at the cost of attractiveness.

The keyboard is most interesting; it's one of those waterproof, chemical proof, completely sealed units and it's stuck on to the main printed circuit board (PCB). Made of a special tough plastic, the undersurface is printed with the key symbols so as to eliminate any rubbing off. Between this keyplate and the PCB containing the metal contact strips (about five per key) is a piece of sticky plastic containing forty holes which line up with the "keys". This material is about .006" thick and is just sufficient to keep the metal underside of the keyplate away from the contacts, except when touched of course.

Typing gives a sensation of drumming your fingers rather than of doing anything useful. This is a totally mistaken impression because it really works rather well. For those who are interested, I found that a "wiping" action was more successful than the tapping movement usually associated with typing. Typists may be pleased to hear that the keys are in standard QWERTY layout although somewhat compressed compared to, say, the office IBM.

Looking inside the machine, I find that it's controlled by an NEC 780-1 processor chip . . . a copy of the well known and very successful Z80. This CPU, running at 3.25MHz, does all the work for the ZX80, including driving the TV and the cassette recorder. You'll notice that if any work is taking place, be it calculation, accepting input from the keyboard or driving the cassette, then the TV picture disappears — only to return when the activity is complete. This can be irritating to observers (at a demonstration for example) but I found it positively beneficial when keying in programs because it gave me positive feedback whenever a key made successful contact.

The Sinclair ZX80 is innovative and powerful. Now there's a magazine to help you get the most out of it.

Get in sync

SYNC magazine is different from other personal computing magazines. Not just different because it is about a unique computer, the Sinclair ZX80 (and kit version, the MicroAce). But different because of the creative and innovative philosophy of the editors.

A Fascinating Computer

The ZX80 doesn't have memory mapped video. Thus the screen goes blank when a key is pressed. To some reviewers this is a disadvantage. To our editors this is a challenge. One suggested that games could be written to take advantage of the screen blanking. For example, how about a game where characters and graphic symbols move around the screen while it is blanked? The object would be to crack the secret code governing the movements. Voila! A new game like Mastermind or Black Box uniquely for the ZX80.

We made some interesting discoveries soon after setting up the machine. For instance, the CHR$ function is not limited to a value between 0 and 255, but cycles repeatedly through the code. CHR$ (9) and CHR$ (265) will produce identical values. In other words, CHR$ operates in a MOD 256 fashion. We found that the "=" sign can be used several times on a single line, allowing the logical evaluation of variables. In the Sinclair, LET X=Y=Z=W is a valid expression.

Or consider the TL$ function which strips a string of its initial character. At first, we wondered what practical value it had. Then someone suggested it would be perfect for removing the dollar sign from numerical inputs.

Breakthroughs? Hardly. But indicative of the hints and kinds you'll find in every issue of **SYNC**. We intend to take the Sinclair to its limits and then push beyond, finding new tricks and tips, new applications, new ways to do what couldn't be done before. **SYNC** functions on many levels, with tutorials for the beginner and concepts that will keep the pros coming back for more. We'll show you how to duplicate commands available in other Basics. And, perhaps, how to do things that can't be done on other machines.

Many computer applications require that data be sorted. But did you realize there are over ten fundamentally different sorting algorithms? Many people settle for a simple bubble sort perhaps because it's described in so many programming manuals or because they've seen it in another program. However, sort routines such as heapsort or Shell-Metzner are over 100 times as fast as a bubble sort and may actually use less memory. Sure, 1K of memory isn't a lot to work with, but it can be stretched much further by using innovative, clever coding. You'll find this type of help in **SYNC**.

Lots of Games and Applications

Applications and software are the meat of **SYNC**. We recognize that along with useful, pragmatic applications, like financial analysis and graphing, you'll want games that are fun and challenging. In the charter issue of **SYNC** you'll find several games. Acey Ducey is a card game in which the dealer (the computer) deals two cards face up. You then have an option to bet depending upon whether you feel the next card dealt will have a value between the first two.

In Hurkle, another game in the charter issue, you have to find a happy little Hurkle who is hiding on a 10 X 10 grid. In response to your guesses, the Hurkle sends our a clue telling you in which direction to look next.

One of the most ancient forms of arithmetical puzzle is called a "boomerang." The oldest recorded example is that set down by Nicomachus in his *Arithmetica* around 100 A.D. You'll find a computer version of this puzzle in **SYNC**.

Hard-Hitting, Objective Evaluations

By selecting the ZX80 or MicroAce as your personal computer you've shown that you are an astute buyer looking for good performance, an innovative design and economical price. However, selecting software will not be easy. That's where **SYNC** comes in. **SYNC** evaluates software packages and other peripherals and doesn't just publish manufacturer descriptions. We put each package through its paces and give you an in-depth, objective report of its strengths and weaknesses.

SYNC is a Creative Computing publication. **Creative Computing** is the number 1 magazine of software and applications with nearly 100,000 circulation. The two most popular computer games books in the world, *Basic Computer Games* and *More Basic Computer Games* (combined sales over 500,000) are published by Creative Computing. Creative Computing Software manufactures over 150 software packages for six different personal computers.

Creative Computing, founded in 1974 by David Ahl, is a well-established firm committed to the future of personal computing. We expect the Sinclair ZX80 to be a highly successful computer and correspondingly, **SYNC** to be a respected and successful magazine.

Order SYNC Today

Right now we need all the help we can get. First of all, we'd like you to subscribe to **SYNC.** Subscriptions cost $10 for one year (6 issues), $18 for two years (12 issues) or, if you really want to beat inflation, $24 for three years (18 issues). Send to the address below or call our toll-free number, **800-631-8112** (in NJ 201-540-0445) to put your subscription on your MasterCard, Visa or American Express card. Canadian and other foreign surface subscriptions are $15 per year or $27 for two years. We guarantee your satisfaction or we will refund the unfulfilled portion of your subscription.

Needless to say, we can't fill up all the pages without your help. So send in your programs, articles, hints and tips. Remember, illustrations and screen photos make a piece much more interesting. Send in your reviews of peripherals and software too—but be warned: reviews must be in-depth and objective. We want you to respect what you read on the pages of **SYNC** so be honest and forthright in the material you send us. Of course we pay for contributions—just don't expect to retire on it.

The exploration has begun. Join us.

The magazine for Sinclair ZX80 users
SYNC

39 East Hanover Avenue
Morris Plains, NJ 07950, USA

Toll free **800-631-8112**
(In NJ 201-540-0445)

ZX80, cont'd...

The Basic interpreter, operating system, character set and editor are all held in a 4K Byte ROM. If you are feeling adventurous there's no reason why you shouldn't pop your own ROM (TMS 2532) in its place.

Memory in the basic system comprises 1K static RAM; you can add to it via the expansion port, giving a maximum potential of 16K. The memory expands with the aid of plug in modules, each designed to carry up to 3K in 1K increments. Thus five modules would be required to give the 16K maximum. At switch-on the machine does a memory check which also tells the system how much memory is on-line. Should you reconfigure the memory, then the command NEW will execute the memory check cycle again.

Moving on to the "outside world" connections, there's a cassette interface, TV socket and a hefty edge connector. The cassette interface comprises two 3.5mm jack plug sockets, securely mounted on the main (and only) PCB. One connects to the "ear" socket on the cassette recorder and the other to the "mic" socket. There is no facility for remote control of the cassette motor.

Although I encountered one or two problems at first, once working, the cassette interface proved trouble free. My particular recorder had a nasty habit of recording noises when the CPU was "sending out" silence. This caused the system to get its knickers in a twist when reading from cassette because it expected silence just before the file header record. After a couple of hours (what a confession) the culprit was found — the "ear" lead, which acts as a monitor while recording, was setting up some sort of oscillation. Answer — simple — disconnect the "ear" jack when recording. Another tip which ensures trouble free loading is to move the tape into the silent section before issuing your LOAD instruction. Rumor has it that the cassette operates at around 250 baud — I believe it, although it doesn't seem terribly important when you're only loading the 1K that I was.

The television connector is simplicity itself. Plug one end of the cable (supplied) into the ZX80 and the other into the television aerial socket, tune to channel 2 and you're in business. The display is magic; rock steady and very clear although reversed characters (white on black) are not so good.

I have already mentioned the business of the display switching off every time the processor needs to do something else. If this drives you mad then you'll have to forfeit some of the undoubted pleasures that this machine has to offer. The screen is not memory mapped; it's treated like a serial file — like a printer in fact — which means that fast moving graphics are out of the question. No doubt some clever Dick out there will take up the challenge and fudge the system, just to prove me wrong. More about the reasons for this in the Software section, but anyone who is hooked on white characters on a black background can suitably modify the PCB, though why they should want to I'll never know. It's a matter of cutting one track and making a small bridge to another.

Do you take your computer camping with you? You'll be pleased to hear that it can run from a car battery, provided that the lead regulates the supply. I believe you can buy a cigarette lighter plug with a built in regulator . . . couple that with a portable TV and a battery powered cassette recorder and you'll be the envy of the campsite.

Technical Specification

CPU:	NEC 780C-1 (copy of Z80) 3.25 MHz
Memory:	1K static RAM, expandable to 16K
Keyboard:	Keyplate, under-surface printed
Screen:	Use own television. Pixel graphics 24 lines x 32 chars.
Cassette:	Use domestic audio cassette recorder.
Bus:	Edge connector with 44 lines — 37 from CPU, 0V, 5V, 9V, Clock, External memory indicator and two earths.
Software:	4K ROM containing Basic, Editor and Operating System

The keyboard is most interesting; it's one of those waterproof, chemical proof, completely sealed units.

Now let's look at the hefty edge connector. This is where the memory expansion modules fit in, each one being "piggy backed" on the one previous. Thus there are always 44 contacts available for outside use. There are 37 lines drawn from the CPU plus 3 power lines (at 0V, 5V and 9V); the other lines comprise two grounds, a "clock" signal and an "external memory in use" indicator.

All in all, the Sinclair ZX80 is a well designed, well produced personal computer. Memory addition comes a bit expensive at about $700 for the full expansion but Clive Sinclair tells me bigger RAMs are on the way — that means cheaper expansion when they appear.

I'm sorry that there are no pictures of the machine's innards. The fact of the matter is that I was given one of the development machines which had a couple of "Veroboarded" EPROMS and a selector IC floating around on the ends of some pieces of wire which in turn were soldered into the "official" ROM socket. I thought it best to spare Mr. Sinclair's blushes.

Software

The software of the ZX80 comprises the Basic interpreter, the Editor and whatever it is that does the rest of the work (Operating System seems too grand a title). Rather than looking at each separately, I shall examine them in the order they might be encountered.

First of all the keying in of programs. For two reasons it's an absolute joy! First you don't have to type in many of the Basic instruction codes, one key is sufficient; second you cannot enter anything that is syntactically incorrect. Some Basic instructions have to be entered the long way (these are listed above te keyboard) but 29 of the instructions may be entered with a single keystroke, while only 8 need to be keyed in full.

As with many small computers most of the instruction codes are stored in a single byte. Normal Z80 machine code can be entered using the POKE statement and executed with the USR instruction. This should keep the buffs happy after they have tired of Basic. Syntax checking is superb — it's impossible to go wrong. Every character is checked on entry and, if the interpreter thinks that you are going to make a mistake, it signals with a reverse S (for Syntax) at the point it thinks you have gone wrong. If, later in the same line, you correct the error, then the marker disappears. What a grown up facility for such a small machine! Incidentally, the program lines are displayed very clearly with line numbers, instructions, operators and what have you being nicely spaced out.

Inside the memory, however, there's a completely different story. The lines of code are held as compactly as possible with most of the commands and operators occupying one byte each. The spaces are removed and there are very few extra bytes needed — for instance the new line code is one byte, although I did notice that the "=" operator needed one extra for some reason. I'm sure there are others, but I'm equally sure they are very few and far between. An example of the storage requirement is as follows:

10 FOR A = 16424 TO 17424	18 Bytes
20 PRINT PEEK(A);	12 Bytes
30 NEXT A	5 Bytes
40 STOP	4 Bytes

FOR TRS-80*

NEW! BASKETBALL



by John Allen

New machine language action game, with sound, from the author of the acclaimed "PINBALL!"

You have to be fast to keep up with the action as you try to outscore your opponent in five minutes of one-on-one basketball. Compete against a friend or your computer.

Steal the ball, duck around your opponent and slant toward the basket for a lay up! The graphics are based on a 3-dimensional depiction of a basketball court, and ball dribbling sounds add to the realism. It's all there but the cheers — so real you'll wonder how the ball keeps from coming through the screen of your TRS-80! Dribble, Dribble!

Available for Level II, 16K. $14.95 for tape, $20.95 on disk.

FAST, REAL-TIME ACTION WITH SOUND



PINBALL

by John Allen

Get your flipper fingers ready for action in this real-time, machine language game.

Lots of sound and flashing graphics make this fast action game so much like the real thing that you'll have to remind yourself not to shake your TRS-80*. Choose from five playing speeds to match your skill — but be prepared for alot of practice if you ever hope to master the fastest speed.

Can you beat your friends' scores? Will you avoid the dreaded "Bermuda Square?" Get PINBALL today and find out. Available for $14.95 on tape or $20.95 on disk.

*TRS-80 is a trademark of Tandy Corp.

Acorn
Software Products, Inc.
634 North Carolina Avenue, S.E., Washington, D.C. 20003

These and other popular Acorn programs are available now at fine computer stores. Ask for them.

DEALER INQUIRIES INVITED

CIRCLE 103 ON READER SERVICE CARD

ZX80, cont'd...

So you see, the storage for that program (displaying the 1K memory) is 39 bytes long — an average of 10 bytes per instruction. I'll leave you to work out what sort of program you can get in 1K. Perhaps I should mention that the screen buffer uses part of the 1K, as does the stack and system control area. The stack is held at the top of memory and "grows" down; I put 327 entries on it before it stopped accepting them.

The program and variables "grow" up into the screen buffer thus reducing the amount of data on display. Eventually it's possible for the program or variables to grow so large that there's nothing left on display. It was while experimenting with this interesting feature that I crashed the system. It seems the software couldn't cope with someone entering a string 868 bytes long! After about 424 bytes of input the screen removed another character every time I keyed in a new one — it was most odd to watch.

Another way of crashing the system, in fact the only other way I could find, is to hit the EDIT key while in the middle of an INPUT loop. This returns the current program line with a syntax error which is impossible to clear. For those who are feeling unhappy about all this talk of crashing systems, don't worry, it's not as bad as it sounds. In the first place you have to enter forty characters after the screen has gone blank, and in the second place you can only hit EDIT when you are also holding the SHIFT key down.

Now it may be that, having loaded your program, you wish to edit it. Well once again there is some rather excellent software to help you. The Editor enables you to move a "current line marker" up and down the program text. Wherever it is you will always be able to see the marked line and at least some of its neighbors (it's called getting it in context). Pressing the HOME key causes the marker to disappear — it has in fact gone to an imaginary position, one above the first program line. Having reached the line to be edited press the EDIT key and the line will be presented at the bottom of the screen ready for you to do your worst. From now on it is as if you are entering the line for the first time.

The benchmark* timings show the ZX-80 to be very fast, even though I had to introduce some extra code to make some of the instructions work. Specifically I had to bracket expressions like LET A=(K/K)*K)+K—K . . . if I hadn't, the expression would have exceeded the ZX80's capacity. The machine can only operate on integers and these must have values from —32768 to 32767. I couldn't execute Benchmark 8 because the machine has no logarithmic or trigonometrical functions built in.

*PCW uses 8 Benchmark programs to compare computers.

Basic

String Expressions

CHR$(n)	TL$(s)	STR$(n)	

Integer Expressions

PEEK(n)	CODE(s)	RND(n)	USR(n)
ABS(n)			

Statements

NEW	LOAD	SAVE	RUN n
RUN	CONTINUE	REM	IF n THEN stmnt
INPUT dest	PRINT	LIST n	LIST
STOP	DIM (n)	FOR =n TO n	GOTO n
POKEn,n	RANDOMIZE n	RANDOMIZE	CLEAR
CLS	GOSUB n	RETURN	NEXT

Operations

n**n	— n	n*n	n/n
n+n	n — n	n = n	n > n
n < n	s = s	s > s	s < s
NOT n	n AND n	n OR n	

n = number
s = string
** = to the power of

Finally, it's possible to save programs and any variables associated with them. If you want to make use of those same variables when reloading the program, use GOTO rather than RUN. Although it's possible to SAVE programs in this way, no provision has been made to save files — yet.

Every character is checked on entry.

That's about it for the software; once again, considering the size of machine and price, I think that it's not at all bad.

Basic

The ZX80 Basic has been well thought-out and, while it lacks some of the elegance and sophistication of the bigger machines, it's a very usable version of the language.

The main limitations relate to file handling and mathematical functions. File handling facilities don't exist, except by SAVEing the whole of memory (which is probably not as daft as it sounds). It does mean that you can save a program with all its variables, reload it the next day, remember to kick off with a GOTO rather than RUN, and carry on from where you left off. On the small memory machine it doesn't seem that important, but on the larger memory machines it means you can hold some reasonable sized files together with your program.

Benchmark timings (in seconds)

BM1	1.46
BM2	4.69
BM3	9.18
BM4	8.95
BM5	12.7
BM6	25.9
BM7	39.2

BM8 not performed (see text)

The mathematical limitations are possibly more serious. The fact is the Basic can only handle integers in the range — 32768 to 32767, no decimals, hence the programmer must write a little routine for each mathematical function that requires decimals to be used. This should pose few problems for those with the larger memory machines but it will undoubtedly occupy a fair chunk of the basic 1K system.

So much for bad news; now here are some of the good features of the language.

Taking numeric functions first, the Basic offers up to 26 single dimension numeric arrays of any length. It also allows three Boolean operations — AND, OR and NOT.

The randomizing functions are worth a mention. RANDOMIZE n sets a seed value, while RND(n) gives a random number in the range 1 to n. PEEK and POKE are both available so it's possible to read or modify memory contents; coupled with the USR function, this means that Z80 machine code routines can be executed.

Up to 26 FOR . . . NEXT loops can be nested and the number of nestable subroutine calls seem to be dictated by the amount of memory available to the stack. On the 1K machine with a short (4 line) program, I ws able to get 327 subroutine calls in before needing to RETURN.

String functions, while adequate, could definitely be improved. The absence of a DATA statement and the lack of string arrays caused particular frustration. Although there are ways around these problems, they can be time consuming and messy.

The functions which are available, and which form the building blocks of string handling subroutines, are STR$, TL$, CODE, CHR$ and INPUT. STR$(n) returns a string of 1 to 6 characters representing the signed, decimal value of n. TL$ returns a string minus its first character, while CODE returns the code for the first



High quality pretested interactive application software packages for personal and small business computers designed by experts — Datasoft. Proven standard accounting and inventory control functions — Datasoft. Special market packages for attorneys, physicians, wholesalers and retailers — Datasoft. Complete documentation — Datasoft. Sophisticated electronic games — Datasoft. Great dealer discounts — Datasoft. Total support — Datasoft. Best value — Datasoft. Guaranteed — Datasoft.

Mail this coupon today or call now for faster delivery — (800) 896-5630

Hurry, send details on:
☐ Business software ☐ Personal software ☐ Dealer information
☐ Programmer ☐ Consumer
☐ Educational

Datasoft Inc., 16606 Schoenborn St., Sepulveda, CA 91343, (213) 894-9154

Type of computer owned _____

Company/Name _____

Address _____

City _____

State _____

Zip _____

Phone _____

Dealer inquiries invited

Datasoft Inc.
COMPUTER SOFTWARE

CIRCLE 179 ON READER SERVICE CARD

ZX80, cont'd...

character in a string. CHR$(n) represents the character whose value is n and INPUT allows the operator to input numeric or alphanumeric information. A nice touch is that if the destination of input is a string variable, then the Basic kindly provides a pair of quotes which act not only as a prompt, they also save a little bit of keying.

There is one trap here for the unwary, and I fell into it. I had this nice little loop going and after a while I got fed up with it. Could I get out of the system — could I heck! I hit everything in sight but all I managed to do was crash the system (see earlier). The trick is that if you are in an input string loop, remove the quotes and then put in an arithmetic expression which will resolve outside the range — 32768 to 32767.

So, that's the Basic — I reckon that it's pretty good under the circumstances and in some respects I prefer it to the Basics that do all your thinking for you.

Documentation

This comprises a programming cum operating manual. It's very well presented, being written by Hugo Davenport of Cambridge Consultants, with appendices by the mystery man from Cambridge who wrote the Basic interpreter. There are a few small mistakes in the manual — none of them terribly serious and all of them being dealt with before the next reprint. It's probably good enough to learn to program from it and my only real criticisms like in the area of what it does (or rather, doesn't do) for the raw beginner. I lent the machine to one such person for a few hours and here in his reply regarding the documentation:

"I read Chapter 2 (Getting Started) and got completely lost by the third page. One minute it's telling me how to wire everything up, the next there's something incomprehensible about storing programs on tape. I couldn't find an 'Idiot's Guide to getting started' anywhere."

Maybe the Operating Manual wasn't designed with such a person in mind — even so, novices like him must surely represent a good sized chunk of the ZX80's ownership potential."

Future Plans

A new ROM is being developed which will overcome most of the shortcomings of the existing system. Being 8K instead of 4K means that file handling routines will enable us to read and write tapes — even discs! This new ROM will also include the missing trigonometrical, logarithmic and floating point arithmetic functions.

Another area of development is on the memory front. A 16K plug in dynamic RAM is a distinct possibility; this will be considerably cheaper than taking the present $700 expansion route. A printer is also likely to appear in due course.

Potential Use

In its present form the ZX80 offers an ideal introduction to computing. It makes Basic easy to learn, it's small enough for it not to be intimidating and it's cheap enough that, should you decide computing is not for you, you can give it away, sell it or whatever. Indeed it's probably cheaper to learn Basic this way than to pay for many of the courses around.

Teachers might buy it for their students' use because at the price there is no need to go through a complicated rigmarole to get the money. The 1K version can be used for fairly simple games and activities, although it's likely you will want to expand it before very long. Later, when the file handling facilities are introduced together with floating point arithmetic, I think the machine will become really useful, though still very much at the personal level. Home accounts and engineering calculations spring to mind immediately — don't ask me why! Suddenly the machine becomes something more than a teaching machine or toy: it starts to become a real computer.

Conclusion

Having just read Science of Cambridge's claims for the machine again, I have to say I agree with most of them. The only point I would question is that it offers high resolution graphics. OK, OK, so they are playing the same game as everyone else . . . all the same I feel that it should be explained. Just lately, people have taken to calling pixel graphics, high resolution graphics. Accordingly, what used to be called high resolution graphics now has to be called ultra high resolution graphics. To put it another way, the ZX80 offers a graphics resolution of one quarter of one character, plus you must write your own software to be able to use it. PET is in exactly the same boat, unless you want to buy the high resolution add-on at about $600.

The ZX80 appears to be a well thought out machine both in terms of hardware and software. It has an excellent editor and interpreter which between them help you avoid all sorts of nasty pitfalls. The Basic instruction set lacks one or two fairly important facilities — namely file handling and floating point calculations. Despite this, it's still a fine machine on which to learn about computing. The new ROM expected later this year will overcome the prime limitations leaving me very little to say except that I hope Mr. Sinclair and his merry men of Cambridge can cope with the expected flood of orders and, perhaps more importantly, the after sales service which is vital in this sort of operation. □

Our thanks go to Clive Sinclair for lending us the machine, and to Jim Westwood (its designer) for patiently answering so many questions.

MORE BASIC COMPUTER GAMES

NOW!
Microsoft Basic
and
TRS-80 Editions

Contents

Artillery-3
Baccarat
Bible Quiz
Big 6
Binary
Blackbox
Bobstones
Bocce
Boga II
Bumbrun
Bridge-It
Camel
Chase
Chuck-A-Luck
Close Encounters
Column
Concentration
Condot
Convoy
Corral
Countdown
Cup
Dealer's Choice
Deepspace
Defuse
Dodgem
Doors
Drag
Dr. Z
Eliza
Father
Flip
Four In A Row
Geowar
Grand Prix
Guess-It
ICBM
Inkblot
Joust
Jumping Balls
Keno
L Game
Life Expectancy
Lissajous
Magic Square
Man-Eating Rabbit
Maneuvers
Mastermind
Masterbagels
Matpuzzle
Maze
Millionaire
Minotaur
Motorcycle Jump
Nomad
Not One
Obstacle
Octrix
Pasart
Pasart 2
Pinball
Rabbit Chase
Roadrace
Rotate
Safe
Scales
Schmoo
Seabattle
Seawar
Shoot
Smash
Strike 9
Tennis
Tickertape
TV Plot
Twonky
Two-to-Ten
UFO
Under & Over
Van Gam
Warfish
Word Search Puzzle
Wumpus 1
Wumpus 2

A Fantastic Book

Here is the sequel to the best-selling book "Basic Computer Games."

In it you'll find 84 fascinating and entertaining games for solo and group play. Talk to Eliza, evade a man-eating rabbit, crack a safe, tame a wild horse, become a millionaire, race your Ferrari, joust with a knight, trek across the desert on your camel, navigate in deep space, hunt a wumpus and much more.

All games are complete with program listing, sample run and description. All run in standard Microsoft Basic. Easy to use with any computer.

Edited by David Ahl and Steve North with a preface by Christopher Cerf. Outrageous illustrations by George Beker. Large format paperbound, 200 pages, $7.50.

To order send your check for $7.50 plus $1.00 shipping in U.S. ($2.00 foreign) to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. Visa, MasterCard or American Express are also acceptable; send card number and expiration date.

Specify Microsoft Basic or TRS-80 Edition.

Order Toll Free in continental U.S.
800-631-8112
(In NJ call 201-540-0445)

master charge
VISA
AMERICAN EXPRESS

Payment for telephone orders must be made with Visa, MasterCharge, or American Express.

creative computing
P.O. Box 789-M Morristown, New Jersey 07960

CIRCLE 350 ON READER SERVICE CARD

Bridge Challengers

Stephen Kimmel

There are at least ten people who play bridge for every chess player in America. It is probably fair to say that while bridge is played by socially active adults, the average chess player abandoned chess when he discovered sex.

Appropriate howls and screams from the chess delegations. . .

Consider. Bridge is a social game, requiring at least four people, frequently involving eight or more. Chess is a brain teaser requiring only two humans or one human and one of the better computer chess players. Bridge requires that the players talk to each other. Chess prefers silence. Bridge has natural breaks that occur every five to fifteen minutes that encourage conversation and socializing. Chess may require four or five hours of intense concentration. Bridge is a game. Chess is armed combat. Bridge can be fun. Chess is like morning calisthenics.

Why are there dozens of chess programs on the market and only two bridge programs? First, personal computers and chess are related activities in that both require concentration and intense mental activity. As such, both are essentially antisocial. You leave your wife and kids, close the door and kill klingons. Or you can seal yourself behind a wall of concentration in a chess game. Neither activity lends itself to socializing.

The second reason is more telling, in my opinion. The chess experts have always agreed that it was theoretically possible for a computer to play acceptable chess. The bridge experts have never made that concession about their game. With chess, all of the information is always available to all of the players all of the time. From a given position in a chess game there are a limited number of moves. While bridge also has a limited number of moves, at least half of the information is hidden all of the time. This key difference, the dealing with certainties versus dealing with unknowns, is what separates the two games.

The problem with bridge is that you need at least four players. Three simply won't cut it. The ideal computerized bridge player would be the extra player you needed. It would know all the major bidding conventions. It would play well on offense and passably on defense. If possible, it would read regular cards. It would be a robot that could sit at the table with three humans and hold its own. Of course, it would keep score.

There are two products on the market that play computerized bridge. Curiously, they are both named Bridge Challenger.

After shuffling the cards, you feed the computer's cards over a built-in optical scanner, where it reads the bar codes marked on each card.

Bridge Challenger is a product of Personal Software, written by George Duisman in Basic. It sells for $14.95 and comes in versions for TRS-80, Apple and Pet. Personal Software are the same people who brought you Microchess. (Personal Software Inc., 1330 Bordeaux Dr., Sunnyvale, CA 94086.)

Bridge Challenger, on the other hand, is a dedicated computer produced by Fidelity Electronics of Miami, Florida. At about $300, it costs slightly more than *Bridge Challenger*. Fidelity are also the manufacturers of Chess Challenger and Backgammon Challenger (Fidelity Electronics, 8800 Northwest 36th St., Miami, FL 33178.)

When I started this project, I thought I'd play them against each other the same way we did in the Creative Computing Computer Chess Tournament. That way I hoped to determine which played the better bridge. Unfortunately, that was impossible.

Personal Software's Bridge Challenger

Imagine if you will a football program designed to simulate the Super Bowl in which you were always the Pittsburgh Steelers while the Computer was always the Los Angeles Rams. Imagine further that the Steelers are always on offense and never play defense. And that they always start their drives on the fifty yard line. That the Rams don't play defense very well and that the computer can't keep score. You'd probably say that the program was incomplete and far from satisfactory.

Personal Software's *Bridge Challenger* has no provision for bidding, so it is missing a substantial portion of the game. It doesn't keep score. It only plays defense, and doesn't play that very well. As an extra bridge player the program is completely unsatisfactory.

What does that leave for the P.S. *Bridge Challenger*? The play of the hand is one of the interesting portions of the game. There are lessons to be learned by simply playing out the hand. Perhaps there is a place for *Bridge Challenger*: something to practice bridge against.

I tried it against a number of humans to test their reactions to it. My experienced bridge players found it laughably inadequate; my inexperienced bridge players (just learning or less than six months of active bridge playing) found it a moderate challenge. One stated that the only hands he had problems with were ones that he had fouled up. My totally naive bridge players couldn't get interested in the program at all.

Bridge Challenger does follow suit. Its defense is mediocre at best and it frequently will enable a player to make a bid

Stephen Kimmel, 4756 S. Irvington Place, Tulsa, OK 74135

"GET A HEAD START ON TOMORROW WITH THE SOFTWARE THAT'S GOING PLACES. THE UCSD p-SYSTEM.™"

JULIE ERWIN, Director of Marketing, SofTech Microsystems

Our microcomputer software system's going places for good reasons:

We're constantly expanding and developing it. We started with UCSD Pascal,™ added FORTRAN, and we'll be introducing more in the months ahead.

We offer a total development and execution environment, from operating system and cross assemblers to screen editor.

We run on most major microprocessors today: Z80, 8080, 8085, 6502, 6800, 6809, 9900 and LSI-11.™ And because the UCSD p-System's portable, you can be sure that what you invest in software today is a good investment in tomorrow.

We're going places and gaining in popularity with microcomputer manufacturers, applications developers, and demanding end users. Get a head start on tomorrow by working with a company that knows how to develop professional quality software, and that's committed to delivering it.

Our system's available for distribution licensing or for single-copy sales. With Pascal, it costs $350... with FORTRAN, $400...and with both languages, $550. Documentation sets are $50. Phone orders are welcome, and Visa and Master Card orders are accepted. Write or call for more details.

SOFTECH MICROSYSTEMS
A SUBSIDIARY OF SOFTECH

9494 Black Mountain Road, San Diego, CA 92126. (714) 578-6105
TWIX: 910-335-1594

UCSD p-System and UCSD Pascal are trademarks of the Regents of the University of California. LSI-11 is a trademark of Digital Equipment Corp.

CIRCLE 251 ON READER SERVICE CARD

Bridge, cont'd...

by overtaking a trick it has already taken. Personal Software's *Bridge Challenger* gets half a star and a don't-bother recommendation. (Considering Personal Software's marketing procedures, the program will probably never get much better.)

Fidelity Electronic's Bridge Challenger

Fidelity Electronics has come much closer to the goal with their Bridge Challenger. I recommend it — if you can find one, that is. Fidelity had production problems and were unable to meet the demand last Christmas. We bought the last one available in Tulsa, America's 43rd largest city.

Physically, the Bridge Challenger is everything you'd want it to be. Nice solid appearance, easy-to-understand instruction book, a nice carrying case. Everything is essentially the way you would design it if you were working from theory. Physically.

Sometimes, however, Bridge Challenger makes bizarre mistakes.

The Bridge Challenger comes with three felt pads where it "holds" up to three hands. After shuffling the cards, you feed the computer's cards over a built-in optical scanner, where it reads the bar codes marked on each card. That way it can play with real people. Some people have reported having difficulty getting the machine to read the cards. It appears to be a matter of speed and touch. I had no problems with it but my bridge expert never did get the hang of it. Fidelity should probably put in some mechanical means of feeding the cards past the scanner at the correct speed.

The Programming

In retrospect, Fidelity introduced this product in the same state of development as the original Chess Challenger. The unit played chess at the novice level. To Fidelity's credit, they are never satisfied with their products and are constantly working to improve them. The current Chess Challenger plays excellent chess. If Fidelity repeats its performance with the Bridge Challenger it will be a good product next year and a terrific product the year after that. And the price will probably be down to $100. Preliminary reports on the next model are very favorable. As for the current model. . .

Bridge is a two-part game. First, all four players bid until one partnership wins the contract. The contract establishes how many tricks the leading partnership must take, and what suit is trumps. In bridge,

you only score points that count toward game if you bid and make your contract. The bidding portion of the game is almost more important than the playing of the hand. If you consistently end up in the wrong contract, you won't win no matter how well you play the cards.

Bridge Challenger's bidding is generally adequate. Experts might quibble over many points of the bidding but normally it ends up in the right contract. Sometimes, however, Bridge Challenger makes bizarre mistakes. Consider this hand:

NORTH (CHALLENGER)
S.10,6,4,3
H.K,7,6,3
D.A,10,8,6,4

WEST	C. -	EAST
S.8,5,2		S.Q,9,7
H.J,10,5		H.Q,9,8
D.5,2		D.Q,J
C.J,7,5,4,2		C.10,9,8,6,3

SOUTH (CHALLENGER)
S.A,K,J
H.A,4,2
D.K,9,7,3
C.A,K,Q

Bidding:

SOUTH	WEST	NORTH	EAST
2NT	Pass	3D	Pass
3H	Pass	4H	Pass
3S	Pass	4C	Pass
5C	Pass	6D	Pass
Pass	Pass		

The computer enters the Gerber convention by bidding 4C over the bid of 3S. Except that three spades isn't a legal bid after a bid of four hearts. Although four clubs is all right after three spades, it isn't legal after four hearts. Bridge Challenger misinterpreted the bids. ended up in a hopeless contract and went down badly.

Or consider this hand:

NORTH (CHALLENGER)
S.7,6
N.K,J,2
D.9,6,5,2
C.A,K,7,4

WEST	EAST
S.K,3	S.5,4,2
H.10,8,7,6,3	H.A,Q,9,5,4
D.K,8,4	D.A,7,3
C.8,5,3	C.10,9

SOUTH (CHALLENGER)
S.A,Q,J,10,9,8
H. —
D.Q,J,10
C.Q,J,6,2

Again Bridge Challenger is North and South and this time it is vulnerable — a condition that seems any too likely to happen.

The bidding in bridge is communication through the restricted language of the bidding. Each partner describes his hand in these terms. When that communication is fouled up, it is very fouled up. This hand is a laydown in four spades. but how did Challenger bid it?

WEST	NORTH	EAST	SOUTH
Pass	Pass	1H	2S
Pass	2NT	Pass	3C
Pass	4C	Pass	4H
Pass	5C	Pass	5S
Pass	6C	Double	Pass
Pass	Pass		

With only 24 high card points between them, North and South should give no real consideration to game in Notrump or in a minor suit. Slam is completely out of the question. South's first bid says "I have a powerful spade suit and an opening hand." North, having already said he doesn't have 13 points says, "I've got powerful little and it is spread out." South should say 4S saying, "Okay, I'll go it alone." *Instead* South says "My only other biddable suit is clubs." North responds, "Well hell, we may have

The Perfect Fit

The Micromodem II data communications system and the Apple II* computer. What better combination to maximize the capabilities of your personal computer!

This popular direct connect modem can transmit data between an Apple II and another Apple II, a terminal, another microcomputer, minicomputer or even a large time-sharing computer anywhere in North America. The Micromodem II has unique automatic dialing and answer capabilities which further increases the communications possibilities between the Apple II and another computer or terminal.

You can send and/or receive messages or data when you are out of your office, home or out of town. Your branch business locations can communicate with each other regarding inventory and other matters over the phone. Or you can communicate with friends across the country. And you can access information utilities like the SOURCE for various business and personal applications.

The Micromodem II consists of two parts. One part includes the printed circuit board which holds the Micromodem II, ROM firmware and the serial interface. The board plugs directly into the Apple II providing all the functions of a serial interface card plus programmable auto dialing and auto answer capabilities. The on-board ROM firmware enables the Micromodem II to operate in any of three modes to perform different tasks-terminal mode, remote console and program control mode.

The other part of the Micromodem II datacomm system is a Microcoupler which connects the Micromodem board and Apple II to a telephone line. The Microcoupler gets a dial tone, dials numbers, answers the phone and hangs up when a transmission is over. There are none of the losses or distortions associated with acoustic couplers. The Microcoupler is compatible with any North American standard telephone lines and is FCC-approved for direct connection in the U.S. It works with standard dial phone service or Touch-tone service.

The Micromodem II is completely compatible with Bell 103-type modems. Full and half-duplex operating modes are available as well as speed selectable transmission rates of 110 and 300 bps.

Why not increase your Apple II's capabilities by outfitting it with the sophisticated Micromodem II data communications system? The Micromodem II is available at retail computer stores nationwide. For the store nearest you, call or write:

Hayes™

Hayes Microcomputer Products Inc.
5835 Peachtree Corners East, Norcross, Georgia 30092 (404) 449-8791

™ Micromodem II is a trademark of Hayes Microcomputer Products, Inc.
* Apple II is a registered trademark of Apple Computer Inc.
The Micromodem II can also be used with the Bell & Howell computer.

CIRCLE 213 ON READER SERVICE CARD

Bridge, cont'd...

a chance at Slam. How many aces do you have?" Or perhaps North is saying, "Yes I have clubs too." South says, "I only have one ace, partner. You figure out how many we have between us." North says, "Yes, I have clubs." South says, "Are you crazy? If you have that many points? Why didn't you open?" I don't have any Kings." North responds, "I have clubs. We have two aces out against us and two kings. Let's play this in clubs." East jumps in now and says, "Ain't no way." South says, "I give up. Who dealt this?"

Almost any contract in clubs is impossible, much less slam. East/West take two diamond tricks, one spade and two heart tricks to win more points than the game was worth.

There are some bad bugs in the bidding portion of the program. They seem most apparent when the machine makes mistakes and when it is bidding slams. One hopes these will be corrected shortly. Until they are corrected, they render the value of the unit minimal at best.

Fidelity's advertisements say, "Superb playing ability. . ." Uhhhhh.

The Bridge Challenger has gotten a lot of bad press lately in the bridge magazines. almost all of it has been directed toward Challenger's poor playing ability. Fidelity has recently stated that the Challenger has "a beginner's play of the hand." That is just about right.

The current Bridge Challenger almost always draws trumps and almost never finesses. It will only finesse if the opportunity presents itself. It will not set up a finesse. Considering how poorly it does finesse when it does try one, it might be better off not trying. However, it does maintain transportation between the declarer and the dummy, which is better than I do sometimes. defense is much more difficult to play well, and Bridge Challenger seems to do all right — although it discards tend toward the stupid.

If Fidelity repeats its performance with the Bridge Challenger it will be a good product next year and a terrific product the year after that.

What is the verdict, then? Forget Personal Software's *Bridge Challenger*. It is too slow — a bridge program should be written in assembler, not Basic — too limited, and too mediocre to consider seriously. There is no realistic prospect that it will get better.

Although I originally hoped to give Fidelity's Bridge Challenger a good review, I'm afraid that this will be a mixed review at best. The device has been crucified in the bridge magazines. *Popular Bridge* stated that the Bridge Challenger was "worthless at any price. . . *Popular Bridge* accepted the first advertisements for the Challenger in good faith, relying on the technical ability of a firm that had produced a good chess and backgammon robot. *Popular Bridge* will accept no further advertisement of the Bridge Challenger." The Contract Bridge *Bulletin* was only slightly more graceful. One magazine went so far as to request its advertisers to stop selling the Challenger.

On the other hand, my local Sears sold out of them and has reported that none of them have been returned by dissatisfied customers. The Sears people went on to tell me that they guarantee customer satisfaction or money back. Obviously there are a lot of satisfied customers out there.

My recommendation is that you wait until the next model comes out. Or better yet, the next model. That one should really be worth the money. Until then . . . well . . . With some more work the Fidelity Bridge Challenger will be a fine product. □

Pump Up Your TRS-80 with the ES/F Mass Storage System

▲ Actual Size

Actual Thickness ▼

THESE FACTS SPEAK FOR THEMSELVES!

	CASSETTE	ES/F	MINI-DISK
SPEED (Seconds to load "Blackjack")	56	6 (5' wafer)	6½
CAPACITY (thousands of bytes)	38 (C-20)	64 (75' wafer)	59 (TRSDOS)
RELIABILITY (Designed for digital data?)	NO	YES	YES
SYSTEM COST (First unit plus interface)	$60	$250	$800
MEDIA COST (in quantities of ten)	$3.10 cassette	$3.00 wafer	$3.20 disk

Let's face it. Cassette players were not designed to store digital data and programs. That's why we designed a digital storage system using a continuous tape loop: the Exatron *Stringy/Floppy* (ES/F) and the Wafer. There's no expensive interface to buy—the ES/F comes ready to pump up your TRS-80.*

Once your TRS-80* is pumped up by our ES/F . . . you won't want to deflate it. We're so sure, that we offer an unconditional 30-day money-back guarantee and a one-year limited warranty. Over 2,000 TRS-80* owners have met the wafer . . . why don't you?

TRS-80*

EXATRON'S STRINGY/FLOPPY...

SPEED, CAPACITY AND RELIABILITY FOR ONLY $249.50

CALL
OUR HOTLINE
(800)-538-8559

IN CALIFORNIA,
CALL (408)-737-7111

exatron, inc.
181 Commercial Street
Sunnyvale, Calif. 94086

CIRCLE 270 ON READER SERVICE CARD

*TRS-80 is a registered trademark of Tandy Corp.

PERMANENT RELIEF

Of today's and tomorrow's Word Processing problems



Apple PIE + Formatter

Apple PIE (Programma International Editor) and FORMAT (text formatter) offer full strength solutions to today's word processing problems. These versatile, powerful programs provide document preparation and word processing capabilities previously found only on much larger computer systems.

PIE is a general purpose, full screen editor that uses control keys and function buttons to provide a full range of editing capabilities such as search and replace, delete, copy, insert, move. Changes may be made directly anywhere on the screen and are shown as they are performed.

FORMAT uses simple instructions embedded in the input text to describe the desired appearance of the final document. It handles *centering*, *underlining*, indenting, page numbering, margins, headers, footers, even form letters, and includes a proofing capability.

These high-quality, cost-effective programs come with comprehensive documentation and run on a 32K Apple II. They are available through your local computer store or direct from Programma International, Inc. at the introductory price of $79.95*.

VIDEX VERSION T.M.
DOUBLE VISION T.M.
SUPR TERM VERSION T.M.
STANDARD VERSION

*December 1, $129.95.

PROGRAMMA
3400 Wilshire Boulevard
Los Angeles, California 90010
213-384-0579

or

Simple enough for the beginner. Versatile enough for the professional. CIRCLE 230 ON READER SERVICE CARD

Apple Pascal

Steve North

For the last several months I have been using the Apple/UCSD Pascal system, and I'd like to share my impressions with you.

To run Pascal on the Apple II, you must plug in a Language System board in slot 0, and insert a 16-pin jumper into a memory chip socket. This allows the 48K Apple to think it has 64K of RAM, or to switch back to normal mode (with Basic in ROM). You must also replace your old disk bootstrap ROMs on the disk controller card to accommodate the higher-density disk format Pascal (and the new Basic DOS) use. After replacing the disk-boot ROMs, you can directly boot Pascal or DOS 3.3, and can convert old Basic disks to the new format or boot them by a two-step process. One should reasonably have at least two disk drives to run Pascal.

Apple Pascal is not only a language compiler, but a complete operating system with utilities and libraries. It is screen-oriented (with lots of paging instead of scrolling) and meshes in a pleasing way with the Apple's graphics, sound effects, game paddles, and plug-in I/O cards. However, this monolithic style of software design — making one giant self-contained system to Do It All — can be more restrictive than very open-ended designs incorporating many very small (sometimes disposable) software tools. (While there are no absolutes, CP/M follows this philosophy much more closely, and this helps explain why it is so popular and there is so much CP/M compatible software.) Certainly Apple Pascal presents the user with a much more integrated view of the system, but at a price.



Steve North, 35A Orchard Street, Summit, NJ 07901.

Pascal is easy to learn and almost forces one to write logical, readable, understandable programs.

The Choices

When Pascal is booted, it displays a menu of commands, each activated by a single keypress. The following are available:

E) Edit a file. The editor is screen-oriented — you have a cursor you move around within the file to do insertions, changes, and deletions — but it is more slanted toward program development than letter-writing. For example, it has an auto-indent mode to encourage the writing of structured programs, and it can also be told to discriminate between quoted text and Pascal code. The editor and the rest of the system can default to a "current work file," which is very convenient for sessions of editing, compiling, and debugging.

F) File system. This subsystem gives you access to another set of commands for listing directories, copying files, testing for bad disk sectors, scrunching free space on disks, and the like. Disks can be accessed symbolically (by a name like GAMES or XYZ98) rather than by physical device number, a feature that would be welcome in other systems. The operating system is also smart about allowing you to change disks (and even asks you to do it when necessary), unlike other operating systems which throw up their hands in despair when disks have been changed without rebooting.

C) Compile. The compiler is the heart of the Pascal system. The compiler and library incorporate almost all of the stuff in the Jensen and Wirth *Pascal User Manual and Report,* and adds some very welcome extensions, such as Logo-like turtle-graphics, without any kludging. *(Editor's note: "turtles" are hypothetical reptiles with pens in their beaks that rotate and crawl on the screen under program control.)*

Pascal itself (as a language, not speaking of any implementation in particular) is a very nice, cleanly designed language for both simple and complex programming. Designed by Wirth in Europe, some Americans found it Teutonic and restrictive. Its only major competitor for this kind of programming on personal computers is C, another "structured" language. Most compupeople seem to agree that C is a somewhat more powerful language than Pascal, especially for systems software writing, but it is harder to

No. 17½
Software with full support

Purchasing our software is just the beginning. We then back it up with professional support:

■ Subscription to "LIFELINES" for automatic notifications of revisions! ■ Update service for software and documentation! ■ Telephone Hotline! ■ Overseas software export service!

Genuine CP/M for Apple II Available now!

Software with Manual / Manual Alone

CP/M* FLOPPY DISK OPERATING SYSTEM—Digital Research's operating system configured for many popular micro-computers and disk systems:

System	Version	Price
Apple II*	2.x	349/NA ◇
New → SoftCard* with Z80 Microsoft BASIC version 5 with high resolution graphics		
North Star Single Density	2.x	170/25
North Star Double/Quad	2.x	170/25
Durango F-85	2.x	170/25
iCOM Micro-Disk 2411	1.4	145/25
iCOM 3712 for MITS 88-2SIO Console	1.4	170/25 *
iCOM 3712 for 3PtS/MITS SIO Rev non-zero console	1.4	170/25 *
iCOM 3812	1.4	170/25 *
iCOM 4511/Pertec D3000	2.x	375/25 * +
Mits 3202/Altair 8800	1.4	145/25
Heath H8 + H17	1.4	145/25 Ⓜ
Heath H89	1.4	145/25 Ⓜ
Heath H89 by Magnolia	2.x	250/25 ◇
Ohio Scientific C3	2.x	200/25
Onyx C8001 Standard	2.x	250/25
Onyx C8001 Enhanced	2.x	330/25
TRS-80 Model I	1.4	145/25 Ⓜ
TRS-80 Model II	2.x	170/25
TRS-80 Model II + Corvus	2.x	250/25
Processor Technology Helios II	1.4	145/25
Intel MDS Single Density	2.x	170/25
Intel MDS Double Density	2.x	170/25
Micropolis Mod I	2.x	200/25 Ⓥ
Micropolis Mod II	2.x	200/25 Ⓥ
Mostek MDX STD Bus System	2.x	350/25 **
The following configurations are scheduled for release soon:		
North Star Double/Quad + Corvus	2.x	250/25
Ohio Scientific C3-C	2.x	250/25
iCOM 3812	2.x	225/25 *
iCOM 4511/Pertec D3000	2.x	375/25 * +

*Software consists of the operating system, text editor, assembler, debugger and other utilities for file management and system maintenance. Complete set of Digital Research's documentation and additional implementation notes included. Systems marked * and ** include firmware on 2708 and 2716. Systems marked + include 5440 media charge. Systems marked Ⓜ require the special Ⓜ versions of software in this catalog. ◇ includes hardware addition to allow our standard versions of software to run under it.*

Z80 DEVELOPMENT PACKAGE—Consists Ⓜ of: (1) disk file line editor, with global inter and Ⓩ intra-line facilities; (2) Z80 relocating assembler, Zilog/Mostek mnemonics, conditional assembly and cross reference table capabilities; (3) linking loader producing absolute Intel hex disk file ..... $95/$20

ZDT—Z80 Monitor Debugger to break and Ⓜ examine registers with standard Zilog/ Ⓩ Mostek mnemonic disassembly displays. $35 when ordered with Z80 Development Package ..... $50/$10

AVOCET SYSTEMS

XASM-68—Non-macro cross-assembler with nested conditionals and full range of pseudo operations. Assembles from standard Motorola MC6800 mnemonics to Intel hex ... $200/$25

XASM-65—As XASM-68 for MOS Technology MCS-6500 series mnemonics ..... $200/$25

XASM-48—As XASM-68 for Intel MCS-48 and UPI-41 families ..... $200/$25

XASM-18—As XASM-68 for RCA 1802 ..... $200/$25

DISTEL—Disk based disassembler to Intel 8080 or TDL/Xitan Z80 source code, listing and cross reference files, Intel or TDL/Xitan pseudo ops optional. Runs on 8080 ..... $65/$10

DISILOG—As DISTEL to Zilog/Mostek Ⓜ mnemonic files ..... $65/$10 Ⓩ

SMAL/80 Structured Macro Assembler Ⓧ Language—Package of powerful general purpose text macro processor and SMAL structured language compiler. SMAL is an assembler language with IF-THEN-ELSE, LOOP-REPEAT-WHILE, DO-END, BEGIN-END constructs. Not compatible with CP/M version 2 or greater. ..... $75/$15

PHOENIX SOFTWARE ASSOCIATES

PASM*—Z80 macro assembler, Intel/TDL Ⓩ mnemonics. Generates Intel hex format or relocatable code in either TDL Object Module format or PSA Relocatable Binary Module format. Supports text insertion, conditional branching within macros, recursive macro calls and parameter passing. ..... $129/$25

EDIT—Character oriented text file editor. In- Ⓩ cludes macro definition capabilities. Handles insertion, deletion, searching, block move, etc. for files of any length. Does not require a CRT. ..... $129/$25

New → **PLINK***—Two pass **disk-to-disk linkage edi- Ⓩ tor/loader** which can produce re-entrant, ROMable code. Can link programs that are larger than available memory for execution targeted on another machine. Full library capabilities. Input can be PSA Relocatable Binary Module, TDL Object Module or **Microsoft REL files**. Output can be a COM file, Intel hex file, TDL Object Module or PSA Relocatable file. ..... $129/$25

New → **BUG* and μBUG***—Z80 interactive machine Ⓩ level debugging tools for program development. BUG has full symbolic trace and interactive assembly (mnemonics compatible with PASM). Dynamic breakpoints and conditional traps while tracing (even through ROM!). μBUG is a subset of BUG and is used in memory limited situations ..... $129/$25

DIGITAL RESEARCH

MP/M—Installed for single density MDS-800. Multi-processing derivative of the CP/M operating system. Manual includes CP/M2 documentation ..... $300/$50

MAC—8080 Macro assembler. Full Intel macro Ⓢ definitions. Pseudo Ops include RPC, IRP, REPT, TITLE, PAGE, and MACLIB. Produces absolute hex output plus symbol table file for use by SID and ZSID (see below) ... $120/$15

SID—8080 Symbolic debugger. Full trace, Ⓢ pass count and breakpoint program testing. Has backtrace and histogram utilities. When used with MAC, provides full symbolic display of memory labels and equated values .$105/$15

ZSID—Z80 Symbolic debugger with all fea- Ⓢ tures of SID ..... $130/$15 Ⓩ

TEX—Text output formatter to create paginat- Ⓢ ed, page-numbered and justified copy. Output can be directed to printer or disk ... $105/$15

DESPOOL—Utility program to permit simulta- Ⓢ neous printing from text files while executing other programs ..... $80/$10

tiny C—Interactive interpretive system for Ⓧ teaching structured programming techniques. Manual includes full source listings $105/$50

New Version → **BDS C COMPILER**—Supports structures, Ⓜ unions, 2 dimensional arrays, pointers, recur- Ⓘ sion and overlays. Features optimized code generator, variable sized buffers for file I/O, and capability to produce ROMable code. Includes macro package to enable user to produce linkable modules with MAC (see under Digital Research). Floating point functions, full run-time package and machine code library sources provided. Linker, library manager and textbook included. Compiler lacks initializers, statics, floats and longs. ..... $145/$25

Software with Manual / Manual Alone

New → **WHITESMITHS C COMPILER**—The ultimate Ⓛ in systems software tools. Produces faster Ⓚ code than a pseudo-code Pascal with more extensive facilities. Conforms to the full UNIX* Version 7 C language, described by Kernighan and Ritchie, and makes available over 75 functions for performing I/O, string manipulation and storage allocation. Linkable to Microsoft REL files. Requires 60K CP/M .... $630/$30

MICROSOFT

BASIC-80—Disk Extended BASIC, ANSI Ⓒ compatible with long variable names, Ⓜ WHILE/WEND, chaining, variable length file records. MBASIC version 4.51 also included on disk. ..... $325/$25

BASIC COMPILER—Language compatible Ⓛ with BASIC-80 and 3-10 times faster execution. Ⓜ Produces standard Microsoft relocatable binary output. Includes MACRO-80. Also linkable to FORTRAN-80 or COBOL-80 code modules ..... $350/$25

FORTRAN-80—ANSI 66 (except for COM- Ⓛ PLEX) plus many extensions. Includes relocat- Ⓜ able object compiler, linking loader, library with manager. Also includes MACRO-80 (see below) ..... $425/$25

COBOL-80—Level 1 ANSI '74 standard plus Ⓛ most of Level 2. Full sequential, relative, and Ⓜ indexed file support with variable file names. Powerful interactive, formatted screen handling with ACCEPT and DISPLAY verbs. Program segmentation for execution of programs larger than memory and CHAIN command with parameter passing. Full support of CP/M version 2 files. Includes MACRO-80 (see above), linking loader, and relocatable library manager. Requires 48K CP/M ..... $700/$25

MACRO-80—8080/Z80 Macro Assembler. Ⓛ Intel and Zilog mnemonics supported. Relocat- Ⓜ able linkable output. Loader, Library Manager and Cross Reference List utilities included ..... $149/$15

XMACRO-86—8086 cross assembler. All Ⓛ Macro and utility features of MACRO-80 package. Mnemonics slightly modified from Intel ASM86. Compatibility data sheet available ..... $275/$25

EDIT-80—Very fast random access text editor Ⓛ for text with or without line numbers. Global and intra-line commands supported. File compare utility included. ..... $89/$15

PASCAL/M*—Compiles enhanced Standard Ⓧ Pascal to compressed efficient Pcode. Totally CP/M compatible. Random access files. Both 16 and 32-bit Integers. Runtime error recovery. Convenient STRINGs. OTHERWISE clause on CASE. Comprehensive manual (90 pp. indexed). SEGMENT provides overlay structure. INPORT, OUTPORT and untyped files for arbitrary I/O. Requires 56K CP/M. Specify 1) 8080 CP/M, 2) Z80 CP/M, or 3) Cromemco CDOS. ..... $175/$20

PASCAL/Z—Z80 native code PASCAL com- Ⓘ piler. Produces optimized, ROMable re-entrant Ⓩ code. All interfacing to CP/M is through the support library. The package includes compiler, relocating assembler and linker, and source for all library modules. Variant records, strings and direct I/O are supported. Requires 56K CP/M ..... $395/$25

PASCAL/MT—Subset of standard PASCAL. Ⓜ Generates ROMable 8080 machine code. Ⓧ Symbolic debugger included. Supports interrupt procedures, CP/M file I/O and assembly language interface. Real variables can be BCD, software floating point, or AMD 9511 hardware floating point. Includes strings enumerations and record data types. Manual explains BASIC-PASCAL conversion. Requires 32K .$250/$30

APL/V80—Concise and powerful language for Ⓩ application software development. Complex programming problems are reduced to simple expressions in APL. Features include up to 27K active workspace, shared variables, arrays of up to 8 dimensions, disk workspace and copy object library. The system also supports auxiliary processors for interfacing I/O ports. Requires 48K CP/M and serial APL printing terminal or CRT ..... $500/$30

ALGOL-60—Powerful block-structured lan- Ⓩ guage compiler featuring economical run-time Ⓜ dynamic allocation of memory. Very compact (24K total RAM) system implementing almost all Algol 60 report features plus many powerful extensions including string handling direct disk address I/O etc. ..... $199/$20

CBASIC-2 Disk Extended BASIC—Non- Ⓜ interactive BASIC with pseudo-code compiler and run-time interpreter. Supports full file control, chaining, integer and extended precision variables, etc. Versions of CRUN for CP/M versions 1.4 and 2.x included on disk. .$120/$15

MICRO FOCUS

STANDARD CIS COBOL—ANSI '74 COBOL Ⓘ standard compiler fully validated by U.S. Navy tests to ANSI level 1. Supports many features to level 2 including dynamic loading of COBOL modules and a full ISAM file facility. Also, program segmentation, interactive debug and powerful interactive extensions to support protected and unprotected CRT screen formatting from COBOL programs used with any dumb terminal ..... $850/$50

FORMS 2—CRT screen editor. Output is Ⓒ COBOL data descriptions for copying into CIS COBOL programs. Automatically creates a query and update program of indexed files using CRT protected and unprotected screen formats. No programming experience needed. Output program directly compiled by STANDARD CIS COBOL ..... $200/$20

Software with Manual / Manual Alone

NEVADA COBOL—Subset of ANSI-74. Fea- Ⓜ tures fast compilation and execution with small object modules. Has extended arithmetic with 18 digit accuracy. Extended I/O includes random access files and sequential files of both fixed and variable length records, and interactive accept/display verbs. Good error messages and debugging facilities enhance program development. Requires a 32K CP/M system ..... $149/$25

EIDOS SYSTEMS

KBASIC—Microsoft Disk Extended BASIC Ⓛ version 4.51 integrated with KISS Multi-Keyed Index Sequential and Direct Access file management as 9 additional BASIC commands. KISS included as relocatable modules linkable to FORTRAN-80, COBOL-80, and BASIC COMPILER. Specify CP/M version 1.4 or 2.x when ordering. Requires 48K CP/M $585/$45 To licensed users of Microsoft BASIC-80 (MBASIC) ..... $435/$45

XYBASIC Interactive Process Control BASIC—Full disk BASIC features plus unique commands to handle byte rotate and shift and to test and set bits. Available in several versions:

Integer ROM squared	$350/$25
Integer CP/M	$350/$25
Extended ROM squared	$450/$25
Extended CP/M	$450/$25
Extended Disk CP/M	$550/$25
Integer CP/M Run Time Compiler	$350/$25
Extended CP/M Run Time Compiler	$450/$25

RECLAIM—A utility to validate media under CP/M. Program tests a diskette or hard disk surface for errors, reserving the imperfections in invisible files, and permitting continued usage of the remainder. Essential for any hard disk. Requires CP/M version 2. ..... $80/$5

BASIC UTILITY DISK—Consists of: (1) Ⓜ CRUNCH-14— Compacting utility to reduce the size and increase the speed of programs in Microsoft BASIC 4.51, BASIC-80 and TRS-80 BASIC. (2) DPFUN—Double precision subroutines for computing nineteen transcendental functions including square root, natural log, log base 10, sine, arc sine, hyperbolic sine, hyperbolic arc sine, etc. Furnished in source on diskette and documentation ..... $50/$35

STRING/80—Character string handling plus routines for direct CP/M BDOS calls from FORTRAN and other compatible Microsoft languages. The utility library contains routines that enable programs to chain to a COM file, retrieve command line parameters and search file directories with full wild card facilities. Supplied as linkable modules in Microsoft format. $95/$20

STRING/80 source code available separately— $295/NA

THE STRING BIT—FORTRAN character Ⓜ string handling. Routines to find, fill, pack, move, separate, concatenate and compare character strings. This package completely eliminates the problems associated with character string handling in FORTRAN. Supplied with source ..... $65/$15

VSORT—Versatile sort/merge system for fixed Ⓜ length records with fixed or variable length fields. VSORT can be used as a stand-alone package or loaded and called as a subroutine from CBASIC-2. When used as a subroutine, VSORT maximizes the use of buffer space by saving the TPA on disk and restoring it on completion of sorting. Records may be up to 255 bytes long with a maximum of 5 fields. Upper/lower case translation and numeric fields supported. ..... $175/$20

CPM/374X—Has full range of functions to create or re-name an IBM 3741 volume, display directory information and edit the data set contents. Provides full file transfer facilities between 3741 volume data sets and CP/M files ..... $195/$10

Coming Soon

CPAids*

MASTER TAX—Professional tax preparation Ⓛ program. Prepares schedules A, B, C, D, E, F, † G, R/RP, SE, TC, ES and forms 2106, 2119, 2210, 3468, 3903, 2441, 4625, 4726, 4797, 4972, 5695 and 6251. Printing can be on readily available, pre-printed continuous forms, on overlays, or on computer generated, IRS approved forms. Maintains client history files and is interactive with CPAids GENERAL LEDGER II (see below) ..... $995/$30 Annual Update Fee $350

STANDARD TAX—As above for schedules A, † B, C, D, E, G, R/RP, SE, TC and forms 2106 and 2441. Also, does not maintain client history files ..... $495/$30 Annual Update Fee $175

GENERAL LEDGER II—Designed for CPA's. † Stores complete 12 month detailed history of transactions. Generates financial statements, depreciation, loan amortizations, journals, trial balances, statements of changes in financial position, and compilation letters. Includes payroll system with automatic posting to general ledger. Prints payroll register, W2's and payroll checks. ..... $450/$30

Lifeboat Associates, 1651 Third Avenue, N.Y., N.Y. 10028
(212) 860-0300 International Telex: 220501, Domestic Telex:64093
Neu in der Schweiz Lifeboat Associates GmbH, Aegeristr. 35, 6340 Baar **Telefon 042/31 2931**

Software with Manual / Manual Alone

☐ **T/MAKER**—Powerful new tool for preparing management reports with tabular data. Makes financial modeling projects easy. Do you want a weekly profitability report? Set up the table and compute. Just change the sales figures for next week and compute. You have a new report! T/MAKER includes a full screen editor for setting up tables which pages left, right, up and down. Compute includes standard arithmetic, percents, exponents, common transcendental functions, averages, maxima, minima, projections, etc. Requires 48K CP/M, CBASIC-2, CRT Terminal with addressable cursor positioning. . . . . **$275/$25**

☐ **BSTAM**—Utility to link one computer to another Ⓜ also equipped with BSTAM. Allows file transfers at full data speed (no conversion to hex), with CRC block control check for very reliable error detection and automatic retry. We use it! It's great! Full wildcard expansion to send *.COM, etc. 9600 baud with wire. 300 baud with phone connection. **Both** ends need one. Standard and Ⓜ versions can talk to one another. This software requires a knowledge of assembler language for installation. . . . . **$150/$10**

☐ **BSTMS**—Intelligent terminal program for Ⓜ CP/M systems. Permits communication between micros and mainframes. Sends character data files to remote computers under complete control. System can record character data sent from remote computer systems and data banks. Includes programs to EXPAND and COMPRESS binary files for transmission. This software requires a knowledge of assembler language for installation. . . . . **$200/$25**

☐ **WHATSIT?***—Interactive data-base system using associative tags to retrieve information by subject. Hashing and random access used for fast response. Requires CBASIC-2 **$175/$25**

☐ **SELECTOR III-C2**—Data Base Processor to † create and maintain multi-key data bases. Ⓜ Prints formatted sorted reports with numerical summaries or mailing labels. Comes with sample applications, including Sales Activity, Inventory, Payables, Receivables, Check Register, and Client/Patient Appointments, etc. Requires CBASIC-2. Supplied in source . . . . **$295/$20**

☐ **GLECTOR**—General Ledger option to SELECTOR III-C2. Interactive system provides for customized COA. Unique chart of transaction types insure proper double entry bookkeeping. Generates balance sheets, P&L statements and journals. Two year record allows for statement of changes in financial position report. Supplied in source. Requires SELECTOR III-C2. CBASIC-2 and 56K system. . . . . **$350/$25**

DMA

☐ **CBS**—Configurable Business System is a † comprehensive set of programs for defining custom data files and application systems without using a programming language such as BASIC, FORTRAN, etc. Multiple key fields for each data file are supported. Set-up program customizes system to user's CRT and printer. Provides fast and easy interactive data entry and retrieval **with transaction processing**. Report generator program does complex calculations with stored and derived data, record selection with multiple criteria, and custom formats. Sample inventory and mailing list systems included. **No support language required** . . . . **$395/$40**

MICROPRO

☐ **SUPER-SORT I**—Sort, merge, extract utility as Ⓛ absolute executable program or linkable module in Microsoft format. Sorts fixed or variable records with data in binary, BCD, Packed Decimal, EBCDIC, ASCII, floating & fixed point, exponential, field justified, etc. Even variable number of fields per record! . . . . **$225/$25**

☐ **SUPER-SORT II**—Above available as abso- Ⓛ lute program only . . . . **$175/$25**

☐ **SUPER-SORT III**—As II without SELECT/ Ⓛ EXCLUDE . . . . **$125/$25**

☐ **DATASTAR**—Professional forms control entry Ⓛ and display system for key-to-disk data capture. Menu driven with built-in learning aids. Input field verification by length, mask, attribute (i.e. upper case, lower case, numeric, auto-dup, etc.). Built-in arithmetic capabilities using keyed data, constant and derived values. Visual feedback for ease of forms design. Files compatible with CP/M-MP/M supported languages. Requires 32K CP/M . . . . **$350/$35**

☐ **WORD-STAR**—Menu driven visual word pro- Ⓛ cessing system for use with standard terminals. Text formatting performed on screen. Facilities for text paginate, page number, justify, center and underscore. User can print one document while simultaneously editing a second. Edit facilities include global search and replace, Read/Write to other text files, block move, etc. Requires CRT terminal with addressable cursor positioning . . . . **$445/$40**

☐ **WORD-STAR-MAIL-MERGE**—As above with Ⓛ option for production mailing of personalized documents with mail lists from DATASTAR or NAD . . . . **$575/$40**

☐ **WORD-MASTER** Text Editor—In one mode Ⓛ has superset of CP/M's ED commands including global searching and replacing, forwards and backwards in file in video mode, provides full screen editor for users with serial addressable-cursor terminal . . . . **$145/$25**

Software with Manual / Manual Alone

☐ **MAGIC WAND***—Word processing system with simple, easy to use full screen text editor and powerful print processor. Editor has all standard editing functions including text insert and delete, global search and replace, block move and library files for boiler plate text. Print processor formatting commands include automatic margins, pagination, headings & footings, centered and justified text. Also prints with true proportional spacing, merges with data files for automatic form letters, and performs run-time conditional testing for varied output. Requires 32K CP/M and CRT terminal with addressable cursor. . . . . **$395/$40**

☐ **TEXTWRITER III**—Text formatter to justify and Ⓜ paginate letters and other documents. Special features include insertion of text during execution from other disk files or console, permitting recipe documents to be created from linked fragments on other files. Has facilities for sorted index, table of contents and footnote insertions. Ideal for contracts, manuals, etc. Now compatible with Electric Pencil* and Word-Star prepared files . . . . **$125/$20**

☐ **DATEBOOK**—Program to manage time just like an office appointment book but using the speed and memory of a computer. Keeps track of three appointment schedules (three dental chairs, three attorneys, etc.) at once. Appointments consist of name, reason for the appointment, the date and time, and the length of the appointment. System can be quickly customized for the individual user. Many helpful features for making, changing, finding, and reporting appointments. Requires 48K CP/M and 180K bytes diskette storage. Not available for Apple CP/M. Specify 8080 CP/M, Z80 CP/M or Cromemco CDOS . . . . **$295/$25**

New lower prices for application Software

PEACHTREE SOFTWARE*

☐ General accounting software for small busi- Ⓛ nesses. Each product can be used alone or with † automatic posting to the general ledger. Supplied in source for Microsoft BASIC 4.51.

GENERAL LEDGER	**$530/$40**
ACCOUNTS PAYABLE	**$530/$40**
ACCOUNTS RECEIVABLE	**$530/$40**
PAYROLL	**$530/$40**
INVENTORY	**$660/$40**

☐ Other application products supplied in source Ⓛ for Microsoft BASIC 4.51.

† MAILING ADDRESS	**$530/$40**
PROPERTY MANAGEMENT	**$925/$40**

GRAHAM-DORIAN SOFTWARE SYSTEMS

☐ Comprehensive accounting software written in Ⓛ CBASIC-2 and supplied in source code. Each Ⓜ software package can be used as a stand- † alone system or integrated with the General Ledger for automatic posting to ledger accounts. Requires CBASIC-2.

GENERAL LEDGER	**$805/$40**
ACCOUNTS PAYABLE	**$805/$40**
ACCOUNTS RECEIVABLE	**$805/$40**
INVENTORY SYSTEM	**$555/$40**
JOB COSTING	**$805/$40**
APARTMENT MANAGEMENT	**$805/$40**
CASH REGISTER	**$805/$40**

☐ **POSTMASTER**—A comprehensive package Ⓜ for mail list maintenance that is completely menu driven. Features include keyed record extraction and label production. A form letter program is included which provides neat letters on single sheet or continuous forms. Includes NAD file translator. Requires CBASIC-2. . . . . **$150/$20**

STRUCTURED SYSTEMS GROUP

☐ Complete interactive accounting software for † business. Each product can be used stand-alone or with automatic posting to the general ledger. Each product is thoroughly tested and very well documented.

GENERAL LEDGER	**$820/$40**
ACCOUNTS RECEIVABLE	**$820/$40**
ACCOUNTS PAYABLE	**$820/$40**
PAYROLL	**$820/$40**
INVENTORY CONTROL	**$820/$40**

LIFELINES
NEWSLETTER FROM LIFEBOAT

LIFELINES is the first step in software support for the serious microcomputer user. Each issue reports new revisions together with information on the purpose for each such release, be it for correction of bugs or the addition of features and facilities

Feature Articles ! New Software ! Product Comparisons ! Info on CP/M Users Group !

SUBSCRIPTION INFORMATION:

$18 for twelve issues: U.S., Canada, and Mexico.

$40 for twelve issues: all other countries.

$2.50 for each back issue: U.S., Canada, and Mexico.

$3.60 for each back issue: all other countries.

Send Check to LIFELINES, 1651 Third Avenue, New York, N.Y. 10028 or use your VISA or MASTERCARD—call (212) 722-1700

Software with Manual / Manual Alone

☐ **ANALYST**—Customized data entry and report- † ing system. User specifies up to 75 data items per record. Interactive data entry, retrieval, and update facility makes information management easy. Sophisticated report generator provides customized reports using selected records with multiple level breakpoints for summarization. Requires a disk sort utility such as QSORT, SUPER-SORT or VSORT. . . . . **$250/$15**

☐ **LETTERIGHT**—Program to create, edit and type letters or other documents. Has facilities to enter, display, delete and move text, with good video screen presentation. Integrates with NAD for form letter mailings. . . . . **$200/$25**

☐ **NAD**—Name and Address selection system. Interactive mail list creation and maintenance program with output as full reports with reference data or restricted information for mail labels. System for extraction and transfer of selected records to create new files. **$100/$20**

☐ **QSORT**—Fast sort/merge program for files with fixed record length, variable field length information. Up to five ascending or descending keys. Full back-up of input files created . . . . **$100/$20**

★ ★ ★ ★ ★ ★ ★

CONDIMENTS

★ ★ ★ ★ ★ ★ ★

☐ **HEAD CLEANING DISKETTE**—Cleans the drive Read/Write head in 30 seconds. Diskette absorbs loose oxide particles, fingerprints, and other foreign particles that might hinder the performance of the drive head. Lasts at least 3 months with daily use. Specify 5¼" or 8":

Single sided	**$20 each/$55 for 3**
Double sided	**$25 each/$65 for 3**

☐ **DC 300 Data Cartridges** Specify 450'XL or 300' certified. Pack of 5. . . . . **$100**

☐ **FLIPPY DISK KIT**—Template and instructions to modify single sided 5¼" diskettes for use of second side in single sided drives **$12.50**

☐ **FLOPPY SAVER**—Protection for center holes for 5¼" and 8" floppy disks. Only 1 needed per diskette. Kit contains centering post, pressure tool and tough 7 mil mylar reinforcing rings for 25 diskettes.

5¼", Kit	**$14.95**
5¼", Rings only	**$7.95**
8", Kit	**$16.95**
8", Rings only	**$8.95**

☐ **PASCAL USER MANUAL AND REPORT**—By Jensen and Wirth. The standard textbook on the language. Recommended for use by Pascal/Z, Pascal/M and Pascal/MT users **$12**

☐ **THE C PROGRAMMING LANGUAGE**—By Kernighan and Ritchie. The standard textbook on the language. Recommended for use by BDS C, tiny C, and Whitesmiths C users . . **$12**

☐ **STRUCTURED MICROPROCESSOR PROGRAMMING**—By the authors of SMAL/80. Covers structured programming, the 8080/8085 instruction set and the SMAL/80 language **$20**

☐ **ACCOUNTS PAYABLE & ACCOUNTS RECEIVABLE-CBASIC** book by Osborne/McGraw-Hill **$20**

☐ **GENERAL LEDGER-CBASIC** book by Osborne/McGraw-Hill **$20**

☐ **PAYROLL WITH COST ACCOUNTING-CBASIC** book by Osborne/McGraw-Hill . . **$20**

★ ★ ★ ★ ★ ★ ★

Hearty Appetite.

★ ★ ★ ★ ★ ★ ★

*CP/M and MP/M are trademarks of Digital Research.
Z80 is a trademark of Zilog, Inc.
UNIX is a trademark of Bell Laboratories.
WHATSIT? is a trademark of Computer Headware.
Electric Pencil is a trademark of Michael Shrayer Software.
TRS-80 is a trademark of Tandy Corp.
Pascal/M is a trademark of Sorcim.
SoftCard is a trademark of Microsoft.
Apple is a trademark of Apple Computer.
PASM, PLINK, BUG and μBUG are trademarks of Phoenix Software Associates Ltd.
CPAids is a trademark of Computer Tax Service, Inc.
MAGIC WAND is a trademark of Small Business Application, Inc.
Peachtree Software is a trademark of Retail Sciences, Inc.

† Recommended system configuration consists of 48K CP/M, 2 full size disk drives, 24 x 80 CRT and 132 column printer.

Ⓜ Modified version available for use with CP/M as implemented on Heath and TRS-80 Model I computers.

Ⓛ User license agreement for this product must be signed and returned to Lifeboat Associates before shipment may be made.

Ⓘ This product Includes/eXcludes the language Ⓧ manual recommended in Condiments.

Ⓢ Serial number of CP/M system must be supplied with orders.

② Requires Z80 CPU.

Ordering Information

MEDIA FORMAT ORDERING CODES
When ordering, please specify format code.

LIFEBOAT ASSOCIATES MEDIA FORMATS LIST. Diskette, cartridge disk and cartridge tape format codes to be specified when ordering software for listed computer or disk systems. All software products have specitic requirements in terms of hardware or software support, such as MPU type, memory size, support operating system or language.

Computer system	Format Code
Altair 8800 Disk	See MITS 3200
Altos	A1*
Apple - SoftCard 13 Sector	R6
Apple - SoftCard 16 Sector	RR
AVL Eagle	RB
BASF System 7100	RD
Blackhawk Single Density	Q3
Blackhawk Micropolis Mod II	Q2
CDS Versatile 3B	Q1
CDS Versatile 4	Q2
COMPAL-80	Q2
Cromemco System 3	A1*
Cromemco Z2D	R6
CSSN BACKUP (tape)	T1 #
Delta	A1*
Digi-Log Microterm II	RD
Digital Microsystems	A1*
Discus	See Morrow Discus
Durango F-85	RL
Dynabyte DB8/2	R1
Dynabyte DB8/4	A1*
Exidy Sorcerer - Lifeboat CP/M	Q2
Exidy Sorcerer - Exidy CP/M	Q4
Heath H8 - H17/H27	P4
Heath H89 - Lifeboat CP/M	P4
Heath H89 - Magnolia CP/M	P7
Helios II	See Processor Technology
Horizon	See North Star
iCOM 2411 Micro Floppy	R3
iCOM 3712	A1
iCOM 3812	A1*
iCOM 4511 5440 Cartridge CP/M 1.4	D1 #
iCOM 4511 5440 Cartridge CP/M 2.2	D2 #
IMS 5000	RA
IMS 8000	A1*
IMSAI VDP-40	R4**
IMSAI VDP-42	R4**
IMSAI VDP-44	R5**
IMSAI VDP-80	A1**
Intecolor	See ISC Intecolor
Intel MDS Single Density	A2
Intel MDS Double Density	A5
Intertec SuperBrain DOS 0 1	R7
Intertec SuperBrain DOS 0 5-2 X	RJ
Intertec SuperBrain DOS 3 X	RK
ISC Intecolor 8063/8360/8963	A1
Kontron PSI-80	RF
Meca 5¼	P6
Micromation (Except TRS-80 below)	A1*
Micropolis Mod I	Q1
Micropolis Mod II	Q2
MITS 3200/3202	B1
Morrow Discus	A1*
Mostek	A1
MSD 5¼	RC
North Star Single Density	P1
North Star Double/Quad	P2
Nylac Single Density	Q3
Nylac Micropolis Mod. II	Q2
Ohio Scientific C3	A3
Onyx C8001	T2 #
Pertec PCC 2000	A1*
Processor Technology Helios II	B2
Quay 500	RO
Quay 520	RP
RAIR Single Density	R9
RAIR Double Density	RE
Research Machines 8	A1
Research Machines 5¼	RH
REX	Q3
Sanco 7000 5¼	RQ
SD Systems 8	A1*
SD Systems 5¼	R3
Sorcerer	See Exidy Sorcerer
Spacebyte	A1
SuperBrain	See Intertec
Tarbell	A1*
TEI 5¼	R3
TEI 8	A1*
Thinkertoys	See Morrow Discus
TRS-80 Model I 5¼	R2
TRS-80 Model I - FEC Freedom	RN
TRS-80 Model I - Micromation	A4*
TRS-80 Model I - Omikron 5¼	RM
TRS-80 Model I - Omikron 8	A1
TRS-80 Model I - Shuffleboard 8	A1
TRS-80 Model II	A1*
VDP-40/42/44/80	See IMSAI
Vector Graphic	Q2
Vector MZ	Q2
Versatile	See CDS Versatile
Vista V80 5¼ Single Density	P5
Vista V200 5¼ Double Density	P6
Zenith Z89 - Lifeboat CP/M	P4
Zenith Z89 - Magnolia CP/M	P7

Prices reflect distribution on 8" single density diskettes. If a format is requested which requires additional diskettes, a surcharge of $8. per additional diskette will be added.

Prices F.O.B. New York. Shipping, handling and C.O.D. charges extra.

Manual cost applicable against price of subsequent software purchase.

The sale of each proprietary software package conveys a license for use on one system only.

VISA MasterCard

* Single-Side Single-Density disks are supplied for use with Double-Density and Double-Side 8" soft sector format systems

** IMSAI formats are single density with directory offset of zero

\# A media surcharge of $25 for orders on tape formats T1 and T2 and of $100 for orders on disk formats D1 and D2 will be added

The list of available formats is subject to change without notice. In case of uncertainty, call to confirm the format code for any particular equipment

Apple Pascal, cont'd...

learn and allows one to get in trouble much more quickly. Pascal is easy to learn and almost forces one to write logical, readable, understandable programs. (Of course, you could also get C up on your Apple by buying the BD Software or Whitesmith's C compiler for the Z-80 along with a Microsoft Z-80 Softcard, but that's another adventure of dubious merit for another article.)

The Compiler

The compiler recognizes the data type STRING, not really in the original Pascal specification (a blunder), which is the same old array of characters that standard Pascal has, but with a length attribute magically tacked on. Compile-time toggles allow you to turn on/off the checking of I/O errors (why would you want to turn them off?), range errors, and the internal swapping of the compiler. the user can include an externally stored text file with special routines or definitions in it.

Anyway, we should mention in passing that the compiler handles errors more gracefully than ANY OTHER we've tried, by allowing you to jump immediately into the editor with the cursor over the offending code, and a description of the problem at the top of the screen. The compiler also generally finds where the error really is, which isn't always easy to do.

The compiler handles errors more gracefully than ANY OTHER we've tried, by allowing you to jump immediately into the editor with the cursor over the offending code.

R) Run a program. This causes the current workfile to be compiled (if necessary), linked (if necessary), and executed.

X) This command executed a named code file (output of assembler or compiler).

A) A 6502 assembler with many juicy pseudo-ops is also included in the package. Subroutines in 6502 machine language can be called from Pascal.

L) The linker can be explicitly called by the user for user-written non-standard libraries.

Gripes

Since there is no debugger in the Pascal system, fixing programs is done the horrible way, by inserting WRITE statements all over the place to try to decipher what's happening. Debuggers for high-level languages are usually primitive at best, but it's sometimes helpful to be able to look at the stack or see a traceback or set breakpoints. Another moderate annoyance is that Pascal wants to run on an 80 column screen, and the plain-old-vanilla flavored Apple II has only 40 columns (whereas the space-age Apple III has 80 columns). The attempted solution for the Apple II was to split the 80 column screen into two imaginary 40-column screens and then you can either flip back and forth between them or scroll horizontally. This technique works OK but if it bothers you, it is also possible to connect an external terminal or use an 80-column video card. This links us to another minor problem — the Pascal system is a bit fussy about talking to non-Apple I/O cards (in particular it did not recognize the SSM Apple RS-232 I/O card which entailed great fussing with user-written I/O drivers).

The documentation is good, but a few items fell between the cracks. In particular, there did not seem to be any specific information in the reference manual on how parameters are passed to assembly language subroutines. Also, the documentation on what's happening in the system at the nuts and bolts level is missing (perhaps for proprietary reasons).

For those curious about details of the implementation, Apple/UCSD is a "portable" (a little bit) compiler which is apparently reworked Zurich p-code. That is, the compiler and operating system and everything else wonderful but not Apple-dependent is written in a machine language for a hypothetical stack architecture processor, which is simulated by the 6502 in the Apple. This might sound inefficient but the p-machine is highly optimized toward running Pascal object code and thus is very reasonable in its use of time and memory.

Overall, Pascal is a very very nice language, and this is a very very nice implementation. If you're a teacher, and have an Apple, perhaps you should be teaching your students Pascal instead of Basic, which encourages bad programming practices and looks backward, not forward. If you're a personal computer user, you'll find Apple Pascal to be fast, powerful, and a pleasure to use. Absolutely get one of these if you can afford the $500 list price. □

What a P-Machine Is

Since good computer software is so difficult to develop it's worthwhile to make it as portable as possible. This is hard enough to do with application software written in a "high-level" language like Microsoft Basic, but the difficulties are compounded when writing system software since it is tied more closely to one particular machine. Further, efficiency (of both cpu and memory usage) are often more critical in system programs.

So, let's say you've cooked up a really super Pascal system written in assembly language for the Z-80, and now you want to move it to the Apple which has a 6502 processor. You could always recode the entire Pascal system for the 6502, but it would be almost as much work as starting from scratch. Or, you could write a Z-80 simulator for the 6502. This would be easier than rewriting all the Z-80 code, but the trade-off is a loss of speed and a few K of memory because of the overhead of this added layer of interpretation. But what makes the Z-80 (or the 6800 or the Z-8000 or any other particular processor) especially great for writing a Pascal compiler and operating system? Well, nothing. As long as we're interpreting one machine on another, then, it makes sense to design a hypothetical processor which would be a nice home for running Pascal- with built-in instructions for doing Pascal-type things.

Guess what, computer fans, that's how UCSD Pascal works. Merely by implementing the infamous p-machine by interpreting it on an existing microprocessor, the entire Pascal compiler and operating system and utilities can be moved. So when you think the Apple is running Pascal, in fact, it is running a simulation of a computer which is running Pascal object programs.

Of course, if you want a real code crunching compiler that can squeeze every cycle and every spare byte out of the object code, then a compiler that makes executable native code for the host processor is in order. This approach is taken by Ithaca Intersystems pascal and Leor Zolman's BD C compiler, for instance. But neither of these compilers could be made to run on another microprocessor too quickly.

An alternative approach to make portable compilers (and other software) is to write everything, including the compiler itself, in a high-level language, let's say on machine A. Then, to move everything to machine B, we need only rewrite to code generator in the compiler on machine A so that it makes programs for machine B, run everything through the new compiler, and transport the resulting programs to machine B. Alas, writing good code generators is a tricky, art-not-a-science thing, and this approach has not been applied much to personal computers.

—SN

HOT OFF THE PRESS!



MICROSHOPPER
the new Computers!

The most comprehensive consumers' guide to microcomputing ever published is hot off the press! The latest edition of the best-selling MicroShopper has been expanded to 192 pages, and is now in a convenient book form . . . includes nearly 200 photographs, illustrations and charts; dozens of hardware and software product reviews, and feature articles on topics from the history of computers to robotics. The new MicroShopper explains the often difficult-to-understand jargon of the computer industry, provides tips on selecting a system for business, professional, educational or personal use, and lets you take a look at the latest microcomputers and peripherals from industry-leading manufacturers!

To order the new edition of the MicroShopper, call toll-free 1-800-528-1418, or fill out and clip the coupon below today! Make checks or money orders payable to PGI Publishing. Master Card and Visa orders welcomed.

TOLL FREE 1-800-528-1418

Please send me _____ MicroShopper(s) at $9.95 each plus $1.75 for postage and handling. Arizona residents add 5% sales tax.

Name _____

Address _____

City _____ State _____ Zip _____

☐ Check or money order enclosed ☐ VISA ☐ Master Card

Acct. No. ☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐

Expiration date ☐☐☐☐

PGI Publishing
1425 W. 12th Place * Tempe, Arizona 85281

CIRCLE 262 ON READER SERVICE CARD

When DecisionMaster™ speaks everybody listens.

Let's face it. We all have to make decisions. Decisions that can change our lives. Decisions that can make us happy or unhappy. Decisions that could win us fame or fortune. Now, DecisionMaster can help you make the best decisions of your life.

Use Bayesian theory to peer into the future...even if you've never heard of the Bayes' Rule. Do a complete weighted factor analysis...without knowing what one is. Use discounted cash flow to compare investment alternatives without bothering with present value tables. These and other sophisticated theories that were once the exclusive domain of professors and top business executives are *built into* DecisionMaster's algorithms... so you can use them at the touch of a key!

DecisionMaster is easy to use. It features:

- A fully documented manual developed by an authority in the field.
- A unique program-controlled cross reference system
- A powerful formatted-screen data entry system.

You'll use DecisionMaster in hundreds of routine decisions, as well as more important ones such as • Buying a house • Changing jobs • Selecting investment • Evaluating insurance policies • Expanding product lines • Leasing vs purchasing.

If you buy only one computer program this year, make it DecisionMaster. And when it speaks, *listen*.

DECISION?MASTER™

To order, see your software dealer or return this form with your check to: DecisionMaster, Dept.CC, 10428 Westpark, Houston, Texas 77042 Add $1.50 for shipping and handling

Diskette for: ☐ Apple II* (32K) $29.95 ☐ TRS-80** (Level II-32K) $29.95 ☐ TRS-80** (Model III) $39.95

Name

Address

City State Zip

CHARGE by phone toll-free: **1-800-231-5768 Ext. 306**
(In Texas: 1-800-392-2348) or return this form:
☐ VISA ☐ MasterCard Bank Code

Account No.

Signature Expiration Date

*Apple II is a registered trademark of Apple Computers, Inc.
**TRS-80 is a trademark of the Radio Shack Division of Tandy Corp.

CIRCLE 200 ON READER SERVICE CARD



The TRS-80 Pocket Computer

Glenn Hart

I have seen the future, and I'm holding it in my hand! The new TRS-80 pocket computer ($249) is a breakthrough, the vanguard of a new generation of computing accessibility.

The TRS-80 PC appears at first glance to be either an unusually designed calculator or some sort of language translator. In fact, it is neither, being far more sophisticated than either. It is a complete *computer,* with keyboard, 24 character alphanumeric output display, Basic and monitor in ROM, 1.9K of non-volatile RAM, and an I/O port for storing programs and data on cassettes. Its capabilities would have been reasonably impressive in a first generation desk-top small computer(and are far in advance of the early *room-size* computers); in a package small enough to fit in a pocket they are astounding!

The Hardware

Measuring only 6⅞″ x 2¾″ x 19/32″ and weighing a bit less than six ounces, the TRS-80 PC is sleek and attractive. The 57-key alphanumeric keyboard is laid out in a modified typewriter arrangement; the letter keys follow standard "QWERTY" practice while the numeric keys appear on the right side in calculator array. There are also several special purpose keys to handle editing and the generation of symbols, and 13 keys have alternate outputs selected by a SHIFT key. While the keys look rather small and close together and there is no tactile or audio feedback when a key has been depressed, keyboard action is very good and with only a little experience it becomes quite easy to enter text. It is even possible to "type" with both hands for quicker entry, although the non-standard location of the numbers and the need to use the SHIFT key to enter simple punctuation takes a bit of getting used to. Eighteen keys are "reservable," meaning that special program segments can be pre-programmed into a dedicated memory area and called up quickly.

The liquid crystal display is highly legible in normal room light, but, like any other LCD display, it should be viewed more or less directly from above. A 5X7 dot matrix is used to generate upper case only letters and the various punctuation marks and special symbols. No graphics symbols are provided, but they would not be particularly appropriate on a one line display anyway. The input buffer is 80 characters, and if a line longer than the 24 characters displayed is entered the display uses horizontal scrolling in either direction. Cursor control is provided to move around the buffer area for editing and viewing long lines.

The input buffer is 80 characters, and if a line longer than 24 characters is entered the display uses horizontal scrolling in either direction.

A nine pin I/O connector on the left edge of the PC is used to connect the optional cassette interface ($49). Normally protected by a plastic cover, this connector could presumably be used to attach other peripherals even though Radio Shack has not announced the availability of anything other than the cassette interface. The cassette interface itself is a plastic cradle into which the PC is inserted. Various slots and protrusions on both the PC and the interface prevent incorrect attachment. Three cables are provided to connect the interface to the microphone, earphone and remote jacks of any cassette recorder. The new Radio Shack Minisette-8 is an excellent match in size and styling; together they form a complete system which fits in one corner of an attache case.

Radio Shack does not provide any information on the microprocessor or support circuitry other than to indicate that large-scale-integration CMOS devices are used. Rumor has it that TWO *four-bit* microprocessors are used: one to handle Basic instructions and one to perform calculations. At a time when some of the biggest excitement in microcomputing



Glenn A. Hart, 51 Church Road, Monsey, NY 10952.

centers on the availability of sixteen bit CPU's (with 32-bit devices in the wings), the TRS-80 PC is graphic proof that important and interesting things can be done with many fewer bits on hand.

CMOS technology offers several advantages, the most significant of which is extremely low power consumption. The TRS-80 PC draws only *one-hundredth of a watt,* and can operate for up to three hundred hours on four small mercury batteries. The cassette interface requires three AA cells and the cassette recorder four.

Most importantly, the computer's memory is *non-volatile,* which means that it is not cleared when the power switch is turned off. Programs and data are retained in memory continuously and are immediately available for use when the computer is turned on. While this continuous memory has begun to appear on advanced pocket calculators, the TRS-80 PC is, to my knowledge, the first true personal computer (other than those with adapted core memory) with this convenient and useful feature.

The 1.9K of RAM available is divided into several segments. Basic program storage is limited to a maximum of 1424 "steps," with each step corresponding to a character in a program line. Note, however, that Basic commands are compressed to one byte tokens, so the *effective* program length is more than 1424 bytes. Twenty-six "fixed" memories are provided. Each can store the contents of one numeric or string variable, with the length of a string variable or constant limited to seven characters. If more variable store is required, up to 178 "flexible memories" can be allocated at the expense of program storage. In addition, there are 48 steps of "reserve memory." These hold up to 18 short program segments which can be retrieved easily for use in manual calculations of programming. The remainder of memory is allocated to the 80 character input buffer, an 8 step "data stack" and a 16 step "function stack." There is no apparent way to expand memory beyond that incorporated into the computer, but a surprising amount of useful programming can be done within the limited memory available.

The Basic Interpreter

The use of a high level language like Basic is what sets the TRS-80 PC apart from the many programmable calculators available today. As the owner of both a Texas instruments TI-59 and a Hewlett Packard HP-41C, I have enjoyed these devices and programmed them to perform many useful functions, but the pseudo assembly language necessary to program them is often a source of frustration at best and a total obstacle to certain tasks at worst. Radio Shack has asserted that the PC renders programmable calculators obsolete, and I would have to agree that machines that seemed advanced until now have suddenly become much less impressive.

The TRS-80 PC Basic interpreter is *not* a direct equivalent to any of the Microsoft-supplied interpreters used on full size Radio Shack computers. I am not particularly familiar with Level I or Level II Basic, but it seems that the PC interpreter has capabilities similar to those of Level I with a few bells and whistles added and some modifications made to handle the specific demands of a computer displaying only one line at a time.

Statements					
LET	INPUT	PRINT	PAUSE	USING	GOTO
IF	THEN	GOSUB	RETURN	FOR	TO
STEP	NEXT	STOP	END	BEEP	CLEAR
DEGREE	RADIAN	GRAD	AREAD	REM	
Command Statements					
RUN	DEBUG	CONT	LIST	NEW	MEM
Cassette Tape Control Statements					
CSAVE	CLOAD	CLOAD?	CHAIN	PRINT#	INPUT#

Table I. TRS-80 Pocket Computer Basic Interpreter Statements and Commands

Most of the Basic statements and commands have abbreviations which make entering programs quicker and more convenient.

TRS-80 PC Basic allows only 26 directly named variables, corresponding with the 26 "fixed" memory locations. Each location can contain *either* numeric or string information (strings are limited to seven characters) but not both. Thus variables A and A$ occupy the same memory, and only one or the other can exist at any time. Only one array, labeled A(), can be used; its elements point to the same memory locations as a direct reference would — at least up to A(26), which is the same thing as memory location Z. Up to 178 additional locations can be allocated to variable storage (at the expense of program storage). These locations can only be accessed as elements of the A array (e.g., A(145)).

The statements and commands provided are listed in Table I. LET works normally to assign values to variables and is, as usual, optional in most cases. (It is necessary only after an IF statement.) INPUT allows the entry of data from the keyboard, with prompting messages if desired. Prompts do *not* scroll horizontally, so it is necessary to limit the prompt message to what will fit on the display.

PRINT outputs messages and data to the display, as in most Basics. Due to the one line display, PRINT interrupts program execution until the ENTER key is depressed, similar to the interruption caused by an INPUT statement. The PAUSE statement performs the same functions as PRINT except that the information displayed appears for only a little less than a second (the display time could be a bit longer for maximum utility).

I was surprised to find that a limited form of PRINT USING is included (the USING formats can also be used with PAUSE). Only numeric formats can be specified. The normal "###.##"-type format sets the display mode; a carat sign sets scientific notation display. No provision is made for special formatting characters like dollar signs, asterisks, floating signs, etc. The format can be specified for all output with a USING statement by itself or the standard PRINT USING constructing can be used.

GOTO and GOSUB operate normally, except that alphabetic labels can be inserted in lines and GOTO and GOSUB can be instructed to branch to these labels as well as to simple line numbers. This is a nice feature rarely found in *any* Basic interpreters.

The IF statement does not require a following THEN (THEN is synonymous with GOTO), but therefore requires a LET if a variable assignment is to be made. FOR/NEXT loops operate normally, with a maximum nesting level of four. The STEP statement is available, but only with integer values.

BEEP sounds a small tone as many times as its parameter indicates. CLEAR clears all data memory. DEGREE/RADIAN/GRAD sets the mode for angular entries and calculations. AREAD reads a value into a variable prior to the start of execution of a defined program. REM allows comments to be inserted into

THE ORIGINAL MAGAZINE FOR OWNERS OF THE TRS-80™* MICROCOMPUTER

SOFTWARE FOR TRS-80™ OWNERS

H & E COMPUTRONICS INC.

MONTHLY NEWSMAGAZINE FOR TRS-80™ OWNERS

MONTHLY NEWSMAGAZINE
Practical Support For Model I, II & III

- PRACTICAL APPLICATIONS
- BUSINESS
- GAMBLING • GAMES
- EDUCATION
- PERSONAL FINANCE
- BEGINNER'S CORNER
- NEW PRODUCTS
- SOFTWARE EXCHANGE
- MARKET PLACE
- QUESTIONS AND ANSWERS
- PROGRAM PRINTOUTS

. . . . AND MORE

PROGRAMS AND ARTICLES PUBLISHED IN OUR FIRST 12 ISSUES INCLUDE THE FOLLOWING:

- A COMPLETE INCOME TAX PROGRAM (LONG AND SHORT FORM)
- INVENTORY CONTROL
- STOCK MARKET ANALYSIS
- WORD PROCESSING PROGRAM (FOR DISK OR CASSETTE)
- LOWER CASE MODIFICATION FOR YOUR VIDEO MONITOR OR PRINTER
- PAYROLL (FEDERAL TAX WITHHOLDING PROGRAM)
- EXTEND 16 DIGIT ACCURACY TO TRS 80™ FUNCTIONS (SUCH AS SQUARE ROOTS AND TRIGONOMETRIC FUNCTIONS)
- NEW DISK DRIVES FOR YOUR TRS 80™
- PRINTER OPTIONS AVAILABLE FOR YOUR TRS 80™
- A HORSE SELECTION SYSTEM***ARITHMETIC TEACHER
- COMPLETE MAILING LIST PROGRAMS (BOTH FOR DISK OR CASSETTE SEQUENTIAL AND RANDOM ACCESS)
- RANDOM SAMPLING***BAR GRAPH
- CHECKBOOK MAINTENANCE PROGRAM
- LEVEL II UPDATES***LEVEL II INDEX
- CREDIT CARD INFORMATION STORAGE FILE
- BEGINNER'S GUIDE TO MACHINE LANGUAGE AND ASSEMBLY LANGUAGE
- LINE RENUMBERING
- AND CASSETTE TIPS, PROGRAM HINTS, LATEST PRODUCTS COMING SOON (GENERAL LEDGER, ACCOUNTS PAYABLE AND RECEIVABLE, FORTRAN 80, FINANCIAL APPLICATIONS PACKAGE, PROGRAMS FOR HOMEOWNERS, MERGE TWO PROGRAMS, STATISTICAL AND MATHEMATICAL PROGRAMS (BOTH ELEMENTARY AND ADVANCED) AND

* TRS 80™ IS A TRADEMARK OF TANDY CORP

FREE*

WORD PROCESSING PROGRAM For writing letters, text, mailing lists, etc., with each new subscriptions or renewal.
LEVEL II RAM TEST Checks random access memory to ensure that all memory locations are working properly.
DATA MANAGEMENT SYSTEM Complete file management for your TRS 80™.
CLEANUP Fast action Maze Game.
ADVENTURE Adventure #0 by Scott Adams (From Adventureland International).

FREE

*** All programs are supplied on cassette (add $3 for Diskette Version - add $5 for modified Mod-II Version).**

SEND FOR OUR NEW 48 PAGE SOFTWARE CATALOG (INCLUDING LISTINGS OF HUNDREDS OF TRS 80™ PROGRAMS AVAILABLE ON CASSETTE AND DISKETTE). $2.00 OR **FREE** WITH EACH SUBSCRIPTIONS OR SAMPLE ISSUE.

H & E COMPUTRONICS INC.
MATHEMATICAL APPLICATIONS SERVICE™

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

master charge

24 HOUR ORDER LINE
(914) 425-1535

VISA

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

ONE YEAR SUBSCRIPTION $24 .....
TWO YEAR SUBSCRIPTION $48 .....
SAMPLE OF LATEST ISSUE $ 4 .....
START MY SUBSCRIPTION WITH ISSUE .....
(#1 - July 1978 • #7 - January 1979 • #12 - June 1979 • #18 - January 1980)
NEW SUBSCRIPTION ..... RENEWAL .....
CREDIT CARD NUMBER _____ EXP. DATE _____
SIGNATURE _____
NAME _____
ADDRESS _____ CITY _____ STATE _____ ZIP _____

*** ADD $6 YEAR (CANADA, MEXICO) - ADD $12 YEAR AIR MAIL - OUTSIDE OF U.S.A., CANADA & MEXICO ***

CIRCLE 138 ON READER SERVICE CARD

a program (although heavy use of comments is unlikely with limited memory).

Commands usable only by manual entry include RUN to execute programs, CONT to continue interrupted programs, LIST to list program lines, NEW to clear memory, and MEM to display the remaining available program and flexible memories. The DEBUG command is similar to Microsoft's TRACE; the line number of each program line is displayed after it is executed.

The commands for cassette storage of programs and data follow closely normal Radio Shack Basic practice. The CSAVE and CLOAD commands perform the obvious functions, while CLOAD? verifies accurate saving or loading by comparing a cassette stored program with the contents of memory. PRINT# and INPUT# save data rather than programs. CHAIN loads new programs from tape and immediately executes them, either at the beginning of the new program or at a specified label within the program; this allows programs longer than memory to be segmented into smaller programs and executed sequentially, greatly increasing the power of the computer.

Table II lists the functions provided. A complete spectrum of trigonometric functions is available as well as several normal Basic functions. No string functions or logical operators are provided, although logical operations can be simulated with programming tricks explained in the user's manual.

Editing of program lines is possible with the cursor movement keys located in the lower right of the keyboard and the line movement keys above the center of the alphabetic area. The cursor can be moved to any spot in a line and the contents of that spot overwritten with new information. Alternatively, characters can be deleted or inserted at will. The line movement keys move the display within a program so any line can be accessed readily. As in other Basics, entire lines are deleted by typing their line number and ENTER and new lines can be added between existing line numbers. No renumbering facility is provided.

SIN	COS	TAN	ASN	ACS	ATN
LN	LOG	EXP	SQRT	DMS	DEG
INT	ABS	SGN			

Table II. TRS-80 Pocket Computer Basic Interpreter Functions

Operation and Evaluation

The TRS-80 PC operates in four modes, indicated by small status displays above the main 24 character display. The RUN mode is used both for manual calculations and to execute programs. If several programs are stored in memory at the same time and each is defined with an alphabetic label, the DEFINE mode is used to run the separate programs. PROGRAM mode is used for entry and correction of Basic programs. Most of the Basic statements and commands have abbreviations which make entry programs quicker and more convenient. RESERVE mode is used to enter short programs and/or statements into the 48 step reserve memory. Two small templates are provided which fit over the reservable keys; these can be used to indicate what program or statement has been assigned to the individual key.

Radio Shack does not supply any information on clock speed. In general, Basic programs execute rather slowly, although they seem to run at least as fast as equivalent programs coded for my programmable calculators. The TRS-80 PC maintains up to 23 digit precision internally (although displayed results are limited to 10 digits before the computer switches to scientific notation), so some premium in execution speed is certainly justified by this very high precision.

The looks on their faces when I demonstrated the TRS-80 PC more than justified its purchase price.

In practical use, the TRS-80 Pocket Computer is a delight. Manual calculations are a pleasure, since so much of the input is retained on the display and can be corrected if necessary. A user who constantly requires trig functions might find a calculator faster than having to type in the function names, since the necessary function keys are immediately available.

Programming is vastly improved over programmable calculators. Any reasonably competent Basic programmer can put the PC through its paces and generate complex programs *much* faster. The interpreter is surprisingly capable and easy to program; the debugging and editing functions make program correction simple. The full alphanumeric 24 character display is a pleasure (the alpha display of the HP-41C seemed advanced only a few months ago; now it is impossibly restricting).

I have already used the PC in several business meetings where I was able to use pre-stored programs to good advantage and even write and execute new programs on the spot to answer complex business problems. Its small size has earned it a permanent spot in my attache case; I am not willing to be without it wherever I travel.

This is not to say that the machine is perfect. Several other manufacturers have announced similar products which would appear to have more capabilities, either more memory or available printers, modems, etc. I am sure that the TRS-80 PC will be surpassed in the future unless Radio Shack makes a major commitment to expanding this end of their business. The presence of that I/O connector would indicate that such expansion is possible. None of the software packages designed for the PC were available at the time this review was written; a large software library will be necessary to wean many prospective purchasers off their programmable calculators and their large software base and user groups. I guess that we computerists are by nature greedy gluttons; we get a wonderful feast of new technology and all we want is more!

In the meantime, the TRS-80 Pocket Computer is the state-of-the-art. It is not denigrating the usefulness of this computer to also point out that it is a terrific toy and an absolute conversation stopper. The day after I bought mine I had two mainframe-computer specialists, each controlling several million dollars of hardware, in my office to discuss development of a complete business control system. The looks on their faces when I demonstrated the TRS-80 PC more than justified its purchase price. Their chagrin when I pointed out to them that it was the lizards who survived, not the dinosaurs, made my day! □



Radio Shack's $399* TRS-80™ Color Computer-- Innovation at it's Very Best!

The Family Christmas Gift That's Functional, Fun and Educational! Tremendous versatility and value at a breakthrough price. Something for everyone in your home! The TRS-80 Color Computer can be used with our plug-in ROM Paks, or write your own programs in BASIC. Mom and Dad can use it for any number of applications, such as keeping track of personal finances; youngsters can learn the basics of computer programming —the whole family will enjoy playing exciting color action games. It's expandable,so its capability grows with yours. Attaches to any color TV quickly and easily or get our optional TRS-80 Color Video Receiver (works as an extra TV too!).

Put a computer in your life this Christmas. Get the full story and specs from your nearest Radio Shack store, dealer or Computer Center. Over 6,000 locations, nationwide. Or write for a free TRS-80 catalog: Radio Shack, Dept. 81-A-62, 1300 One Tandy Center, Fort Worth, TX 76102.

*Retail prices may vary at individual stores and dealers

Radio Shack
The biggest name in little computers™

CIRCLE 146 ON READER SERVICE CARD

The Apple II and Apple II Plus

David Lubar

Making the plunge for a personal computer is a big decision, involving a fair amount of money. If you're in the market, the Apple is a good choice, with a lot of positive aspects, and a few bad points, much of which will be covered here. People buy computers for a variety of reasons; some just want to play games, some want to develop programs, and some need specific applications such as word processing. I'll address the game players first. The Apple has all the requirements in this area; high-resolution color graphics, paddle or joystick control, and a large amount of available software. Let's take a closer look at these areas. The graphics, with six colors, are good enough to produce games that are close to arcade quality. The low resolution mode, with sixteen colors, also is the basis for a number of good games.

In the paddle capabilities, a distinction must be made between potential and actual use. The Apple can handle four paddles and three buttons. But, since the system comes with two paddles and two buttons, most software is written for this configuration. A manufacturer would be taking a chance selling a game that couldn't be used by the majority of Apple owners. Some dual-joystick packages are beginning to appear, with hardware and software. If this catches on, we'll see some nice software in the near future. (A joystick is the equivalent of two paddles, and is easier to use in games where one player is controlling two factors, such as horizontal and vertical movement.) In the past, the paddles that came with the Apple were rather poor in quality. The new Apples have different paddles, but it is hard to tell whether they are better internally.

The availability of software from a number of sources is important. There are hundreds of games for the Apple; arcade games, chess and bridge games, adventures. The Apple comes with enough software to keep you up till sunrise for a few weeks. The Integer version has *Startrek* and *Starwars*, the Applesoft version also has some nice games, including *Penny Arcade*.

The instruction manuals, covering everything from setting up the computer and loading tapes to programming and debugging are well done, extensive, and easy to follow. Even if you get an Apple just to play games, you'll probably end up doing some programming, which brings us to the next aspect of the Apple. There are two versions of Basic available; Integer and Applesoft. Integer Basic is fast, easy to use, and gives immediate error messages. But it has some limitations. It only handles integers in a range from –32767 to 32767, and allows integer arrays of only one dimension, with no string arrays. This might not be an important issue since Integer seems to be phasing out, with most new programs being written in Applesoft or machine language. And, since either Apple can, with the addition of a special card, handle both Basics, a purchase of either Apple doesn't restrict future use.

Applesoft is a version of Microsoft Basic, with extended functions for graphics. Both Applesoft and Integer Basic give understandable error messages. A mistake will produce something such as, "Memory full" as opposed to a cryptic "Error 23." The Apple can also be programmed in 6502 assembly language. The Integer version has a mini assembler. The Plus doesn't, but there are a number of good assemblers available. I won't go into any debate over the good and bad points of the 6502, but will mention that anyone who learns to use it will be able to "talk to" a number of popular computers, including the PET, Atari, and OSI.

Apple's great documentation means that programmers will have an easy time making use of all the features of the machine. Whatever Apple hasn't had a chance to tell has been covered by the many fine user's groups. Apple owners are an active bunch, and most areas of the country have at least one Apple club.

Another important consideration is expansion. While the Apple might be a bit more expensive at the start, it is designed for expansion and will cost less in the long run. Disk drives can be attached to a card that plugs right into the Apple; no extra power supply is needed. Memory is also plugged right in; no interface is needed. As with software, there are also a lot of hardware companies making products for the Apple. Everything from music boards and speech boards to graphics pads and light pens can be found. Apple seems to encourage this, knowing that it helps make the computer better and more versatile.

My only criticism in this area is that Apple charges too much for extra memory. This seems to be the case with all the computer manufacturers. Luckily, many stores that carry the Apple also carry memory kits at a reasonable price.

The Apple doesn't come with lower case; a bit of a problem for those who want to do word processing. But lower-case modifications are available, and there are several companies selling good software for word processing on the Apple.

What else? The company is fairly responsive to user questions, but somewhat inconsistent. Some queries are answered quickly, others are ignored. Still, in general, Apple seems to be concerned about the user. The Apple produces some radio-frequency interference (RFI) which might interfere with near-by television sets, but the company is working on the problem and has found some ways to reduce the RFI.

The dependability of the Apple should also be mentioned. Hardware problems are very rare. The chance that any repairs will be needed is small. And most repairs can be handled by a dealer since Apple trains all authorized dealers.

To sum things up, the Apple has a lot going for it. New software and hardware will continue to appear. I highly recommend this computer. □



The Atari

Bob Callan

Merry Christmas to those who find an Atari under their Christmas tree this year. There are many discoveries awaiting you which might not appear in ads, or may not be discussed by salespeople.

The Atari has excellent RF (Radio Frequency) shielding. This is evident in the lack of Radio Frequency Interference (RFI) on the color TV that you hook up to the Atari. The low RFI permits distortion-free characters and crisp, undiluted colors. Your neighbors will also enjoy your Atari, as they can watch their TV without seeing weird patterns of RFI caused by your computer. The Atari was one of the first small computers with adequate RF shielding. Although all new home computers are required to have this shielding, there are still many unshielded ones in stockrooms.

The RF shielding surrounds the cartridge cavities, located under the cover, behind the keyboard. If you lift off the cover you will see the heavy-looking metal shielding that is molded into the pits that contain the RAM, ROM, and game cartridges. The cartridges fit snugly into these spaces, leaving little room for air to circulate.

The snug fit and metal enclosure combine to create problems on warm days, or after many hours of operation. The electrical resistance of the parts in the RAM cartridges generates heat. The metal shielding acts like a heat sink. The air vents in the cover of the Atari don't provide sufficient ventilation to keep the Atari functioning properly after many hours of operation. When this happens, error messages appear frequently, without the errors occuring. Debugging becomes impossible.

Don't be overly concerned. First, heat can cause small computers, as well as the big ones, to malfunction. Unless you use your Atari for eight hours, or on hot days without air conditioning, you probably won't encounter any difficulties. Second, you can cool it. Remove the RAM, ROM, and Operating System cartridges and place them in a cool, dry stream of air. In five minutes the cartridges and the metal shielding should be cool enough to give you several more hours of trouble-free operation.

There are other discoveries to be made concerning the Atari. The *Star Raiders* game and *Basketball* are only two of the many cartridges available as part of the entertainment aspect of the Atari. On the educational side, the cartridges range from Sociology to Physics.

The Atari presents a challenge to both the beginning and the more experienced programmer. For the beginning programmer, the *Atari Basic: A Self-Teaching Guide* is a good self-paced instruction manual for Atari Basic. For the more experienced programmer, the *IRIDIS* vol 1 and 2 provide valuable information on such varied programming aids as; partial memory map, screen display lists, and real time programming. These books are valuable to programmers, especially when converting programs from the Apple to the Atari. The manual that comes with the Atari is essentially a reference manual describing the commands and some of the operations. The programs listed in this manual are very explicit and are documented, but the manual isn't particularly helpful when you are trying to animate a shape or display letters on the screen in a graphics mode. Atari's Assembler cartridge and documentation will make this type of programming less difficult.

Programming the Atari is wonderful in several ways. When you type in a command improperly, an error message appears. What could be more friendly? It even prints the erroneous character in inverse video. You can see where you made a mistake. This doesn't replace debugging, but it certainly helps. The Atari has full variable names like SHOT, AMMO, GEESE, and COUNTER. Following the flow of a program is much easier with these variables. If you want to type in inverse video, to signal a REM, the beginning or end of a subroutine, or to print on the screen, you have to press just one key. Lower case letters are procured by pressing the cap and shift key.

Perhaps the most functional part of the keyboard is the Editor. Using the control key and six or so other keys, the cursor can be easily moved anywhere on the screen. Program lines or characters can be quickly and easily replaced, inserted or deleted.

There is another feature that is particularly useful to teachers. You can get two video outputs from the Atari without using RF boosters. One output is an RCA-type which connects to a regular RF unit attached to a TV. The other output can be attached to a monitor, or to a video-recorder. Using this arrangement, you can watch the video display, what is happening in the back row, and what you are inputting into the computer. This is easier than turning around constantly. If turning around doesn't bother you, there are now two video displays, which means everyone

some interesting lessons using computer-video integration may be possible.

The Atari's color and sound, and the accessibility of these to even an inexperienced programmer, make the Atari a good choice for involving students, even young ones, in computer programming. Although there is not a large amount of software available at the K-8 and high school level, more software is being developed. It is important for teachers to make their software needs known, and to let software developers know there is a market for educational software. Wouldn't textbooks be different if classroom teachers gave more input? As an instructional aide, television has not met its potential. This is the stage of development of software where teachers can help computers reach their full potential as educational aides.

The Atari is entertaining, and educational. As a fourth generation computer, Atari has many of the good features of earlier computers plus some innovative ideas. The addition of several new peripherals to the line deletes a commonly-cited objection to buying an Atari. Although the Atari Basic incorporates easy use of graphics and sound, the next big improvement would be a version of Microsoft Basic. Maybe Santa will bring it for Christmas. □

Why I Like the TRS-80

Stephen B. Gray

It's become fashionable in many personal-computer circles to call Radio Shack's machine the "Trash-80," to speak of Model I's hardware as poorly designed, and to cite various inadequacies of Level II Basic.

Yet, despite all these hardware and software problems, Radio Shack has somehow managed to sell over 200,000 (perhaps 250,000 by the time you read this) of these "poorly designed and inadequate" computers.

How did Radio Shack manage to fool so many people? How were a quarter of a million people hoodwinked into buying such an inferior piece of merchandise?

What They Wanted

One answer is that Radio Shack provided what many people out there wanted, at a price they felt was right, and at thousands of outlets all over the country where a person could go try it out before buying.

Once the TRS-80 caught on, the name became as magic in its own field as IBM's in the mainframe business. IBM may not make the best computers, or the fastest ones, but it knows, better than all the rest, the importance of service and support.

Radio Shack made a lot of mistakes with the TRS-80, as would any company marketing the first popular ready-to-run personal computers. But they've learned a lot, they've made tens of thousands of free fixes, and they've brought out three more TRS-80 computers that alone may well outsell both Apple and PET.

My TRS-80

Nobody who's used a personal computer for more than a few weeks is completely satisfied with it. There are always some features on other machines he'd like to have on his.

I've had a 16K Level II Model I since December 1977. I've been writing the TRS-80 column in this magazine since the Nov-Dec 1978 issue.

It took me months before I realized that some of my dissatisfaction with my TRS-80 was due to my not completely understanding how it works, and exactly how to program some difficult tasks.

Once I began to realize what my TRS-80 could do, and could not do, I began to appreciate it much more.

There's a great deal I still don't know about the TRS-80. I'm not all that much into machine language, preferring to use Basic, (which I'm still learning about,) in areas such as strings, matrices, and TRS-80 graphics.

But the more I use the Level II computer, the more I like it. I know just about what it can do, and can't, and I recommend it to most of the people who ask me what personal computer to buy.

Most, but not all. The TRS-80 can't please everybody, which is why the Apple II, PET, Atari and Sorcerer computers sell as well as they do.

What I Like About the TRS-80

Service and support are two of the main reasons for my liking the Level II TRS-80.

As for service, when I had problems with my RAM memory, and also wanted the lower-case modification installed, along with the free cassette-loading fix, all I had to do was take my keyboard unit down to a Computer Center in lower Manhattan, where a skilled technician took all of 55 minutes to fix the memory problem (a faulty RAM IC) and install the two mods.

Who else has over 85 Computer Centers around the country? How many other personal-computer manufacturers require that you *mail* the computer to them for service?

As for support, I'm talking about the vast amount of absolutely fascinating Level II software available.

I don't mean Radio Shack's programs, most of which have shown a great deal of conservativism and lack of imagination. (Although they're beginning to break away from the mold, and have brought out some good programs lately, mostly written by outsiders, and including Scripsit, Astrology and Dancing Demon.)

Although a great many poor programs are being sold by people whose main interest seems to be in making a fast dollar, some very clever software is being written by programming geniuses. Leo Christopherson, who wrote Dancing Demon, has written several outstanding games. Lance Micklus is another master gamesman.

The pages of *Creative Computing* and other computer magazines are full of ads for some highly imaginative TRS-80 games and some very well thought out utility and business programs for the TRS-

80. There are programs for fighting your way through a dungeon full of demons, playing music, drilling children in math, balancing a checkbook, communicating on a network, performing advanced math, writing paychecks, word processing, playing baseball, simulating lab experiments, playing the horses, turning on household appliances, creating and using a database, printing a mailing list, controlling inventory, working in double-precision math, managing a budget, tracking stock trends, generating a horoscope, drawing animated movies, playing chess and backgammon, and hundreds more.

Yes, the other popular personal computers have a lot of programs, but nowhere near the variety and number written for the Level II TRS-80.

More publications specialize in the TRS-80 than in all the others put together: *80-US, The Eighty, 80 Microcomputing, PROG/80, S-80 Bulletin, Insiders,* and probably a couple more I don't know about. That's in addition to the magazines that regularly run TRS-80 articles.

What I Don't Like About the TRS-80

There are some things I don't like about the TRS-80, although several of these have been taken care of with free modifications.

I got terribly annoyed when extra letters started showing up on my screen, as in NEXXT, FFOR and RNND. That can be fixed by prying up the keys and cleaning the spring contacts; the newer keyboards don't use spring contacts.

The lack of lower-case letters was a nuisance until I had the lower-case mod installed. There were problems loading some tapes, until I had the free cassette-loading mod installed, which enabled me to load all but the very worst tapes.

The Level II TRS-80 Model I doesn't have color. But now there's the TRS-80 Color Computer. Several things were left out of Level II Basic. But they are in Microsoft's Level III Basic.

The Level II manual is really a reference manual, and as such is missing a great deal of helpful information. But Radio Shack promises to publish its own Level II user's manual some day. And several fine Level II manuals have been written outside Radio Shack.

Using cassettes for storing programs used to require a lot of cable-plugging and unplugging. But then I discovered a switchbox (Dick Fuller's RF-II) that eliminates all the cable-handling, also provides a speaker for listening to the bit-stream, and permits easy copying of tapes from one cassette recorder to another.

The TRS-80 Model I has no software-definable keys like the Exidy Sorcerer. But the TSHORT program from Web Associates provides that capability, in addition to several others.

The TRS-80 Voice Synthesizer is difficult to understand. But for another $300 you can get a much more easily understood voice synthesizer elsewhere. And I wouldn't be surprised if Radio Shack brings out a better voice synthesizer next year. (No, I haven't heard any rumors to that effect.)

A good letter-quality printer costs about $2,000. Well, that's really a problem, and my only solution is to save up for one.

Conclusions

After three years of using a TRS-80, I've learned its many capabilities and few weaknesses, and have learned to live with them. Occasionally there are some problems, such as when the Scripsit word-processing program doesn't work the way I want it to, but that's mostly because I don't use it enough to be fluent in all its idiosyncracies.

I wouldn't trade my Level II TRS-80 for any other personal computer made, except for Radio Shack's Model III, with integral disk drives and keyboard.

If there's a peripheral or program I want that doesn't exist, and it's not too far out, somebody will be selling it before long. □

The PET

Frank Covitz

This article describes the pros and cons of the Commodore PET 2001 series personal computer. It is written from the point of view of someone (me) who has used a PET since it was first introduced, and has had some (admittedly limited) experience with other personal computers.

No single machine has everything, so the crux of the matter is to gain an appreciation of how the hardware, firmware, and software interact to your benefit, and to what extent they limit you. These three topics are not strictly separable, but I will use this categorization to keep me from wandering in the following discussion.

HARDWARE

The PET has everything required to operate in a single attractive package — except the cassette recorder. The original PET had a built-in recorder, but a small keyboard. (Although the small keyboard version is no longer being produced, you may be able to get an excellent buy on a used and therefore thoroughly "burned in" small-keyboard model.) The advantage (or disadvantage) of having everything built-in is very much like the corresponding situation with audio equipment, i.e., receiver vs. separate components. For me, it is an advantage since I don't want to contend at the start with a mess of connecting cables (I tend to weave my own tangled web, so who needs additional wires), and I don't have to tie up a TV set for the display. It does, however, mean that the PET is not easily portable.

The black-and-white video image is crisp and stable, and the background is truly black. The display is memory-mapped (more about that later) into 25 lines of 40 characters. Each character is formed via a character generator ROM within an 8*8 pixel cell (the total screen resolution is therefore 320 horizontal by 200 vertical). In addition to the standard alpha-numerics, you also get a set of graphic symbols, some of which are obviously game-oriented (the card suit symbols, for example). These permit pictorial and graphic images to be formed under program control. I am constantly amazed at the degree of cleverness with which people have put these graphic symbols to use within their programs. A lower-case character set (with descenders) is software selectable, with an attendant loss of most of the graphic symbols.

The (full-sized) keyboard is of good but not superb quality, and the numeric and cursor control keypad are in a conveniently separate cluster. Graphic symbols are visible on the forward vertical side of the keycaps and are accessed in conjunction with the SHIFT key. All alpha-numeric and graphic symbols may be displayed in normal or reverse-field mode at the keyboard or under program control. A single RUN/STOP key permits you to load in whatever program is next on tape with a single key-stroke, although in general named programs will probably be used within the format of a LOAD command. (A PET operating system, called Basic 4.0, is available which default loads from the disc rather than tape.) The STOP function of this key is somewhat misleading. It is normally effective when the program is running under the control of the Basic operating system, and will get you cleanly out of loops and allow you to abort your programs early. It is essentially useless, however, if you intend to do machine language programming. Under "crash" conditions, you are normally forced to do a power-on reset, which obviously wipes out your program. There is, however, a user-supplied hardware solution, using the RESET and DIAGNOSTIC SENSE wires. It is relatively simple to wire in, but should not be attempted unless you have some hardware abilities, and are willing to invalidate the warranty. On the positive side, the STOP key can be de-activated under program control, which technique can be used to prevent "curious fingers" from stopping your program.

Next in the hardware discussion is the cassette tape storage and retrieval function. Programs and data can be stored and retrieved on cassette tape at the moderate speed of about 80 characters per second. My experience has been good in the sense that I have been able to read in 95+% of PET tapes written by other PET's and have never received complaints when I've sent out tapes.

Actually, two separate tape drives are supported, so that aside from the slow speed and inherently sequential nature of data on tape, it is at least possible to do data-base programming. The tape motor (but not the PLAY and RECORD buttons) is under system control, so the tape will stop when the end of a program or data file is reached. The COMMODORE tape units do not have audio output, so you will not get an audio feedback (which can be quite comforting at times) to let you know all is well, nor do they have tape counters. Thus, it is pretty inconvenient to store several programs or data sets on the same cassette. However, there is nothing magic about the cassette hardware, so that conventional cassette recorders can be adapted to work on the PET, again with some hardware experience.

Next on the hardware agenda is the IEEE-488 bus. This capability permits the PET to service multiple peripheral devices, such as printers, disk drives, plotters, etc.

Frank Covitz, Deerhill Rd., Lebanon, NJ 08833

MICROCOMPUTER MEASUREMENT and CONTROL for PET, Apple, KIM, and AIM



The world we live in is full of variables we want to measure. These include weight, temperature, pressure, humidity, speed and fluid level. These variables are continuous and their values may be represented by a voltage. This voltage is the analog of the physical variable. A device which converts a physical, mechanical or chemical quantity to a voltage is called a sensor.

Computers do not understand voltages: They understand bits. Bits are digital signals. A device which converts voltages to bits is an analog-to-digital converter.

Our AIM 16 (Analog Input Module) is a 16 input analog-to-digital converter.

The goal of Connecticut microComputer in designing the uMAC SYSTEMS is to produce easy to use, low cost data acquisition and control modules for small computers. These acquisition and control modules will include digital input sensing (e.g. switches), analog input sensing (e.g. temperature, humidity), digital output control (e.g. lamps, motors, alarms), and analog output control (e.g. X-Y plotters, or oscilloscopes).

Connectors







The AIM 16 requires connections to its input port (analog inputs) and its output port (computer interface). The ICON (Input CONnector) is a 20 pin, solder eyelet, edge connector for connecting inputs to each of the AIM16's 16 channels. The OCON (Output CONnector) is a 20 pin, solder eyelet edge connector for connecting the computer's input and output ports to the AIM16.

The MANMOD1 (MANifold MODule) replaces the ICON. It has screw terminals and barrier strips for all 16 inputs for connecting pots, joysticks, voltage sources, etc.

CABLE A24 (24 inch interconnect cable) has an interface connector on one end and an OCON equivalent on the other. This cable provides connections between the uMACSYSTEMS computer interfaces and the AIM 16 or XPANDR1 and between the XPANDR1 and up to eight AIM 16s.

XPANDR1

The XPANDR1 allows up to eight Input/Output modules to be connected to a computer at one time. The XPANDR1 is connected to the computer in place of the AIM16. Up to eight AIM 16 modules are then connected to each of the eight ports provided using a CABLE A24 for each module. Power for the XPANDR1 is derived from the AIM16 connected to the first port.

Analog Input Module

The AIM 16 is a 16 channel analog to digital converter designed to work with most microcomputers. The AIM16 is connected to the host computer through the computer's 8 bit input port and 8 bit output port, or through one of the uMAC SYSTEMS special interfaces.

The input voltage range is 0 to 5.12 volts. The input voltage is converted to a count between 0 and 255 (00 and FF hex). Resolution is 20 millivolts per count. Accuracy is 0.5% ± 1 bit. Conversion time is less than 100 microseconds per channel. All 16 channels can be scanned in less than 1.5 milliseconds.

Power requirements are 12 volts DC at 60 ma.

The POW1 is the power module for the AIM16. One POW1 supplies enough power for one AIM16, one MANMOD1, sixteen sensors, one XPANDR1 and one computer interface. The POW1 comes in an American version (POW1a) for 110 VAC and in a European version (POW1e) for 230 VAC.

TEMPSENS

This module provides two temperature probes for use by the AIM16. This module should be used with the MANMOD1 for ease of hookup. The MANMOD1 will support up to 16 probes (eight TEMPSENS modules).

Resolution for each probe is 1°F.

Computer Interfaces and Sets

For your convenience the AIM16 comes as part of a number of sets. The minimum configuration for a usable system is the AIM16, one POW1, one ICON and one OCON. The AIM16 Starter Set 2 includes a MANMOD1 in place of the ICON. Both of these sets require that you have a hardware knowledge of your computer and of computer interfacing.

For simple plug compatible systems we also offer computer interfaces and sets for several home computers.

INTRODUCING
SUPER X-10 MODULE

Open a door or window and turn on a light, tape recorder, alarm!

Control lab equipment. CLOSE THE LOOP on the real world.

AN INEXPENSIVE CONTROL SOLUTION FOR

HOME SECURITY
ENERGY CONSERVATION
GREENHOUSES
ENVIRONMENTAL CONTROL
INDUSTRIAL CONTROL
LABORATORIES

SUPER X-10 MOD SPECS

1. Remote controller
   Controls up to 256 different remote devices by sending signals over the house wiring to remote modules. Uses BSR remote modules available all over the USA (Sears, Radio Shack, etc.). Does not require BSR control module. Does not use sonic link.
2. Clock/calendar
   Time of day - hours, minutes, seconds
   Date - month, day - automatically corrects for 28,29,30 and 31 day months.
   Day of the week.
3. Digital inputs/outputs
   8 inputs - TTL levels or switch closures. Can be used as triggers for stored sequences.
   8 outputs - TTL levels
4. Computer interfaces
   S-100: Requires one 8-bit input port and one 8-bit output port. Requires cable assembly.
   PET, APPLE, TRS-80, KIM, SYM, AIM65: Plug-in sets available - no cable assembly required.
   Other: same as S-100
5. Self-contained module in metal case with its own power supply. Physical size approximately 5X6X2.

AC REMOTE CONTROL FROM YOUR COMPUTER

PLUS:
CLOCK, CALENDAR,
REMOTE SEQUENCE TRIGGERS

All prices and specifications subject to change without notice. Our 30-day money back guarantee applies.

AIM16 (16 channel-8 bit Analog Input Module)	179.00
POW1a (POWer module-110 VAC)	14.95
POW1e (POWer module-230 VAC)	24.95
ICON (Input CONnector)	9.95
OCON (Output CONnector)	9.95
MANMOD1 (MANifold MODule)	59.95
CABLE A24 (24 inch interconnect cable)	19.95
XPANDR1 (allows up to 8 Input or Output modules to be connected to a computer at one time)	59.95
TEMPSENS2P1 (two temperature probes, -10°F to 160°F)	49.95
LIGHTSENS1P1 (light level probe)	59.95
The following sets include one AIM16, one POW1, one OCON and one ICON.	
AIM16 Starter Set 1a (110 VAC)	189.00
AIM16 Starter Set 1e (230 VAC)	199.00
The following sets include one AIM16, one POW1, one OCON and one MANMOD1.	
AIM16 Starter Set 2a (110 VAC)	239.00
AIM16 Starter Set 2e (230 VAC)	249.00
The following modules plug into their respective computers and, when used with a CABLE A24, eliminate the need for custom wiring of the computer interface.	
PETMOD (Commodore PET)	49.95
KIMMOD (KIM, SYM, AIM65)	39.95
APMOD (APPLE II)	59.95
TRS-80 MOD (Radio Shack TRS-80)	59.95
The following sets include one AIM16, one POW1, one MANMOD1, one CABLE A24 and one computer interface module	
PETSET1a (Commodore PET - 110 VAC)	295.00
PETSET1e (Commodore PET - 230 VAC)	305.00
KIMSET1a (KIM, SYM, AIM65 - 110 VAC)	265.00
KIMSET1e (KIM, SYM, AIM65 - 230 VAC)	295.00
APSET1a (APPLE II - 110 VAC)	295.00
APSET1e (APPLE II - 230 VAC)	305.00
TRS-80 SET1a (Radio Shack TRS-80 - 110 VAC)	295.00
TRS-80 SET1e (Radio Shack TRS-80 - 230 VAC)	305.00

Order Form

CONNECTICUT microCOMPUTER, Inc.
150 POCONO ROAD
BROOKFIELD, CONNECTICUT 06804
TEL: (203) 775-9659 TWX: 710-456-0052

QUANTITY	DESCRIPTION	PRICE	TOTAL
	SUBTOTAL		
	Handling and shipping — add per order		$3.00
	Foreign orders add 10% for AIR postage		
	add 7% sales tax		
	TOTAL ENCLOSED		

NAME _____
COMPANY _____
ADDRESS _____
_____
CITY _____
STATE _____ ZIP _____
VISA ○ M/C ○ Expiration date _____
Card number _____

PET, cont'd...

As many as 26 external devices can be physically connected in "daisy-chain" style to the PET's IEEE-488 bus, although a maximum of 10 can be active at the same time. The beauty of this way of handling peripheral devices is that there is no programming overhead in operating these devices, i.e., communication to the printer, disk drive, etc. is handled with the same programming techniques. Commands as well as data can be transmitted, so that the external device can have its own "smarts." For example, you can command the disk peripheral to make a disk-to-disk copy with a single command; as soon as the command is sent, the disk system goes on its merry way to complete this several minute task, but the PET is free for any non-disk related task. IEEE-488 devices presently available from Commodore are line printer, dual floppy-disk, telephone modem, and recently, a speech synthesizer. Other IEEE-488 devices are available from a wide variety of manufacturers, but I would definitely advise the reader to specifically verify that they will work with the PET by contacting the manufacturer. On the negative side, IEEE-488 compatible devices tend to be somewhat more expensive than RS-232 devices.

The PET has an 8 bit USER PORT, and two "handshake" lines that are uncommitted, and therefore are completely under control of the user. The physical wires are accessible on an edge connector at the rear of the PET. Software control out of Basic is accomplished by PEEK'ing and POKE'ing to specific address locations. Utilization of the user port requires hardware experience. The lines can in general drive one TTL load, and would therefore need buffering to be used, for example, to turn on a power relay. I have personally used the user port in several ways, for example, to drive a digital-to-analog (DAC) converter to produce music, to communicate data at high speed (about 40,000 bytes per second) between the PET and a KIM or AIM, and to input high speed analog-to-digital data. One of the most common uses of the single bit "CB2" control line is to generate sound effects when connected to an audio amplifier and speaker. Not particularly well known is the fact that the user port has access to a fairly sophisticated timer (part of the 6522 integrated circuit which supplies the user port function) which again is under user control.

The final hardware item to be discussed is the EXPANSION BUS. These wires are accessible at the right side of the PET and communicate at nearly the lowest possible level to the 6502 microprocessor chip that runs the whole show. Available are buffered address lines 0-11, 4K selects for blocks 0-7 and 9-B,, the buffered data bus, the R/W, IRQ, RESET, and CLOCK signals. The expansion bus is not easily used, since it required detailed hardware and software expertise on a machine language level. However, it can be used for memory expansion in both ROM, RAM, and I/O. Several manufacturers make memory expansion boards that connect to the expansion bus.

FIRMWARE

Turn on the power switch of the PET, and you are in the Basic operating system. One of the most important features of the PET firmware is its advanced screen editor. What this means is that as long as your command or program text is visible on the screen, it can be edited with minimum effort. Cursor control keys take the blinking cursor anywhere on the screen, at which point you can overwrite, delete, or insert characters, without having to type in anything additional except RETURN. For example, if you are keying in Basic program lines and discover that you misspelled something 5 lines back, you just position the cursor over the offending area and correct only the error (remember to hit RETURN). Once you get used to this feature, you will look at any operating system that doesn't have this powerful editing feature as "primitive."

Another powerful feature of the operating system firmware is the real-time clock, updated every 1/60 second. Two special variables, TI and TI$, are available to the user for use directly or within programs. This interrupt driven feature also scans the keyboard, and permits look-ahead key entry. This feature means that your keystrokes are remembered, even when the system is nominally "busy." Again, you will only appreciate this on comparison with systems which don't have this feature. On the negative side, the interrupt driver can get in your way in certain machine language programming techniques.

Almost all the commands available to Basic are usable in the direct mode (no line number). This means, for example, you can evaluate arithmetic expressions directly, without writing a separate program. Overall, PET Basic compares favorably in both flexibility and speed with most other Basic's I've seen on other personal computers. PET Basic has a fairly advanced instruction set, including some very powerful string handling functions, and an easy to use IEEE-488 command set. Variables can be integer, real, or string type, and all of them can be multiply subscripted. It also has PEEK and POKE, which allows you to interrogate and alter memory directly. The SYS and USR commands allow you to access machine language routines, but the beginner should be aware that there are many pitfalls (potential crashes) involved.

The final firmware feature that the potential PET user should be aware of is the machine language monitor (MLM). In the early version of the PET, this needed to be loaded from tape. In current versions (Basic 2.0 and 4.0) the MLM is in ROM. The contents of sequential memory locations can be displayed via the command M XXXX-YYYY (XXXX is the start addresses and YYYY is the end address). The nice feature here is the ability to use normal cursor editing to modify either memory locations or register contents. The other commands available via the MLM allow you to execute machine code at a specified address, load and save programs or data on either tape or via an IEEE-488 device, and finally, to return to Basic. The beginner may be reluctant to enter the machine

language realm (but why not give it a try? — the command structure is actually simpler than Basic), but the MLM is there if and when you need it.

SOFTWARE

Software is where it's really at — without good software, even the most sophisticated personal computer will look dumb. One of the most important factors one must consider when trying to decide on a personal computer is the availability and quality of software. No one person has the time and ability to program everything; the best you can hope to do is accept the specific challenges which fit your own interests and capabilities. Many fine products (see advertisements in this issue) are available commercially. These cover a range from action games (*Breakout, Space Invaders, Zap,* etc.), to more serious games (*Microchess, Backgammon, 1000 Miles,* etc.); from relatively simple applications programs to complete systems (various assemblers, word procesors, financial and business packages, educational packages, etc.). Obviously, the PET has no monopoly on good software nor even the largest share within the market. The point I am trying to make is just that software quality and availability is not a limiting factor in the utility of the PET.

Another aspect that deserves mention here is the fact that the PET has attracted a body of personal programmers who, I believe, are unsurpassed in imagination, cleverness, and willingness to share the results of their expertise. I don't feel it is appropriate, nor that I am even qualified to mention names, but I would advise the reader to scan the various personal computer magazines and journals to make their acquaintance. The people at Commodore have, perhaps justifiably, not revealed much of the inner workings of the PET (this situation is steadily improving due to the unrelenting commitment of certain Commodore staff members). However, the active community of PET users has done an essentially complete analysis on their own. There is indeed much "hidden gold" within the PET but unfortunately there is no one place where it is documented fully.

In summary, I would say that you really can't go wrong if you choose the PET as your personal computer. My own experience has been excellent in terms of reliability and capability. The PET shows no signs of obsolescence, and continues to be a popular machine. In all fairness, in case it hasn't been clearly stated above, I should restate what I feel are the PET's main weaknesses; its limited graphics, lack of a built-in RESET switch, and incomplete Commodore documentation. In my opinion, its main strengths are; good Basic operating system, advanced screen editor, good hardware/firmware marriage, IEEE-488 support, and broad based software availability. □

The CBM 2022 Smart Printer

A Second Look And Guide to the Control Codes

Roger C. Crites

Note: This interesting printer uses the PET Bus — 488 or IEEE Bus — and unfortunately, won't hook to most personal computers. Still, we thought its features might pique even the PETless.

I was very much surprised at the evaluation of the Commodore CBM 2020 printer published in *Creative Computing*, May 1980, "A Printer For Your PET — From Commodore?" I use a 2022 daily in the preparation of technical reports, and in the generation of graphs and plots. My experience and the May evaluation agree on only two points. First, the printer is well built. Second, the 7x6 character font limits the effectiveness of single-line reverse field output.

Allowing the customer to unravel the sometimes mysterious behavior of his new equipment all by himself gives him a glowing sense of accomplishment and personal achievement. Well, maybe — but if he is trying to achieve some particular objective in limited time, it can also give him ulcers.

Conspicuous by its absence was any description of the 2022's special features — specifically, formatted output, programmable line spacing, a programmable character, automatic paging with programmable lines per page, and others. If the purpose of an equipment profile is to aid the perplexed buyer, then a more objective approach seems essential.

Because the CBM 2022 is worth serious consideration by anyone in the under-$1000 market, because an objective description of the 2022 is lacking, and because clear documentation is elsewhere unavailable, I am offering a second look at this fine little printer.

Admittedly, it lacks documentation. The user manual (with errata sheets) is better than the documentation furnished with the early PETs, but not much. As with the PET, there is a lot more capability built in than Commodore took the time to explain adequately.

Possibly Commodore feels they are doing their customers a great service. Allowing the customer to unravel the sometimes mysterious behavior of his new equipment all by himself gives him a glowing sense of accomplishment and personal achievement. Well, maybe — but if he is trying to achieve some particular objective in limited time, it can also give him ulcers.

Before putting on my objective-analysis hat, I would like to deal with a couple of impressions given by the May equipment profile. First, the 2022 is portrayed as an extremely noisy printer. Well, noisy is as noisy does. My study is located in a spare bedroom. In the adjacent bedroom two of my daughters sleep undisturbed while my 2022 spits out page after page. Compared to thermal or electrostatic printers, the 2022 may be judged noisy. Compared to other impact printers, since that's what 2022 is, it is not noisy at all.

Secondly, the impression is given that changing or loading paper is a cumbersome task — removing screws, lifting the upper housing, etc. Possibly the unit evaluated was an early prototype (which might also explain the noise). In any case, this impression is incorrect. Standard fanfold paper is loaded very quickly and easily from the top. It is not necessary to remove any screws or lift the upper housing. Changing from standard data processing forms to graph paper, etc., can be accomplished in a matter of seconds with no tools required.

Print Head and Printing Modes

Now, down to business. The CBM 2022 is an 80-column serial impact dot-matrix printer. A heavy-duty Epson 7-wire print head (with a life expectancy of 100 million characters) outputs a 6x7 character font.

Roger C. Crites, 11880 Rio Grande, St. Louis, MO 63138.

AC REMOTE CONTROL FROM YOUR COMPUTER

AIM65

Data Acquisition

16 analog inputs for your AIM65 for measuring temperature, humidity, pressure, position, light levels, or any other analog voltage in the range of 0 to 5 volts. Each input is converted to a number in the range of 0 to 255. Conversion time is less than 100 microseconds — Only $295 complete. Includes cables and power supply. Assembled and tested. Our usual 30 day money back trial period applies.

Order direct or contact your local computer store.

VISA and M/C accepted — send account number, expiration date and sign order
Add $3. per order for shipping and handling — foreign orders add 10% for air postage
Mention this magazine with your order and deduct 2%

CmC

Connecticut microComputer, Inc.
34 Del Mar Drive, Brookfield, CT 06804
203 775-4595 TWX: 710 456-0052

PET Printer Adapter

CmC's ADA 1400 drives a printer with an RS-232 interface from the Commodore PET IEEE-488 bus. The ADA 1400 is addressable, works with the Commodore disk and prints upper and lower case ASCII.

A PET IEEE type port is provided for daisy-chaining other devices.

A cassette tape is included with programs for plot routines, data formatting and screen dumps. The ADA 1400 sells for $179.00 and includes a PET IEEE cable, RS-232 cable, power supply, case, instructions and software.

Order direct or contact your local computer store.

VISA & M/C ACCEPTED-SEND ACCOUNT NO., EXPIRATION DATE AND SIGN ORDER
ADD $3 PER ORDER FOR SHIPPING & HANDLING-FOREIGN ORDERS ADD 10% FOR AIR POSTAGE

CmC

Connecticut microComputer, Inc.
34 Del Mar Drive, Brookfield, CT 06804
203 775-4595 TWX: 710 456-0052

• PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET •

PET PRODUCTS

Programs — Workbooks
for Floppy Disk — for Cassette



See your Dealer

Dealer Inquiries Invited

Put your PET to work!

T I S

PROGRAMS		WORKBOOKS	
SW-1*	MAILB mailing list system	WB-1 Getting Started with Your PET	$3.95
SW-2*	CHECKBOOK record	WB-2 PET String and Array Handling	$3.95
SW-3*	ACCOUNTS keep track of who owes you how much	WB-3 PET Graphics	$4.95
SW-4	MEDIT create and maintain data files	WB-4 PET Cassette I/O	$4.95
SW-5*	CALENDAR appointments, meetings at a glance	WB-5 Miscellaneous PET Features	$3.95
		WB-6 PET Control and Logic	$3.95

*These programs are special purpose data base management systems. They all can:
- Sort numeric or string fields
- Select based on numeric or string (=)
- Select based on substring match
- Select based on range of entry number

Prices: $9.90 each for programs using cassette storage for data
$12.95 each using sequential floppy disk storage for data.
Price includes 40 - 60 page instruction manual

Add $2.00 for shipping and handling
Money back guarantee

TIS
P.O. Box 921, Dept. CC
Los Alamos, NM 87544

VISA

On bank card orders, give all numbers

PET is a trademark of Commodore Business Machines

• PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET • PET •

CIRCLE 193 ON READER SERVICE CARD



Skyles Electric Works
231 E South Whisman Road
Mountain View, CA 94041

CIRCLE 249 ON READER SERVICE CARD

2022, cont'd...

The ribbon spool is similar to a typewriter spool, but the ribbon itself is a special heavy duty nylon-fibered material. It has a life expectancy of 4 million characters. The print-head strikes only the upper half of the ribbon, and after an estimated 2 million characters it is necessary to flop the ribbon to expose the unused lower half. Wire-impact force and print-head clearances will receive any standard (5/32 x .5) pin feed paper or forms ranging in width from about 1 inch to 9.5 inches (which tears to the popular 8-1/2 width.)

The user may operate the 2022 in full dot-by-dot mode through a programmable character (explained later). This dot-by-dot control, used while sweeping the print-head with no gaps between the lines, allows you to emulate a digital plotter. the resolution of the 2022 in this mode is about 0.017 inches. However, line-to-line repeatability in print-head trajectory and timing results in an uncertainty of about .010 inches in dot placement. With this kind of slop, the 2022 is obviously not going to displace Versatec or Calcomp; nevertheless, with a programmable character (in addition to the PEt graphics characters), acceptable plots can be made.

Standard character size is 0.;100 wide by 0.110 high. While there is a full lower case, lower-case letters do not have true descenders on this machine (see sample).

An enhanced print mode is incorporated. In this mode an "enhancement" code is prefixed to the output string. The result is a boldface, double width print, which is very useful for headings.

CHR$(1) prefixed to the output string is the enhancement code that widens characters that follow. An "unenhance" character, CHR$(129), can be inserted to terminate enhanced mode anywhere in a string. Enhanced mode is also terminated by a carriage return.

Multiple enhancement characters may be prefixed, resulting in bolder and bolder print. The real limit on this enhancement is legibility. The characters get wider, but not higher. For example, a string prefixed with 9 enhancement codes would print about 1 inch wide characters, but they would still be only .11 inches high. (While such exaggerated print has little use in reports, it can be used with graphic characters to produce some interesting three-dimensional illusions.)

Embedded Control Characters

The printer may be controlled in two ways. The simple method is by inserting transparent control characters in the print string. The first two of these, enhance — CHR$(1)-and unenhance — CHR$(129)-have been mentioned.

Uppercase is CHR$(145), lowercase is CHR$(17).

Reverse field On-CHR$(18)-indicates that following characters are to be printed in reverse field. Reverse Field Off — CHR$(146)-terminates reverse field output.

A Carriage Return — CHR$(13)-performs a carriage return/line feed, and also terminates enhancement, reverse field, and lower case operation. Carriage Return with No Line Feed — CHR$(141)-permits overprinting the same line. Line Feed — CHR$(10)-produces one line feed.

Auto-Paging On — CHR$(14)-functions with the number of lines per page (written to control file 3; see below) to index a top of form. When auto-paging is on, the 2022 counts lines and automatically inserts line-feeds to avoid printing on the page-separation perforations.

Paging Off/ Form Feed — CHR$(19)-uses the *previous* top-of-form index to perform a form-feed, and then inhibits auto-paging. Auto-paging must again be selected, if desired, after every form feed.

SkipSpace — CHR$(29) and Quote — CHR$(34)-complete the special control characters. Most of these may be implemented with the PET by use of the cursor control and screen control keys.

Secondary Address, or "Control Files"

The 2022 is also controlled by writing to appropriate secondary printer addresses. With a PET this is done by simply opening "control files", actually certain associated secondary addresses, and then writing the desired control codes into these files. There are 5 control files, or addresses, in the 2022, whose secondary addresses are 2 to 6.

Auto-Formatting

A print format is specified to the printer by writing to a control file with a secondary address of 2. There are several format options with considerable flexibility of implementation. String literals may be embedded in format statements. These literals are printed with the output data in the indicated location.

The predefined format may be switched on and off depending on the secondary address of data to be printed.

Data output to the printer having only the secondary address of zero are printed exactly as received; this is the default value. Data output with a secondary address of 1 are first processed by the printer according to a previously defined format. Both alpha and numeric data can be formatted.

Special forms can also be created by overprinting a line. That is, using appropriate graphics you can print the form lines or divisions and then send a carriage return without a line feed. The output data

CBM 2022 PRINTER

UPPER CASE: A B C D E F G H I J K L M N O P Q R S T U V W X Y Z 0 1 2 3 4-etc.

LOWER CASE: a b c d e f g h i j k l m n o p q r s t u v w x y z 0 1 2 3 4-etc.

PET GRAPHICS: -etc.

REVERSE FIELD:

ENHANCED PRINT: BIGGER

PROGRAMMABLE CHARACTER: -etc.

OTHER FEATURES:

-PROGRAMMABLE LINE SPACING
-PROGRAMMABLE LINES PER PAGE
-AUTO PAGING/FORM FEED
-FORMAT CONTROL(alpha & numeric)
-FORMAT ERROR DIAGNOSTICS

EXAMPLES:

PRINT YOUR OWN LETTERHEAD-

CRITES RESEARCH COMPANY

SIMPLE GRAPHICS-

is then, under format control, printed over the same line.

By using embedded literals, the printer may additionally create a special data form about the data as it is tabulated. Indeed, it is quite easy to instruct the *printer* to format the output data, truncating numbers (for instance) to the specified number of decimal places and aligning them into columns.

In case a format statement doesn't process the output as expected, a format diagnostic printout can be enabled by writing into control file/secondary address 4. The printer will detect any formatting error and print out the format statement with a diagnostic message indicating the problem; an arrow is printed pointing to the offending code.

Paper Travel

Control files (or secondary addresses) 3 and 6 are used to specify the number of lines per page and the number of steps per line feed respectively. The paper advance mechanism has 144 steps per inch of paper travel. A number written to control file 6, specifies how far the paper rises with each line feed; for instance, writing "24" to control file 6 will advance the paper 24/144, or 1/6 of an inch. (This is the powerup default value, the standard 6 lines per inch.)

Any number of steps may be specified. Thus double spacing, triple spacing, half spacing, etc. can be selected. A value of 8 produces a line-feed of half a character height and is useful for printing subscripts on headings. A value of 16 will program the paper stepper to 16 steps per line feed or 16/144 of an inch. This value is equal to .111, or just one thousandth of an inch greater than the .110 character height.

This dot-by-dot control, used while sweeping the print-head with no gaps between the lines, allows you to emulate a digital plotter.

This is extremely useful for graphic output. The character dot matrix of adjoining lines just touch, producing a continuous print field.

The Special Character

A single programmable character can be specified as any combination of dots in the 6x7 matrix. This is programmed by writing to control file/secondary address 5.

Problems

The printer's operating system has a couple of bugs. Closing control files sometimes "listen" to the bus when they shouldn't. This is indicated by the red light on the paper-advance button. (When this happens, the *next* print statement is likely to be ignored.) This can be avoided by not closing control files until the end of the program, or by including dummy print statements after closing each control file.

Certain format statements also seem to produce unexpected results. This is not very common, but once in a while a format code will cause double line-feeds on every carriage return. Quite probably there are other bugs also, just waiting to be uncovered.

The way in which upper and lower case is implemented has some undesirable consequences when making program listings. If the program contains upper and lower case, *the listing is generated with all the lower-case characters replaced by graphics characters.* If the use of lower case is extensive, the listing is hard to decipher. If lower-case text is not used a great deal this will not be a problem. If it is, the only way to get readable listings is to use a translator program which inserts the lower-case control character into the print string when applicable.

Endorsement

All in all, the CBM 2022 is quite a printer for $995.00. But like the early PET, it takes a little individual experimentation to make it really perform. □



PEARL

David Lubar

(With a Lot of Help From Laura McLaughlin)

A program in Basic can cost as much as $6.00 a line for development and debugging. Since many businesses have similar needs, it would seem that a lot of work is being repeated in different places at a rather high cost. There should be a better way. Enter PEARL (Producing Error-free Automatic Rapid Logic). The review package we received was a sample of Level 2, designed for both programmers and laymen. Housed in a high-quality notebook, the system contained two 8-inch disks and over one hundred fifty pages of documentation. To get PEARL running, you need CP/M (a registered trademark of Digital Research), 48K of RAM, CBasic version, 2.03, and two disk drives with at least 150K capacity per disk. There is also a version configured for the TRS-80.

O.K., with that out of the way, the next question is, "What exactly does PEARL do?" PEARL creates programs for filing, editing, updating, and printing data. Let's say a company wants to keep track of customers, with information such as name, address, phone number, account number, and so on. PEARL will develop a program that manages the defined data file. Once the program has been developed, the user has a customized system, complete with prompts, error checks, and defaults.

Was it easy to use? Yes and no, but mostly yes. In a sense, we had the ideal conditions for a test. I had never used CP/M before, but there was someone on staff who had and could play the part of experienced programmer while I took the role of novice.

I left the first few steps to the pro. This consisted of setting up work disks, and configuring the disks. This was a snap for the pro. To quote her, "It's easy if you are at all familiar with CP/M." The configuration process also required a bit of knowledge concerning the equipment that was to be used. However, according to our programmer, the program provided for this task made it amazingly painless, with most of the popular terminals being pre-defined and the rest of the necessary information relatively straightforward.

After that, the tyro can take over, though it is comforting to have a pro around to answer questions such as, "What do they mean by variable code word?" or "How do I make an edit mask?" Throughout the steps, the system displays menus and gives meaningful prompts for all questions. The user enters each field and its length, then specifies what kind of variable will be used, such as integer, floating point, string, date, and so on. The user may also indicate what, if any, editing should be performed and, if, once entered, the field should be protected. After all the fields have been defined, any arrays have to be defined. For example, if you want to use the numbers one through five to represent five different counties, you just have to tell PEARL what each number stands for. Later, when a report is generated, PEARL will replace the number with the correct information.

System generation and compilation take a while. The example we tried took about an hour and a half. Of course, you don't have to sit watching the screen while the compilation is in progress (though that is a great way to kill time and look busy). Once that part is done, the rest is a breeze. You get the program up by entering "run xxxx," using whatever name you gave it. In a few seconds, the menu will appear. Whenever input is about to be made in a field, the screen will show the last value used. This value will be kept if you press return. The program, once generated, ran with no problems, and was very easy to use.

The PEARL manual provided a lot of information for programmers who might want to make changes or add other programs or subroutines. Moreover, the generated CBasic code is clear, with abundant remarks. Documentation is included by program, showing subroutine entry points and giving a complete description of the program's function as well as the variables being used. There is also an explanation of the file structures implemented (both random and indexed-sequential).

Anyone who has need of this type of program could make good use of PEARL. You do need a programmer for some of the early steps, and for any desired modifications, but the programmer will only be tied up for a few hours. She won't have to spend days creating and debugging a system.

PEARL Level 2 is available from Computer Pathways Unlimited, Inc., 2151 Davcor St. S.E., Salem, OR 97302, at a cost of $350. □

Now NRI takes you inside the world's most popular microcomputer to train you at home as the new breed of computer specialist!

NRI teams up with Radio Shack to teach you how to use, program and service microcomputers...make you the complete technician.

It's no longer enough to be just a programmer or a technician. With microcomputers moving into the fabric of our lives (over 200,000 of the TRS-80™ alone have been sold), interdisciplinary skills are demanded. And NRI can prepare you with the first course of its kind, covering the complete world of the microcomputer.

Learn At Home in Your Spare Time

With NRI training, the programmer gains practical knowledge of hardware, enabling him to design simpler, more effective programs. And, with advanced programming skills, the technician can test and debug systems quickly and easily.

Only NRI gives you both kinds of training with the convenience of home study. No classroom pressures, no night school, no gasoline wasted. You learn at your convenience, at your own pace. Yet you're always backed by the NRI staff and your instructor, answering questions, giving you guidance, and helping you over the tough spots.

Training includes TRS-80 computer, transistorized volt-ohm meter, digital frequency counter, and the NRI Discovery Lab with hundreds of tests and experiments.

(TRS-80 is a trademark of the Radio Shack division of Tandy Corp.)

Explore the TRS-80 Inside and Out

NRI training is hands-on training, with practical experiments and demonstrations as the very foundation of your knowledge. You don't just program your computer, you introduce and correct faults ...watch how circuits interact...interface with other systems...gain a real insight into its nature.

You also build test instruments and the NRI Discovery Lab, performing over 60 separate experiments in the process. You learn how your trouble-shooting tools work, and gain greater understanding of the information they give you. Both microcomputer and equipment come as part of your training for you to use and keep.

Send for Free Catalog... No Salesman Will Call

Get all the details on this exciting course in NRI's free, 100-page catalog. It shows all equipment, lesson outlines, and facts on other electronics courses such as Complete Communications with CB, TV and Audio, Digital Electronics, and more. Send today, no salesman will ever bother you. Keep up with the latest technology as you learn on the world's most popular computer. If coupon has been used, write to NRI Schools, 3939 Wisconsin Ave., Washington, D.C. 20016.

NRI McGraw-Hill

NRI Schools
McGraw-Hill Continuing Education Center
3939 Wisconsin Avenue
Washington, D.C. 20016
NO SALESMAN WILL CALL
Please check for one free catalog only.

All career courses approved under GI Bill.
☐ Check for details.

- ☐ Computer Electronics Including Microcomputers
- ☐ TV/Audio/Video Systems Servicing
- ☐ Complete Communications Electronics with CB • FCC Licenses • Aircraft, Mobile, Marine Electronics
- ☐ CB Specialists Course
- ☐ Digital Electronics • Electronic Technology • Basic Electronics
- ☐ Small Engine Repair
- ☐ Electrical Appliance Servicing
- ☐ Automotive Mechanics
- ☐ Auto Air Conditioning
- ☐ Air Conditioning, Refrigeration, & Heating including Solar Technology

Name (Please Print) Age

Street

City/State/Zip

Accredited by the Accrediting Commission of the National Home Study Council

175-120

CIRCLE 214 ON READER SERVICE CARD

Comparative Evaluations of Basic Systems

M. Firebaugh, T. Fossum, P. Sorensen and W. Stone

I. Background and Method

Following the flood of small computer hardware has come a continual stream of Basic language systems. Some of these run under the Digital Research Corporation operating system CP/M for the 8080/Z80 family of personal computers and some are designed for specific personal computers.

We felt it would be instructive for us and valuable to potential computer users to compare several of these systems, measuring such properties as memory requirements, speed, error diagnostics, and quality of documentation. The method used was similar to that used in the comparative evaluation of small computer hardware published previously.[1,2] Software houses were invited to submit their Basic systems for evaluation with the understanding that they could review and comment on a draft version of the results.

Our evaluation results are summarized in the form of three tables. In Table I we present system characteristics, most of which should be available by a careful reading of well-written system documentation. Some characteristics were verified by short test programs. In Table II we present the results of five benchmark programs which were run to measure experimentally memory requirements, speed, and accuracy on each system. Finally, in Table III we present our evaluation of some of the more subjective features of each system, such as the quality of documentation, editing capabilities, and convenience.

M. Firebaugh, T. Fossum, P. Sorensen, and W. Stone, University of Wisconsin-Parkside, Kenosha, WI 53141

Work supported in part by the Center for the Application of Computers University of Wisconsin-Parkside, Kenosha, Wisconsin.

We would stress that the purpose of this evaluation is not to rank these systems or to categorize any system as being "good" or "bad." Since individual needs as well as the prices of various Basic systems vary widely, a system appropriate for one application may be entirely inappropriate for another. In designing the benchmark programs we tried to achieve a balance of "typical" applications including sorting, number crunching, string manipulation, and tests of various functions and error responses. While this selection of benchmark programs was arbitrary and reflects our own experience, it probably produces a fairer test than would a single application program. Finally, to compare the present generation of small computer Basic systems to older and present generation minicomputer based systems, we include the results of running the benchmark programs on a Hewlett-Packard 2000 time-sharing system and a Digital Equipment PDP-11/45 respectively.

II. Results

A. *Defined System Characteristics*

In Table I we present system characteristics as obtained from the software manuals. Such characteristics are clearly important considerations to users in selecting a software package. We did not list all special features available on each system.

B. *Measured System Characteristics—Benchmark Results*

In Table II we present the results of running our set of five benchmark programs. The CP/M system was implemented and the first four systems tested on an Altair 8800B with 48K of memory. The last six systems were tested, respectively, on a 48K APPLE II, a 32K Commodore PET, a 32K TRS-80, a North Star Horizon, a 128K HP-2000 time sharing system (in single-user mode), and a 64K PDP-11/45 under the RSTS/E system. To make the timing and memory requirement results meaningful, the benchmark programs run on each system were identical with the exception of minor system dependent instruction changes. A listing of the set of benchmark programs is available from the authors upon request. We summarize the function of each program below:

FCNEXR — Function exercising program. This program called system predefined functions including the trig functions, log and exponential functions, square root and power functions, and random number generator. The general algorithm was to repeat the process $y = f(x)$; $x = f^{-1}(y)$ a number of times and compare the final result for x with the initial value of x. This gives some measure of the accuracy of the algorithm used in the function and the inverse function and should detect any significant error in either (unless the error in the function compensates precisely the error in the inverse function). The random number generator was tested by calculating the Nth moment x^N of the random number x and comparing this to the theoretically expected value of $1/(N+1)$ for values of N up to 10. Since the accumulated errors were consistent with round-off

NEW! TPM* for TRS-80 Model II
NEW! System/6 Package
Computer Design Labs

Z80* Disk Software

We have acquired the rights to all TDL software (& hardware). TDL software has long had the reputation of being the best in the industry. Computer Design Labs will continue to maintain, evolve and add to this superior line of quality software.

— Carl Galletti and Roger Amidon, owners.

Software with Manual/Manual Alone

All of the software below is available on any of the following media for operation with a Z80 CPU using the CP/M* or similar type disk operating system (such as our own TPM*).

for TRS-80* CP/M (Model I or II)
for 8" CP/M (soft sectored single density)
for 5¼" CP/M (soft sectored single density)
for 5¼" North Star CP/M (single density)
for 5¼" North Star CP/M (double density)

BASIC I

A powerful and fast Z80 Basic interpreter with EDIT, RENUMBER, TRACE, PRINT USING, assembly language subroutine CALL, LOADGO for "chaining", COPY to move text, EXCHANGE, KILL, LINE INPUT, error intercept, sequential file handling in both ASCII and binary formats, and much, much more. It runs in a little over 12 K. An excellent choice for games since the precision was limited to 7 digits in order to make it one of the fastest around. $49.95/$15.

BASIC II

Basic I but with 12 digit precision to make its power available to the business world with only a slight sacrifice in speed. Still runs faster than most other Basics (even those with much less precision). $99.95/$15.

BUSINESS BASIC

The most powerful Basic for business applications. It adds to Basic II with random or sequential disk files in either fixed or variable record lengths, simultaneous access to multiple disk files, PRIVACY command to prohibit user access to source code, global editing, added math functions, and disk file maintenance capability without leaving Basic (list, rename, or delete). $179.95/$25.

ZEDIT

A character oriented text editor with 26 commands and "macro" capability for stringing multiple commands together. Included are a complete array of character move, add, delete, and display function. $49.95./$15.

ZTEL

Z80 Text Editing Language - Not just a text editor. Actually a language which allows you to edit text and also write, save, and recall programs which manipulate text. Commands include conditional branching, subroutine calls, iteration, block move, expression evaluation, and much more. Contains 36 value registers and 10 text registers. Be creative! Manipulate text with commands you write using Ztel. $79.95/$25.

TOP

A Z80 Text Output Processor which will do text formatting for manuals, documents, and other word processing jobs. Works with any text editor. Does justification, page numbering and headings, spacing, centering, and much more! $79.95/$25.

MACRO I

A macro assembler which will generate relocateable or absolute code for the 8080 or Z80 using standard Intel mnemonics plus TDL/Z80 extensions. Functions include 14 conditionals, 16 listing controls, 54 pseudo-ops, 11 arithmetic/logical operations, local and global symbols, chaining files, linking capability with optional linker, and recursive/reiterative macros. This assembler is so powerful you'll think it is doing all the work for you. It actually makes assembly language programming much less of an effort and more creative. $79.95/$20.

MACRO II

Expands upon Macro I's linking capability (which is useful but somewhat limited) thereby being able to take full advantage of the optional Linker. Also a time and date function has been added and the listing capability improved. $99.95/$25.

LINKER

How many times have you written the same subroutine in each new program? Top notch professional programmers compile a library of these subroutines and use a Linker to tie them together at assembly time. Development time is thus drastically reduced and becomes comparable to writing in a high level language but with all the speed of assembly language. So, get the new CDL Linker and start writing programs in a fraction of the time it took before. Linker is compatible with Macro I & II as well as TDL/Xitan assemblers version 2.0 or later. $79.95/$20.

DEBUG I

Many programmers give up on writing in assembly language even though they know their programs would be faster and more powerful. To them assembly language seems difficult to understand and follow, as well as being a nightmare to debug. Well, not with proper tools like Debug I. With Debug I you can easily follow the flow of any Z80 or 8080 program. Trace the program one step at a time or 10 steps or whatever you like. At each step you will be able to see the instruction executed and what it did. If desired, modifications can then be made before continuing. It's all under your control. You can even skip displaying a subroutine call and up to seven breakpoints can be set during execution. Use of Debug I can pay for itself many times over by saving you valuable debugging time. $79.95/$20.

DEBUG II

This is an expanded debugger which has all of the features of Debug I plus many more. You can "trap" (i.e. trace a program until a set of register, flag, and/or memory conditions occur). Also, instructions may be entered and executed immediately. This makes it easy to learn new instructions by examining registers/memory before and after. And a RADIX function allows changing between ASCII, binary, decimal, hex, octal, signed decimal, or split octal. All these features and more add up to give you a very powerful development tool. Both Debug I and II must run on a Z80 but will debug both Z80 and 8080 code. $99.95/$20.

ZAPPLE

A Z80 executive and debug monitor. Capable of search, ASCII put and display, read and write to I/O ports, hex math, breakpoint, execute, move, fill, display, read and write in Intel or binary format tape, and more! on disk

APPLE

8080 version of Zapple

NEW! TPM now available for TRS-80 Model III!

TPM*

A NEW Z80 disk operation system! This is not CP/M*. It's better! You can still run any program which runs with CP/M* but unlike CP/M* this operating system was written specifically for the Z80* and takes full advantage of its extra powerful instruction set. In other words its not warmed over 8080 code! Available for TRS-80* (Model I or II). Tarbell, Xitan DDDC, SD Sales "VERSA-FLOPPY", North Star (SD&DD), and Digital (Micro) Systems. $79.95/$25.

SYSTEM MONITOR BOARD (SMB II)

A complete I/O board for S-100 systems. 2 serial ports, 2 parallel ports, 1200/2400 baud cassette tape interface, sockets for 2K of RAM, 3-2708/2716 EPROM's or ROM, jump on reset circuitry. Bare board $49.95/$20.

ROM FOR SMB II

2KX8 masked ROM of Zapple monitor. Includes source listing $34.95/$15.

PAYROLL (source code only)

The Osborne package. Requires C Basic 2.
5" disks $124.95 (manual not included)
8" disks $ 99.95 (manual not included)
Manual $20.00

ACCOUNTS PAYABLE/RECEIVABLE (source code only)

By Osborne, Requires C Basic 2
5" disks $124.95 (manual not included)
8" $99.95 (manual not included)
Manual $20.00

GENERAL LEDGER (source code only)

By Osborne. Requires C Basic 2
5" disks $99.95 (manual not included)
8" disks $99.95 (manual not included)
Manual $20.00

C BASIC 2

Required for Osborne software. $99.95/$20.

SYSTEM/6

TPM with utilities, Basic I Interpreter, Basic E compiler, Macro I assembler, Debug I debugger, and ZEDIT text editor.
Above purchased separately costs $339.75
Special introductory offer: Only $179.75 with coupon!!



ORDERING INFORMATION

Visa, Master Charge and C.O.D. O.K. To order call or write with the following information.

1. Name of Product (e.g. Macro I)
2. Media (e.g. 8" CP/M)
3. Price and method of payment (e.g. C.O.D.) include credit card info. if applicable.
4. Name, Address and Phone number.
5. For TPM orders only: Indicate if for TRS 80, Tarbell, Xitan DDDC, SD Sales (5¼" or 8"), ICOM (5¼" or 8"), North Star (single or double density) or Digital (Micro) Systems.
6. N.J. residents add 5% sales tax.

Manual cost applicable against price of subsequent software purchase in any item except for the Osborne software.

For information and tech queries call
609-599-2146

For phone orders ONLY call toll free
1-800-327-9191
Ext. 676
(Except Florida)

OEMS

Many CDL products are available for licensing to OEMs. Write to Carl Galletti with your requirements.

* Z80 is a trademark of Zilog
* TRS-80 is a trademark for Radio Shack
* TPM is a trademark of Computer Design Labs. It is not CP/M*
* CP/M is a trademark of Digital Research

Prices and specifications subject to change without notice.

DEALER INQUIRIES INVITED.

COMPUTER DESIGN LABS

342 Columbus Avenue
Trenton, N.J. 08629

CIRCLE 127 ON READER SERVICE CARD

Comparative, cont'd...

TABLE I(a): DEFINED SYSTEM CHARACTERISTICS

System	Version Tested (Date)	List Price	System Memory Requirement	Maximum Symbolic Variable Length (#Significant Characters)	Integer Arithmetic ?	Multi-Statement Functions ?	Function Recursion[1] ?
CBASIC	2.04 (©1978)[2]	$100-140	20K Compiler 17K Runtime	Unlimited (31)	yes	yes	no
MICROSOFT	5.01(7-23-79)	$350	24K	40(40)	yes	no	no
TARBELL	12.14(8-6-79)	$50	24K	23(23)	yes	yes	yes
OPUS	2.3C(©1978)	$99-195	24K	72(72)	no	yes	yes
APPLESOFT II	DOS 3.2 plus (©1979)	$200 (firmware card)	10K ROM or 16K RAM	238(2)	yes	no	no
COMMODORE PET	2001-32N(6-79)	$1200 with hardware	16K	80(2)	yes	no	no
TRS-80	2.3(©1979)	comes with hardware	22K	255(2)	yes	no	no
NORTH STAR	DOS 4.0	comes with hardware	13K	2(2)	no	yes	yes
HP-2000 TS	1976	comes with hardware	28K BASIC complete sys.	2(2)	no	no	no
BASIC-PLUS	RSTS/E V 7.0	comes with RSTS/E sys.	64K for complete operating sys.	30(30)	yes	yes	yes

[1] This feature allows a function to call itself.
[2] The current versions of CBASIC are 2.05 for CRUN2 and 2.03 for CBAS2.

TABLE I(b): DEFINED SYSTEM CHARACTERISTICS - (continued)

System	Multi-Statement Lines?	Line-by Line Syntax Check?	String Arrays ?	Error Message Format	Statement Number Format	Variable Dimension Default	Floating Pt. Mantissa Precision
CBASIC	yes	yes (compile time)	yes (255 char. deep)	2 letter code 37 for compile 51 for runtime	optional - any floating point #	none	14
MICROSOFT	yes	no (only at runtime)	yes (88 char. deep)	full phrase	required 0-65K	11	7 single prec. 16 double prec.
TARBELL	yes	yes	yes	40 short word mnemonics	optional - any alpha numeric string	none	8
OPUS	yes	no	yes	minimal execution error messages	optional - numeric	none	2-55 under program control
APPLESOFT II	yes	no (only at runtime)	yes (256 char. deep)	17 2-3 word messages	required - 0-65K	11	9
COMMODORE PET	yes	no (only at runtime)	yes (255 char. deep)	27 full phrases	required - 0-65K	11	9
TRS-80	yes	no (only at runtime)	yes (255 multi-dimension)	complete sentences	required - 0-65K	10	5.7 single prec. 15.9 double prec.
NORTH STAR	yes	no (only at runtime)	yes	26 2-3 word messages	required - 0-65K	10	8, 10, 12, or 14
HP-2000 TS	no	yes	no	complete sentences	required - numeric	10	6.9
BASIC-PLUS	yes	yes	yes	complete sentences	required - 0-32K	10	6 single prec. 15 double prec.

CHRISTMAS MUSIC
FOR THE HOLIDAYS

GIVE THE TIMELESS GIFT OF MUSIC THIS HOLIDAY SEASON FOR YEAR-ROUND ENJOYMENT

A L F PRODUCTS HAS A COMPLETE LINE OF MUSIC SYNTHESIZER PRODUCTS FOR THE APPLE II™ COMPUTER, INCLUDING ONE OF THE LARGEST COLLECTIONS OF PRE-PROGRAMMED CHRISTMAS MUSIC AVAILABLE.

OUR QUALITY THREE-VOICE APPLE MUSIC SYNTHESIZER (ORDER NO. 10-5-16) IS $265*, AND OUR NEW LOW-COST **NINE-VOICE** APPLE MUSIC II SYNTHESIZER (ORDER NO. 10-5-1) IS JUST $195*. (A DEMONSTRATION RECORD OF OUR APPLE MUSIC II SYNTHESIZER IS AVAILABLE FOR $1)

WE HAVE THREE COMPLETE FLOPPY DISKS FULL OF CHRISTMAS MUSIC FOR OUR SYNTHESIZERS!

ALBUM 0 HAS 24 OF YOUR FAVORITE CHRISTMAS SONGS INCLUDING **JOY TO THE WORLD, THE TWELVE DAYS OF CHRISTMAS, DECK THE HALL,** AND **JOLLY OLD SAINT NICHOLAS.** ALBUM 4 INCLUDES **FROSTY THE SNOWMAN, SILVER BELLS, RUDOLPH THE RED-NOSED REINDEER, WHITE CHRISTMAS,** AND MORE. EACH OF THESE ALBUMS IS ONLY $14.95*. PLUS, OUR **GENERIC CHRISTMAS ALBUM** HAS 22 GENERIC CHRISTMAS SONGS SUITABLE FOR EVERYDAY USE. ORDER BEFORE MIDNIGHT TOMORROW, ONLY $9.95*.

FOR THE REST OF THE YEAR, A L F PRODUCTS ALSO HAS OVER 40 OTHER PRE-PROGRAMMED SONGS AND YOU CAN ALSO ENTER YOUR OWN SONGS WITH OUR HIGHLY ACCLAIMED MUSIC ENTRY SYSTEM

SEE THEM AT YOUR LOCAL APPLE DEALER
OR WRITE FOR INFORMATION

A L F PRODUCTS INC.
1448 ESTES
DENVER, CO 80215
(303) 234-0871

DEALER INQUIRIES INVITED

*WRITE FOR DETAILS

Comparative, cont'd...

TABLE I(c): DEFINED SYSTEM CHARACTERISTICS - (continued)

System	Floating Pt. Exponent Range	Floating Pt. Byte Requirements	Statement Renumbering Command?	Nested IF Structure?	Depth of Nested Subroutines	Assembly Language Linkage?	Formatted Output
CBASIC	-64 +63	8 BCD	not applicable	no	20	yes	yes
MICROSOFT	±38	4 binary, 8 double prec.	yes	yes	no limit specified	yes	yes
TARBELL	±99	6 BCD	no (line designators)	yes	no limit specified	yes	yes
OPUS	±63	3-30 BCD	yes	yes (block structure permitted)	no limit specified	yes	yes
APPLESOFT II	±38	5 binary	no	yes	24	yes	no
COMMODORE PET	±33	5 binary	no	yes	no limit specified	yes	no
TRS-80	±38	4 binary, 8 double prec.	yes	yes	no limit specified	yes	yes
NORTH STAR	±62	5 binary	yes	yes	no limit specified	yes	yes
HP-2000 TS	±38	4	yes	no	no limit specified	no	yes
BASIC-PLUS	±38	4 single prec., 8 double prec.	no	yes	no limit specified	no	yes

errors in every case, we conclude there are no obvious problems with the functions supplied with the systems under test.

QSORT — Sorting program. This program generated 300 random numbers and used the Quicksort algorithm[3] to rank them in increasing order.

MATINV — Matrix inverting program. This program used the synthetic elimination algorithm[4] to invert a N x N "Hilbert Matrix" [in which the element M(I,J) is defined as M(I,J) = 1/(I+J-1)]. The inverse matrix was then multiplied by the original matrix and the resulting matrix compared to the theoretically expected identity matrix [Id(I,J) = 1 for I = J; 0 otherwise]. The maximum deviation of the calculated result from the theoretical value for a 5 x 5 Hilbert Matrix is listed as the "Floating Point Accuracy" in Table II. The timing test results are based on the run time required to invert a 10 x 10 matrix.

STRMAN — String manipulating program. This program created a string and exercised some of the string manipulating subroutines, including CHR$, MID$, and concatenation.

ERRTST — Error testing program. This program simulated the most common errors made in Basic language programming and tested the error exit, defaults, and diagnostics. The general categories of errors tested included: dimension errors,

TABLE I(d): DEFINED SYSTEM CHARACTERISTICS - (continued)

System	Max. Number of Array Dimensions	Break Procedure	Number of String Functions	Peek and Poke Commands	Chaining and Common Variables?	Error Trapping?
CBASIC	no limit specified	none	10	yes	yes	on file errors
MICROSOFT	no limit specified	CTRL C	8	yes	yes	yes
TARBELL	no limit specified	CTRL C	15	yes	yes (no common variables)	no
OPUS	no limit specified	CTRL C	6	yes	yes	yes
APPLESOFT II	88	CTRL C	8	yes	yes (no common variables)	yes
COMMODORE PET	3	STOP CTRL C	8	yes	yes (no common variables)	no no
TRS-80	no limit specified	CTRL C Break	9	yes	yes	yes
NORTH STAR	no limit specified	CTRL C	7	yes	yes (no common variables)	yes
HP-2000 TS	2	Break	--	no	yes	yes
BASIC-PLUS	2	Break CTRL C	23	yes	yes core common area	yes

OSI SOFTWARE FOR OSI OSI

A JOURNAL FOR OSI USERS!!

The Aardvark Journal is a bimonthly tutorial for OSI users. It features programs customized for OSI and has run articles like these:

1) Using String Variables.
2) High Speed Basic On An OSI.
3) Hooking a Cheap Printer To An OSI.
4) An OSI Disk Primer.
5) A Word Processor For Disk Or Tape Machines.
6) Moving The Disk Directory Off Track 12.

Four back issues already available!
$9.00 per year (6 issues)



ADVENTURES

Adventures are interactive fantasies where you give the computer plain English commands (i.e. take the sword, look at the control panel.) as you explore alien cities, space ships, ancient pyramids and sunken subs. Average playing time is 30 to 40 hours in several sessions. There is literally nothing else like them — except being there yourself. We have six adventures available.

ESCAPE FROM MARS — Explore an ancient Martian city while you prepare for your escape.
NUCLEAR SUBMARINE — Fast moving excitement at the bottom of the sea.
PYRAMID — Our most advanced and most challenging adventure. Takes place in our own special ancient pyramid.
VAMPIRE CASTLE — A day in old Drac's castle. But it's getting dark outside.
DEATH SHIP — It's a cruise ship — but it ain't the Love Boat and survival is far from certain.
TREK ADVENTURE — Takes place on a familiar starship. Almost as good as being there.

$14.95 each

NEW SUPPORT ROMS FOR BASIC IN ROM MACHINES

C1S — for the C1P only, this ROM adds full screen edit functions (insert, delete, change characters in a basic line.), Software selectable scroll windows, two instant screen clears (scroll window only and full screen.), software choice of OSI or standard keyboard format, Bell support, 600 Baud cassette support, and a few other features. It plugs in in place of the OSI ROM. NOTE: this ROM also supports video conversions for 24, 32, 48, or 64 characters per line. All that and it sells for a mesly $39.95.

C1E/C2E for C1/C2/C4/C8 Basic in ROM machines.
This ROM adds full screen editing, software selectable scroll windows, keyboard correction (software selectable), and contains both an extended machine code monitor and a fix for the string handling bug in OSI Basic!! It has breakpoint utilities, machine code load and save, block memory move and hex dump utilities. A must for the machine code programmer replaces OSI support ROM. Specify system! $59.95

STRING BUG FIX (replaces basic ROM chip number 3)
All this chip does is to replace the third basic ROM and correct the errors that were put into the ROM mask. $19.95

DATA SHEETS

OS65D LISTING
Commented with source code, 83 pages. $24.95
THE (REAL) FIRST BOOK OF OSI
65 packed pages on how OSI basic works. Our best selling data sheet. $15.95
OSI BASIC IN ROM
Ed Carlson's book of how to program in basic. Now available from Aardvark. $8.95

P.C. BOARDS

MEMORY BOARDS!! — for the C1P. — and they contain parallel ports!
Aardvarks new memory board supports 8K of 2114's and has provision for a PIA to give a parallel ports! It sells as a bare board for $29.95. When assembled, the board plugs into the expansion connector on the 600 board. Available now!

REAL SOUND FOR THE C1P — and it's cheap! This bare board uses the TI sound chip to give real arcade type sound. The board goes together in a couple of hours with about $20.00 in parts. Bare board, plans, and sample program — $15.95

ARCADE AND VIDEO GAMES

ALIEN INVADERS with machine code moves — for fast action. This is our best invaders yet. The disk version is so fast that we had to add selectable speeds to make it playable.
Tape - $10.95 — Disk - $12.95

TIME TREK (8K) — real time Startrek action. See your torpedoes move across the screen! Real graphics — no more scrolling displays. $9.95

STARFIGHTER — a real time space war where you face cruisers, battleships and fighters using a variety of weapons. Your screen contains working instrumentation and a real time display of the alien ships. $6.95 in black and white - $7.95 in color and sound.

SEAWOLFE — this one looks like it just stepped out of the arcades. It features multiple torpedoes, several target ships, floating mines and real time time-to-go and score displays. — $6.95 in black and white $7.95 in color and sound.

SCREEN EDITORS

These programs all allow the editing of basic lines. All assume that you are using the standard OSI video display and polled keyboard.

C1P CURSOR CONTROL — A program that uses no RAM normally available to the system. (We hid it in unused space on page 2). It provides real backspace, insert, delete and replace functions and an optional instant screen clear.
$11.95

C2/4 CURSOR. This one uses 366 BYTES of RAM to provide a full screen editor. Edit and change lines on any part of the screen. (Basic in ROM systems only.)

FOR DISK SYSTEMS — (65D, polled keyboard and standard video only.)

SUPERDISK. Contains a basic text editor with functions similar to the above programs and also contains a renumberer, variable table maker, search and new BEXEC* programs. The BEXEC* provides a directory, create, delete, and change utilities on one track and is worth having by itself. — $24.95 on 5" disk - $26.95 on 8".

DISK UTILITIES

SUPER COPY — Single Disk Copier
This copy program makes multiple copies, copies track zero, and copies all the tracks that your memory can hold at one time — up to 12 tracks at a pass. It's almost as fast as dual disk copying. — $15.95

DISK CATALOGER
This utility reads the directory of your disks and makes up an alphabetic list off all your programs and what disks they are on. $14.95

MACHINE CODE RENUMBERER
(C2/4-MF only)
Renumbers all or part of a program at machine code speeds. — $15.95

VISA

This is only a partial listing of what we have to offer. We now offer over 100 programs, data sheets, ROMS, and boards for OSI systems. Our $1.00 catalog lists it all and contains free program listings and programming hints to boot.

master charge

OSI

Aardvark Technical Services • 1690 Bolton • Walled Lake, MI 48088
(313) 669-3110 or (313) 624-6316

OSI

CIRCLE 102 ON READER SERVICE CARD

Comparative, cont'd...

assignment errors, arithmetic errors, function errors, program structure errors, and miscellaneous errors such as exit procedure from a tight loop. Since this program was purely diagnostic, no timing test was run on it.

C. *System Evaluation*

In Table III we present a subjective evaluation of each system based upon our experience in working with it. Most of the characteristics listed in the evaluation summary should be self-explanatory. However, we should comment briefly on the "Transportability of Dialect" category. Here we are concerned with two questions. By outward transportability, we mean "How easy is it to convert programs written under this system to other Basic systems?" By inward transportability, we mean "How easy is it to convert Basic programs written elsewhere to this system?" The answers to both questions clearly depend on what systems are under consideration.

We raise the transportability issue because we believe potential users should be keenly aware of both the advantages and disadvantages of highly-touted "extended features" of various Basic systems. The advantages include the additional power and flexibility which such features provide. The primary disadvantage must be the system-dependent nature of programs incorporating these extended features. Potential users should recognize that the more extended features a given Basic system offers, the more difficult will be the task of converting resulting programs to other Basic operating systems. In general, the closer the Basic system adheres to the new ANSI Minimal Basic standard, the easier the job of transporting programs into and away from the systems will be.

III. Observations and Conclusions

Below we present some observations and conclusions based on the results tabulated above and our experience in working with each system.

Cbasic — The strengths of this system include its compiler structure and very high precision. As a compiler, it optimizes the use of memory (but not necessarily speed) and is a good system for designing commercial end-user programs. However, since it requires separate processors for editing, compiling, and running, it does not lend itself easily to frequent program changes. This makes program development and debugging inconvenient, although it does have a good set of error messages.

Microsoft — This is an excellent, all-purpose system. Its availability on most hardware systems and adequate customer support have helped make it the standard of the industry. It performed well on all tests but was the most expensive system evaluated.

Tarbell — Several unique features make this interesting system potentially one of the most powerful of those tested. These include flexible I/O features and a line descriptor label format which provides a clear "assembly-language-like" logical structure to programs. The system is also the least expensive of those tested, and the source program is available for modifications and deletions. On the negative side, the documentation was minimal, our system was prone to crashes, and the benchmark programs required the most memory space of any system tested.

Opus — This system, although technically not a true Basic language, has its roots in Basic. With its well-designed block structure and string labels for logic control, it provides the best capability for implementing well-structure end-user application programs of all the systems tested. Other unique features include no distinction between string and numeric variables, and programmer-controlled precision of up to 55 digits. It is not a good language for beginners, and the error detection and diagnostics have not reached the sophistication of the structured programming concepts. Run time error detection is essentially incomprehensible, which makes debugging long programs difficult. The extended features greatly reduce the transportability of programs written in OPUS. Our test results indicate it was the slowest program in execution. However, it is a powerful language and we agree with its author that it "both challenges and rewards the programmer."

Applesoft II — This is the extended, floating-point Basic which we ran under DOS Version 3.2 on one of the popular Apple II Plus computers. This version is Microsoft's Basic extended by Apple to include commands for low- and high-resolution graphics, analog game control input, and speaker output. These commands have been incorporated in a very natural way. In general this system is very convenient to use. It performed extremely well in the speed and accuracy tests and about average in program memory requirements. Because of the extensive, well-written documentation and convenient implementation, this system is well suited

TABLE I (e): DEFINED SYSTEM CHARACTERISTICS - (continued)

System	Random Access of Files	Nested Loop Depth	Number of Key Words	Trace Features	Special Features
CBASIC	yes	no limit	92	yes line # option	compiled
MICROSOFT	yes	no limit	80	yes	
TARBELL	yes excellent file commands	no limit	110	none indicated	line descriptors - assembly like flexible I/O facility
OPUS	yes	no limit	94	yes single step option	block structure, multiple precision arithmetic
APPLESOFT II	yes	10 levels	106	yes	color graphics, analog inputs, TTL I/O Ports, Tone generator
COMMODORE PET	theoretically, but bugs remain	10 levels	71	no	real time clock, graphics character set, screen editor
TRS-80	yes	no limit	89	yes	black and white graphics
NORTH STAR	yes	no limit	73	yes	extensive business applications software available
HP-2000 TS	yes	no limit	---	no	excellent diagnostics, extensive system library
BASIC-PLUS	yes	no limit	238	yes	excellent diagnostics, extensive system library

GIFT IDEAS FOR ANY APPLE II® OR II plus®

SANTA'S VOICE™

If you own an Apple and have a child learning to read, you should own this program. Your child selects a sequence of words from the standard vocabulary and Santa happily repeats them. Your child instantly hears the sense or nonsense of the sentence. Easily record your own words and make your Apple say anything you like. Allows you to include speech in any Basic program using Print commands. Nonseasonal 'demo man' face included. Caution: You will enjoy this program as much as your kids. (48K) $39.95



BEST OF MUSE™

Five of our most popular games on one disk. Escape and The Maze Game alone are worth the price. Perform holiday tunes with the Music Box. Side Shows six mini-games each give you hours of fun. Includes Tank War, an exciting two player shoot out. Original publication combined value of $64.75 (32K) $39.95

THREE MILE ISLAND (SPECIAL EDITION)

It's here . . . The simulation game that reviewers have called a 'classic'. Now in quick-response machine language running on any Apple. You are in complete control of a pressurized nuclear reactor. Read all you want about the nuke controversy, but try this simulation if you really want to experience managing a nuclear facility. (48K) $39.95

from the leader in quality software

MUSE SOFTWARE™

Apple II is a trademark of Apple Computer Corp.

330 N. CHARLES STREET
BALTIMORE, MD 21201
(301) 659-7212

Call or write for information and
the name of your nearest **MUSE** dealer

CIRCLE 226 ON READER SERVICE CARD

TABLE II: MEASURED SYSTEM CHARACTERISTICS - BENCHMARK RESULTS

System	Program Size - No. of Bytes Before Run (No. of bytes after run) FCNEXR	QSORT	MATINV	STRMAN	ERRTST	Program Run Time (sec) FCNEXR	QSORT	MATINV	STRMAN	Floating Pt. Accuracy (Matrix Test, N=5)
CBASIC	1339	597	1679	492	4309	695	62	164	106	4 E-9
MICROSOFT	1747 (1862)	1095 (3602)	1613 (10,326)	895 (6831)	6161 (6201)	68	80	90	114	5.9 E-3
TARBELL	2786 (2953)	1966 (5646)	3972 (7572)	1352 (1425)	9268 (9474)	293	103	96	138	2.0 E-3
OPUS	- - - - - - - - - Not Available - - - - - - - - -					1853	319	413	226	5.3 E-3(8 digit accuracy)
APPLESOFT II	1601 (1768)	1081 (4154)	1604 (12,448)	849 (904)	5642 (5746)	62	56	55	63	1.2 E-5
COMMODORE PET	1706 (1902)	1140 (4203)	1792 (12,636)	904 (966)	6075 (6133)	70	68	67	82	1.2 E-5
TRS-80	1668 (1800)	1200 (3600)	1270 (1854)	923 (1024)	Not Available	76	94	92	134	5.9 E-3
NORTH STAR	1790	1057	1792	904	5632	67	46	41	49	1.0 E-3
HP-2000 TS	1670	1240	1398	942	5988	6.5	20	17	70	7.8 E-3
BASIC-PLUS	8192 (8192)	6144 (12,288)	8192 (12,288)	6144 (6144)	Not Available	6	7	9	20	1.4 E-12

for both the beginner and expert interested in serious computing.

Commodore Pet Basic — This language was written by Microsoft for Commodore. It includes therefore, most of the language features which have made Microsoft Basics the industry standard. The performance of this version of Basic is very similar to other Microsoft-generated dialects. Some programs run a little slower, but this is probably due to the fact that Commodore Basic is a real-time interrupt driven language. This aspect is a powerful one since certain interrupt vectors are maintained in volatile RAM memory and may be changed by user software. The most significant feature of this version of Basic is the screen editor which makes changing programs far easier than on many other systems.

TRS-80 Basic — This system was originally developed by Microsoft for the very popular Radio Shack computer. One of the primary advantages of the system is the excellent, nationwide support provided through company owned Radio Shack stores and a majority of the dealerships. New system update diskettes are provided without cost as they appear. The system has a full text editor, easy assembly link-

TABLE III(a): SYSTEM EVALUATION

System	Built-in Function Performance	Error Identification and Diagnostics	Quality of External Documentation Reference Manual	User's Guide	Ease of Editing
CBASIC	Slow execution, high precision	Good, with two letter coded message	good	minimal	none
MICROSOFT	Satisfactory, single precision only	Good, with adequate diagnostics	good	good	very good
TARBELL	Slow execution, approx. 6 digit precision	Some errors undetected, otherwise good error detection, descriptive error messages	fair	minimal	excellent flexibility prone to crash, documentation poor
OPUS	Slow execution, approx. 6 digit precision	Errors detected but not easily identified	good	good	retype line
APPLESOFT II	Satisfactory	Good error detection, appropriate diagnostics	excellent	good	excellent screen editor
COMMODORE PET	Satisfactory	Good detection, adequate diagnostics	good	fair	excellent screen editor
TRS-80	Satisfactory, single precision only	Good, with adequate diagnostics	excellent	good	very good, adequate screen editing, minimal documentation
NORTH STAR	Satisfactory	Good detection, adequate diagnostics	excellent	good	very good line editor
HP-2000 TS	Satisfactory, approx. 6 digit precision	Good error detection, complete diagnostics	excellent	good	retype line
BASIC-PLUS	Fast execution, high precision	Good error detection, complete diagnostics	excellent	good	retype line or use excellent text editor

WE WILL NOT BE UNDERSOLD

DISK DRIVES $314

40 track, 102K Bytes. Includes power supply and TRS-80* compatible silver enclosure. Ready to plug-in and run the moment you receive it. Can be intermixed with each other and Radio Shack drive on same cable. 90 day warranty. One year on power supply. Available for 220 Vac (50 Hz) operation. **External card edge included.**

FOR TRS-80*

CCI-100	5¼", 40 Track (102K Bytes) for Model I	**$314**
CCI-280	5¼", 80 Track (204K Bytes) for Model I	$449
CCI-800	8" Drive for Model II (½ Meg Bytes)	$795

For Zenith Z89

CCI-189	5¼", 40 Track (102K Bytes) add-on drive	$394
Z-87	Dual 5¼" add-on drive system	$995

DISKETTES — Box of 10 (5¼") – with plastic library case

Maxell $30 • **BASF or Verbatim $24**

8" double density for Model II (box of 10) $36

CLEAR PLASTIC CASE – Holds 50 diskettes $19

DISK OPERATING SYSTEMS

PATCHPAK #4 by Percom Data $ 8.95

CP/M® for Model I, Zenith **$145** • for Model II, Altos $169.00

NEWDOS Plus 40track $ 95.00

NEWDOS 80 $135.00

COMPLETE SYSTEMS

ALTOS 64K, DD, SS, 2-Drive, 1MB ACS 8000-2 $3395

APPLE 16K $988

TRS-80* Model II-64K $3499

TRS-80* LEVEL II-16K with keypad $689

TRS-80* Expansion Interface $249

HEWLETT PACKARD HP-85 $2790

ZENITH Z89, 48K all-in-one computer $2440

ZENITH Z19 $735

TELEVIDEO 912B $698 912C $698 920B $748 920C $748

ATARI 400 $489 ATARI 800 $747

APF Game Only $99 Complete System $499

MATTEL INTELLIVISION $229

MONITORS

LEEDEX	12" B&W Video 100	$129
ZENITH	13" Color	$379
SANYO	9" B&W VM4509	$155
SANYO	12" B&W DM5012	$210
SANYO	12" Green Screen DM5112	$215
SANYO	13" Color DMC6013	$375
APF	9" B&W TVM-10	$139

TELECOMMUNICATIONS

CAT MODEM Works same as Radio Shack Telephone Interface II $148

D-CAT HARD WIRED DIRECT MODEM $199

COMMUNICATIONS SOFTWARE

CCI-TELNET VERSION 5: A communication package which enables microcomputer users to communicate both with large mainframes and other microcomputers. Completely CP/M compatible. Multiple communication protocols supported. **$149**

INTELLIGENT TERMINAL SYSTEM ST-80 III: Enables a TRS-80* to act as a dial-up terminal on any time sharing network. **$139**

16K MEMORY UPGRADE KITS 2 for $82.50 $43

200 ns for TRS-80*, Apple II, (specify): **Jumpers $2.50**

PRINTERS

NEC Spinwriter

Letter Quality High Speed Printer

Includes TRS-80* interface software, quick change print fonts, 55 cps, bidirectional, high resolution plotting, graphing, proportional spacing: R.O. **$2395**

R.O. with Tractor Feed **$2575** KSR with Tractor Feed **$2950**

C.ITOH Starwriter, 25 CPS, daisy wheel printer **$1895**

C.ITOH Starwriter II, 45 CPS, daisy wheel printer **$2195**

Letter quality printers. Use up to 15" paper. 1 year warranty on parts. 3 months on labor. Proportional spacing and bidirectional printing. Same as VISTA V300.

779 CENTRONICS TRACTOR FEED PRINTER $969

Same as Radio Shack line printer I

737 CENTRONICS FRICTION & PIN FEED PRINTER $795

n × 9 proportional and 7 × 8 mono spacing.

Same as Radio Shack line printer IV

730 CENTRONICS FRICTION & PIN FEED PRINTER $595

7 × 7 matrix Same as Radio Shack line printer II

P1 CENTRONICS PRINTER Same as Radio Shack quick printer $269

PAPER TIGER (IP440) Includes 2K buffer and graphics option $879

(IP460) Bidirectional, 160 cps, graphics and 2K buffer $1075

TI-810 Faster than Radio Shack line printer III. Parallel and serial w/TRS-80* interface software w/u + I case & paper tray $1589

Compressed print, vertical form control $1865

OKIDATA Microline 80 Friction and pin feed $545

Tractor Feed, friction, and pin feed $645

Microline 83 Bidirectional, 120 cps, uses up to 15" paper $1050

EATON LRC 7000 + 64 columns, plain paper $289

ANADEX DP-9500/01 $1350 DP-8000 $795

ACCESSORIES

HEAD CLEANING DISKETTE: Cleans drive Read/Write head in 30 seconds. Specify 5¼" or 8". **$20 ea/$45 for 3**

FLOPPY SAVER: Protection for center holes of 5¼" floppy disks. Installation tools and rings for 25 diskettes. $ 11.95

Re-orders of rings only $ 6.95

EXTERNAL DATA SEPARATOR: Eliminates data separation problems (crc). Improves reliability. This plug in unit comes fully assembled and tested. $ 29.95

Z-80 SOFTCARD: Your key to software expansion. The plug-in Z-80 Softcard transforms your Apple into a Z-80 while keeping all the benefits of the 6502. Comes with CP/M in two disk format, MBASIC and GBASIC, full documentation and utility programs. $339

RF MODULATOR: Adapts video to TV $ 35.00

TRS-80 & OTHER MYSTERIES $ 18.95

NEC SPINWRITER THIMBLE $11.95 **RIBBON** $ 6.00

CCS CARDS: Parallel or serial printer interface cards $115.00

RS232: For Radio Shack Interface. $ 84.00

TRS232: Teletype current loop output from cassette port $ 49.00

DISK-DRIVE EXTENDER CABLES: Fits all mini-disk drives. $ 16.95

SIX (6) PRONG ISOLATOR: ISO-2 $ 54.00

AC FILTER/6 PRONG POWER STRIP $ 39.00

DISK DRIVE CABLES: 2 drive **$29.00** 4 drive $ 35.00

DUST COVERS: TRS-80/Apple $ 7.95

PLASTIC DISKETTE HOLDER: For ring binder, holds 20 $ 8.00

For fast delivery, send certified checks, money orders or direct bank wire transfers. Personal or company checks require two to three weeks to clear.

DEALER (NATIONAL/INTERNATIONAL) INQUIRIES INVITED **Send for FREE Catalogue**

The CPU SHOP

TO ORDER CALL TOLL FREE 1-800-343-6522

TWX: 710-348-1796 Massachusetts Residents call 617/242-3361

5 Dexter Row, Dept. K12M
Charlestown, Massachusetts 02129
Hours 10AM-6PM (EST) Mon.-Fri. (Sat. till 5)

Massachusetts Residents add 5% Sales Tax
*TRS-80 is a Tandy Corporation Trademark
® Digital Research

master charge THE INTERBANK CARD VISA®

CIRCLE 171 ON READER SERVICE CARD

TABLE III(b): SYSTEM EVALUATION - (continued)

System	Ease of Code Documentation	Convenience	Transportability of Dialect Outward	Transportability of Dialect Inward
CBASIC	Remarks allowed in source file, flexible statement format	Poor - separate processor for edit, compile, and run	Fair	Good
MICROSOFT	Standard REM statements	Excellent	Excellent	Excellent
TARBELL	Easy to set off blocks of code, standard REM statements	Good - editing is confusing and prone to crashes	Poor - due to "line descriptors" (see special features)	Excellent - designates lines in error
OPUS	Flexible standard REM statements allow structured programming, but use of spaces is confusing	Good	Poor	Fair
APPLESOFT II	Standard REM statements	Good disk operating system	Good - except for color graphics	Very good
COMMODORE PET	Standard REM statements	Inconvenient disk operating system	Good - except for graphics and I/O	Very good
TRS-80	Standard REM statements	Excellent	Excellent	Excellent
NORTH STAR	Standard REM statements	Excellent	Excellent	Fair
HP-2000 TS	Standard REM format limited to entire line	Excellent	Excellent	Fair
BASIC PLUS	Standard REMs, append comments with "!", embedded comments allowed	Excellent	Excellent	Excellent

age, and variable pointers which simplify program modification. Some of the early hardware problems with key contact bounce have been solved by the use of silicone spray treatment and software modification. The expansion interface bug detected in the unit used for this evaluation was corrected free of charge in three days at the area service store.

North Star Basic — This system was implemented by Charles Grant and Mark Greenberg of North Star Computers, Inc. It is a well documented system, similar in style to the HP Basic, and has a very simple and convenient line editor. It was an early entry into the personal computer field, in conjunction with the North Star mini-floppy disk. Consequently, much software exists in North Star Basic. The system is available on disk in 8, 10, 12, or 14 digit integer precision, and the smallest version requires 11.5K of memory. The efficient disk operating system provides relatively fast and quiet file access.

HP-2000 TS Basic — This older generation minicomputer-based system was designed specifically to execute Basic efficiently in a time-sharing environment and serves 32 users. It has been superceded by the HP-3000 series of computers with which it is downwardly compatible. It is a very simple and convenient system to use, but the HP Basic does not have many of the convenient extended features available on most small computers.

PDP-11/45 Basic-Plus under RSTS/E — Basic-Plus is one of the finest Basic languages available. It is implemented on the PDP-11/45 under a time-sharing operating system. It is well suited for the beginner because it is convenient and easy to use as well as for the expert interested in serious programming because of the advanced features provided. An easily implemented "EXTEND" option provides this powerful extension, but seriously reduces the outward transportability of resulting programs. There is extensive external documentation and excellent utility program support.

The data presented here may be useful to programmers interested in comparing Basic systems. The features evaluated will be of interest for many user applications, but the scope of the study did not permit investigation of such important areas as file management and program optimization using integer arithmetic. Reference 5 presents a thorough discussion of software interpreters, and References 6-8 present other evaluations of small computer software systems.

IV. Acknowledgements

We wish to thank a number of persons who helped us on this project. In particular we want to thank the following for running the benchmark programs and assisting in the evaluation: Mark Kleine, UW- Parkside student, on the TRS-80; Dr. Don T. Piele,, UW-Parkside mathematics professor, on the North Star Horizon; Dr. Howard R. Gage, mathematics professor at Whitworth College, Spokane, WA, on Basic-Plus; and Jim Dunion of the American Museum of Science and Energy in Oak Ridge, TN, on the Commodore PET. We appreciate the suggestions and comments of our UW-Parkside colleagues Ron Gatterdam and Ming Kuo and our colleagues Dave Boyd and P.R. Bell at the Oak Ridge Institute for Energy Analysis where much of this work was done. We appreciate the excellent support of IEA secretary Ms Janet Kile.

Finally, we appreciate the cooperation of the distributors of Cbasic, Microsoft, Tarbell, and Opus for making these systems available for this evaluation. □

Footnotes and References

1. "Microcomputers — A Comparative Evaluation," by Morris Firebaugh, Luther Johnson, and William S one, *The Physics Teacher*, pp. 459-490, October 1978.
2. "A Feast of Microcomputers," by Morris Firebaugh, Luther Johnson, and William Stone, *Personal Computing II*, pp. 60-70, November 1978.
3. "Quicksort!," by Steven Harrington, *Kilobaud*, pp. 96-98, April 1979.
4. *Linear Algebra with Linear Differential Equations*, by Frank Lowenthal, pp. 150-151, John Wiley & Sons, New York (1975).
5. *Software Interpreters for Microcomputers*, by Thomas C. McIntire, John Wiley & Sons, New York (1978).
6. "Tiny C. Microsoft Basic 5.0, Research Machines Z80 Algol, Structural Analysis SP80 Macros, Digital Research CP/M 2.0, and MP/M," by Steve North, *Creative Computing 6*, pp. 40-44, March 1980.
7. "TRS-80 Performance Evaluation by Program Timing," by James R. Lewis, *BYTE 5*, pp. 84-94, March 1980.
8. "Atari in Perspective—Atari and PET Compared," by Len Lindsay, *Creative Computing 6*, p. 22-30, April 1980.

THE CONTROLLER®
TAKES A PARTNER...

...THE ANALYZER®

DAKIN5 CORPORATION

CIRCLE 120 ON READER SERVICE CARD

The Electronic Cottage

Alvin Toffler

Alvin Toffler gave the world a new phrase and a new way of thinking when he introduced *Future Shock*. Now he takes an optimistic look at the future in *The Third Wave*. According to Toffler, the "First Wave" of change to transform human history was the agricultural revolution of some 10,000 years ago, and the "Second Wave" of about 300 years ago was the industrial revolution. The changes brought about by the "Third Wave", he believes, will provide startling opportunities for a better life for most people. A major factor in the changing world is, of course, the computer. Following are Toffler's views on this subject, excerpted from *The Third Wave*. Stand back or dive in; the choice is yours.

Hidden inside our advance to a new production system is a potential for social change so breathtaking in scope that few among us have been willing to face its meaning. For we are about to revolutionize our homes as well.

Apart from encouraging smaller work units, apart from permitting a decentralization and de-urbanization of production, apart from altering the actual character of work, the new production system could shift literally millions of jobs out of the factories and offices into which the Second Wave swept them and right back where they came from originally: the home. If this were to happen, every institution we know, from the family to the school and the corporation, would be transformed.

Watching masses of peasants scything a field three hundred years ago, only a madman would have dreamed that the time would soon come when the fields would be depopulated, when people would crowd into urban factories to earn their daily bread. And only a madman would have been right. Today it takes an act of courage to suggest that our biggest factories and office towers may, within our lifetimes, stand half empty, reduced to use as ghostly warehouses or converted into living space. Yet this is precisely what the new mode of production makes possible: a return to cottage industry on a new, higher, electronic basis, and with it a new emphasis on the home as the center of society.

To suggest that millions of us may soon spend our time at home, instead of going out to an office or factory, is to unleash an immediate shower of objections. And there are many sensible reasons for skepticism. "People don't want to work at home, even if they could. Look at all the women struggling to get *out* of the home and into a job!" "How can you get any work done with kids running around?" "People won't be motivated unless there's a boss watching them." "People need face-to-face contact with each other to develop the trust and confidence necessary to work together." "The architecture of the average home isn't set up for it." "What do you mean work at home—a small blast furnace in every basement?" "What

Cottage, cont'd...

about zoning restrictions and landlords who object?" "The unions will kill the idea." "How about the tax collector? The tax people are getting tougher on deductions claimed for working at home." And the ultimate stopper: "What, and stay home all day with my wife (or husband)?"

Even old Karl Marx would have frowned. Working at home, he believed, was a reactionary form of production because "the agglomeration in one workshop" was "a necessary condition for the division of labor in society." In short, there were, and are, many reasons (and pseudoreasons) for regarding the whole idea as silly.

DOING HOMEWORK

Yet there were equally, if not more, compelling reasons three hundred years ago to believe people would never move *out* of the home and field to work in factories. After all, they had labored in their own cottages and the nearby land for 10,000 years, not a mere 300. The entire structure of family life, the process of child-rearing and personality formation, the whole system of property and power, the culture, the daily struggle for existence were all bound to the hearth and the soil by a thousand invisible chains. Yet these chains were slashed in short order as soon as a new system of production appeared.

Today that is happening again, and a whole group of social and economic forces are converging to transfer the locus of work.

To begin with, the shift from Second Wave manufacturing to the new, more advanced Third Wave manufacturing reduces, as we just saw, the number of workers who actually have to manipulate

physical goods. This means that even in the manufacturing sector an increasing amount of work is being done that—given the right configuration of telecommunications and other equipment—could be accomplished anywhere, including one's own living room. Nor is this just a science fiction fantasy.

When Western Electric shifted from producing electromechanical switching equipment for the phone company to making electronic switching gear, the work force at its advanced manufacturing facility in northern Illinois was transformed. Before the changeover, production workers outnumbered white-collar and technical workers three to one. Today the ratio is one to one. This means that fully half of the 2,000 workers now handle information instead of things, and much of their work can be done at home. Dom Cuomo, director of engineering at the Northern Illinois facility put it flatly: "If you include engineers, ten to twenty-five percent of what is done here could be done at home with *existing* technology."

Cuomo's manager of engineering, Gerald Mitchell, went even further. "All told," he stated, "600 to 700 of the 2,000 could *now*—with existing technology—work at home. And in five years, we could go far beyond that."

These informed "guesstimates" are remarkably similar to those made by Dar Howard, manufacturing manager of the Hewlett-Packard factory in Colorado Springs: "We have 1,000 in actual manufacturing. Technologically, maybe 250 of them could work at home. The logistics would be complicated, but the tooling and capital equipment would not prevent it. In white collar research and development, if you're willing to invest in [computer] terminals, one half to three quarters could also work at home." At Hewlett-Packard that would add up to an additional 350 to 520 workers.

All told, it means that fully 35 to 50 percent of the entire work force in this advanced manufacturing center could even now do most, if not all, their work at home, providing one chose to organize production that way. Third Wave manufacturing, Marx notwithstanding, does not require 100 percent of the work force to be concentrated in the workshop.

Nor are such estimates found in electronic industries alone or in giant enterprises. According to Peter Tattle, vice-president of Ortho Pharmaceutical (Canada) Ltd., the question is not "How many can be permitted to work at home?" but rather, "How many *have* to work in the office or factory?" Speaking of the 300 employed in his plant, Tattle says: "Fully 75 percent could work at home if we provided the necessary communications technology." Clearly, what applies to electronics and pharmaceuticals also applies to other advanced industries.

If significant numbers of employees in the manufacturing sector could be shifted to the home even now, then it is safe to say that a considerable slice of the white-collar sector—where there are no materials to handle—could also make that transition.

Indeed, an unmeasured but appreciable amount of work is already being done at home by such people as salesmen and saleswomen who work by phone or visit, and only occasionally touch base at the office; by architects and designers; by a burgeoning pool of specialized consultants in many industries; by large numbers of human-service workers like therapists or psychologists; by music teachers and language instructors; by art dealers, investment counselors, insurance agents, lawyers, and academic researchers; and by many other categories of white-collar, technical, and professional people.

These are, moreover, among the most rapidly expanding work classifications, and when we suddenly make available technologies that can place a low-cost "work station" in any home, providing it with a "smart" typewriter, perhaps, along with a facsimile machine or computer console and teleconferencing equipment, the possibilities for home work are radically extended.

Given such equipment, who might be the first to make the transition from centralized work to the "electronic cottage"? While it would be a mistake to underestimate the need for direct face-to-face contact in business, and all the subliminal and nonverbal communication that accompanies that contact, it is also true that certain tasks do not require much outside contact at all—or need it only intermittently.

Thus "low-abstraction" office workers for the most part perform tasks—entering data, typing, retrieving, totaling columns of figures, preparing invoices, and the like—that require few, if any, direct face-to-face transactions. They could perhaps be most easily shifted into the electronic cottage. Many of the "ultrahigh-abstraction" workers—researchers, for example, and economists, policy formulators, organizational designers—require both high-density contact with peers and colleagues *and* times to work alone. There are times when even deal-makers need to back off and do their "homework."

Nathaniel Samuels, an advisory director of the Lehman Brothers Kuhn Loeb investment banking house, agrees. Samuels, who already works at home 50 to 75 days a year, contends that "future technology will increase the amount of 'homework.'" Indeed, many companies are already relaxing their insistence that work be done in the office. When Weyerhaeuser, the great timber-products company, needed a new brochure on employee conduct not long ago, Vice-President R. L. Siegel and three of his staff members met at his home for almost a week until they had hammered out a draft. "We felt we needed to get out [of the office], to avoid the distractions," says Siegel. "Working at home is consistent with our shift toward flexible hours," he adds. "The important thing is getting your job done. It's incidental to us where you do it."

According to the *Wall Street Journal*, Weyerhaeuser is not alone. "Many other companies also are letting their employees work at home," the newspaper reports, among them United Airlines, whose

Suddenly, RCA makes talking to your computer a lot cheaper.

New interactive data terminal with color graphics—only $369.*

RCA's new VP-3301 is a professional quality, ASCII encoded, interactive data terminal, suitable for a wide variety of industrial, educational, business and individual applications requiring interactive communication between computer and user. Connects directly to your computer or to a standard modem for over the phone access to time sharing networks and data bases. And it's compatible with networks such as those provided by CompuServe Information Services and Source Telecomputing Corp. Microprocessor intelligence and LSI video control integrated circuits bring performance, features and flexibility at a low price. Power supply included.

Unique color locking circuitry creates sharp, jitter free, true color graphics and rainbow free characters.

Displays the entire field of characters in any of 8 colors against any of 8 background colors (7 gray scales with monochrome monitors). Or to add special emphasis, you can display individual letters, words or lines in different colors or in reverse video.

The VP-3301 offers you a choice of two software-selectable display formats: Either 40 characters by 24 lines. Or 20 characters by 12 lines.

The terminal's resident character set consists of 52 upper and lower case alphabetics, 10 numerals, 32 punctuation/math symbols, and 31 control characters. You can also define a total of 128 of your own characters. Including: Greek letters and other foreign alphabets, graphic symbols, large graphics building blocks,playing card suits, unique character fonts, and "little green men."

The keyboard section features flexible-membrane key switches with contact life rated at greater than five million operations. A finger positioning overlay and positive keypress action give good operator "feel".

An on-board sound generator and speaker provides aural feedback for key presses and may also be activated with escape sequences to provide an audio output.

The sealed keyboard surface is spill proof and dust proof. This combined with high noise immunity CMOS circuitry makes the VP-3301 ideal for hostile environments.

Output is industry standard asynchronous RS232C or 20 mA current loop with six switch selectable baud rates and 8 selectable data formats.

The terminal can be connected directly to a 525 line color or monochrome monitor. Or to a standard TV set using an Rf modulator.

For more information, contact RCA MicroComputer Marketing, New Holland Avenue, Lancaster, PA 17604.

Or call our toll-free number: 800-233-0094.

*Suggested user price.

RCA

CIRCLE 245 ON READER SERVICE CARD

Cottage, cont'd...

director of public relations allows his staff people to write at home as much as 20 days a year. Even McDonald's, whose lower-rung employees are needed to staff the hamburger grills, encourages home work among some top executives.

"Do you really need an office as such at all?" asks Booz Allen & Hamilton's Harvey Poppel. In an unpublished forecast, Poppel suggests that "by the 1990s, two-way communications capability [will have been] enhanced sufficiently to encourage a widespread practice of working at home." His view is supported by many other researchers, like Robert F. Latham, a long-range planner at Bell Canada in Montreal. According to Latham, "As information jobs proliferate and communications facilities improve, the number of people who may work at home or at local work centres will also increase."

Similarly, Hollis Vail, a management consultant for the United States Department of the Interior, asserts that by the mid-1980's "tomorrow's word-processing centers could easily be in one's own home"; he has written a scenario describing how a secretary, "Jane Adams," employed by the "Afgar Company" could work at home, meeting her boss only periodically to "talk over problems, and, of course, to attend office parties."

This same view is shared by the Institute for the Future, which, as early as 1971, surveyed 150 experts in "leading edge" companies dealing with the new information technologies, and spelled out five different categories of work that could be transferred to the home.

Given the necessary tools, the IFF found, many of the present duties of the secretary "could be done from home as well as in the office. Such a system would increase the labor pool by allowing married secretaries caring for small children at home to continue to work. . . . There may be no overriding reason why a secretary could not just as well, in many instances, take dictation at home and type the text on a home terminal which produces a clean text at the author's home or office."

In addition, IFF continued, "Many of the tasks performed by engineers, draftsmen, and other white-collar employees might be done from home as readily as, or sometimes more readily than, from the office." One "seed of the future" exists already in Britain, for example, where a company called F. International Ltd. (the "F" stands for Freelance) employs 400 part-time computer programmers, all but a handful of whom work in their own homes. The company, which organizes teams of programmers for industry, has expanded to Holland and Scandinavia and counts among its clients such giants as British Steel, Shell, and Unilever. "Home computer programming," writes the *Guardian* newspaper, is "the cottage industry of the 1980s."

In short, as the Third Wave sweeps across society, we find more and more companies that can be described, in the words of one researcher, as nothing but "people huddled around a computer." Put the computer in people's homes, and they no longer need to huddle. Third Wave white-collar work, like Third Wave manufacturing, will not require 100 percent of the work force to be concentrated in the workshop.

One should not underestimate the difficulties entailed in transferring work from its Second Wave locations in factory and office to its Third Wave location in the home. Problems of motivation and management, of corporate and social reorganization will make the shift both prolonged and, perhaps, painful. Nor can all communication be handled vicariously. Some jobs—especially those involving creative deal-making, where each decision is nonroutine—require much face-to-face contact. Thus Michael Koerner, President of Canada Overseas Investments, Ltd., says, "We all need to be within a thousand feet of one another."

THE TELECOMMUTERS

Nevertheless, powerful forces are converging to promote the electronic cottage. The most immediately apparent is the economic trade-off between transportation and telecommunication. Most high-technology nations are now experiencing a transportation crisis, with mass transit systems strained to the breaking point, roads and highways clogged, parking spaces rare, pollution a serious problem, strikes and breakdowns almost routine, and costs skyrocketing.

The escalating costs of commuting are borne by the individual workers. But they are, of course, indirectly passed on to the employer in the form of higher wage costs, and to the consumer in higher prices. Jack Nilles and a team sponsored by the National Science Foundation have worked out both the dollar and the energy savings that would flow from any substantial shift of white-collar jobs out of centralized downtown offices. Instead of assuming the jobs would go into the homes of employees, the Nilles group used what might be termed a halfway-house model, assuming only that jobs would be dispersed into neighborhood work centers closer to employee homes.

The implications of their findings are startling. Studying 2,048 insurance company employees in Los Angeles, the Nilles group found that each person, on average, traveled 21.4 miles a day to and from work (as against a national average of 18.8 miles for urban workers in the United States). The higher up the managerial scale, the longer the commute, with top executives averaging 33.2 miles. All told, these workers drove 12.4 million miles each year to get to work, using up nearly a half-century's worth of hours to do so.

At 1974 prices, this cost twenty-two cents per mile, or a total of $2,730,000—an amount borne indirectly by the company and its customers. Indeed, Nilles found that the company was paying its downtown workers $520 a year more than the going rate in the dispersed locations—in effect, "a subsidy of transportation costs." It was also providing parking spaces and other costly services made necessary by the centralized location. If we now assume a secretary was earning in the neighborhood of $10,000 a year, the elimination of this commuting cost could have permitted the company to hire nearly 300 additional employees or, alternatively, to add a substantial amount to profits.

The key question is: When will the cost of installing and operating telecommunications equipment fall below the present cost of commuting? While gasoline and other transport costs (including the costs of mass-transit alternatives to the auto) are soaring everywhere, the price of telecommunications is shrinking spectacularly.* At some point the curves must cross.

But these are not the only forces subtly moving us toward the geographical dispersal of production and, ultimately, the electronic cottage of the future. The Nilles team found that the average American urban commuter uses the gasoline equivalent of 64.6 kilowatts of energy to get back and forth to work each day. (The Los Angeles insurance employees burned 37.4 million kilowatts a year in commuting.) By contrast, it takes far less energy to move information.

A typical computer terminal uses only 100 to 125 watts or less when it is in operation, and a phone line consumes only one watt or less while it is in use. Making certain assumptions about how much communications equipment would be needed, and how long it would operate, Nilles calculated that "the relative energy consumption advantage of telecommuting over commuting (i.e., the ratio of commuting energy consumption to telecommuting consumption) is at least 29:1 when the private automobile is used; 11:1 when normally loaded mass transit is used; and 2:1 for 100 per cent utilized mass transit systems."

Carried to their conclusion, these calculations showed that in 1975, had even as little as 12 to 14 percent of urban commuting been replaced by telecommuting, the United States would have saved approximately 75 million barrels of gasoline—and would have thereby completely eliminated the need to import any gasoline from abroad. The implications of that one fact for the U.S. balance of payments and for Middle East politics might also have been more than trivial.

* Satellites slash the cost of long-distance transmission, bringing it so near the zero mark per signal that engineers now speak of "distance-independent" communications. Computer power has multiplied exponentially and prices have dropped so dramatically that engineers and investors alike are left gasping. With fiber optics and other new breakthrough technologies in the wings, it is clear that still further cost reductions lie ahead—per unit of memory, per processing step, and per signal transmitted.

PROGRAM STORE

CALL TOLL FREE 800 424-2738



new DUEL «N» DROIDS

By Leo Christopherson from Acorn
Your 'droid has already learned NIM, so now it's time to teach it how to wield a laser sword! Leo Christopherson, author of "Android NIM," "Dancing Demon" and other animations, has developed a new type of animation and high-quality sound in his latest work.

Your 'droid starts out as a lowly clown. You teach it how to use a laser sword by controlling its movements. After training it to be a "Grand Master," you enter the tournament against the program's skilled 'droid! Entertainment for all ages.

Protected Tape...$14.95
Protected Disk...$20.95

DEATH-MAZE 5000

from Med Systems
A new breed of adventuring! Venture through a graphically represented 3-D maze, with halls that could dead end -- or recede to infinity. Step through the doors or drop into the pits. Will you encounter monsters and mayhem, or will you be treated to useful objects and information? Will you ever get out alive?

You may never find your way out of Deathmaze 5000, but you'll keep trying!

16K TRS-80, 32K APPLE II...$12.95



HAIL to the CHIEF

By P. Brasher & R. Vance from Sensational Software
How would you run a political campaign for the highest office in the land? Would you be elected? Find out with this campaign strategy simulation developed by political scientists. Choose (and perhaps change) your positions on major issues as you conduct your campaign, all the while keeping an eye on the weekly polls.

TRS-80 32K Cassette, 48K Disk
Apple II & Apple II+ 48K Disk
Atari 400 32K Cassette, Atari 800 40K Disk
.....$24.95

TRS-80 Level II 16K unless otherwise noted

new BASKETBALL Dribble Dribble

By John Allen from Acorn
New machine language action game, with sound, from the author of the acclaimed "PINBALL"!

You have to be fast to keep up with the action as you try to outscore your opponent in five minutes of one-on-one basketball. Compete against a friend or your computer.

Steal the ball, duck around your opponent and slant toward the basket for a lay up! The graphics are based on a 3-dimensional depiction of a basketball court, and ball dribbling sounds add to the realism. It's all there but the cheers -- so real you'll wonder how the ball keeps from coming through the screen of your TRS-80! Dribble, Dribble!

Protected Tape...$14.95
Protected Disk...$20.95

GALACTIC TRILOGY

By Douglas Carlston
Take control of the Galactica as you navigate through an uncharted 3-dimensional universe. In "Galactic Empire," you attempt to unify a universe that is randomly created each time you play.

"Galactic Trader" pits your bartering skills against those of the other inhabitants as you try to accumulate riches and power. But watch out for the assassins and the energy cartel -- they're out to getcha!

Diplomacy and deviousness play equal parts in "Galactic Revolution." It's a game that combines tactics, social manipulation and Machiavellian ruthlessness. For more intrigue, this game allows more than one player. Sound effects.

Choose any game at $14.95 for TRS-80 16K on tape, $24.95 for Apple II 48K Disk.

To control the entire universe, get all three!

JET FIGHTER PILOT

from Instant Software
Launch one of several realistic jet fighters from an airport, or catapult from the deck of an aircraft carrier. Incredibly realistic simulation, right down to maintenance problems.

You will not only learn about the dynamics of flight, you'll discover the complex operation of modern military jet aircraft as you sit back and try to keep up with the constantly changing instrument panel display. Challenging and informative.

Cassette...$14.95

EDAS Editor/Assembler

By Roy Soltoff from MISOSYS
With EDAS, you are no longer tied to memory limitations while writing in assembly language. Now you can assemble directly from text stored on disk. Branching lets you test your program, then return directly to EDAS. Great for editing and debugging.

Other features include: global editing, upper/lower case support, block moves, plus availability of DOS commands within EDAS. It's the Editor/Assembler designed with the programmer in mind!

Disk...$79.00

MiGs & Messerschmidts

"It is the summer of 1941 and the Blitzkreig is smashing into the heart of Russia..."

This is how your instructions begin when you become the fighter squadron leader in "Migs & Messerschmitts", one of four exciting new Discovery Air Combat Simulations.

These World War II re-enactments are historically accurate -- they challenge you to learn the tactics used by the actual combatants! Written in machine language for fast response.

MIGs and Messerschmidts
RAF: The Battle of Britain
Jagdstaffel
Winged Samurai

For TRS-80, Apple II, PET -- 16K...$19.95

ACCEL & ACCEL II

From Allen Gelder Software
Imported from England, a compiler for TRS-80 Level II Basic (ACCEL) and Disk Basic (ACCEL II). ACCEL lets you compile the integer portion of your Basic programs to fast, efficient Z-80 machine code. ACCEL II compiles floating-point arithmetic as well, and supports Disk Basic.

Both allow a significant improvement in run-time -- up to 3000% faster in some cases -- and improved program security!

ACCEL.....$44.95
ACCEL II....$89.95

Visit Our New Store: W. Bell Plaza – 6600 Security Blvd · Baltimore, MD

TO ORDER CALL TOLL FREE 800 424-2738 For information Call (202) 337-4691

MAIL ORDERS: Send check or M.O. for total purchase price, plus $1.00 postage & handling. D.C. residents, add 5% tax. Charge card customers: include all embossed information on card.

THE PROGRAM STORE
4200 Wisconsin Avenue NW, Dept. C12 Box 9609
Washington, D.C. 20016

CIRCLE 175 ON READER SERVICE CARD

Cottage, cont'd...

As gasoline prices and energy costs in general rise in the decades immediately ahead, both the dollar cost and energy cost of operating "smart" typewriters, telecopiers, audio and video links, and home-size computer consoles will plummet, still further increasing the relative advantage of moving at least some production out of the large central workshops that dominated the Second Wave era.

All these mounting pressures toward telecommuting will intensify as intermittent gas shortages, odd-even days, long lines at the fuel pump, and perhaps rationing disrupt and delay normal commuting, further jacking up its cost in both social and economic terms.

To this we can add even more pressures tending in the same direction. Corporate and government employers will discover that shifting work into the home—or into local or neighborhood work centers as a halfway measure—can sharply reduce the huge amounts now spent for real estate. The smaller the central offices and manufacturing facilities become, the smaller the real estate bill, and the smaller the costs of heating, cooling, lighting, policing, and maintaining them. As land, commercial and industrial real estate, and the associated tax load all soar, the hope of reducing and/or externalizing these costs will favor the farming-out of work.



The transfer of work and the reduction of commuting will also reduce pollution and therefore the tab for cleaning it up. The more successful environmentalists become at compelling companies to pay for their own pollution, the more incentive there will be to shift to low-polluting activities, and therefore from large-scale, centralized workplaces to smaller work centers or, better yet, into the home.

Beyond this, as environmentalists and conservation-minded citizens groups battle against the destructive effects of the auto, and oppose road and highway construction, or succeed in banning cars from certain districts, they unwittingly support the transfer of work. The net effect of their efforts is to force up the already high cost and personal inconvenience of transport as against the low cost and convenience of communication.

When environmentalists discover the ecological disparities between these two alternatives, and as the shift of work to the home begins to look like a real option, they will throw their weight behind this important decentralist move and help coax us into the civilization of the Third Wave.

Social factors, too, support the move to the electronic cottage. The shorter the workday becomes, the longer the commuting time in relationship to it. The employee who hates to spend an hour getting to and from the job in order to spend eight hours working may very well refuse to invest the same commuting time if the hours spent on the job are cut. The higher the ratio of commuting time to working time, the more irrational, frustrating, and absurd the process of shuttling back and forth. As resistance to commuting rises, employers will indirectly have to increase the premium paid to workers in the big, centralized work locations, as against those willing to take less pay for less travel time, inconvenience, and cost. Once again there will be greater incentive to transfer work.

Finally, deep value changes are moving in the same direction. Quite apart from the growth of privatism and the new allure of small-city and rural life, we are witnessing a basic shift in attitude toward the family unit. The nuclear family, the standard, socially approved family form throughout the Second Wave period is clearly in crisis. We shall explore the family of the future in the next chapter. For now, we need only note that in the United States and Europe—wherever the transition out of the nuclear family is most advanced—there is a swelling demand for action to glue the family unit together again. And it is worth observing that one of the things that has bound families tightly together through history has been shared work.

Even today one suspects that divorce rates are lower among couples who work together. The electronic cottage raises once more on a mass scale the possibility of husbands and wives, and perhaps even children, working together as a unit. And when campaigners for family life discover the possibilities inherent in the transfer of work to the home we may well see a rising demand for political measures to speed up the process—tax incentives, for example, and new conceptions of workers' rights.

During the early days of the Second Wave era, the workers' movement fought for a "Ten Hour Day," a demand that would have been almost incomprehensible during the First Wave period. Soon we may see the rise of movements demanding that all work that *can* be done at home *be* done at home. Many workers will insist on that option as a right. And, to the degree that this relocation of work is seen as strengthening family life, their demand will receive strong support from people of many different political, religious, and cultural persuasions.

The fight for the electronic cottage is part of the larger superstruggle between the Second Wave past and the Third Wave future, and it is likely to bring together not merely technologists and corporations eager to exploit the new technical possibilities but a wide range of other forces—environmentalists, labor reformers of a new style, and a broad coalition of organizations, from conservative churches to radical feminists and mainstream political groups—in support of what may well be seen as a new, more satisfactory future for the family. The electronic cottage may thus emerge as a key rallying point of the Third Wave forces of tomorrow.

THE HOME-CENTERED SOCIETY

If the electronic cottage were to spread, a chain of consequences of great importance would flow through society. Many of these consequences would please the most ardent environmentalist or techno-rebel, while at the same time opening new options for business entrepreneurship.

Community Impact: Work at home involving any sizeable fraction of the population could mean greater community stability —a goal that now seems beyond our reach in many high-change regions. If employees can perform some or all of their work tasks at home, they do not have to move every time they change jobs, as many are compelled to do today. They can simply plug into a different computer.

THE ONLY MAGAZINE BY AND FOR S-100 SYSTEM USERS!

S-100 MICROSYSTEMS™

At last there is a magazine written exclusively for S-100 system users. No other publication is devoted to supporting S-100 system users. No longer will you have to hunt through other magazines for an occasional S-100, CP/M* or PASCAL article. Now find it all in one publication. Find it in **S-100 MICROSYSTEMS.**

Every issue of **S-100 MICROSYSTEMS** brings you the latest in the S-100 world. **Articles on applications, tutorials, software development, letters to the editor, newsletter columns, book reviews, new products, etc.** Material to keep you on top of the ever changing microcomputer scene.

SOFTWARE
CP/M*
Assembler
BASIC
PASCAL
applications
and lots more

SYSTEMS
Cromemco
Intersystems
North Star
IMSAI
SOL
and lots more

HARDWARE
8 bit & 16 bit CPUs
interfacing
hardware mods
bulletin board systems
multiprocessors
and lots more

*TMK Digital Research

Edited by Sol Libes
Published every other month

USA	Canada, Mexico	Other Foreign (Air)
	THREE YEARS (18 issues)	
☐ $24	☐ $38	☐ $69
	TWO YEARS (12 issues)	
☐ $18	☐ $27	☐ $48
	ONE YEAR (6 issues)	
☐ $10	☐ $15	☐ $25

☐ New ☐ Renewal
☐ Payment Enclosed
☐ Visa
☐ MasterCard
☐ American Express
Signature _____
Card No. _____
Expiration date _____

☐ Please bill me ($1.00 billing fee will be added; foreign orders must be prepaid)

S-100 MICROSYSTEMS
P.O. Box 789-M, Morristown, NJ 07960

S-100 MICROSYSTEMS™ ORDER FORM

Name _____
Address _____
_____
City _____ State _____ Zip _____

BACK ISSUES

☐ 1-1 Jan/Feb 1980 $5.00
☐ 1-2 Mar/Apr 1980 $2.50
~~1-3 May/Jun 1980 $2.50~~ *Sold out!*
☐ 1-4 Jul/Aug 1980 $2.50
☐ 1-5 Sep/Oct 1980 $2.50
☐ 1-6 Nov/Dec 1980 $2.50

Postpaid in USA; add $1.00 per issue foreign postage. Subscriptions start the month following receipt of order. Subscriptions cannot start with earlier issues.

CIRCLE 247 ON READER SERVICE CARD

Cottage, cont'd...

This implies less forced mobility, less stress on the individual, fewer transient human relationships, and greater participation in community life. Today when a family moves into a community, suspecting that it will be moving out again in a year or two, its members are markedly reluctant to join neighborhood organizations, to make deep friendships, to engage in local politics, and to commit themselves to community life generally. The electronic cottage could help restore a sense of community belonging, and touch off a renaissance among voluntary organizations like churches, women's groups, lodges, clubs, athletic and youth organizations. The electronic cottage could mean more of what sociologists, with their love of German jargon, call *gemeinschaft*.

Environmental Impact: The transfer of work, or any part of it, into the home could not only reduce energy requirements, as suggested above, but could also lead to energy decentralization. Instead of requiring highly concentrated amounts of energy in a few high-rise offices or sprawling factory complexes, and therefore requiring highly centralized energy generation, the electronic cottage system would spread out energy demand and thus make it easier to use solar, wind, and other alternative energy technologies. Small-scale energy generation units in each home could substitute for at least some of the centralized energy now required. This implies a decline in pollution as well, for two reasons: first, the switch to renewable energy sources on a small-scale basis eliminates the need for high-polluting fuels, and second, it means smaller releases of highly concentrated pollutants that overload the environment at a few critical locations.

Economic Impact: Some businesses would shrink in such a system, and others proliferate or grow. Clearly, the electronics and computer and communications industries would flourish. By contrast, the oil companies, the auto industry, and commercial real estate developers would be hurt. A whole new group of small-scale computer stores and information services would spring up; the postal service, by contrast, would shrink. Papermakers would do less well; most service industries and white-collar industries would benefit.

At a deeper level, if individuals came to own their own electronic terminals and equipment, purchased perhaps on credit, they would become, in effect, independent entrepreneurs rather than classical employees—meaning, as it were, increased ownership of the "means of production" by the worker. We might also see groups of home-workers organize themselves into small companies to contract for their services or, for that matter, unite in cooperatives that jointly own the machines. All sorts of new relationships and organizational forms become possible.

Psychological Impact: The picture of a work world that is increasingly dependent upon abstract symbols conjures up an overcerebral work environment that is alien to us and, at one level, more impersonal than at present. But at a different level, work at home suggests a deepening of face-to-face and emotional relationships in both the home and the neighborhood. Rather than a world of purely vicarious human relationships, with an electric screen interposed between the individual and the rest of humanity, as imagined in many science fiction stories, one can postulate a world divided into two sets of human relationships—one real, the other vicarious—with different rules and roles in each.

No doubt we will experiment with many variations and halfway measures. Many people will work at home part-time and outside the home as well. Dispersed work centers will no doubt proliferate. Some people will work at home for months or years, then switch to an outside job, and then perhaps switch back again. Patterns of leadership and management will have to change. Small firms would undoubtedly spring up to contract for white-collar tasks from larger firms and take on specialized responsibilities for organizing, training, and managing teams of homeworkers. To maintain adequate liaison among them, perhaps such small companies will organize parties, social occasions, and other joint holidays, so that the members of a team get to know one another face-to-face, not merely through the console or keyboard.

Certainly not everyone can or will (or will want to) work at home. Certainly we face a conflict over pay scales and opportunity cost. What happens to the society when an increased amount of human interaction on the job is vicarious while face-to-face, emotion-to-emotion interaction intensifies in the home? What about cities? What happens to the unemployment figures? What, in fact, do we mean by the terms "employment" and "unemployment" in such a system? It would be naïve to dismiss such questions and problems.

But if there are unanswered questions and possibly painful difficulties, there are also new possibilities. The leap to a new system of production is likely to render irrelevant many of the most intractable problems of the passing era. The misery of feudal toil, for example, could not be alleviated within the system of feudal agriculture. It was not eliminated by peasant revolts, by altruistic nobles, or by religious utopians. Toil remained miserable until it was altered entirely by the arrival of the factory system, with its own strikingly different drawbacks.

In turn, the characteristic problems of industrial society—from unemployment to grinding monotony on the job, to overspecialization, to the callous treatment of the individual, to low wages—may, despite the best intentions and promises of job enlargers, trade unions, benign employers, or revolutionary workers' parties, be wholly unresolvable within the framework of the Second Wave production system. If such problems have remained for 300 years, under both capitalist and socialist arrangements, there is cause to think they may be inherent in the mode of production.

The leap to a new production system in both manufacturing and the white-collar sector, and the possible breakthrough to the electronic cottage, promise to change all the existing terms of debate, making obsolete most of the issues over which men and women today argue, struggle, and sometimes die.

We cannot today know if, in fact, the electronic cottage will become the norm of the future. Nevertheless, it is worth recognizing that if as few as 10 to 20 percent of the work force as presently defined were to make this historic transfer over the next 20 to 30 years, our entire economy, our cities, our ecology, our family structure, our values, and even our politics would be altered almost beyond our recognition.

It is a possibility—a plausibility, perhaps—to be pondered.

It is now possible to see in relationship to one another a number of Third Wave changes usually examined in isolation. We see a transformation of our energy system and our energy base into a new *techno-sphere*. This is occurring at the same time that we are demassifying the mass media and building an intelligent environment, thus revolutionizing the *info-sphere* as well. In turn, these two giant currents flow together to change the deep structure of our production system, altering the nature of work in factory and office and, ultimately, carrying us toward the transfer of work back into the home.

By themselves, such massive historical shifts would easily justify the claim that we are on the edge of a new civilization. But we are simultaneously restructuring our social life as well, from our family ties and friendships to our schools and corporations. We are about to create, alongside the Third Wave techno-sphere and info-sphere, a Third Wave *socio-sphere* as well. □

Is BASIC too SLOW?

OSBORNE/ McGraw-Hill's Assembly Language books help you speed up your programs



Assembly language programming is fast and efficient. For some applications, like computer animation or close control of peripherals, its speed makes it indispensable.

Now Osborne/McGraw-Hill helps to simplify assembly language programming. You needn't know anything about assembly language to use our ALP series. Each book is a straightforward, self-teaching textbook that is both concise and easy to understand. Each book explains assembly language programming, describes the function of assemblers, structured programming, and presents over 80 fully debugged practical programming examples.

Table of Contents:

Book	Price	Qty	Amount
6502 Assembly Language Programming	$16.99		
Z80 Assembly Language Programming	$16.99		
6800 Assembly Language Programming	$15.99		
8080A/8085 Assembly Language Programming	$15.99		
Z8000 Assembly Language Programming	$19.99		
6809 Assembly Language Programming available January 1981	$16.99		
The 8086 Book	$16.99		
		Tax	
		Shipping	
		TOTAL	

Name_____

Address_____

City_____

State_____ ZIP_____

Phone_____

HOW TO SHIP_____

To order, return coupon with check or money order. Include 75¢ per item for 4th class mail, $1.25 per book UPS, or $2.50 per book air mail in the U. S. California residents also include local sales tax. To place an order by phone, call: 415/548-2805

1123

OSBORNE/McGraw-Hill
630 Bancroft Way, Dept. L9
Berkeley, CA 94710

CIRCLE 167 ON READER SERVICE CARD



Do Computers Byte?

Judy Neyhart

"Bytes — shmytes!" I said, "Computers may be the *in* thing, but what will having one in my home do for me?" That was my response when my husband and son suggested that we just *had* to have a personal computer. We bought one despite my objections. But now, our Apple, Mac, (it seemed logical to name him Mac since we live in Macintosh country) has become a trusted and much appreciated member of our family. To me a computer was only useful for fouling up the information in my charge account or making mistakes in my bank account, but now I've found that as a mother and homemaker, there are many uses that are valuable to me.

This realization did not come easily. I had a mental block about computers as does, I believe, the average non-data processing adult. My eight-year-old son eagerly read all the manuals and soon learned to program, but I was always "too busy."

My husband demonstrated Mac at a charity computer fair. I sat in the background and watched the many people "playing" delightedly with the keyboard, watching the brightly-colored images on the large TV screen, and listening to the distinctly tuneful computer music. I wondered what I might be missing. Is this box in my house really something I can use?

After months of ignoring Mac, I got some quick tips from my husband on loading the disks and listing the programs. He was so ecstatic that I was at last beginning to share his enthusiasm. Then I began to learn at my own speed. The mental wall was beginning to fall. I'd sit down during the day and practice when no one was watching.

At the National Computer Conference in New York City came the final turning point. I saw the vast and exciting possibilities that lie ahead in the computer field — control of home appliances, color printing, even robots. We bought a printer there, making it possible to display on paper the words and graphics on the screen. With the expanded uses of the printer, my conversion to happy computer owner was complete.

Judy Neyhart, R.D. 5, Box 66D, Kingston, NY 12401.

To all the wives and mothers sympathizing with my computer apathy, I hope you'll give a home computer a chance. I'll list the advantages I now see and the uses I now make of *my* Apple.

1. My checkbook balancing was always a challenge. When the monthly statement came, I'd dread the battle of the numbers. Now with Mac's help — it's easy.

At the National Computer Conference I saw the vast and exciting possibilities that lie ahead in the computer field.

Each Monday as I pay bills, I enter the checks and he does the balancing. As an added bonus, he also sorts according to category (household, entertainment, insurance, etc.). When the statement comes, I just enter the checks that have been cleared through the bank and he does the rest. The numbers are a snap because, as you know, "Computers don't make misteaks (sic)."

2. My children are in the elementary grades and with the Back-to-Basics movement, arithmetic (the old type) is again in vogue. Mac is an excellent unbiased drill sergeant. He can display addition, subtraction, or multiplication problems, do the problem-solving timing, and even grade the results. Along with that he gives praise when earned — "Very Good," "You're Getting Better," or "Try Again." One session a day, and they're both tops in their class.

3. Spelling is also done the same way. When they bring home the list of "Words to study at home," Mommy enters the words in the Spelling Program. Then Mac does the teaching and I'm free to do the wash.

4. As a PTA member, I use Mac and the printer to make Room Mother lists of the students in the class and their phone numbers. I can see that when the news of Mac's capability gets out, I will be a valuable member in other nonprofit groups for keeping member lists.

5. Every week during the fall, we have a family football pool. I enter my choices of college and pro games for the week and make a printout for each of us. We read the predictions and past scores and circle our choices. After the games of the weekend are over, I print out the results of games won, lost, and percentages. We all enjoy this as a family activity and Mac makes it easy.

6. With a supplemental speaker Mac makes a very acceptable organ/music box. The children have learned much about reading music in the conversion of sheet music to computer music (notes, duration, voice). There's a great deal of satisfaction in typing in the proper collection of numbers and letters and getting a very recognizable tune as the result.

7. My address card file box is now obsolete. Mac can not only keep all my friends' names and addresses, but also alphabetize them and print out mailing labels. My Christmas cards are very original and the graphics potential in designs for them is limited only by my imagination. I can make designs by plotting points on the screen or using the etch-a-sketch program. There are also elaborate programmed designs available.

8. The homemaker can sometimes get lost in the humdrum of washing, ironing and cooking. There's not much in our day-

to-day life that can be stimulating to our mental processes. Mac acts as the stimulation for my brain power through logic games such as Othello, Mastermind, and chess. Through Mac I know my homemaker/mother brain will never decay from lack of use.

9. The word processor programs are very useful in arranging and copying informative family letters. The busy days of tending to a growing family's needs do not leave much free time to keep the nonlocal family members (aunts, grandmothers) informed on our activities and happenings. Mac gives me the capability to write one newsy letter and copy it for all family members from Timbuktu to Outer Mongolia. I write short notes on the bottom of each for that personalized touch. The price of a letter really does beat the charges of Ma Bell.

10. My latest project is a family tree program to trace our family's roots. Mac can store and organize the ancestor name and vital information — dates and locations of birth, marriage, and death — and keep the generations in order.

My Apple and I are great friends. I realize that I am very fortunate to be able to "get in on the ground floor" of the personal computer explosion. I don't know what lies ahead in the computer field, but whatever it is, I'm going to be right in step with the progress along the way. □

Interactive Systems and the



Design of Virtuality Part Two

Ted Nelson

In Part I, we considered some nice examples of highly responsive systems. The reality of their implementation details is comparatively unimportant. What *is* important is the design of the conceptual structure and feel of a system; we call this its "virtuality" as distinct from the (unimportant) reality.

In this concluding section we consider some more design examples, and endeavor to find the right principles on which to base the design of interactive systems in general.

A COMPLETE SYSTEM

In one design, the Funny-Face Softree™system, I have endeavored to show that one simple, overarching control structure can be used for a *complete* personal computer system—including word processor, scheduling system, graphics package, bookkeeping package, typesetting and layout programs, etc. (I do not wish to imply, of course, that this is the only way to organize such an integrated system; merely that this one interests me.)

There are four basic controls. These are the *only* controls. They may be understood quickly in a brief demonstration, but in fact the further ramifications of their interaction may become clear gradually.

The controls we call *up, down, around* and *flip.*



I would marry these to the Radio Shack keyboard as follows:



Up and *down* are the easiest. The user

SOFTWARE FOR THE ATARI* 800 AND THE ATARI 400

TARI TREK™
By Fabio Ehrengruber

Get ready for an exciting trek through space. Your mission is to rid the galaxy of Klingon warships, and to accomplish this you must use strategy to guide the starship Enterprise around stars, through space storms, and amidst enemy fire. Sound and color enliven this action-packed version of the traditional trek game. Nine levels of play allow the player to make the mission as easy or as challenging as he wishes. At the highest level you are also playing against time. Damage to your ship can be repaired in space at a cost of time and resources if you can't make it back to base. TARI TREK gives you a lot of trek at a low price. This program is written entirely in BASIC and requires at least 24K of user memory. For the Atari 800 only.

Cassette - $11.95 Diskette - $14.95



FASTGAMMON™
By Bob Christiansen

Play backgammon against a talented computer opponent. This is the latest and best version of the most popu-backgammon-playing program for personal computers - FASTGAMMON. Roll your own dice or let the computer roll them for you. Adjust the display speed to be fast or slow. If you wish you can play a game using the same dice rolls as the previous game - a great aid in improving your skills at backgammon. Beginners find it easy to learn backgammon by playing against the computer, and even very good players find it a challenge to beat FASTGAMMON. The 12-page instruction booklet includes the rules of the game. Written in machine language. Requires only 8K of RAM and runs on both the Atari 400 and the Atari 800.

On cassette only - $19.95



TANK TRAP
By Don Ursem

A rampaging tank tries to run you down. You are a combat engineer, building concrete barriers in an effort to contain the tank. Use either the keyboard or an Atari joystick to move your man and build walls. If you trap the tank you will be awarded a rank based on the amount of time and concrete you used up. But they'll be playing taps for you if you get run over. There are four levels of play. Higher levels of play introduce slow curing concrete, citizens to protect, and the ability of the tank to shoot through any wall unless you stay close by. Music, color, and sound effects add to the excitement. Written in BASIC with machine language subroutines. Requires at least 16K of user memory. Runs on the Atari 800 and on an Atari 400 with 16K RAM.

Cassette - $11.95 Diskette - $14.95

QS FORTH™ By James Albanese. Step into the world of the remarkable FORTH programming language. Writing programs in FORTH is much easier than writing them in assembly language, yet FORTH programs run almost as fast as machine code and many times faster than BASIC programs. QS FORTH is based on fig-FORTH, the popular model from the FORTH Interest Group that has become a standard for microcomputers. QS FORTH is a disk-based system that can be used with up to four disk drives. There are five modules included:

1. The FORTH KERNEL (The standard fig-FORTH model customized to run on the Atari computer).
2. An EXTENSION to the basic vocabulary that contains some handy additional words.
3. An EDITOR that allows editing source programs (screens) using Atari type editing.
4. An IOCB module that makes I/O operations easy to set up.
5. An ASSEMBLER that allows defining FORTH words as a series of 6502 assembly language instructions.

Modules 2-5 may not have to be loaded with the user's application program, allowing for some efficiencies in program overhead. Full error statements (not just numerical codes) are printed out, including most disk error statements. QS FORTH requires at least 24K of RAM and at least one disk drive. For the Atari 800 only.

On diskette only - $79.95

★ ★ ★ ★ ★ ★ ★ ★ ★ ★

ASSEMBLER by Gary Shannon. Write your own 6502 machine language programs with this inexpensive in-RAM editor/assembler. Use the editor to create and edit your assembler source code. Then use the assembler to translate the source code into machine language instructions and store the code in memory. Simple commands allow you to save and load the source code to and from cassette tape. You can also save any part of memory on tape and load it back into RAM at the same or at a different location. The assembler handles all 6502 mnemonics plus 12 pseudo-ops that include video and printer control. Commenting is allowed and error checking is performed. A very useful feature allows you to view and modify hexadecimal code anywhere in memory. Instructions on how to interface machine language subroutines to your BASIC programs are included. ASSEMBLER requires 16K of user memory and runs on both the Atari 800 and the Atari 400.

On cassette only - $24.95

★ ★ ★ ★ ★ ★ ★ ★ ★ ★

6502 DISASSEMBLER by Bob Pierce. This neat 8K BASIC program allows you to disassemble machine code, translating it and listing it in assembly language format on the video and on the printer if you have one. 6502 DISASSEMBLER can be used to disassemble the operating system ROM, the BASIC cartridge, and machine language programs located anywhere in RAM except where the DISASSEMBLER itself resides. (Most Atari cartridges are protected and cannot be disassembled using this disassembler.) Also works as an ASCII interpreter, translating machine code into ASCII characters. 6502 DISASSEMBLER requires only 8K of user memory and runs on both the Atari 800 and the Atari 400.

Cassette - $11.95 Diskette - $14.95

QS QUALITY SOFTWARE
6660 Reseda Blvd., Suite 105, Reseda, CA 91335
(213) 344-6599

*Atari is a registered trademark of Atari Personal Computers, a division of Warner Communications, Inc.

WHERE TO GET IT: Call us at (213) 344-6599 for the name of the Quality Software dealer nearest you. If necessary you may order directly from us. Mastercard and Visa cardholders may place orders by telephone. Or mail your check or bankcard number to Quality Software, 6660 Reseda Blvd., Suite 105, Reseda, CA 91335. California residents add 6% sales tax. SHIPPING CHARGES: Within North America orders must include $1.50 for first class shipping and handling. Outside North America the charge for airmail shipping and handling is $5.00. Pay in U.S. currency.

SOFTWARE FOR THE SORCERER*



FASTGAMMON



HEAD-ON COLLISION



CRIBBAGE

UTILITY PROGRAMS

FORTH. Now Sorcerer owners can enjoy the convenience and speed of the fascinating FORTH programming language. Based on fig-FORTH and adapted for the Sorcerer by James Albanese, this version uses simulated disk memory in RAM and does not require a disk drive. Added to standard fig-FORTH are an on-screen editor, a serial RS-232 driver, and tape save and load capability. Eight-bit input/output has been added allowing use of the Sorcerer's graphics keys Documentation includes examples. Requires 32K or more of RAM. **$49.95**

new! BEDIT by Ernest Bergmann. A BASIC editor. This short and easy to use program is a machine language routine that loads in low memory and allows you to edit your BASIC programs by modifying text on the video screen. No more retyping a long line just to change one character. A few cursor movements make the necessary modifications. Even renumbering lines is easy to do. This program is a real timesaver. Runs on any size Sorcerer. **$11.95**

new! GRAPHICS ANIMATION by Lee Anders. This package provides the BASIC programmer with a powerful set of commands for graphics and animation. The program is written in machine language but is loaded together with your BASIC program and graphics definitions with a CLOAD command. Any image from a character to a large graphic shape may be plotted, moved, or erased with simple BASIC commands. Encounters of plotted character sets with background characters are detected and background images are preserved. Contains a medium resolution plotting routine. A keyboard routine detects key presses without carriage returns. Includes a separate program for constructing images. Runs on any size Sorcerer. **$29.95**

QS SMART TERMINAL by Bob Pierce. Convert your Sorcerer to a smart terminal. Used with a modem, this program provides the capability for you to communicate efficiently and save connect time with larger computers and other microcomputers. The program formats incoming data from time-sharing systems such as The Source for the Sorcerer video. Incoming data can be stored (downloaded) into a file in RAM. Files, including programs, may be saved to or loaded from cassette, listed on the video, transmitted out through your modem, or edited with an on-board text editor. Interfaces with BASIC and the Word Processor Pac. **$49.95**

DPX™ (Development Pac Extension) by Don Ursem. Serious Z80 program developers will find this utility program to be invaluable. Move the line pointer upward. Locate a word or symbol. Change a character string wherever it occurs. Simple commands allow you to jump directly from EDIT to MONITOR or DDT80 modes and automatically set up the I/O you want for listings. Built-in serial driver. Stop and restart listings. Abort assembly with the ESC key. Save backup files on tape at 1200 baud. Load and merge files from tape by file name. Versions for 8K, 16K, 32K, and 48K Sorcerer all on one cassette. Requires the Sorcerer's Development Pac. **$29.95**

PLOT by Vic Tolomei. Now Apple owners will be envious of how easy you can get good graphics on your SORCERER. PLOT includes both a super high resolution mode and a quick low resolution mode. Both are accessible from your BASIC programs using simple commands. Hi-res & lo-res examples included on tape. **$14.95**

SHAPE MAKER™ by Don Ursem. An on-screen character maker. **$14.95**

DEBUG by Bob Pierce. Debug machine language programs. **$14.95**

Z80 DISASSEMBLER by Vic Tolomei. Decode machine language programs. **$14.95**

SOFTWARE INTERNALS MANUAL FOR THE SORCERER by Vic Tolomei. A must for anyone writing software for the SORCERER. Seven chapters: Intro to Machine Language, Devices & Ports, The Monitor, Cassette Interface, BASIC structure, Video & Graphics, The Keyboard. Indexed. Includes diagrams and software routines. 64 pages. **$14.95**

SIMULATIONS AND GAMES

new! CRIBBAGE by Bob Stafford. The computer challenges you to a game of cribbage. An excellent use of graphics displays the cribbage board and all the playing cards. The computer pegs the score, computes all the counts, and plays the good game, adhering strictly to the rules of standard cribbage. Beginners will find it easy to learn the game by playing against the computer, and experienced players will enjoy trying to outsmart the computer with crib layaways and careful play. Requires at least 16K of memory. **$17.95**

STARBASE HYPERION™ by Don Ursem. At last, a true strategic space game for the Sorcerer! Defend a front-line Star Fortress against invasion forces of an alien empire. You create, deploy, and command entire ship squadrons as well as ground defenses in this complex tactical simulation of war in the far future. Written in BASIC and Z-80 code. Full graphics and realtime combat status display. Includes full instructions and STARCOM battle manual. Requires at least 16K of RAM. **$17.95**

HEAD-ON COLLISION™ by Lee Anders. You are driving clockwise and a computer-controlled car is driving counter clockwise. The computer's car is trying to hit you head on, but you can avoid a collision by changing lanes and adjusting your speed. At the same time you try to drive over dots and diamonds to score points. Three levels of play, machine language programming, and excellent graphics make this game challenging and exciting for all. At least 16K of RAM is required. **$14.95**

LUNAR MISSION by Lee Anders. Land your spacecraft softly on the moon by controlling your craft's three propulsion engines. Avoid lunar craters and use your limited fuel sparingly. You can see both a profile view of the spacecraft coming down and a plan view of the landing area. Land successfully and you get to view an animated walk on the moon. Nine levels of play provide a stiff challenge to the most skillful astronaut. Requires at least 16K of RAM. **$14.95**

new! HANGMAN/MASTERMIND by Charles Finch. Two traditional games are brought to life by Sorcerer graphics. HANGMAN has three different vocabulary levels for you to choose from. In MASTERMIND, the computer selects a four-character code and you have to uncover it. These two games provide an enjoyable way for young people to develop their vocabulary and their logical reasoning ability. Written in BASIC, for any size Sorcerer. **$11.95**

FASTGAMMON™ by Bob Christiansen. Backgammon players love this machine language program that provides a fast, skillful opponent. Option to replay a game with the same dice rolls. Eight-page instruction manual includes rules of backgammon. **$19.95**

MARTIAN INVADERS™ by James Albanese. How long can you hold out against a persistent invasion force from Mars? Zap all the members of the landing party and another group comes after you. The longer you hold out, the higher your score. The Sorcerer's programmable graphics make this game look great, plus we've added special keyboard routines to really zip it up. Written in machine language. **$14.95**

NIKE II™ by Charles Finch and Bob Broffel. You may never get your computer back from your kids once they start playing Nike II. The object is to destroy enemy bombers by firing Nike missiles at them. If you miss the bombers, they bomb your factories and return for a second pass. Nine levels of play make this game a challenge for everyone. Written in machine language. **$11.95**

TANK TRAP by Don Ursem. An action game that combines skill, strategy, and luck. A rampaging tank tries to run you down. You are a combat engineer, building concrete barriers in an effort to contain the tank. Four levels of play make this animated game fun for everyone. Written in BASIC with machine language subroutines. **$11.95**

MAGIC MAZE™ by Vic Tolomei. A challenging maze game. Ten levels of play. Holding your lantern, you wander through a maze trying to stay on the right path and avoid pitfalls. Automatic scoring tells you how good a pathfinder you are. **$11.95**

QS **QUALITY SOFTWARE**

6660 Reseda Blvd., Suite 105, Reseda, CA 91335
(213) 344-6599

WHERE TO GET IT: Ask your nearest Sorcerer dealer to see *Quality Software's* Sorcerer programs. Or, if you prefer, you may order directly from us. MasterCharge and Visa cardholders may telephone their orders and we will deduct $1 from orders over $19 to compensate for phone charges. Or mail your order to the address above. California residents add 6% sales tax. *Shipping Charges:* Within North America orders must include $1.50 for first class shipping and handling. Outside North America the charge for airmail shipping and handling is $5.00 — payable in U.S. currency.

*The name "SORCERER" has been trademarked by Exidy, Inc.

Virtuality, cont'd...

is at all times on a tree of functions. Each node is a particular activity or waystation on the tree. *Up* of course takes you to the node above you on the tree. And on this tree, *down* is always specified at any given moment as one of the specific alternatives below.



We may call this a *latching tree*. From your current node you may go down or up. If you go up, you get to the top; if you go down, you follow the path of already latched, or chosen, selections.

How do you change the selection of the node which is *down*? You do this by pressing *around*, which selects in turn each of the different alternatives below. (I call such a circular succession of choices a *ringstep*.) Thus to go between any two places on the tree only a few particular steps are required: something like *up*, *up*, *around*, *down*, *down*.



How do you see where you are and make the choices? Now comes the really unusual part. Each menu is a *jack-o-lantern face*.



You go up and down a tree of menus. Each face has one of its features (left or right eye, nose or mouth) *flashing slightly*. This is the current selection below.

Now a frequent complaint about menus is that you have to take time to read them. In this system that is only true at first; because *every menu has a different facial expression*. So that as you become familiar with the different menus, their scowls and grins tell you where you are at once, and you can make your choices faster and faster.

At the very bottom level of the tree are particular activities; *down* there commands the events themselves.

There are also working faces, however, corresponding to every menu, on which materials may be viewed, scrolled, etc. This working face is the "other side" of the menu. You get to the workface, or back to its menu, by *flip*.



That's essentially all there is to it. What you have seen is what the beginner sees. I have left out showing how the different parts combine, so that, for example, the graphics tablet used with the scheduler produces animation, or the scheduler used with the word processor permits a magazine layout.

I would point out certain other features, however. One is that there are very few steps between paired activities, and the user going repeatedly back and forth between them gets into a rhythm. Faster methods would be in reality less simple.

Another aspect is the system's uniformity of replicative structure. You can go anywhere with confidence that the structure will hold. (It does become quite irregular, however, at the bottom or execution level.)

Some people tell me they'd rather have an input-string command language. That's a mater of taste. Other critics say this system lacks generality, which misses the point. It is simple, easy to learn, and integrated. You cannot get lost. And the funny faces are good for a laugh.

THE XANADU ™ HYPERTEXT ENVIRONMENT

The Xanadu ™ hypertext system, toward which I and colleagues have worked for some twenty years now, is intended as a super document library and annotation system, among other things. We may also think of it as a new form of storage and publication.

The Xanadu system is planned as a network of storage computers in McDonald's-like franchised stands around the country. By dialing into your local Xanadu stand, you may get anything on the whole network—to which your local stand is tied by high-speed lines. You must access the system from a fairly powerful terminal—that is, a computer, for reasons which will become clear later.

While most of the Xanadu work has gone into problems of its implementation—especially algorithmic design and analysis—the system's emerging virtuality has acquired an extremely interesting character, which I will now describe.

Everything stored in the Xanadu system we call a *document*. A piece of text, a picture, a movie (someday), a lonesome marginal note—each of these is a document.

Any document you want comes when you ask for it, if you are entitled to it. A document is private or public—that is, published. Any user may call up any public document instantly, as well as his own private documents or any other private documents he has permission to use.

LINKS AND WINDOWS

Links may be put anywhere in any document. Links, like footnotes or marginal comments, permit a user to jump to related material at any time—and come back from that other material when he likes.

Free-form, non-sequential writing of any kind—what we call collectively "hypertext"—is made possible by these links. But the virtuality of general hypertext would take a book in itself.

An important type of link is the window. A window may be thought of as a "hole" in one document through which shows a part of another document.

CHANGES AND VERSIONS

Not only may an author store a document in its present form; he may, if he chooses, write or rework the document on the system, with the changes themselves stored. The Xanadu system does this at a uniquely low incremental cost, since our data structure and algorithms essentially assemble parts of a given version as they are needed—without ever bothering to assemble the full *consecutive* structure, unless it is asked for.

Thus the user has access, if the materials are saved and open to him, to a reconstruction of any previous version of a document at any previous moment he cares to specify.

Not merely consecutive historical changes, but alternative versions, may be generated at any time. Thus a document may be "rewritten" for different types of readers, and these different versions stored at low overhead.

The user may ask to see any given piece of text (or other information) in any version or at any previous time.

PRICE BREAKTHROUGH



We have used the VersaWriter to draw a picture of itself. Text may be added in any size or direction.

VersaWriter

High-Resolution Color Graphics for Apple II or Apple II Plus

The VersaWriter graphics tablet lets you create multicolor graphics and drawings with your Apple computer. It compares in quality to graphic bit pads and digitizers costing three times more money.

VersaWriter is a digitizer and software package which presents a new approach to hi-res graphics. It consists of a mylar plotting board with a clear plastic overlay. Attached to this board is the drawing arm, which has a magnifying lens with a crosshairs at its end. You simply place any graph, picture or drawing (up to 8½" x 11") under the plastic overlay and "trace" it with the drawing arm. As you trace the drawing appears on the video screen.

The superior software of the VeraWriter enables you to do much more than just trace. Immediate commands include: color choice, brush size (the width of the drawing line), fill figure with color, draw a straight line between two points, use a different scale for drawing (.25 to 4), edit, erase, smothing factor (rounds off the rough edges as you draw), store picture on disk, and more.

One exceptional feature of the VersaWriter is the Shape Table function. You can take any picture, or portion of a picture, and store it as a shape table. Then the table can be recalled from memory and placed on any part of the screen. You can change the size of the image, rotate it, add to it, etc. By incorporating a series of images into a single shape table, commonly used symbols can be easily inserted into a variety of different programs. VersaWriter software includes an Electronic Drawing program which is a shape table of common schematic symbols-this program will give you a good idea of what the shape table can do, as well as let you easily produce electronic or logic diagrams.

Other programs included in the software are: the Textwriter, with which text can be added to graphics (UPPER & lower case, choice of color, text size, direction of text, starting point of text). Area/Distance-this program allows you to calculate distances (or perimeters) by establishing a measuring unit (of your choice) and tracing the shape or map route with the drawing arm. Areas of figures are calculated in the same way-this includes irregular and open figures. A very simple calibration program is also on this software disk.

A second software disk contains VersaWriter demonstration programs. For more advanced use of high-res graphics, there is a skeleton program which contains the guts of the VersaWriter. The VersaWriter is a sturdy peripheral device which plugs into the game paddles I/O port-the VersaWriter does not use up a card slot in the Apple computer. Also, the VersaWriter is not subject to the grounding problems and strong magnetic field problems of other, more expensive, hi-res graphic devices.

VersaWriter requires an Apple II with Applesoft in ROM (or an Apple II Plus), Disk, and a least 32K of memory.

VersaWriter comes complete with 8½" x 11" drawing surface, plastic overlay and two disks of software. Price $252.00 postpaid in continental USA. VersaWriter has a 90-day warranty on parts and labor.

Credit card customers include card number and expiration date of your Visa, Mastercard or American Express card. No C.O.D.'s. Bankcard customers may order toll-free to:

800-631-8112

(In NJ call 201-540-0445)

Dealer Inquiries Invited.

Peripherals Plus

119 Maple Ave., Morristown, NJ 07960

A link made to a certain part of one version of a document may be automatically followed through to the same material in any other version of that document or in its previous incarnations or in other public documents that windows it.

We believe that this "versioning" facility, of linkage across backtrack and alternative versions, solves a central problem of text systems — that of cross-referencing any parts still being worked on; a problem which is chopped at and nibbled at everywhere but is often dealt with in ineffectual ways.

FREE LINKING BY ANYBODY

You may create a document that links to any other documents, if they are public (he who publishes must agree to this in advance).

You may create, in your document, windows to anybody else's public documents. (Since they get the royalty when their part shows, they should be pleased.)

This is how we handle marginal notes. If you create a marginal note, it is automatically put in a new companion document, your document, which is permanently linked to the document you have annotated.

(This "companion document" idea also frees you to *alter and rewrite any public document any way you like*—since the alteration is in a private file of your own that points to the intact original.)

COPYRIGHT

"What of the copyright problem?" you ask. Our solution is simple: as you use the system, you are continuously paying small increments of royalties to copyright owners. These are modest amounts, the same for all users: for instance, if we can supply the service for two dollars an hour at 30 characters per second, the fixed royalty runoff will probably be about five cents an hour. This is divided among the copyright holders in proportion to how much you used from each—sliced very finely.

What keeps people from making copies? Nothing, since terminals are under the control of individual users; but since everything is still stored on the system and available instantly, the cost and inconvenience of making and filing private copies will be often seen as superfluous.

OVERVIEW: THE XANADU SYSTEM AS A VIRTUALITY

The above description specifies a general and powerful facility for business, literature, correspondence and digital storage of all kinds.

As such it represents a cohesive and unified virtuality which has been thought about and reworked for years. Its appearance of simplicity and obviousness is the distinctive quality of a carefully wrought design: *There are hundreds of other ways to do these things*, as experienced computer people well know; yet making the parts hold together clearly, complement each other, and *make sense*, takes a very great deal of work.

XANADU FRONT ENDS

Of the functions described above, only a few are actually handled by the Xanadu service network: *put this away* and *give me that in such-and-such a version* are really all that the Xanadu back-end machines do.

The rest has to be done, actually, in your personal computer. Marginal notes, for instance, require making a companion document out of your marginal notes, for instance, and declaring it and putting it away in the network. Most users will also want to keep track of how they have been jumping among various documents and activities. These necessary functions belong in your own computer.

Thus the "full" Xanadu system, as we recommend it be used, entails a cooperating program in your personal machine that acts in these ways.

Thus full Xanadu service has two parts. The "back end" is the proposed Xanadu network; esentially all it does is store and fetch by versions and links.

But a high-powered terminal is needed by the user, to show the documents sent by the back end, to present the possible actions the user may take, and to translate these choices into the proper fetch-and-store instructions for the back end.

This is of course the "front end." There are many possible ways to visualize and control the Xanadu functions—even before graphics or music are stored on the system—and we welcome imaginative front-end programs of any design, even if marketed independently. The Xanadu project will, however, offer guidelines for front-end design.

If you choose to use the back-end network in some other way, that is your privilege as a customer; but in order to encourage what we see as desirable modes of operation, we will be offering various trademarks to software vendors who wish to create cooperating front-end programs.

Given the overall virtuality of the Xanadu system, there are countless possible ways to summon, visualize and control its operations on screen. All of these are valid and welcome. To give some ideas of the possible varieties, I will discuss two very different Xanadu front ends.

(Since these are highlights of the two front ends, no attempt will be made to show all the functions, reconcile their different emphases, or intercompare them.)

THE XANATREK™ FRONT END

The standard Apple computer, laudable as may be its general qualities and capabilities, has a few conspicuous limitations. One is its text screen, only forty characters wide.

However, an Apple strength is fast-action low-res graphics. Two pages of hardware memory are dedicated to either text *or* low-res graphics. We will proceed to use this fact.

The Xanatrek front end has been designed for fast and exciting use of the Xanadu facilities, as well as for invigorating use of its low-res graphics.

The system was, quite frankly, inspired by *Star Wars*, and shows how far you can go in playful and analogous use of graphics.

One of the things a Xanadu user must be able to do instantaneously is ask exactly what he is looking at—that is, having jumped to something or wandered by degrees from his original activity, he

The MAGIC WAND™ is ALMOST PERFEC.

We've been saying it for a few months now, and the reviewers seem to agree.

"Until I saw the Magic Wand, if I were allowed to own one and only one editor, Word Star* would have been it. . . . My personal preference is for Pencil or Magic Wand for text creation."

Jerry Pournelle
On Computing, Summer 1980

"The basic functions of the Magic Wand editor are as easy to learn as those of Electric Pencil*. . . . Magic Wand dominates in the area of print formatting."

Larry Press
On Computing, Summer 1980

"Of all the word processors I have used (and that includes a dozen or more), the Magic Wand is the most versatile. The Wand has almost all of the features of other processors, plus many new ones of its own. It measures up to even the word-processing software running on the largest mainframe computers."

Rod Hallen
Microcomputing, June 1980

"The Magic Wand is one of the most flexible word processing packages available, and should be considered by any potential word processing purchaser."

Glenn A. Hart
Creative Computing, August 1980

Available for both the CP/M® and OASIS operating systems

small business applications, inc.

3220 Louisiana • Suite 205 • Houston, Texas 77006 • 713-528-5158

Electric Pencil is a trademark of Michael Shrayer Software, Inc.
WordStar is a trademark of Micro Pro International, Inc.
CP/M is a registered trademark of Digital Research Corp.

CIRCLE 194 ON READER SERVICE CARD

needs an instant and valid explanation of what he is looking at.

Very well. While reading anything from the Apple screen (from page one of memory) the user may instantly demand a map of what he is seeing. This is continually available and up-to-date in low-res color, on page two. But aha, you say, how can you read it, since the color display disables the character generator? The answer is that the various patches of identifying text are indeed visible on this map as patches of seemingly random color, but since the Apple allows *one text window* on a low-res screen, successive boppings of a particular control will step the various text labels into a readable panel.

The most amusing visualization in the Xanatrek front end has to do with seeing the major features of a document such as chapter breaks and seeing links as well from a companion or other document.

This brings out the "Star Wars" styling. What the user sees looks like a huge passing spaceship or perhaps a packing crate, in the vault of night.

One of its visible sides shows the major parts of the text itself, as streaks of color. The other visible side shows the entrance points provided in your companion document. (You may select any of these places for your next trip.)

Other ships that pass in the night are documents linked to this one. Want to see the links? Hit a button, and animated squares *fire from one ship to the other*, with that p'tew p'tew sound we *Star Wars* fans have grown to know and love as the sound of a laser weapon in a vacuum.

THE CORNERCOPIA™ FRONT END

This Xanadu front end has been thought out for implementation on an actor language on a small Sorcerer computer.

There are many approaches to the design of screen panels. One approach, generally associated with Xerox PARC, strews panels diagonally on the screen. The approach that follows is intended to be a little easier.

Five to ten screen panels are accesible at a given time. They come out of corners of the screen.

Each panel keeps one free corner anchored in a particular corner of the screen. Its opposite corner remains always visible but may be moved by the



user to any position which does not obscure any other panel's free corner. As with PARC panels, any "behind" panel may be instantly brought to the front without moving its borders.

Each panel is labelled with a one-line title (at the top of the lower panels or the bottom of the upper ones).

The text may show and scroll in any panel; naturally dependent or "parallel" text (a standard Xanadu statement) may scroll in any other visible panel with links to the independent text shown by scrolling symbols on the panel borders.

Perhaps this environment seems not to show enough. Very well: some panels themselves represent *other* such environments; when brought to the fore they swell up to become other multipanelled views.

OOF

The "office of the future" will consist basically of cabinets for incoming correspondence, printers for outgoing correspondence, and in between, screens, screens, screens.

In this highly competitive area, harried programming managers everywhere are under pressure to work out what *happens* on the screens. But what do they, or *anybody*, know about it? It's *not a technical problem!* It's merely delegated like one.

The problem has nothing to do with technicalities; all of these are squared away. The problem is in the design of virtuality. But I know of few designers at present competent and imaginative enough to make those screens come alive and make working at them a joy. Which is the *real* problem.

WORLD AND VIEWS

An interactive virtuality is essentially a



world created by a programmer or designer. This world has a certain structure which may be easy to understand or hard. This World is visible through different *views* allowed by the designer.

The World is what you're really thinking about; the view is the temporary way you're looking at it.

The distinction between World and View is crucial. The World is what the user is supposed to be acting on and thinking about; the View is all he really gets. (Controls are in a way part of the view.) If Views are good, the World comes to seem real, natural, at hand, under control. Poor Views (or worse, a hard-to envision world) create confusion and poor usability.

The system should have easy-to visualize states and conditions, and, preferably, some kind of spatial orientation that readily becomes a map in the user's mind.

The designer should begin by thinking about visualizing the *World*, not the Views, and let the Views come later.

(Yet designers are always getting seduced by particular views and treating them as the world itself.)

The principles of the World are the central, integral, virtuality; how you see it is secondary. It is important to acknowledge the cruciality of World design, and consequently the importance of the principles you develop for it.

The designer creates a simplification or stylization of the original world. There must always be some reduction or stylization; the important thing is that these reductions or stylizations not detract from the principal things you need to understand and control.

In transposing an old activity, the question is what to retain in the world and what to dismiss as part of the view. (For instance, Text Pages—divisions of text—are part of the View, not the World.)

Anything can be shown, any buttons or sticks or whatever, with any preentational machinery. People are always asking for bigger screens—but actually to ask for a bigger screen is usually a copout. Ask for higher performance. Faster flips and flaps and scrolls and panel pop-ins. Fast action and seething cues. Leave several things on the screen at once, to remind you of what you've been doing, what you might be doing, what else there is to do, and any other current options.

The operations in the user enviroment should feel more and more like operations on the world. As stated above, controls are in a sense part of a view. Anything can be controlled by almost anything, buttons or sticks or keyboards.

An interactive system should have very few controls and these few should have far-reaching and powerful uses.

Marry the available controls and the

BÄNZAI SOFTWARE

P.O. BOX 1374, ROSEBURG, OR97470

STELLAR OUTPOST

From the Black Hole come the ZYLOG RAIDERS whose mission is to destroy you. Battle it out with increasing skill until you beat the invaders (if you can). As your skill improves so does that of the raiders..... $14.95

For the man who has everything....

THE BARTENDER

Mix a Maidens Prayer, Suicide, Vodka Martini, and much more by simply asking your computer how to do it. If you want it all $14.95

STREET DRUG INDEX

A MUST for parents and teachers. The Street Drug Index is a random-access information system designed to aid you in learning what your child or student is talking about or carrying in their pockets. Perhaps the best investment you will ever make...$14.95

BANSAI, P.O.Box 1374, Roseburg,OR97470
Name _____
Address _____
City _____ State ____ Zip ____

☐ Stellar Outpost (4K) ☐ cass. ☐ 4K disk
☐ Bartender (16K) ☐ cass. ☐ 32K disk
☐ Drug Index (16K) ☐ cass. ☐ 32K disk

DISK IS $17.95 SHIPPING $1.00
AVAILABLE FOR TRS-80 ONLY

CIRCLE 150 ON READER SERVICE CARD

STOCK MARKET SUCCESS

NOW the home computer owner can have the same analytical techniques used by the TOP PROFESSIONAL MONEY MANAGERS. CYBER-TECH now offers a Stock Valuation Program based on Modern Portfolio Theory which provides logical computerized criteria for identifying undervalued stocks.

The CYBER-TECH STOCK VALUATION PROGRAM:

- Is based on a model developed by Wells Fargo Bank, an acknowledged leader in pension fund management.
- Takes the average investor out of the age of MYSTERY, MAGIC and VOODOO and into the age of SCIENCE.
- Comes with a 22-page printed INSTRUCTION MANUAL which explains the operation of the program, provides background theory and analyzes two separate stocks.
- Input data required for program operation can be obtained from investment periodicals such as Value Line Investment Survey.
- Output consists of expected DIVIDENDS, EARNINGS, GROWTH RATES, PAYOUT RATIOS, the INTERNAL RATE OF RETURN over a MULTI-YEAR PERIOD and a COMPUTERIZED RISK ADJUSTED STOCK-ATTRACTIVENESS RATING.
- Since the purchase of this program is an investment expense, the FULL PRICE of your CYBER-TECH STOCK VALUATION PROGRAM IS TAX DEDUCTIBLE

For more information send one dollar (refundable with order)
VISA OR M.C. ORDERS ARE SHIPPED THE NEXT DAY

NAME _____ TRS-80 level II (32K) ☐
ADDRESS _____ APPLE II/APPLESOFT (32K) ☐
CITY _____ CASSETTE $49.95 ☐
STATE _____ ZIP _____ DISKETTE $49.95 ☐
(CA residents add $3.00 sales tax)
SIGNATURE _____ VISA ☐ M.C. ☐ CHECK ☐
CARD NO. _____ EXP DATE _____

MAIL TO: Cyber-Tech P.O. BOX 924 CHATSWORTH, CA. 91311

CIRCLE 173 ON READER SERVICE CARD

EDU-WARE

WHO IS EDU-WARE?
WE ARE C.A.I. PROFESSIONALS FOR THE APPLE II.

IF YOU ARE AN EDUCATIONAL INSTITUTION:

Edu-Ware's primary business is the development of pre-packaged instructional software systems to be employed with the microcomputer. We challenge those who may make similar claims to match these specifications:

- A management team trained in and focused on Instructional Development.
- Programs that pre-test, specify learning objectives, provide practice, reinforce, and test for mastery learning.
- Instructional algorithms which reject incorrect responses while reinforcing those which are indicative of desired learning.
- Screen displays which capture attention and motivate interest by utilizing established principles of perception.
- Program documentation developed for both student understanding and teacher utilization.
- Programs specifically designed to provide for acquisition, learning, maintenance learning and remediation.

IF YOU ARE A TEACHER:

Edu-Ware recognizes your need for instructional materials that can make a most demanding task—teaching—easier and more effective. Our software supports you in this effort because:

- The employment of recognized, state-of-the-art, instructional methodologies maximizes attainment of teaching goals.
- Edu-Ware programs transform your computer into a powerful teaching tool, not a trivial student toy.
- Interaction with Edu-Ware systems develops student self-management of learning.

If you or your school employ an Apple Computer and have an interest in quality C.A.I., please write us for product information . . . or contact Sherwin Steffin at 213-346-6783.

EDU-WARE SERVICES, INC.
22035 Burbank Blvd., Suite 223, Woodland Hills, CA 91367

CIRCLE 164 ON READER SERVICE CARD

desired functions. Menus should be used, rather than input languages or the fictitious "natural language dialogue;" or better, yet, control diagrams.

Actions should be easily reversible and their consequences immediately recognizable so the user can back out of a mistake without being punished. (Compare this with the word-processor horror stories you hear all the time.)

Most important, the overall *principles* you choose for a system should be sweeping and have few or no exceptions. In order to clarify these issues we must consider the issues of both soft principle and soft clarity.

THE PHILOSOPHY OF SOFT PRINCIPLE

The following discussion has to do with the design of principles, which is in fact the essential issue.

incomplete. I would like to put it another way and call a principle whose implications are inexact, a *soft* principle.

This throws things in another light. Rather than suppose the soft principle is just "not finished yet," let us consider it instead *another logical category*—somehow analogous to the conventional hard principle, but not subject to deduction.

If you can't deduce, how can it be logical? The answer may be that we've been looking at the wrong features of logic and have missed the analogy. There are in a sense soft equivalents to implication, contradiction, and other logical configurations. (See table.) I hope to develop these ideas more broadly at a later time.

What good is this analysis? At the very least it is suggestive. If a principle is *by nature* soft then we can understand it on its own terms rather than insisting that it hasn't properly hardened "yet."

Or take soft design ideas. A given idea could be worked out into hard form in numerous different ways. Some you may like better than others, and a variety may be valid.

SOME FAMILIAR IDEAS SOFTENED AND RECONSIDERED

	Hard	*Soft (or mixed)*
IMPLICATIONS, RAMIFICATION	Hard Implication, Consequences	Possibility, Tendency, Expectation, Connotation
PARADOX	Contradiction	Irony, Oxymoron
COMPLICATION	Obstruction, Interference, Contervailing Principle, Something in the Way; Amendment, Modification	Things to be Clarified, Resolved Worked Out

We frequently consider something and ask ourselves: *What are the implications of this?* And one of the nice things about science and technology is that the implications tend to be clear and exact.

In many cases, though, implications tend to be less certain. Implications don't follow clearly from premises. Those who want clear-cut answers become edgy or annoyed. The main tradition of Western thought has been to try to find the exact implications of every idea. (Ideas which don't seem to have exact implications, as well as people who *prefer* unclear situations, cluster in the humanities or "fuzzy studies.")

But some things are by their nature unclear in implication. These include both cluster-concepts ("Democracy," "Womanhood") and design ideas ("Let's see, maybe it could fold back onto itself somehow").

By tradition we often tend to talk of such ideas as improperly formulated or

Now take *several* soft design ideas, all at once. How do their ramifications fit together? The answer is *indeterminate*, since the ramifications of each could take many forms. But if you are aware of this, then you can search carefully for the *combinations* of possible workings-out, their variety and their interactions.

The "inspired" design of something final and precise comes, I believe, from sifting many such co-implications of possible hardenings of the ideas.

And the important guideline is: *don't rush it*. Don't take shortcuts. Don't assume that decisively pinning down one aspect of a design will speed things up; it's like nailing your left shoe to the floor.

If we think of design as the search of many possibilites, "soft design" is that which is sensitive to unexpected simplifications, conveyances and harmonies.

In short, *don't be too sure of what you're looking for, and be ready to appreciate the ramifications of surprises.*

Principles in Practice

Eventually, the soft design principles we have tried out lovingly must be hardened into specific hard forms of computer operation. What should the principles be like? Again tradition may militate against recognizing the best design decisions.

The general principles of a system, *once chosen,* should be consistent, but "consistent" according to looser criteria than the designer may be used to. In particular, a design principle may be psychologically clear for people to work with, easily visualized or imagined, yet not reducible to any customary formalism.

Indeed, "consistency" here takes on a strong psychological flavor: a thing is consistent if users think it is consistent and use it consistently—even if we don't like it, like the double negative in Spanish. (We may call this naive consistency or soft clarity.)*

Thus the final chosen principles need not be "logical" in the rigid sense of conforming to somebody's predefined notion of how things should behave. But working out in soft form, we study their fittings-together in great detail.

The designer should eliminate any background notion that the user must be like him. All too many designers reward the user for being like himself, the designer, or punish the user for being different or thinking differently. The objective is to be of service, not to clone yourself.

TECHNICAL TRADITIONS VS. SOFT DESIGNS

The design of virtuality is essentially the design of operating principle. The design of principle, in turn, has to do with the generation and modification and inter-sculpturing of soft principles.

The biggest design problem though, is that the designer tends to freeze too quickly on a particular set of rules and arrangements. Technically-oriented people tend to seize one or two principles and hang onto them through thick and thin, not perceiving when it is time to rework their ideas.

I have learned through bitter experience, indeed, that only a small proportion of technical people are even capable of *listening* to this viewpoint. The soft design of virtuality seems to be totally alien to technical training.

* Mark Miller, who worked on the original JOT system, considers it a consistent virtuality, even though it "corresponds to no known paradigm of program structure."

GAMBIET '80

The World's No.1 Microcomputer Chess Program

Gambiet 80 was ranked as the best commercially available Chess Program at the official World Microcomputer Chess Championship in London, September 1980.

Designed and programmed by Wim Rens for the Tandy TRS80 Level II with 16K RAM

FACILITIES INCLUDE:

* 6 levels of play from speed chess to tournament level
* Graphic board display
* Chess Clock
* Game record in standard notation on the screen and optionally on a printer
* Board set up for solution of chess problems
* 'Take-back' facility
* Continual display of moves being evaluated by the program
* Mate anticipation

CIRCLE 233 ON READER SERVICE CARD

microtrend

Here's your opportunity to order Gambiet '80 for only $39.95 ea.

Visa Card # _____

Mastercharge # _____

Check enclosed for $ _____

Please send my copy of Gambiet '80 to:

Name _____

Address _____

City/State _____

Zip _____ Phone _____

*Kentucky residents call collect 502/491-9827 8:15 to 5:15 EST

Mail orders to:
Microtrend
1900 Plantside Dr.
Louisville, KY
40299
or
Call Toll-Free
1-800-626-6268

Virtuality, cont'd...

Those who design interactive systems tend to be technically trained, and technical training generally promotes the background assumption that what you are working on is given and well-defined.

Training in the arts and creative fields, on the other hand, promotes the ideas that a design (or piece of writing or a movie) is fluid, may take many forms, and will be reworked over and over until it reaches a final state that may be wholly unlike its earlier stages. I believe this latter outlook is far more appropriate for the design of interactive systems.

CONCLUSION

Interactive system design is a field in itself, utterly unlike what is taught in any computer science department I know of. If I have not proved this point, I hope the designs and ideas presented here will at least provoke some unease.

(This is no claim that these designs are righter than any others; but rather that these designs are a unified package that feels right and is therefore of interest. They represent local peaks in design space, in the sense that small changes would, I think, detract from their unity and clarity.)

These designs represent hundreds of hours of work, but the difficulties of the decisions and the rough edges don't show. (That's part of good design and art).

The art of designing things in general is very little understood. People think that something is well-designed if it is *sleek*, *stylistically unified*, and *if its controls look as much alike as possible*. (An example is the "designer" audio equipment from Bang and Olufsen, show at the Museum of Modern Art and copied everywhere, where every control resembles every other control.)

This approach is wrongheaded beyond belief. (I think stereo equipment is poorly designed, and B&O the worst of them.) You do not want controls that look alike. You want controls that look and feel *different*. If you have a big round knob for the volume control, you should have a square knob, or a slider, for the tuning. There should not be a row of similar buttons for different functions, but a row of *different* buttons—or better, not in rows, but some other arrangement contrastively arrayed. Do you need glasses to read what it says above the knobs? Lousy. Can you tell at a glance one control from another? Good. CAN YOU WORK IT IN THE DARK? Terrific.

As a rough guide, *good design is inversely proportional to the probability of a user making a mistake*. And this criteria carries over to interactive computer systems.

To make a system easy to use is extremely difficult and time consuming, in the same way that it takes more work to write a short article than a long one.

You should not "design the system" first, and then put on a "friendly front end", (although this is what must be done in many cases), any more than you should first shoot a movie and decide what it is to be about (although this occasionally works).

An interactive system should become second nature, and become second nature quickly. This is essential for many reasons. One is that we will have to move among many different interactive systems in the future, and there will be no time to savor and adapt to the local complications of each. They will have to spring clearly and straighforwardly at the mind and hand.

Moreover, interactive systems will be used intensely for hours, often by tired, high-strung, frantic people, who are trying to get a job done in a hurry, and who are thinking only of the world they are trying to operate in—not the intervening complications. It is up to us as designers to create fast, safe, elegant systems of view and operation without snags, dangers or complications.

The system designer, or movie director—let's call him *you* —must have a full understanding of what things are easy to do, what things are not, and what is hopelessly impossible. You then make a collection of all the ideas and visualizations (and scraps and parts) you would like to put together in your system. Then your rework them and rework them, and rework them.

THINK OUT THE WORLD

—Its many views and aspects; it s *real* nature (unlike what has been thought of as its nature);

IMAGINE ALL THE CONTROLS AND PRESENTATIONS YOU'D LIKE TO HAVE,
REDUCE THE CONTROLS
AND PRESENTATIONS
TO AN ADEQUATE,
POWERFUL,
EASY-TO-UNDERSTAND SET:

MARRY THEM TO THE AVAILABLE SCREENS, KEYBOARDS AND POINTING TOOLS.

ABOVE ALL, DESIGN THE FULLEST SYSTEM FIRST—THEN CUT IT DOWN, IF YOU HAVE TO. YOU MAY FIND YOU DON'T HAVE TO.

That this is nowhere taught is much worse than regrettable. Because unfortunately the salaried programmer has, in effect, a license to inflict on innocent users anything he likes under the pretense of technical necessity or on the basis of some off-the cuff (or cufflink consultant's) assessment of "user needs."

I regard the decisions involved in designs like those as intricate and interdependent as moves in chess. This kind of design needs a respect and even reverence for the far-flung ramifications of tiny decisions, and the staggering complexity of making things simple.

I hope I have given a sense of this style of design.

I hope, too, that the reader will see it as an art form—somewhere between movies, diagramatics, the design of machinery, the design of games, and the building of philosophical systems.

When done well, it is done with simplicity, consistency, conceptual clarity and vividness. This is not "technical" work in any usual sense. I consider it a form of design and a form of art.

I believe that interactive design is, more than anything else, what the computer field is really about. I find it monstrous and appalling that these general principles are so little understood; that despite all the pompous "computer science curricula," nobody teaches these anywhere; and that innocent customers who want an easy-to-use system—really, is it too much to ask?—are too often led by consultants and tekkies down a primrose path to endless horrors of complication and unnecessary claptrap.

How you feel about all this depends on what you think computers are all about and where the world should be going.

If you want to show off to your family and friends—or financial backers—as a macho master of complicated technicalities, then you don't *want* things to be easily comprehensible. (In that case you should be reading certain other personal computer magazines.

But if you believe that somewhere beyond all the technicalities lies some kind of hope for a better future and a smarter mankind, rich in ideas and knowledge and dreams—as well as gadgets—then the question is how to front-end the gadgets so that they bring us knowledge, and ideas, and dreams, without the technicalities being in the way. □

CRAE 2.0

A fast co-resident Applesoft editor for Applesoft programmers. Now perform global CHANGES & FINDS to anything in your program (no restrictions on the global CHANGE & FIND).

QUOTE (copy a range of lines from one part of your program to another.

A powerful RENUMBER that is 5 times faster than other renumbers. A single line MODIFY insert/delete mode. AUTO line numbering. Formatted memory DUMP to aid in debugging. APPEND ability.

A total of 15 commands in all
Crae need be loaded only once and changes your program in memory. 48K RAM, APPLE II or PLUS, APPLESOFT ROM, and disk.

****

MCAT 2.0

MCAT 2.0 IS A FAST BINARY UTILITY WHICH CREATES A SORTED MASTER CATALOG WHICH IS SAVED ON DISK AS A BINARY FILE (FAST). THE MASTER CATALOG CAN BE EASILY UPDATED A WHOLE DISKETTE AT A TIME (ADD, DELETE, REPLACE). LIST/PRINT HAVE GLOBAL SEARCH CAPABILITY AND ONE OR TWO COLUMNS. PROVISIONS FOR DUPLICATE VOLUME NUMBERS. APPROXIMATELY 1200 FILE NAMES, 48K OR 32K, 13 OR 16 SECTORS DOS SUPPORTED.

CRAE on disk with 20 page manual	MCAT on disk with 10 page manual	CRAE and MCAT on one disk
$24.95	**$19.95**	**$39.95 with manuals**

****

The TARTURIAN/WIZARD II

THE TARTURIAN requires 48K RAM, APPLESOFT ROM, and disk. As you explore the 160 rooms (each done in HI-RES) gathering weapons and treasure that will prepare you for the final battle against the TARTURIAN, you will encounter deadly KROLLS, battle the MINOTAUR, try and get by COUNT SNOOTT-WEEKER, decipher the YUMMY YAKKY'S secret, make friends with the TULIE-SWEEP, avoid GHOULS, explore the PILLAR tombs, discover secret passages and more. 5 interlocking programs.

TARTURIAN on disk $24.95

SEE YOUR LOCAL DEALER OR SEND CHECKS TO

HIGHLANDS COMPUTER SERVICES

14422 S.E. 132nd
Renton, Washington 98055
(206) 228-6691

Washington residents add 5.3% sales tax. Applesoft and Apple are registered trademarks of Apple Computers, Inc.

CIRCLE 215 ON READER SERVICE CARD

Interview with Clive Sinclair

David Ahl

Clive Sinclair is the man behind the first mass pocket calculator, the first scientific calculator kit and, now, a mass-market computer. I talked to Clive while in London at the PCW show.

Ahl: How did you get started in the electronics business?

Sinclair: I started in 1962 when I first came to Sinclair Radionics. We were in the kit business with hi fi systems and pocket calculators, (we made the first pocket calculator which is on display in the Museum of Modern Art in New York). From there we went into digital watches and TV sets and for a while we were linked with a government body in the U.K. At this point I left, as this arrangement did not work out too well. I took the same people with me and reformed the company as Sinclair Research Ltd. and launched the personal computer.

Ahl: Does Sinclair Radionics and its products still exist?

Sinclair: Only as a legal entity, but it doesn't trade.

Ahl: So effectively today your main product is ZX80?

Sinclair: That's right, but it's not our main research program. Our biggest research/development program is on flat screen television.

Ahl: Have you shown that at all? Or proved its capability?

Sinclair: Yes we have. We are at the stage where we have demonstrated it and will be doing so again later this year. We have pilot production and hope to shortly be at the next stage.

Ahl: What type of technology is used?

Sinclair: It is a flat screen Cathode Ray Tube.

See a review of the Sinclair ZX-80 on page 28.

Ahl: Does it have electron guns?

Sinclair: It has a conventional electron gun, but instead of the beam following a straight path, it bends to a right angle and it splits the screen.

Ahl: Is it monochrome or could it be color?

Sinclair: It is monochrome today, but eventually it will be color. We will pursue that.

Ahl: That sounds very interesting. Sharp had shown one about two years ago which provoked much interest in the electronics community but nothing ever came of it. Today it doesn't look like they are any closer to a commercial product than two years ago.

The philosophy of the company is very clear—to lead in technology.

Sinclair: What Sharp showed was an early development model of vertical projection, which, novel as it was, was a long way from a commercial product. But that is not the case with ours. Ours gives a picture which is not simply as good as a conventional Cathode Ray Tube, but it is better, and all the snags have been ironed out.

Ahl: Do you anticipate that the price of this will be competitive with the existing technology?

Sinclair: Absolutely. There is no way we would introduce something which cost more than existing technology. Not only does this have more feature advantages, it has price advantages over conventional technology. But in order to achieve this and because conventional tubes are made in such vast numbers, the only way it can be competitive is to have very large scale production. That is why it will take quite some time before the tube emerges.

Ahl: About the ZX80; how long has that been in development?

Sinclair: It started in March 1979 and it was put on the market in February 1980.

Ahl: How many people were involved? It seems to be quite a breakthrough on many fronts. Did you have simultaneous projects going on to bring it to fruition? Or was it mainly you, or a small team of people?

Sinclair: There were very few people involved really. I had the original idea and some of the system ideas. Then there were about two or three engineers who were involved in the detail and design; one engineer in particular did the final design and one wrote the software.

Ahl: Some people look at it and conclude that it is no more than a larger computer scaled down to smaller dimensions, while others will look at it and think of it as one of those language translators with a little more capability. From glancing at the specifications and seeing it at the Consumer Electronics Show, I have the impression that it has much more capability than that and that it does not seem to be just a scaled down computer. What is your concept? How do you view the machine?

Sinclair: While the ZX80 is a true computer in every sense, without any inherent limitations, it obviously was restricted in performance in its minimum configuration. We wanted to sell at as low a price as we possibly could, a computer upon which people could start to learn, really seriously, how to break into computers and how to really learn what computers were about. Now that might be an end in itself for many of them, but these may be executives who want to understand computing so when they buy computers for their firms or talk to people about the use of computers in their firms, they do so from a knowledgeable standpoint and they don't feel awed by it. Equally, we see it as a very powerful aid for students wanting to

NOW.

A satire of the sensational Interlude* program!

A way to get more **involved** with your computer than ever before!

A program with an answer to "Have a nice day!"

There's a subtle revolution sweeping the nation. A new wave elevating the human condition from the mundane to the cosmic. Now, Clone Software brings you back down to Earth with:

Encounter

It's more than just a game. It's an adult comedy. It's a parody, a satire—it's the penultimate experience!

A computer interview determines your romantic mood. Then the computer selects a "Lewd" — a personalized surprise suggestion for your enjoyment. There's no "manual" to reveal the suggestions in advance — every Lewd is buried in the program, awaiting the proper moment.

But that's not all. You can even Enter your own Lewds! Place your wildest desires in the computer! Surprise your mate.

Order today, and you'll also get a hearty program that interrogates your innermost appetites and then selects the perfect pizza to satisfy you — at no extra charge.

For an Apple II† or an Apple II-Plus† with 48K and Disk. Send your name and address, and $14.95 (plus $1.50 for shipping, Colorado residents add 90¢ tax) to: Clone Software, 1446 Estes St., Lakewood, CO 80215.

clone clone software

1446 estes st., lakewood, co 80215, 303 234-0630

Dealer Inquiries Invited
(303) 234-0630

*Interlude is a trademark of Syntonic Software.

†Apple II and Apple II-Plus are trademarks of Apple Computer Inc.

A CREATION OF COMPUTER HEADWARE

WHATSIT?™

(Wow! How'd All That Stuff get In There?)

A sophisticated, self-indexing filing system—flexible, infinitely useful and easy to use, that adapts to your needs.

WHATSIT's unique capabilities:

***Multiple Entries** allowed per field: For example, a bibliographic file can associate each work with any number of authors. WHATSIT allocates file space as needed for each.*

***New Data Fields** added "on the fly": You're not confined to a particular "record layout" that must be declared in advance. Your file evolves to fit your needs.*

***Immediate Response:** Even in the largest files, WHATSIT responds in seconds, thanks to pointer linkages and hash coding.*

***Conversational Dialogue:** Query and update requests may be intermixed in any order, without returning to a "menu selector."*

NEW
Apple II Plus WHATSIT at special introductory price:
$95

(Regular price, $150 after December 31, 1980).

WHATSIT comes ready to run on your Apple, Apple II Plus, AlpaMicro NorthStar, or CP/M computer. See your dealer for a full demonstration . . . or write or call:

HARDHAT Software

P.O. Box 14815 • San Francisco, CA 94114 • Tel: (415) 621-2106

CIRCLE 197 ON READER SERVICE CARD

JOIN THE GALAXY'S TOP GAME PLAYERS! WORK OUT AT BRØDERBUND!

STRATEGIC EXERCISES
The Galactic Trilogy

These first three games in the Galactic Saga put you in the commander's seat with complete graphics giving you all the information you need.

1. Galactic Empire
The Problem — unite the Galaxy of 20 worlds under a single flag, starting from a single world neither large nor powerful. The Challenge — Time and distance are real; if you don't get troops and material to the right place at the proper time they will do you no good. The solution — Scouting, planning, a head for logistics and picking your targets are the ingredients for your success!

2. Galactic Trader
Relieved of your command in peacetime, you are forced to become a trader to survive. Use your bartering ability and knowledge of the galaxy to outwit the sharpest business creatures in the galaxy. 10 levels of difficulty so you never outgrow the game!

3. Galactic Revolution
Pit your skill at manipulation against the Emperor as you compete for the allegiance of the various power groups whose help you need to wage the Galactic Revolution! For 1 to 3 players.

TRS-80, L2, 16K cassette $14.95 per game.
APPLE II Plus, 48K, disk with complete hi-res graphics and sound $24.95 per game.

FAST ACTION FROM JAPAN

HYPER HEAD ON — You'll need to be quick to maneuver your car around the course without letting the computer's car(s) smash you head on. The fastest action available for the APPLE. If your Head On doesn't say "Hyper" you're driving a horse and buggy. Four skill levels. Uses keyboard or joystick. Integer or Applesoft 32K disk, $24.95.

GALAXY WARS — Full color graphics and machine language sound effects and action make this an eerie challenge for you pilots anxious to maneuver your rocket through enemy fire and space fish to destroy enemy saucers. Each game is deadlier with surprises at advanced levels of play. Integer or Applesoft 32K disk, $24.95.

How to order: Ask your dealer or send check or money order for the exact retail price to:

Brøderbund Software
Box 3266, Eugene, Oregon 97403

Call (503) 343-9024 to order. NO CHARGE FOR SHIPPING AND HANDLING!
Visa and Mastercard accepted.

We've got more! Send for our free catalog!

CIRCLE 129 ON READER SERVICE CARD

learn computing. But at the same time it is expandable. We have just announced a Basic for it — which is more of a professional Basic than the original one and a 16K byte RAM pack for it at a very keen price, (around $100), so that it can be taken from the basic configuration to a really very powerful system at a very low cost. Hence our price will be somewhere around half the conventional competitions. I would make the point that in order to do this we have done everything in-house, i.e., in the way of anything having to be specially done we had to write our own Basic because we wanted to achieve performance in the Basic as it wasn't available on the existing Basics.

Ahl: Is that Basic compatible with Micro-Soft Basic or some other Basic on the market or has it got a lot of bells and whistles that make it incompatible with others?



Sinclair: It is not compatible. It is our own. We had to take that step in order to achieve the bells and whistles that you mentioned and have those features that we feel are important to our customers. In order to hit our cost goal we had to do a better packing job than had been done before. The ROM in our basic machine is just 4K bytes which contains everything — Basic, operating system, keyboard control and display I/O. Now there is no way we could have done all that with an off-the-shelf Basic. Furthermore, we then pack data into the RAM at least four times as tightly as anyone else. We would not have been able to do that unless we had our own Basic. Another thing that we wanted was keyword entries. You may have noticed that by pressing a certain key a keyword is entered. So there is very little for a non-typist to do. A lot of people are put off in the learning stages with having to type PRINT every time and abbreviations can be misleading. We felt this was very crucial and it is not included in standard Basics, so we had to choose to go away from the existing patterns.

Ahl: Pertaining to the marketing of the ZX80, do you anticipate selling it through computer stores, department stores, or other types of outlets or through direct-mail as you have done with some of your other products?

Sinclair: We are going to sell the computer by direct-mail in England and the U.S. There may come a time when store distribution is possible, but you can't really distribute to a store until you have a much better informed public. A very large mail-order campaign may help do that, so it may be possible later to distribute to stores.

Ahl: Many people buying computers today, particularly at this price level, are concerned with where or who can they go back to for service, particularly if they buy a machine by direct-mail.

Sinclair: There are two points there: the first involves the product, the second is who to come back to for service. We have a permanent office in the States and we stand behind our product at all times. We haven't seen anything but 1% or under 1% failure rate in the field in the U.K. It is a very reliable product so we haven't got a serious problem. We operate with service contract houses and this is all part of the guarantee of the product.

Ahl: Jumping back to the technical aspect of the ZX80, it appears that although now that it is designed for a power supply to be plugged into standard power, it could probably be battery operated and completely portable. Is this in your plans?

Sinclair: Yes it is. It has a very low power consumption and could certainly run for a reasonable time on batteries. Of course you need a battery T.V. set as well.

Ahl: What about other peripherals, floppy disk, mass storage, printers etc.? Are they in the works?

Sinclair: Yes they are, we have a floppy disk coming in about a month; the other items should be out the middle of next year.

Ahl: How do you feel about other alternative forms of mass storage? Some people have said that the bubble memory is coming down in price fast enough that it may in two or three years replace the floppy disk as a mass storage device. Do you think that's likely to happen?

Sinclair: The price projections we see from manufacturers over the next two or three years don't suggest that to me.

Ahl: What else would you like the world to know about you, the product, philosophy etc?

Sinclair: The philosophy of the company is very clear — to lead in technology. We've got a good start in this field and we plan to take as good a lead as we can. Some of the things we are developing, such as the flat TV screen, a truly portable system, etc. are coming along too. Clearly we think these are things we can do. □

The first personal computer for under $200.

The Sinclair ZX80. A complete computer—only $199.95 *plus $5.00 shipping.*

Now, for just $199.95, you can get a complete, powerful, full-function computer, matching or surpassing other personal computers costing several times more.

It's the Sinclair ZX80, the computer that independent tests prove is faster than all previous personal computers. The computer that "Personal Computer World" gave 5 stars for 'excellent value.'

The ZX80 cuts away computer jargon and mystique. It takes you straight into BASIC, the most common, easy-to-use computer language.

You simply take it out of the box, connect it to your TV, and turn it on. And if you want, you can use an ordinary cassette recorder to store programs. With the manual in your hand, you'll be running programs in an hour. Within a week, you'll be writing complex programs with confidence.

All for under $200.

Sophisticated design makes the ZX80 easy to learn, easy to use.

We've packed the conventional computer onto fewer, more powerful LSI chips—including the Z80A microprocessor, the faster version of the famous Z80. This makes the ZX80 the world's first truly portable computer (6½" x 8½" x 1½" and a mere 12 oz.). The ZX80 also features a touch sensitive, wipe-clean keyboard and a 32-character by 24-line display.

Yet, with all this power, the ZX80 is easy to use, even for beginners.

Your course in computing.

The ZX80 comes complete with its own 128-page guide to computing. The manual is perfect for both novice and expert. For every chapter of theory, there's a chapter of practice. So you learn by doing—not just by reading. It makes learning easy, exciting and enjoyable.

The ZX80's advanced design features.

Sinclair's 4K integer BASIC has performance features you'd expect only on much larger and more expensive computers. These include:

- Unique 'one touch' entry. Key words (RUN, PRINT, LIST, etc.) have their own single-key entry and are stored as a single character to reduce typing and save memory space.
- Automatic error detection. A cursor identifies errors immediately to prevent entering programs with faults.
- Powerful text editing facilities.
- Also programmable in machine code.
- Excellent string handling capability—up to 26 string variables of any length.
- Graphics, with 22 standard symbols.
- Built-in random number generator for games and simulations.

Sinclair's BASIC places no arbitrary restrictions on you—with many other flexible features, such as variable names of any length.

And the computer that can do so much for you now will do even more in the future. Options will include expansion of 1K user memory to 16K, a plug-in 8K floating-point BASIC chip, applications software, and other peripherals.

Order your ZX80 now!

The ZX80 is available only by mail from Sinclair, a leading manufacturer of consumer electronics worldwide. We've already sold tens of thousands of units in Europe, so demand will be great.

To order by mail, use the coupon below. But for fastest delivery, order by phone and charge to your Master Charge or VISA. The ZX80 is backed by a 30-day money-back guarantee, a 90-day limited warranty with a national service-by-mail facility, and extended service contracts are available for a minimal charge.

Price includes TV and cassette connectors, AC adaptor, and 128-page manual.

All you need to use your ZX80 is a standard TV (color or black and white). The ZX80 comes complete with connectors that easily hook up to the antenna terminals of your TV. Also included is a connector for a portable cassette recorder, if you choose to store programs. (You use an ordinary blank cassette.)

The ZX80 is a family learning aid. Children 10 and above will quickly understand the principles of computing—and have fun learning.

Phone orders only: (203) 265-9171. We'll refund the cost of your call.
Information: General and technical—(617) 367-1988, 367-1909, 367-1898, 367-2555. Phones open Monday-Friday from 8 AM to 8 PM EST.

sinclair **Sinclair Research Ltd., 475 Main St., P.O. Box 3027, Wallingford, CT 06492.**

CC-12-0

To: **Sinclair Research Ltd., 475 Main St., P.O. Box 3027, Wallingford, CT 06492.**

Please send me _____ ZX80 personal computer(s) at $199.95* each (US dollars), plus $5 shipping. (Your ZX80 may be tax deductible.)
I enclose a check/money order payable to Sinclair Research Ltd. for $_____.

Name _____

Address _____

City _____ State _____ Zip _____

Occupation: _____ Age: _____

Intended use of ZX80: _____

Have you ever used a computer? ☐ Yes ☐ No.
Do you own another personal computer? ☐ Yes ☐ No. *For Conn. deliveries, add sales tax.

SUPER

Now With Multi-Key Capabilities For Apple & Pet

Since KRAM™ was introduced in 1979 it has fast become known as the users. Now, after hundreds of requests we have added MULTI-KEY,

IBM/370 users have VSAM (Virtual Storage Access Method) to provide fast, flexible keyed-access to their data. Now SUPER KRAM (Keyed Random Access Method), from United Software of America, gives Apple and Pet users the same flexibility, substantially increasing the processing power of the Apple and Pet.

Until SUPER KRAM the only "random access" capability in the Apple and Pet consisted of a crude form of "relative record" processing. While this is usable for very simple applications, it falls far short of the needs of today's business and analytical applications. Using SUPER KRAM records may be processed by any one of multiple "Key" values, which may consist of any kind of data: numbers, letters, special characters, etc. Even Apples's long-awaited DOS 3.3 doesn't have anything like this!!

KRAM™ 2.0 Regular Features

- Written in 6502 machine code Basic compatible
- Create/Open a dataset
- Put record by key
- Add & delete records by key
- Get any record by Full/Partial key
- Access by any key in as little as .2 sec. (.1 sec. with Corvus disk)
- Supports multiple disks
- Read next or previous record
- Dynamic space allocation
- Dynamic space reclamation
- Dynamic index compression
- Files never need reorganization
- Compatible with language systems

KRAM™ 2.0 Only $99.95

APPLE / ATARI

"Precise, humanized, well documented an excellent value" are the applauds being given

3-D ANIMATED COLOR GRAPHICS



APPLE WORLD by Paul Lutus

The Program made famous on National TV!

Written in machine code.

APPLE WORLD turns your Apple into a sophisticated graphics system capable of creating animated three-dimensional color images, projecting them in true perspective on the screen, rotate them, move them closer, further away, and many other exciting and imaginative things.

Draws objects with 65,000 points per side.

A powerful screen-oriented text editor is included to facilitate image formation. This program was recently featured on Tom Snyder's Prime Time Saturday TV Show and is now available for sale.

APPLE WORLD'S powerful editor is so easy to use that children will love it. You can now "sketch" your dream house, boat, car, or fantasy empire. Then view it as it would be seen from 10,000 feet, or you can ZOOM in until the screen is filled with a doorknob. You could then go inside and move from room to room examining furniture placement as your screen rotates within the room. Images or specific parts of images can easily be saved to disk or printer

Does all this sound like science fiction? You won't think so after you have visited **Apple World.**

Introductory Price $59.95

36 page manual included

For 48K Apple II or Plus with Disk

Look for the RED-WHITE-BLUE United Software Display at your local computer dealer, or send check or moneyorder, plus $3.00 shipping to:

USA UNITED SOFTWARE OF AMERICA

750 3RD Avenue,
New York NY 10017
(212) 682-0347 ***Telex 640055***

DEALER INQUIRIES INVITED

KRAM is a trade mark of United Software of America.

KRAM™

By Ken Germann

You've Asked For It, Now You Got It!

quickest and most powerful access method for serious Apple and Pet MULTI-INDEX, functions, as well as increasing processing speed.

SUPER KRAM'S™ Added Features

- MULTIKEY SUPPORT — Allowing simultaneous access to a KRAM file by more than one key field.
- HI-SPEED READ — This feature allows increased I/O speed up to 60% faster during processing of SUPER KRAM read next, read previous, put and delete requests.
- IMPROVED INDEX ARCHITECTURE — Allowing faster index searchers and more efficient disk space utilization.
- INTEGRATED BASIC COMMANDS — Allowing SUPER KRAMTM commands to be coded in-line with Basic, providing easier usage of KRAM than ever before.
- USER-SPECIFIABLE BUFFER POOL — Allowing the user to specify how many KRAM files are allowed open at one time; will support any number of KRAM files.
- LOGICAL RECORDS (KEYS MAY BE NON-UNIQUE) — Records added to the KRAM files are immediately accessible by any of the defined keys for the file (Automatic Upgrade).
- KRAM 2.0 files are totally compatible with SUPER KRAM

Requirements

Apple & Pet requirements - KRAM 2.0 and SUPER KRAM are designed to work with both Apple II's, Disk II, and Corvus Systems 10 Megabyte Winchester Disk, and Commodore's 2040, 3040, and 8050 Disk units. KRAM 2.0 and SUPER KRAM require 32K/48K Apple and a least on disk drive. (KRAM 2.0 requires Integer Basic in ROM). KRAM and SUPER KRAM work on any 40/80 column 16K/32K Pet.

SUPER KRAM™ Only $175

BREAKTHROUGHS

these sophisticated programs des... to meet the stringent needs of individuals and business professionals.

NEW 3-D ... GRAPHICS

...MENT SYSTEM IN COLOR

by Paul ...

W...





FOR COMMODORE 16K/32K COMPUTERS

DATABASE MANAGEMENT SYSTEM — A comprehensive, interactive system like those run on mainframes! Six modules comprising 42K of programming allow you to; create, edit, delete, display, print, sort, merge, etc., etc. - databases of up to 10,000 records. Printer routines automatically generate reports and labels on demand. **60** pages of concise documentation are included. Requirements - 16-32K PET and 2040 Dual Disk (printer optional) ..... **COST $125**

OTHER SOFTWARE

APPLE COMPUTERS

Super Space Wars	$ 9.95
States & Capitals	9.95
Moving Point Average	19.95
...tock Options	24.95
...hance	12.95
...ds	12.95

...COMMODORE PET

...ptions	24.95
	12.95
Stock Analyzer	22.95
Mortgage	14.95
Space Intruders ("Best Game of 1979")	$19.95
Jury/Hostage	9.95
Kentucky Derby/Roulette	9.95
Alien I.Q./Tank	9.95
Tunnelvision/Maze Chase	14.95
Submarine Attack	9.95
Battle of Midway	7.95
Laser Tank Battle	9.95
Swarm	14.95
Baseball	9.95
Super Startrek	14.95



The Legal Protection of Computer Programs

Ross Olmstead

The ownership rights associated with computer programs and data bases should be afforded the same legal protection as is available to other kinds of creative ideas and expressions. Although there are few people who would disagree with this statement, there has been considerable disagreement as to how it should be done. Over the decades, different laws have been developed to protect different kinds of creative works. But computer software is not quite like anything that preceded it. On the one hand, a software package may be thought of as a work of authorship. On the other hand, it is functionally mechanistic. Things are further complicated by the fact that it has become remarkably easy to quickly copy large amounts of information. Of course, the easier it is to reproduce a protected work, the harder it is to protect it.

The confusion and disagreement among those caught up in the necessity of applying old laws to new phenomena was brought into focus during the seventies as Congress attempted to overhaul the 1909 copyright laws. Although a new Copyright Act was finally passed in the fall of 1976 (effective January 1, 1978), Congress decided that the implications of data processing and reproduction technology had to be further clarified before they could be properly reflected in the new law. In order to allow for this they did two things. They inserted a stop-gap paragraph pertaining to computers in the new law, and they created a commission to further study the issues. The paragraph reads:

#117. *Scope of exclusive right: Use in conjunction with computers and similar information systems.*

Notwithstanding the provisions of sections 106 through 116 and 118, this title does not afford to the owner of copyright in a work any greater or lesser rights with respect to the use of the work in conjunction with automatic systems capable of storing, processing, retrieving, or transforming information, or in conjunction with any similar device, machine, or process, than those afforded to works under the law, whether title 17 or the common law or statutes of a State, in effect on December 31, 1977, as held applicable and construed by a court in an action brought under this title.

Section 117 is a holding action which indicates that old laws, as inadequate as they may be, still pertain.

The National Commission on New Technological Uses of Copyrighted Works (CONTU) was first convened in 1975 and issued its *Final Report* in 1978.[1] In addressing the copyright problems of data processing, CONTU examined the various existing laws that could presumably be used to protect data bases and software, and recommended changes in the new copyright law to reflect their findings. My discussion of the issues involved is based largely on the CONTU reports.

The confusion and disagreement among those caught up in the necessity of applying old laws to new phenomena was brought into focus during the seventies.

There are four specific areas of law that have been perceived as available for the general proprietary protection of computer data bases or software. These are trade secrecy, unfair competition, patent and copyright.

Trade Secrecy

The laws of trade secrecy are administered by the States and vary somewhat from state to state, thus resulting in a la[...] of uniformity and in varied inte[...] tions. The common purpose [...]

therefore be afforded legal protection. A person who, without authorization, appropriates or reveals a trade secret is guilty of theft. As CONTU points out, however, trade secrecy is hostile to the free exchange and dissemination of ideas, and is inappropriate with respect to general purpose computer programs or data bases having a potentially wide-scale commercial distribution. The maintenance of trade secrecy requires stringent security and, once the secret is disclosed, protection becomes generally unenforceable. The wider the distribution of a specific computer program, the more expensive and difficult, if not impossible, it becomes to keep the program a secret, especially since the nature of a computer program is usually obvious to the trained observer. Furthermore, the remedies against illegal appropriation are limited. Generally speaking, there is only a oneshot remedy because, once disclosed, the program will cease to be a secret. If the owner decides to bring suit, the necessity of proving the validity of a trade secret may be expensive and difficult, often involving the retention of expert witnesses. And, of course, secrecy may be lost when a secret is introduced as evidence, becoming part of the public record of the trial.

Unfair Competition

The common law doctrine of unfair competition is also part of State law and is thus subject to the same lack of uni[...] mity as trade secrecy. The law, [...] eral, is based on the princip[...] unfair to appropriate a co[...] expenditure, and lab[...] such properties [...] ple, obtainin[...] gram an[...] when [...]



The Ultimate Application Development System

Nothing can compete with the brain when it comes to information storage capacity and speed of data entry and recall — but we're working at it.

Our **SELECTOR-IV™** data base management system will let your microcomputer operate with the flexibility available (up to now) only on larger systems. You can create, maintain and report on files limited in size only by your *CP/M™ compatible operating system or disk storage capacity.

The basis of the power of **SELECTOR-IV™** is our unique method of cross-indexing the information in your files. You can immediately recall records by the contents of any piece of information required — from account numbers to ZIP codes to the date of your last audit. You can update records, individually or all at once. You can create new, uniquely, selected sub-files from existing ones (in the same or a different format), and perform computations in the process. You can define procedures to generate computed invoices, personalized letters, or gummed labels with the information coming from several files at once, and invoke them whenever needed. You can add new items to a record definition and change or delete them at will.

We've come a long way since we released the first information management system in microcomputers. We've listened to your suggestions and incorporated the best of them. We've built screen editing functions into the system which make operating the system as convenient as possible. We've had **SELECTOR-IV's™** documentation produced by our experts emphasizing its use for the novice, the applications developer, as well as, the retailer. Our applications specialists can provide you with a "turnkey" **SELECTOR-TV™** system customized for virtually any requirement.

With **SELECTOR-IV™** and a good word processor program, chances are you won't need any other software.



Look for SELECTOR-IV™ at your local computer retailer, or call:

MICRO•AP, INC.
9807 Davona Dr.
San Ramon, CA 94583
(415) 828-6697

MICRO•AP

*CP/M is a registered trademark of Digital Research.

CIRCLE 154 ON READER SERVICE CARD

Protection, cont'd...

mote the progress of science and useful arts, by securing for limited times to authors and inventors the exclusive rights to their respective writings and discoveries (Article I, Section 8)." Congress has exercised this power by enacting patent and copyright laws, both of which have some advantage over trade secrecy and unfair competition in that infringers are more likely to be persuaded to comply without the institution of a lawsuit. If a lawsuit does arise, trade secrecy laws require that the plaintiff prove the validity of the secret. In patent cases there is a presumption of validity, and in copyright actions a registration certificate is direct evidence of copyright's validity.

Computer software is not quite like anything that preceded it.

Patent

Patent law is set forth in Title 35 of the United States Code. It affords strong protection, for a period of seventeen years, to demonstrably useful, novel, and nonbvious inventions. Whereas copyright is designed to protect the "expression" of an idea or process, patent is designed to protect inventions, which are ideas or processes in themselves. Although there have been patents awarded to software, the rigid standards of novelty and nonobviousness would seem to preclude the awarding of patents in most cases. furthermore, the availability of patent protection to software is now unclear. The U.S. Supreme Court has found computer programs to be ineligible for patent protection in two cases. In November of 1972, in *Gottschalk v. Benson* (409 U.S. 63), the Supreme Court

"held that (a) computer program (is) a mathematical formula without substantial practical application except in connection with (a) digital computer (and) was not a patentable process."

In *Dann v. Johnston* (425 U.S. 219), a patent was sought for software which provided a bank with automatic record keeping of bank checks and deposits, and produced specialized account transaction records for the bank's customers. In March 1976, the Supreme Court decided that the software in question "would ... have been obvious to one 'reasonably skilled in (the applicable) art'"and was, therefore, unpatentable. This last decision emphasizes the potential difficulty in meeting the patent law's test of nonobviousness.

Copyright

A clear case can be made for considering computer programs and data bases as works of authorship, and thus qualified for copyright protection. The 1976 Copyright Act provides protection for

"original works of authorship fixed in any tangible medium of expression, now know or later developed, from which they can be perceived, reproduced, or otherwise communicated, either directly or with the aid of a machine or device (Section 102 (a)."

Works that can be communicated only with the aid of a computer are thus within the copyright law's scope of protection.

In 1964, the Register of Copyrights agreed to accept computer programs for registration provided that 1) they contained sufficient original authorship, 2) they had been published, and 3) copies submitted for registration were in human-readable form.

Point number 1 is still a valid requirement for two reasons. Very simple and obvious programs are not only lacking in originality, but may well be the only means by which to accomplish a given task. Such very basic programs are then closer to "ideas" than "expressions," and, as stated earlier, copyright protection is available only to expressions. Point number 2, publication, is not required by the new Copyright Act, but both publication and registration provide some extra margin of protection. Firstly, they provide a public record of ownership in the event of copyright violation. And secondly, they may entitle the copyright owner to an award of statutory damages and attorney's fees, remedies not otherwise available. Point number 3 has been a bone of contention and requires some background discussion.

In 1908, the Supreme Court held that a piano roll was not a "copy" of music because it was not, for most purposes, human-readable. *(White-Smith Music Publishing Co. v. Apollo Co.*, 209 U.S. 1). For similar reasons, it has been argued that a program in object code lacks communicative potential and might therefore be constitutionally uncopyrightable. But, as CONTU points out, copyright protection has been extended by the courts to such diverse works of authorship as freight tables *(Guthrie v. Curlett*, 36 F. 2d 694), interest tables (*Edwards & Deutch Lithographing Co. v. Boorman*, 15 F, 2d 35), and lists of otherwise meaningless fiveletter code "words" (*Reiss v. National Quotation Bureau*, 276 Fed. 717). These works of authorship, like computer programs, are valued for their utility rather than their artistic merit.

As to the applicability of copyright to data bases, such creations are appropriately defined as compilations, which are protectable under copyright (Section 103). Compilations are defined, in Section 101 of the new law, as works

"formed by the collection and assembling of preexisting materials or of data that are selected, coordinated, or arranged in such a way that the resulting work as a whole constitutes an original work of authorship. The term 'compilation' includes collective works."

The extension of copyright protection to compilations has evolved over the years out of several court cases. In 1937 telephone books were afforded copyright protection (*Leon et al v. Pacific Telephone and Telegraph Co.*, 91 F. (2d) 484). In 1922 a directory of jeweler's trade marks was held to be copyrightable (*Jeweler's Circular Pub. Co. v. Keystone Pub. Co.*, 281 F. 83). The Court decided in this case that:

"The right to copyright a book upon which one has expended labor in its preparation does not depend upon whether the materials which he has collected consist or not of matters which are *publici juris*, or whether such materials show literary skill or originality, either in thought or in language, or anything more than industrious collection. The man who goes through the streets of a town and puts down the names of each of the inhabitants, with their occupations and their street number, acquires material of which he is the author. He produces by his labor a meritorious composition, in which he may obtain a copyright, and thus obtain the exclusive right of multiplying copies of his work."

It seems clear that computer data bases must be accorded the same protection as compilations in traditional hard-copy format. But their remains one point to be clarified. In order for a copyright to be registered, Section 407 of the new law requires that copies of the work be deposited in the Library of Congress. Because a data base is dynamic in nature, subject to constant updating, it is pointed out that a deposit reflection every new updata is impractical. Furthermore, a proprietor, by virtue of the constant updating, could claim copyright in perpetuity, rather than the 75 years now allowable. But, Sections 407(c) and 408(c) authorize the Register of Copyrights to exempt categories of material from the deposit requirements, or to require alternative forms of deposit. Data bases could presumably be treated in the same fashion as are new editions of telephone books, which require periodic registration renewal.

The owner of copyright in a work has the exclusive right to copy or authorize copying of the work, as well as to prepare derivative works based upon it. Accord-

Protection, cont'd...

ing to CONTU, the placement of a copyrighted work into a computer is merely one form of reproduction. Nevertheless, there are limitations to the exclusivity of protection. The "fair use" doctrine of the Copyright Act (Section 107) allows limited, unauthorized reproduction for production for educational and informational, as opposed to commercial, purposes. For example. whenever a single photocopy of a copyrighted magazine article is made for an individual's educational or informational use, legal permission to do so is ordinarily afforded by the "fair use" doctrine. More specific to computer programs and data bases, once a copy of a work has been rightfully acquired, it may become necessary for the user to make an archival copy or to convert a work from one computer language to another (i.e., prepare a derivative work). Such necessary, but limited, in-house copying should be provided for in the copyright law.

Copyright protection is available only to expressions.

CONTU'S Final Recommendations

CONTU concluded that copyright protection should be specifically extended to computer programs and data bases for two fundamental reasons. Firstly, it is unreasonable and inefficient to create an entirely new layer of legal protection when the laws of copyright can do the job effectively and inexpensively. Secondly, copyright law serves to balance conflicting individual and societal needs. Works of authorship need to be widely available if they are to be of full value to society, and yet the individual author needs to be protected against unauthorized duplication so that the costs of authorship can be spread over multiple copies and thus recovered.

CONTU goes on to recommend that specific regulations concerning notice, deposit, and registration of computer programs and data bases be developed by the Register of Copyrights. Copyright notice ("Copyright," the abbreviation "Copr.," or the symbol ©, together with the year of publication and name of the copyright owner) should be printed or coded so that the notice is immediately apparent when a work appears in human-readable form. Notice should also appear on external packaging, including such things as preprogrammed semiconductor chips.

It is also suggested that certain changes be made to the new copyright law in order to spell out the specific authorization and scope of copyright's applicability to computer programs. Section 117 as enacted should be repealed. To Section 101, which is a list of pertinent definitions, CONTU suggests that the following be added:

"A 'computer program' is a set of statements or instructions to be used directly or indirectly in a computer in order to bring about a certain result."

CONTU also proposes that Section 117 be replaced with the following:

"#117: *Limitations on exclusive rights: computer programs* Notwithstanding the provisions of #106, it is not an infringement for the rightful possessor of a copy of a computer program to make or authorize the making of another copy or adaptation of that computer program provided:

(1) that such a new copy or adaptation is created as an essential step in the utilization of the computer program in conjunction with a machine and that it is used in no other manner, or

(2) that such a new copy or adaptation is for archival purposes only and that all archival copies are destroyed in the event that continued possession of the computer program should cease to be rightful. Any exact copies prepared in accordance with the provisions of this section may be leased, sold, or otherwise transferred, along with the copy from which such copies were prepared, only as part of the lease, sale, or other transfer of all rights in the program. Adaptations so prepared may be transferred only with the authorization of the copyright owner.

The foregoing passage was designed to make it clear that neither the "inputting" of a program by a rightful possessor, nor the archival storage of a program as insurance against such things as accidental erasure, is an infringement of copyright.

According to the U.S. Copyright Office, copyright protection is currently available for computer programs, but not for data bases. Protection lasts for the life of the author plus 50 years, or, in the case of a work made for hire, a total of 75 years. A program is coyrighted by sending one copy or print-out of the program, along with a completed application Form TX and $10.00, to the United States Copyright Office, Library of Congress, Washington, D.C. 20559. Copies of Form TX, "Application for Copyright Registration for a Nondramatic Work," are avilable free from the above address. Publication of a work is no longer required for copyright protection.

Although CONTU's recommendations were presented to Congress in July of 1978, a bill to incorporate these recommendations into copyright law has yet to be introduced. Judging from the pace of copyright reform in the past, action by Congress will be anything but swift. □

Logic Problem Solver

Tom Pratt

Have you ever been baffled by those mind-teasers called logic problems? Ever get the temptation to take a peek at the solution, but just feel too guilty to do it? This program offers you a happy medium — an alternate to cheating.

The key to solving logic problems lies in the interpretation of the given information. After properly interpreting what is given, the bulk of the time spent solving your logic problem will be in carrying out mechanical calculations. So, instead of wasting precious hours and risking mistakes, why not let the computer carry these out for you?

This program was written for my SWTPC 6800 w/16K and Robert Uiterwyk's Basic version 2.0. I have used commands that are common to most all Basics. It will use approximately 8K on top of the basic interpreter.

Using a computer to solve logic problems still leaves you with a fair amount of mental exercise. You must first make equations out of the statements used in the logic problem. For example, take a look at the sample logic problem. It is composed of four groups, each having five members. Let's call the group composed of Arkansas, Baltimore, Carson City, Daytona and El Dorado Group 1. The group of Rawhides, Superstars, Triplers, Underdogs and Victors will be Group 2. Group 3 will be the order of finish in this year's pennant race, and the order of finish in last year's pennant race will be Group 4. Also, either a "T" (for "this year") or an "L" (for "last year") will follow the numbers used for the order of finish. So, "1L" means first place last year, and "5T" means fifth place this year.

In making equations out of the logic problem statements, there are a few rules to follow. Obviously "<>" represents "not equal to" and "=" represents "equal to." But in an inequality, you must make a normal inequality statement (using "<" or ">") plus you must add what I call a "group specifier" and a "position specifier." The first statement of the sample logic problem says "This year, Baltimore's team finished one place higher than the Rawhides, who finished one place higher than last year's fourth place team." Since the inequality Baltimore > Rawhides takes place in this year's order of finish, and since we are calling the group of this year's order of finish Group 3, the group specifier is 3. Since Baltimore's team finished one place higher than the Rawhides, the position specifier is 1. Put all together, the inequality should look like this: Baltimore > Rawhides,3,1. Now, if the statement said "This year, Baltimore's team finished higher than the Rawhides," you would not know the position specifier, so you would use a zero as the position specifier: Baltimore > Rawhides,3,0.

You must make all possible equations out of the logic problem statements (that is, equations that do not restate other equations). Again, referring to the first statement of the sample logic problem, you should get the two following equations: Baltimore > Rawhides,3,1 and Rawhides > 4L,3,1. In addition, you might also want to say: Baltimore <> Rawhides and Rawhides <> 4L and 4L <> Baltimore, but these are unnecessary. You are merely restating the first two equations (if one thing is greater than another, they certainly are not equal!). You can, however, do this to make sure you have covered all possible equations.

After figuring all of the equations from the logic problem statements, you must type them in as data lines in lines 6000-6999. Remember to separate each character entry with commas.

You are now ready to run the program. The computer will ask "How many equations?" This means how many equations did you type in the data lines. It will then ask for "members in order." Type in the members in the numerical order that you have designated the groups i.e., first type in the members of Group 1, then of Group 2, etc. If, in an inequality, a group specifier deals with the group you are to type in (in the sample logic problem, groups 3 and 4), you must type in the members of that group in ascending order. In the sample run, since 1T and 1L are the highest rank, I consider these to be the greatest values and consider 5T and 5L to be the lowest values. Therefore, I type in Group 3 starting with 5T and ending with 1T and Group 4 starting with 5L and ending with 1L.

Since poke and peek commands are used in the program to conserve memory, use caution as to the memory locations used to store and retrieve these numbers. Otherwise, you could bomb your program, as well as your basic, or end up in a continuous loop — all of these being undesirable. However, there is an alternative to using these commands, but requires more memory (20K instead of 16K). It is the use of the array (D(24,24). All you must do is change the poke and peek statements to D(n,n) statements. I think it can be best explained by use of examples:

Poke statements

The statement POKE(S+X*20+X,3) should be changed to D(X,X)=3. The statement

POKE (S+G(X)*20+G(X+1),2)

should be changed to

D(G(X),G(X+1))=2.

Peek statements

The statement PEEK (S+X*20+Y) should be changed to D(X,Y). PEEK (S+G(X+1)*20+G(X)-1) should be changed to D(G(X+1),G(X)-1). I think you understand. You will have no problems at all if you follow these examples.

This program solves *most logic* problems and could be modified to solve any logic problem. It takes my computer about one hour to solve a four group-five member logic problem. Since most basic interpreters are much quicker than SWTPC's, using this program on other systems could speed up run time considerably. If you would like to attempt to cut down run time by modifying the program, I suggest you rearrange the order of routines (lines 1060-1077) that the computer executes.

Good luck in using the program. I hope you enjoy using it as much as I did writing it.

Tom Pratt, 6101 Hoffman Lane, Fair Oaks, CA 95628.

If you just bought another printer, boy are you gonna be sorry.

Epson.

The Epson MX-80. It's not just another worked-over rehash of last year's model. It's our top-of-the-line 80-column printer. It's new. From the ground up. And it's the most revolutionary printer to hit the market since Epson invented small printers for the 1964 Olympics in Tokyo. Don't take our word for it, though. Compare. There simply isn't a better value in an 80-column printer. Period.

But here's the fact that's going to stand the printer world on its ear. The MX-80 sports the world's first *disposable* print head. After it's printed about 50 million characters, you can throw it away. Because a new one costs less than $30, and the only tool you need to change it is attached to the end of your arm.

Now that's revolutionary, but that's only the beginning. The MX-80 also prints bidirectionally at 80 CPS with a logical seeking function to minimize print head travel time and maximize throughput. It prints 96 ASCII, 64 graphic and eight international characters in a tack-sharp 9x9 matrix. And it provides a user-defined choice of 40, 80, 66 or 132 columns and multiple type fonts.

We spent three long years developing the MX-80 as the first of a revolutionary series of Epson MX Printers. We employed the most advanced automatic assembly and machining techniques in existence to produce a printer that is incredibly versatile, remarkably reliable and extraordinarily inexpensive. It's a printer that could only come from the world's largest manufacturer of print mechanisms: Epson.

If it sounds like we're proud of the MX-80, we are. Not only does it do things some of the world's most expensive printers can't do, it'll do them for you for less than $650. That's right. Under $650.

And if that isn't revolutionary, we don't know what is.

The world's first disposable print head. It has a life expectancy of over 50 million characters, yet it's so simple, you can change it with one hand. And it costs less than – repeat less than – $30.

EPSON
EPSON AMERICA, INC.

23844 Hawthorne Boulevard, Torrance, California 90505, Telephone (213) 378-2220

CIRCLE 208 ON READER SERVICE CARD

SAMPLE LOGIC PROBLEM

Pennant Race

From the following clues, can you deduce the complete name of each team, and the order in which the teams placed both this year and last year?

1. This year, Baltimore's team finished one place higher than the Rawhides, who finished one place higher than last year's fourth place team.
2. Last year, Daytona's team placed ahead of the Superstars.
3. Arkansas' name is not the Rawhides or the Victors.
4. Last year's pennant winner placed third this year.
5. This year, the Superstars finished one place higher than last year's fifth place team, who placed ahead of Arkansas' team.
6. Carson City's team did not place third last year.
7. The Underdogs placed higher than the Victors this year.
8. No team finished in the same place both years.




```
READY
#RUN

INSTRUCTIONS- TYPE IN YOUR EQUATIONS IN
DATA LINES 6000-6999. WHEN THE COMPUTER
ASKS FOR 'MEMBERS IN ORDER'(LINE 40)
YOU MUST TYPE IN THE MEMBERS GROUP BY
GROUP.  ALSO, IF THE MEMBERS OF A GROUP
HAVE AN ASCENDING ORDER, YOU MUST TYPE
THEM IN IN THAT ASCENDING ORDER

HOW MANY EQUATIONS? 15

# OF GROUPS? 4

# OF MEMBERS IN EACH GROUP? 5

MEMBERS IN ORDER
? EL DORADO
? BALTIMORE
? DAYTONA
? CARSON CITY
? ARKANSAS
? VICTORS
? TRIPLERS
? SUPERSTARS
? RAWHIDES
? UNDERDOGS
? 5T
? 4T
? 3T
? 2T
? 1T
? 5L
? 4L
? 3L
? 2L
? 1L

EL DORADO-SUPERSTARS-1T-3L-
BALTIMORE-VICTORS-3T-1L-
DAYTONA-RAWHIDES-4T-2L-
CARSON CITY-UNDERDOGS-2T-5L-
ARKANSAS-TRIPLERS-5T-4L-

READY
```

```
0001 PRINT "INSTRUCTIONS- TYPE IN YOUR E
QUATIONS IN"
0002 PRINT "DATA LINES 6000-6999. WHEN T
HE COMPUTER"
0003 PRINT "ASKS FOR 'MEMBERS IN ORDER'(
LINE 40)"
0004 PRINT "YOU MUST TYPE IN THE MEMBERS
 GROUP BY"
0005 PRINT "GROUP.  ALSO, IF THE MEMBERS
OF A GROUP "
0006 PRINT "HAVE AN ASCENDING ORDER, YOU
 MUST TYPE"
0007 PRINT "THEM IN IN THAT ASCENDING OR
DER."
0008 DIM V(11),V1(11),G(12),D$(20),R(6),
R1(6)
0009  S=15626:I9=1
0010 READ W,W,W,W,W
0019 INPUT "HOW MANY EQUATIONS",P2
0020 INPUT "# OF GROUPS",N
0030 INPUT "# OF MEMBERS IN EACH GROUP",
A
0031  H=A
0040 PRINT "MEMBERS IN ORDER"
0050 FOR X=1 TON*A:INPUTD$(X):NEXTX
0100 FOR X=1 TO N*H
0110 POKE( S+X*20+X,3):IFX<=H THENGOSUB4
500
0120 NEXT X
0155 FOR R2=A-1 TO2 STEP -1
1005 READ C$,D$,F$
1010  K=0:Z=0:Z1=0
1019  P2=P2-1
1020 FOR X=1 TON*A
1022 IF C$=D$(X) THENZ=X
1024 IF F$=D$(X) THENZ1=X
1026 NEXT X
1027 IF Z1<>0 THENIFZ<>0 THEN1038
1028 PRINT "THERE IS A TYPING ERROR....S
MEWHERE!!!!":END
1030 IF D$="=" THENK=1:F=3:GOTO1100
1035 IF D$="<>"  THENK=2:GOTO1100
1038 IF D$="<" THENL$=F$:F$=C$:C$=L$:W=Z
:Z=Z1:Z1=W:W4=1:GOTO4700
1040 IF D$=">" THENW4=1:GOTO4700
1060 GOTO 1300
1070 GOTO 1200
1071 IF I9/3=INT(19/3) THENGOSUB1500
1072  I9=I9+1:IFX7>N+A-INT(A/2) THENGOSU
B1400
1073 GOTO 3000
1076 IF W4=1 THEN4800
1077 GOTO 1060
1100 POKE( S+Z*20+Z1,F):IFF=3 THENIFZ<=H
 THENGOSUB4500
1110 POKE( S+Z1*20+Z,F):IF F=3 THENIF Z1
<=H THENGOSUB4500
1114 IF K=0 THEN1FP2=0 THEN1060
1115 IF K=0 THEN1005
1120  L1=Z1:L=Z
1125  J8=1
1127 IF INT(Z/H)<>Z/H THENZ=Z+H
1128  W=INT(Z/H)
1129 GOTO 1135
1130  L1=L:L=Z1
1131 IF INT(Z1/H)<>Z1/H THEN21=Z1+H
1132  W=INT(Z1/H)
1135  X=(N*A-((N-W)*A))-H
1136  X=X+1
1137 IF X>N*A THEN1175
1138 IF X>N*A-((N-W)*A) THEN1175
1139 IF X=L THEN1170
1140 POKE( S+L1*20+X,2)
1170 GOTO 1136
1175 IF J8=1 THENJ8=0:GOTO1130
1177 IF S4=P2 THEN1060
1178 GOTO 1005
1200 FOR X=1 TON*A
1206 RESTORE
1210 READ W
1211 IF W=0 THEN1290
1212  Y=(W-1)*A
1215  X1=0
1220  Y=Y+1
1230 IF Y>N*A-((N-W)*A) THEN1270
1240 IF PEEK(S+X*20+Y)=2 THENX1=X1+1
1245 IF PEEK(S+X*20+Y)>2 THEN1210
1260 GOTO 1220
1270 IF X1=A-1 THENQ=((W*A)-A)+1:Q1=W*A:
GOSUB1750
```

FOR TRS-80*

Stocking Stuffers

for good little computers

PIGSKIN

by J. Laurence, R. Sothen & W. Gavenda

Play football against a friend or your computer with PIGSKIN. Featuring a graphic display of the field, the ball and scoreboard statistics, when you have the ball you choose from eleven offensive plays while your opponent picks which of the seven defenses might stop you.

If you play against your TRS-80, there are five levels of difficulty. And they aren't easy! You can even save a game for later completion. Don't limit yourself to Sunday football—get PIGSKIN now for only $14.95 on tape, $20.95 on disk.

INVADERS FROM SPACE

Full sound effects

by Carl Miller

A NEW ATTACK IS LAUNCHED!

A new and faster machine language approach to this classic (and addictive) space game.

In INVADERS FROM SPACE, you choose the game speed, the enemy bomb frequency and accuracy, the number of shots on screen and the number of your bases.

Available for TRS-80* 16K Level II for only $14.95 on tape or $20.95 on disk.

SYSTEM SAVERS

by Tom Stibolt

If you ever type "SYSTEM" on your TRS-80*, this two-program package will make life easier for you.

One of the programs, FLEXL, lets you make backup copies of any system format tape.

Disk drive owners can use TDISK to save any system format tape onto disk. It will even load non-contiguous tapes. You will get more out of disk drive ownership with TDISK.

Get this two-program package now for only $14.95. Just one of Acorn's fine utility programs.

DUEL -N- DROIDS

by Leo Christopherson

Your 'droid has already learned NIM, so now it's time to teach it how to wield a laser sword!

Your 'droid starts out as a lowly clown. You teach it how to use a laser sword by controlling its movements. After training it to be a "Grand Master," you enter the tournament against the program's skilled 'droid! Entertainment for all ages.

Available now for $14.95 on tape or $20.95 on disk, for TRS-80* Level II, 16K.

SUPERscript

by Richard Wilkes

Enhances Radio Shack's great Scripsit word processor with many new and useful features.

Call up the disk directory or kill files while still in Scripsit.

Using any printer with backspace capability, you can underline text and produce computer-type slashed zeros.

All these capabilities, and more, are available when you add SUPERCRIPT to your Scripsit program. Available for just $29.95 on disk.

or choose from these popular programs. . . .

. . . SPACE WAR
Two-player, real-time space battle. $9.95

. . . ATERM
ASCII terminal communications program. $19.95

. . . MUSIC
Compose and play your own music, using your TRS-80*. $9.95

. . . CODEBREAKER
Puzzle-solving game tests your logical skills. $9.95

Available now from these and other fine Acorn dealers

ADVENTURES INTERNATIONAL
178 Oxford Rd.
Fern Park, FL 32703

CINCINNATI COMPUTER STORE
Princeton Plaza–
11711 Princeton Rd.
Cincinnati, OH 45246

COMP-U-TRS
51 Florissant Oaks
Shopping Center
Florissant, MO 63031

DIGIBYTE COMPUTER CENTER
31 East 31st St.
New York, NY 10016

HOBBY WORLD ELECTRONICS
19511 Business Center Dr.
North Ridge, CA 91324

LEVEL IV PRODUCTS, INC.
32238 Schoolcraft Rd.
Livonia, MI 48185

MICRO MANAGEMENT SYSTEMS
115-C Second Ave.
Cairo, GA 31728

MICROMATIC SYSTEMS
1303 Powell St.
Vancouver, BC V5B-1G6

THE PROGRAM STORE
4200 Wisconsin Ave.
Washington, DC 20016
and
W. Bell Plaza–
6600 Security Blvd.
Baltimore, MD 21207

RADIO SHACK
White Oak Shopping Center
Silver Spring, MD 20904
and
Gaithersburg Square
Gaithersburg, MD 20760

* TRS-80 is a trademark of Tandy Corp.

DEALER INQUIRIES INVITED

Acorn
Software Products, Inc.

634 North Carolina Avenue, S.E., Washington, D.C. 20003

Logic, cont'd...

```
1280 GOTO 1210
1290 NEXT X:GOTO1071
1300 FOR X=1 TO N*A
1310 FOR Y=1 TO N*A
1320 IF X=Y THEN1335
1329 IF PEEK(S+X*20+Y)=2 THENPOKE( S+Y*2
0+X,2)
1330 IF PEEK(S+X*20+Y)=3 THENGOSUB1350
1335 NEXT Y:NEXTX:GOTO1070
1350 FOR I=1 TON*A
1360 IF PEEK(S+20*X+1)=2 THENPOKE( S+20*
Y+I,2)
1365 IF PEEK(S+Y*20+1)=3 THEN1380
1370 IF PEEK(S+X*20+1)=3 THENPOKE( S+Y*2
0+1,3):IFY<=H THENGOSUB4500
1380 IF PEEK(S+Y*20+1)=2 THENPOKE( S+X*2
0+1,2)
1385 IF PEEK(S+X*20+1)=3 THEN1395
1390 IF PEEK(S+Y*20+1)=3 THENPOKE( S+X*2
0+1,3):IFX<=H THENGOSUB4500
1395 NEXT I:RETURN
1400 FOR X=1 TOA
1405  R1=0:R2=0:R3=0
1410  W6=0
1420 FOR Y=1 TO N*A
1430 IF PEEK(S+X*20+Y)=3 THENW6=W6+1:GOT
O1470
1435 NEXT Y
1440 IF W6=N THEN1479
1445 NEXT X
1450 RETURN
1470 IF Y<2*H+1 THENR1=Y:GOTO1435
1472 IF W6<2 THEN1445
1474 IF Y<3*H+1 THENR2=Y:GOTO1435
1476 IF W6<3 THEN1445
1478  R3=Y:GOTO1435
1479 IF R3=0 THENR3=R2
1480 POKE( S+X*20+X,4):POKE( S+X*20+R1,4
):POKE( S+X*20+R2,4)
1482 POKE( S+X*20+R3,4):POKE( S+R1*20+X,
4):POKE( S+R1*20+R1,4)
1485 POKE( S+R1*20+R2,4):POKE( S+R1*20+R
3,4):POKE( S+R2*20+X,4)
1488 POKE( S+R2*20+R1,4):POKE( S+R2*20+R
2,4):POKE( S+R2*20+R3,4)
1490 POKE( S+R3*20+X,4):POKE( S+20*R3+R1
,4):POKE( S+20*R3+R2,4)
1495 POKE( S+20*R3+R3,4)
1496 GOTO 1445
1500 FOR R2=A-1 TO2 STEP -1
1502 RESTORE
1504 READ N
1506 IF N=0 THEN1564
1507 IF N>A THEN1564
1508 FOR J8=(N-1)*A+1 TON*A-((N-N)*R)
1509  R1(1)=0:R1(2)=0:R1(3)=0:R1(4)=0:R1
(5)=0:R1(6)=0
1510  X=(N-1)*A+1
1511  R(1)=0:R(2)=0:R(3)=0 R(4)=0:R(5)=0
:R(6)=0

1516  C=0:L=0:K=1
1518 FOR R1=J8 TOX+A-1
1519 IF K>N THEN1563
1520  B=0:Y=(K-1)*A:R3=0
1524 IF Y+1=X THEN1556
1526  Y=Y+1:R3=R3+1
1528 IF R1>J8 THEN1FY>(K-1)*A+A THENIFA-
B=R2 THEN1554
1530 IF R1>J8 THEN1FY>(K-1)*A+A THEN1556

1531 IF Y>(K-1)*A+A THENIFA-B<>R2 THEN15
56
1532 IF Y>(K-1)*A+A THEN1554
1534 IF R1>J8 THEN1548
1536  R(R3)=PEEK(S+R1*20+Y):IFR(R3)>0 TH
ENL=1
1538  I=1
1540 IF R(R3)=2 THENB=B+1
1541 IF A-B=R2 THEN1554
1542 GOTO 1526
1544 IF A-B=R2 THEN1554
1546 GOTO 1556
1548  L1=(K-1)*A
1549 GOTO 3700
1552 GOTO 1526
1554  C=C+1:R1(1)=J8:R1(C)=R1
1556 IF A-B<>R2 THEN1FR1=J8 THENR1=J8+R
1557 NEXT R1:K=K+1
1558  I=0
1560 IF C=R2 THENIFL=1 THEN1570
1561  C=0:L=0:GOTO1518
1563 NEXT J8:GOTO1504
1564 NEXT R2:GOTO1072
1566 NEXT X
1568 GOTO 1072
1570  Y=(K-2)*A+1
1572 FOR Z=X TOX+A-1
1574 IF R1(1)<>Z THEN1FR1(2)<>Z THEN1FR1
(3)<>Z THEN1FR1(4)<>Z THEN1578
1576 NEXT Z:GOTO1564
1578 IF R1(5)<>Z THEN1FR1(6)<>Z THEN1582

1580 GOTO 1576
1582 FOR X1=1 TOA
1590 IF R(X1)=0 THENPOKE( S+Z*20+(Y+X1-1
),2)
1592 NEXT X1:GOTO1530
1750 FOR W=0 TOQ1
1760 IF PEEK(S+X*20+W)=2 THEN1780
1770 POKE( S+X*20+W,3):IFX<=H THENGOSUB4
500
1780 NEXT W
1790 RETURN
2000 FOR X=1 TOA
2010 PRINT ""
2020 FOR Y=1 TON*A
2050 IF PEEK(S+X*20+Y)<2 THEN2090
2060 NEXT Y:NEXTX:END
2090 REM
2100 PRINT D$(Y);"-";
2101 GOTO 2060
2116 POKE( S+X*20+L1,2)
3000 FOR X=1 TON*A
3010  X1=0
3020 FOR Y=1 TON*A
3060 IF PEEK(S+X*20+Y)=3 THEN3130
3070 NEXT Y:NEXTX:GOTO1075
3100  J8=X
3101 IF INT(X/H)<>(X/H) THENJ8=J8+H
3104 ON INT(J8/H)GOTO3200,3300,3400,3500
,3500
3110 FOR I=L TOL1
3120 IF I=X THEN3140
3130 POKE( S+I*20+Y,2)
3140 NEXT I
3145 GOTO 3070
3150 RETURN
3200  L=1:L1=A:GOTO3110
3300  L=A+1:L1=2*A:GOTO3110
3400  L=2*A+1:L1=3*A:GOTO3110
3500  L=3*A+1:L1=N*A:GOTO3110
3600 FOR Q=R3+1 TOA
3610  R(Q)=0:NEXTQ:RETURN
3700 FOR Q=1 TOA
3710  L1=L1+1
3720 IF R(Q)=2 THEN1FPEEK(S+R1*20+L1)<>2
 THEN1556
3740 NEXT Q
3741 GOTO 1554
4500  X7=X7+1
4510 IF X7=N*A THEN2000
4520 RETURN
4700  U=U+1
4710 READ V(U),V1(U)
4720  G(U)=Z
4730  U=U+1
4740  G(U)=Z1
4750 IF S4=P2 THEN1060
4760 GOTO 1005
4800 FOR X=1 TOU STEP2
4830 FOR Y=(V(X)-1)*H+1 TOV(X)*H
4851 POKE( S+G(X)*20+((V(X)-1)*H)+1,2)
4852 POKE( S+G(X+1)*20+V(X)*H,2)
4853 POKE( S+G(X)*20+G(X+1),2)
4854 POKE( S+G(X+1)*20+G(X),2)
4855 IF V1(X)<=1 THEN4860
4856 FOR R1=1 TOV1(X)
4857 POKE( S+G(X)*20+((V(X)-1)*H+R1),2)
4858 POKE( S+G(X+1)*20+(V(X)*H)-R1,2)
4859 NEXT R1
4860 IF PEEK(S+G(X)*20+Y)>2 THEN1FV1(X))
0 THENGOSUB7000
4870 IF PEEK(S+G(X+1)*20+Y)>2 THEN1FV1(X
)>0 THENGOSUB7010
4880 IF PEEK(S+G(X)*20+Y)>2 THENIFV1(X)=
0 THENGOSUB7020
4890 IF PEEK(S+G(X+1)*20+Y)>2 THEN1FV1(X
)=0 THENGOSUB7080
4891 IF PEEK(S+G(X+1)*20+Y)=2 THEN8500
4892 IF PEEK(S+G(X)*20+Y)=2 THEN8600
4895 GOTO 8800
5998 DATA 1,2,3,4,0
6000 DATA BALTIMORE,>,RAWHIDES,3,1,RAWHI
DES,>,4L,3,1
6010 DATA DAYTONA,>,SUPERSTARS,4,0,ARKAN
SAS,<,VICTORS
6020 DATA ARKANSAS,<,RAWHIDES,1L,=,3T,S
UPERSTARS,>,5L,3,1
6030 DATA 5L,>,ARKANSAS,3,0,CARSON CITY,
<,3L
6040 DATA UNDERDOGS,>,VICTORS,3,0
6050 DATA 5T,<,5L,4T,<,4L,3T,<,3L,2T,
<,2L,1T,<,1L
7000 IF PEEK(S+G(X+1)*20+(Y-V1(X)))>2 TH
ENRETURN
7005 POKE( S+G(X+1)*20+(Y-V1(X)),3):IFG(
X+1)<=H THENGOSUB4500
7006 RETURN
7010 IF PEEK(S+G(X)*20+(Y+V1(X)))>2 THEN
RETURN
7015 POKE( S+G(X)*20+(Y+V1(X)),3):IFG(X)
<=H THENGOSUB4500:RETURN
7016 RETURN
7020 FOR J8=Y TOV(X)*H
7050 POKE( S+G(X+1)*20+J8,2)
7060 NEXT J8:RETURN
7080 FOR J8=(V(X)-1)*H+1 TOY
7110 POKE( S+G(X)*20+J8,2)
7120 NEXT J8:RETURN
8000 IF PEEK(S+G(X)*20+Y)=2 THEN1F V1(X)
>0 THEN1FY>(V(X)*H)+1 THEN9000
8010 IF PEEK(S+G(X+1)*20+Y)=2 THENIFV1(X
)>0 THEN1FY<(V(X)*H)+1 THEN9010
8040 NEXT Y:NEXTX:GOTO1077
8500  W=(V(X)-1)*H
8510  W=W+1
8520 IF W>Y THENPOKE( S+G(X)*20+Y,2):POK
E( S+G(X)*20+(Y+1),2):GOTO4892
8530 IF PEEK(S+G(X+1)*20+W)<>2 THEN4892
8540 GOTO 8510
8600  W=Y
8610  W=W+1
8620 IF W>V(X)*H) THENPOKE( S+G(X+1)*20
+Y,2):POKE( S+G(X+1)*20+(Y-1),2)
8625 IF W>V(X)*H) THEN4995
8630 IF PEEK(S+G(X)*20+W)<>2 THEN4895
8640 GOTO 8610
9000 POKE( S+G(X+1)*20+(Y-V1(X)),2):GOTO
8040
9010 POKE( S+G(X)*20+(Y+V1(X)),2):GOTO80
40
```

Interact Interactions

In response to my piece, "Where Are They Now", David Ross, president of Micro Video said, "here we are." Micro Video has taken over the manufacturing facilities and inventory of Interact Electronics and is continuing to market and support the unit. Not only that, but Micro Video has lowered the price of the basic computer to $375, and added an RS-232 interface and supporting software to the line as well as several new games.

They have located 3500 Interact owners and are providing support to them. However, they are still seeking the remaining 2000 or so Interact owners who did not have a warranty card on file with Interact. If you are one, or if you're interested in an inexpensive entry system, write Sue Denim, Micro Video, P.O. Box 7357, Ann Arbor, MI 48107.

(For a complete review of the Interact computer, see *Creative Computing*, December 1979, available for $2.50 postpaid.)—DHA

ALF/Apple Music Synthesizer



With the ALF software, entry of music is easy, fast and accurate.

The ALF Apple Music Synthesizer (AMS) is an easy to use peripheral which allows you to program music into an Apple II computer using standard musical notation. The ALF kit includes the synthesizer board (plugs into any peripheral slot), exceptional quality software, and an extensive user manual.

Sophisticated Music Entry Program

Sheet music is easily entered using the Apple game paddles. The high-resolution ENTRY program features the familiar music staff with a "menu" of musical items listed beneath it (note lengths, rests, edit commands, accidentals, etc.). One game paddle moves a cursor up and down the music staff and is used to select the note pitch; the second paddle chooses from the menu items (note length, etc.) With the ALF hi-res ENTRY program, you won't have to use cryptic codes to select note parameters.

As you program sheet music with ENTRY, measure bars are inserted automatically (and note values are tied over the bar where necessary). Key signatures are also automatic—you don't have to keep writing in every sharp or flat!

Three monophonic, individual parts can be programmed with each ALF Music Synthesizer. Two boards are required for stereo. A total of three synthesizers can be used simultaneously for a maximum of nine voices. By controling the envelope (or shape) of each voice, many different instrumental sounds can be simulated.

Eight-octave Range

The ALF Music Synthesizer has a pitch range of eight octaves—a wider range than a grand piano. The ALF can also play semitones—"blues notes" or the pitches in between the keyboard notes of a piano. (The pitch range is from 27.5 to 55,000 Hertz, well beyond the limits of human hearing.) Tuning accurancy is virtually perfect within two cents of pitch value.

Every parameter of the ENTRY program can be changed again and again during a musical piece. For example, you can make changes in key, time signature, volume, and timbre (envelope). Parts can be edited at any time, also. Notes can be added or deleted, note length can be changed, as well as pitch, volume, etc.

You can save songs on either cassette or disk, and play them back using either ENTRY or PLAY. The playback speed is adjusted with one of the game paddles, and can be varied during the playback, if you wish to change the overall tempo.

Colorful Playback Display

The ALF Music Synthesizer features a 16-color low-res graphic display during song playback. Each musical part is represented on a stylized piano "keyboard"—the intensity of the note determines the color, and the pitch is shown in relation to "middle C".

The ALF Music Synthesizer requires the use of an external audio amplifier. Stereo programming is possible with the use of two or three synthesizer boards.

The ALF software includes the ENTRY and PLAY programs, sample songs, an introduction to "envelope shaping", and demonstrations of advanced uses of the synthesizer.

Nine Voices for only $198

The new ALF "AM-II" music synthesizer offers an unbeatable value for the Apple owner who is a music hobbyist. With nine voices on a single music board for $198.00, the AM-II is the most economical device for creating music with the Apple.

The AM-II uses the same excellent ENTRY and PLAY programs as the more sophisticated ALF Music Synthesizer (AMS); the same hi-res graphic display from which notes are selected with the Apple game paddles (not typed with cryptic codes). All of the conveniences of the ENTRY program apply—easy editing, playback with low-res display, ability to save songs on cassette or disk, etc.

The AM-II has **stereo output** (3 voices in left, 3 voices in the middle, 3 voices in the right).

How can the AM-II offer so much for only $198.00? The two basic differences between the AM-II and the ALF Apple Music Synthesizer (AMS) are pitch accuracy and dynamic range. The AM-II has an accurate pitch range of about six octaves. Pitch values above the treble staff become increasingly inaccurate. Also, the AM-II has a dynamic range of 28db, with 16 different volume levels, (the AMS has a dynamic range of 78db).

The AM-II is manufactured with the same high quality standards as other products from the ALF Corporation. No sacrifice has been made in reliability; the new AM-II is simply a great bargain.

Professional musicians will still want to use the original Apple Music Synthesizer (AMS) for its extended range and volume controls (the AMS has a range of 8 octaves). But for the Apple owner who is interested in music as a hobby, the AM-II is the best music peripheral value available today.

Requires: 16K Apple II or Apple II Plus, cassette or Disk II, and an external audio amplifier (all necessary patch cords are included).

AM-II ALF/Apple Synthesizer	$198.00
AMS ALF/Apple Synthesizer	268.00

To order, send payment plus $3.00 shipping and handling to Peripherals Plus, 119 Maple Ave., Morristown, NJ 07960. Credit card customers should include card number and expiration date of Visa, MasterCard or American Express. Credit card customers may also order toll-free:

800-631-8112

(In NJ call 201-540-0445)

Peripherals Plus

119 Maple Ave., Morristown, NJ 07960

CIRCLE 239 ON READER SERVICE CARD

CHRISTMAS TREE

Stephen R. Berggren

One of the most enjoyable jobs of the Christmas season is decorating the Christmas tree. It is unfortunate that this pleasant and satisfying task can only be done once each year. Besides, how can you be any good at something you do only once a year? You should be able to decorate a Christmas tree whenever you want to. Can a personal computer solve a problem like this? Of course, it can! Using the *Christmas Tree* program you can decorate and display your own Christmas tree any time you want to.

The *Christmas Tree* program displays a Christmas tree and allows you to decorate it with up to 200 colored lights. Game paddles control the placement of the lights. The colors may be red, green, blue, violet or white. A delete function can be used to erase any mistakes. Once the tree is decorated to your satisfaction, it can be displayed with either flashing or non-flashing lights.

The program was written for the Apple II computer. The language used is Applesoft, the floating point version of Basic used in the Apple II. The program can operate under either the ROM or RAM versions of this language. However, under the RAM version, the number of lights used may be limited to about 150. Using any more lights may overwrite the graphics screen. Removing the REM statements will allow more lights to be used. The program makes use of the hi-resolution color graphics, game paddle inputs and shape table drawing routines of this system. Other systems with color graphics such as the Atari or the Compucolor should be able to run the program after changing the drawing and cursor routines. Of course, the data used to draw the tree must be modified to fit the different screen sizes.

The program itself is really very simple. Line 10 sets aside memory for the X and Y position and color of each light. The "%" sign means that they are integer values. After providing directions in lines 200 to 370, it uses lines 600 to 710 to draw the outline of a Christmas tree in green on the hi-resolution graphics screen. The data table at lines 150 and 160 provides the shape. Note that it draws the shape twice with the second shape right next to the first. This just makes a wider line. Next, a very simple shape table is put into the memory using data at line 840. This shape is a tiny square made up of four dots. This shape table is used to draw the lights and is also the cursor that shows where the lights will be placed. Its size is just large enough to show clearly on the screen. Now the program uses lines 1010 to 1060 to put a cursor on the screen in a place determined by the two paddle controls. The XDRAW commands at lines 1030 and 1050 reverse the colors of the background at that position. Since two reversals leave the screen looking just as it did, this procedure does not erase anything. The cursor may be moved anywhere without leaving a trail.

Once the tree is decorated to your satisfaction, it can be displayed with either flashing or non-flashing lights.

As the cursor is being drawn, the program uses line 1040 to see if a key has been pressed. If one has, lines 2040 to 2080 determine what key was pressed and branch to the needed routines. Line 2035 is simply a warning that all 200 lights have been put on the tree. Lines 2088 to 2130 put the light on the screen at the cursor position and put the position and color into memory. If a light is to be removed, the program jumps down to lines 6000 to 6030. This subroutine checks the position of the cursor square against the positions in memory. If it finds a match, it changes the color in memory to black and erases the light from the screen.

When the Christmas tree is finished, a "Control-N" key will send the program to lines 5000 to 5040. There the cursor square is removed and the program waits for a carriage return while the tree remains displayed. If a "Control-F" is typed instead, the program goes to lines 3000 to 4060. The cursor is first removed. Then a light is selected at random and turned on while another light is selected at random and turned off. This process is repeated very rapidly and gives the effect that the lights are flashing. The flashing continues until interrupted by a "Control-C" or "reset."

Several modifications to the program might be interesting. First, by saving the arrays that hold the light colors and positions a particularly pleasing tree might be kept indefinitely. Second, shape tables for stars, candy canes or bells could be included to allow for decorations besides lights. Finally, a means for drawing lines could be included to draw in background and unique decorations.

Decorating is part of the fun of the Christmas season. With this *Christmas Tree* program your computer can contribute to this fun by displaying a beautiful Christmas decoration designed by you. Merry Christmas! □

```
]RUN
     C H R I S T M A S   T R E E

          BY STEPHEN R BERGGREN

THIS PROGRAM ALLOWS YOU TO DECORATE
AND DISPLAY A CHRISTMAS TREE.  YOU MAY
PUT UP TO 200 LIGHTS ON THE TREE AND
MAKE THEM FLASH OR GLOW STEADILY.

TO PUT LIGHTS ON THE TREE, MOVE THE
FLASHING DOT TO THE RIGHT POSITION AND
PRESS A COLOR KEY.  WHEN FINISHED,
PRESS 'CTRL-F' FOR FLASHING LIGHTS OR
'CTRL-N' FOR NORMAL.  THESE ARE THE
AVAILABLE COLORS.  'DELETE' REMOVES
THE LIGHT UNDER THE CURSER.

          W = WHITE       G = GREEN

          R = RED         V = VIOLET

          B = BLUE        D = DELETE

     (PRESS RETURN TO BEGIN)
```

Stephen R. Berggren, 2347 Duncan Drive, Dayton, Ohio 45324.



```
LIST

10  DIM XN%(200),YN%(200),CN%(200
    )
20  REM  XN%() = X POSITION OF LI
    GHT
30  REM  YN%() = Y POSITION OF LI
    GHT
40  REM  CN%() = COLOR OF LIGHT
140  REM  DATA TO DRAW TREE
150  DATA 180,124,180,70,148,86,1
    50,80,118,96,120,90,88,106,9
    0,100,58,116,60,110,28,126,2
    0,128
160  DATA 28,130,60,146,58,140,90
    ,156,88,150,120,166,118,160,
    150,176,148,170,180,186,180,
    132,190,132
200  HOME
210  PRINT "     C H R I S T M A
    S   T R E E"
220  PRINT : PRINT "          BY ST
    EPHEN R BERGGREN"
230  PRINT : PRINT "THIS PROGRAM
    ALLOWS YOU TO DECORATE"
240  PRINT "AND DISPLAY A CHRISTM
    AS TREE.  YOU MAY"
250  PRINT "PUT UP TO 200 LIGHTS
    ON THE TREE AND"
260  PRINT "MAKE THEM FLASH OR GL
    OW STEADILY."
270  PRINT : PRINT "TO PUT LIGHTS
     ON THE TREE, MOVE THE"
280  PRINT "FLASHING DOT TO THE R
    IGHT POSITION AND"
290  PRINT "PRESS A COLOR KEY.  W
    HEN FINISHED, "
300  PRINT "PRESS 'CTRL-F' FOR FL
    ASHING LIGHTS OR"
310  PRINT "'CTRL-N' FOR NORMAL.
     THESE ARE THE"
315  PRINT "AVAILABLE COLORS.  'D
    ELETE' REMOVES"
318  PRINT "THE LIGHT UNDER THE C
    URSER."
320  PRINT : PRINT "     W = WHIT
    E       G = GREEN"
330  PRINT : PRINT "     R = RED
            V = VIOLET"
340  PRINT : PRINT "     B = BLUE
            D = DELETE"
370  PRINT : INPUT "   (PRESS RET
    URN TO BEGIN)";A$
590  HGR2
595  REM  DRAW TREE
600  HCOLOR= 1
610  HPLOT 124,190 TO 124,180
620  FOR I = 1 TO 24
630  READ Y,X
640  HPLOT  TO X,Y
650  NEXT I
660  HPLOT 123,189 TO 123,178
670  RESTORE
680  FOR I = 1 TO 24
690  READ Y,X
700  HPLOT  TO X - 1,Y - 1
710  NEXT I
720  HCOLOR= 0
790  REM  LOAD THE SHAPE TABLE FO
    R THE LIGHTS
800  FOR I = 768 TO 774
810  READ SHAPE
820  POKE I,SHAPE
830  NEXT I
840  DATA   1,0,4,0,37,55,0
850  POKE 232,0: POKE 233,3
860  ROT= 0
870  SCALE= 1
880 N = 0
1000  REM  DRAW CURSOR DOT, LOOK
    FOR KEY INPUT
1010 XP = 256 -  PDL (0) + 15
1020 YP =  PDL (1): IF YP > 189 THEN
    YP = 189
1030  XDRAW 1 AT XP,YP
1040 KEY =  PEEK ( - 16383): IF K
    EY > 127 THEN 2000
1050  XDRAW 1 AT XP,YP
1060  GOTO 1010
1990  REM  TEST THE KEY INPUT
2000  POKE  - 16368,0
2010  IF KEY = 142 THEN 5000
2020  IF KEY = 134 THEN 3000
2030  IF KEY = 196 THEN  GOSUB 60
    00: GOTO 1050
2035  IF N = 200 THEN  PRINT  CHR$
    (7) CHR$ (7) CHR$ (7): GOTO
    1050
2040  IF KEY = 215 THEN CN%(N) =
    3: GOTO 2090
2050  IF KEY = 194 THEN CN%(N) =
    6: GOTO 2090
2060  IF KEY = 214 THEN CN%(N) =
    2: GOTO 2090
2070  IF KEY = 210 THEN CN%(N) =
    5: GOTO 2090
2080  IF KEY = 199 THEN CN%(N) =
    1: GOTO 2090
2085  GOTO 1050
2088  REM  DRAW A NEW LIGHT
2090  HCOLOR= CN%(N)
2100  DRAW 1 AT XP,YP
2110 XN%(N) = XP:YN%(N) = YP
2120 N = N + 1
2130  GOTO 1010
2990  REM  REMOVE THE CURSOR DOT
3000  HCOLOR= 0
3010  DRAW 1 AT XP,YP
3990  REM  FLASH THE LIGHTS BY RA
    NDOMLY TURNING ONE ON AND ON
    E OFF
4000 P =  INT ( RND (1) * N)
4010  HCOLOR= CN%(P)
4020  DRAW 1 AT XN%(P),YN%(P)
4025 P =  RND (1)
4030 P =  INT ( RND (1) * N)
4040  HCOLOR= 0
4050  DRAW 1 AT XN%(P),YN%(P)
4060  GOTO 4000
4990  REM  REMOVE THE CURSOR DOT
    AND QUIT WITH ALL LIGHTS ON
5000  HCOLOR= 0
5010  DRAW 1 AT XP,YP
5020  INPUT A$
5030  TEXT
5040  END
5990  REM  ERASE THE DOT UNDER TH
    E CURSOR
6000  FOR I = 0 TO N
6010  IF XP = XN%(I) AND YP = YN%
    (I) THEN  HCOLOR= 3:CN%(I) =
    0: DRAW 1 AT XP,YP: PRINT  CHR$
    (7)
6020  NEXT I
6030  RETURN
```

Are you missing any back issues of **Creative Computing** or **ROM** magazine? The applications, programming techniques, simulations, problems, commentary, articles and fiction are practically timeless. Not only that, but the earlier issues are actually increasing in value.

Prices are $2.00 each, three for $5.00, or ten for $15.00. Postage $1.00 for up to 3 issues, $2.00 for 4 or more.

Super Special: One of everything we have—28 magazines in all—for only $40 postpaid.

creative computing

Vol. 3, No. 4 - Jul/Aug 1977
Guide to selecting a microcomputer. Write your own CAL, Part 2. Computers in medicine and health care. Dwyer: "8-Hour Course in Basic-Part 1." Thinking Strategies-Part 3." Sherlock Holmes and Charles Babbage. Four new games.

Vol. 3, No. 5—Sep/Oct 1977
A dynamic debugging system for 8080 assembly language, bibliography of "limits to growth" models, Dywer: 8-hour course in Basic-Part 2, Programming approaches to solving complex equations, Electronic information exchange, Symmetric art with your computer, in-depth reviews of 5 microcomputer BASICs, software technology music system, Games: Nomad, Rotate, Lissajous.

Vol 3, No. 6—Nov/Dec 1977
Programming techniques- Part 1. CAI. Topics in Logic. Three 8080 8K BASIC evaluations. Smart electronic game reviews. How computers can write final exams. Mastermind II and Othello computer games. Profile of the Alpha 1 and Alpha 2 for the TDL Xitan.

Vol. 4, No. 1—Jan/Feb 1978
File structures, 16-bit computers, LOGO Language, Murphy's laws, review of Radio Shack TRS-80 and Heath H8, World model, biorythms, how to write a simulation, Hart sort algorithm, 3 games, 8-Hour Basic Course - Part 4.

Vol. 4, No. 4—Jul/Aug 1978
Reviews of Commodore PET, Apple II, Atari computer, Video games, interfacing to the real world: 5 articles, business computing: 4 word processing systems, ROM section: 7 articles, backgammon game, bar code.

Vol. 4, No. 5—Sep/Oct 1978
Equipment profiles: TRS-80, Exidy sorcerer, Bally Arcade, PolyMorphic 8813, Merlin Video Display preview of nine new personal computers. Accounts receivable systems, All about PASCAL, real world games, a real time clock to build, PET cassettes, special education features, new software: Star Wars, Hex.

Vol. 4, No. 6—Nov/Dec 1978
Subject index and file index in BASIC, consumer computers buying guide, electronic game reviews, critical path analysis, mailing label programs, robot programming, experiment in teaching strategic thinking, evaluations of Northstar Horizon, CP/M operating system and backgammon computers, columns on Apple II PET and TRS-80, plus game section including "Corral", "Joust" and Puzzle"

Vol. 5, No. 1—January 1979
Computers in fiction; Survey of Educator's Attitudes; K-State; How to Hide Your Basic Program; World Chess Championship Computer; Compleat Computer Catalog, Microchess for the TRS-80; Exidy Sorcerer; Ohio Scientific superboard II; Robots in Fiction; Help for the Weary Taxpayer; A counterfeit Cursor for your PET; Medical Audit Time.

Vol. 5, No. 2—February 1979
Evaluations: Electric Pencil, Heathkit H-8, Computer Music Records. Computer Games: Gold Mine, Atom-20. Computerized Sports Predictions, Multiple Regression Analysis Simplified, Value of Computers in Education, Budget Management System, Help for the beleaguered consumer.

Vol. 5, No. 3—March 1979
Six articles on data base management; Evaluations of TRS-80 and Apple Disk Systems; Payroll system; the Game of Go; Small business computing with the Sourcerer; Judging of sports events; Social Science survey program.

Vol. 5, No. 4—April 1979
Safeguarding your computer; Interpretive programming; Elements of a good computer game, Music composition; "What will happen if"; Vertical graphs and bar charts; People Programming; Home applications.

Vol. 5, No. 5—May 1979
Word processing systems — buying a system and 5 evaluations; Writing 2 user-oriented program; Tutorial on PILOT; 3 new games; Amoritization schedules, reading and comprehension tests.

Vol. 5, No. 6—June 1979
8 Articles on computer graphics and plotting; Evaluations: HiPlot, NAD System, ALF/Apple Music Synthesizer; Copyright of Software; Sesame Place; Probability Study; String Manipulations; 3 New Games.

Vol. 5, No. 7-July 1979
Two Ecology Simulations, Creativity Test; World Power Systems; Files and Data Basis — 4 Articles; Evaluations of Six Peripherals and Software Systems; Personal finance Model, 2 logic games.

Vol.5, No. 8 August 1979
Adventure, Computers and Dance, Can Computers Think? The Law and Your Computer, muMath, Image Processing, Manipulating Pencil Files, Structured Programming Techniques. Evaluation of TI99/4, TRS-80 Model II, SWTPC PR-40, IMSAIVIO. Games: HVOLT and Fort.

Send order to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. Or save time and call your credit card order toll free to: **800-631-8112** (in NJ, 201-540-0445).



ISSUES

F

Vol.5, No. 10 October 1979

Battle of the Word Processors, The Computer as a Gun, Computer Driven Real 3-D Display. Applications: RCA VIP and COSMAC .ELF* Graphics Digital Clock. Evaluations: Peripheon 511, Compucolor II, Health H14 Printer, Atari Video Computer Cartridges, Mountain Hardware Super-Talker.

Vol.5, No. 11 November 1979

Comparison Chart of Six Popular Personal Computers, Comparison of Single Board Computers, Electronic Toys and Games, Quick Printer II, Interact Computer, TRS-80 Level III Basic, Battle of the Word Processors, IntroIX-10 Home Control System, Adventure: Complete Listing in Basic, Build Your Own Telephone Dialer and Joysticks.

Vol.5, No. 12 December 1979

More Electronic Games, Language Translators, APFMP1000 Video Game System, Buying a Word Processor printer, Satellite Tracking Software, Syskit for the 8080, Assemblers: CP/M vs. TSC, Statistics for the TRS-80. Part 2: Controlling Household Devices, Computerized Biofeedback. Applications: The Microcomputer as an Investment Tool, "Turnkey" CP/M systems, Animation for the Apple. Digitized Video Images.

Vol. 6, No. 1 January 1980

Interviews with Donald E. Knuth and William Wulf; Six Features on Artificial Intelligence; Air Traffic Controller; Computerized Resume; GROW: A Program that Learns; Evaluations: Six Basics; NEWDOS and TRSDOS; Auto Scribe; Micro Music.

Vol. 6. No. 2 February 1980

Six articles on Investment Analysis; David Levy: Intelligent Computer Games; Programs: Geneology, Graphing, Genetics; Evaluations of Word Star vs Electric Pencil; Pascal for the TRS-80; Micro Composer; Data Dubber; Sorcerer Word Processing Pac; Trivia Contest Results.

Vol. 6, No. 3 March 1980

Evaluations: TI 99/4; Cobol: Microsoft vs Micro Focus; Pencil Sharpener; Mailroom Plus; Ten software packages; Networks for Personal Computers; Three Mile Island Game; Interview with Joel Birnbaum; How to Make a Basic Tree.

Vol. 6, No. 4 April 1980

Dr. KiloBYTE's Creative Popular Personal Recreational Micro Computer Data Interface World Journal—the Famous 73 page April Fool parady. 8 Articles on Reading and Language; Interview with Gordon Bell; Evaluations of Heath WH-89, Atari 800 vs PET; Chatsworth Mark Sense Card Reader, Adventure.

Vol. 6, No. 5 May 1980

7 Features on Saving Money with your Computer: Analysis of Stock Options, Budgeting Model, Shopping Lists, Home Inventory, Home Purchase, Retirement Planning. Computer-Aided Model Rocket Design; Two Natural Language Systems; Evaluations of PET 2022 Line Printer, APF Imagination Machine, Personal Software's Desktop/Plan, Universal Data Entry System.

Vol. 6, No. 6 June 1980

14 Graphics Articles: Polar Plots, 3-D Graphics, Animation, Graphic Mazes, Motion Simulation, Inside Space Invaders. 7 Music Articles: Digital Audio, Computer-Aided Sight Reading, Design of a Synthesizer, Digital Enhancement of Old Recordings. Comparison of printers; Evaluations of The Atari Machine, Neeico's Music Box for the PET, HeathKit-Thomas Electronic Organ Kit.

ROM

July 1977

SOL. The Inside Story; Braille and the Computer Video newspaper; A Chip is Born; The Care and Feeding of Your Home Computer; Digital Foam — the peripheral of the future.

August 1977

The Kit and I, Part I, by someone who's never soldered before; Introduction to the fundamentals of Computer Memory; Tips for the do-it-yourself hardware beginner; Binary clocks; APLomania.

September 1977

Xeroxes and other hard copy off your CRT; Payroll Program; How Computers Work; The Kit and I, Part II: or Power to the Computer; CCD's How They Work and How They're Made; A look at PLATO, an Educational Computer System; IBM 5100.

October 1977

Binary Arithmetic For the Beginner; Microprocessor Aid for the Deaf and Blind; The Kilobyte Card; Scott Joplin on Your Sci-Fi Hi-Fi; Building a Basic Music Board; Flowcharting; Payroll Program.

November 1977

Solar Energy Measurement; A Beginners Introduction to BASIC; The Kit and I, Part III; More Music to Play on Your Computer; Micro Maintenance; Solomon and Viet: Putting Together a Personal Computing System; Time Sharing on the Family MICRO.

December 1977

A Beginners Guide to Peripherals; The Best Slot Machine Game ever; Artificial Intelligence?; An Electronic Jungle Gym for Kids; File Copy Program; Better Health Through Electronics; the Kit and I Part IV.

January 1978

Synthetic Skin for Your Robot and How to Make It; TLC: A Visual Programming Language; The Code That Can't Be Cracked; Beginners Guide to Computer Graphics; The Computer and Natural Language; First-Timer's Guide to Circuit Board Etching.

Apple Nuclear Power Plant



Stephen R. Berggren

The political implications of personal computers are only gradually becoming clear. By trying to run a nuclear power plant, for example, you get a better feel for the risks involved . . .

The safety, usefulness and desirability of nuclear power plants is a subject that has recently been a very "hot" topic of conversation. It seems that almost everyone has an opinion about what should be done about nuclear power plants. It's too bad that only a very few people have actually been at the controls of one of the big generating plants to get a firsthand feel for how it works.

That's all I wanted to do; to run my own nuclear power plant. Unfortunately, I did not have several hundred million dollars or a license from the Nuclear Regulatory Commission. Neither did I want to wait the ten years it would take to build a power plant. I was therefore forced to use what I did have, my Apple II computer. This wasn't such a bad alternative. After all, on a computer the worst thing that could result from my mismanagement would be a software crash. I would be completely safe from explosions, radiation and irate protesters.

My efforts at a safe study of nuclear power have resulted in a program that simulates the performance of a pressurized water nuclear power plant. The program is designed to be educational, as well as challenging and fun. It starts with a simple description of the workings of a plant I designed. This is followed by an animated diagram of the plant and its operation in color graphics. Then instructions are provided on how to operate the controls. Finally the plant starts operation with a daily status report appearing on the screen. The keyboard is used to adjust the controls and then move to the next day. Within the program, a series of equations simulates the response of the reactor and power system and presents the next day's status. Warnings are provided when the plant is not operating properly or when any damage is done. This report is a much simplified version of the computerized status reporting used in most nuclear power plants.

Stephen R. Berggren, 104 Ridgeway Ave. Louisville, KY 40207

I did not have several hundred million dollars or a license from the Nuclear Regulatory Commission. I was therefore forced to use what I did have, my Apple II computer.

As with a real power plant, the object is to produce as much electrical power as possible without injuring anyone or damaging the equipment. This plant can produce up to two megawatts of power before overloading, but the average power output depends on how close to this maximum the plant is operated and how long the plant is down for maintenance. When the plant's nuclear fuel is exhausted (after about 120 days) the program evaluates the operator's performance based on the average power output and the damage sustained by the plant. Of course, if the plant's operation should result in a meltdown, the operator should consider his performance rather poor.

A Disastrous Sample Run

In the sample program run, you can see that at day one the plant was in cold shutdown and everything was at 25 (degrees centigrade). Of course, the control rods were fully inserted and all coolant flow was stopped. I started the plant by pulling out the control rods. As the reactor heat went up, primary and secondary coolant flow was started to cool the reactor and run the generator turbine. By day 15, the plant's temperatures had settled down and the plant was running well, although not very close to its maximum power output. That's the trick; keeping the power output high and the temperatures in the operating ranges.

At day 19, a small coolant leak developed, but I decided not to shut down just to fix it. However, by day 23 things had really turned sour, and I had to try for a maintenance shutdown. With all coolant systems on full and the control rods in, the reactor cooled quickly and then entered the automatic maintenance shutdown mode. It took 32 days to repair the damage but then the plant was ready to start again. But I made a mistake. I tried to heat the reactor too quickly and went beyond the safe temperature range. Then, I tried to compensate by increasing the primary coolant flow and got into more trouble. Before I could get the emergency coolant on, the reactor went out of control and disaster struck. Too bad, but I deserved it. At least no one was hurt.

The program is written in a very straightforward manner and only the keyboard input and operating algorithms should be at all hard to understand. Lines 955 to 985 demonstrate the keyboard input. The key is entered as A$ and filtered in line 965 to allow only (space), (return) and 0 thru 9 to pass through. The (space) will skip to the next variable while the (return) will allow the program to continue to the next day's report. A$ is then concatenated to B$ whose VAL becomes the new input variable. The FOR statement in line 955 limits the input to four keystrokes. The program is almost entirely crashproof. *(Famous last words.—Ed.)*

If you are really interested in the operating algorithm, lines 1280 to 1395 simulate heat flow equations that have been simplified slightly. Don't feel too bad if you don't understand exactly how they work. They do work. The REM statements

COLLEGE BOARDS

for TRS-80 PET, APPLE

The best way to sharpen your skills for the College Board Exams is to work on actual examinations. Each of these program sets confronts the user with a virtually limitless series of questions and answers. Each program is based on past exams and presents material of the same level of difficulty and in the same form as used in the College Board examination. Scoring is provided in accordance with the formula used by College Boards.

SAT, PSAT, N.M.S.Q.T., set includes 7 programs covering Vocabulary, Word Relationships, and Mathematics. Price$59.95

GRE set includes 10 programs covering Vocabulary, Word Relationships, Mathematics, Logical Diagrams, Analytical Reasoning. $99.95

GAME PACKAGE #1

HOSTAGE Negotiate and/or attack in this contest between the Authorities and the Terrorists. Terrorists select their target; choosing to seize Hostages at Foreign Embassies, the U.N. Building, Airliners, Hospitals, School Buses, or even Nuclear reactors. During play, Terrorists and Authorities have ample opportunity to bargain and double-cross each other. As in real life, public opinion counts and shapes the player's actions. Players have a dramatic and realistically wide range of tactical options. This game accurately reflects the intricacies of threat, promise, and all facets of negotiation.

BLACK GOLD Strike oil and build your own petroleum empire in this exciting simulation. Players strive to dominate the oil market. Options must be bought, wells drilled, and marketing strategies chosen. Players face a host of problems in this simulation. These range from uncertain geological and price conditions to labor strikes, the impact of natural disasters, and perhaps most troublesome, the demands of El Supremo, a greedy oil potentate and ruler of some of the best territory for oil exploration.

PRIMARY FIGHT A Political-Math game in which up to 6 players compete for the nomination of their party. Results depend upon campaign strategy and mathematical skill.

$19.95

GAME PACKAGE #3

PRIME TIME Players compete as network executives. Each selects T.V. Shows for competing time slots. Choose from a wide range of programs including sit-coms, dramas, soaps, westerns, sci-fi, news and documentary shows, etc. Up to three players compete for ratings and advertising revenue. Program simulates fan loyalties and industry events including FCC rulings and criticism from various civic groups. Exciting and realistic.

STAR CLIPPER Sophisticated interplanetary trading game. Profit from technical change and discovery, exploit planetary scarcities, shape your buying and selling strategies as new planets are discovered and opportunities revealed. You must strive to avoid space-time warps and a host of lesser dangers as you ply the galactic trade routes. Players (up to 6) must navigate and trade as prices change and obstacles are met. Beware the space pirates!

BULLS AND BEARS Financial investment game for up to six players. Make a fortune by correctly using news bulletins and rumors central to this fast moving game. Stocks range from the speculative and highly volatile to the more staid. The Wall Street Bulletin reports run the gamut from general economic trends to new technology, discoveries, disasters and even the doings of the Ayatollah.

$19.95

TIME TRAVELER

The best of the adventure games. Confronts player with complex decision situations and the demand for real time action. Using the Time Machine, players must face a challenging series of enviornments that include; the Athens of Pericles, Imperial Rome, Nebuchanezzar's Babylon, Ikhaton's Egypt, Jerusalem at the time of the crucifixion, The Crusades, Machiavelli's Italy, the French Revolution, the American Revolution, and the English Civil War. Deal with Hitler s Third Reich, Vikings, etc. At the start of each game players may choose a level of difficulty . . . the more difficult, the greater the time pressure. To suceed you must build alliances and struggle with the ruling powers. Each game is unique. $24.95

SUPER STAR BASEBALL

ALL TIME SUPER STAR BASEBALL Sample Lineup

B. Ruth	T. Williams
L. Gehrig	J. Foxx
J. DiMaggio	H. Greenberg
J. Jackson	R. Hornsby
G. Sisler	H. Wilson
S. Musial	B. Terry
T. Cobb	M. Mantle
W. Mays	H. Aaron
C. Young-P	W. Johnson-P

SUPER STAR BASEBALL Sample Lineup

D. Parker	J. Rice
W.Stargell	H. Aaron
W. Mays	L. Brock
P. Rose	R. Carew
O. Cepeda	H. Killebrew
C. Yazstremski	R. allen
W. McCovey	R. Leflore
R. Jackson	R. Zisk
G. Brett	B. Madlock
R. Guidry-P	T. Seaver-P

Performance is based on the interaction of actual batting and pitching data. Game can be played by one or two players with the computer acting as a second player when desired. Players select rosters and lineups and excersize strategic choices including hit and run, base stealing, pinch hitting, intentional walk, etc. Highly realistic, there are two versions, ALL TIME SUPER STAR BASE—BALL, and SUPER STAR BASEBALL featuring players of the current decade. Each includes about 50 players allowing nearly infinite number of roster and lineup possibilities.

$14.95

SWORD OF ZEDEK

Fight to overthrow Ra, The Master of Evil. In this incredible adventure game, you must confront a host of creatures, natural and supernatural. To liberate the Kingdom, alliances must be forged and treasures sought. Treachery, deceit and witchcraft must be faced in your struggles as you encounter wolves, dwarves, elves, dragons, bears, owls, orcs, giant bats, trolls, etc. Each of the 12 treasures will enhance your power, by making invisible, invulnable, more eloquent, more skillful in combat etc., etc., as you explore the realms of geography, both on the surface and underground. Dungeons, temples, castles, mountains etc., are all a part of the fantastic world of Ra. Each game is unique in this spectacular and complex world of fantasy. $24.95

*ALL PROGRAMS AVAILABLE FOR TRS—80, APPLE II & PET

master charge

VISA

KRELL SOFTWARE

Send check or money order to
21 Milbrook Drive, Stony Brook, NY 11790 **(516) 751-5139**

All programs require 16K ● TRS-80 programs require Level II BASIC ● Apple programs require Applesoft BASIC

CIRCLE 219 ON READER SERVICE CARD

at the end of the program give the prefixes and suffixes used to create the variables. They also describe what each section is supposed to do.

Program Details

The program is written in Applesoft, Apple's floating point Basic, and fits in a 16K memory. Translation should be very easy with some exceptions. The diagram routines use color graphics. If your system does not have graphics, delete lines 6000 to 7060. You must also fix lines 220 and 222, since calling a deleted subroutine is an easy way to crash. The program also makes extensive use of logic evaluations within expressions. For example, (A 100) equals one if true, and zero if false. This is a quick and easy way to avoid IF statements. If your system does not have this capability, convert each of these expressions to IF statements. Many of the variables have percent signs following them. This is Applesoft's way of saying 'integer variable.' I used them to keep fractions out of the numbers printed in the status report. If your system can easily control the number of decimal places printed, forget the percent signs.

Before I could get the emergency coolant on, the reactor went out of control and disaster struck. Too bad, but I deserved it.

In Applesoft, the PEEK in line 910 returns the vertical position of the cursor. If you can't find your cursor, you will have to think up another way to input the control variable. Finally, the instructions and the status report are made to fit a 40 by 24 character screen. These can be easily modified to fill a wider screen.

I have some final words to engineers, nuclear technicians and other qualified readers. No, I have never seen a real power plant that was designed like this. Yes, I know it takes much less than a day for a reactor to respond to changes in coolant flow and control rod position. Besides, who ever heard of a reactor with only one emergency cooling system, and that one with a limited supply of coolant? And, blasphemy of blasphemies, no SCRAM mechanism? I am sure your list of discrepancies is far more complete. What I have tried to do is to incorporate characteristics and responses of a simplified and idealized nuclear power plant into a computer simulation game. Several concessions to accuracy were made in order to create a simulation that would provide realistic responses to simple inputs and make an interesting and instructive game. □

```
10  HOME
20  PRINT  SPC( 8)"APPLE NUCLEAR POWER PLANT"
30  PRINT  SPC( 9)"BY STEPHEN R. BERGGREN
40  PRINT
50  PRINT "THIS PROGRAM SIMULATES THE OPERATION OF"
60  PRINT "A NUCLEAR POWER REACTOR.  THE OBJECT"
70  PRINT "IS TO OPERATE THE PLANT AT A MAXIMUM"
80  PRINT "AVERAGE POWER OUTPUT WITHOUT CAUSING"
90  PRINT "A REACTOR MELTDOWN."
100  PRINT
110  PRINT "THE CONTROL RODS ADJUST THE AMOUNT OF"
120  PRINT "HEAT PRODUCED BY THE REACTOR.  PRIMARY"
130  PRINT "COOLANT TRANSFERS THIS HEAT TO THE HEAT"
140  PRINT "EXCHANGER.  SECONDARY COOLANT TRANSFERS"
150  PRINT "HEAT FROM THE HEAT EXCHANGER TO THE"
160  PRINT "TURBINE, WHERE POWER IS PRODUCED, AND"
170  PRINT "FINALLY TO THE COOLING TOWER.  THE"
180  PRINT "EMERGENCY COOLANT IS USED TO HELP SHUT"
190  PRINT "DOWN THE REACTOR WHEN OTHER SYSTEMS"
200  PRINT "FAIL.  UNLIKE THE OTHER COOLANTS, "
210  PRINT "EMERGENCY COOLANT IS NOT RECYCLED."
220  PRINT : INPUT "ENTER 'D' TO SEE REACTOR DIAGRAM    ENTER 'I' FOR WORKIN
G INSTRUCTIONS      ENTER 'S' TO START OPERATION     ";A$
221  IF A$ = "D" THEN  GOSUB 6000: GOTO 220
222  IF A$ = "S" THEN 390
225  TEXT : HOME
230  PRINT "THE CONTROLS ARE OPERATED BY TYPING IN"
235  PRINT "THE DESIRED CONTROL ROD SETTING AND"
240  PRINT "FLOW RATES.(USE VALUES FROM 0 TO 100)"
245  PRINT "IF NO ENTRY IS MADE, THE VALUES WILL"
250  PRINT "NOT CHANGE.  USE THE SPACE BAR TO STEP"
255  PRINT "TO THE DIFFERENT FUNCTIONS.  WHEN THE"
260  PRINT "DESIRED ENTRIES HAVE BEEN MADE, USE THE"
265  PRINT "'RETURN' KEY TO ADVANCE TO THE NEXT DAY."
270  PRINT "THE REACTOR CAN BE OPERATED UNTIL A"
275  PRINT "MELTDOWN OCCURS OR THE REACTOR FUEL IS"
280  PRINT "EXHAUSTED.  THE FUEL WILL LAST FOR"
285  PRINT "ABOUT 100 TO 150 DAYS.  WHEN THE FUEL"
290  PRINT "IS EXHAUSTED, YOUR PERFORMANCE WILL BE"
295  PRINT "EVALUATED.
298  PRINT : INPUT "   (PRESS RETURN TO CONTINUE)";A$: HOME
300  PRINT : PRINT "IF YOU WANT TO REPAIR DAMAGE OR REPLACE"
305  PRINT "COOLANT, BRING THE REACTOR TEMPERATURE"
310  PRINT "DOWN BELOW 100 AND SHUT OFF THE COOLANT"
315  PRINT "FLOWS.  THIS WILL CAUSE AN AUTOMATIC"
320  PRINT "MAINTENANCE SHUTDOWN AND ALL COOLANT"
325  PRINT "WILL BE REPLENISHED AND REPAIRS MADE."
330  PRINT "THE GREATER THE DAMAGE, THE LONGER THE"
335  PRINT "REPAIRS WILL TAKE."
340  PRINT
350  PRINT "      WARNING: THIS POWER PLANT HAS"
360  PRINT "      NO AUTOMATIC SAFETY DEVICES!!"
370  PRINT
380  GOTO 220
390  REM  INITIATE
400  GOSUB 2000
410 RH = 0
420 RL = 0
430 DAY% = 0
440 TT = 0
450 DMGE% = 0
455 A% = 0:A1% = 0:A2% = 0
460  REM WRITE REPORT
470  TEXT : HOME
475 DAY% = DAY% + 1
480  PRINT  SPC( 7)"APPLE NUCLEAR POWER PLANT"
490  PRINT  SPC( 8)"STATUS REPORT - DAY ";DAY%
500  PRINT
510  PRINT "WARNINGS:"
520  IF RT% > 800 THEN  PRINT " REACTOR OVERHEATED":RD% = RD% + 1 + (RT%
     > 850) + (RT% > 900) + 2 * (RT% > 950):PD% = PD% + 1:ED% = ED% + 1
     + (RT% > 850)
530  IF XT% > 500 THEN  PRINT " HEAT EXCHANGER OVERHEATED":XD% = XD% + 1
     + (XT% > 600):PD% = PD% + 1:SD% = SD% + 1
540  IF GO% > 2000 THEN  PRINT " TURBINE OVERLOADED":TD% = TD% + 1 + (GO%
     > 2500  ):SD% = SD% + 1
550  IF CT% > 300 THEN  PRINT " COOLING TOWER OVERHEATED":SD% = SD% + 1
560  IF GO% < 1000 THEN  PRINT " POWER OUTPUT LOW"
570  IF EV% < 200 THEN  PRINT " EMERGENCY COOLANT LOW"
580  IF PV% < 100 THEN  PRINT " PRIMARY COOLANT LOW":PD% = PD% + 1
590  IF SV% < 100 THEN  PRINT " SECONDARY COOLANT LOW":SD% = SD% + 1
600  PRINT
610  PRINT "DAMAGE:"
620  IF RD% > 3 THEN  PRINT " REACTOR CORE DAMAGED"
630  IF PD% > 4 THEN  PRINT " PRIMARY COOLANT LEAK - ";PD%;"/DAY":PV% =
     (PV% - P
D%) * ((PV% - PD%) > 0)
640  IF SD% > 4 THEN  PRINT " SECONDARY COOLANT LEAK - ";SD%;"/DAY":SV% =
```

Economic and Ecology Simulations

The Ecology Simulations series are a unique educational tool. They are based on "simulation models" developed by the Huntington Two Computer Project at the State University of New York at Stony Brook under the direction of Dr. Ludwig Braun. The programs and accompanying documentation are written for self-teaching or classroom use and include background material, sample exercises and study guides. Graphic displays were specially developed by Jo Ann Comito at SUNY and Ann Corrigan at Creative Computing. The Ecology Simulations packages are a remarkable educational application of micro-computers.

Ecology Simulations-1, CS-3201 (16K)

1. Pop

The POP series of models examines three different methods of population projection, including exponential, S-shaped or logistical, and logistical with low density effects. At the same time the programs introduce the concept of successive refinement of a model, since each POP model adds more details than the previous one.

2. Sterl

STERL allows you to investigate the effectiveness of two different methods of pest control—the use of pesticides and the release of sterile males into the fly population. The concept of a more environmentally sound approach versus traditional chemical methods is introduced. In addition, STERL demonstrates the effectiveness of an integrated approach over either alternative by itself.



3. Tag

TAG simulates the tagging and recovery method that is used by scientists to estimate animal populations. You attempt to estimate the bass population in a warm-water, bass-bluegill farm pond. Tagged fish are released in the pond and samples are recovered at timed intervals. By presenting a detailed simulation of real sampling by "tagging and recovery," TAG helps you to understand this process.

4. Buffalo

BUFFALO simulates the yearly cycle of buffalo population growth and decline, and allows you to investigate the effects of different herd management policies. Simulations such as BUFFALO allow you to explore "What if" questions and experiment with approaches that might be disastrous in real life.

Ordering Information

The series is designed for the 16K TRS-80 Level II and is attractively packaged in a vinyl binder with a complete study guide. *Ecology Simulations-I:* disk CS-3501, cassette 3201. *Ecology Simulations-II:* disk CS-3502, cassette CS-3204. *Social and Economic Simulations:* disk CS-3508, cassette CS-3204. At a modest $24.95 each, the series is an affordable necessity.

To order, send payment plus $1.00 shipping and handling to Creative Computing Software, Dept. ACGG, P.O. Box 789-M, Morristown, NJ 07960. For Faster Service, call in your order toll-free to our order hotline 800-631-8112. In NJ call 201-540-0445.

Ecology Simulations-2, CS-3202 (16K)

1. Pollute

POLLUTE focuses on one part of the water pollution problem; the accumulation of certain waste materials in waterways and their effect on dissolved oxygen levels in the water. You can use the computer to investigate the effects of different variables such as the body of water, temperature, and the rate of dumping waste material. Various types of primary and secondary waste treatment, as well as the impact of scientific and economic decisions can be examined.

2. Rats

In RATS, you play the role of a Health Department official devising an effective, practical plant to control rats. The plan may combine the use of sanitation and slow kill and quick kill poisons to eliminate a rat population. It is also possible to change the initial population size, growth rate, and whether the simulation will take place in an apartment building or an entire city.





3. Malaria

With MALARIA, you are a Health Official trying to control a malaria epidemic while taking into account financial considerations in setting up a program. The budgeted use of field hospitals, drugs for the ill, three types of pesticides, and preventative medication, must be properly combined for an effective control program.

4. Diet

DIET is designed to explore the effect of four basic substances, protein, lipids, calories and carbohydrates, on your diet. You enter a list of the types and amounts of food eaten in a typical day, as well as your age, weight, sex, health and a physical activity factor. DIET is particularly valuable in indicating how a diet can be changed to raise or lower body weights and provide proper nutrition.

Social and Economic Simulations CS-3204 (16K)

1. Limits

LIMITS is a micro-computer version of the well known "Limits to Growth" project done at MIT. It contains a model of the world that is built of five subsystems (population, pollution, food supply, industrial output, and resource usage) linked together by six variables: birth rate, death rate, pollution generation, resource usage rate, industrial output growth rate, and food production rate.

2. Market

Market allows two or more people to play the roles of companies who are competing for the market for a particular product: in this case, bicycles.

Each player makes marketing decisions quarterly including the production level, the advertising budget, and the unit price of the product for his/her company.

3. USPop

USPOP allows the user to study many aspects of the United States' human demography (population change) including population growth, age and sex distribution. USPOP makes population projections and investigates the consequences of many different demographic changes.

Power Plant cont'd...

```
     (SU% - SD%) * ((SU% - SD%) > 0)
650  IF ED% > 2 THEN PRINT " EMERGENCY COOLANT LEAK - ";2 * ED%;"/DAY":
     EU% = (E U% - 2 * ED%) * ((EU% - 2 * ED%) > 0)
660  IF PB% THEN PRINT " PRIMARY COOLANT PUMP FAILURE - ";10 * PD% *
     (PD% < 10) + 100 * (PD% > = 10);"%"
670  IF SB% THEN PRINT " SECONDARY COOLANT PUMP FAILURE - ";10 * SD% *
     (SD% < 1 0) + 100 * (SD% > = 10);"%"
680  IF XB% THEN PRINT " HEAT EXCHANGER FAILURE"
690  IF GB% THEN PRINT " TURBINE FAILURE"
700  PRINT
710  IF RD% > 5 THEN PRINT "      MELTDOWN! MELTDOWN! MELTDOWN!":
     GOTO 3000
720  PRINT "INDICATORS:"
730  PRINT " REACTOR TEMP. (MAX 800) ";RT%
740  PRINT " HEAT EXCHANGER TEMP. (MAX 500) ";XT%
750  PRINT " COOLING TOWER TEMP. (MAX 300) ";CT%
760  PRINT " POWER OUTPUT (MAX 2000KW) ";GO%;"KW"
765 KW% = TT / DAY%
770  PRINT " AVERAGE POWER OUTPUT  ";KW%;"KW/DAY
800  PRINT " CONTROL RODS- ";A%
810  PRINT " COOLANTS"
820  PRINT "  EMERGENCY  LEVEL- ";EU%;"  FLOW- ";EF%
830  PRINT "  PRIMARY    LEVEL- ";PU%;"  FLOW- "PF%
840  PRINT "  SECONDARY  LEVEL- ";SU%;"  FLOW- "SF%;
850  IF (100 - RL) < 5 THEN PRINT : PRINT : PRINT "REACTOR FUEL
     EXHAUSTED": GOTO 4000
900  REM GET NEW CONTROL VALUES
910 P =  PEEK (37)
920  VTAB (P - 3)
930  HTAB (20)
950 A2% = A1%:A1% = A%
955 B$ = "": FOR I = 1 TO 4
960  GET A$:Z =  ASC (A$)
965  IF (Z <  > 13 AND Z <  > 32) AND (Z > 57 OR Z < 48) THEN 960
970 B$ = B$ + A$: IF Z = 13 THEN 1170
975  IF Z = 32 THEN 990
980 A% = VAL (B$):A% = A% + (100 - A%) * (A% > 100)
985  PRINT A$;: NEXT I
990  VTAB (P - 1)
1000  HTAB (35)
1005 B$ = "": FOR I = 1 TO 4
1010  GET A$:Z =  ASC (A$)
1015  IF (Z <  > 13 AND Z <  > 32) AND (Z > 57 OR Z < 48) THEN 1010
1020 B$ = B$ + A$: IF Z = 13 THEN 1170
1025  IF Z = 32 THEN 1050
1030 EF% =  VAL (B$):EF% = EF% + (100 - EF%) * (EF% > 100)
1035  IF EF% > EU% THEN EF% = EU%
1040  PRINT A$;: NEXT I
1050  VTAB (P)
1060  HTAB (35)
1065 B$ = "": FOR I = 1 TO 4
1070  GET A$:Z =  ASC (A$)
1075  IF (Z <  > 13 AND Z <  > 32) AND (Z > 57 OR Z < 48) THEN 1070
1080 B$ = B$ + A$: IF Z = 13 THEN 1170
1085  IF Z = 32 THEN 1110
1090 PF% =  VAL (B$):PF% = PF% + (100 - PF%) * (PF% > 100)
1100  PRINT A$;: NEXT I
1110  VTAB (P + 1)
1120  HTAB (35)
1125 B$ = "": FOR I = 1 TO 4
1130  GET A$:Z =  ASC (A$)
1135  IF (Z <  > 13 AND Z <  > 32) AND (Z > 57 OR Z < 48) THEN 1130
1140 B$ = B$ + A$: IF Z = 13 THEN 1170
1145  IF Z = 32 THEN 1165
1150 SF% =  VAL (B$):SF% = SF% + (100 - SF%) * (SF% > 100)
1160  PRINT A$;: NEXT I
1165  HTAB (1): VTAB (P - 3): CALL  - 958: GOTO 800
1170  IF PF% = 0 AND SF% = 0 AND RH < 1 AND RT% < 100 AND A% = 0 THEN
      GOSUB 200 0: HTAB (1): VTAB (24): CALL  - 922: PRINT "
      MAINTENANCE SHUTDOWN - ";MD%;" DAYS": FOR I = 0 TO 5000: NEXT
1180  IF EF% > EU% THEN EF% = EU%
1200  REM DAMAGE ASSESSMENT AND OPERATION CALCULATIONS
1205 EU% = EU% - EF% - 2 * ED% * (ED% > 3)
1210 PD% = PD% + (PF% > 90) * ( RND (20) > .95)
1220 SD% = SD% + (SF% > 90) * ( RND (20) > .92)
1230 PB% = PD% > 5
1240 SB% = SD% > 5
1250  IF PF% > (100 - PD% * 10) AND PB% THEN PF% = (100 - PD% * 10) *
      (100 - PD%  * 10 > 0)
1260  IF SF% > (100 - SD% * 10) AND SB% THEN SF% = (100 - SD% * 10) *
      (100 - SD%  * 10 > 0)
1270 RL = RL + RH / 50
1280 RH = (A% * 30 + A1% * 60 + A2% * 10) / 2500 * (100 - RL)
1300 PH = PF% * (100 * (PU% > 100) + PU% * (PU% <  = 100)) / 350
1310 EH = EF% / 200 * (RT% - 25)
1320 RT% = RT% + RH - EH - PH - 5 * (RT% > 25)
1325 RT% = 25 + (RT% - 25) * (RT% > 25)
1330 XT% = ((RT% - 25) * PF% + (CT% - 25) * SF%) / (PF% + SF% + 1) + 25
```

```
1340  IF XB% THEN XT% = RT% * .8 + 5
1350 SH = SF% * (100 * (PU% > 100) + PU% * (PU% <  = 100)) / 350 *
     (XT% - CT%)
1360  IF XB% THEN SH = SH * .2
1370 GO% = SH / XT% * (XT% - CT%) * 2 / 3
1375  IF GO% > 2600 THEN GO% = 2600
1380 GO% = GO% * (GO% > 0) * (GB% = 0)
1390 CT% = 25 + ((XT% - 25) * (SH - GO%) / (SH + 1) * .75)
1395 CT% = 25 * (CT% <  = 25) + CT% * (CT% > 25)
1400  IF XB% < 1 THEN XB% = (XD% > 2) * ( RND (4) > .9)
1410  IF GB% < 1 THEN GB% = (GD% > 4) * ( RND (4) > .9)
1420 TT = TT + GO%
1430  GOTO 470
2000  REM MAINTENANCE REPAIR SUBROUTINE
2010 EU% = 300
2020 PU% = 120
2030 SU% = 120
2040 RT% = 25
2050 XT% = 25
2060 CT% = 25
2070 DMGE% = DMGE% + 2 * RD% + ED% + PD% + XD% + SD% + GD%
2080 MD% = 5 + 3 * (10 * (RD% > 3) + (ED% > 3) + (PD% > 3) + (SD% > 3)
     + 2 * PB%  + 2 * SB% + 3 * XB% + 3 * GB%):DAY% = DAY% + MD%
2090 RD% = 0
2100 ED% = 0
2110 PD% = 0
2120 XD% = 0
2130 SD% = 0
2140 GD% = 0
2150 PB% = 0
2160 SB% = 0
2170 XB% = 0
2180 GB% = 0
2190 EF% = 0:PF% = 0:SF% = 0
2195 GO% = 0
2200  RETURN
3000  REM  MELTDOWN ENDING
3010  PRINT
3020  IF RD% > 6 THEN 3100
3030  PRINT "THE REACTOR CORE HAS BEEN DISTROYED BY"
3040  PRINT "UNCONTROLLED THERMAL RUNAWAY.  HOWEVER,"
3050  PRINT "THE CONTAINMENT BUILDING HAS NOT YET"
3060  PRINT "RUPTURED.
3070  PRINT
3080  PRINT "INITIATE YOUR EVACUATION PLAN."
3090  GOTO 5000
3100  PRINT "THE REACTOR CORE HAS MELTED DOWN AND"
3110  PRINT "PRODUCED A STEAM EXPLOSION.  THE"
3120  PRINT "CONTAINMENT BUILDING HAS RUPTURED."
3130  PRINT "LETHAL RADIOACTIVE GASES AND DEBRIS"
3140  PRINT "HAVE ESCAPED."
3150  PRINT
3160  PRINT "INITIATE YOUR EVACUATION AND RADIATION"
3170  PRINT "CLEANUP PLANS AND GET MEDICAL"
3180  PRINT "ASSISTANCE."
3190  GOTO 5000
4000  REM  EVALUATION OF GAME RESULTS
4010  PRINT
4020  PRINT "OVER A PERIOD OF ";DAY%;" DAYS, YOU HAVE"
4030  PRINT "PRODUCED AN AVERAGE POWER OUTPUT OF"
4040  PRINT KW%;" KILOWATTS PER DAY."
4050 AKW% = 1 + (KW% > 1000) + (KW% > 1200) + (KW% > 1500) + (KW% > 1800)
4060  PRINT
4070  PRINT "YOUR AVERAGE POWER PRODUCTION RATE IS"
4080  ON AKW% GOTO 4090,4100,4110,4120,4140
4090  PRINT "HORRIBLE! FIND A LESS DEMANDING JOB.": GOTO 4200
4100  PRINT "WAY BELOW YOUR AREA'S POWER NEEDS.": GOTO 4200
4110  PRINT "ADEQUATE. YOU COULD DO BETTER.": GOTO 4200
4120  PRINT "EXCELLENT! POWER COSTS IN YOUR AREA"
4130  PRINT "WILL NOT BE INCREASED.": GOTO 4200
4140  PRINT "NEAR THE MAXIMUM!  POWER COSTS IN YOUR"
4150  PRINT "AREA WILL DROP SIGNIFICANTLY."
4200  REM DAMAGE EVALUATION
4210  PRINT
4215  GOSUB 2000
4220 D% = 1 + (DMGE% > 10) + (DMGE% > 20) + (DMGE% > 30)
4230  PRINT "THE EQUIPMENT DAMAGE SUSTAINED DURING"
4240  PRINT "THIS PERIOD WAS ";
4250  ON D% GOTO 4260,4270,4280,4290
4260  PRINT "VERY LIGHT.": GOTO 5000
4270  PRINT "MODERATE.": GOTO 5000
4280  PRINT "HEAVY.": GOTO 5000
4290  PRINT "SEVERE."
5000  REM END
5010  PRINT
5020  PRINT "WOULD YOU LIKE TO TRY AGAIN? (Y OR N)";
5030  INPUT A$
5040  IF A$ = "" THEN 5030
5050  IF A$ = "Y" THEN  GOSUB 2000: GOTO 390
5060  HOME
5070  END
5100 B$ = ""
```

Power Plant cont'd...

```
5105  FOR I = 1 TO 4
5110  GET A$
5130  IF  ASC (A$) <  > 32 THEN 5140
5134  IF B$ = "" THEN  RETURN
5136 OUT% =  VAL (B$)
5138  RETURN
5140  IF  ASC (A$) = 13 THEN  POP : GOTO 1170
5150 B$ = B$ + A$
5160  PRINT A$;
5170  NEXT I
5180  RETURN
6000  GR : COLOR= 15: FOR I = 0 TO 39: HLIN 0,39 AT I: NEXT I
6005 DE = 6000
6010  HOME : VTAB 23
6020  PRINT "  THIS IS THE REACTOR VESSEL"
6030  RESTORE
6035  COLOR= 1
6040  FOR I = 1 TO 29
6050  READ X1,X2,Y
6060  HLIN X1,X2 AT Y
6070  NEXT I
6080  DATA 7,9,6,15,17,6,6,18,7,5,19,8,5,7,9,17,19,9,5,6,10,18,19,10,5,6,
      11,18,19,11,5,6,12,18,19,12,5,6,13,18,19,13,5,6,14
6090  DATA 18,19,14,5,6,15,18,19,15,5,6,16,18,19,16,5,6,17,18,19,17,5,6,
      18,18,19 ,18,5,7,19,17,19,19,6,18,20,7,17,21,8,16,22
6100  COLOR= 0
6110  HLIN 13,14 AT 6
6120  COLOR= 12
6130  HLIN 14,15 AT 5
6140  HLIN 14,16 AT 4
6150  HLIN 15,16 AT 3
6160  FOR I = 1 TO DE: NEXT I
6170  VTAB 23
6180  PRINT "  THIS IS THE REACTOR CORE      "
6190  COLOR= 8
6200  FOR I = 9 TO 15
6210  VLIN 11,17 AT I
6220  NEXT I
6230  FOR I = 1 TO DE: NEXT I
6240  VTAB 23
6250  PRINT "  THESE ARE THE CONTROL RODS  "
6260  COLOR= 13
6270  VLIN 2,17 AT 11
6280  VLIN 2,17 AT 13
6290  FOR I = 1 TO DE: NEXT I
6300  VTAB 23
6310  PRINT " THE EMERGENCY COOLANT CAN COOL THE"
6320  PRINT " REACTOR IN AN EMERGENCY."
6330  COLOR= 2
6340  FOR I = 1 TO 36
6350  READ Y,X
6360  PLOT X,Y
6370  FOR J = 1 TO 200: NEXT J
6380  NEXT I
6390  DATA 4,2,4,4,5,2,5,3,5,4,6,2,6,3,6,4,7,3,8,3,9,3,10,3,11,3,12,3,
      12,4,12,5, 12,6,12,7,12,8,12,9
6400  DATA 13,9,14,9,15,9,16,9,16,8,16,7,16,6,16,5,16,4,16,3,17,3,18,3,
      19,3,20,3 ,22,3,24,3
6410  FOR I = 1 TO DE: NEXT I
6420  HOME : VTAB 23
6430  PRINT " THE PRIMARY COOLANT CARRIES HEAT FROM"
6440  PRINT " THE REACTOR CORE TO THE HEAT EXCHANGER"
6450  FOR I = 1 TO 52
6460  READ Y,X
6470  PLOT X,Y
6480  FOR J = 1 TO 200: NEXT J
6490  NEXT I
6500  FOR I = 1 TO DE: NEXT I
6510  DATA 4,25,4,27,5,25,5,26,5,27,6,25,6,26,6,27,7,26,8,26,9,26,10,26,
      11,26,12 ,26,12,25,12,24,12,23,12,22,12,21,12,20,12,19
6515  DATA 12,18,12,17,12,16,12,15,13,15,14,15,15,15,16,15,16,16,16,
      17,16,18
6520  DATA  16,19,16,20,16,21,16,22,16,23,16,24,16,25,16,26,16,27,16,28,
      16,29,16 ,30,15,30,14,30,13,30,13,30,12,30,12,29,12,28,12,27
6540  HOME : VTAB 23
6550  PRINT " THIS IS THE HEAT EXCHANGER"
6560  COLOR= 5
6570  HLIN 28,34 AT 10
6580  VLIN 10,18 AT 34
6590  HLIN 28,34 AT 18
6600  VLIN 10,18 AT 28
6605  COLOR= 2: PLOT 28,12: PLOT 28,16: COLOR= 5
6610  FOR I = 1 TO DE: NEXT I
6620  VTAB 23
6630  PRINT " THIS IS THE GENERATOR TURBINE"
6640  HLIN 5,18 AT 30
6650  VLIN 30,36 AT 18
6660  HLIN 5,18 AT 36
6670  VLIN 30,36 AT 5
```

```
6680  COLOR= 0
6690  HLIN 2,17 AT 33
6700  FOR I = 7 TO 15 STEP 2
6710  PLOT I,34: PLOT I + 1,32
6720  NEXT I
6730  FOR I = 1 TO DE: NEXT I
6740  VTAB 23
6750  PRINT " THIS IS THE COOLING TOWER           "
6760  COLOR= 5
6770  VLIN 23,25 AT 24
6780  VLIN 23,25 AT 36
6790  VLIN 25,26 AT 25
6800  VLIN 25,26 AT 35
6810  VLIN 26,28 AT 26
6820  VLIN 26,28 AT 34
6830  VLIN 28,36 AT 27
6840  VLIN 28,36 AT 33
6850  PLOT 34,36
6860  PLOT 26,36
6870  HLIN 25,35 AT 38
6880  FOR I = 1 TO DE: NEXT I
6890  VTAB 23
6900  PRINT " THE SECONDARY COOLANT CARRIES HEAT"
6910  PRINT " FROM THE HEAT EXCHANGER TO THE "
6920  PRINT " TURBINE AND THEN TO THE COOLING TOWER"
6925  COLOR= 2
6930  FOR I = 1 TO 123
6940  READ Y,X
6950  PLOT X,Y
6960  FOR J = 1 TO 200: NEXT J
6970  NEXT I
6980  DATA 4,35,4,37,5,35,5,36,5,37,6,35,6,36,6,37,7,36,8,36,9,36,10,36,
      11,36,12,36,12,35,12,34,12,33,12,32,13,32,14,32,15,32,16,32
6990  DATA 16,33,16,34,16,35,16,36,17,36,18,36,19,36,20,36,20,35,20,34,
      20,33,20, 32,20,31,20,30,20,29,20,28,20,27,20,26,20,25,20,24,20,23,
      20,22,20,21
7000  DATA 21,21,22,21,23,21,24,21,25,21,26,21,27,21,27,20,27,19,27,18,
      27,17,27, 16,27,15,27,14,27,13,27,12,27,11,27,10,27,9,27,8,27,7
7010  DATA 28,7,29,7,30,7,31,7,32,7,34,10,32,13,34,16,35,16,35,17,35,18,
      35,19,35 ,20,35,21,35,22,35,23,35,24,35,25,35,26,35,27,35,28
7020  DATA 34,28,34,29,34,30,35,30,35,31,35,32,34,32,34,33,34,34,34,35,
      34,36,34, 37,34,38,33,38,32,38,31,38,30,38,29,38,28,38,27,38,26,38,
      25,38,24,38,23,38
7030  DATA 22,38,21,38,20,38,19,38,18,38,17,38,16,38,15,38,14,38,13,38,
      12,38,12, 37
7040  HOME : VTAB 23
7060  RETURN
9000  REM VARIABLE PREFIXES
9010  REM A-CONTROL RODS, C-COOLING TOWER, E-EMERGENCY COOLANT,
      G-TURBINE, P-PRIMARY COOLANT, R-REACTOR, S-SECONDARY COOLANT,
      X-HEAT EXCHANGER
9020  REM VARIABLE SUFFIXES
9030  REM B-BROKEN, D-DAMAGE, F-FLOW RATE, H-HEAT FLOW, L-LIFE, O-OUTPUT,
      T-TEMPERATURE, V-VOLUME
9040  REM OTHER VARIABLES TOT-TOTAL POWER OUTPUT, KW-AVERAGE POWER
      OUTPUT, DAY-DAY OF OPERATION, DMGE-TOTAL EQUIPMENT DAMAGE
9050  REM PROGRAM DISCRIPTION BY LINE NUMBER
9060  REM 10-220 INTRODUCTION
9070  REM 225-380 INSTRUCTIONS
9080  REM 390-455 VARIABLE INITIATION
9090  REM  460-850 WRITE REPORT AND ASSESS DAMAGE
9100  REM  900-1165 INPUT NEW CONTROL VARIABLES
9110  REM 1170 MAINTENANCE SHUTDOWN EVALUATION
9120  REM 1200-1260 PUMP FAILURE ASSESSMENT
9130  REM 1270-1430 PLANT OPERATING ALGORITHMS
9140  REM 2000-2200 MAINTENANCE SHUTDOWN SUBROUTINE
9150  REM 3000-3190 MELTDOWN ENDING
9160  REM 4000-4290 EVALUATION OF GAME RESULTS
9170  REM 5000-5070 END
9180  REM 6000-7060 PLANT DIAGRAM SUBROUTINE
9190  REM 9000-9190 REMARKS
9200  REM  APPLE NUCLEAR POWER PLANT
9210  REM  BY STEPHEN R BERGGREN


RUN
          APPLE NUCLEAR POWER PLANT
            BY STEPHEN R. BERGGREN

THIS PROGRAM SIMULATES THE OPERATION OF
A NUCLEAR POWER REACTOR.  THE OBJECT
IS TO OPERATE THE PLANT AT A MAXIMUM
AVERAGE POWER OUTPUT WITHOUT CAUSING
A REACTOR MELTDOWN.

THE CONTROL RODS ADJUST THE AMOUNT OF
HEAT PRODUCED BY THE REACTOR.  PRIMARY
COOLANT TRANSFERS THIS HEAT TO THE HEAT
EXCHANGER.  SECONDARY COOLANT TRANSFERS
HEAT FROM THE HEAT EXCHANGER TO THE
TURBINE, WHERE POWER IS PRODUCED, AND
FINALLY TO THE COOLING TOWER.
```

Power Plant cont'd...

```
THE EMERGENCY COOLANT IS USED TO HELP SHUT
DOWN THE REACTOR WHEN OTHER SYSTEMS
FAIL.  UNLIKE THE OTHER COOLANTS,
EMERGENCY COOLANT IS NOT RECYCLED.

ENTER 'D' TO SEE REACTOR DIAGRAM      ENTER 'I' FOR WORKING INSTRUCTIONS
ENTER 'S' TO START OPERATION
THE CONTROLS ARE OPERATED BY TYPING IN
THE DESIRED CONTROL ROD SETTING AND
FLOW RATES.(USE VALUES FROM 0 TO 100)
IF NO ENTRY IS MADE, THE VALUES WILL
NOT CHANGE.  USE THE SPACE BAR TO STEP
TO THE DIFFERENT FUNCTIONS.  WHEN THE
DESIRED ENTRIES HAVE BEEN MADE, USE THE
'RETURN' KEY TO ADVANCE TO THE NEXT DAY.
THE REACTOR CAN BE OPERATED UNTIL A
MELTDOWN OCCURS OR THE REACTOR FUEL IS
EXHAUSTED.  THE FUEL WILL LAST FOR
ABOUT 100 TO 150 DAYS.  WHEN THE FUEL
IS EXHAUSTED, YOUR PERFORMANCE WILL BE
EVALUATED.

    (PRESS RETURN TO CONTINUE)

IF YOU WANT TO REPAIR DAMAGE OR REPLACE
COOLANT, BRING THE REACTOR TEMPERATURE
DOWN BELOW 100 AND SHUT OFF THE COOLANT
FLOWS.  THIS WILL CAUSE AN AUTOMATIC
MAINTENANCE SHUTDOWN AND ALL COOLANT
WILL BE REPLENISHED AND REPAIRS MADE.
THE GREATER THE DAMAGE, THE LONGER THE
REPAIRS WILL TAKE.

      WARNING: THIS POWER PLANT HAS
      NO AUTOMATIC SAFETY DEVICES!!
```




```
ENTER 'D' TO SEE REACTOR DIAGRAM   ENTER 'I' FOR WORKING INSTRUCTIONS
ENTER 'S' TO START OPERATION        S
        APPLE NUCLEAR POWER PLANT
          STATUS REPORT - DAY 1

WARNINGS:
 POWER OUTPUT LOW

DAMAGE:

INDICATORS:
 REACTOR TEMP. (MAX 800) 25
 HEAT EXCHANGER TEMP. (MAX 500) 25
 COOLING TOWER TEMP. (MAX 300) 25
 POWER OUTPUT (MAX 2000KW) 0KW
 AVERAGE POWER OUTPUT  0KW/DAY
 CONTROL RODS- 0
 COOLANTS
  EMERGENCY   LEVEL- 300  FLOW- 0
  PRIMARY     LEVEL- 120  FLOW- 0
  SECONDARY   LEVEL- 120  FLOW- 01
        STATUS REPORT - DAY 2

WARNINGS:
 POWER OUTPUT LOW

DAMAGE:

INDICATORS:
 REACTOR TEMP. (MAX 800) 26
 HEAT EXCHANGER TEMP. (MAX 500) 25
 COOLING TOWER TEMP. (MAX 300) 25
 POWER OUTPUT (MAX 2000KW) 0KW
 AVERAGE POWER OUTPUT  0KW/DAY
 CONTROL RODS- 1
 COOLANTS
  EMERGENCY   LEVEL- 300  FLOW- 0
  PRIMARY     LEVEL- 120  FLOW- 0
  SECONDARY   LEVEL- 120  FLOW- 0100
```

```
        APPLE NUCLEAR POWER PLANT
          STATUS REPORT - DAY 19

WARNINGS:

DAMAGE:
 SECONDARY COOLANT LEAK - 5/DAY

INDICATORS:
 REACTOR TEMP. (MAX 800) 778
 HEAT EXCHANGER TEMP. (MAX 500) 465
```

```
COOLING TOWER TEMP. (MAX 300) 254
POWER OUTPUT (MAX 2000KW) 1858KW
AVERAGE POWER OUTPUT  1478KW/DAY
CONTROL RODS- 9
COOLANTS
 EMERGENCY  LEVEL- 300  FLOW- 0
 PRIMARY    LEVEL- 120  FLOW- 70
 SECONDARY  LEVEL- 105  FLOW- 100
       STATUS REPORT - DAY 20


       APPLE NUCLEAR POWER PLANT
        STATUS REPORT - DAY 23

WARNINGS:
 HEAT EXCHANGER OVERHEATED
 COOLING TOWER OVERHEATED
 POWER OUTPUT LOW
 SECONDARY COOLANT LOW

DAMAGE:
 SECONDARY COOLANT LEAK - 11/DAY
 SECONDARY COOLANT PUMP FAILURE - 100%

INDICATORS:
 REACTOR TEMP. (MAX 800) 783
 HEAT EXCHANGER TEMP. (MAX 500) 667
 COOLING TOWER TEMP. (MAX 300) 327
 POWER OUTPUT (MAX 2000KW) 790KW
 AVERAGE POWER OUTPUT  1487KW/DAY
 CONTROL RODS- 9
 COOLANTS
  EMERGENCY  LEVEL- 300  FLOW- 0
  PRIMARY    LEVEL- 120  FLOW- 70
  SECONDARY  LEVEL- 76  FLOW- 20

       APPLE NUCLEAR POWER PLANT
        STATUS REPORT - DAY 30

WARNINGS:
 POWER OUTPUT LOW
 EMERGENCY COOLANT LOW
 PRIMARY COOLANT LOW
 SECONDARY COOLANT LOW

DAMAGE:
 PRIMARY COOLANT LEAK - 7/DAY
 SECONDARY COOLANT LEAK - 19/DAY
 PRIMARY COOLANT PUMP FAILURE - 70%
 SECONDARY COOLANT PUMP FAILURE - 100%
 HEAT EXCHANGER FAILURE

INDICATORS:
 REACTOR TEMP. (MAX 800) 96
 HEAT EXCHANGER TEMP. (MAX 500) 81
 COOLING TOWER TEMP. (MAX 300) 25
 POWER OUTPUT (MAX 2000KW) 0KW
 AVERAGE POWER OUTPUT  1140KW/DAY
 CONTROL RODS- 0
 COOLANTS
  EMERGENCY  LEVEL- 0  FLOW- 0
  PRIMARY    LEVEL- 82  FLOW- 0
  SECONDARY  LEVEL- 0  FLOW- 0
       MAINTENANCE SHUTDOWN - 32 DAYS
        APPLE NUCLEAR POWER PLANT
         STATUS REPORT - DAY 63

        APPLE NUCLEAR POWER PLANT
         STATUS REPORT - DAY 69

WARNINGS:
 REACTOR OVERHEATED
 TURBINE OVERLOADED

DAMAGE:
 REACTOR CORE DAMAGED
 EMERGENCY COOLANT LEAK - 10/DAY

     MELTDOWN!  MELTDOWN!  MELTDOWN!

THE REACTOR CORE HAS MELTED DOWN AND
PRODUCED A STEAM EXPLOSION.  THE
CONTAINMENT BUILDING HAS RUPTURED.
LETHAL RADIOACTIVE GASES AND DEBRIS
HAVE ESCAPED.

INITIATE YOUR EVACUATION AND RADIATION
CLEANUP PLANS AND GET MEDICAL
ASSISTANCE.

WOULD YOU LIKE TO TRY AGAIN? (Y OR N)?N
```



Weighting For Take off

David L. Phillips

Please note that this program has not been certified by the FAA and is published as a novelty only representing the opinions of the author.

When you fly small aircraft, you learn quickly that you have to pay attention to the weight and distribution of the payload you plan to carry. There are several reasons, all related to the limited carrying capacity of light aircraft.

If the load is too heavy, the plane won't take off, or it won't climb very well if you do manage to horse it off the ground. Or the load might be concentrated toward the rear of the plane, in which case the nose will come up, but uncontrollably, so the plane will climb too steeply and stall out, falling to the ground (a definite no-no!). That gives you the idea.

A pilot also learns that computing weight and balance is a complicated, time-consuming chore, and that tends to make one try to rationalize it away as not being necessary in "obvious" cases. The complications are that one must determine actual weight of various elements: oil, fuel, front passengers, rear passengers and baggage, as well, of course, as the empty weight of the aircraft.

These elements each have a discrete "arm aft datum" depending on their distance from a reference point — the datum line (in the case of my Cherokee

David L. Phillips, 471 Park Lane, State College, PA 16801.



Figure 1

SEND FOR OUR FREE CATALOG

COMPUMART LETS YOU PUT APPLE ON TRIAL

WITH OUR EXCLUSIVE 10-DAY FREE RETURN ON ALL THESE GREAT APPLE COMPUTERS AND ACCESSORIES.

CompuMart carries complete lines of microcomputers from Apple to Zenith, as well as thousands of microcomputer peripherals and accessories. Write for our FREE 36 page catalog.

Apple Computer
We carry the most complete inventory of Apple computers, peripherals, and software. CALL!
Our Christmas Apple Special: Save over $250 on our most popular Apple System. System includes a 48K Apple II, Apple Disk & Controller, and a Sup R Mod RF Modulator.
List: **$2,020**
Compumart Sale Price: **$1,769**
New from Apple for the Apple II:
DOS 3-3 Convert disks to 16 sector format for 23% more storage and faster access **$60**

Apple Plot. The perfect graphic complement for Visicalc. **$70**
Dow Jones News & Quotes **$95**
Adventure (Uses 48K) **$35**
DOS Tool Kit **$75**
Apple Fortran **$200**
Silentype Printer w/Xface **$595**
Visicalc **$149**
Tax Planner **$120**
From Symtech & Info Unlimited
Super Sound Generator.. (mono) **$159**
(stereo) **$259**
Light Pen **$249**
X-10 Controller (plugs into paddle port) **$49**
From Personal Software
Visicalc **$149**
Desk top plan **$99**

New from Videx! — Video Term
80 Col. x 24 line
7 x 9 matrix, plug in compatible board for the Apple II. Price **$325**
without graphics EPROM.
With graphics EPROM ..... **$350.**

New from MUSE
The Voice **$39.95**
Super Text **$99.00**
Address Book **$49.95**
Mountain Hardware — Expansion accessories for your Apple
Introl/X-10 System **$289**
Super Talker **$299**
The Music System **$545**
ROM plus board w/keyboard filter **$199**
Clock Calendar **$280**
16 Channel A to D Converter **$350**
Apple Expansion Chassis **$650**
ROM Writer **$175**
Miscellaneous Apple II Accessories:
Easy Writer (80 col. need Videx) **$249**
Easy Mover **$49**
Easy Mailer **$69**
Dysan Diskettes ..... **ea. $5**
S.S.M. Serial & Parallel Apple Interface **$225**
ABT's Numeric Key Pad **$110**

270 THIRD ST. DEPT 152 **COMPUMART** CAMBRIDGE, MA 02142

TOLL FREE 1-800-343-5504 Master Charge VISA **IN MASS 617-491-2700**

apple computer
Authorized Dealer

CIRCLE 133 ON READER SERVICE CARD

Plane, cont'd...

180, roughly the front of the engine compartment). The propellor, for example, is a small negative number; pilot and front passenger are at 85.5 inches. Weight multipled by the arm aft datum for each element provides the "moment of force" in inch-pounds. Total moment for all elements divided by the total weight gives an overall arm aft datum for the loaded plane, or its "center of gravity."

If the total weight is less than allowable gross weight (2400 pounds in this case), and if the baggage weight is less than 200 pounds (maximum allowed for the Cherokee 180), you still have to determine whether the load is too far forward or rearward — is it within the center of gravity "envelope" specified by the manufacturer (see Figure 1)? For each weight, the chart shows the envelope parameters. At 2400 pounds, for example, the forward limit is 92.1 and the rearward limit is 94.5; at 1650 pounds, these are 84.0 and 95.9.

In the days before pocket calculators, this was a laborious task indeed. You end up adding five- and six-digit numbers and dividing the result by a four-digit number — not a happy task for people who want to be flying airplanes and not being accountants. Even today, doing this job manually takes some thinking and doing (see Figure 2).

On the other hand, the home computer can accomplish the total computation in less than 15 seconds, including the input of four pieces of data (assuming normal typing competence). It will not only tell you the total weight of the loaded plane and whether it is in the CG envelope but also the maximum amount of baggage you can carry to stay within allowable limits. Or you can input the amount of baggage you want to carry and the program will tell you whether it's allowable. (By the way, 50 and 36 gallons are specified because those are convenient in filling the Cherokee's tanks; any number will be calculated.)

Inputs are at lines 110, 120, 140 and 235. Note that the program does not ask for baggage until it calculates whether there is room for any, based on the passenger and fuel inputs. It is possible for it to kick out at line 234 with the warning that "Weight is (XX) pounds over gross without baggage!" A second "over-gross" flag is contained in line 500.

Lines 610 to 830 compare the overall arm aft datum with the allowable limits for the total weight as calculated.

With this program, I find that I actually enjoy working out various permutations of where to place passengers, how much fuel to carry versus payload, etc. That can only enhance the safety factor of weight and balance in small aircraft. It sure makes me feel more comfortable when I load up and take off! □

SAMPLE LOADING PROBLEM
Piper Cherokee 180D

	Weight (lbs)	Arm Aft Datum (inches)	Moment (inch-pounds)
Licensed Empty Weight	1402.0	86.2	120852
Oil (6 quarts)	11.0	32.5	357.5
Pilot and Front Passenger	340.0	85.5	29070
Rear Passengers	340.0	118.1	40154
Fuel (36 gals. — 50 max.)	216.0	95.0	20520
Baggage (200 lbs. max.)	91.0	142.8	12994.8
TOTAL, LOADED AIRCRAFT	2400.0	93.3 (calc.)	223948.3

Figure 2

```
10 REM ** WEIGHT & BALANCE COMPUTATION **
20 REM ** CHEROKEE 180D **
30 REM ** BY DAVID L. PHILLIPS **
40 REM ** VARIABLES DEFINED **
50 REM ** ARM AFT DATUM (IN INCHES): EMPTY WT = EA ** OIL =OA **
 PILOT & FRONT PASSENGER = FA ** REAR PASSENGERS = RA ** BAGGAGE
 = BA ***
55 REM *** MOMENT (INCH/POUNDS): EM=EMPTY WT ** GW=GROSS WT ** O
M=OIL ** FM=FRONT PASSENGERS ** RM=REAR PASSENGERS ** FW=FUEL **
*
60 REM *** PW=TOTAL WT W/OUT BAGGAGE ** OG=WT OVER ALLOWABLE GRO
SS W/OUT BAGGAGE ***
65 REM *** TW=TOTAL WT ** TM=TOTAL MOMENT ***
70 REM *** FW=FUEL WT ** FI=FUEL MOMENT ***
100 EW = 1402
105 CLS:PRINT:PRINT
110 INPUT "WHAT IS COMBINED WEIGHT OF FRONT PASSENGERS";FP
120 INPUT "WHAT IS COMBINED WEIGHT OF REAR PASSENGERS";RP
130 OIL = 11
140 INPUT "HOW MUCH FUEL (50 OR 36 GALLONS)";FU
150 EA = 86.2
160 OA = 32.5
170 FA = 85.5
180 RA = 118.1
190 BA= 142.8
200 EM = EW*EA
205 GW=2400
210 OM = OI*OA
220 FM = FP*FA
230 RM = RP*RA
231 FW = FU * 6
232 PW=EW+FP+RP+FW+OI
233 OG=PW-GW
234 IF PW)2400 PRINT"WEIGHT IS";OG;"POUNDS OVER GROSS WITHOUT BA
GGAGE!":END
235 INPUT "DO YOU HAVE BAGGAGE WEIGHT TO CALCULATE";BC$
236 IF BC$ = "NO" THEN BG=GW-PW:GOTO 240
237 INPUT "WHAT IS THE WEIGHT";BG
240 IF BG)200 THEN BG=200
245 BM=BA*BG
250 GW = 2400
256 FI=FW*95
280 TW = EW + FP + RP + FW + OI + BG
282 IF TW)2400 GOTO 500
285 PRINT:PRINT "MAXIMUM BAGGAGE ALLOWANCE IS";BG;"POUNDS."
286 TM = EM+OM+FM+RM+FI+BM
287 FL=TM/TW
300 IF TW (= 2400 AND TW)2200 GOTO 600
310 IF TW (=2200 AND TW)1975 GOTO 700
320 IF TW (=1975 AND TW)1650 GOTO 800
500 TD = TW-GW:PRINT "TOTAL WEIGHT IS OVER GROSS BY";TD;"POUNDS"
:END
600 PRINT "TOTAL WEIGHT IS";TW "POUNDS."
610 IF FL(89.2 PRINT "CG IS BEYOND FORWARD LIMIT!":END
620 IF FL)95.9 PRINT "CG IS BEYOND REARWARD LIMIT!":END
630 IF FL=)89.2 AND FL(=95.9 PRINT "CG IS IN ENVELOPE.":END
700 PRINT "TOTAL WEIGHT IS";TW;"POUNDS."
710 IF FL(89.2 PRINT "CG IS BEYOND FORWARD LIMIT!":END
720 IF FL)95.9 PRINT "CG IS BEYOND REARWARD LIMIT!":END
730 IF FL=)85.9 AND FL(=95.9 PRINT "CG IS IN ENVELOPE.":END
800 PRINT "TOTAL WEIGHT IS";TW;" POUNDS."
810 IF FL(84 PRINT "CG IS BEYOND FORWARD LIMIT!":END
820 IF FL)95.9 PRINT "CG IS BEYOND REARWARD LIMIT:END
830 IF FL=)84.0 AND FL(=95.9 PRINT "CG IS IN ENVELOPE.":END
999 END
```

PET to NEC and CENTRONICS PRINTER ADAPTER

LOWEST COST COMPLETE INTERFACE ON THE MARKET

Simple to use — low cost — designed for NEC 5530 Spinwriter and Centronics parallel printers. Works with WORDPRO and other software. Switch for upper-lower case conversion or upper case only.

Plugs into the PET and into the printer — all cables and connectors included — extra IEEE connector for Commodore disk drives.

Uses BASIC PRINT statements — no machine code needed.

Device address selectable — works with other peripherals.

$129 complete — compare to others at $225.

Generous dealer discounts.

Assembled and tested. Our usual 30 day money back trial period applies.

Order direct or contact your local computer store.

VISA and M/C accepted — send account number, expiration date and sign order.
Add $3 per order for shipping and handling — foreign orders add 10% for air postage.
Mention this magazine with your order and deduct 2%

CmC

Connecticut microComputer, Inc.
34 Del Mar Drive, Brookfield, CT 06804
203 775-4595 TWX: 710 456-0052

PRINTER PRICES DROPPED!

Model 730 ..... **$649**
Parallel Interface (reg. $795)
Upper & Lower Case
100 cps — 80 character line
5 x 7 Free Flight Ballistic Head
Roll, Single-Sheet, & Tractor Feed Paper

Model 737 ..... **$849**
Proportional Spacing (reg. $995)
Right Justification
Underline & Expanded Print
Bidirectional Paper Motion
(for superscript and subscript)
High Density Dot Matrix
(N x 9 free flight print head)
(18 possible horizontal dot places)
Roll, Single-Sheet, & Tractor Feed Paper

Computerware Offers:

- Full Factory Warranty
- Immediate Delivery
- Dependability - as a stocking Centronics distributor for 2 yrs
- The latest models at affordable prices

TO ORDER
Phone orders are invited. Use VISA, Master Charge, or send cashiers check or money order drawn on a U.S. bank. Add shipping and handling (2% for 730, 4% for 704) or printer will be sent freight C.O.D.

COMPUTERWARE
1512 Encinitas Blvd., Box 668
Encinitas, CA 92024
(714) 436-3512

CIRCLE 125 ON READER SERVICE CARD

DR. DALEY OFFERS SOFTWARE FOR EVERYONE

DATA BASE

The data base package allows total user control over the contents of each entry in the file. Features user selectable record size from 5 to 242 characters per record, statistical and plotting package, output with WORDPRO files or printer. Includes full user definable output formatting. With optional indexing routine can produce a comprehensive index of a data set.

$299.95
Index 99.95

MAIL LIST

This powerful mailing list package features a variety of options for producing labels. It includes user defined file structure and label format. Label format can list to the printer or to WORDPRO format files.

$159.95

SOFTWARE LIBRARY

Hundreds of schools and individuals have purchased this package for use as an educational tool or just plain fun. It contains 50 (yes fifty!) programs. This ranges from our famous TREK 3 and horse race to fun learning programs for children to checkbook and a micro mail list program with lots in between. At about $1.40 per program how can you miss?

Cassette $69.95
Diskette 79.95
For APPLE II or PET

For PET or CBM 2000 or 8000 series with 32K memory please specify your machine configuration.

Charge to your MC/VISA

master charge THE INTERBANK CARD

VISA

DR. DALEY'S SOFTWARE

425 Grove, Berrien Springs, Michigan 49103
Phone (616) 471-5514 Sunday-Thursday noon to 9 p.m. Eastern Time

CIRCLE 196 ON READER SERVICE CARD



WEATHER STATION

Paul Raymer

The most pressing problem the average computer owner faces is the weather. Some folks may feel that developing new algorithms, testing out logic problems, running simulation and adventure games or performing complex mathematical tasks have a greater priority, but when I asked the two people I know who have computers, they agreed with me, it *was* weather.

The following "Weather Station" program will bring your computer in touch with the real world, without expensive electronic coupling devices or complex meteorological equipment. No hardware modifications to your computer will be required.

You will need only a plain white piece of paper, approximately 8½" x 11" (21.59 x 27.94 cm) and a pencil and a pad for writing down certain scientific data. No prior knowledge of weather forecasting is required, but such knowledge may prove to be helpful.

Although this program is written for the Apple II in Applesoft Basic, it can easily be translated to any Microsoft Basic dialect with a few dozen simple, but tedious, changes.

The program and listing is restricted to personal use only and may not be used by local radio and/or television stations for forecasting the weather, without permission. □

Paul Raymer, P.O. Box 42831, Las Vegas, NV 89104.



```
]PR#0
]PRINT""
]LIST
100  REM
110  REM  ***********************
120  REM  *                     *
130  REM  * WEATHER  STATION    *
140  REM  *                     *
150  REM  *   PAUL RAYMER       *
160  REM  *    POB 42831        *
170  REM  * LAS VEGAS NEVADA    *
180  REM  *       89104         *
190  REM  *                     *
200  REM  ***********************
210  REM
220  REM  I/XXIX/MCMLXXX
230  REM
240  REM  THIS PRINTS THE TITLE NEATLY
250  REM
260  TEXT : HOME : CLEAR
270  VTAB 10: HTAB 12: PRINT "WEATHER STATION"
280  FOR M = 1 TO 2000: NEXT M
290  CALL  - 936
300  REM
310  REM  INSTRUCTIONS FOR USE
320  REM
330  PRINT "YOU NOW HAVE THE ABILITY TO INTERFACE"
340  PRINT "YOUR COMPUTER WITH THE OUTSIDE WORLD.": PRINT
350  PRINT "TAKE AN ORDINARY SHEET OF PAPER ABOUT"
```

```
360  PRINT "8-1/2 X 11 (ORDINARY TYPING PAPER WILL"
370  PRINT "DO) AND PLACE IT OUTDOORS FOR FIVE"
380  PRINT "MINUTES.": PRINT
390  PRINT "THE COMPUTER WILL NOW GO INTO A HOLDING"
400  PRINT "PATTERN FOR ABOUT FIVE MINUTES OR SO..."
410  FOR X = 1 TO 10000: NEXT X
420  CALL  - 936: FOR X = 1 TO 5: PRINT  CHR$ (7): NEXT X
430  PRINT "WHEN READY PRESS SPACE BAR TO GET THE "
440  PRINT "WEATHER REPORT ";: GET A$
450  CALL  - 936: FOR X = 1 TO 1000: NEXT X
460  REM
470  REM  HUMAN INTERACTION WITH REFERENCE MATERIAL
480  REM
490  PRINT "PLEASE ANSWER THE FOLLOWING QUESTIONS"
500  REM
510  REM  DELAY LOOPS GIVING TIME FOR HUMANS TO THINK
520  REM
530  GOSUB 1170
540  PRINT "WITH EXTREME ACCURACY TO INSURE MOST"
550  GOSUB 1170
560  PRINT "SCIENTIFIC RESULTS.": PRINT
570  GOSUB 1170
580  GOSUB 1210
590  INPUT "WAS THE PAPER STILL OUTSIDE? ";S$
600  GOSUB 1170
610  GOSUB 1210
620  INPUT "WAS THE PAPER WET?";R$
630  GOSUB 1170
640  GOSUB 1210
650  INPUT "DID THE PAPER MOVE?";W$
660  GOSUB 1170
670  GOSUB 1210
680  REM
690  REM  NOTE CLEVER USE OF 'IF' STATEMENT
700  REM
710  IF  LEFT$ (W$,1) = "Y" THEN  PRINT "IN WHICH DIRECTION? ";: INPUT D$
720  GOSUB 1170
730  GOSUB 1210
740  IF  LEN (D$) > 0 THEN  PRINT "HOW FAR? ";: INPUT F$
750  GOSUB 1170
760  GOSUB 1210: GOSUB 1210: CALL  - 936
770  REM
780  REM  USE OF FOLLOWING SLOW PRINTOUT OPTIONAL WITH SKILL IN UNDERSTAND
     ING METEOROLOGICAL INFORMATION
790  REM
800  SPEED= 100
810  PRINT "HERE IS TODAY'S WEATHER REPORT BASED ON"
820  PRINT "SCIENTIFIC DATA YOU HAVE ENTERED INTO"
830  PRINT "THE COMPUTER...": PRINT
840  REM
850  REM  DOING METEORLOGICAL STUDY OF DATA AND OTHER STUFF FED INTO COMPU
     TER
860  REM
870  REM
880  REM  EXTREME HIGH WIND INDICATOR
890  REM
900  IF  LEFT$ (S$,1) = "N" THEN  PRINT "TORNADO APPROACHING!"
910  REM
920  REM  MOISTURE FACTOR ANALYZER
930  REM
940  IF  LEFT$ (R$,1) = "Y" THEN  PRINT "RAIN PROBABILITY 90% -- SHOWERS L
     IKELY  TOMORROW"
950  REM
960  REM  WIND VELOCITY SCALE
970  REM
980  IF  VAL (F$) > 0 THEN X1$ = " MILD"
990  IF  VAL (F$) = 3 THEN X1$ = " MODERATE"
1000  IF  VAL (F$) > 3 THEN X1$ = " STRONG"
1010  REM
1020  REM  ELECTRONIC WIND SOCK
1030  REM
1040  IF  LEFT$ (W$,1) = "Y" THEN X2$ = " WIND"
1050  IF  LEFT$ (D$,1) = "E" THEN X3$ = " WEST"
1060  IF  LEFT$ (D$,1) = "W" THEN X3$ = " EAST"
1070  IF  LEFT$ (D$,1) = "N" THEN X3$ = " SOUTH"
1080  IF  LEFT$ (D$,1) = "S" THEN X3$ = " NORTH"
1090  IF  LEFT$ (W$,1) = "Y" THEN  PRINT "A";X1$;X2$;" IS BLOWING FROM THE
     ";X3$
1100  REM
1110  REM  NICE WEATHER DATA BANK
1120  REM
1130  IF  LEFT$ (R$,1) = "N" THEN  PRINT "WEATHER CLEAR AND DRY"
1140  IF  LEFT$ (W$,1) = "N" THEN  PRINT "AIR IS CALM AT PRESENT"
1150  SPEED= 255
1160  END
1170  FOR M = 1 TO 100: NEXT M: RETURN
1180  REM
1190  REM  CHEAP WAY TO MAKE TALKIES OUT OF YOUR SILENT WEATHER REPORTS
1200  REM
1210  FOR X = 1 TO 3: PRINT  CHR$ (7): NEXT X: RETURN
```



IT'S A BLURB—

IT'S A GAME—

IT'S 

Bill Dyck

The setting of "Superman" is in the fine city of Metropolis, U.S.A. You, as Superman, must rid the city of the ten super criminals hiding in 18 different areas. If you can't achieve this within the 80 hours given to you, or if one of the criminals destroys you, it gives the rest the chance to get to their hide-away and push the button that finishes their plan to take over the world. In other words, if one of these things happens to you, you lose.

To start with, you have a certain amount of energy (between 4000 and 5000 calories) given to you. As you go after each criminal, you lose parts of that energy, but as soon as you have destroyed the criminal, the full amount of energy is restored. The way energy is lost is through the pound of kryptonite that each of the super criminals have in their possession. The closer you get to them, the more energy you lose. If the level of energy ever goes below zero, or if you accidentally move yourself right on top of a super criminal, it gives that criminal a chance to take out his long-held aggressions against you, and you lose the game.

To find and destroy the ten criminals, you have a total of five different abilities. The first and second abilities are used for finding the criminals and the last three for destroying the criminals. Here is a description of all five:

1. Flying: used to move both inside and outside of the areas.

2. X-ray Vision: used to see if there is a criminal in your area, and then to see approximately how far away he is from you.

3. Heat Vision: can only be used within 20 paces of the criminal and has a 30% chance of nailing him.

4. Super Strength: can only be used within 10 paces of the criminal and has a 50% chance of getting him.

Bill Dyck, 1119 S. Cryier Ave., Reedley, CA 93654.

5. Super Breath: can only be used within 30 paces of the criminal and has a 20% chance of destroying him.

Once you have scourged Metropolis of the criminals, you have won the game. It is as simple as that, but don't be fooled. It's not as easy as it looks.

The basic strategy that I have used (but with limited success) is to go to one end of the city and work my way down to the other end. That way you don't miss any of the criminals by accidentally skipping over them and then not knowing where they are hiding. The only problem with this is that the game sometimes becomes a little boring due to repetition. You might want to jump around and just go by luck (or if you are blessed with ESP, you can use that).

A Detailed Description

Here is a description of the two different sections of this program (line by line), and also a description of the different variables and what they are used for in the program.

Lines 10-340: Assigns values to the various variables and gives the option of instructions.

Lines 350-430: Command section.

Lines 440-490: X-Ray Vision command.

Lines 500-1000: Flying command.

1. Lines 570-740: move inside of the area.
2. Lines 740-1000: move outside to another area.

Lines 1010-1230: Heat Vision command.

Lines 1240-1410: Super Strength command.

Lines 1420-1590: Super Breath command.

Lines 1600-1860: Program completion statements and replay choice.

Lines 1870-2650: Subroutine for the instructions.

Lines 2660-2770: Subroutine for an unacceptable command number.

Lines 2780-2880: Subroutine to place the criminals in their different areas.

Lines 2890-3140: Subroutine to find out how far you are from the criminal.

Lines 3150-3310: Subroutine for X-Ray Vision.

Lines 3320-3580: Subroutine to see how much energy you have left.

1. Lines 3360-3460: Energy is taken off if the criminal is on the right side of Superman.
2. Lines 3470-3560: Energy is taken off if the criminal is on the left side of Superman.

Lines 3590-3690: Subroutine to see if Superman won and reassign variables.

Lines 3700-4100: Subroutine for the names of the 18 different areas.

Lines 4110-4230: Subroutine to assign the criminal's number to him.

Lines 4240-4450: Subroutine for the names of the ten different criminals.

Lines 4460-4490: Subroutine to assign the beginning amount of energy.

Lines 4500-4530: Subroutine to end the game if time has run out.

Lines 4540-4600: Subroutine to return you to the areas you were last at if you try to visit an area already visited.

Lines 4610-4650: Subroutine to force you to move on after nailing the criminal in that area.

Variables

A — Number of the command wanted.

A(1-10) — Numbers to tell which criminal is in the area you are in (if there is one).

B — Variable that tells which criminal you are working on (10-B tells how many

Superman cont'd...

criminals there are left to nail).

B7 — Flag to tell the computer if the areas being read are being used for the instructions or for the rest of the program.

C — Position of the criminal in the areas.

C5 — Flag to tell the computer if a criminal is in your area.

C8 — Real distance from the criminal if C is greater than M.

C9 — Approximate distance from the criminal if C is greater than M.

D4 — Flag to tell the computer if Superman has lost all of his energy.

E(1-9) — Check used to see if a criminal is in your area if Q is less than 10.

F(1-9) — Check used to see if a criminal is in your area if Q is more than 9.

G1 — Running amount of energy.

G2 — Amount of energy taken off as you get closer to the criminal.

G7 — Returns the original amount of energy to G1 once you have nailed the criminal in your present area.

H — Hours left before the criminals win.

I — Amount of paces or areas to move over inside or outside of the areas.

K — Flag to tell the computer if Superman has moved after he nailed the criminal in that area.

L(1-18) — Flag to tell the computer whether or not you have already visited the area to which you just moved.

M8 — Real distance from the criminal if M is greater than C.

M9 — Approximate distance from the criminal if M is greater than C.

M — Position of Superman in the areas.

N(1-10) — Number that is compared to either E(1-9) or F(1-9) to see if there is a criminal in your present area.

Q — Number of the area in which you are presently.

R2 — Random number used to determine the chance of Superman nailing the criminal.

T — Area number reserved in case you have to be returned because of trying to visit an area to which you have already been.

TØ — Breaks down your distance from the criminal to determine how much energy to take off.

W — Flag to tell the computer if Superman has won the game.

X7 — Flag to tell the computer if Superman has used his X-Ray Vision in the area where he is currently.

C$ — Area name reserved in case you have to be returned because of trying to visit an area to which you have already been.

H$ — The name of the area in which you are currently.

N$ — The name of the criminal you are currently fighting.

X$ — Direction to move and all other miscellaneous strings.

Modifications

Here are some modifications you can use to make the program a little simpler (and easier, if you find that you are never winning).

1. You can increase the chance of nailing the criminal in lines 1100, 1320, and 1500.

2. You can lessen the amount of energy you lose as you get closer to the criminal you are fighting in lines 3390 and 3500.

3. You can make the amount of energy you start off with larger in lines 4450 and 4460.

4. You can lessen the randomness of the approximation of the distance between you and the criminal.

5. You can raise the time limit in line 60.

Also, if you find this program too easy and you are winning all of the time (which would take a miracle), you could do the exact opposite to the above points (which is obvious, but I thought I would mention it anyway).

Since this program is pretty long, there are also some modifications you can do to the program to make it shorter.

1. You can cut out all of the instructions, or you can make two separate programs — one with the instructions and the other with the rest of the program — and chain the two together.

2. Using data statements, you could assign the names of the areas and criminals to such strings as H$(1) or N$(5). Since the computer I used wouldn't accept such statements, I had to make the program much more bulky by changing H$ every time Superman moved to a different area.

I leave it to you to find out any others, which, if you are clever enough, will surely be there.

The computer system I used for this program has several quirks in its use of Basic. In lines 430, 3710, 3910 and 4230, the statement 'Goto X of linenumber, linenumber' appears. In all Microsoft Basics, it is only accepted as 'On X goto linenumber, linenumber.' In lines 40 and 3660, there are multiple assignment statements. In your computer, you might have to put each of the variables on a different line. In the instructions, several lines are used such as 1980 (which is 'Hit return when ready'). You might have to input something instead of just hitting 'return.' Don't worry about it, because it won't cause the rest of the program any harm.

If your computer system has a bell function, it could be used in lines 1170, 1390, 1570 and 1640 as a signal that you have either nailed a criminal or won the game.

Well, that is the whole program in great detail. I sure hope you have as much fun with it as I have. Oh yeah, before I finish, I want to wish you good luck with the game. You'll need it. □

—Program begins on Page 148—

DYNACOMP

Quality software for:

ATARI
PET
APPLE II Plus
TRS-80 (Level II)
NORTH STAR
CP/M 8" Disk

GAMES

BRIDGE 2.0 (Available for all computers) — **Price: $17.95 Cassette, $21.95 Diskette**

An all-inclusive version of this most popular of card games. This program both BIDS and PLAYS either contract or duplicate bridge. Depending on the contract, your computer opponents will either play the offense OR defense. If you bid too high, the computer will double your contract! BRIDGE 2.0 provides challenging entertainment for advanced players and is an excellent learning tool for the bridge novice.

HEARTS 1.5 (Available for all computers) — **Price: $14.95 Cassette, $18.95 Diskette**

An exciting and entertaining computer version of this popular card game. Hearts is a trick-oriented game in which the purpose is not to take any hearts or the queen of spades. Play against two computer opponents who are armed with hard-to-beat playing strategies.

CRIBBAGE 2.0 (TRS-80 only) — **Price: $14.95 Cassette, $18.95 Diskette**

This is a well-designed and nicely executed two-handed version of the classic card game, cribbage. It is an excellent program for the cribbage player in search of a worthy opponent as well as the beginner wishing to learn the game, in particular the scoring and jargon. The standard cribbage score board is continually shown at the top of the display (utilizing the TRS-80's graphics capabilities), with the cards shown underneath. The computer automatically scores and also announces the points using the traditional phrases.

CHESS MASTER (North Star and TRS-80 only) — **Price: $19.95 Cassette, $23.95 Diskette**

This complete and very powerful program provides five levels of play. It includes castling, en passant captures and the promotion of pawns. Additionally, the board may be preset before the start of play, permitting the examination of "book" plays. To maximize execution speed, the program is written in assembly language (by SOFTWARE SPECIALISTS of California). Full graphics are employed in the TRS-80 version, and two widths of alphanumeric display are provided to accommodate North Star users.

STARTREK 3.2 (Available for all computers) — **Price: $ 9.95 Cassette, $13.95 Diskette**

This is the classic Startrek simulation, but with several new features. For example, the Klingons now shoot at the Enterprise without warning while also attacking starbases in other quadrants. The Klingons also attack with both light and heavy cruisers and move when shot at! The situation is hectic when the Enterprise is besieged by three heavy cruisers and a starbase S.O.S. is received! The Klingons get even!

SPACE TILT (Apple only) — **Price: $10.95 Cassette, $14.95 Diskette**

Use the game paddles to tilt the plane of the TV screen to "roll" a ball into a hole in the screen. Sound simple? Not when the hole gets smaller and smaller! A built-in timer allows you to measure your skill against others in this habit-forming action game.

GAMES PACK I and GAMES PACK II — **Price: $ 9.95 each, Cassette, $13.95 each, Diskette**

GAMES PACK I contains BLACKJACK, LUNAR LANDER, CRAPS, HORSERACE, SWITCH and more. GAMES PACK II includes CRAZY EIGHTS, JOTTO, ACEY-DUCEY, LIFE, WUMPUS and others. Available for all computers.

Why pay $5.95 or more per program when you can buy a DYNACOMP collection for just $9.95?

STUD POKER (ATARI only) — **Price: $11.95 Cassette, $15.95 Diskette**

This is the classic gambler's card game. The computer deals the cards one at a time and you (and the computer) bet on what you see. The computer does not cheat and *usually* bets the odds. However, it sometimes bluffs! Also included is a five card draw poker betting practice program. This package will run on a 16K ATARI.

STATISTICS and ENGINEERING

DATA SMOOTHER (Available for all computers) — **Price: $14.95 Cassette, $18.95 Diskette**

This special data smoothing program may be used to rapidly derive useful information from noisy business and engineering data which are equally spaced. The software features choice in degree and range of fit, as well as smoothed first and second derivative calculation. Also included is automatic plotting of the input data and smoothed results.

FOURIER ANALYZER (Available for all computers) — **Price: $14.95 Cassette, $18.95 Diskette**

Use this program to examine the frequency spectra of limited duration signals. The program features automatic scaling and plotting of the input data and results. Practical applications include the analysis of complicated patterns in such fields as electronics, communications and business.

TFA (Transfer Function Analyzer) — **Price: $19.95 Cassette, $23.95 Diskette**

This is a special software package which may be used to evaluate the transfer functions of systems such as hi-fi amplifiers and filters by examining their response to pulsed inputs. TFA is a major modification of FOURIER ANALYZER and contains an engineering-oriented decibel versus log-frequency plot as well as data editing features. Whereas FOURIER ANALYZER is designed for educational and scientific use, TFA is an engineering tool. Available for all computers.

FOURIER ANALYZER and TFA may be purchased together for a combined price of $29.95 (Cassettes) and $37.95 (Diskettes).

REGRESSION I (Available for all computers) — **Price: $19.95 Cassette, $23.95 Diskette**

REGRESSION I is a unique and exceptionally versatile one-dimensional least squares "polynomial" curve fitting program. Features include very high accuracy; an automatic degree determination option; an extensive internal library of fitting functions; data editing; automatic data and curve plotting; a statistical analysis (e.g., standard deviation, correlation coefficient, etc.) and much more. In addition, new fits may be tried without reentering the data. REGRESSION I is certainly the cornerstone program in any data analysis software library.

REGRESSION II (PARAFIT) (Available for all computers) — **Price: $19.95 Cassette, $23.95 Diskette**

PARAFIT is designed to handle those cases in which the parameters are imbedded (possibly nonlinearly) in the fitting function. The user simply inserts the functional form, including the parameters (A(1), A(2), etc.) as one or more BASIC statement lines. Data and results may be manipulated and plotted as with REGRESSION 1. Use REGRESSION 1 for polynomial fitting, and PARAFIT for those complicated functions.

REGRESSION I and II may be purchased together for $36.95 (cassettes) and $44.95 (diskettes)

Availability

DYNACOMP software is supplied with complete documentation containing clear explanations and examples. All programs will run within 16K program memory space (ATARI requires 24K). Except where noted, programs are available on ATARI, PET, TRS-80 (Level II) and Apple (Applesoft) cassette and diskette as well as North Star single density (double density compatible) diskette. Additionally, most programs can be obtained on standard 8" CP/M floppy disks for systems running under MBASIC.

BUSINESS and UTILITIES

MAIL LIST II (North Star only) — **Price: $21.95**

This many-featured program now includes full alphabetic and zip code sorting as well as file merging. Entries can be retrieved by user-defined code, client name or Zip Code. The printout format allows the use of standard size address labels. Each diskette can store more than 1100 entries (single density; over 2200 with double density systems)!

TEXT EDITOR I (Letter Writer) — **Price: $14.95 Cassette, $18.95 Diskette**

An easy to use, line-oriented text editor which provides variable line widths and simple paragraph indexing. This text editor is ideally suited for composing letters and is quite capable of handling much larger jobs. Available for all computers.

FINDIT (North Star only) — **Price: $19.95**

This is a three-in-one program which maintains information accessible by keywords of three types: Personal (e.g., last name), Commercial (eg: plumbers) and Reference (eg: magazine articles, record albums, etc). In addition to keyword searches, there are birthday, anniversary and appointment searches for the personal records and appointment searches for the commercial records. Reference records are accessed by a single keyword or by cross-referencing two or three keywords.

DFILE (North Star only) — **Price: $19.95**

This handy program allows North Star users to maintain a specialized data base of all files and programs in the stack of disks which invariably accumulates. DFILE is easy to set up and use. It will organize your disks to provide efficient locating of the desired file or program.

COMPARE (North Star only) — **Price: $12.95**

COMPARE is a single disk utility software package which compares two BASIC programs and displays the file sizes of the programs in bytes, the lengths in terms of the number of statement lines, and the line numbers at which various listed differences occur. COMPARE permits the user to examine versions of his software to verify which are the more current, and to clearly identify the changes made during development.

COMPRESS (North Star only) — **Price: $12.95**

COMPRESS is a single-disk utility program which removes all unnecessary spaces and (optionally) REMark statements from North Star BASIC programs. The source file is processed one line at a time, thus permitting very large programs to be compressed using only a small amount of computer memory. File compressions of 20-50% are commonly achieved.

GRAFIX (TRS-80 only) — **Price: $12.95 Cassette, $16.95 Diskette**

This unique program allows you to easily create graphics directly from the keyboard. You "draw" your figure using the program's extensive cursor controls. Once the figure is made, it is automatically appended to your BASIC program as a string variable. Draw a "happy face", call it H$ and then print it from your program using PRINT H$! This is a very easy way to create and save graphics.

TIDY (TRS-80 only) — **Price: $10.95 Cassette, $14.95 Diskette**

TIDY is an assembly language program which allows you to renumber the lines in your BASIC programs. TIDY also removes unnecessary spaces and REMark statements. The result is a compacted BASIC program which uses much less memory space and executes significantly faster. Once loaded, TIDY remains in memory; you may load any number of BASIC programs without having to reload TIDY!

SIMULATIONS and EDUCATION

BLACK HOLE (Apple only) — **Price: $14.95 Cassette, $18.95 Diskette**

This is an exciting graphical simulation of the problems involved in closely observing a black hole with a space probe. The object is to enter and maintain, for a prescribed time, an orbit close to a small black hole. This is to be achieved without coming so near the anomaly that the tidal stress destroys the probe. Control of the craft is realistically simulated using side jets for rotation and main thrusters for acceleration. This program employs Hi-Res graphics and is educational as well as challenging.

VALDEZ (Available for all computers) — **Price: $14.95 Cassette, $18.95 Diskette**

A simulation of supertanker navigation in the Prince William Sound and Valdez Narrows. The program uses an extensive 256X256 element radar map and employs physical models of ship response and tidal patterns. Chart your own course through ship and iceberg traffic. Any standard terminal may be used for display.

FLIGHT SIMULATOR (Available for all computers) — **Price: $17.95 Cassette, $21.95 Diskette**

A realistic and extensive mathematical simulation of take-off, flight and landing. The program utilizes aerodynamic equations and the characteristics of a real airfoil. You can practice instrument approaches and navigation using radials and compass headings. The more advanced flyer can also perform loops, half-rolls and similar aerobatic maneuvers.

TEACHER'S PET I (Available for all computers) — **Price: $ 9.95 Cassette, $13.95 Diskette**

This is the first of DYNACOMP's educational packages. Primarily intended for pre-school to grade 3, TEACHER'S PET provides the young student with counting practice, letter-word recognition and three levels of math skill exercises.

Ordering Information

All orders are processed and shipped postpaid within 48 hours. Please enclose payment with order along with computer information. If paying by VISA or Master Card, include all numbers on card. For orders outside North America add 10% for shipping and handling.

Add $2.50 to diskette price for 8" floppy disk (soft sectored, CP/M, Microsoft BASIC)

Deduct 10% when ordering 3 or more programs.

Ask for **DYNACOMP** programs at your local software dealer. Write for detailed descriptions of these and other programs from **DYNACOMP**.

DYNACOMP, Inc.
6 Rippingale Road
Pittsford, New York 14534
(716) 586-7579

VISA

master charge

New York State residents please add 7% NYS sales tax.

SUPERMAN

```
0010  DIM X$[10],N$[50],H$[100],C$[100]
0020  DIM L[18]
0030  B=1
0040  X7=C5=C=M=M3=Q7=W=D4=B7=K=0
0050  G2=100
0060  H=80
0070  D2=10
0080   FOR A5=1 TO 18
0090   L[A5]=0
0100   NEXT A5
0110  PRINT
0120  PRINT
0130  PRINT "THIS IS THE GAME OF SUPERMAN"
0140  PRINT "DO YOU WANT THE INSTRUCTIONS";
0150  INPUT X$
0160  PRINT
0170  IF X$="YES" THEN  GOSUB 1870
0180  Q=INT(RND(0)*18)+1
0190  L[Q]=1
0200  GOSUB 3700
0210  GOSUB 4460
0220  G1=G7
0230  PRINT "YOU HAVE A TOTAL OF ";G1;" CALORIES OF ENERGY"
0240  PRINT "TO DESTROY EACH CRIMINAL WITH, SO WATCH OUT."
0250  PRINT
0260  GOSUB 2780
0270  GOSUB 4110
0280   FOR D1=1 TO 9
0290   E[D1]=D1
0300   NEXT D1
0310   FOR D1=1 TO 9
0320   F[D1]=D2
0330   D2=D2+1
0340   NEXT D1
0350  PRINT
0360  PRINT "ENERGY LEFT-";G1;"LOCATION-";H$;"     HOURS LEFT-";H
0370  PRINT "COMMAND";
0380  INPUT A
0390  A=INT(A)
0400  IF A>0 AND A<6 THEN 430
0410  GOSUB 2660
0420  GOTO 350
0430  GOTO A OF 440,500,1010,1240,1420
0440  REM   *** X-RAY VISION ***
0450  IF K=1 THEN 4610
0460  GOSUB 2890
0470  H=H-1
0480  IF H=0 THEN 4500
0490  GOTO 350
0500  REM   *** FLYING ***
0510  PRINT "MOVE INSIDE OR OUT. (0-INSIDE    1-OUTSIDE)";
0520  INPUT I
0530  IF I=0 OR I=1 THEN 560
0540  PRINT "JUST 1 OR 0 PLEASE"
0550  GOTO 500
0560  IF I=1 THEN 750
0570  IF C <> M THEN 610
0580  PRINT "YOU DO NOT EVEN KNOW IF THERE IS A CRIMINAL HERE IN THIS"
0590  PRINT "AREA, SO BEFORE YOU TRY TO MOVE INSIDE OF IT, FIND OUT FIRST"
0600  GOTO 470
0610  IF C<M THEN 690
0620  PRINT "HOW MANY PACES OVER TO THE ";X$;
0630  INPUT I
0640  M=M+I
0650  IF M=C THEN 1700
0660  GOSUB 3320
0670  IF D4=1 THEN 1780
0680  GOTO 470
0690  PRINT "HOW MANY PACES OVER TO THE ";X$;
0700  INPUT I
0710  M=M-I
0720  IF M=C THEN 1700
0730  GOSUB 3320
0740  GOTO 670
0750  C$=H$
0760  T=Q
0770  PRINT "HOW MANY AREAS OVER";
0780  INPUT I
0790  PRINT "TO THE LEFT OR RIGHT";
0800  INPUT X$
0810  IF X$="RIGHT" THEN 850
0820  IF X$="LEFT" THEN 960
0830  PRINT "INPUT JUST RIGHT OR LEFT PLEASE"
0840  GOTO 790
0850  Q=Q+I
0860  IF Q>18 THEN 880
0870  GOTO 910
0880  Q=18
0890  PRINT "YOU CAN NOT MOVE OVER THAT FAR ";X$;" SO YOU ARE OVER AS FAR"
0900  PRINT X$;" AS POSSIBLE"
0910  GOSUB 3700
0920  IF L[Q]=1 THEN 4540
0930  L[Q]=1
0940  K=0
0950  GOTO 470
0960  Q=Q-I
0970  IF Q<1 THEN 990
0980  GOTO 910
0990  Q=1
1000  GOTO 890
1010  REM   *** HEAT VISION ***
1020  IF K=1 THEN 4610
1030  R2=RND(0)
1040  IF C=M THEN 1210
1050  IF C>M THEN 1110
1060  IF M8<21 THEN 1120
1070  PRINT "YOU ARE NOT CLOSE ENOUGH TO ";N$;" TO USE YOUR HEAT VISION"
1080  PRINT "SO GET CLOSER TO HIM"
1090  GOSUB 3320
1100  GOTO 670
1110  IF C8>20 THEN 1070
1120  IF R2>.7 THEN 1170
1130  PRINT "WELL, YOU DID NOT HIT ";N$;", BUT ACTUALLY MISSED HIM BY"
1140  PRINT R2*100;"FEET.  WHAT A SHOT"
1150  G1=G1-200
1160  GOTO 1090
1170  PRINT "WHAT A SUPER SHOT, SUPERMAN, YOU NAILED ";N$
1180  GOSUB 3590
1190  IF W=1 THEN 1600
1200  GOTO 470
1210  PRINT "YOU DON'T KNOW WHETHER OR NOT THERE IS A CRIMINAL HERE IN THE"
1220  PRINT H$", SO BEFORE YOU SHOOT, FIND OUT"
1230  GOTO 470
1240  REM   *** SUPER STRENGTH ***
1250  IF K=1 THEN 4610
1260  IF C=M THEN 1210
1270  R2=RND(0)
1280  IF C>M THEN 1330
1290  IF M8<11 THEN 1340
1300  PRINT "YOU ARE NOT CLOSE ENOUGH TO ";N$;" TO USE YOUR SUPER"
1310  PRINT "STRENGTH, SO GET CLOSER"
1320  GOTO 1090
```

SAVE ON ADD-ON PRODUCTS FOR TRS-80

The largest family of disk drives from the largest supplier, drives come complete with power supply and cabinet.

MTI-40 Disk Drive, 35 & 40 track	$369
TF-1 Pertec FD200, 40 track, use both sides	$389
TF-3 Shugart SA400, 35 track, same as tandy	$389
TF-5 MPI B51, 40 track	$379
TF-70 Micropolis, 77 track with 195K of storage	$639
TDH-1 Dual sided drive, 35 track	$499

Maxi Disk 2: 10 Megabyte (fixed) Winchester Technology ... **$5349**

NEW PRODUCTS

16K Memory	$86
Modem	$179
Expansion Interface 32K	$499
AC Isolator	$47.95

PRINTERS

DP800 Anadex, 80 column, 112cps	$949
LP779 Centronics 779	$1099
LP730 Centronics 730	$950
LP700 Centronics 700	$1395
LP701 Centronics 701	$1759
LP702 Centronics 702	$1995
SPW-1 Spinwriter-NEC	$2525

NEW! LINE PRINTER BASE 2

Base 2 Printer 80, 132 col., graphics 60 LPM with tractors ... **$599**

*** DRIVES FOR ANY MICROCOMPUTER ***

Does not include power supply & cabinet.

MOD II DISK DRIVES NOW AVAILABLE

Perfec FD200	$282		
Perfec FD250 (dual head)	$399		
Shugart SA400 (unused)	$286		
Shugart SA800	$479		
MPI B52	$349	B51	$279

SOFTWARE

Disk Drive Motor Speed Test	$19.95
New DOS+ with over 200 modifications and corrections to TRS-DOS	$99
New DOS+ 40 track	$110
AJA Word Processor	$75
AJA Business Program	$250
Racet Infinite Basic	$49.95
Disk Drive Alignment Program	$109
Radix Data Base Program	$99.95
Electric Pencil	$150

ALL PRICES CASH DISCOUNTED. FREIGHT FOB/FACTORY

MTI MICROCOMPUTER TECHNOLOGY INCORPORATED

3304 W. MacArthur
Santa Ana, CA 92704
(714) 979-9923

Apparat, Inc.

7310 E. Princeton Ave.
Denver, CO 80222
(303) 758-7275

CIRCLE 151 ON READER SERVICE CARD

There's never been a better time to buy an Apple II.

48K APPLE II OR PLUS ONLY **$1095.** Cash price

Apple DOS 3.3 Software
A2D0023.....$60.00

Visit our newly expanded showroom and see one of the original Apple Is on display.

apple computer
Authorized Dealer

FARNSWORTH COMPUTER CENTER
1891 N. FARNSWORTH AVE.
(At the East-West Tollway)
AURORA, IL. 60505
(312) 851-3888
Weekdays 10-8; Sat. 10-5

CIRCLE 211 ON READER SERVICE CARD

HEATH-ZENITH H8-H89-Z89

AT LAST !

PROFESSIONAL QUALITY

Business and Educational Software is now available for the powerful Heath and Zenith computer systems.

Experience and Professionalism are the hallmarks of XtraSoft and are reflected by the products we sell.

For our current catalog contact:

XtraSoft
PROFESSIONAL SOFTWARE DEVELOPMENT

P.O. Box 91063
Louisville, KY 40291

master charge VISA

HEATH & ZENITH Are Registered TM's Of HEATH & ZENITH CORP's

CIRCLE 269 ON READER SERVICE CARD

```
1330  IF C8>10 THEN 1300
1340  IF R2>.5 THEN 1390
1350  PRINT "WHAT A ROUNDHOUSE PUNCH.  GOOD, BUT TOTALLY MISSED"
1360  PRINT N$
1370  G1=G1-100
1380  GOTO 1090
1390  PRINT "WHAT A PUNCH SUPERMAN.  IT KNOCKED OL ";N$;" BABY"
1400  PRINT "DEAD AS A DOORNAIL.  THAT IS ";B;"DOWN AND ";10-B;"TO GO"
1410  GOTO 1180
1420  REM   *** SUPER BREATH ***
1430  IF K=1 THEN 4610
1440  IF C=M THEN 1210
1450  R2=RND(0)
1460  IF C>M THEN 1510
1470  IF M8<31 THEN 1520
1480  PRINT "YOU ARE NOT CLOSE ENOUGH TO ";N$;" TO USE YOUR SUPER"
1490  PRINT "BREATH, SO TRY TO GET CLOSER"
1500  GOTO 1090
1510  IF C8>30 THEN 1480
1520  IF R2>.8 THEN 1570
1530  PRINT "WHAT BAD BREATH YOU HAVE.  IT DIDN'T EVEN COME CLOSE TO"
1540  PRINT "PUTTING ";N$;" AWAY"
1550  G1=G1-300
1560  GOTO 1090
1570  PRINT "WHAT A 'SUPER'MAN.  KNOCKED ";N$;" HEAD OVER"
1580  PRINT "HEELS WITH THAT BLAST.  THAT IS ";B;" DOWN AND ";10-B;" TO GO"
1590  GOTO 1180
1600  REM   *** ENDING STATEMENTS ***
1610  PRINT "CONGRADULATIONS.  IN DOING AWAY WITH "N$;" YOU DID AWAY WITH"
1620  PRINT "THE LAST SUPER CRIMINAL.  THE SUPER CRIMINAL'S PLAN "
1630  PRINT "CAN NOW NO LONGER GO INTO EFFECT, AND YOU HAVE SAVED THE WORLD"
1640  PRINT ""
1650  PRINT "DO YOU WISH TO TRY AGAIN";
1660  INPUT X$
1670  IF X$="YES" THEN 30
1680  PRINT "SUPERMAN SAYS GOOD-BYE"
1690  GOTO 4660
1700  PRINT
1710  PRINT
1720  PRINT "YOU HAVE MOVED YOURSELF RIGHT ON TOP OF ";N$
1730  PRINT "BECAUSE YOU WERE NOT READY FOR HIM, IT GAVE ";N$;" A CHANCE TO"
1740  PRINT "SLIP HIS GREEN KRYPTONITE DOWN YOUR BACK AND YOU HAVE LOST"
1750  PRINT "ALL OF YOUR ENERGY.  TOO BAD"
1760  D4=1
1770  GOTO 670
1780  PRINT
1790  PRINT "YOU HAVE LOST ALL OF YOUR ENERGY, AND BECAUSE YOU"
1800  PRINT "ARE NO LONGER ABLE TO PROTECT YOURSELF, ";N$
1810  PRINT "WAS ABLE TO OVERCOME YOU.  NOW THE SUPERCRIMINALS WILL BE"
1820  PRINT "ABLE TO CARRY OUT THEIR PLAN, AND EARTH IS DOOMED"
1830  PRINT "WAY TO GO BIG BOY.  THREE CHEERS FOR SUPER KLUTZ"
1840  PRINT
1850  PRINT "DO YOU WISH TO REDEEM YOURSELF AND TRY AGAIN";
1860  GOTO 1660
1870  REM   *** INSTRUCTIONS ***
1880  PRINT "HERE ARE THE INSTRUCTIONS:"
1890  PRINT
1900  PRINT "THERE ARE 10 SUPERCRIMINALS ON EARTH AND THEY HAVE"
1910  PRINT "A MASTER PLAN WITH WHICH THEY WANT TO TAKE OVER THE"
1920  PRINT "WORLD.  TO START IT MOVING, ONLY ONE OF THEM HAS TO PUSH THE"
1930  PRINT "BUTTON.  IT IS YOUR JOB AS SUPERMAN TO GET RID OF ALL"
1940  PRINT "10 SUPER CRIMINALS.  ALL 10 OF THEM ARE IN THE CITY OF"
1950  PRINT "METROPOLIS, SCATTERED THROUGHOUT 18 DIFFERENT AREAS"
1960  PRINT "WITH NO MORE THAN 1 IN AN AREA"
1970  PRINT
1980  PRINT "HIT RETURN TO CONTINUE";
1990  INPUT X$
2000  PRINT "HERE ARE THE AREAS:"
2010  PRINT
2020  B7=Q=1
2030   FOR V1=1 TO 6
2040    FOR V2=1 TO 3
2050    GOTO 3700
2060    PRINT H$;
2070    IF Q<18 THEN  PRINT " -> ";
2080    Q=Q+1
2090    NEXT V2
2100   PRINT
2110   NEXT V1
2120  B7=0
2130  PRINT
2140  PRINT "YOU CANNOT GO FURTHER LEFT THAN THE PARKING LOT AND NO"
2150  PRINT "FURTHER RIGHT THAN THE NUCLEAR PLANT.  IF YOU TRY TO, YOU WILL BE"
2160  PRINT "PLACED IN THE LAST ONE IN EITHER DIRECTION."
2170  PRINT
2180  PRINT "HIT RETURN TO CONTINUE";
2190  INPUT X$
2200  PRINT
2210  PRINT "TO CATCH AND DESTROY THE CRIMINALS, YOU HAVE FIVE DIFFERENT"
2220  PRINT "ABILITIES, DESCIBED AS FOLLOWS:"
2230  PRINT
2240  PRINT "1 - X-RAY VISION-USED TO SEE IF A CRIMINAL IS IN YOUR AREA,"
2250  PRINT "OR AFTER THAT, TO SEE APPROXIMATELY HOW FAR AWAY HE IS FROM YOU"
2260  PRINT "THE DISTANCE I TELL YOU IS NOT EXACTLY RIGHT, SO BE CAREFUL."
2270  PRINT "2 - FLYING-USED TO MOVE FROM ONE AREA TO ANOTHER, OR INSIDE OF"
2280  PRINT "THE AREA YOU ARE IN.  IF YOU LAND RIGHT ON THE CRIMINAL, YOU LOSE, SO WATCH OUT"
2290  PRINT "3 - HEAT VISION- CAN ONLY BE USED WHEN YOU ARE WITHIN 20 FEET"
2300  PRINT "OR LESS OF THE CRIMINAL, AND IT HAS A 30% CHANCE OF NAILING"
2310  PRINT "HIM.  IT TAKES UP 200 CALORIES OF ENERGY EACH TIME YOU USE IT"
2320  PRINT "4 - SUPER STRENGTH- CAN ONLY BE USED WHEN YOU ARE WITHIN 10 FEET"
2330  PRINT "OR LESS OF THE CRIMINAL, AND HAS A 50% CHANCE OF GETTING"
2340  PRINT "HIM.  IT TAKES 100 CALORIES OF ENERGY TO USE IT EACH TIME"
2350  PRINT "5 - SUPER BREATH- CAN ONLY BE USED WHEN YOU ARE WITHIN 30"
2360  PRINT "FEET OF THE CRIMINAL, AND HAS A 20% CHANCE OF NAILING HIM.  IT TAKES"
2370  PRINT "300 CALORIES OF ENERGY TO USE EACH TIME"
2380  PRINT
2390  PRINT "THE ABILITIES NUMBER 1 AND 2 ARE USED TO LOCATE THE CRIMINAL AND"
2400  PRINT "THE ABILITIES NUMBER 3,4,5 ARE USED TO NAIL THE CRIMINALS"
2410  PRINT
2420  PRINT "HIT RETURN TO CONTINUE";
2430  INPUT X$
2440  PRINT
2450  PRINT "THE WAY THAT THE CRIMINALS CAN GET YOU IS LIKE THIS:"
2460  PRINT "EACH ONE OF THE CRIMINALS HAS A POUND OF GREEN KRYPTONITE, WITH"
2470  PRINT "WHICH TO GET YOU WITH.  THE CLOSER YOU GET TO THEM, THE MORE ENERGY"
2480  PRINT "YOU LOSE.  IF YOU LOSE ALL OF YOUR ENERGY, YOU BECOME TO WEAK TO"
2490  PRINT "DEFEND YOURSELF AND THE CRIMINAL CAN OVERCOME YOU, AND YOU LOSE"
2500  PRINT "YOU HAVE A TOTAL OF 80 HOURS WITH WHICH TO STOP THEM FROM PUTTING"
2510  PRINT "THEIR PLAN INTO ACTION.  IF YOU TAKE LONGER, THEN THEY GET TO THE"
2520  PRINT "BUTTON, AND YOU LOSE ALSO. "
2530  PRINT
2540  PRINT "WHEN YOU NAIL THE CRIMINAL, ALL YOUR ENERGY IS RESTORED TO YOU"
2550  PRINT "AND YOU CAN KEEP ON GOING TO GET THE REST OF THE CRIMINALS."
2560  PRINT "IF YOU LEAVE AN AREA, YOU CAN'T RETURN TO IT,"
2570  PRINT "SO BE SURE TO GET THE CRIMINAL BEFORE YOU LEAVE, OR YOU CAN NEVER GET ALL TEN"
2580  PRINT
2590  PRINT "ONCE YOU HAVE NAILED A CRIMINAL, YOU HAVE TO MOVE ON, AND YOU CAN DO NOTHING"
2600  PRINT "ELSE UNTIL YOU DO SO"
2610  PRINT
2620  PRINT "HIT RETURN TO CONTINUE";
2630  INPUT X$
2640  PRINT
2650  RETURN
2660  REM   *** CHOICE OF ABILITIES ***
```

micro lab presents

DOGFIGHT

NEW FOR THE APPLE

BY BILL BASHAM

A NEW CHALLENGE

DOGFIGHT will capture your imagination. You are the pilot of a jet going into combat. You may fly alone on this mission, or you may have another pilot flying with you to defeat the enemy. First you fly against one enemy jet. You are in complete control: fly faster or slower, turn left or right — but most importantly, FIRE. If you are shot down, and you act quickly, you can bail out. You and your parachute float gently downward, hoping an enemy plane does not shoot you. If you survive, you will quickly return to the fierce dogfight. The enemy can also bail out!! You must shoot him down before he has a chance to return.

THE ENEMY RETURNS

Each time you defeat all enemy jets or helicopters, you advance to the next level where you fly against faster and/or more enemy planes. There are sixteen levels of difficulty to fight through. Bill Basham, the talented author of this high resolution program, has made it through only 8 levels before his planes were destroyed.

MANY WAYS TO PLAY

DOGFIGHT may be played in several different ways. You, alone, may challenge the computer, or, two players may fly against the computer — either on the same team or on different teams. With DOGFIGHT you can create your own custom game with as many as eight players crowding around your Apple keyboard controlling their own planes. You may select jets or helicopters on any level — be a daredevil with 7 computer jets against you. You are in charge with the custom mode.

FOR THE ACES

Micro Lab will award a special achievement plaque to the first 10 pilots who reach 10,000 points in any of the auto modes (one player, two players same team, two players different teams). A special, individual, secretly coded message will appear when reaching that score. Report that code to Micro Lab to claim the Ace title.

AVAILABLE NOW

The Dogfight is available on disk at your Apple Dealer for $29.95.

micro lab

systems that work

811 STONEGATE • HIGHLAND PARK, IL 60035

312-433-7877

CIRCLE 156 ON READER SERVICE CARD

```
2670  PRINT
2680  PRINT "THESE ARE YOUR FIVE ABILITIES:"
2690  PRINT "1-X-RAY VISION"
2700  PRINT "2-FLYING"
2710  PRINT "3-HEAT VISION"
2720  PRINT "4-SUPER STRENGTH"
2730  PRINT "5-SUPER BREATH"
2740  PRINT "IF YOU INPUT ANY OTHER NUMBER THAN THESE FIVE, YOU WILL BE"
2750  PRINT "SENT BACK TO HERE.  TRY AGAIN"
2760  PRINT
2770  RETURN
2780  REM   *** PLACE THE CRIMINALS IN THEIR AREAS ***
2790   FOR R9=1 TO 10
2800   IF R9>1 THEN 2830
2810   N[R9]=INT(RND(0)*18)+1
2820   GOTO 2870
2830   N[R9]=INT(RND(0)*18)+1
2840    FOR R8=R9 TO 2 STEP -1
2850    IF N[R9]=N[R8-1] THEN 2830
2860    NEXT R8
2870   NEXT R9
2880  RETURN
2890  REM   *** WHERE IS THE CRIMINAL IN RELATION TO YOU ***
2900  IF C5 <> 10 THEN 3150
2910  IF X7>0 THEN 3130
2920  M=INT(RND(0)*200)+1
2930  C=INT(RND(0)*200)+1
2940  IF C>M THEN 2970
2950  IF C<M THEN 3050
2960  GOTO 2920
2970  C8=C-M
2980  X3=INT(RND(0)*20)+1
2990  C9=C8+2*(INT(RND(0)*X3)+1)
3000  X$="RIGHT"
3010  PRINT "X-RAY VISION TELLS YOU THAT YOU ARE APPROXIMATLEY ";C9
3020  PRINT "PACES AWAY FROM ";N$;" TO THE ";X$
3030  X7=1
3040  GOTO 3320
3050  M8=M-C
3060  X3=INT(RND(0)*20)+1
3070  M9=M8+2*(INT(RND(0)*X3)+1)
3080  X$="LEFT"
3090  PRINT "X-RAY VISION TELLS YOU THAT YOU ARE APPROXIMATELY ";M9
3100  PRINT "PACES AWAY FROM ";N$;" TO THE ";X$
3110  X7=1
3120  GOTO 3320
3130  IF C>M THEN 2970
3140  GOTO 3050
3150  REM   *** SUB-ROUTINE FOR X-RAY VISION ***
3160  IF Q>9 THEN 3210
3170   FOR X3=1 TO 10
3180   IF E[Q]=N[X3] THEN  C5=10
3190   NEXT X3
3200  GOTO 3240
3210   FOR X3=1 TO 10
3220   IF F[Q-9]=N[X3] THEN  C5=10
3230   NEXT X3
3240  IF C5 <> 10 THEN 3290
3250  PRINT "YOU HAVE CAUGHT ";N$;" SOMEWHERE IN THE ";H$
3260  PRINT "NOW ALL YOU HAVE TO DO IS FIND HIM"
3270  G1=G1-50
3280  RETURN
3290  PRINT "X-RAY VISION HAS DETECTED NO SUPER CRIMINAL HERE IN THE"
3300  PRINT H$;", SO MOVE ON"
3310  RETURN
3320  REM   *** SEE HOW MUCH ENERGY YOU HAVE LEFT ***
3330  IF G1 <= 0 THEN 3680
```



```
3340  IF C>M THEN 3360
3350  GOTO 3470
3360  C8=C-M
3370   FOR T0=190 TO 0 STEP -10
3380   IF C8>T0 AND C8 <= T0+10 THEN 3400
3390   GOTO 3430
3400   G1=G1-G2
3410   IF G1 <= 0 THEN  D4=1
3420   GOTO 3440
3430   G2=G2+35
3440   NEXT T0
3450  X$="RIGHT"
3460  GOTO 3570
3470  M8=M-C
3480   FOR T0=190 TO 0 STEP -10
3490   IF M8>T0 AND M8 <= T0+10 THEN 3510
3500   GOTO 3540
3510   G1=G1-G2
3520   IF G1 <= 0 THEN  D4=1
3530   GOTO 3550
3540   G2=G2+35
3550   NEXT T0
3560  X$="LEFT"
3570  G2=100
3580  RETURN
3590  REM   *** CHANGE CRIMINALS AND SEE IF SUPERMAN HAS WON ***
3600  IF B<10 THEN 3630
3610  W=1
3620  RETURN
3630  B=B+1
3640  G1=G7
3650  K=1
3660  C=M=X7=C5=W=0
3670  GOTO 4250
3680  D4=1
3690  GOTO 3580
3700  REM   *** NAMES OF THE AREAS ***
3710  IF Q>9 THEN 3920
3720  GOTO Q OF 3730,3760,3780,3800,3820,3840,3860,3880,3900
3730  H$="PARKING LOT"
3740  IF B7=1 THEN 2060
3750  RETURN
3760  H$="SUPER MARKET"
3770  GOTO 3740
3780  H$="JUNK YARD"
3790  GOTO 3740
3800  H$="GARBAGE DUMP"
3810  GOTO 3740
3820  H$="DAILY PLANET"
3830  GOTO 3740
3840  H$="SEWER"
3850  GOTO 3740
3860  H$="RIVER"
3870  GOTO 3740
3880  H$="OCEAN"
3890  GOTO 3740
3900  H$="AIRPORT"
3910  GOTO 3740
3920  GOTO Q-9 OF 3930,3950,3970,3990,4010,4030,4050,4070,4090
3930  H$="TRAIN STATION"
3940  GOTO 3740
3950  H$="RADIO STATION"
3960  GOTO 3740
3970  H$="T.V. STATION"
3980  GOTO 3740
3990  H$="AMUSEMENT PARK"
4000  GOTO 3740
```

A NEW DIMENSION IN ADVENTURE... DEPTH

Deathmaze 5000 and Labyrinth are the first in a new breed of machine language adventure. Instead of wandering through the English language, typing GO EAST or GO WEST, you move through a colossal maze represented on the screen three-dimensionally. Hallways recede into infinity or come to dead-ends. Doors open to right and left. Pits open in floor and ceiling. As you encounter objects, monsters, and mayhem, one or two word commands may be used. The command set is extensive and sophisticated. The proper commands allow the solution of problems and the manipulation of objects. The improper choice of words could spell the end . . .

Deathmaze 5000 places you on the top floor of a five story building. Each floor is a maze of twisting passageways. Floors are connected by elevators and open pits. You have but one goal. **ESCAPE ALIVE!** Where is the only door out of this nightmare? Monsters, bats, mad dogs, hunger, and many more horrors plague your every step as you struggle to escape the most complex adventure ever written.

Labyrinth places you in a maze of gigantic proportions. But you are not alone! A minotaur searches for you, seeking a grisly meal. You must deal with ghosts and cave gnomes. You *must* avoid the minotaur until the moment is right for the final battle.

Each program $12.95 on cassette for TRS-80 Level II 16K, APPLE II 32K, or APPLE II PLUS 32K.

Med Systems Software **unconditionally guarantees** satisfaction with all the software it sells. If you are dissatisfied with a program for any reason, return it within 14 days for a prompt and cheerful refund.

Med Systems Software
P.O. Box 2674 Chapel Hill, N.C. 27514
(919) 933-1990

VISA
master charge

CIRCLE 221 ON READER SERVICE CARD



MPD 117

NO "GLITCHES", SURGES OR INTERFERENCE

Clean power distribution for your:

- **Microcomputer system**
- **Audio Visual system**
- **Lab instrumentation**

Marway Products' new MPD 117 AC Power Controller upgrades a standard AC utility outlet into a convenient noise-free source of AC power. The MPD 117 features:

- High energy EMI filter
- Transient voltage suppressor
- 10 amp circuit breaker
- 6 switched outlets
- 2 direct (unswitched) outlets
- Illuminated "on/off" switch
- UL recognized components

At $89.00 (plus tax and shipping) the MPD is the low-cost solution to your power distribution needs, and the best dollar value available in AC power distribution and noise suppression products.

Marway can solve your power distribution problems and save you money.

MARWAY PRODUCTS INC.
2421 S. Birch St., Santa Ana, CA 92707 (714) 549-0623

CIRCLE 220 ON READER SERVICE CARD

DOSPLUS 3.1

AEROCOMP DISC DRIVES FOR TRS — 80*

• MODEL 80-1 DISC DRIVE $449.95 ea.
Single-sided, "Flippy", 96TPI (80 track; single density unformated 250K bytes/side; double density unformated 500K bytes/side).

• MODEL DISC DRIVE 160-2 $599.95
Double-sided, 96TPI (160 track/80 per side; single density unformated 500K bytes; double density unformated 1 megabyte)

All models are capable of single or double density and are complete with power supply and silver enclosure. Send for information on AEROCOMP 2-and 3-drive systems available in 40 and 80 track.

The Doubler™: Percom's new proprietary double-density adapter for the TRS-80* computer.

- **Increase formatted storage capacity of your minidiskettes from 1 1/2 to almost 4 times.**
- **Use with standard 5-inch drives rated for double-density operation.**
- **The DOUBLER™ reads, writes and formats either signle - or double density disks. Only $219.95.**

NEW FROM MICRO-SYSTEMS!!!

Micro-Systems Software Inc. now has double density software available for TRS-80* Model I's that are equipped with the Percom Doubler.+

First is a disk editor called "Disk Zap 2.3". This editor will work either single or double density diskettes. It is track and sector oriented, and offers total access to all parts of the disk. It has the ability to format and backup diskettes as well as editing them.

Second is our new double density DOS. DOSPLUS 3.1D, like our regular DOS, will run 35-80 track drives; but offers the increased disk storage of double density.

Disk Zap is $19.95 and DOSPLUS 3.1 or 3.1D is $99.95. To order, call or write us at the address below. Master Card and Visa welcome. Orders accompanied by a personal check will be shipped when the check clears the bank.

master charge
VISA

MICRO SYSTEMS SOFTWARE INC.
Specializing in the Tandy Line
CIRCLE 165 ON READER SERVICE CARD
(305) 983-3390
5846 Funston Street
Hollywood, FL 33023

* TRS - 80 is a trademark of Tandy Corp
+ Doubler is a trademark of Percom Data Corp
Now available in Spanish

CIRCLE 165 ON READER SERVICE CARD

```
4010  H$="MOVIE THEATRE"
4020  GOTO 3740
4030  H$="APARTMENT BUILDING"
4040  GOTO 3740
4050  H$="DEPARTMENT BUILDING"
4060  GOTO 3740
4070  H$="BOOK STORE"
4080  GOTO 3740
4090  H$="NUCLEAR PLANT"
4100  GOTO 3740
4110  REM   *** CHOOSE CRIMINALS ***
4120  R8=INT(RND(0)*7)+1
4130  IF R8=3 OR R8=7 THEN 4150
4140  GOTO 4120
4150  R6=INT(RND(0)*10)+1
4160   FOR R9=1 TO 10
4170   A[R9]=R6
4180   R6=R6+R8
4190   IF R6>10 THEN 4210
4200   GOTO 4230
4210   R7=R6-10
4220   R6=R7
4230   NEXT R9
4240  REM   *** NAMES OF THE CRIMINALS ***
4250  GOTO A[R] OF 4260,4280,4300,4320,4340,4360,4380,4400,4420,4440
4260  N$="DOCTOR DOOM"
4270  RETURN
4280  N$="THE RED SKULL"
4290  RETURN
4300  N$="LEX LUTHER"
4310  RETURN
4320  N$="AMALEK"
4330  RETURN
4340  N$="BLACKROCK"
4350  RETURN
4360  N$="THE PENGUIN"
4370  RETURN
4380  N$="THE RIDDLER"
4390  RETURN
4400  N$="THE RAGMAN"
4410  RETURN
4420  N$="DARTH VADER"
4430  RETURN
4440  N$="THE KLINGON"
4450  RETURN
4460  REM   *** GET ENERGY ***
4470  G7=INT(RND(0)*5000)+1
4480  IF G7<4000 THEN 4470
4490  RETURN
4500  REM   *** TIME RUN OUT ***
4510  PRINT "YOUR TIME IS UP.  THE CRIMINALS HAVE GOTTEN TO THEIR"
4520  PRINT "SWITCH AND HAVE STARTED UP THEIR PLAN.  YOU HAVE LOST"
4530  GOTO 1830
4540  REM   *** REVISITING THE AREAS ***
4550  PRINT
4560  PRINT "YOU HAVE ALREADY VISITED THE ";H$;" SO YOU WILL HAVE TO MOVE ON"
4570  Q=T
4580  H$=C$
4590  PRINT
4600  GOTO 360
4610  REM   *** TRYING TO NOT MOVE AFTER NAILING A CRIMINAL ***
4620  PRINT
4630  PRINT "YOU HAVE JUST GOTTEN RID OF THE SUPER CRIMINAL IN THE ";H$
4640  PRINT "IT IS TIME TO GO ON"
4650  GOTO 750
4660  END
```

```
RUN
SUPERMAN


THIS IS THE GAME OF SUPERMAN
DO YOU WANT THE INSTRUCTIONS?YES

HERE ARE THE INSTRUCTIONS:

THERE ARE 10 SUPERCRIMINALS ON EARTH AND THEY HAVE
A MASTER PLAN WITH WHICH THEY WANT TO TAKE OVER THE
WORLD.  TO START IT MOVING, ONLY ONE OF THEM HAS TO PUSH THE
BUTTON.  IT IS YOUR JOB AS SUPERMAN TO GET RID OF ALL
10 SUPER CRIMINALS.  ALL 10 OF THEM ARE IN THE CITY OF
METROPOLIS, SCATTERED THROUGHOUT 18 DIFFERENT AREAS
WITH NO MORE THAN 1 IN AN AREA

HIT RETURN TO CONTINUE?
HERE ARE THE AREAS:

PARKING LOT -> SUPER MARKET -> JUNK YARD ->
GARBAGE DUMP -> DAILY PLANET -> SEWER ->
RIVER -> OCEAN -> AIRPORT ->
TRAIN STATION -> RADIO STATION -> T.V. STATION ->
AMUSEMENT PARK -> MOVIE THEATRE -> APARTMENT BUILDING ->
DEPARTMENT BUILDING -> BOOK STORE -> NUCLEAR PLANT

YOU CANNOT GO FURTHER LEFT THAN THE PARKING LOT AND NO
FURTHER RIGHT THAN THE NUCLEAR PLANT.  IF YOU TRY TO, YOU WILL BE
PLACED IN THE LAST ONE IN EITHER DIRECTION.

HIT RETURN TO CONTINUE?

TO CATCH AND DESTROY THE CRIMINALS, YOU HAVE FIVE DIFFERENT
ABILITIES, DESCIBED AS FOLLOWS:

1 - X-RAY VISION-USED TO SEE IF A CRIMINAL IS IN YOUR AREA,
OR AFTER THAT, TO SEE APPROXIMATELY HOW FAR AWAY HE IS FROM YOU
THE DISTANCE I TELL YOU IS NOT EXACTLY RIGHT, SO BE CAREFUL.
2 - FLYING-USED TO MOVE FROM ONE AREA TO ANOTHER, OR INSIDE OF
THE AREA YOU ARE IN.  IF YOU LAND RIGHT ON THE CRIMINAL, YOU LOSE, SO WATCH OUT
3 - HEAT VISION- CAN ONLY BE USED WHEN YOU ARE WITHIN 20 FEET
OR LESS OF THE CRIMINAL, AND IT HAS A 30% CHANCE OF NAILING
HIM.  IT TAKES UP 200 CALORIES OF ENERGY EACH TIME YOU USE IT
4 - SUPER STRENGTH- CAN ONLY BE USED WHEN YOU ARE WITHIN 10 FEET
OR LESS OF THE CRIMINAL, AND HAS A 50% CHANCE OF GETTING
HIM.  IT TAKES 100 CALORIES OF ENERGY TO USE IT EACH TIME
5 - SUPER BREATH- CAN ONLY BE USED WHEN YOU ARE WITHIN 30
FEET OF THE CRIMINAL, AND HAS A 20% CHANCE OF NAILING HIM.  IT TAKES
300 CALORIES OF ENERGY TO USE EACH TIME

THE ABILITIES NUMBER 1 AND 2 ARE USED TO LOCATE THE CRIMINAL AND
THE ABILITIES NUMBER 3,4,5 ARE USED TO NAIL THE CRIMINALS

HIT RETURN TO CONTINUE?

THE WAY THAT THE CRIMINALS CAN GET YOU IS LIKE THIS:
EACH ONE OF THE CRIMINALS HAS A POUND OF GREEN KRYPTONITE, WITH
WHICH TO GET YOU WITH.  THE CLOSER YOU GET TO THEM, THE MORE ENERGY
YOU LOSE.  IF YOU LOSE ALL OF YOUR ENERGY, YOU BECOME TO WEAK TO
DEFEND YOURSELF AND THE CRIMINAL CAN OVERCOME YOU, AND YOU LOSE
YOU HAVE A TOTAL OF 80 HOURS WITH WHICH TO STOP THEM FROM PUTTING
THEIR PLAN INTO ACTION.  IF YOU TAKE LONGER, THEN THEY GET TO THE
BUTTON, AND YOU LOSE ALSO.
```

« MISOSYS »

MISOSYS is proud to announce EDAS, a sophisticated Z-80 Editor Assembler for the '80 Model I & Model III

EDAS ***** JUST LOOK AT THESE FEATURES ***** **EDAS**

.. All EDAS commands and source text may be entered in either upper case or lower case providing ease of operation as a text editor.

.. Direct assembly from memory or disk by means of *GET assembler directives entered into the text buffer. This provides for a symbol table buffer area of over thirty thousand bytes with text buffer equal to your drive capacity!

.. Direct assembly to disk or memory for faster debugging operations! Branch allows you to execute your program, that has been assembled to memory, and then return to EDAS.

.. Source and object files interface directly with disk using TRSDOS (tm), VTOS (tm), or other compatible system.

.. DOS "System" command functions KILL, DIR, FREE, and LIST are available from within the environment of EDAS.

.. The Editor, with renumber, maintains command syntax identical to the BASIC editor. Global change allows the user to alter a string throughout a designated range of lines while block move relocates lines of text.

.. Great amounts of time and effort were expended to give this Editor Assembler the absolute best in ease of operation and functional efficiency. Optimize assembly programing time; use the Editor Assembler designed with the programmer in mind. EDAS is priced at $79.00 plus $3.00 S&H. A 72-page EDAS reference manual is included.

MISOSYS - Dept C
5904 Edgehill Drive
Alexandria, Virginia 22303
703-960-2998
Dealer Inquiries Invited

master charge VISA

CIRCLE 224 ON READER SERVICE CARD

QUALITY PROFESSIONAL & BUSINESS SOFTWARE FOR THE APPLE II AND APPLE PLUS COMPUTERS

LETTER MASTER - This is a lightning fast Word Processor which is simple to use and operates like a character oriented system. It features a menu driven operating system which allows entry, storage, editing, draft printing, and final justified printing. Editing includes line corrections (add up to 200 characters if you want), global search, string replacement, delete, add, and merge. Text floats as needed to make up lines of text. Print justified, unjustified, or a mixture. System prepares and prints form letters with its own 500 name/diskette full feature mailing list program. Applesoft II Disc. Item M-34, $139.95. Processor without mailing list and form letter, Item M-33, $69.95.

PROGRAMMER PLUS - A 16 lesson course in Applesoft II on two full disks or super-load tape which will teach you all you need to know to program in BASIC. Lessons cover all string, math and logical operations necessary for personal, scientific or business applications. Special units teach graphics and sound to add a little 'Apple Class' to your programs. Applesoft II, Item 35. Tape, $24.95. Disc, $34.95.

SCIENTIST - A powerful scientific data base and statistics program which will turn your Apple into a mathematical and graphics tool. It will do simple statistics or such complicated functions as Chi- Square, Normal, Student-t, and Poisson. With the Data Base element you can build your own analytical programs. Applesoft II Disc, $89.95.

[illegible] CA residents add sales tax

TO ORDER CALL TOLL FREE 24 HOURS
800-854-0561 Ext 802
In CA 800-432-7257
OR WRITE FOR TECHNICAL ASSISTANCE TO
MONUMENT COMPUTER SERVICE
Village Data Center - P.O. Box 603
Joshua Tree, California 92252

CIRCLE 152 ON READER SERVICE CARD

WHAT DO YOU GET WHEN YOU CROSS APPLES WITH JOYSTICKS?

JOYPLES!

The **Dual** Joystick system with the most appropriate shape for the APPLE II* computer.

Joyples come ready to plug in to your APPLE II Game I/O Port.

Each **Joyple** is a delicious red, hard plastic apple, with its own pushbutton and multi-direction joystick.

Get all the versatility & fun of a dual joystick system for only $39.95.

Joyples let you create exciting action games for 1 or 2 players. Here are a few that we offer:

Charge The Net, Tennis — **Joyples** let you move your paddles in all directions.....$12.95

Tank Assault — You control the speed & direction to attack your enemy $12.95

Please send ____Set(s) (2 Joyples/Set) of **Joyples** Joysticks @$39.95/set.

☐ **CHARGE THE NET, TENNIS**..... $12.95
☐ **TANK ASSAULT** $12.95
☐ **BOTH GAMES**..... $23.95

Specify Disk ☐ or Tape ☐.
Add 5% for postage/handling (15% foreign)
Mass. res. add 5% tax.
Send check or money order to:

NILONEL MFG.
5 Stevens Rd.
Worcester, MA. 01603

Dealer Inquiries Welcome
*Apple II is a Trademark of Apple Computer, Inc.

CIRCLE 203 ON READER SERVICE CARD

```
WHEN YOU NAIL THE CRIMINAL, ALL YOUR ENERGY IS RESTORED TO YOU
AND YOU CAN KEEP ON GOING TO GET THE REST OF THE CRIMINALS.
IF YOU LEAVE AN AREA, YOU CAN'T RETURN TO IT,
SO BE SURE TO GET THE CRIMINAL BEFORE YOU LEAVE, OR YOU CAN NEVER GET ALL TEN

ONCE YOU HAVE NAILED A CRIMINAL, YOU HAVE TO MOVE ON, AND YOU CAN DO NOTHING
ELSE UNTIL YOU DO SO

HIT RETURN TO CONTINUE?

YOU HAVE A TOTAL OF  4510     CALORIES OF ENERGY
TO DESTROY EACH CRIMINAL WITH, SO WATCH OUT.


ENERGY LEFT- 4510     LOCATION-PARKING LOT     HOURS LEFT- 80
COMMAND?1
YOU HAVE CAUGHT LEX LUTHER SOMEWHERE IN THE PARKING LOT
NOW ALL YOU HAVE TO DO IS FIND HIM

ENERGY LEFT- 4460     LOCATION-PARKING LOT     HOURS LEFT- 79
COMMAND?1
X-RAY VISION TELLS YOU THAT YOU ARE APPROXIMATELY  124
PACES AWAY FROM LEX LUTHER TO THE LEFT

ENERGY LEFT- 4115     LOCATION-PARKING LOT     HOURS LEFT- 78
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?0
HOW MANY PACES OVER TO THE LEFT?114

ENERGY LEFT- 3350     LOCATION-PARKING LOT     HOURS LEFT- 77
COMMAND?4
WHAT A ROUNDHOUSE PUNCH.  GOOD, BUT TOTALLY MISSED
LEX LUTHER

ENERGY LEFT- 2485     LOCATION-PARKING LOT     HOURS LEFT- 76
COMMAND?4
WHAT A PUNCH SUPERMAN.  IT KNOCKED OL LEX LUTHER BABY
DEAD AS A DOORNAIL.  THAT IS  1     DOWN AND  9     TO GO

ENERGY LEFT- 4510     LOCATION-PARKING LOT     HOURS LEFT- 75
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?1
HOW MANY AREAS OVER?1
TO THE LEFT OR RIGHT?RIGHT

ENERGY LEFT- 4510     LOCATION-SUPER MARKET     HOURS LEFT- 74
COMMAND?1
X-RAY VISION HAS DETECTED NO SUPER CRIMINAL HERE IN THE
SUPER MARKET, SO MOVE ON

ENERGY LEFT- 4510     LOCATION-SUPER MARKET     HOURS LEFT- 73
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?1
HOW MANY AREAS OVER?1
TO THE LEFT OR RIGHT?RIGHT

ENERGY LEFT- 4510     LOCATION-JUNK YARD     HOURS LEFT- 72
COMMAND?1
YOU HAVE CAUGHT THE KLINGON SOMEWHERE IN THE JUNK YARD
NOW ALL YOU HAVE TO DO IS FIND HIM

ENERGY LEFT- 4460     LOCATION-JUNK YARD     HOURS LEFT- 71
COMMAND?1
X-RAY VISION TELLS YOU THAT YOU ARE APPROXIMATELY  81
PACES AWAY FROM THE KLINGON TO THE LEFT
```



```
ENERGY LEFT- 3905     LOCATION-JUNK YARD     HOURS LEFT- 70
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?0
HOW MANY PACES OVER TO THE LEFT?70

ENERGY LEFT- 3140     LOCATION-JUNK YARD     HOURS LEFT- 69
COMMAND?4
WHAT A ROUNDHOUSE PUNCH.  GOOD, BUT TOTALLY MISSED
THE KLINGON

ENERGY LEFT- 2275     LOCATION-JUNK YARD     HOURS LEFT- 68
COMMAND?4
WHAT A PUNCH SUPERMAN.  IT KNOCKED OL THE KLINGON BABY
DEAD AS A DOORNAIL.  THAT IS  2     DOWN AND  8     TO GO

ENERGY LEFT- 4510     LOCATION-JUNK YARD     HOURS LEFT- 67
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?1
HOW MANY AREAS OVER?1
TO THE LEFT OR RIGHT?RIGHT

ENERGY LEFT- 4510     LOCATION-GARBAGE DUMP     HOURS LEFT- 66
COMMAND?1
X-RAY VISION HAS DETECTED NO SUPER CRIMINAL HERE IN THE
GARBAGE DUMP, SO MOVE ON

ENERGY LEFT- 4510     LOCATION-GARBAGE DUMP     HOURS LEFT- 65
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?1
HOW MANY AREAS OVER?1
TO THE LEFT OR RIGHT?LEFT

YOU HAVE ALREADY VISITED THE JUNK YARD SO YOU WILL HAVE TO MOVE ON

ENERGY LEFT- 4510     LOCATION-GARBAGE DUMP     HOURS LEFT- 65
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?1
HOW MANY AREAS OVER?1
TO THE LEFT OR RIGHT?RIGHT

ENERGY LEFT- 4510     LOCATION-DAILY PLANET     HOURS LEFT- 64
COMMAND?1
X-RAY VISION HAS DETECTED NO SUPER CRIMINAL HERE IN THE
DAILY PLANET, SO MOVE ON

ENERGY LEFT- 4510     LOCATION-DAILY PLANET     HOURS LEFT- 63
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?1
HOW MANY AREAS OVER?1
TO THE LEFT OR RIGHT?RIGHT

ENERGY LEFT- 4510     LOCATION-SEWER     HOURS LEFT- 62
COMMAND?1
YOU HAVE CAUGHT THE RIDDLER SOMEWHERE IN THE SEWER
NOW ALL YOU HAVE TO DO IS FIND HIM

ENERGY LEFT- 4460     LOCATION-SEWER     HOURS LEFT- 61
COMMAND?1
X-RAY VISION TELLS YOU THAT YOU ARE APPROXIMATLEY  59
PACES AWAY FROM THE RIDDLER TO THE RIGHT

ENERGY LEFT- 3800     LOCATION-SEWER     HOURS LEFT- 60
COMMAND?2
MOVE INSIDE OR OUT. (0-INSIDE     1-OUTSIDE)?0
HOW MANY PACES OVER TO THE RIGHT?49
```

creative computing

Basic Computer Games

Edited by David Ahl, this book contains 101 imaginative and challenging games for one, two, or more players — Basketball, Craps, Gomoko, Blackjack, Even Wins, Super Star Trek, Bombs Away, Horserace. Simulate lunar landings. Play the stock market. Write poetry. Draw pictures.

All programs are complete with listing in Microsoft Basic, sample run and description. Basic conversion table included. 125,000 copies in print. 192 pages softbound. [6C] $7.50.



More Basic Computer Games

Contains 84 fascinating and entertaining games for solo and group play — evade a man-eating rabbit, crack a safe, tame a wild horse, become a millionaire, race your Ferrari, joust with a knight, trek across the desert on your camel, navigate in deep space.

All games come complete with program listing in Microsoft Basic, sample run and description. 192 pages softbound. [6C2] $7.95.

All games come complete with program listing in Microsoft Basic, sample run and description. 200 pages softbound. [6C2] $7.95. TRS-80 Edition. 208 pages [6C4] $7.95.

The Best of Creative Computing

The first two years of **Creative Computing** magazine have been edited into two big blockbuster books. **American Vocational Journal** said of Volume 1, "This book is the 'Whole Earth Catalog' of computers." [6A] Volume 2 continues in the same tradition. "Non-technical in approach, its pages are filled with information, articles, games and activities. Fun layout." —**American Libraries.** [6B] Each volume $8.95.

Problems for Computer Solution

Here are 90 problems with a thorough discussion and references for each. Eleven types of problems are included, for example, arithmetic, algebra, geometry, number theory, probability and science. Even includes three classic unsolved problems and seven appendices. 104 pages softbound, $4.95 [9Z].

The teacher's edition contains solutions with complete listing in Basic, sample run and in-depth analysis explaining the algorithms and theory involved. 280 pp softbound, $9.95 [9Y].

Katie and the Computer

Fred D'Ignazio and Stan Gilliam. This is a delightful story told in words and full color drawings of Katie's adventures when she "falls" into a computer. In Katie's journey through the land of Cybernia she meets the Software Colonel, the Bytes, the Table Manager and even a ferocious Program Bug. Her journey parallels the path of a simple command through he stages of processing in a computer, thus explaining the fundamentals of computer operation to 4-10 year olds. Supplemental explanatory information is contained in the front and back end papers. 42 pp. hardbound $6.95. (12A)

Computer Music Record

A recording was made of the First Philadelphia Music Festival which is now available on a 12" LP record. It features eight different computer music synthesizers programmed to play the music of J.S. Bach, J. Pachelbel, Rimsky-Korsakov, Scott Joplin, Neil Diamond, Lennon & McCartney and seven others. The music ranges from baroque to rock, traditional to rag and even includes an historic 1963 computerized singing demonstration by Bell Labs. $6.00 [CR101].

The Best of Byte

This is a blockbuster of a book containing the majority of material from the first 12 issues of Byte magazine. The 146 pages devoted to hardware are crammed full of how-to articles on everything from TV displays to joysticks to cassette interfaces and computer kits. But hardware without software might as well be a boat anchor, so there are 125 pages of software and applications ranging from on-line debuggers to games to a complete small business accounting system. A section on theory examines the how and why behind the circuits and programs, and "opinion" looks at where this explosive new hobby is heading. 386 pp softbound. $11.95 [6F]

a gaggle of great books

Two Free Catalogs

Send for our big 20-page **Book Catalog** featuring a full line of Creative Computing Press and Book Service titles, back issues of Creative Computing Magazine, t-shirts, posters and games. A **Sensational Software Catalog** of over 400 outstanding microcomputer programs is also available. **Each** package is outlined in detail with accompanying screen photos and illustrations. Make the most of your computer resources with **Creative Computing!**

Computer Coin Games

Computer Coin Games by Joe Weisbecker aids newcomers to the field of computers by simplifying the concepts of computer circuitry through games which can be played with a few pennies and full sized playing boards in the book. Enhanced by outrageous cartoons, teachers, students and self-learners of all ages will enjoy this 96 page softbound book. [10R] $3.95.



The Colossal Computer Cartoon Book

Edited by David H. Ahl. The best collection of computer cartoons ever is now in its second printing. There are fifteen chapters of several hundred cartoons about robots, computer dating, computers in the office, and much more. Keep the book with your reference works. When needed, the right cartoon can say it all for you. Provides hours of fun and comic insight. 120 pp. 8½ x 11" softbound. (6G) $4.95.



Computers in Mathematics: A Sourcebook of Ideas

Here is a huge sourcebook of ideas for using computers in mathematics instruction. This large format book contains sections on computer literacy, problem solving techniques, art and graphing, simulations, computer assisted instruction, probability, functions, magic squares and programming styles.

One section presents over 250 problems, puzzles and programming ideas--more than is found in most "collection of problems" books.

Pragmatic, ready-to-use, classroom tested ideas are presented for everything from the most basic introduction to binary numbers to advanced techniques like multiple regression analysis and differential equations. Every item discussed has a complete explanation including flowcharts, programs and sample runs.

The book includes many activities that don't require a computer. And if you're considering expanding your computer facilities you'll find the section on how to select a computer complete with a microcomputer comparison chart invaluable.

Much of the material has appeared in **Creative Computing** but the back issues are no longer available. Hence this is your only source to this practical and valuable material. Edited by David H. Ahl, this mammoth 224-page softbound book costs only $15.95. (The individual issues, if they were available, would cost over $60.00). [12D]



The Impact of Computers on Society and Ethics: A Bibliography

REFERENCE

Gary M. Abshire.

Where is the computer leading us? Is it a menace or a messiah? What are its benefits? What are the risks? What is needed to manage the computer for society's greatest good? Will we become masters or slaves of the evolving computer technology? This bibliography was created to help answer questions like these. It contains 1920 alphabetical entries of books, magazine articles, news items, scholarly papers and other works dealing with the impact of computers on society and ethics. Covers 1948 through 1979. 128 pp hardbound. $17.95. [12E].

Be A Computer Literate



Marion J. Ball & Sylvia Charp

This informative, full color book is an ideal first introduction to the world of computers. Covers kinds of computers, how they work, their applications in society, flowcharts and writing a simple program. Full color drawings, diagrams and photos on every page coupled with large type make this book easy to read and understand. Used as a text in many schools. 66 pp softbound, $3.95 [6H].

To Order

Send your check for books plus $2.00 shipping and handling per order to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. NJ residents add 5% sales tax. Visa, Master Charge or American Express are also acceptable. For faster service, call in your bank card order toll free to

800-631-8112

(in NJ, call 201-540-0445)

creative computing

P.O. Box 789-M, Morristown, NJ 07960

CIRCLE 350 ON READER SERVICE CARD

Compleat Computer Catalogue

COMPUTERS

ENTRY-LEVEL SYSTEM

Vector Graphic Inc., has announced an intelligent, low cost entry-level computer system.

The VIP (Vector Intelligent Partner) is specifically designed to allow the user to grow into the full range of Vector products as individual demands warrant, rather than as price dictates.

The VIP's upgradability derives from its use of the same core unit as in Vector's higher priced systems — the Vector 3, an integrated video console with built-in S-100 electronics. The single 315K minidisk drive is housed separately, allowing addition of up to three more identical drives, or replacement by Vector's 2 Megabyte "Dualstor" diskette unit, by its 30 Megabyte "Megastor" Winchester drive, or by any other drive units Vector may release. $3695.

Vector Graphic Inc., 31364 Via Colinas, Westlake Village, CA 91362. (213) 991-2302.

CIRCLE 272 ON READER SERVICE CARD

S-100 BUSINESS SYSTEM

Angel-1 is a small business system designed for word processing, payables and receivables, inventory, sales activity, check and expense register, name-address-appointments, client-patient records, library and special events. Also available are payroll, purchasing, general ledger, mailing list and customized programs.

Housed in a formica desk it consists of an S-100 mainframe, Z-80 CPU, 64K RAM, two single-sided, single-density 8″ floppy disk drives, an 80 character x 24 lines CRT and a daisy-wheel printer. $7,995.

E & U Engel Consulting, 1719 So. Carmelina Ave., Los Angeles, CA 90025. (213) 820-4231.

CIRCLE 273 ON READER SERVICE CARD

MEMORY

64K DYNAMIC RAM BOARD

California Computer Systems Model 2065 64K Dynamic RAM board gives the S-100 user 64K fast, reliable memory.



Conforming to the IEEE proposed standards for the S-100 bus, fast enough to require no Wait states with a 4 MHz CPU, and supporting front-panel operations, the 2065 is compatible with most S-100 systems.

In addition, it supports memory expansion to 512K through its bank-selection system. Used by Cromemco and others, the bank-select system allows the software-enabling of a bank through the output of a bank-select byte to the bank port. Berg jumpers on the 2065 allow selection of the board's bank and the bank port's address.

California Computer Systems, 250 Caribbean, Sunnyvale, CA 94086. (408) 734-5811.

CIRCLE 274 ON READER SERVICE CARD

EXPANDABLE BOARD FOR Z-80

QT Computer Systems has announced the Expandable + Dynamic Memory Board, which works with most Z-80 CPU boards including Cromemco Systems (ZPU-64K), S.D. Systems (SBC 100, 200 and Z-80 Starter Kit), SSM (CB2A), Jade (Big Z), QT (SBC+ 2/4), Ithaca Audio and North Star.

The Expandable + is available as a bare board, kit or assembled and tested unit. It supports 16K, 32K, 48K or 64K of memory, and uses a 3242 refresh chip with delay line, as well as a Z-80 refresh signal. Prices range from $70 for the bare board and manual to $625 for the 64K assembled

SAVE MORE THAN 20%!
NORTH STAR INTERTUBE MICROTEK
ZENITH RCA-COSMAC ITHACA
THINKER TOYS GODBOUT SUPERBRAIN

THE SMARTEST COMPUTERS AT THE SMARTEST PRICE

HORIZON-1-32K-DOUBLE DEN ASSM & TESTED	$1994		
HORIZON-2-32K-DOUBLE DEN ASSM & TESTED	2299		
2 NORTH STAR SOFTWARE DISKS w/HORIZON.....	FREE		
NORTHWORD	$ 299	MAILMANAGER	239
INFOMANAGER	369	GENERALEDGER	799
HRZ-64Q+HARDDISK	7199	HRZ-2-32K-Q ASM	2699
NS HARD DISK 18M	3939	NS PASCAL ON DISK	190
NORTH STAR BASIC	FREE	COLOR!!	PHONE
ITHACA COMPUTER	2695	ITHACA RAM 64K	845
8086 CPU 16 BIT	556	SSM Z80 CPU KIT	221
MEAS 64K RAM ASM.	599	SSM VIDEO BRD VB3	412
GODBOUT 16K STAT	285	SUPERRAM 32K	580
DISCUS/2D + CP/M	975	SUPERRAM 16K	290
2D ADD DRIVE	650	2+2 ADD DRIVE	975
TARBELL CONTROLER	295	DISCUS/2+2	1259
INTERTUBE II	725	HARD DISK 26 Mb	3995
SUPERBRAIN	2395	SUPERBRAIN QUAD	2995
ZENITH Z-19 A & T	739	ZENITH H-11	2995
HEATH Z-89 48K	2495	MICROTEK PRINTER	675
ANADEX 9500-1	1389	ANADEX 8000	865
NEC PRINTER	2799	SECRETARY WORD PRO	77
TEXTWRITER III	112	GOFAST SPEEDBASIC	71
PDS Z-80 ASSEMBLER	89	NS BASIC COMPILER	??
EZ-80 Z-80 TUTOR	25	EZ-CODE IN ENGLISH	71
ECOSOFT ACCOUNTNG	315	WORDSTAR	325
BOX OF DISKETTES	29	BASIC DEBUGGER	89

Which Computers are BEST? BROCHURE.....FREE
ORDER 2 or more COMPUTERS.....BIGGER DISCOUNTS
WE WILL BEAT OUR COMPETITION'S PRICE
FACTORY ASSEMBLED & FACTORY WARRANTY
AMERICAN SQUARE COMPUTERS
KIVETT DR * JAMESTOWN, NC 27282 * 919-889-4577

CIRCLE 105 ON READER SERVICE CARD

INTRODUCING HEWLETT-PACKARD'S HP-41C. A CALCULATOR. A SYSTEM. A WHOLE NEW STANDARD.

The new HP-41C from Hewlett-Packard is a powerful programmable calculator that features: an LCD display with alphanumeric capability, 63 registers of data storage or up to 400 lines of program memory — expandable to 319 registers or up to 2,000 program lines, up to 6 levels of subroutines, 10 conditionals and 56 internal flags, specific loop control, indirect addressing, local and global branching, Continuous Memory, RPN logic.

And when you need them: Memory Modules — plug-in modules for storing programs and data; an "extra smart" Card Reader; a Printer that prints upper and lower case alpha plus special characters and does high resolution plotting, the Wand to input programs in bar code form (available early 1980); Application Modules — preprogrammed, plug-in modules that give solutions to a wide range of problems.

The HP-41C lets you reassign any standard function, any programs you've written, or programs provided in the Application Modules — to any keyboard location you want. And of course Hewlett-Packard backs the HP-41C with total software support including an Owner's Manual and thousands of programs in the HP-41C Applications Pacs, Solutions Books, and the HP Users' Library.

Experience this remarkable instrument. The new HP-41C from Hewlett-Packard. A calculator. A system. A whole new standard.



1.1 Memory Modules

2.1 The Printer

The computer corner

White Plains Mall, 200 Hamilton Ave.
White Plains, N.Y. 10601
(914)WHY-DATA.

CIRCLE 126 ON READER SERVICE CARD

16K MEMORY EXPANSION KIT FOR YOUR TRS-80, APPLE, AND S-100 COMPUTER

only $59

- 200 Nsec Access, 375 Nsec Cycle
- Burned-in and Fully Tested
- 1 yr. Parts Replacement Guarantee
- Qty. Discounts Available

BETA COMPUTER DEVICES
1230 W. COLLINS AVE.
ORANGE, CA 92668
(714) 633-7280

For Apple™—TRS-80™—Super Brain™ and others using 4116

RAM RIOT!

Mostek

16k- as low as $39.95

Guaranteed 200ns/55°c RAM

1-5 sets	49.95 each
6-10	44.95 each
11 and up	39.95 each

Berliner Computer Center
102 Jericho Tpke.,
New Hyde Park, NY 11040
(516) 775-4700

Add $2.50 shipping/handling charges. No C.O.D.'s N.Y.S. residents add applicable sales tax. Check or money orders only.

CIRCLE 115 ON READER SERVICE CARD

THE LEAST EXPENSIVE PROGRAMS YOU CAN BUY.

NONPROFIT PEOPLE'S SOFTWARE

Up to 77 high-quality programs for TRS-80, only $10.95

LEVEL II TAPES:

'Tiny' Pascal runs on any 16K Level II system, includes the programming structuring capabilities of full Pascal, but not data structuring.

Able to compile Z-80 machine code, programs run about five-times faster than Level II Basic—graphics run eight-times faster! Requires use of T-Bug and Edit-Assembler.

Tape 3, People's Pascal I $19.95

Tape 6P PASPATCH allows old Pascal II (no longer available) to use printer, floppy disk $15.00

Tape 1, 34 business, educational, game programs $10.95
Tape 2, 77 programs from Osborne book: 'Some Common Basic Programs' $10.95
Tape 5, 24 business, educational, game programs $10.95
Tape 7, 31 business, educational, game programs $10.95
Tape 8, about 30, including 1,700-baud tape loader $10.95

Overseas, add $1us per tape for postage
California residents add 6 pct tax Dealer inquiries invited

COMPUTER INFORMATION EXCHANGE
Box 159
San Luis Rey CA 92068

CIRCLE 124 ON READER SERVICE CARD

OHIO SCIENTIFIC

. . . . . With This Ad . . . . . .

HAZELTINE 1420	$780
CENTRONICS 779 W/TRACTOR	$969
NEC SPINWRITER	$2250

. . . . . Get the Catalog . . . . . .
&
Our Low Prices

DATA PRODUCTS MAINTENANCE CORP.
OHIO SCIENTIFIC

9460 Telstar Avenue (213) 573-5991
El Monte, CA 91731 (714) 994-4180

CIRCLE 178 ON READER SERVICE CARD

AT LAST!

Mass production prices on this high-quality software. Buy direct and save 50%. Now, also available for CBASIC on CP/M and MBASIC on HEATH HDOS

DATA BASE MANAGER Mod-I $69 Mod-II $199
You can use it to maintain a data base & produce reports without any user programming. Define file parameters & report formats on-line. Key random access, fast multi-key sort, field arith., label, audit log. No time-consuming overlays. 500 happy users in a year.

A/R Mod-I $69 Mod-II $149
Invoices, statements, aging, sales analysis, credit checking, form input, order entry. As opposed to most other A/R, ours can be used by doctors, store managers, etc.

WORD PROCESSOR Mod-I $49 Mod-II $49
Center, justification, indentation, page numbering. Mod-I version features upper/lower case without hardware change!

MAILING LIST Mod-I $59 Mod-II $99
The best! Compare and be selective. Form input, 5-digit selection code, zip code ext., sort any field, multiple labels. Who else offers a report writer?

INVENTORY Mod-I $99 Mod-II $149
Fast, key random access. Reports include order info, performance summary, E.O.Q., and user-specified reports. Many have converted their inventory system to ours!

GL, A/R, A/P, & PAYROLL Mod-II $129 each
Integrated accounting package. ISAM, 100+ page manual. Uses 80 column screen, not 64. A $1,000 value. Dual disk required.

L216, a cassette package of 10 business programs for Level II 16K systems. $59. Includes word processor & data base. Poker game $19.

MICRO ARCHITECT, INC.,
96 Dothan St., Arlington, MA 02174

CIRCLE 222 ON READER SERVICE CARD

SORCERER BASIC EDITOR

This program eliminates the TEDIUM of retyping. You can move a blinking cursor (similar to that on the Word Processor Pac) in all four directions on the screen where the listing of your program is displayed. When you wish to make a change, you simply type over it.

Includes: HASH erases part of line on right of cursor. EXPAND allows you to add things in the middle of your line. (like parentheses)
DELETE removes unwanted material from any part of the line.
(TAB) makes the cursor jump to the end of the line (not the screen)
(SHIFT) (TAB) makes it jump to the left side of the screen

This editor does limit you to 64 character but each BASIC command (such as PRINT, FOR, NEXT etc.) is automatically counted as one character-so you can fit much more in 64 characters.

You can also repeat BASIC or MONITOR commands such as SAVE as long as they are still on the screen.

SEND $14.95 CHECK/MONEY-ORDER
TO: •••SPECIFY MACHINE SIZE!•••

CARL B. PAGE
1980 RUTGERS CIR.
E. LANSING MI. 48823

ALLOW 10 DAYS FOR DELIVERY.

CIRCLE 237 ON READER SERVICE CARD

NEW MUSIC SOFTWARE

TRS-80 LEVEL II (16K)

MINI-KEYS play 7 octaves like any keybd. instrument. 100's of speeds. **$12.95**

ReKord — hear prerecorded data play. Stars & Stripes Forever, Hallelujah! ***$16.95***

MYTEE MUSIC — assemble over 3000 tones in a music score. E-Z to use. E-Z to edit. Whole notes thru 1/64, dotted & triplet. 100's of speed signatures. Instruction booklet makes program fun to use!

MYTEE MUSIC-1	good	**$14.95**
MYTEE MUSIC'2	better	**$29.95**

MYTEE MUSIC-1	good	**$14.95**
MYTEE MUSIC-2	better	**$29.95**
MYTEE MUSIC-3	best	**$44.95**

(add $5.00 for disc)

MYTEE MUSIC
P.O. Box 2432
Evansville, IN 47714

CIRCLE 227 ON READER SERVICE CARD

and tested unit.

QT Computer Systems, Inc., 15620 South Inglewood Ave., Lawndale, CA 90260. (213) 970-0952 or (800) 421-5150.

CIRCLE 275 ON READER SERVICE CARD

COLOR FOR CROMEMCO



Cromemco introduces two new two-port memory boards, the 16KTP and the 48KTP, for use with their Model SDI Color Graphics Interface.

The SDI is a high resolution, color graphics interface which can be used to display images with up to 754 x 482 point resolution. This interface and the two-port memory, when used in conjunction with an RGB color monitor, turn any Cromemco computer into a highly sophisticated graphics system with features unparalleled in the industry.

The two-board color graphics interface is available for $595. The 16K two-port memory board is $795 and the 48K two-port memory board is $1785.

Cromemco, Inc., 280 Bernardo Ave., Mountain View, CA (415) 964-7400.

CIRCLE 276 ON READER SERVICE CARD

S-100 COMPATIBLE 64K RAM MEMORY



Measurement systems & controls announces the addition of the DM6400 64K RAM module to its line of computer memory systems.

The DM6400 RAM modules are fully compatible with Cromemco, North Star, Processor Technology's Sol 20, Vector Graphics, Ithaca Audio, Mits, Marin Chips M9900 and most other 8080 and Z80A based S-100 systems. It will also run with most 8085, 3 MHz CPU boards.

Each S-100 compatible DM6400 contains a dynamic memory array, bus interface/control logic, on-board crystal timing, refresh oscillators, and voltage regulators.

The memory board is deselectable in 4K increments and has a power dissipation of 8 Watts maximum.

Measurement systems & controls, 867 North Main St., Orange, CA 92668. (714) 633-4460.

CIRCLE 277 ON READER SERVICE CARD

TERMINALS & I/O

TOUCH SENSITIVE CRT

The ISI Public Access Terminal features a rugged touch sensitive screen divided into multiple transparent, capacitive touch pads that simplify interactive dialog and eliminate the need for a keyboard.

Designed for unattended public use, all switches, adjustments, and cable connections are inaccessible to prevent tampering. Power and maintenance modes are key operated.

Equipped with a program selectable two-page display memory, the Z-80 based terminal incorporates a high resolution 15″ CRT and a 10 x 14 dot matrix to provide a large, easy-to-read display. Full upper and lower case ASCII character set is standard; customer specified fonts up to 240 characters are available. $2,800.

Interaction Systems, Inc., 24 Munroe St., Newtonville, MA 02160. (617) 244-9557.

CIRCLE 278 ON READER SERVICE CARD

LETTER-QUALITY PRINTER



Micromatic Corporation introduces the Micromatic 80, a TTL based interface designed to integrate the TRS-80 and many other small computers. It consists of an IBM Selectric computer printer combined with a compact interface.

The letter-quality printer has a speed of 8 to 9 CPS. The Micromatic 80 connects to the keyboard interface port or the expansion interface. All code conversions and timing software are contained within the Micromatic 80, and no special software is required. $795.

The Micromatic Corporation, 5747 West 85th St., Indianapolis, IN 46278. (317) 299-8614.

CIRCLE 279 ON READER SERVICE CARD

PARALLEL PRINTER INTERFACE FOR ATARI

Macrotronics, Inc. has introduced a parallel printer interface for the Atari line of microcomputers. It allows the Atari 400 or 800 to drive directly a parallel ASCII printer.

A cable assembly plugs into controller jacks 3 and 4 on the front of the computer. A short program is read into the computer from cassette; from then on, all printer

data is directed to the parallel printer interface instead of the Atari serial port.

The program remains in memory until the computer power is turned off. The interface works equally well with Basic, DOS, or the Atari Assembler/Debug. $69.95.

Macrotronics, Inc., 1125 N. Golden State Blvd., Turlock, CA 95380. (209) 667-2888.

CIRCLE 280 ON READER SERVICE CARD

WORD PROCESSING QUALITY CRT

The WP2000 word processing quality CRT terminal from Industrial Micro Systems, Inc. features LSI microprocessor control with expandable control program, along with EPROM character generator and special function keys which make it adaptable for foreign languages and other special applications.

A high resolution video monitor provides a clear display utilizing a 9 x 13 dot matrix. Screen size is 12" displaying 25 lines including a status line with user message capability.

The WP2000 also features normal and reverse video, blinking fields, underlined fields and highlighted fields. Other special features include upper and lower case characters with descenders, 2-page memory, automatic self test, pen interface, and printer port.

Industrial Micro Systems, Inc., 628 Eckhoff St., Orange, CA 92668. (714) 978-6966.

CIRCLE 281 ON READER SERVICE CARD

SERIAL OUTPUT ASCII ENCODED KEYBOARDS

Two 128-character ASCII encoded keyboards with asynchronous serial output, the VP-606 with a 58-key typewriter format and the similar VP-616 with an additional 16-key calculator-type keypad, have been added to the RCA



MicroComputer Products line.

Professional-quality keyboards suitable for demanding environments, the units incorporate high-technology, flexible-membrane key switches with a light positive activation pressure. Contact life is rated at greater than five million operations. Units are priced at $46. for parallel output with case and $65. for serial output with case.

MicroComputer Products Marketing, RCA, New Holland Ave., Lancaster, PA 17604. (717) 697-7661.

CIRCLE 282 ON READER SERVICE CARD

PERIPHERALS

FULL-COLOR HARD COPY

Full-color hard copy reproductions of computer graphics are available with the introduction of the Videoprint Systems from Image Resource.

The Videoprint 3000 series, priced from $2,990 to $3,550, is used as a hard copy computer peripheral for the educational, small business, and personal computer graphics markets. The Videoprint 5000 series, priced at $5,950, is a higher performance system, equipped with more flexibility for the industrial and commercial computer graphics user.

Both systems are self-contained and fully automatic for minimizing optical distortion, with color, brightness, and exposure adjustments under microprocessor control. Both produce 4″ x 5″ hard copy prints in seconds. Also available are Polaroid SX-70 and 35mm sizes.

Image Resource, 2260 Townsgate Rd., Westlake Village, CA 91361. (805) 496-3317.

CIRCLE 284 ON READER SERVICE CARD

INTERACTIVE VIDEO INTERFACE



The C.A.V.I. Model 400 from BCD Associates, Inc. is a single board video tape controller for Apple II microcomputers. The system hardware/software permits precise video tape positioning by counting pulses from the control track of the tape.

The interface contains a video/audio switcher to allow alternate display of computer-generated or taped video on a single monitor. The system will control industrial type VHS, Beta, and ¾″ video recorder/players. No modifications to the computer or the VTR are required.

Basic software is included on disk to allow the user to "Search To" the beginning of a video scene and "Play Until" the end of that scene. Starting and ending frame numbers of each scene may be saved to the disk for future reference. $495.

An advanced Computer Assisted Instruction software system is available on a separate disk. "The Instructor" allows persons with no computer expertise to create and modify C.A.I. lessons and video tape logs. $295.

BCD Associates, Inc., 1216 N. Blackwelder Ave., Oklahoma City, OK 73106. (405) 524-7403.

CIRCLE 285 ON READER SERVICE CARD

DIGITIZER FOR APPLE

Computer Station offers a high speed binary video digitizer for the Apple II. The Dithertizer II is a peripheral board for the Apple II which utilizes a video camera with external sync to load the high resolution page of the Apple II with any image that can be captured with the video camera.

The Dithertizer II was designed as a frame grabber, DMA type, digitizer to require only one frame or 1/60th of a second to capture a binary image (140 nanoseconds per pixel).

Software is included to build dithered (pseudo gray scale via half tones) images from multiple binary images and to capture image intensity contours using image subtraction. $300.

Computer Station, 12 Crossroads Plaza, Granite City, IL 62040. (618) 452-1860.

CIRCLE 286 ON READER SERVICE CARD

BAR CODE READER FOR APPLE

Advanced Business Technology, Inc. announces the BarWand, the latest addition to its line of Apple peripherals.

The BarWand is a precision electro-optical device which reads programs and data when the user guides it along a line of bar code. When bar code has been successfully entered, a scan tone sounds, indicating the last line of data was correctly read.

The wand contains a light-emitting diode and a photosensor that detects changes in the light reflected from the material being scanned. $195.

Advanced Business Technology Inc., 12333 Saratoga-Sunnyvale Rd., Saratoga, CA 95070. (408) 446-2013.

CIRCLE 287 ON READER SERVICE CARD

SYSTEMS SOFTWARE

SYSTEMS

ZDM is a **Z-80 debugger** and monitor designed to operate within the CP/M environment. It is patterned after and intended to replace the CP/M module DDT for Z-80 and 8080 software development and general Z-80 and 8080 program debugging. $30. RD Software, 1290 Monument St., Pacific Palisades, CA 90272. (213) 454-8270.

CIRCLE 288 ON READER SERVICE CARD

Digital Research has introduced **CP/M-86**, an operating system for Intel 8086/8088-based microcomputers. The file format of CP/M release 2 has been retained for compatibility. Also available is an enhanced version of the **PL/I-80 Compiler** and Run-Time System. PL/I-80 1.1 features an overlay system which can produce a "menu-driven" application program, where each user command references an overlay module. Digital Research, P.O. Box 597, 801 Lighthouse Ave., Pacific Grove, CA 93950. (408) 649-3896.

CIRCLE 289 ON READER SERVICE CARD

Micro Video **Monitor for the Interact** gives users access to the machine language capability of the computer. It allows combined Microsoft Basic and machine code programming. $19.95. Micro Video, P.O. Box 7357, 204 E. Washington St., Ann Arbor, MI 48107. (313) 996-0626.

CIRCLE 290 ON READER SERVICE CARD

Accel2 for the TRS-80 is a double-optimising compiler which produces compact machine code translations of selected Disk Basic statements and functions in all variable types. $88.95. Allen Gelder Software, Box 11721 Main Post Office, San Francisco, CA 94101.

CIRCLE 291 ON READER SERVICE CARD

NEWDOS/80 for the TRS-80 is an enhancement which extends the capabilities of NEWDOS 2.1. It is designed for the sophisticated user and professional programmer. $149. Apparat, Inc., 4401 S. Tamarac Pkwy., Denver, CO 80237. (303)741-1778.

CIRCLE 292 ON READER SERVICE CARD

Dynasoft **Pascal**, a cassette-based Pascal program development system, is a compact p-code implementation of a Pascal subset. The package includes the compiler, interpreter, and line-oriented editor and will run on a 16K Apple II or Apple II Plus. $50. Dynasoft Systems, Ltd., P.O. Box 51, Windsor Junction, Nova Scotia, Canada, BON 2VO.

CIRCLE 293 ON READER SERVICE CARD

LANGUAGES

Softronics has released version 2.3 of the **APL** language for computers using the CP/M operating system. A minimum of a 48K CP/M system is required. $350. Softronics, 36 Homestead Lane, Roosevelt, NJ 08555.

CIRCLE 294 ON READER SERVICE CARD

Forth Version 1.7 for the Apple includes the Forth Interest Group programming language plus development aids and a tutorial manual. It also features a structured macro assembler which allows the user to create machine-language subroutines. $140. Cap'n Software, P.O. Box 575, San Francisco, CA 94101.

CIRCLE 295 ON READER SERVICE CARD

BPilot is a version of Pilot for the TRS-80 which is compatible with Basic and allows the user to intermingle Basic and Pilot instructions in his program. $24.95. CAMI, P.O. Box 2030, Goleta, CA 93018.

CIRCLE 296 ON READER SERVICE CARD

Appilot II adds hi-resolution graphics, speech and the ability to accept student input from an optional light pen to the capabilities already included in the original Appilot. Designed to allow educators and courseware developers to write lessons using text, color graphics and sound, the language will run on an Apple II or Apple II Plus with one disk drive, Integer Basic and 48K. $99.95. Muse Software, 330 North Charles St., Baltimore, MD 21201. (301) 659-7212.

CIRCLE 297 ON READER SERVICE CARD

The **Waterloo Basic** software package for the PET which incorporates structured programming techniques and the constructs necessary for effective instruction in programming style and discipline. The enhancements are coded in 6502 machine language and reside in 2716 EPROM. The package is compatible with Basic V.2 and Basic V.4 for 40-column and 80-column PETs. Computer Systems Group, University of Waterloo, Waterloo, OT, Canada N2L 3G1.

CIRCLE 298 ON READER SERVICE CARD

DATA BASE MANAGEMENT SYSTEMS

Omnifile is an in-memory database program with sorting, formatting and computational features for PET or CBM computers with at least 16K of memory. Cassette, $30; disk, $36. Channel Data Systems, 5960 Mandarin Ave., Goleta, CA 93017. (805) 964-6695.

CIRCLE 299 ON READER SERVICE CARD

Filemaster II for the Apple II includes four Applesoft programs: File Designer, a menu-driven guide for developing the

structure of the information; Search and Retrieval, for entering data and retrieving records; Sort Information, which provides the required input for use with the Single Disk Sort by Datacope; and File Converter, which converts Filemaster I files. It requires 48K, Applesoft in ROM and a disk drive. $99.50. Rainbow Computing, Inc., Garden Plaza Shopping Center, 9719 Reseda Blvd., Northridge, CA 91324. (213) 349-5560.

CIRCLE 301 ON READER SERVICE CARD

APPLICATIONS SOFTWARE

BUSINESS

Technology Systems announces an integrated **business software** system which includes accounts receivable, accounts payable, order entry, invoicing, payroll and name/address. The system is designed to run on any 8080/Z80 based computer using North Star Basic. The program modules are available on single, double or quad density 5 ¼" or 8" floppy disk or a hard disk. Technology Systems, 208 Greenwood Ave., Bethel, CT 06801.

CIRCLE 302 ON READER SERVICE CARD

Sales is a program for the TRS-80 that prints invoices, sales slips, packing slips and address labels using standard blank forms. $39.95. **Sales Status** allows the user to generate sales reports, sales tax summaries and customer files or mailing lists from files created by the Sales program. $39.95. A 32K disk system and line printer are required. Bluebird's Inc., 2267 23rd St., Wyandotte, MI 48192. (313) 285-4455.

CIRCLE 303 ON READER SERVICE CARD

Mail 80 is a disk-based mailing system for the TRS-80 Model II. All names may be contained in one file or separate files may be maintained for different groups. $69.95. Mark Gordon Computers, 15 Kenwood St., Cambridge, MA 01239.

CIRCLE 304 ON READER SERVICE CARD

Small Business Systems Group announces an **Invoicing System** designed to run in conjuction with the existing SBSG Osborne Accounts Receivable systems for the TRS-80 Models I and II. Small Business Systems Group, Inc., 6 Carlisle Rd., Westford MA 01886. (617) 692-3800.

CIRCLE 305 ON READER SERVICE CARD

The **Estimator** is a computerized worksheet which allows the user to enter item titles, material quantities, material unit costs, hours of labor and miscellaneous items. Totals are produced for both the individual items and the estimate as a whole. Prices range from $40 to $95. The **Framing Calculator**, estimates material quantities and hours of labor required for general wood frame construction. Prices range from $125 to $150. Both programs are avilable for TRS-80 Models I and II, CP/M on Micropolis and Standard 8" CP/M. Mendocino Software, P.O. Box 1564, Willits, CA 95490. (707) 485-7893 or (707) 459-9130.

CIRCLE 306 ON READER SERVICE CARD

GL, a **general ledger** program is the heart of an integrated accounting package for the TRSDOS 1.2 on TRS-80 Model II. Features include double entry accounting, ISAM, and 80-column screen display. It is interactive and menu-driven. $129. Also available for the TRS-80 Model II is PR, a **payroll** system which calculates payroll for hourly, salaried and commissioned employees while maintaining monthly, quarterly and yearly totals. $129. MicroArchitect, 96 Dothan St., Arlington, MA 02174. (617) 643-4713.

CIRCLE 307 ON READER SERVICE CARD

A **Job Costing** option has been added to the Microcomputer Consultants General Ledger System. Designed for CP/M systems, it provides a job analysis report, showing the ratio of costs to income by job; job budget report, comparing actual expenditures with the amount budgeted; and class analysis report, showing costs by classification across all jobs. $600. Microcomputer Consultants, P.O. Box T, 1623-A Fifth St., Davis, CA 95616. (916) 756-8104.

CIRCLE 308 ON READER SERVICE CARD

SoftCare is a series of programs designed to automate the billing and record-keeping functions in a medical office of

one to thirty physicians. The system operates on any Z-80, 6502 or DEC 11/03 computer which runs UCSD Pascal Version 2.0, and requires 27K of usable RAM. Professional Business Software, 119 Fremont St., San Francisco, CA 94105. (415) 546-1596.

CIRCLE 311 ON READER SERVICE CARD

Property Management, designed for use in the real estate business, produces reports which track all forms of income property. **Financial Analysis** provides cash flow analysis, tax analysis and information on tax deferred exchanges for income property. Both programs run under CP/M. American Software Corporation, P.O. Box 427, Mill Valley, CA 94941. (415) 381-1600.

CIRCLE 312 ON READER SERVICE CARD

Tax/Saver is an interactive program designed to help the taxpayer prepare his or her return. If there is more than one way to prepare the return, the program allows the user to compare the results and choose the most advantageous one. It is avilable for TRS-80 Level II 16K on three cassettes for $65, or for a 32K TRS-80 with two disk drives on four diskettes for $80. Micromatic Programming Co., P.O. Box 158, Georgetown, CT 06829. (203) 544-8777.

CIRCLE 313 ON READER SERVICE CARD

MenuManager was written by a restaurateur to monitor food costs, predict sales trends and calculate the estimated profit of a restaurant. Using two 5 ¼", double-density diskettes, the program can store 1200 recipes, 100 menu items and 100 raw food items. Microsource, 1425 West 12th PL., Tempe, AZ 85281. (602) 894-9247.

CIRCLE 314 ON READER SERVICE CARD

CDS Corporation announces **Mail List**, a user-oriented program which stores up to 1050 records on each disk. Mailing labels can be sorted alphabetically, by zip code, by status (active or inactive), or by a six-character utility field designated by the user. The program runs on a Commodore CBM 16K or 32K computer with CBM 2040 disk drives and a CBM or ASCII printer. $95. CDS Corporation, 695 East Tenth North, Logan, UT 84321. (801) 753-6990.

CIRCLE 315 ON READER SERVICE CARD

MDMS Planner is a desk top business planner which provides financial and business information to users of Ohio Scientific computers. Features include: unlimited model size, formatted report generation, English-like calculation rules, and a plotting capability. The system is compatible with Ohio Scientifics MDMS data base manager. Ohio Scientific, 1333 S. Chillicothe Rd., Aurora, OH 44202. (800) 321-6850.

CIRCLE 316 ON READER SERVICE CARD

National Software Marketing announces the release of a system for the **management of apartment and condominium complexes**. The system includes three modules: Tentroll ($200); Maintenance, Security Deposit and Three-day Notice ($100); and General Ledger and Accounts Payable ($145). It is written in Basic for the TRS-80 Model II. National Software Marketing, Inc., P.O. Box 6195, Hollywood, FL 33021. (305) 625-6062.

CIRCLE 349 ON READER SERVICE CARD

Configurable Business System provides **customized accounting** systems, including payables, receivables, inventory control and order entry. It features a comprehensive report generator for producing invoices, purchase orders, re-order reports, special reports and mailing labels; the ability to produce and read ASCII data files; menu-chaining; and batched updating. The system requires a 48K CP/M compatible system and at least 200K bytes of mass disk storage. $395. Lifeboat Associates, 1651 Third Ave., New York, NY 10028 (212) 860-0300.

CIRCLE 317 ON READER SERVICE CARD

ASCII EXPRESS II
By Bill Blue

THE MOST COMPLETE COMMUNICATIONS PACKAGE FOR THE APPLE II AVAILABLE

This professional terminal system includes:

- Full upper/lower case support
- Upload/download files to ANY type of online computer
- Built-in line editor for files
- Keyboard macros for efficient operation

Recommended system requirements include a 48K APPLE II with disk, FP ROM or language card, and Micromodem or Comm. card.

$59.95 plus 6% for Calif. residents

Available from your local computer store or:

southwestern data systems

P.O. BOX 582-C2 • SANTEE, CA 92071

(714) 562-3670

CIRCLE 184 ON READER SERVICE CARD

APPLE II® DISK SOFTWARE

Professional Time and Billing

2 disk drive program, written in assembly language and applesoft II completely menu-driven. Maintain all billing of clients and personnel. Generates Statements. Numerous reports based on all types of criteria. Easy data entry for rates, clients, and matters. Has search, sort, charge (On-screen editing), view and balance forward. If you are a job contractor, attorney, accountant, general consultant, or any one that needs to charge or account for time, this program is must. complete turnkey operation. Numerous reports are produced to aid in the time analysis process. Holds 120 employees & up to 300 client with a max of 1600 transactions per period. All this and much more.

Requires 48K and Applesoft II on ROM (or Apple II Plus). Accommodates serial1parallel 132 column printer. Error protection devices provided. Program diskette and instruction manual-$325.00

MAILING LIST PROGRAM-Print labels sorted or searched by 6 fields. On-screen editing. Line up routine. $40.00

Inventory Program-$140
Payroll Package-$240 (Specify state)
Apartment Manager-$325
IFO-DATA BASE MANAGER-$100
Speed Reading-$100

Send check/money order to:

SOFTWARE TECHNOLOGY for COMPUTERS (STC)
P.O. Box 428
Belmont MA 02178

or available from your local dealer

CIRCLE 253 ON READER SERVICE CARD

APPLE II Ⓐ TRS·80 Ⓣ
QUALITY DISK SOFTWARE

VISA master charge

☐ HOME FINANCE PAK I: Entire Series $49.95 ⒶⓉ

☐ BUDGET: The heart of a comprehensive home finance system. Allows user to define up to 20 budget items. Actual expense input can be by keyboard or by automatic reading of CHECKBOOK II files. Costs are automatically sorted and compared with budget. BUDGET produces both monthly actual/budget/variance report and a year-to-date by month summary of actual costs. Color graphics display of expenses. . . $24.95

☐ CHECKBOOK II: This extensive program keeps complete records of each check/deposit. Unique check entry system allows user to set up common check purpose and recipient categories. Upon entry you select from this pre-defined menue to minimize keying in a lot of data. Unique names can also be stored for completeness. Rapid access to check files. Check register display scrolls for ease of review. 40 column printout. Up to 100 checks per month storage. Files accessible by BUDGET program $19.95

☐ SAVINGS: Allows user to keep track of deposits/withdrawals for up to 10 savings accounts. Complete records shown via screen or 40 column printer. $14.95

☐ CREDIT CARD: Keep control of your cards with this program. Organizes, stores and displays purchases, payments and service charges. Screen or 40 column printer display. Up to 10 separate cards $14.95

☐ UNIVERSAL COMPUTING MACHINE: $39.95 ⒶⓉ

A user programmable computing system structured around a 20 row x 20 column table. User defines row and column names and equations forming a unique computing machine. Table elements can be multiplied, divided, subtracted or added to any other element. User can define repeated functions common to a row or column greatly simplifying table setup. Hundreds of unique computing machines can be defined, used, stored and recalled, with or without old data, for later use. Excellent for sales forecasts, engineering design analysis, budgets, inventory lists, income statements, production planning, project cost estimates-in short for any planning, analysis or reporting problem that can be solved with a table. Unique curser commands allow you to move to any element, change its value and immediately see the effect on other table values. Entire table can be printed by machine pages (user-defined 3-5 columns) on a 40 column printer.

☐ COLOR CALENDAR: *$19.95* Ⓐ

HI-RES color graphics display of your personal calendar. Automatic multiple entry of repetitive events. Review at a glance important dates, appointments, anniversaries, birthdays, action dates, etc. over a 5 year period. Graphic calendar marks dates. Printer and screen display a summary report by month of your full text describing each day's action item or event. Ideal for anyone with a busy calendar.

☐ BUSINESS SOFTWARE: Entire Series $159.95 ⒶⓉ

☐ MICRDACCOUNTANT: The ideal accounting system for the small business. Based on classic T accounts and double-entry bookkeeping, this efficient program records and produces reports on account balances, general ledger journals, revenue and expenses. Screen or 40 column printer reports. Handles up to 1000 journal entries per month up to 300 accounts. Includes a short primer in Financial Accounting. . . $49.95

☐ UNIVERSAL BUSINESS MACHINE: This program is designed to SIMPLIFY and SAVE TIME for the serious businessman who must periodically Analyze, Plan and Estimate. The program was created using our Universal Computing Machine and it is programmed to provide the following planning and forecasting tools.

CASH FLOW ANALYSIS — PROFORMA BALANCE SHEET — SOURCE AND USE OF FUNDS
PROFORMA PROFIT & LOSS — SALES FORECASTER — JOB COST ESTIMATOR

Price, including a copy of the Universal Computing Machine $89.95

☐ BUSINESS CHECK REGISTER AND BUDGET: A combination of our CHECKBOOK II and BUDGET programs expanded to include up to 50 budgetable items and up to 500 checks per month. Includes bank statement reconciliation and automatic check search (48K). $49.95

☐ ELECTRONICS SERIES: Entire Series $159.95 Ⓐ

☐ LOGIC SIMULATOR: SAVE TIME AND MONEY. Simulate your digital logic circuits before you build them. CMOS, TTL, or whatever, if it's digital logic, this program can handle it. The program is an interactive, menu driven, full-fledged logic simulator capable of simulating the bit-time by bit-time response of a logic network to user-specified input patterns. It will handle up to 1000 gates, including NANDS, NORS, INverters, FLIP-FLOPS, SHIFT REGISTERS, COUNTERS and user defined MACROS. Up to 40 user-defined, random, or binary input patterns. Simulation results displayed on CRT or printer. Accepts network descriptions from keyboard or from LDGIC DESIGNER for simulation. $89.95

☐ LOGIC DESIGNER: Interactive HI-RES Graphics program for designing digital logic systems. A menu driven series of keyboard commands allows you to draw directly on the screen up to 15 different gate types, including 10 gate shape patterns supplied with the program and 5 reserved for user specification. Standard patterns supplied are NAND, NOR, INVERTER, EX-OR, T-FLOP, JK FLOP, D-FLOP, RS-FLOP, 4 Bit COUNTER and N-BIT SHIFT REGISTER. User interconnects gates just as you would normally draw using line graphics commands. Network descriptions for LDGIC SIMULATOR generated simultaneously with the CRT diagram being drawn. $89.95

☐ MATHEMATICS SERIES: Entire Series $49.95 Ⓐ

☐ STATISTICAL ANALYSIS I: This menu driven program performs SIMPLE LINEAR REGRESSION analysis, determines the mean, standard deviation and plots the frequency distribution of user-supplied data sets. Printer, Disk, I/O and edit routines included (32K min.) $19.95

☐ NUMERICAL ANALYSIS: HI-RES 2-Dimensional plot of any function. Automatic scaling. At your option, the program will plot the function, plot the INTEGRAL, plot the DERIVATIVE, determine the ROOTS, find the MAXIMA and MINIMA and list the INTEGRAL VALUE. $19.95

☐ MATRIX: A general purpose, menu driven program for determining the INVERSE and DETERMINANT of any matrix, as well as the SOLUTION to any set of SIMULTANEOUS LINEAR EQUATIONS. Disk I/O for data save. Specify 55 eqn. set (48K) or 35 eqn. (32K) $19.95

☐ 3-D SURFACE PLOTTER: Explore the ELEGANCE and BEAUTY of MATHEMATICS by creating HI-RES PLOTS of 3-dimensional surfaces from any 3-variable equation. Disk save and recall routines for plots. Menu driven to vary surface parameters. Hidden line or transparent plotting $19.95

☐ ACTION ADVENTURE GAMES: Entire Series $29.95 Ⓐ

☐ RED BARON: Can you outfly the RED BARON? This fast action game simulates a machine gun DOG FIGHT between your WORLD WAR I BI-PLANE and the baron's. You can LOOP, DIVE, BANK or CLIMB in any one of 8 directions and so can the BARON, in HI-RES graphics $14.95

☐ BATTLE OF MIDWAY: You are in command of the U.S.S. HORNETS' DIVE BOMBER squadron. Your targets are the Aircraft carriers, Akagi, Soryu and Kaga. You must fly your way through ZEROS and AA FIRE to make your DIVE BOMB run. In HI-RES graphics $14.95

☐ SUB ATTACK: It's April, 1943. The enemy convoy is headed for the CORAL SEA. Your sub, the MORAY, has just sighted the CARRIERS and BATTLESHIPS. Easy pickings. But watch out for the DESTROYERS they're fast and deadly. In HI-RES graphics $14.95

☐ FREE CATALOG - All programs are supplied on disk and run on Apple II w/Disk & Applesoft ROM Card & TRS-80 Level II and require 32K RAM unless otherwise noted. Detailed instructions included. Orders shipped within 3 days. Card users include card number. Add $1.50 postage and handling with each order. California residents add 6½% sales tax.

Make checks payable to:
SPECTRUM SOFTWARE
P.O. Box 2084 142 Carlow, Sunnyvale, CA 94087
For phone orders - 408-738-4387
DEALER INQUIRIES INVITED

CIRCLE 189 ON READER SERVICE CARD

WORD PROCESSING

Paper-Mate Command 60 for the PET is a word processor which incorporates full screen editing with graphics for all 16K and 32K PETs, all printers, and disk or tape drives using 60 commands. $29. A B Computers, 115 E. Stump Rd., Montogomeryville, PA 18936. (215) 699-5826.

CIRCLE 318 ON READER SERVICE CARD

Designed as an affordable yet powerful text editing addition to popular word processing software, **WordMaster Release 1.07** enhances existing file management facilities with searching, replacing, looping, conditional execution and matching capabilities,and provides compatibility with CRT "window" reviewing and "scratchpad" stored text editing functions. The CP/M compatible program sells for $150. MicroPro International Corporation, 1299 Fourth St., San Rafael, CA 94901. (415) 457-8990.

CIRCLE 319 ON READER SERVICE CARD

WordMagic is a word processor designed for the TRS-80 Model II. Its features include total TRS file Compatibility, cursor control, edit capability, paging, printing and automatic page number insertion. $100. CalData Systems, P.O. Box 178446, San Diego, CA 92117.

CIRCLE 320 ON READER SERVICE CARD

Electric Pencil II is now available for TRS-80 Model II users with CP/M. The Standard Print Package will run with serial or parallel interfaced printers. $275. The Diable/Qume Package will work with serial versions of these printers ($300), and the NEC Print Package will work with serial interface NECs only. $300. **Convert** is a conversion utility program which converts files created by Electric Pencil II into CP/M compatible files. $35. Michael Shrayer Software, Inc., 1198 Los Robles Dr., Palm Springs, CA 92262. (714) 323-1400.

CIRCLE 321 ON READER SERVICE CARD

EDUCATIONAL

The **Earth Science Series** for the TRS-80 includes 12 independent programs, each designed to teach a particular topic covered in junior or senior high school earth science courses. Also provided is **Lab Aid**, a program containing 20 of the most common formulas used in lab experiments. $59.95. **T.E.S.T**, also for the TRS-80, includes a Maintenance Program, which allows the user to create a test of up to 35 questions, and a Test and Drill Program, which is a utility designed to accept the test so created. $11.95. TYC Software, 40 Stuyvesant Manor, Geneseo, NY 14454.

CIRCLE 322 ON READER SERVICE CARD

CompuSoCo announces a school administration package for the Apple II and Apple II Plus. The system consists of four modules: The **Electric Gradebook**, which maintains assignment by assignment records of student progress ($49.95); the **Grade Program**, which allows the inputting of grades and test scores in order to prepare report cards ($259.95); the **Counsellor Element**, which is designed to aid in student scheduling ($89.95), and the **Schedule Component** which prepares master school class schedules and individual student schedules ($259.95). CompuSoCo, 26251 Via Roble, P.O. Box 2325, Mission Viejo, CA 92690.

CIRCLE 323 ON READER SERVICE CARD

Education Sampler for PET and TRS-80, provides test and drill practice in Algebra, Geometry and Chemistry. It includes user-selectable accuracy levels. $15. Harry H. Briley, Livermore, CA 94550.

CIRCLE 324 ON READER SERVICE CARD

CONDUIT, a non-profit organization which distributes computer-based **instructional materials**, has announced the availability of several units for Apple, TRS-80 and PET. Primarily simulations, the units address topics in biology, chemistry, physics, sociology and pyschology. Prices range from $30 to $100. CONDUIT, P.O. Box 388, Iowa City, IA 52244.

CIRCLE 325 ON READER SERVICE CARD

Apple Locker & accessories

Apple Cart
Heavy duty metal with casters. 24"w. x 23¼"d. x 37¾"h. with optional 32"w. table top ($16.00 extra).
$180.00

Apple Locker
A security locking device, with locks, connectors, cables, and full installation instructions.
$78.50

Apple Sack
Transport your APPLE, one or two disk drives, accessories, cables and diskettes all in this soft vinyl bag.
$98.00

FOR MORE INFORMATION AND ORDERS CONTACT:
DEALER INQUIRIES WELCOMED

TELE-TERMINALS

7216 BOONE AVE. NORTH
BROOKLYN PARK, MN 55428
PHONE (612) 535-5330
MN Wats 800/442-3006
NAT Wats 800/328-3072

MasterCard VISA

CIRCLE 261 ON READER SERVICE CARD

NEW TARBELL S-100 CPU/IO BOARD



- Z-80™ will run at 2 or 4 Mhz
- 2 RS-232 Serial I/O ports
- Powerful Memory Management
- Programmable Timer
- Full masked priority interrupts
- Has everything needed for MP/M™
- 6 month full warranty

Z-80 is a trademark of Zilog Inc.
MP/M is a trademark of Digital Research

Tarbell Electronics

950 Dovlen Place, Suite B
Carson, CA 90746
Phone (213) 538-4251

CIRCLE 259 ON READER SERVICE CARD

Now

tiny C Soars!

...with tiny-c two — the compiler

Tiny-c two is ten times faster than tiny-c one, with many features, including long (32 bit) integers, lots of new operators, and redirectable and direct access input/output. Viable for professional work, either systems programming or business applications.

It comes with a UNIX™ style command interpreter called the "tiny-shell"™. Every compiled tiny-c program becomes a new shell command. Commands can have arguments, and dash (-) options, just as real UNIX shell commands do. The < and > input/output redirection operators are supported.

Fifty standard library functions, and readily extended. The input/output functions are UNIX styles, including fopen, fprintf, etc. Both ascii and raw (binary) input/output are supported.

Package is portable. Bringing it up on a new processor or new operating system should take just days. And as usual with tiny-c products, all the source code is included.

Tiny-c two is available now on standard 8" CP/M.

$250.00 - Includes Owners Manual and Disk
Manual Only $50.00
(20% Discount to tiny-c one owners)

The original tiny-c ONE is still available on a wide variety of cassettes and diskettes. This version is an interpreter, complete with a Program Preparation System. Disk or cassette versions $100 (this price includes the Owners Manual, available separate-at $50). Disks: CP/M, Apple DOS 3.2, H8/89 HOS, PDP-11, Flex 2.0, Northstar, CDOS. Cassettes: KIM, SYM, TRS-80, Tarbell, Cuts.

tiny C

Call or write tiny-c associates, P.O. Box 269, Holmdel, N.J. 07733 (201) 671-2296. You'll discover tiny-c is flying higher and faster.

New Jersey residents include 5% sales tax. Visa or Master Card accepted. Include charge plate number with order.

UNIX is a trademark of Bell Laboratories, Inc.
tiny-c and tiny-shell are trademarks of tiny c assoc.

CIRCLE 264 ON READER SERVICE CARD

Compak, Inc., announces **Mathematics Package** for grades one through eight. The package, desinged for use on the 32K Apple and TI 99/4, covers addition, subtraction, multiplication, division, common fractions, decimal fractions, percents, measurements geometry and elementary algebr. Features include multiple skill levels, recordkeeping, color graphics, and sound. The complete package is $494, all concepts for a single grade level are $65, and one concept for all grade levels is $50. Compak, Inc., P.O. Box 14852, Austin, TX 78761. (512) 452-1680.

CIRCLE 326 ON READER SERVICE CARD

The **Class Scheduling System** for the Apple prepares all input forms, reports expected class conflicts and prepares final master school rosters and individual student schedules. The system, which will handle up to 2400 students at a time, requires 48K and two disk drives along with an 80-column printer. $249.95. Also available is **Light Pen Quiz** which allows teachers to create student quizzes which accept input from a light pen. The program requires Applesoft, 32K and one disk drive. $49.95. The **Counsellor's Program** allows for preparation of the school guidance counsellor's master student records and file folder records. $89.95. Charles Mann & Associates, Micro Software Division, 7594 San Remo Trail, Yucca Valley, CA 92284. (714) 365-9718.

CIRCLE 327 ON READER SERVICE CARD

Advanced Graphics Mini-Instruction Course, Volume 1, Curves is the first in a series of projects on graphics applications programming techniques for the 16K Level II or 4K Level I TRS-80. $19.95. Datagraphics. P.O. Box 566, Dept. G, Union Station. Endicott, NY 13760.

CIRCLE 328 ON READER SERVICE CARD

RECREATIONAL, GAMES

Monty Plays Monopoly and **Monty Plays Scrabble** are designed for use with game boards and equipment. The computer participates as one of the players. Monopoly is available for Apple and TRS-80 Level II on cassette for $24.95 and disk for $27.95. Scrabble is also available for CP/M systems at $29.95. Ritam Corporation, P.O. Box 921, Fairfield, IA 52556.

CIRCLE 329 ON READER SERVICE CARD

Squadron Leader games are historical simulations which place the player in command of a fighter squadron in one of six decisive campaigns of World War II. Games include, RAF: The Battle of Britain, MiGs and Messerschmidts, Jagdstaffel, Winged Samurai, Malta Strike, and Chennault's Flying Tigers, and are available for 16K TRS-80 Level II, Apple II, or PET. $19.95. Discovery Games, 936 W. Hwy. 36, St. Paul, MN 55113.

CIRCLE 330 ON READER SERVICE CARD

FS1 Flight Simulators for Apple and TRS-80 are visual flight simulators that offer a real-time 3D out-the-window view of flight. Animation and flight characteristics are said to allow the non-pilot to learn basic flight control and the experienced pilot to explore the flight characteristics of an aircraft. Available on cassette for $25, or Apple disk for $33.50. SubLogic Distribution Corp., Box V, Savoy, IL 61874. (217) 359-8482.

CIRCLE 331 ON READER SERVICE CARD

Sorcerer Asteroids is a machine language version of the arcade game. Other games available for Sorcerer include Action Bowling and Sub. Prices range from $9.95 to $19.95. Staley's Sorcerer Software, 3497 School Rd., Murryville, PA 15668.

CIRCLE 332 ON READER SERVICE CARD

NEW For The ATARI™

PRESCHOOL FUN
(16K BASIC) This readiness program has two parts with several individual modules. Part one reinforces color, shape and number recognition. Part two has units on upper and lower case letters and directions. No reading required. Full color graphics and sound. ..... cass. $15.00

MATH FACTS - LEVEL 1
(16K BASIC) First in a series of self-paced instructional programs for elementary school children. The program automatically advances to the next unit when the child has mastered 80% of the work generated by the computer. The previous unit will be reviewed if the child cannot master 50% of the work in a particular unit. Concepts covered are: numbers, number placement and number words (1-20), addition and subtraction (visual and abstract). (Grades K-2) ..... cass. $15.00

CRIBBAGE
(24K BASIC) Play cribbage with the computer at two different levels. As a beginner, the computer will point out your errs without penalizing you. But watch out! At the intermediate level, the computer will peg your points if you don't ..... cass. $15.00

CASINO I
(16K BASIC) Try your luck at the Lucky Lady . . . Play BLACKJACK . . . The computer will be the dealer for you and your friends (1-4 players). You can split and double your hand as you attempt to break the house. OR hit it big on the SLOT MACHINE. Two programs on one tape..... cass. $15.00

*ATARI is a trademark of Atari, Inc.

T.H.E.S.I.S.
P.O. Box 147
Garden City, MI 48135
or call (313)595-4722 for C.O.D.

Please add $1.50 for shipping
Mich. residents add 4% tax
WRITE for FREE FLYER
DEALER INQUIRIES WELCOME

CIRCLE 241 ON READER SERVICE CARD

SPECTACULAR Offers

BASF "FLEXYDISK" Superior quality data storage medium, certified and guaranteed 100% error free.
5¼" or 8"* Diskettes 10/ $24
5¼" or 8" Vinyl Storage Pages 10/ $5
Write for quantity discounts
*Single sided / Single Density

SFD CASSETTES "Super Ferro Dynamic" Using the finest Agfa PE 611 tape in a professional quality housing.
C-10 Cassette Sonic Weld Housing 10/ $7
Add 10¢ p/cassette for 5 screw housing
Cassette Album Page $1.89
Write for quantity discounts

LIBRARY CASE 3-ring binder album, Protects your valuable programs on disks or cassettes. Fully enclosed and protected on all sides similar to Kas-sette storage box.
Library 3-ring binder $6.50
5¼"mini Kas-sette 10/$2.49
8" Kas-sette 10/$2.99
Write for quantity discounts

DISKETTE DRIVE head cleaning kits prevent head crashes and insure efficient error-free operation.
5¼" or 8" KIT
INTRODUCTORY PRICE $19.50

HARDHOLE reinforcing ring of tough mylar protects your disks from damage.
8" applicator $4.00
5¼" applicator $3.00
8" mylar hardholes (50) . $8.00
5¼" mylar hardholes (50) $6.00

ABM PRODUCTS
631 "B" St.
San Diego, CA 92101
(714) 235-6602

VISA • MASTERCHARGE • MONEY ORDERS CERTIFIED CHECK • FOR PERSONAL CHECKS ALLOW 2 WEEKS • C.O.D. REQUIRES A 10% DEPOSIT • CAL RES ADD 6% SALES TAX MIN. $2 SHIPPING & HANDLING • MINIMUM ORDER $10 • SATISFACTION GUARANTEED OR FULL REFUND.

CIRCLE 104 ON READER SERVICE CARD

Tarbell Double Density Floppy Disk Interface

FOR 8" DISK DRIVES

Under Tarbell Double-Density CP/M, single and double density disks may be intermixed. The system automatically determines whether single or double density is in place.

- Software select single or double density.
- Phase-locked-loop and write precompensation for reliable data recovery and storage.
- On-board phantom bootstrap PROM is disabled after bootstrap operation so all 64K memory address space is available to user.
- DMA in single or double density permits multi-user operation.
- Extended addressing provides 8 extra address bits, permitting direct transfer anywhere in a 16 megabyte address range.
- Select up to 4 drives, single or double sided.
- New BIOS for CP/M included on single-density diskette.

CP/M is a reg. trademark of Digital Research.



Tarbell Electronics
950 Dovlen Place, Suite B, Carson, Ca. 90746
(213) 538-4251 (213) 538-2254

CIRCLE 202 ON READER SERVICE CARD

TURTLES



TEACH

Fantastically fun, the Terrapin™ Turtle rolls, blinks, beeps, draws, and feels. Learn, teach and demonstrate geometry, assembly and high level programming, life sciences, Artificial Intelligence.

Interface this small home robot to TRS-80, APPLE, DEC—any digital computer (not included).

Send for brochure and prices.

Terrapin, Inc.

Terrapin, Inc.
678 Massachusetts Avenue # 205
Cambridge, Mass. 02139
617-492-8816

CIRCLE 205 ON READER SERVICE CARD

Computer Napoleonics: The battle of Waterloo is a division scale game that recreates Napoleon's last battle against the Duke of Wellington. $59.95. **Computer Quarterback** is a real-time strategy football game. $39.95. Both games are available on disk for the Apple with 48K memory and Applesoft, and allow the user to play against the computer or a human opponent. Strategic Simulations, Inc., 450 San Antonio Rd., Suite 62, Palo Alto, CA 94306.

CIRCLE 334 ON READER SERVICE CARD

Sunmax for 16K TRS-80 Level II computers gives each of from one to nine players a solar energy job such as home heating, hot water heating or home air conditioning in one of 200 cities around the world. The player must guess the tilt of the solar collector which will maximize the amount of solar energy collected. $8. Solartek, P.O. Box 298, Guilderland, NY 12084.

CIRCLE 335 ON READER SERVICE CARD

Pigskin, a football strategy game for the TRS-80 Level II, features a graphic display of the field and shows ball movement and statistics. Cassette, $9.95; disk, $15.95. Acorn Software, Inc., 634 North Carolina Ave., S.E., Washington, D.C. 20003. (202) 544-4259.

CIRCLE 336 ON READER SERVICE CARD

Small Business Systems Group announces a **games package** for the TRS-80 Model II. The Mean Checkers Machine is executed from DOS, while the other six—Star Trek, Dog Star Adventure, Treasure Hunt, Concentration and Banko—are written in Basic. $75. Small Business Systems Group, Inc., 6 Carlisle Rd., Westford, MA 01886. (617) 692-3800.

CIRCLE 337 ON READER SERVICE CARD

Morton's Fork, the third in the Maces & Magic series of adventure programs for TRS-80, CP/M and Micropolis disk systems, features a multi-level role playing, simulation set in an ancient wizard's fortress. $35. Chameleon Software, Inc., 4733 North Mitchner, Indianapolis, IN 46226. (317) 545-5098.

CIRCLE 338 ON READER SERVICE CARD

BOOKS AND BOOKLETS

SOFTWARE VENDOR DIRECTORY

The **Software Vendor Directory**, a listing of microcomputer software vendors, is now available from Micro-Serve, Inc.

The publication lists over 700 vendors within 35 categories of hardware and operating systems. Software is classified into: personal, programming, general business, and industry. Vendors of books and other publications have also been included. $37.95.

Micro-Serve, Inc., P.O. Box 482, Nyack, NY 10960.

CIRCLE 339 ON READER SERVICE CARD

HANDBOOK ON FUNDING FOR EDUCATORS

A handbook developed to assist educational institutions in identifying sources of financial support--enabling acquisition and use of microcomputer technology for instruction--has been published by Bell & Howell's Audio-Visual Products Division.

Titled "Funding Report for Microcomputers," the 44-page publication is the result of contact with officials of eight federal agencies and the departments of education.

Bell & Howell Audio-Visual Products Division, 7100 N. McCormick Rd., Chlicago, IL 60645.

CIRCLE 340 ON READER SERVICE CARD

COMPUTER-ORIENTED BIBLIOGRAPHY

More than 250 new computer books were published last year. All are listed in the 13th Edition of the **Annual Bibliography of Computer-Oriented Books**, released by the University of Colorado.

There was a decline in the number of new books in the application areas (only 20), and an increase in books on microcomputers and personal computing (14).

The bibliography contains more than 1,000 books from over 150 publishers. It

At last! You can VIDEOTAPE apple color graphics



THE *ADWAR* APPLE PROC. MOD.

Modifies nonstandard Apple color sync signals to fall within NTSC videotape recorder tolerances. Record, edit, duplicate without loss of color.

COLOR DOES NOT RECORD

STABLE NTSC COLOR IMAGE

Add colorful graphics and illustrated titles to your videotapes. Easy to install in slot #7 of Apple computer.

ADWAR APPLE PROC MOD ..... $250.

ADWAR VIDEO CORP 100 Fifth Ave., New York 10011
(212) 691-0976 • Telex 420801

CIRCLE 210 ON READER SERVICE CARD

Give an ear to your computer this Christmas!

COGNIVOX lets your computer respond to your spoken commands.

PET, TRS-80 LII AIM-65 and SORCERER

NEW COGNIVOX SR-100 has 32 word (or short phrase) vocabulary (AIM-65 with 4K RAM, 16 words). Up to 98% recognition rate. Breakthrough price of only **$119** includes microphone, cassette with software and manual. Version for the TRS-80 (VIO-332) costs $149 but also has 32 word speech output and music capability, includes all above plus speaker/amplifier. For the Sorcerer, in addition to SR-100, we offer COGNIVOX VIO-132 which includes speech output and music and extensive software and costs $179. Please add $3 for shipping in the US, Calif. add 6% tax. Foreign orders welcome, add 10% for processing and shipping by air. When ordering, please specify make, model and memory size of your computer.

VOICETEK

Dept. C, P.O. Box 388, Goleta, Ca 93017

CIRCLE 267 ON READER SERVICE CARD

---

tiny C

Tiny-C Two — The Compiler

tiny-c two® is ten times faster than **tiny-c one®** . It has many extra features, including long (32) bit integers, lots of new operators, and redirectable and direct access input/output. This version of tiny-c is viable for professional work, either systems programming or business applications. It comes with a UNIX® style command interpreter called the "tiny-shell"® . With the tiny-shell, every compiled tiny-c program becomes a new shell command. Tiny-shell commands can have arguments, and dash(-) options, just as real UNIX shell commands do. The < and > input/output redirection operators are supported. There are over fifty standard library functions, and this set is readily extended. The input/output functions are UNIX style, including fopen, fprintf, etc. Both ascii and raw (binary) input/output are supported. And the entire package is portable. Bringing it up on a new processor or new operating system should take a few days or a few weeks at the most. And as usual with tiny-c products, all the source code is included.

tiny-c two.....**$250** Manual Only . . $50
tiny-c one .....**$100** Manual Only . . $50

Visa/Mastercharge Welcome

Formats: Std. 8", 5" NorthStar DD, TRS-80 MOD II® & H89/Z89.
To order call: **(206)542-8370**
or write: **VANDATA**
17541 Stone Avenue North
Seattle, WA 98133

TRS-80 is a registered trademark of Radio Shack, Inc. UNIX is a registered trademark or Bell Laboratories, Inc. tiny-c and tiny-shell are trademarks of tiny-c associates.

CIRCLE 266 ON READER SERVICE CARD

---

this publication is available in microform



Please send me additional information.

University Microfilms International

300 North Zeeb Road
Dept. P.R.
Ann Arbor, MI 48106
U.S.A.

18 Bedford Row
Dept. P.R.
London, WC1R 4EJ
England

Name_____
Institution _____
Street_____
City_____
State_____ Zip _____

CIRCLE 265 ON READER SERVICE CARD

separates the books into 55 categories and catalogs them according to type and style of presentation. $4.

Computing Newsletter, Box 7345, Colorado Springs, CO 80933.

CIRCLE 341 ON READER SERVICE CARD

MAGAZINES, NEWSLETTERS

REVIEWS OF APPLE SOFTWARE

Peelings is a publication devoted exclusively to reviews of software for the Apple II and Apple II Plus microcomputers.

Each bi-monthly issue will contain in-depth reviews of twelve to fifteen programs or software packages. Subscriptions are $15.

Peelings, c/o Ed Burlbaw, 945 Brook Cir., Las Cruces, NM 88001. (505) 523-5088.

CIRCLE 342 ON READER SERVICE CARD

PASCAL NEWSLETTER

Rational Data Systems announces a free **Pascal Newsletter.**

It includes articles dealing with subjects of general interest such as Pascal standards and programming techniques. Recent newsletter articles have included a history of Pascal compilers, a Pascal bibliography, a comparison of RDS Pascal to competitive products and the "Programmer's Page" which deals with matters of programming style.

Rational Data Systems, 245 West 55th St., New York, NY 10019. (212) 757-0011.

CIRCLE 343 ON READER SERVICE CARD

MISCELLANEOUS

LAZY SUSAN FOR CRT

A swivel device that applies the "lazy susan" principle to the CRT terminal, increasing operator efficiency and potentially saving the cost of extra terminals, is available from Inmac.

The Turn 'n Key swivel device allows full 180° rotation of a CRT terminal, enabling two or more operators to use the same terminal.

Turn 'n Key comes in two sizes, each able to hold up to 200 pounds. The 16"-square size is priced at $55, and the 20"-square size at $62.

Inmac, 2465 Augustine Dr., Santa Clara, CA 95051.

CIRCLE 344 ON READER SERVICE CARD

PASCAL REFERENCE CARD AND AUTO DIALER

The Pascal Reference Card is a compressed assemblage of almost everything needed to program in Pascal. On one folded 8½ x 11" card, all the following data are available: ASCII chart, Procedure and Function definitions, Reserved and Predefined words, I/O Error return, Setup Parameters, P-code chart, and Operators with Precedence, $2.

The Autodialer II allows Apple II users to dial ABBS, CBBS, and Forum 80. It features a multi-page menu and single key select. Autodialer II requires Applesoft II and Micromodem, $15.

Modular Software, POB 12883, San Antonio, TX 78212.

CIRCLE 345 ON READER SERVICE CARD



CALIFORNIA

Rainbow Computing, Inc.—9719 Reseda Blvd., Northridge 91324; (213) 349-5560. 10-7 Tues-Fri, 10-5 Sat, 12-5 Sun. Apple, DEC, and Atari. Authorized Sales and Service.

D.E.S. Data Equipment Supply—8315 Firestone, Downey 90241. (213) 923-9361. 7 days. Commodore PET specialists. Hardware Software, Books, Mags, Supplies, In House Maintenance.

Advance Data Concepts—2280 Diamond Blvd., Concord, 94520; (415) 671-9016. 9-5 Mon-Fri. Vector-Graphic, CP/M Software Headquarters-User's Group.

CONNECTICUT

Computerworks—1439 Post Rd., East Westport 06880; (203) 255-9096. 12-6 Tues-Fri, 12-9 Thu, 10-5 Sat.

FLORIDA

AMF Electronics—11158 N. 30th St, Tampa 33612; (813) 971-4072. 10-6 Mon-Sat. Apple Computer Sales & Service; TRS-80, Apple Software & Peripherals; S-100 boards, computer parts & books.

GEORGIA

Atlanta Computer Mart—5091 Buford Hwy, Atlanta 30340; (404) 455-0647. 10-6 Mon-Sat.

ILLINOIS

Computer Junction—543 S. York Rd., Elmhurst 60126; (312) 530-1125. Mon & Thu 9:30-8:30 pm; Tues-Sat 9:30-5:30; Sun 12-4:30.

The Computer Room—106 E. Oak St, Chicago 60611; (312) 337-6744. 11-7 Mon-Fri, 11-6 Sat.

Data Domain of Schaumburg—1612 E. Algonquin Rd, Schaumburg 60195; (312) 397-8700. 12-9 Tue-Fri, 11-5 Sat. Largest book & magazine selection.

Lillipute Computer Mart, Inc.—4446 Oakton, Skokie 60076; (312) 674-1383. M-F 10:30-8 pm, Sat 10-6. We sell Cromemco, Gimix, Bell & Howell, NorthStar and others. Starting our fifth year in business.

KENTUCKY

ComputerLand of Louisville—10414 Shelbyville Rd, Louisville 40223; (502) 245-8288. 10-5:30.

MASSACHUSETTS

Computer Mart, Inc.—1395 Main St, Waltham 02154; (617) 899-4540. 11-6 Tue-Sat. Atari, Heath, NEC, SWTP & S-100 bus systems; Word Processing Specialists.

Neeco—679 Highland Ave, Needham 02194; (617) 449-1760. 9-5:30 Mon-Fri. Commodore, Apple, Superbrain, TI 99/4.

NEW JERSEY

Computernook—Rt. 46, Pine Brook Plaza, Pine Brook 07058; (201) 575-9468. 10-6:30 MTWS, 10-8 Thurs., Fri. Apple/Commodore Authorized dealer.

Stonehenge Computer Shop—89 Summit Avenue, Summit 07901; (201) 277-1020. 10 am - 6:30 pm Mon-Sat. Apple/Bell & Howell/Commodore Authorized Dealer, Sales and Service.

NEW YORK

The Computer Corner Inc—200 Hamilton Ave, White Plains 10601; (914)-WHY DATA. 10-6 Mon-Sat, 10-9 Thu.

OHIO

The Basic Computer Shop—2671 W. Market St, Akron 44313; (216) 867-0808. 10-6 Mon-Sat.

Micro Mini Computer World—74 Robinwood Ave., Columbus 43213; (614) 235-5813/6058. 11-7 Tues-Sat. Authorized Apple/Commodore dealer. Sales, Service, Business Software.

PENNSYLVANIA

Personal Computer Corp.—24-26 W. Lancaster Ave, Paoli 19301; (215)647-8463. 10-6 Mon-Fri, 10-8 Wed, 10-5 Sat.

VIRGINIA

ComputerLand/Tysons Corner — 8411 Old Corthouse Rd, Vienna 22180; (703) 893-0424. 10-6 MTWF, 10-9 Thu, 10-5 Sat.

Computer Plus, Inc—6120 Franconia Rd, Alexandria 22301; (703) 971-1996. 10-9 Mon-Fri, 10-6 Sat. Micro specialists, books, classes, software, maintenance. "The PLUS makes the difference."

OUTPUT

Claire Stuart

Gamma Six
Altron Calculator Co. Third Annual Research and Marketing Workshop

Zatok beamed at his staff. "The new model student's calculator is just what we need to push us ahead of the competition. I'm putting the specifications into the computer bank now, and they'll be at the disposal of everyone in sales and marketing. You may begin work on the advertising campaigns immediately."

His digits raced over the keys. INSERT ORDER, DATA BANK, DISC 100110, STORAGE TYPE-BSU LOCATION 111101, CALL CODE 001101/ABX.

West Hill Community Hospital

Brian Manning fumbled open his third pack of cigarettes just as the nurse bounced into the room. "It's a fine baby girl, Mr. Manning!"

In the delivery room, Laura Manning smiled weakly as the doctor held up her newborn daughter. "Christine," she whispered. "We're calling her Christine."

April 2
Breckenridge State College

Chris Manning nibbled thoughtfully on the end of her pencil as Dr. Bailey covered the blackboard with angular scrawls.

"As you see, the computer's hardware is under the control of the software— that's the program. The program tells it what to do, and that is what the computer does. No more and no less. That's why it is so essential that a good program be complete and unambiguous."

Chris broke in. "But the computer can make decisions, can't it?"

"Of course, but only based on the information it has been given. For example, if you give the computer a series of numbers in pairs and ask it to indicate the larger number in each pair, you must first define 'larger' or the computer cannot execute the instructions."

"Do you think that someday we'll be able to build a computer that really thinks? I mean, with consciousness?"

Dr. Bailey sighed and rolled his eyes. "Ms. Manning, we build a computer to perform certain operations and we define the problem we wish solved. We give it input. It generates output based on that input. It is simply a machine. Now even you wouldn't ask if we expect a programmable microwave oven to develop consciousness, would you, Ms. Manning?"

Chris reddened and slid down in her seat, wishing she could make herself invisible. She stared at the clock, and as soon as the minute hand reached the hour, she grabbed her books and bolted for the door.

Chris started for her next class at a brisk walk. As she passed the campus computer center, she impulsively stopped in the doorway. Students were busy at all the keypunch machines and the air seemed to vibrate with the hums of the instruments and the whirrs and slaps of the card sorters. Chris watched and listened a few moments, glanced at the clock and realized she was late for psych class, then hurried on her way.She slipped quitely *through* the rear door of the classroom and into a seat beside her boyfriend, Alex.

Dr. Bronstein was clearing his throat and tapping his pointer on a large plastic model of a human brain. "With all we know about the brain, there is much more

Claire Stuart, 937-B West Main, Bridgeport, W VA 26330.

AIR TRAFFIC CONTROLLER

In **Air Traffic Controller** you assume responsibility for the safe flow of air traffic within a 15x25 mile area up to 5,000 feet in altitude. During your shift as a controller in charge of this airspace, 26 aircraft become active and under your control. Jets and prop planes have to be guided to and from the two airports, navigational beacons and ten entry/exit fixes. The aircraft enter the controller's airspace at various altitudes and headings whether or not you are ready.

Air Traffic Controller retains the basic realism of air traffic control. This program requires the same steady nerves under pressure and the same instant, almost instinctive, analyses of complex emergencies which are demanded of a professional air traffic controller. But "ATC" adds the excitement and well-defined goals of a game. This is just a simulation, and all passengers left in air traffic limbo by a panicked player will live to fly another day.

Your goal is to get all of the aircraft to their assigned destination before the shift is completed. At your disposal are a radar display of the aircraft positions in the control area; coded information concerning aircraft heading, destination and fuel supply; navaids enabling you to hold aircraft or assign them automatic approaches; and commands to alter the altitude and heading of the aircraft. Working against you are altitude and heading requirements, fuel restrictions and, of course, the inimitable clock.

The most obvious measure of difficulty of a game is the clock setting at the beginning. In a 99 minute game you will have time to go fix a sandwich between the appearance of two successive aircraft, while in the 16 minute game you may not have time to swallow before all of the aircraft have appeared.

No two games, even at the same clock setting, are ever alike. As controller, you must cope with the unique requirements of each aircraft. The game will end if you commit a "boundry error," that is, if an aircraft fails to leave your area at the proper altitude and exit fix...causing an unpleasant surprise for the controller next door. The game also ends if you fail to leave a comfortable margin of safety between the aircraft as they whiz past each other. In cases of excessive delay, fuel supply considerations will become invested with a particular sense of urgency.

Successful guidance of all aircraft to their destination is a heady accomplishment. This never fails to thrill ATC enthusiasts at each successive level of play.

Your local retail store should carry Creative Computing Software. If your favorite retailer does not carry the software you need, have him call in your order to (800) 631-8112. Or you can order directly from Creative Computing. Write to Creative Computing Software, P.O. Box 789-M, Morristown, NJ 07960. **Air Traffic Controller** is now available for the 16K TRS-80 (3006), for the 16K Apple II and Apple II Plus (4008), the 8K Sorcerer (5008) and for the 4K Sol-20 (8001). All are on cassette for $9.95. Include $1.00 for postage and handling. For faster service, call in your bank card order toll free on our order hotline, (800) 631-8112.

Prices are subject to change without notice.



creative computing software

sensational software

CIRCLE 300 ON READER SERVICE CARD

we DON'T know. For example, no one really understands the phenomena we call consciousness. Last time we met, a student asked,'Where is my consciousness when I am asleep?' "

The class snickered, but Bronstein scowled and went on. "You laugh! But think about it! It is a valid question. So! Where are you when you are asleep? We do not know! We have found no 'place' where consciousness can 'go.' It IS and then it IS NOT. Perhaps we may consider consciousness as only occurring when certain electro-chemical processes are going on. When they are not occurring, there is no consciousness. But the POTENTIAL for consciousness still exists at the sites of the reactions."

"Dr. Bronstein," interrupted Chris, "do you mean that when these reactions aren't going on, I don't exist, and that I'm 'reborn' so to speak, every time they begin again?"

"You could put it that way. But let's not lose sight of the fact that we're only guessing about things we do not yet understand. To continue, let's consider the brain as an electrical billboard like those used at ball games. The board is covered with light bulbs which have the potential for spelling out messages. When certain circuits are engaged, certain bulbs light up and a message appears. When the bulb goes out, is the message gone?Yes and no. It is no longer visible, but it is still POTENTIALLY there and can reappear when certain bulbs go on again. Perhaps consciousness is similarly generated."

Chris frowned. "Since the message is maybe what you'd call a by-product of certain circuits hooking up, maybe our consciousness is only a by-product of something else our brains are doing."

"Ms. Manning, I think we're digressing into things more appropiately discussed in a philosophy class, don't you? Let's move onto something we can examine in the lab. Now if I may have everyone's close attention, you'll notice that this cage contains a rat with an electrode implanted in it's brain . . ."

Alex grinned at Chris and whispered, "You're really into some heavy thoughts."

"Well, don't you ever wonder about things like that? Like what we are and what life is for?"

"What I wonder about is if I'll call you someday and your roommate will tell me you went to Tibet to contemplate your navel or something!"

Gamma Six
Altron Calculator Co. Computer Seminar for New Employees

Zatok rapped on the table with his brensch. "Today we'll see the operation of our data storage and retrieval systems, tremendously efficient systems, by the way. The basic storage storage unit is the Biological Storage Unit, or the BSU. BSU's vary tremendously in size and complexity, but regardless of size, all are self replicating. The self-replicating system is the greatest work-saver in modern history! And it was developed right here, at Altron! Each unit is initially programmed to replicate the data it carries as many times as the information will be required, and to replicate the data WHEN it is required. A very simple BSU carries data that will only be needed a few times. A large BSU may carry billions of data replications if many departments will need the information simultaneously. In that way, there is no time delay while one department waits for information being used by another. And there is no wasted material. Old BSU's may be destroyed, although most are programmed to self-distruct at a given time. In any event, the components of the BSU's are always recycled in the building of new units.

April 3
Breckenridge State College

Dr. Alonzo switched off the projector. "You've seen the double-helical structure of DNA, and we've discussed how the 'unzipping' of the helix allows replication, as well as how messenger and transfer RNA work in building proteins. Remember, the group of three nucleotides constitutes a 'codon,' the basic unit of information in the genetic code. GUU is the codon for the amino acid valine, CCA for proline, and so on, with these amino acids being joined to make a protein. UAA, UAG and UGA are codons which mean 'stop' and which lead to the termination of the protein chain."

Chris poked Alex. "It's just like a computer, isn't it!"

Dr. Alonzo raised her eyebrow, then continued. "In the nucleus of each cell is a complete 'blueprint' for building a new individual, whether a human being or a one-celled organism. Included are timed instructions for starting and stopping the manufacture of tissue and organ systems. It may say, 'Differentiate into lung tissue' at a given time, then 'Stop building lung tissue.' " Chris' hand shot up. "What about consciousness? Is there a message in the genes that tells when consciousness begins?"

"If someone could answer that question, it would certainly help in dealing with the abortion issue, wouldn't it," replied Dr. Alonzo dryly.

April 3
Alex Brandon's apartment

Chris wriggled out of Alex's arms and propped herself up on one elbow. Then she flickered.

Gamma Six
Altron Calculator Co. Computer Seminar for New Employees

Zatok assembled the group around the console. "Nemk has punched the code for retrieval of a BSU. You can see the retrieval order in the screen. The data bank has been searching for Disc100110, BSU 001101/ABX from location 111101. AH, it has arrived. Now we shall read it."

The reader whirled faster than eyes could follow, and data flashed on the screen. ". . . .GUUAUCUUC-ACAAU. . . . . UAG."

"Now we feed this output into our translator (developed here at Altron, by the way). Fine! As you can see, this BSU contains specifications for a student's calculator. Incidentally, this calculator design really needs to be revamped."

April 3
Alex Brandon's apartment

Alex's face was white. "My God, Chris, I must be going nuts! I could have sworn you disappeared for a second and then reappeared!"

"Disappeared! What were you *smoking* before I got here?" Chris started to laugh, then fell silent when she saw the expression on Alex's face. "Hey! You're serious, aren't you? Do you feel okay? Do you want to go over to the Student Health Center?"

"Chris, really, it looked like you sort of FLICKERED!Oh, never mind, forget it! My eyes must be playing tricks on me. Too much reading or something."

Gamma Six
Altron Calculator Co. Fourth Annual Research and Marketing Workshop

Zatok pointed to the calculator displayed on the screen. "You are all aware of the fact that this calculator is out-dated, and the competition is moving ahead. Now with just a few modifications, we can get back in the lead. With a minimum of work, we can combine our current student's calculator with some of Model J-5's circuitry. The result will be a teriffic new machine with the same compact size and some great new selling features. It will appeal not only to students but to technicians, merchants, just about everyone. Bolf is feeding in the specifications of both existing calculators, and the computer will put them together and give us a mockup of the proposed new unit."

Bolf gathered the printouts that spewed from the computer. "Here we are! Designs for our new calculator!"

June 10
Alex Brandon's apartment

Chris stared moodily out the window, ignoring the nervous drumming of Alex's fingers on the table. Finally Alex hit the table with his fist.

"I can't stand any more of this! Chris, what's eating you? You've been acting weird for weeks."

"I guess there's no easy way to say it. I'm pregnant." □



SYN SYN SYN DLE SOH COMMUNICATA FROM ALAZAR DLE STX

Pick carefully amid the noise and breaks, and recover what bits there may be in signal. As far as possible without chaos be on compatible protocols with all systems. Send your bits RS-449, but receive RS-232, and even from ASR-33s; they too have their input. Avoid local sales representatives; they are vexations to the spirit.

If you interface with others, you may become constrained, for there will always be higher and lower protocol layers than yours. Link your transmissions as well as your queues. Keep interested in your hardware, however humble; it is a real constraint in the changing fortunes of time.

Exercise encryption in your transmissions, for the world is full of trickery. But let this not blind you to what cleartext there is; many systems fail to encrypt, and everywhere life is full of opportunity.

Be yourself. Especially, do not feign compatibility. Neither be cynical about FORTRAN, for in the face of all aridity and disenchantment, it is perennial as grass. Fail softly over the years, gracefully surrendering the throughput of peaks.

Nurture duplicates to shield you in sudden misfortune, but do not overload yourself with redundancy. Many errors are born of congestion and complexity. Beyond a wholesome backup, be space-efficient.

You are a child of the Univac I, no less than the 1100; you have access rights to be here. And, whether or not it is clear to you, no doubt the Univac I is computing as it should. Therefore be at peace with Ma Bell, whatever you conceive Her to be, and whatever your executive and applications, in the noisy confusion of lines keep pace with your clock. With all its bugs, kludgery, and broken tapes, it is still a beautiful operating environment. Don't forget to double a DLE DLE. Strive to be happy.

DLE ETX SYN SYN

Alazar, 1980

Creative Computing-- Albert Einstein in black on a red denim-look shirt with red neckband and cuffs.

Creative's own outrageous **Bionic Toad** in dark blue on a light blue shirt for kids and adults.

Plotter display of **Pi to 1362 Places** in dark brown on a tan shirt.

I'd rather be playing spacewar-- black with white spaceships and lettering.

Give your tie a rest!

All T-shirts are available in adult sizes S,M,L,XL. Bionic Toad, Program Bug and Spacewar also available in children's sizes S (6-8), *M (10-12) and* L (14-16). Made in USA. $6.00 each postpaid.

Specify design and size and send $6.00 for each shirt to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. Orders for two or more shirts may be charged to Visa, MasterCard or American Express. Save time and call toll-free **800-631-8112** (in NJ 201-540-0445).

Computer Bum-- black design by car toonist Monte Wolverton on gray denim-look skirt with black neckband and cuffs.

The **Program Bug** that terrorized Cybernia in Katie and the Computer is back on this beige t-shirt with purple design. You can share the little monster with your favorite kid.

Roll down the block with this little black **Robot Rabbit** (on a bright orange t-shirt) on your back and you can intimidate every carrot, radish or cuke in your way.

puzzles & problems

1. T, N, E, S, S, . . .
2. S, F, T, W, T, . . .
3. D, N, O, S, A, . . .



The School Days Puzzle

One of Merlin's old teachers, Ms. Priscilla Sunshine, kicks this puzzle session off by presenting a triple problem sent into us by one of our readers, Mr. Matthew P. Fisher of Apalchin, New York.

"Students, you have just ten minutes to complete this pass-fail test. You are to extend each series of letters to a point that indicates that you understand the progression that each is based on. Merlin, stop reading that computer magazine and pay attention. The first one finished gets to clean the erasers!"

And, for sending us this problem, Mr. Fisher gets a copy of "Merlin's Puzzler I."

The Rich Broth Puzzle

Now, in the figure at the left we have an interesting puzzle. The soup tureen pictured here is not valued at $700, but rather it contains $700. The money is all in silver and it is divided into quarters, half-dollars, and dollars, there being an equal number of each. How many of each are there? (This puzzle is from "Merlin's Puzzler 2").

A Repellent Problem

Four bugs were positioned on top of a table as shown in the picture. Each bug was exactly ten inches away from the bug that it was facing. If each bug starts crawling simultaneously, and at a constant speed, towards the bug that it is facing, that is, *A* towards *B*, *B* towards *C*, *C* towards *D*, and *D* towards *A*), what distance will each bug have traveled when they all meet?





The Fore And Aft Puzzle

Above is a puzzle board for an old problem by America's greatest puzzle inventor, Sam Loyd, called "The Fore And Aft Puzzle." The playing board is made up of seventeen squares on which are placed eight white counters and eight black counters. (The illustration shows how the counters are positioned at the beginning of play.) This is a transpositional type of puzzle where you must make the white and black counters change positions in the fewest possible moves. A counter can be moved from one square to an adjacent vacant square. It may also jump over an adjacent counter of either color to an empty square beyond. All moves must be either horizontal or vertical, no diagonal moves please! (This puzzle is from "Merlin's Puzzler 3").

The Bell and the Durango Kid

Reverend I.N. Spire has purchased a new bell for his church, and somehow, he was able to talk the Durango Kid into helping him hang it. The interesting thing is that the bell and the Kid weigh exactly the same. When the Kid started hauling on the rope a surprising thing happened. See if you can guess.

(1) Did the bell go up while the Kid stayed down?
(2) Did the Kid go up while the bell stayed down?
(3) Did the Kid and the bell go up together?
(This puzzle is from "Merlin's Puzzler 3").

Answers on page 224



If you would like a free copy of one of Merlin's puzzle books, send along your favorite puzzle, and, if Merlin uses it, he will send you one of his books.

See you all again next month.

Your editor,

Charles Barry Townsend

Edmond H. Weiss, Ph.D.

Too Many Words



Edmond H. Weiss teaches effective writing seminars for business, industry, and government. To contact him, call 609-795-5580.

Most first drafts are too long. The sections are too long; the paragraphs are too long; the sentences are too long. Many people mistakenly believe that this excess length comes from trying to say too much, trying to give too much information or too many details. Actually, most of the reports and memos I read do *not* have too much information; what they have is *too many words.*

First drafts are almost always wordy and long-winded — and for a good reason. By using several words where one will do, writers have more time to think. Writing *should it prove to be the case that* in place of *if* gives your mind an eight-word stretch in which to plan the important parts of the sentence.

Wordiness, then, is a natural condition of first drafts. And the only way to cure your writing of the condition is to edit and revise your first drafts until they are free of wind and fog.

DO NOT TRY TO WRITE A CONCISE FIRST DRAFT. It takes less time to write a clumsy first draft and polish it later than to try to write a first draft that is stylistically correct. Rather, to save time and do a better job, inspect your first drafts for the following bugs.

Phobias

Many writers seem neurotically frightened of small function words like *about, then, if, with,* and others. (I suppose the neurosis has something to do with being told to write "five hundred word themes" in college; empty-headed sentences could get you a C if they were wordy enough.)

For example —

Instead of *about,* people will write:
- with regards to
- on the subject of
- relating to the matter of
- relative to

Instead of *then,* people will write:
- at that time
- at that point in time
- during that earlier period of time
- in that prior time frame

Instead of *if,* people will write:
- in the event that
- should it turn out that
- with regard to the possibility that
- should it prove to be the case that

Instead of *with,* people will write:
- by means of
- by utilizing
- through the employment of
- with the utilization of

Redundancy

Look out for phrases that say the same thing twice. You do not need to write *man-day of effort;* a man-day is a unit of effort. (*Man-day of effort* is as bad as *gram of mass* or *a square foot of area.*) Do not write *consensus of opinion;* that's the only kind of consensus there is. Here are a few others to avoid:

REDUNDANT	BETTER
period of time	period
interval of time	interval
present status	status
past history	history
concatenated together	concatenated

Excess Qualification

Do not modify or qualify terms that do not need to be modified or qualified. *Entirely complete* usually means the same thing as *complete.*

TOO MUCH	BETTER
complete stop	stop
totally dedicated	dedicated
active consideration	consideration
utterly unique	unique
perfectly compatible	compatible

These extra modifiers do not really add any emphasis or impact. *We reject the proposal* is stronger than *We completely reject the proposal;* and calling something *clear* is much more emphatic than calling it *perfectly clear.*

Phrases

Phrases, then, can be turned into single words. *As of this time* can become *now; extremely radical* can become *radical.* There are many other ways to trim phrases into single words — or even into tiny suffixes. Consider these pairs of sentences:

Before: *It is obvious* that they were looking for a manager *with more experience.*
After: *Obviously,* they were looking for a *more experienced* manager.

Before: *As is becoming apparent,* they will not accept the test report until it is *without a flaw.*
After: *Apparently,* they will not accept the test report until it is *flawless.*

Among the phrases that are best turned into single words are the "smothered verbs" (see my column in the August issue). Most first drafts are filled with opportunities to convert *conduct a meeting* to *meet;* or *achieve a resolution* to *resolve;* or *undertake an investigation* to *investigate.*

Edmond H. Weiss, Ph.D., 1612 Crown Point Lane, Cherry Hill, NJ 08003.

Clauses

In many sentences, even whole clauses can be trimmed to a short phrase or, sometimes, a single word. Consider this pair:

Before: *Once the meeting had been completed,* the senior programmer went to work on the improvements *that were demanded by the customer.*
After: *The meeting over,* the senior programmer went to work on the improvements *demanded by the customer.*

Fog

As many of you know, the most popular technique for assessing how difficult a text is to read (its "readability") is Robert Gunning's famous Fog Index. Gunning's measure — like those of several others — treats words-per-sentence as one of the two main predictors of difficulty. (Word length is usually the other.) Obviously, the phrase trimming techniques described above will shorten your sentences and improve your "readability" scores — and without any loss of information or precision. Consider this pair:

Before: The general feeling of the meeting was that within the framework of the tests a great deal has been accomplished and learned by all parties, and the prototype system had achieved most of the objectives with regard to showing the functional capabilities of SHIP in an INFO/TSO environment.
After: At the meeting everyone agreed that the tests were successful, having proved that SHIP works efficiently in an INFO/TSO environment.

Although you really should not use the Fog Index with a single sentence, it is still interesting to point out that the "before" version has a fog score of *25* (25th grade reading difficulty), while the "after" version has a *14* (14th grade). And most important, the second version *leaves out nothing important.*

Most managers and technical people are wordy — and they know it. Fortunately, though, theirs is an easy problem to solve.

There are others, however, who do not use too many words; they use far too few. True, their writing is lean and tight. But it is so compressed that no one but the writer can understand it! □

NEXT TIME: Too Few Words



The comments and opinions of the author are given for educational purposes only and are not meant to be legal advice. Specific legal questions should be referred to your personal attorney.

Harold L. Novick

The discussion about the copyright controversy involving computer programs continues this month. Last month, guest columnist, P. V. Piescik, gave his views about the copyright state of affairs and discussed the trial judge's decision in the so-called CompuChess case. That decision was appealed and the appellate court recently published its decision. This month's *Forum* continues the dialog and sets forth a rebuttal to Mr. Piescik's views.

The factual background for the recent exchange of views began in the fall of 1977 when Data Cash Systems, Inc. (DCS) began marketing a computer chess game called CompuChess. The computer program that operated the computer was "capable of receiving the player's instructions, determining the computer's possible legal moves, choosing among the permissible moves in accordance with tactical principles, and displaying the computer's move" (Appellate court's description of the program). The program was stored in a ROM which DCS believed could not be copied and the entire game was packaged in a convenient case.

In late 1978, JS&A Group, Inc. began selling its JS&A Computer Chess which was manufactured in Hong Kong and used a ROM that was identical to and concededly copied from, the one used by DCS. DCS then filed a lawsuit for copyright infringement and unfair competition.

After hearing legal arguments relating to motions to terminate the lawsuit, the trial judge ruled that there was no copyright infringement because a ROM was not a "copy" under the copyright laws. Neither DCS nor JS&A had argued this point and the judge reached his conclusion solely on his own. The trial judge made several other amazing rulings which were the apparent basis for Mr. Piescik's pessimism. However, in order to understand the significance of the trial judge and the appellate decisions and, to put Mr. Piescik's pessimism in perspective, it is necessary to provide some background information.

The old copyright act was originally enacted in 1909 and for all matters of present importance, remained unchanged until it was replaced by the new copyright act which generally became effective on January 1, 1978. Under the old act there were three classes of works. A work (e.g. a book) was automatically federally copyrighted after it was "published" with a proper copyright notice. Generally, "publication" consisted of a public sale or public distribution of the work. The copyright notice, which is the same under the new act, consists of the word "Copyright" or the abbreviation "Copr." or the symbol "©"; the year of first "publication" of the work, and the name of the copyright owner. However, if a work were "published" without the copyright notice, then except for very restrictive exceptions, the work is irrevocably dedicated to the public. The third class or possibility under the old act was that the work was embodied in some tangible form, but was not "published." Such a work was not protected by the federal copyright law but was covered under each state's common law copyright. In an over-simplification, this protection was basically akin to that provided by the law against misappropriation (i.e., stealing).

On January 1, 1978, when the new act became effective, each of the three classes was treated separately. If a work were in the public domain, free for anyone to use, then the new act had no effect. If a work were protected by a federal copyright (i.e. published with notice), then the new act changed the life of the copyright. Under the old act the life was a 28 year term renewable once for another 28 years. Under the new act, if the copyright were in its first term on January 1, 1978, its second term, if applied for, is extended to 47 years (for a total of 75 years). If the copyright was already in its second term, the term was automatically extended from 28 years to 47 years. Finally, if a work were unpublished and hence subject to the common law copyright, the new act automatically provides federal copyright protection as though the work were created on January 1, 1978.

For all works created on or after January 1, 1978, the new act applies, and the work is copyrighted without any formalities as soon as it is "fixed" in a tangible medium of expression for more than a transitory duration. Thus, in contrast to the prior law, under the new act a work need not be "published" for it to be copyrighted. Just as important, if the new work were published without the copyright notice, the copyright may still be saved under some liberal savings clauses.

With this background, what happened in the CompuChess case? The trial judge ruled that although the copyright infringement lawsuit should be brought under the new act (presumably because JS&A first sold its chess game with the copied ROM after the new act became effective), the new act did not apply! He said this because section 117 of the new act "does not afford to the owner of copyright in a work any greater or lesser rights with respect to the use of the work in conjunction with (computer systems) than (the "law" in effect on the day before the act became effective." Since the new act did not apply, he opined, he had to look to the prior law and under the prior law the ROM was not "a copy." If a ROM was not a copy, then there was no copyright viola-

Harold L. Novick, Patent Attorney, Larson, Taylor and Hinds, Arlington, Virginia 22202.

tion in reproducing the ROM. The trial judge said much more including that even if the new act did apply, the ROM was still not a "copy."

It is believed the trial judge made several clearly erroneous rulings. First, the judge said that the translation of the programming language (i.e. the source code) into machine language was the development of an "assembly program." Wrong! He next said that the assembly language was "unintelligible except by the computer itself." Wrong again! He then said that an "object code" is "a conversion of the machine language into a device commanding a series of electrical impulses." Since when?

In this author's opinion, the most grievous error was the reason the judge gave for holding that the new act did not apply. The act of infringement was the duplication of the object code stored in the CompuChess ROM into one stored into the JS&A ROM. The act of infringement in this case did not involve the *use* of the computer program; it involved the copying of a work. The work was "fixed" in a material object from which the work could be perceived with the aid of a computer. This is the new act's definition of a "copy." Under the judge's reasoning, he should have ruled that the new act did apply. The second most grievous error was the judge's failure to appreciate that the object code is a translation of the source code, and therefore was presumptively copyrightable subject matter.

In all fairness, however, it has been argued by some that a ROM is not a "copy" in the same sense that an electronic circuit is not a copy of its electronic schematic. One can copyright a schematic and prevent others from photocopying that schematic. However, one cannot use the copyright law to prevent another from building the circuit depicted in the schematic. The water gets even muddier when it is realized that many integrated circuits including ROM's are manufactured by using photographic techniques. Is not a ROM just an electronic circuit? The trial judge apparently thought so. This author does not. A functional test should be used. Can one use a machine or device to "read" the ROM? Does the ROM store *information* that is retrievable? Of course. Therefore, a ROM should be a copy.

Unfortunately, the appeals court that reviewed the trial judge's decision did not explicitly reject any of the lower court's erroneous statements. Although the appellate court upheld the trial judge's statement that there was not a copyright infringement, it did so for entirely new reasons. It seems that when DCS first sold its CompuChess in 1977 (i.e. first published it), it did not use any copyright notice. Over 2,500 games were sold before the new act became effective and "(n)owhere on the ROM, the game board, the packaging, or the accompanying instructions was there a copyright notice." Furthermore, if the contents of the ROM were dumped, no copyright notice would appear because none was there. DCS did not use a copyright notice because "it did not know that it was possible to read the program as (JS&A) did, if one had only the ROM. Too bad, ruled the appellate court. DCS *published* without notice and thus dedicated the ROM to the public.

If this column were to stop here, a great disservice might be done to the readership because of an interesting anomaly. Under both the new law and the old law, the live performance of a song or a play is not a publication; the giving of a live speech is not a publication; the live showing of a T.V. program is not a publication. Nothing is embodied in a "copy" that is "sufficiently permanent or stable to permit it to be perceived . . . for a period of more than transitory duration." Therefore, the live performance of a play does not dedicate, invalidate or forfeit any copyright, whether it is federal copyright or state common law copyright. It follows that since the appellate court held the sale of the ROM without notice was a forfeiture of the copyright, the ROM had to be a "copy." No copy, no forfeiture. Thus, the trial judge was inherently reversed on his holding that the ROM was not a copy.

Mr. Piescik concluded that the precedent established by the trial judge made all software effectively unprotectable. However, that judge's decision is not binding on any other judge. Because neither DCS nor JS&A argued either before the trial judge or before the appeals court that a ROM was not a copy, it is doubted that another judge would give much weight to that holding. Thus, Mr. Piescik may not have anything to worry about. DCS, you do have to worry. If you appeal to the Supreme Court and argue that the ROM is a copy, you may lose because of dedication of the ROM to the public. If you argue that a ROM is not a copy (and hence no publication, no dedication), then the product in JS&A computer chess is not a copy and not an infringement.

Next month, there will be a report on the oral arguments before the Supreme Court in the cases involving the patentability of computer programs. The oral argument was held on October 7, 1980, and a decision should be forthcoming in early 1981. In the interim, if you have computer programs in ROM, publish with notice if you believe ROM's are copies; don't sell them at all if you believe they are not copies. If you don't know, don't live in Las Vegas, and you must sell the program, store the program on magnetic tapes, paper tapes, floppy diskettes, etc., but not on ROM's. □



THE TYPRINTER 221

The TYPRINTER 221 is the only intelligent printer that is **Totally Compatible** with **every** computer and **all** word processing software. Features such as Automatic Underlining, Automatic Bold Print, Reverse Print, Columnization, Decimal Location are all included at no extra cost. This daisy wheel printer prints 20 characters per second with Pica, Elite or Mikron size type. Standard Centronics type interface, RS-232 or IEEE available. This incredible printer can be used off-line as a typewriter with a 17" paper width capacity. Unit has a non-volatile resident memory for: Automatic recall of often-used formats, Automatic recall of often-used phrases.This is the only printer in the world that can be programmed for use with any word processing software. $2850.00

THE MICROLINE-80

The Microline-80 offers business-quality and reliability at an attractive price. Small and lightweight, it easily fits in an attache case. It operates at 80 characters per second, and accomodates three-part forms up to 9.5" in width. It can switch from standard 80 column printing at ten characters per inch to 132 column condensed printing at 16.5 characters per inch. The condensed printing, combined with program controlled line spacing at six and eight lines per inch, provides for substantial savings in paper. Features: Upper and Lower Case, Centronic Interface, 9x7 Matrix, Block Graphics, 110V/220V 50/60 cps, Friction & Pin-Feed. $639.00



PRINTERS

	LIST PRICE	OUR PRICE
Centronics 730	$795.00	$749.00
Centronics 730-3	$895.00	$795.00
Centronics 737	$995.00	$869.00
Centronics 779 w/lower case	$1595.00	$1195.00
Epson MX-80	$645.00	$599.00
LRC 7000 + (64 col.)	$405.00	$299.00
NEC 5510 SpinWriter	$3195.00	$2695.00
NEC 5520 SpinWriter	$3395.00	$2995.00
NEC 5530 SpinWriter	$3195.00	$2595.00
NEC Tractor-Feed Option	$249.00	$225.00
Okidata Microline-80	$800.00	$699.00
Okidata Microline-82	$960.00	$799.00
Okidata Slimline SL300	$5380.00	$4395.00
TYPRINTER 221		$2850.00
Vista V300	$1895.00	$1795.00

COMPUTERS

	LIST PRICE	OUR PRICE
Model I, Level II, 4K	$649.00	$619.00
Model I, 16K no keypad	$768.00	$669.00
Model I, 16K w/keypad	$849.00	$729.00
Model II, 64K Ram	$3899.00	$3799.00
Model III, 16K Ram	$999.00	$929.00
Model III, 32K Dual Disk	$2495.00	$2299.00
Pocket Computer w/Interface	$289.95	$269.00
TRS-80 Color Computer	$399.00	$359.00
TRS-80 Color Computer Expanded	$599.00	$519.00
Atari 400 Computer System, 8K	$629.95	$499.00
ATARI 800 Computer System, 16K	$1079.95	$849.00
16K APPLE II Computer	$1195.00	$999.00
16K APPLE II + Computer	$1195.00	$999.00
32K APPLE II + Computer	$1295.00	$1059.00
48K APPLE II + Computer	$1395.00	$1119.00

TERMS: Prices and specifications are subject to change. HARDSIDE accepts VISA & MASTERCARD, Certified checks & Money Orders; Personal checks accepted (allow 3 weeks to clear). HARDSIDE pays all shipping charges (within 48 states) on all PREPAID orders OVER $100.00. UPS Blue Label or Air Freight is available at extra cost. COD orders accepted (orders over $100 require 25% deposit).

HARDSIDE™

TO ORDER TOLL-FREE
1-800-258-1790
(In NH call 673-5144)

MasterCard VISA

TRS-80 Strings

Stephen B. Gray



For TRS-80 column number 11001, 31, 19 or 25, depending on how you count, we take a very long look at a bunch of ways to create graphics, and short looks at a book on the TRS-80 ROM and a brief program that displays the contents of the ROM.

Six Ways to Graphics

If you have a Level II TRS-80, you can create graphics in at least six different ways:

- SET/RESET
- PRINT@/CHR$
- PRINT@/CHR$+CHR$
- PRINT@/STRING$
- POKE
- String packing.

The first two are well known, the third is an extension of the second, the fourth and fifth are used by many, and the sixth first appeared in TRS-80 publications over a year ago.

SET/RESET

The SET/RESET method of creating TRS-80 Level II graphics is explained fairly well on page 8/1 of the Level II manual.

If you want to create a small box (Fig. A) for a game, you have at least three ways to do it with SET/RESET graphics. Either the horizontal bars extend as far as possible, as shown in the "exploded" version in Fig. B, or the vertical bars extend as far as they can go (Fig. C).

Figures A, B, C.

Or you can create a solid white rectangle with SETs, and then make a "hole" in the center with a few RESETs.

You can create the "compressed" equivalent of Fig. C, with a result that looks like Fig. A, using this:

```
100 CLS
110 FOR X=61 TO 66
120 SET(X,22):SET(X,24)
130 NEXT X
140 FOR Y=22 TO 24
150 SET(60,Y):SET(67,Y)
160 NEXT Y
```

Or you can make a dark hole in a white rectangle with:

```
100 CLS
110 FOR X=60 TO 67
120 FOR Y=22 TO 24
130 SET(X,Y)
140 NEXT Y:NEXT X
150 FOR X=61 TO 66
160 RESET(X,23)
170 NEXT X
```

The problem with both these programs is that although they do the job, the small box can't be moved to another location on the screen without having to write a whole new bunch of instructions for each new location.

If you wanted to move that small box around the screen as part of a game, you could use variables, such as

```
110 FOR X=A TO B
```

but the resulting program would be quite complicated, if you insist on using SET and RESET. Also, this is the slowest method for creating graphics, because SET/RESET turns on (or off) only one graphics block at a time.

PRINT@/CHR$

A much faster way of creating TRS-80 graphics is by using the 64 graphics characters. These characters are made up of six graphics blocks, and because the entire character is turned on all at once, instead of a block at a time, creating graphics this way is six times as fast as with single-block graphics blocks.

All you need is a chart to figure out which number from 128 (all six blocks off) to 191 (all six on) to use when creating graphics this way. Or you can use this program to figure out which is which:

```
100 CLS
110 A=128
120 FOR X=A TO A+9
130 PRINT X;
140 PRINT CHR$(X);
150 NEXT X
160 PRINT:PRINT
170 A=A+10
180 IF A>190 GOTO 200
190 GOTO 120
200 GOTO 200
```

which gives you the full set of graphics characters along with their code numbers (and which appeared in a longer version in *Creative,* Nov. 1979, p 179).

Graphics Characters

With the chart, or the video image, it doesn't take long to see that the small box can be created by using only four of these characters: 183 (looks like a C), 179 (center pair off), 179 (center pair off), 187 (upside-down C).

Now the program is much shorter, using PRINT@ and CHR$

MODEL II

26-4002
64K 1 Drive
$3466.00

MODEL III

26-1061 4K I.....$630.00
26-1062 16K III.....900.00
26-1063 32K III
2-Drives, RS232.....2246.00

DISCOUNT TRS-80® DEALER A301

COMPUTER SPECIALISTS

26-1051 4K Level I System.....$424.00
26-1054 4K Level II System.....552.00
26-1145 RS-232 Board.....84.00
26-1140 "O" K Interface.....249.00
26-1141 "16" K Interface.....359.00
26-1142 "32" K Interface.....469.00
26-1160 Mini Disk - Drive O.....419.00
26-1161 Mini Disk - Additional.....419.00
26-1154 Lineprinter II.....699.00
26-1156 Lineprinter III.....1799.00
26-1159 Lineprinter IV.....859.00
26-1104 Factory Upper/Lower Case Modification Installed.....70.00
26-1506 Scripsit - Tape.....60.00
26-1563 Scripsit - Disk.....79.00
26-1566 Visicalc.....83.00
26-1562 Profile.....72.00

NOTE: Call for availability of VIDEO TEX, Model III, Color, and other new products.

MODEL I



26-1056
16K Level II System
$670.00

COLOR



26-3001 4K.....$360.00
26-3002 16K.....540.00
26-3010 Color Video.....360.00
26-1206 Recorder.....54.00
26-3008 Joysticks.....22.50

ALL OTHER R.S. SOFTWARE FURNITURE, STANDS, CABLES AND ACCESSORIES DEDUCT 10% FROM CATALOG PRICE

Novation Cat Modem..$149.00
CCA Data Management System.....72.00
Adventure Games Games 1-9 each.....14.00

CENTRONICS

Fast 100 CPS Centronics 730 Printer.....$659.00
Text Quality Centronics 737 Printer.....$819.00

Model II Cobol Compiler $360.00
Cobol Run Time Package $36.00

Pocket Computer



26-3501 1.9K P.C.....$225.00
26-3503 Cassette I/F.....45.00
14-812 Recorder.....72.00

Acorn Software Products, Inc.

GAMES:
Alien Invasion.....$9.00
Stock Market.....9.00
Star Trek.....9.00
Block 'Em.....9.00
Ting-Tong.....9.00
UTILITIES:
System Savers.....14.00
EDUCATION:
Language Teacher.....18.00

FREE: COMPUTER CATALOG UPON REQUEST

1-800-841-0860 Toll Free Order Entry

MICRO MANAGEMENT SYSTEMS, INC.

No Taxes on Out Of State Shipments

Immediate Shipment From Stock on Most Items

DOWNTOWN PLAZA SHOPPING CENTER
115 C SECOND AVE. S.W.
CAIRO, GEORGIA 31728
(912) 377-7120 Ga. Phone No.

R.S. 90 Day Limited Warranty
F-48 Form Provided

Largest Inventory In the S.E. U.S.A.

*TRS-80 is a registered trademark of the Tandy Corp.

CIRCLE 163 ON READER SERVICE CARD

TRS-80, cont'd...

```
100 CLS
110 PRINT @ 412,CHR$(183)
120 PRINT @ 413,CHR$(179)
130 PRINT @ 414,CHR$(179)
140 PRINT @ 415,CHR$(187)
```

If this version of the small box were "exploded" it would look like Fig. D, but if "unexploded," then it would look like Fig. E, which is just like Fig. A. But now it's made with four program lines instead of six.

Figures D, E

PRINT@/CHR$+CHR$

Somewhere along the line, somebody discovered that a figure like the small box could be created in a single line by just running the CHR$ pieces together with plus signs, which is called concatenation:

```
100 CLS
110 PRINT @ 412,CHR$(183)+CHR$(179)
    +CHR$(179)+CHR$(187)
```

Another version of this is

```
100 CLS
110 A$=CHR$(183)
120 B$=CHR$(179)
130 C$=CHR$(187)
140 PRINT @ 412,A$+B$+B$+C$
```

If you're wondering why the dollar (string) signs are used after A, B and C, try removing them and see which error message you get.

Note that assigning individual graphics characters to strings, as in lines 110-130, isn't practical in most cases, because too much program space is taken up needlessly.

Now we're ready to move the small box around the screen. All you've got to do is make the location a variable, and change it in a predetermined sequence:

```
100 CLS
110 A$=CHR$(183)
120 B$=CHR$(179)
130 C$=CHR$(187)
140 FOR Q=0 TO 900
150 PRINT @ Q,A$+B$+B$+C$
160 NEXT Q
```

The only problem with this program is that it fills the screen with a perforated sheet of white, which is not what was wanted. To make the small box move across the screen without leaving a trail, the small box has to be erased right after each time it's turned on. This can be done by adding

```
155 PRINT @ Q,"
```

There should be eight spaces between the two quotation marks. Try using less than eight, and see what happens.

Also, try changing line 140 to

```
140 FOR Q=0 TO 900 STEP 8
```

and then try a step of 6 or 12, or other number instead of 8, to see how this affects the "flitting" of the small box.

Note that you could also assign the concatenated four strings to a fifth string, which would simplify moving the small box around:

```
135 D$=A$+B$+B$+C$

150 PRINT @ Q,D$
```

PRINT@/STRING$

Page 5/7 of the Level II manual says that STRING$ (n,character) "returns a string composed of n character-symbols." So to start the small box with a pair of horizontal lines, use four of graphics character 179, which has the top and bottom pairs of blocks lit:

```
100 CLS
110 PRINT @ 410,STRING$(4,179)
```

The two missing blocks can be filled in, prosaically, with

```
120 SET(52,19):SET(59,19)
```

As created here, the small box is difficult to move around the screen. Can you rewrite the program, using STRING$, to create a more easily manipulated box?

TRY THIS ONE!

We read with interest in the June 1980 issue of *Omni* that Daniel Shine is offering a $100 prize for the first person to provide the solution to this problem:

A large number of points are randomly placed in a square. What is the probability that any randomly chosen point is the nearest neighbor to its nearest neighbor, i.e., that it forms with its nearest neighbor a pair such that each is the nearest neighbor to the other? It is easy to determine that the answer is less than two thirds, but what is it exactly?

Shine remarks that "this ought to be solvable in our lifetime since the corresponding problem in one dimension (which I posed) has been solved" (see Daniel P. Shine, "Birds on a Wire," *Journal of Recreational Mathematics*, 11,3, problem 650).

If you think you have the solution—computers are permitted—write Daniel P. Shine, 1038 Nimitz Lane, Cincinnati, OH 45230.

POKE

The basics for POKE graphics are explained briefly on page 8/5 of the Level II manual, which says that "POKE is about 6 times faster than SET" and that for Level II graphics, "it is very important . . . to stay in the range for display locations," which in display memory is 15360 to 16383.

So to print the small box in the middle of the screen, use this:

```
100 CLS
110 POKE 15835,183
120 POKE 15836,179
130 POKE 15837,179
140 POKE 15838,187
```

Or this variation on the same theme:

```
100 CLS
110 FOR X=15835 TO 15838
120 READ D
130 POKE X,D
140 NEXT
150 DATA 183,179,179,187
```

String Packing

Now we come to the most complicated method of creating screen graphics with the TRS-80. Actually, it isn't all that complex, except where variable pointer VARPTR is used.

But first let's step back a bit and look at ordinary strings. You can assign just about anything on the keyboard to a string, simply by putting the alphanumerics in quotes, such as

```
A$="ABC"
```

That string can now be manipulated with a variety of operators. But suppose you want to create and manipulate a string consisting of one or more of the 64 graphics characters. These characters could be easily assigned to a string, if they could be input directly from the keyboard.

That is, if Radio Shack had wanted the TRS-80 to be highly graphics-oriented. The design engineers could have added two more shift keys to the keyboard, plus some more electronics, and then assigned the 64 characters to keys, two to a key — because there are 64 graphics characters and only four dozen keys that could be used.

So either the manual would contain an assignment list, or two graphics keys would be engraved on the top or front of each of 32 keys. Commodore did something like that on the PET, putting graphics characters on some of the keys.

But Radio Shack didn't, no doubt to keep costs down. However, there's a way to put graphics characters in a string. It's called string packing, and it was discovered by Leo Christopherson, whose Android Nim *(Creative,* June 1979, p 125) and Dancing Demon (Oct. 1980, p 178) programs are extraordinary.

The idea is simple: You assign blanks to a "dummy" string, as many blanks as you want graphics characters in the string. Then you look into memory to find out where the computer stored the string. And then you just poke the graphics codes into the string.

NEW EATON 7000+ PERSONAL COMPUTER PRINTER

Now you can add hard copy capability to your computer with plug-in simplicity that matches up to any micro system. And with the Eaton 7000+ dot-matrix printer, you get complete printout versatility at an affordable price.

Interfaces with any personal computer
Apple, Commodore Pet, TRS-80, Northstar and others—no matter what type of computer you have or are thinking of buying, Eaton 7000+ fits. Just plug it in and start printing. You'll get virtually maintenance-free operation with a minimum of moving parts. And minimum life of 100 million characters with Eaton's newest printhead, while the print mechanism is designed for a minimum of 10 million cycles.

High performance design
The 7000+ features uni-directional printing at a speed of 1.25 lines per second. It accepts any standard single or 2-ply roll paper from ¾" to 3⅞" wide and prints 3⅓" line with 40 to 64 adjustable character capacity.

PLUG IN AND PRINT OUT— IN SECONDS!

For immediate information call: Eaton Printer Product Operations, 307/856-4821.

For descriptive literature and the name of your nearest dealer write Eaton Corporation, Count Control/ Systems Division, 901 South 12th St., Watertown, WI 53094.

Dealer inquiries invited.

EATON
Electrical/Electronic Control

CIRCLE 153 ON READER SERVICE CARD

STOCK TRACKER T.M.

IN CBASIC UNDER CP/M®

A POWERFUL, VOLUME-BASED ANALYSIS PROGRAM TO COMPUTE BUY, SELL AND HOLD RECOMMENDATIONS ON STOCKS, OPTIONS AND COMMODITIES, WITH FULLY EDITABLE DISK DATA FILES IN CP/M VERSION PROGRAMMED BY MICRO-AP.

AVAILABLE IN THESE DISK DRIVE FORMATS:
- 8" IBM SOFT SECTOR, SINGLE DENSITY
- 8" DYNABYTE SINGLE OR DOUBLE DENSITY
- 5¼" DYNABYTE SOFT SECTOR
- 5¼" NORTH STAR DOUBLE DENSITY
- 5¼" MICROPOLIS MOD II

REQUIRES: MIN 52K CP/M 1.4 OR HIGHER OPERATING SYSTEM
CBASIC 2.05 OR HIGHER
1 OR MORE DISK DRIVES
24L × 80C OR LARGER CURSOR-ADDRESSABLE TERMINAL

ALSO AVAILABLE: APPLE][® OR APPLE][PLUS® VERSION (MIN 32K RAM, 1 OR MORE DISKS, AND APPLESOFT CARD OR LANGUAGE SYSTEM)
TRS-80® MOD I VERSION (MIN 32K RAM AND 2 OR MORE DISKS)

$350.00	CP/M VERSION COMPLETE; SPECIFY DISK DRIVE FORMAT
$190.00	APPLE OR TRS-80 VERSIONS COMPLETE; SPECIFY WHICH
$ 15.00	ANY MANUAL ALONE; SPECIFY VERSION

ASK FOR THE EVIDENCE!

FOR MORE INFORMATION OR TO ORDER, SEE YOUR DEALER OR:

H & H TRADING COMPANY
POST OFFICE BOX 23546
PLEASANT HILL, CALIFORNIA 94523
Telephone 415/937-1030
VISA & MASTERCARD

ASK ABOUT OUR NEW MARKET TRACKER™ PROGRAM!

® of Digital Research, Apple Computer Inc., and Radio Shack, respectively. ©

CIRCLE 135 ON READER SERVICE CARD

DISCOUNT PRICES

APPLE II COMPUTERS

16K APPLE II	$959.00
32K APPLE II	1024.00
48K APPLE II	1089.00
DISK W/CONTROLLER	525.00
DISK ONLY	450.00
APPLESOFT CARD	159.00
INTEGER CARD	159.00
PASCAL	440.00
SILENTYPE PRINTER	525.00
RAM MEMORY FOR TRS-80, APPLE 16K SET 4116's	65.00

NORTH STAR COMPUTERS

HRZ-1D-32K-KIT	$1595.00
HRZ-1D-32K-ASM	2125.00
HRZ-2D-32K-KIT	1950.00
HRZ-2D-32K-ASM	2475.00

VERBATIM DISKETTES

BOX OF 10	5¼"	29.50
BOX OF 10	8"	39.50

FREDERICK COMPUTER PRODUCTS
MUNICIPAL AIRPORT
FREDERICK, MD. 21701
(301) 694-8884

CIRCLE 140 ON READER SERVICE CARD

TRS-80, cont'd...

So first you assign four blanks to the dummy string

```
100 CLS
110 A$="    "
```

or you can use "XXXX" or "1234"; it doesn't mater, because they'll be replaced by the characters you POKE into the string. If you're using a string more than six or seven characters long, then it's better to fill it with numbers, as in D$="1234567 89012", to help make sure you create a string of the exact length desired.

Then you put into a DATA statement the graphics codes for the four graphics characters

```
120 DATA 183,179,,179,187
```

Next you find the place in memory where the computer has stored the first of the four blanks, using variable pointer VARPTR

```
130 X=PEEK(VARPTR(A$)+2)*256
      +PEEK(VARPTR(A$)+1)
```

Page 8/8 of the Level II manual gives basic information on VARPTR, but because it's a reference manual, doesn't show how to use it.

Let's do some math in calculator mode on the TRS-80. First RUN lines 100-130, then input

```
PRINT PEEK(VARPTR(A$)+2)
```

and you get 66, which is the most significant byte (MSB) of the string-value starting address. You multiply this by 256 to shift it over into the high end of the 16-bit byte-pair, and you get 16896.

To this you add

```
PRINT PEEK(VARPTR(A$)+1)
```

which is the least significant byte (LSB) of the string-value starting address, in this case 241, and you get the complete decimal address 17137, which is what you get if you try

```
PRINT X
```

This decimal address, 17137, is the address into which you poke the first of the four graphics codes in the DATA statement using

```
140 FOR I=0 TO 3
150 READ J
160 POKE X+I,J
170 NEXT I
```

This pokes 183 into address 17137, 179 into address 17138, etc. To try out this program, enter lines 100-170, RUN it, and then simply enter

```
PRINT A$
```

A great deal of memory space is saved using this string-packing technique, which is important if you're trying to squeeze a complicated animation program such as Dancing Demon into 16K. About a third less space is used, compared with using string elements such as CHR$(183). Hang on for further details.

If you LIST this program after RUNning it, you'll find that line 110 has changed from

```
110 A$="    "
```

to something quite different and much longer:

```
110 A$="AUTOCONTCONTNEW"
```

This is because the computer thinks that in this particular context, the numbers 183, 179 and 187 are tokens.

Tokens

When you enter a Basic program into your your Level II TRS-80, the computer doesn't store words such as VARPTR, CLS and DATA in that form, but saves space by translating them into digital tokens. The token for AUTO is 183, for CONT is 179, and for NEW is 187.

The computer can do this because character codes 128 through 191 are used for graphics commands, and 192 through 255 for space-compression codes, and would never be used in Basic statements. So these values, 128 through 255, can be used to store one-character values for each of the words or symbols reserved for Level II Basic.

The computer, not knowing any better, instead of printing out the graphics codes, prints the tokens, making programs written with string packing seem to have been written with tokens.

As an exercise, you might try to figure out how to program graphics using tokens instead of graphics codes 128 through 255. Can it be done?

Bytes and Bits

Just in case the math involved in turning the MSB and LSB into a decimal memory address didn't make much sense to you, let's look into the binary equivalents.

If the most significant byte of the string-value starting address is 66, and the least significant byte is 241, why not just place them together to get that starting address? That would be 66241. Unfortunately, it's not as simple as that.

In combining 66 and 241 to make 66241, what we've done is to change 66 into 66000 and then add 241. This would be all right if the computer's internal language, the language understood by the digital circuits, were decimal. But it's binary.

So you have to take the 66 and multiply it by a binary number to move it over to the left far enough to make room for the 241. This is the binary equivalent of what was done in decimal fashion in the preceding paragraph, multiplying 66 by 1,000, so as to have room for adding in the 241.

The two bytes, the most significant and the least significant, are each eight bits long. So you have to multiply the MSB by a figure that will move it eight spaces to the left, to make room for adding in the LSB, and thus generate the 16-bit address needed for packing.

Multiplying a binary number by 2 will move it one space to the left (just as in decimal numbers, multiplying a number by the base, 10, will move the significant digits one space to the left). Multiplying a binary number by 4 moves it two spaces to the left, etc. Multiplying it by 256, which is 2^8, will move the MSB eight places to the left.

Thus multiplying 66 by 256 produces essentially the same pattern of bits as in binary 66, but with eight zeroes trailing after it, and that trailing portion is where binary 241 goes. Or, in binary:

```
                 MSB      LSB

16896 = 0100001000000000
 +241 =         11110001
-------------------------
17137 = 0100001011110001

          66       241
```

Inside Level II

This is the title of a 70-page paperback, subtitled "A Programmer's Guide to the TRS-80 ROMs", that shows an assembly-language programmer how to use the routines already resident in the ROMs, and how to link assembly language and Basic programs to write a single program that combines the best features of both languages.

The book is $15.95, plus .75 postage, from Mumford Micro Systems, Box 435-B, Summerland, CA 93067, if you can't find it at your local computer store.

Short Program #14

A short program that "displays the contents of the ROM" was sent by Michael Rutenberg of Kingston, Ontario, Canada. He writes:

"It does this without at the same time messing up the screen with control characters such as CHR$(23), CHR$(28), etc. It does this by poking the character into the screen instead of using the PRINT routine." □

```
10 '  THIS PROGRAM DISPLAYS ROM MEMORY WITHOUT MESSING UP THE
20 '  SCREEN WITH CONTROL CHARACTERS ETC...
30 '
40 DEFINT A-Z
50 PRINT STRING$(20,13)    'CLEAR SCREEN AND SET LINE POINTER
60                         'TO BOTTOM LINE OF IT
70 FOR AD = 0 TO 32767
80    PP = AD - INT(AD/64) * 64    'AD MOD 64,  0 <= PP <= 63
90    POKE 16320 + PP, PEEK(AD)    'DISPLAY LOCATION
100   IF PP = 63 THEN PRINT        'SCROLL SCREEN IF END OF LINE
110 NEXT AD
120 STOP : END
```

Stock and Options Analysis



Keep the data you need to make timely investment decisions at your fingertips with this incredibly powerful investment tool. Considerable effort has gone into methods of tilting the odds in the investment game. Out of this has come the discovery that the strategy of hedging listed options against common stocks can tilt the odds drastically. In fact, it can be *more conservative* and *more consistently profitable* than the simple buying and selling of stock.

The four programs in this package are designed to be used in the real world, and include the effects of commissions, margin interest and dividends, where applicable. Possible investment attitudes, the listed option markets, puts and calls and option strategies are covered in extensive documentation.

The program **Opgraph** presents important indices of both opening and closing call option transactions. The manual includes sample runs illustrating combination strategies with covered and uncovered calls, and covered and uncovered straddles recieve detailed treatment.

The **Option** program presents a graph or a table, as the user chooses, of profit from any combination of six basic positions: long or short a stock, long or short a call and long or short a put. Sample runs are presented which cover hedging with calls, out-of-the-money hedges and in-the-money hedges.

Newprem enables the user to predict the future premiums of an option at whatever time and future stock price the user selects. This method requires the establishment of a data base of historical option premiums in whatever detail the user desires.

Finally, **Portval** enables the user to determine on an item by item basis, the cost, current value per share, total current value and capital gain of a portfolio consisting of long and short stock, and long and short option positions. This program assists the user in keeping a readily available and easily updatable record of his portfolio and, at the same time, assists him in measuring his progress towards financial success.

In order for an investor to continually improve his performance it is necessary for him to refer to past performance; this requires useful records. Finally, he should constantly be evaluating his performances to assure himself he is playing the right game.

The **Stock and Options Trading Analysis** package is available for the 32K TRS-80 Level II on cassette (CS-3306) and disk (CS-3801) for $99.95. Creative Computing Software should be available at your local computer store. If your favorite retailer does not stock the software you need, have him call our retail marketing department at the number below. Or you can order directly from Creative Computing Software, Dept AGII; P.O. Box 789-M, Morristown, NJ 07960. Visa, MasterCard, or American Express are also welcome. For faster service, call in your bank card order toll free to 800-631-8112. In NJ call 201-540-0445.

TRS-80 Professional Software

creative computing software

CIRCLE 300 ON READER SERVICE CARD

H&E COMPUTRONICS INC.

•••EVERYTHING FOR YOUR TRS-80™•••

TRS-80 is a trademark of the Radio Shack Division of Tandy Corporation

★ *All Orders processed within 24-Hours*
★ *30-Day Money Back Guarantee on all Software (less a $3 penalty for handling)*
★ *10-Day Money Back Guarantee on Disk Drives and Printers* **PLUS** *120-Days Free Service*

- **LEARNING LEVEL II** By David Lien
  The Original Author Of The Level Manual
  A Step By Step approach to Learning Level II especially geared to new TRS-80™ Owners **$15.95**

- **TRS-80™ DISK AND OTHER MYSTERIES**
  Over 100 pages of indespensible information for disk owners. Learn to recover information from bad disks, how to make Basic programs unlistable and 12 more chapters of never published tips and information. Written by H.C. Pennington. (For all Disk Owners). **$22.50**

NEW SBSG BUSINESS SYSTEM FOR MODEL I OR MODEL II - IN STOCK
- General Ledger
- Accounts Receivable
- Accounts Payable
- Payroll
- Inventory Control with Invoicing

- Each module can be operated individually or as a coordinated **SYSTEM.** Turn-Key error catching operation for beginners.
- Complete manual and documentation accompany each program.
- Minimum System requirements 2-Disk Drives for Model I...1-Disk Drive for Model II
- Each module can be formatted to span data on up to 4-Disk Drives
- Free 30-Day telephone consultation
- Call for complete specifications
- Model I Version **$125.00** Per Module, **$495.00** Per System
- Model II Version **$225.00** Per Module, **$995.00** Per System

DATA MANAGEMENT SYSTEMS
- DMS replace index cards or any data requiring long lists of information.

- TBS In-Memory Information System (For Cassette Systems) **$39.95**
- TBS Disk Data Manager (Requires 1 or more disk drives)...Set up fast random access, files in minutes. Stores up to 320K of information on 4 Drives. Up to 10 fields and 255 characters per record. Supports upper and lower case. RS-232 or TRS-232...Features complete editing **$49.50**
- Personal Software CCA Data Management System...Completely user oriented, menu drive, 130 page Step By Step Manual...Capable of inventory control, sorting data, reporting data in nearly any form (for reports and mailing labels). Sorts data by up to 10 fields for zip code, balance due, geographic location or whatever. Prints reports with subtotals and totals automatically calculated. Fast random access **$75.00**

FROM RACET COMPUTES
- **REMODEL-PROLOAD** - Renumbers program lines, combines programs. The only renumber program that will renumber the middle of a program. Specify 16K, 32K or 48K. Works with Cassette or Disk **$34.95**
- **GSF** - Use in your Basic Programs for Instant Sorting (will sort 1000 items in 9 seconds). Other commands include Compress and Uncompress Data. Duplicate Memory, Display Screen Controls and Fast Graphic Controls **$24.95** (For Cassette or Disk, specify 16K, 32K or 48K).
- **DOSORT** - All G.S.F. commands plus special Multiple Disk Sorting Routines **$34.95** (Specify 32K or 48K)
- **INFINITE BASIC** - Adds 70 commands to your TRS-80™ including Instant Sort, Matrix Commands, String Commands, Left and Right Justification, String Centering, Simultaneous Equations, Upper and Lower Case Reverse and more. (For Cassette or Disk) **$49.95**
- **INFINITE BUSINESS** (Requires Infinite Basic) Eliminate Round-off error, 127-Digit Calculation Accuracy, Insert New Elements in Sorted Arrays, Automatic Page Headings, Footings and Pagination, Multiple Precision Arithmetic and more. (For Cassette or Disk) **$29.95**
- **COPSYS** - Copy Machine Language Programs (For Cassette Only) **$14.95**
- **DSM** (Disk Sort Merge) **$75.00**

FROM SMALL SYSTEM SOFTWARE
- **RSM-2** Machine Language Monitor **$26.95**
- **RSM-2D** Disk Version of RSM-2 **$29.95**
- **DCV-1** Converts Machine Language Programs from tape to disk **$9.95**
- **AIR RAID** - The ultimate TRS-80™ game converts your TRS-80™ into a real time shooting gallery **$14.95**
- **BARRICADE** - A fast pong style game **$14.95**
- **CPM** - (For Disk Only) **$150.00**
- **TRS-232 INTERFACE** - Interface with Software driver RS-232 printers to your TRS-80™ **$49.95**
- **TRS-232 FORMATTER** - Additional (optional) Software for TRS-232 owners. Adds many printer commands to your TRS-80™ **$14.95** (With purchase of TRS-232) **$9.95**
- **PENMOD** - Use the Electric Pencil with RS's lower case modification **$19.95**

FROM GALACTIC SOFTWARE
- **MAIL PAC** - For Model I Disk Systems only **$99.95**
  Quick-sorting full user control over mailing list from Galactic Software.
- **STOCK MARKET PAC** **$99.95**

FROM APPARAT NEW DOS + **$99.95**
35, 40 and 77 Track Versions available.
- **NEW DOS/80** (With variable record length files, chainings and many other features **$149.95**

FROM THE BOTTOM SHELF
- **CHECKBOOK II** (For Cassette or Disk) **$39.95**
- **SYSTEM DOCTOR** (A complete diagnosis of your TRS-80™...Checks memory, video, cassette, disk, ROM, and all other parts of your system) For Cassette or Disk **$28.50**
- **CHECKBOOK REGISTER ACCOUNTING SYSTEM** (Requires 2 disk drives) **$75.00**
- **LIBRARY 100** - 100 established business, game and educational programs plus **FREE** Tiny Pilot all for **$49.50**
- **BASIC TOOL KIT** - Lists all variables, GOTO's and GOSUB's in your program **$19.80**

- **SOUNDWARE** - Adds sound to your TRS-80™ Just plus it in **$29.95**
  Sample programs included.
- **TING TONG** - Can be used with Soundware for a **Sound** version of pong **$9.95**

- **VIC - The Carta Visual Instructional Computer Program** **$19.95**
  The Level II 16K Cassette is designed to teach beginners the Basics of Machine Language and Assembly Language Programming. See every Machine Language Instruction Display on your video. VIC includes Step By Step 55 page manual.

VISTA V80 DISK DRIVE - 110K of Storage **$395.00**
Add $29.95 for Cable (Free with purchase of 2-Disk Drives). 10 day money back guarantee.

FROM HOWE SOFTWARE
- **MON-3** - Machine Language Programming for beginners. MON-3 is a complete System Monitor with Users Manual **$39.95**
- **MON-4** - Disk Version of MON-3 **$49.95**

FROM MICROSOFT
- **LEVEL III BASIC** **$49.95**
  Now Cassette owners can add Disk Commands to their TRS-80™ without owning a Disk Drive
- **MICROSOFT DISK ADVENTURE** **$29.95**
- **TRSDOS BASIC COMPILER** **$195.00**
  Run Basic Programs up to 15 times faster.

- **NEC BUSINESS QUALITY PRINTERS** (For MOD-I or MOD-II) **$2,995.00**

THE ELECTRIC PENCIL
Cassette **$99.95**
Disk **$150.00**
MOD-II Version **$325.00**

- **HORSE SELECTOR II** By Dr. Hal Davis
  The TRS-80™ version updated for the TRS-80™ and originally reviewed in Systems and Methods **$50.00**

••• EVERYTHING ••• FOR MOD-II OWNERS

NEW MOD-II NEWSLETTER	
MOD-II Catalog **Free** w/subscription	**$12/year**
MAIL PAC	**$199.95**
MICROSOFT BASIC COMPILER	**$395.00**
MICROSOFT BASIC	**$325.00**
GSF SORT ROUTINE	**$50.00**
CP/M	**$170.00**
PEACHTREE BUSINESS SOFTWARE	**Call**
WORD STAR	**$495.00**

H&E COMPUTRONICS INC.
MATHEMATICAL APPLICATIONS SERVICE™

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

HOURS: 9-5
Monday thru Saturday

master charge — **24 HOUR ORDER LINE** — VISA

(914) 425-1535

48-Page Catalog $2 **FREE** *With Any Order*
Order By Phone Or Mail
Add $1 Per Order For Shipping Within UPS Areas
Add $3 For C.O.D.
Add $3 For All Foreign And Non-UPS Shipments
Add $3 For UPS Blue Label

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

COMPUTRONICS

MATHEMATICAL APPLICATIONS SERVICE™

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

EVERYTHING

* **APPLE** IS A TRADEMARK OF THE APPLE CORP.

★ *All orders processed within 24-Hours*
★ *30-Day money back guarantee on all Software (less a $3 penalty for handling)*

FROM COMPUMAX BUSINESS SYSTEMS

The COMPUMAX business applications programs are written with the novice computer user in mind. They are easy to use, yet powerful in their capabilities. Further, COMPUMAX supplies the BASIC source code. Thus the programs are easy to modify.

MICROLEDGER

This General Ledger system performs the essential functions of dual entry bookkeeping and matches revenues and expenses:
MICROLEDGER includes the following programs.:
LEDGER 1 - builds and maintains the CHART OF ACCOUNTS file. This file contains both current and accumulated totals for each account.
LEDGER 2 - builds and updates the JOURNAL TRANSACTION file.
LEDGER 3 - lists both the the JOURNAL file and the CHART OF ACCOUNTS.
LEDGER 4 - computes the TRIAL BALANCE and executes POSTING of journal transactions into the CHART OF ACCOUNTS. An AUDIT TRIAL of all transaction is output.
LEDGER 5 - produces the PROFIT AND LOSS STATEMENT.
LEDGER 6 - produces the BALANCE SHEET. Assets, liabilities and owners' equities are shown by account and by totals. **$140.00**

MICROPAY

An Accounts Payable system, MICROPAY includes the following program & functions:
PAY 1 - initializes both Transaction and Master files, then begins the Accounts Payable process by inputting and adding records in the Transaction file.
PAY 2 - allows for changes and deletions of Transaction and Master records.
PAY 3 - reports outstanding Accounts Payables in four categories; under 30 days, 31-60 days, 61-90 days, and over 90 days.
PAY 4 - reports all outstanding Accounts Payables for a single customer or for all customers, and computes Cash Requirements.
PAY 5 - reports all outstanding Accounts Payables for a single date or for a range of dates and computes the Cash Requirements.
PAY 6 - lists both the Transactions and Master files.
PAY 7 - prints checks and accumulates and journalizes Accounts Payables. This program simultaneously creates entries for the MICROLEDGER file. **$140.00**

MICROREC

An Accounts Receivable system, MICROREC includes the following programs and functions:
REC 1 - initializes Accounts Receivable files, adds A/R record and prints invoices.
REC 2 - accepts receipt of customer payments and changes or deletions of A/R Transaction or Master file records.
REC 3 - reports outstanding Accounts Receivables in four categories; under 30 days, 31-60 days, 61-90days, and over 90 days.
REC 4 - reports all outstanding Accounts Receivables for a single customer, or for all customers and computes Cash Projections.
REC 5 - produces reports for all outstanding Accounts Receivables for a single date or for a range of dates and computes Cash projections.
REC 6 - lists Transaction and Master files and accumulates and journalizes Accounts Receivables, creating JOURNAL entries which communicate with the MICROLEDGER JOURNAL file. **$140.00**

MICROINV

This Inventory Control system presents a general method of Inventory Control and produces several important reports. Its program includes:
INV 1 - initializes Transaction and Master files and adds and updates Transaction and Master records.
INV 2 - handles inventory issued or received, creating inventory records. This program also accumulates and journalizes transactions, producing JOURNAL entries which communicate with the MICROLEDGER file.
INV 3 - lists both Transaction and Master files.
INV 4 - produces the STOCK STATUS REPORT, showing the standard inventory stock data and stock valuation, and the ABC ANALYSIS breaking down the inventory into groups by frequency of usage.
INV 5 - gives a JOB COST REPORT/MATERIALS, showing allocation of materials used year-to-date by each job or work code. (This is complemented by the Job Cost Report/Personnel in the MICROPERS program.)
INV 6 - computes and provides the E.O.Q. (Economic Order Quantities) **$140.00**

MICROPERS

This is a Payroll/Personnel program whose functions include:
PERS 1 - initializes the Master file and allows for entry and updates of Master records.
PERS 2 - initializes the Payroll file and allows for entry and updates of payroll records.
PERS 3 - lists an Employee Master Record or the entire Employee Master file; lists a single Payroll Record or the entire Payroll file.
PERS 4 - computes Payroll and prints the PAYROLL REGISTER. Prints PAYCHECKS and creates JOURNAL entries to be fed into the MICROLEDGER JOURNAL file.
PERS 5 - produces the JOB COST REPORT/PERSONNEL, computes the quarterly 941 bank deposit, and the Annual W-2 run. **$140.00**

All COMPUMAX programs available in machine readable format (diskette form) for the following machines:

TRS-80™ Model I	Micropolis 1053/11
APPLE II	Microsoft under CP/M
PET	CBASIC under CP/M
	Cromemco

FROM ADVENTURE INTERNATIONAL (By Scott Adams)

† 1. **ADVENTURELAND** - You wander through an enchanted world trying to recover the 13 lost treasures. You'll encounter wild animals, magical beings, and many other perils and puzzles. Can you rescue the Blue Ox from the quicksand? Or find your way out of the maze of pits? Happy Adventuring . . . . .

† 2. **PIRATE'S ADVENTURE** - "Yo ho ho and a bottle of rum" You'll meet up with the pirate and his daffy bird along with many strange sights as you attempt to go from your London flat to Treasure Island. Can you recover Long John Silver's lost treasures? Happy Sailing, matey . . . . .

3. **MISSION IMPOSSIBLE ADVENTURE** - Good morning, your mission is to...and so it starts. Will you be able to complete your mission in time? Or is the world's first automated nuclear reactor doomed? This one's well named. It's hard, there is no magic, but plenty of suspense. Good luck . . . . .

4. **VOODOO CASTLE** - Count Cristo has had a fiendish curse put on him by his enemies. There he lies, with you his only hope. Will you be able to rescue him or is he forever doomed? Beware the Voodoo Man . . . . .

5. **THE COUNT** - You wake up in a large brass bed in a castle somewhere in Transylvani. Who are you, what are you doing here, and WHY did the postman deliver a bottle of blood? You'll love this Adventure, in fact, you might say it's Love at First Byte . . . . .

6. **STRANGE ODYSSEY** - Marooned at the edge of the galaxy, you've stumbled on the ruins of an ancient alien civilization complete with fabulous treasures and unearthly technologies. Can you collect the treasures and return or will you end up marooned forever? . . . . .

7. **MYSTERY FUN HOUSE** - Can you find your way completely through the strangest Fun House in existence, or will you always be kicked out when the park closes? . . .

8. **PYRAMID OF DOOM** - An Egyptian Treasure Hunt leads you into the dark recesses of a recently uncovered Pyramid. Will you recover all the treasures or more likely will you join its denizens for that long eternal sleep? . . . . .

9. **GHOST TOWN** - Explore a deserted western mining town in search of 13 treasures From rattlesnakes to runaway horses, this Adventure's got them all! Just remember, Pardner, they don't call them Ghost Towns for nothin'. (Also includes new bonus scoring system!) ..... **$14.95 Per Adventure**

* **Note:** Apple requires 24K and has no lower case.
† Recommended for the novice adventurer, with many built-in HELPS!

FROM PERSONAL SOFTWARE INC.

VISICALC **$150.00**

Take virtually any problem you would explore using calculator, pen, and paper, working in rows and columns. Apply VisiCalc and you'll see why every reviewer of this product has said the same thing: VisiCalc is the most useful, most important program yet developed for personal computing.

With VisiCalc, you work with an electronic worksheet of up to 63 columns and 254 rows. At the juncture of any column and row you can type in words and numbers. VisiCalc automatically performs all arithmetic functions, net present value, and transcendental functions - instantly!

CCA DATA MANAGEMENT SYSTEM $74.95

DMS Features:
File Creaton and Maintenance:
- Fields may be alphanumeric, numeric, integer, floating point, or fixed decimal with commas.
- Fields may be COMPUTED FIELDS. DMS will compute any field within a record, using constants or other fields in the same record. Functions include add, subtract, multiply, divide, and raise exponential powers.
- Records are easily located, using the SCAN feature. SCAN for records with a field over, below, or between a range of values.
- Records are easily added and updated. DMS "prompts" you with questions.
- Multi-diskette capabilities for larger files - up to 85,000 characters per file!
- Sort the records into almost any order, using up to 10 fields as "keys". So you can sort for customer numbers; within zip code, for instance.
- Delete records, "compact" files, and backup files on data diskettes easily.

Report Features:
- Print reports with records in any order.
- Select fields to be printed.
- Print mailing labels.
- Numeric totals and subtotals can be specified when a value in an unrelated field in the same record changes. For example, sort, subtotal, and print according to department, or month, or customer number, or model number.

GUARANTEED PROFIT **91%** WINS PLACES SHOWS **32%** AVERAGE PROFIT AT ALL TRACKS-1978

THE HORSE SELECTOR II (FLATS) (By Dr. Hal Davis) $50.00

New simplified version of the original Horse Selector. The first Horse Selection System to actually calculate the estimated odds of each horse.
HIGHER PROFITS (OVER 100%) POSSIBLE THROUGH SELECTIVE BETTING ON:
- Rates each horse in 10 seconds.
- Easy to follow rules.
- Can be used with any Apple II Computer.
- 100% money back guarantee (returned for any reason).
- Uses 4 factors (speed rating, track variant, distance of the present race, distance of the last race)
- Using the above factors, the Horse Selector calculates the estimated odds. BET on horses whose actual payoff (from the Tote Board or Morning Lines) is higher than payoff based on estimated odds.
- Using the above factors, the Horse Selector calculates the estimated odds. BET on any selected horse with an estimated payoff (based on Tote Board or Morning Lines) higher than calculated payoff (based on Horse Selector II).
- Source listing for the TRS-80™, TI-59, HP-67, HP-41, Apple and BASIC Computers.
- No computer or calculator necessary (although a calculator would be helpful for the simple division used to calculate estimated odds)

FREE Dutching Tables allows betting on 2 or more horses with a guaranteed profit.

master charge **24 HOUR ORDER LINE** VISA
(914) 425-1535

ADD $2.00 FOR SHIPPING UPS AREAS
ADD $3.00 FOR C.O.D. OR NON-UPS AREAS
ADD $4.00 OUTSIDE U.S.A, CANADA & MEXICO

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

CIRCLE 137 ON READER SERVICE CARD

George Blank

Intercepted message from an unidentified suborbital earth vehicle on stardate 1980.360/0120Z

```
10 GR. 7
20 C. 3
30 PL. 40,65
40 DR. 120,65
50 DR. 80,5
60 POS. 40,65
70 POKE 765,3
80 XIO 18,#6,0,0,"S:"
90 C. 2
100 PL. 76,6
110 DR. 85,2
120 DR. 75,2
130 DR. 83,6
140 DR. 80,0
150 DR. 77,6
160 PL. 79,3
170 DR. 81,3
180 SE. 0,12,2
190 C. 1
200 F. Y=78 TO 82
210 PL. Y,65
220 DR. Y,80
230 N. Y
240 PR.,
250 F. X=1 TO 15
260 REA. Y
270 PR. CHR$(Y);
280 N. X
290 D. 77,101,114,114,121,32,67,104,
114,105,115,116,109,97,115
```

Transmission Report

TO: All Outposts

FROM: Headquarters

SUBJECT: Defective message traffic from Outpost Atari

TEXT: The following difficulties have been reported in previous transmissions from Outpost Atari:

Report of August 1980 — "For Apple HLIN and VLIN are for lo-res only. For hi-res HPLOT TO is as good as anything Atari has." Fred Gerlach, Houston, TX

George Blank, Foster Road, Milford, NH 03055

Report of September 1980 — "You said that a USR machine language routine was needed for timer accuracy: no need! Merely calculate time twice (2 sets of PEEKs); if they differ by more than one second, loop until they don't." Wilson Dillaway, Johsonville, NY.

"You stated that one should NOT put more than 40K of RAM into an Atari 800 because the last 8K is used for ROM cartridges. The Atari is a sophisticated machine and will allow access to the last 8K of RAM if there are no cartridges present, and to 4K of that if only one cartridge is present. For Atari VisiCalc we strongly recommend the additional memory" Bob Frankston, VisiCalc Co-author.

Programming Hint

With the powerful screen editing capabilities of the Atari, there are times when you want to edit some lines frequently. For example, you might want to try different color hues and luminances until you get the ones that look best. Here is a routine that allows you to RUN your program, then press enter to LIST it. The RUN is printed at the end of the list so that you can just press RETURN on that line to restart.

```
20000 DIM XX$(1):INPUT XX$
20010 GRAPHICS 0:LIST:PRINT"RUN":END
```

Philosophical Essay — Computer Comparisons

One of the most serious illnesses in our national thought process is our philosophical bent toward positivism. Positivism is the attempt to reduce all of life to numbers, so that is can be compared mathematically. This virulent American disease tends to overvalue that which is easily quantifiable, and overlook that which is difficult to express mathematically.

For example, I know of a law firm that would have been able to use a small computer profitably, but decided not to buy because other law firms in the area had minicomputers. The decision was made, not on the basis of ability to do the job, but strictly on the basis of price tag. For this lawyer to buy a less expensive computer would be to lose face with his competition. Price is easily quantifiable. An Atari computer system might cost $3,000 while an IBM system might cost $300,000. While this certainly out to be considered in a purchase decision, the abilities of the individual computer is a far more important decision.

In our typically American positivistic way, we have sought to quantify the abilities of different computers. Certainly, some good tests have been established, giving us benchmarks and price-performance ratios. But this is often carried to the point of ridiculousness. Does it really matter that Brand X can sort a 1000 element array in 22 seconds while Brand Y takes 29 seconds? It might, if you are going to spend a lot of time waiting for your computer to sort 1000 element arrays. However, there are probably circumstances in which it might be more sensible to buy Brand Y because it comes in a color that matches the rest of the office!

I am not saying that we should ignore quantitative data in the purchase of a computer. I certainly don't. For example, I think that the length of the warranty period, the number of nearby service centers, the cost of service, and a lot of other quantitative information is helpful in a computer purchase. But I think people who are comfortable with computers have a special tendency to rely too much on numbers.

Probably the best way to test a computer is actually to use it. You will probably find some things you really like, and other things you hate. For example, I am currently typing this article on a non-Atari microcomputer. With it's sharper definition of letters, longer text lines, and excellent word processing software, the other computer is a better choice than the Atari for word processing. However, I find times when I can barely tolerate the other com-

puter. Perhaps the biggest annoyance is shoddy power supplies that constantly hum and buzz. The Atari is much better built. In addition, the other computer generates so much television interference that I can only use the Atari when the rest of the family is home.

Recently, at *SoftSide* magazine, we have discovered an excellent stress test for comparing computers subjectively. It is the process of trying to write an entire program in a single line. Please note that I am not recommending this as good programming practice. Programming in one line is highly dependent on fancy tricks and does not make for elegant or easy to read programs. But it does rapidly show up certain strengths and limitations of the particular computer.

With the Atari, we have found it possible to put a program in a single line that includes continuous graphics, sound effects, and imaginative use of color. We have also found that the Atari is wasteful of memory space, and we really miss having IF .... THEN .... ELSE construction. We have also discovered a lot of fascinating tricks that are also bad programming practice. Among the tricks are using POKE instead of SETCOLOR to set colors and using abbreviations to write lines that are so long that they cannot be edited because the Atari expands them to fill more than three lines.

There is a great temptation to use numbers when we have a computer available, because the computer can produce such elaborate reports. But I strongly request that we resist the positivistic impulse, and a good place to begin our resistance is in the decision to buy the computer in the first place. Let us save our society from inundation in meaningless statistics! □



©Creative Computing

Apple-Cart

Chuck Carpenter

Correspondence is always welcome and a response will be made to those accompanied by a SASE. Send your letters to: Chuck Carpenter, 2228 Montclair Pl., Carrollton, TX 75006.

Season's Greetings. Seems odd to be saying that this time of year (4 Aug '80). We've had over 40 days of temperatures greater than 100 degrees. This column will be devoted mostly to a number of things you may want to get or give for Christmas. Or if you didn't get some things you wanted, the items included here might round out your stocking. Also, in Figure 1, you will find my rendition of the complete (more or less) Apple II memory map.

Books

6502 Software Design
By Leo J. Scanlon
Sams #21656, $10.50

This is a new book in the Blacksburg series and probably the best book for beginners. Even though the AIM 65 was used as the demonstration system, the information is useful for any 6502 system. The more than 90 programming examples are thoroughly described starting with the simple and progressing to the complex.

Chapter 1 provides a discussion about the history and the significance of the 6502. The characteristics of the device are described and so are the features of the AIM 65 Microcomputer. Chapter 2 begins a thorough treatment of the 6502 instruction set. A summary of the instruction set is first, then a presentation of the thirteen 6502 address modes. Other chapter sections break the instruction set into 9 related groups. In chapters 3 and 4, *subroutines*, and lists and lookup tables are presented. Subroutines include nesting, data moving and time delays. Lists and tables include unordered lists, sorting, ordered lists, lookup and jump tables. Chapters 5 and 6 include the mathematical routines. This is the first book I've seen that doesn't bog you down with computer mathematics until the chapters where it's used. Really pleasant. All types of mathematical functions are included here. Programs for the basic four functions along with all sorts of conversions from one number base to another are included.

Interrupts and resets are presented in chapter 7. These are the features that let you control the outside world while running your favorite program. The Nov. '80 *Apple Cart* column provided explanation and applications of these 6502 features too. Chapters 8 and 9 discuss how to connect the 6502 to all sorts of input/output (I/O) devices. Some of the popular internal hardware devices are discussed along with familiar external peripherals. There's plug-in hardware now available for the Apple that lets you do some of the I/O things described here. The Appendix includes a summary of the ASCII character set and a detailed summary of the entire 6502 instruction set. This was a refreshing change too since other books have been entirely devoted to the instructions without explanation of how to use them.

The Blacksburg series includes two other books I found extremely helpful for learning about machine language programming. They are titled *8080/8085 Software Design* parts I and II. The subject of assembly language programming is very well presented. And, even though the architecture of the micro's is different, the techniques are similar. If you were to read these first, then read *6502 Software Design*, you would be very well versed in the subject.

Introduction to Low Resolution Graphics
By Nat Wadsworth
Scelbi Publications, about $15.00

This book is a summary of low resolution graphics for the TRS-80, Commodore (PET) and Apple II computers. Most of the programs are written for the Apple II making it of use to Apple owners. It is a good book for use by the newcomer. There are 5 chapters including Getting Started, A Whole Chapter on Math, Drawing Simple Shapes, Drawing Lines, and A Graphics Library.

Radio Teletype Apples

Radio Amateurs who are interested in Radio Teletype (RTTY) and morse code (CW) operation will be interested in a new hardware and software package, *Integer Basic*. The package includes a circuit board containing narrow band FM detection and generation circuitry and CW keying and detection circuitry. I used the software a few years ago when it was first available from Chris Galfo. He has since teamed with Alex M. Massimo who is marketing the complete hardware/software package. The package is intended for the experienced operator who understands the theory and operation of RTTY and CW. Once connected to your radio equipment, the screen of the Apple II becomes a display of messages being sent and received. The screen is divided into three separately scrolling areas. The top section displays 16 lines of messages received, the bottom section shows the last 5 lines of the output message buffer, and the middle line displays, in billboard fashion, the text as it is being transmitted. The software provides customizing functions so you can do those things like CR, LF and LTRS in RTTY and ID's and your station setup in RTTY and CW. The package called RADCOM PLUS +, is $190,000 for the circuit board, an *Integer Basic* software disk (It used to be available on tape too) and documentation. For more information contact Alex M. Massimo — AF6W, 4041 41st Street, San Diego, CA 92105.

Software By Phone

The Software Connection has added at least 3 more programs. You can now get by phone, a *Phone Secretary*, *Computer Calculator*, and *Phone Chess*. The *Phone Secretary* lets you automatically dial a list of phone numbers. You can also log incoming calls on your computer. The

SPACE WAR

You're in command in **SPACE WAR!** Destroy your opponent's ship by forcing him to collide with the sun or to explode upon re-entry from hyperspace or challenge him face to face with missile fire. You're in command of the speed and direction of your ship. You control the timing of your missiles. You select the game mode from five options, including Reverse Gravity, and the battle begins. Accelerate to place your shots--and escape into hyperspace before your opponent comes within range. But be wary, he (or she!) may circle out of sight and reappear on the opposite side of the galaxy! (This is the classic MIT game redesigned especially for the Apple.)

and SUPER INVASION

- **Super Invasion** is the original invasion game, with the original moon creatures and faster action than any other invasion game.
- Features superb high resolution graphics, nail-biting tension and hilarious antics by the moon creatures!
- Self-running "attract mode" of operation for easy learning and demonstrating of the game.
- As good in every way as the famous Invaders arcade game.
- High speed action! • Sound effects!
- Runs on the Apple II and the Apple II Plus





Fifty-five aliens advance and shower you with lethal writhing electric worms. As you pick off the aliens, one-by-one, they quicken their descent. They whiz across the screen wearing away your parapets, your only defense, coming closer and closer to your level. **Super Invasion** is the **original** invasion game with the original moon creatures and faster action than any other invasion game on the market.

Super Invasion is available for only $19.95 on cassette (CS-4006) for a 32K Apple II. **Space War** is $14.95 on cassette (CS-4009) for a 16K Apple II. **Space War** and **Super Invasion** are on one disk (CS-4508) for a 48K Apple II for only $29.95.

Send payment plus $1.00 shipping and handling to Creative Computing Software, P.O. Box 789-M, Morristown, NJ 07960. NJ residents add $1.00 sales tax. Bankcard orders may be called in toll free to 800/631-8112. In NJ call 201/540-0445.

sensational software

creative computing software

Apple, cont'd...

Computer Calculator provides you with the capabilities of a 98 function calculator. There are many options with the calculator program to let you save or print-out the results of your calculations. *Phone Chess* provides the capability for you to play chess with a friend over the phone. Only one of the players needs to have the program. Use your accoustic or direct modem to capture the programs on your initialized diskette. You need to have Applesoft in ROM (or language card), and the system doesn't like the autodialer programs in use on some machines. Make sure your first program is the free TSC autodial program; this one is compatible. The Telephone Software Connection's modem can be reached at (213) 329-3715, 24 hours a day.

Apple II Resource

WIDL Video is publishing the most complete directory of products and sources of information for the Apple I've seen. The book is not a catalog and you can't order things from it. But you don't need to get copies of all the magazines to find things for your Apple. As indicated by the following quote, the company is dedicated to promoting the Apple II computer.

"If you are considering the purchase of a personal computer and have not as yet made your choice, we recommend the Apple II very highly over every other mini computer currently on the market. The features, quality, and overall value of the Apple are, in our opinion, outstanding. It has the ability to grow and expand as your needs change because its excellent design was built around modular concepts. The standard Apple contains eight built-in connectors that allow you to add a variety of languages, printers, floppy disk drives, modems for telephone communication, and many more."

"If you are undecided, we feel that the Apple is an excellent choice. See your local Apple dealer today for a full demonstration. Feel free to contact us if you have further questions. We will attempt to answer them as best we can without selling you anything, as we do not sell the Apple. We only believe in the product."

Included in the contents of the book are 13 categories of Apple resources. These include Boards, 34 entries covering do-it-yourself hobby boards, special interface boards, communications boards, video digitizing boards, the 80 column video boards and much more. There are 4 Music board entries, 36 Peripherals and devices, 17 Accessories, 10 sources for expanding Storage, and 7 more Resources And Supplies entries to help you find things. Other contents include Books, Magazines And Publications, Special Apples (incouding an Arabic Apple), Time Sharing Systems, User Groups, Software Producers And Sources and Authorized Apple Dealers.

Most of the entries are up-to-date. I noticed some that are no longer around and some that are incorrect. The directory is dated Spring 1980 so it's quite possible there have been some changes. As always, the buyer beware approach is best. I would estimate the contents are better than 90% correct, making the book an excellent Apple information resource. Call or write to the specific listed company if you're not sure about the current status. *The Resource Directory* is available for $4.95 postpaid from WIDL Video, 5245 West Diversy, Chicago, Illinois 60639 (phone (312) 622-9606).

Lower Case Adapter

Dan Paymar has had his adapter on the market for some time now. By plugging-in an adapter board and a couple of chips, you can have upper and lower case on the screen. Unlike other lower case generators, the Paymar adapter does not use a lot of your program memory to generate the characters. The hardware adapter extends the Apple's normal text display to a full 96 ASCII set, including lower case letters with descenders. In addition you gain 5 additional symbols including right and left curly brackets and vertical dashes.

The adapter includes Integer Basic demonstration software and machine language software is available. Several of the word processors are compatible with the adapter, including Super-Text, the one I am now using. Installation is not difficult but may be tricky in some of the newer Apples. You may have to remove the case in order to plug in the adapter. The adapter is $64.95 (June '80) from Enhanceware, 91 Pioneer Place, Durango, CO 81301.

Serial IO Board

A low-cost serial board is available from Electronic Specialties. The board is RS-232 compatible and includes the DTR (Data Terminal Ready) signal for handshaking. Software residing in memory — usually page 3 — is required to run the board. As received, the software is for slot zero. Information is included to let you make changes in the calls for other slots. Since the language cards use this slot you will want to do this. I was told that the software is available on tape and possibly diskette. If you include the software in your hello program, you can load it each time you start-up your system. The speed adjustments are made by changing components values, and tuning of the timing is required. Software for making the adjustments using your computer is also included. Also as supplied, the software sets the printing width to 72 characters. A POKE to the width address can be used to change it as required. Even though the board is simple in design, I have used it and found it quite effective. As a general purpose I/O board in my development system, it is more than adequate. You can get a board only with instructions for $15.00, a kit of all the parts for $42.00 or a completely assembled and tested unit for $62.00. For more information contact Electronic Systems, P.O. Box 21638, San Jose, CA 95151 (phone (408) 448-0800).

S-C Assembler II Update

S-C Software has announced The Disk Version 4.0 Upgrade Kit. There is also a new 4.0 tape version that will work with any Apple II. For those of you who now have the S-C Assembler the upgrade kit provides many new features including considerably increased assembly speed (for whatever reason you might need it). Here are the new features.

New Editing Features

- ability to append source programs from disk or tape.
- automatic line numbering
- parameterized RENUMBER
- memory usage display
- escape IJKM with or without Autostart ROM
- tabs set up for 6-char labels
- star-dash line automatic generation
- no conflict with D.C. Hayes modem

New Assembly Features

- multiple source files using .IN directive.
- object code direct to disk using .TF directive.
- listing on and off using .LIST OFF and .LIST ON.
- .PG to issue form feeds during listing
- .BS to reserve a block of storage
- tremendous speed increase
- labels up to 32 characters
- labels may include periods
- local labels
- after an assembly error the line is listed
- .EQ values and .BS addresses are printed on the listing.
- assembler and DOS memory is protected during assembly
- symbol table printed in alphabetical order

The 20-page update manual includes detailed descriptions and examples of the new features. Also included are memory usage, Specific ROM entry points for routines used with the assembler, and a bibliography of sources for 6502 information. The new manual brings the total manual pages to over 60. In addition, the new update includes a programmer reference card. The card includes a quick reference to all the Assembler commands, directives, a memory map, ASCII chart, relevant DOS commands, the 6502 opcodes, Apple's Sweet 16, sixteen bit

SOFTWARE for TRS-80 MODEL I & II

★ General Ledger, C.P.A.
★ Balance-Forward Accounts Receivable
Open-Item Accounts Receivable
★ Contractor Job Costing
★ Accounts Payable
★ Payroll-Union-Piece-Farm-Restaurant
★ Cash Flow Statements
$240.00 each

Quality business software written especially for the Radio Shack computers.
These are not Osborne programs.

Submit blank diskette for sample report printouts.

COMPUTER SYSTEMS DESIGN, INC.

P.O. Box 735
Yakima, WA 98907
(509) 575-0320

CIRCLE 271 ON READER SERVICE CARD

GALAXY SPACE WAR I

Galaxy Space War 1 (WAR1) is a game of strategy in which the player has complete control of his space fleet's tactical maneuvers. Each fleet battles its way toward the opponents galaxy in an attempt to destroy it and win the war. WAR1 simulates the actual environment encountered in a space war between two galaxies. Optimum use is made of Apple's high resolution graphics (HIRES) and colors in displaying the twinkling stars universe, the colored ships of each fleet, long range sensors colored illuminations, and the alternating blinking colors used in battles between ships. Complementing HIRES are the sounds of war produced by Apple's speaker.

WAR1 is played between Apple and a player or between two players. You may play with total knowledge of each others fleet or only ships sensor knowledge of the opponents fleet. Each player builds his starting fleet and adds to it during the game. This building process consists of creating the size and shape of each ship, positioning it, and then allocating the total amount of energy for each ship.

During a player's turn he may dynamcially allocate his ships total energy between his screen/detection and attack/move partitions. The percentage of the total energy allocated to each partition determines its characteristics. The screen/detection partition determines how much energy is in a ship's screens and the detection sector range of its short range sensors. The attack/move determines the amount of energy the ship can attack with, its attack sector range, and the number of sectors it can move in normal or hyperspace.

When an enemy ship is detected by short range sensors, it is displayed on the universe and a text enemy report appears. The report identifies the ship, its position, amount of energy in its screens, probable attack and total energy, a calculated detection/attack/move range, and size of the ship. Also shown is the number of days since you last knew these parameters about the ship. When a ship's long range sensor probes indicate the existence of an enemy presence at a sector in space, this sector is illuminated on the universe.

An enemy ship is attacked and destroyed with attack energy. If your attack energy breaks through his screens, then his attack energy is reduced by two units of energy for every unit you attack with. A text battle report is output after each attack. The program maintains your ship's data and the latest known data about each enemy ship. You may show either data in text reports or display the last known enemy positions on the universe. You can also get battle predictions between opposing ships. The text output calculates the amount of energy required to destroy each ship for different energy allocations.

APPLE® II, 48K, APPLESOFT ROM CARD, DISK II DOS 3.2
WAR1 DISK & MANUAL ...$39.95
(CA residents add 6% sales tax)
Write or call for more information

GALAXY
DEPT. CC4
P.O. BOX 22072
SAN DIEGO, CA 92122
(714) 452-1072

Find Your Way Around The New Apple® DOS With The Dakin5® Programming Aids 3.3®

Dakin5 Corporation, a Colorado software house, is making available to the public 12 utility programs on one 16 sector diskette, utilizing the new Apple DOS 3.3, which provides 23% more storage.

All of the Dakin5 Programming Aids 3.3 programs are also compatible with the Corvus Disk Drive system.

Features

- Remove REM statements, unreferenced (dead) code, and compress code to increase program speed and save memory and disk space.
- Copy any file or program from one diskette to another. Only the name is needed.
- Print or display a line cross reference and variable name cross reference.
- Print or display all or selected records from a text file.
- Display any sector of a given file or program, and then update any data within that sector, or specify the sector you wish to update, such as directory sectors and sectors occupied by DOS.
- Create, print and modify your own text and Exec files.
- Perform 20-digit arithmetic.
- Copy a diskette without DOS; initialize without DOS; verify source diskette; verify copied data is the same as the original.
- Use a powerful data entry routine that handles both string and numeric data.

Plus Many More Utility Programs for Sophisticated Programmers

Many of these utility programs have been developed and tested for in-house use while producing The Controller™ business package for Apple Computer Inc.

Each programming aids package includes a program diskette and very complete documentation, all attractively packaged in a padded, blue print vinyl 3-hole notebook with silver lettering. An identifying tab separates each program for convenient reference.

See your Apple dealer or contact Dakin5 Corporation, P.O. Box 21187, Denver, Colo. 80221. Telephone: 800-525-0463. VISA or MC welcome.

Apple is a registered trademark of Apple Computer Inc. The Controller is a registered trademark of Dakin5 Corporation.

DAKIN5 CORPORATION

CIRCLE 122 ON READER SERVICE CARD

APPLE — JACK

the graphics & games people

New!

THE DESIGNER

HIRES GRAPHICS



$24.95 DISK & MANUAL

THE DESIGNER is a user oriented APPLESOFT program that does the HPLOTing for you. Sometimes referred to as the 'poor man's graphics tablet', it places lines and complex circular functions on the APPLE HIRES screen with the use of game controls and single key-strokes. 2 page animations, disk save and recall, and simple cursor-driven executions are among the features of this crash proof program.

REQUIRES 48K APPLE/APPLESOFT ROM/DISK

AVAILABLE FROM YOUR DEALER OR DIRECT FROM
APPLE — JACK, BOX 51, CHERRY VALLEY, MA 01611
(INQUIRIES INVITED)

CIRCLE 106 ON READER SERVICE CARD

Apple, cont'd...

interpreter opcodes and a list of useful I/O addresses. The card, priced at $2.50, is included with the 4.0 update but is worth the price to have it just for the information it contains.

Since there are now several options for the S-C Assembler II, here is a list of the options and prices.

- old cassette version (requires I/B), $25.00
- version 3.2 disk, $35.00
- upgrade old cassette to 3.2 disk, $12.50
- upgrade from 3.2 disk to 4.0 disk, $22.50
- complete new 4.0 disk, $55.00
- complete new 4.0 tape, $45.00
- upgrade 4.0 tape to 4.0 disk, $12.50

Each version includes appropriate manuals and diskettes or tape. Note that the old tape version requires that you have Integer Basic; either in the original version or the Integer Basic language card. The S-C Assembler II was reviewed in the July '80 column and the point about the tape version requiring I/B was missed. For more information contact S-C Software, P.O. Box 5537, Richardson, TX 75080 (phone (214) 324-2050). Don't forget with the S-C Assembler, it's easy to learn, use and remember.

Game Paddle Extender

Have you ever wanted to have more game paddles? Or, have you wanted to plug other gadgets into the game paddle connector? If so, here's a little kit that can help you make those extra connections. The kit consists of an extender cable and a circuit board. Six, sixteen pin sockets can be mounted on the board. One of the sockets has the pins connected so you can connect 4 game paddles at the same time. Sorry folks, there are only 3 switch inputs just the same. I mounted the board on a small plastic cabinet that I bought at Radio Shack. The sockets came from Radio Shack too. With this adapter/extender, you can plug in a variety of gadgets and circuits. My serial printer program and connections remain plugged-in now. And, I don't have to switch plugs with the game paddles either. You can use other connectors to supply signals for any other devices you want to connect too. Just make sure there is no conflict with the input/output pins, and that the current drawn from the 5-volt pin does not exceed 100ma. You can get the adapter kit from CDS INC., 14222 Dallas Parkway #1104, Dallas, TX 75240. The cost is $9.95 post paid.

Apple's Support Policy

Comments from readers in recent letters indicated a lack of support from Apple. I wrote a letter to Phil Roybal, an executive at Apple, for a clarification of the current policy. Here is Phil's unedited reply . . .

Dear Chuck,

Thanks for your letter asking about our approach to customer problems. I enjoy your column, and appreciate the opportunity to respond to questions in it. Here's what's happening.

I set up the Hot-Line in early 1978 to help customers with applications problems. Since then the Hot-Line crew has grown to 5 full-time people. But in the same time the user base mushroomed to well over 100,000.

How could we service that number of people efficiently? Our answer has been three-fold:

1. EDUCATE THE DEALER BASE

Dealers are our first line of contact with the public. We depend upon them heavily for customer technical support. (And they are compensated for this in the profit they make from a computer sale.) Through newsletters, demos, and training programs like APPLE MEANS BUSINESS, we have provided a lot of tools and motivation for learning our products in the past six months.

The results of this training are beginning to show. In the last 4 months, the percentage of dealer calls to the Hot-Line have tripled. That means more knowledgeable dealers (who learned the answers and thus have them when you need them), and less traffic tying up the line (because answers are available locally) when you call.

2. MOVE SUPPORT INTO THE FIELD

It has been hard to get through to the factory for a while, due to the volume of incoming calls. So we are moving support outside, closer to the dealers.

We are now building Field Applications Support groups in each Area Sales Office across the U.S. These groups will perform the traditional Hot-Line function for their territories, while the headquarters



Figure 1.
The Complete (More or Less) Apple II Memory Map.

group concentrates upon writing application notes, digging up technical information, and keeping the field informed. We have already hired people in two areas, and will soon put them through formal training. The dealers should see the effect of their presence by October.

3. SUPPORT USER GROUPS

Apple has strongly supported the International Apple Core and its member groups, and encourages all new users to seek out and join such groups. We will continue to do this, because we know that there's no better source of detailed information than an enthusiastic and knowledgeable user.

Dealers are paid to support products, not just to supply them. Apple offers an ample margin to cover a dealer's efforts, and expects that users will insist upon a certain level of support from retailers they give their business to. So when you ask how a mail-order customer gets help, the answer is the same as it is for any other user: he goes first to his dealer.

We've gone through a period of incredibly rapid growth, and the user base temporarily outgrew our ability to support it. But I have a strong commitment to keeping Apples productive in the field. This requires timely, accurate technical information. Our goal is to provide that information through retailers, backed up by Field Applications Engineers, backed up by the central support team.

Sincerely,
Phil Roybal
Mgr. Communications Programs

There you have it. I find it to be a reasonable approach. Remember, if you are having problems, make sure your dealer provides the necessary help. They are charged with the responsibility by Apple. As I have mentioned in the past, be rational. You won't get much help by being unreasonable. With as many circuits as there are in an Apple it is unavoidable that things will go wrong. Being firm but tactful will help solve the problems quickly.

Apple II Memory Map

Figure 1 is my rendition of current memory use in the Apple II. RAther than clutter the map with all the memory boundaries, only key reference addresses are included. The addresses are hexadecimal. For more information, refer to the *Apple II Reference Manual*. Once again, Happy Holidays. □



Correspondence is welcome. Letters with interesting questions and ideas will be used in the column along with a response. No personal replies can be made. Send to: David Levy, 104 Hamilton Terrace, London NW8 9UP, England

CHESS (Part 2)

This month we shall continue our historical survey of the most important milestones in mainframe chess programming.

The first program of the modern generation was written at M.I.T. by Richard Greenblatt, a student, and two colleagues. Work on the program began in November 1966, and by April the following year it had scored two wins, two draws and no losses in a tournament with human players. Based on statistics given in Greenblatt's paper, I would estimate that his program, at that time, was stronger than any commercially available chess machine currently on the market. The name of his program was MacHack VI.

MacHack employed a plausible move generator containing some 50 heuristics. The program was intelligent enough to know that certain heuristics were not always applicable, but depended on the nature of the position. In this way, moves selected by the plausible move generator were not always exactly the same set of moves as those which would have been chosen by a linear evaluation function. From this aspect of MackHack's decision process the programmer can learn an important trick — it is often useful to use one evaluation mechanism (or set of heuristics) to select the plausible moves for the tree, and another one for performing the evaluation of terminal nodes.

The plausible move generator made its decisions by considering the moves themselves, rather than the positions arising after the moves were made. For example, if a move is bad because it blocks the line of attack of another of the player's pieces, the program would recognize the fact rather than look at the resulting position and say to itself "Hey! This position is bad because my bishop is blocked." By accepting or rejecting moves for the plausible move list in this way, the program saved a great amount of computation.

During the plausible move computation, each square of the chess board was assigned a measure of importance, corresponding roughly to the estimated value of having an extra piece attacking that square, or the cost of moving away a piece which currently attacked that square. The most important criteria used for assigning these values included how near the square was to the center of the board or to the enemy king, and whether or not the square was occupied by one of the program's pieces which is under serious threat.

The value of a piece in strategic terms (as opposed to its actual material value) was related to the number of squares it attacked, i.e., its mobility, and to the number of enemy pieces that it attacked. These strategic values were computed for the piece in its old and new locations, and a strategic gain was taken as an indication that the move should be on the plausible move list. In other words, if a move appears to put a piece on a better square, that move is worth further examination.

The program encouraged certain types of attack on squares that were considered possible weak points, for example weak pawns, pinned pieces, and pieces defending other pieces. Moves which fell into these categories were also added to the plausible move list.

MacHack performed an alpha-beta search, with forward pruning. The plausible move generator would select a certain number of moves at each level of lookahead, and add to this number any moves which satisfied certain conditions: All safe checks were examined; at the first and second plies all captures were investigated; the moves of a certain number of distant pieces are examined, so that the program would not ignore most of the board if all of the moves of a single piece were highly plausible. The minimum number of moves selected by the plausible move generator was normally 6 at each level of lookahead, but in tournament mode, i.e., when playing at a rate of 2-3 minutes per move, the program would examine a minimum of 15 moves at the first two ply, 9 moves at the next two ply, and 7 moves at each subsequent level. Only when the minimum number did not exist (for example when one side was in check or had only its king on the board) would the search be narrower, though of course the alpha-beta algorithm would often prune away branches on which there were plausible moves.

One of the few advantages that mainframe programmers have over those writing for a micro, is the availability of enormous backing store. This enables a program to employ transposition tables, which are advantageous in preventing the program from evaluating the same position more than once. In chess, as in many other games, it is frequently possible to reach the same position by different routes, and we call this phenomenon transposition. As a simple example, if White makes move A, Black makes move B, and White then makes move C, we shall reach the same position as if White had made his moves A and C in the reverse order. MacHack produced a hash value for every position evaluated in the tree search, and together with this value the program stored the score for the position and a note of the depth of search at which the evaluation took place. If the position is created again during the search, the program would not recompute the score for the position but would take it from the value scored together with the hash for that position. Even though MacHack stored only 32,000 positions in hashed form, it was able to save considerable computation time, and as a side benefit, it was quickly able to detect draws by repetition.

The MacHack program represents the first really significant milestone after Shannon's paper, because it was the first

creative computing

(Please Print)

Name ______________________

Title ______________________

Address ______________________

City ______________________

State ______________ Zip ________

1. How many children live at home between ages 6 and 18?
☐ A. None ☐ D. Three
☐ B. One ☐ E. Four or more
☐ C. Two

2. How much money do you spend annually on Software
☐ A. Less than $50 ☐ D. $250-500
☐ B. $50-100 ☐ E. over $500
☐ C. $100-250

3. Your annual Income
☐ A. Under $10,000 ☐ D. $20-25,000
☐ B. $10-15,000 ☐ E. $30,000 or over
☐ C. $15-20,000

4. Which type of Printer do you own or operate
☐ A. Thermal ☐ E. Daisy wheel
☐ B. Dot-Matrix Impact ☐ F. Electrostatic
☐ C. Type ball printer ☐ G. At present do not own a printer
☐ D. Print thimble

Is it—
☐ A. Friction Feed ☐ B. Tractor Feed

101	102	103	104	105	251	252	253	254	255
106	107	108	109	110	256	257	258	259	260
111	112	113	114	115	261	262	263	264	265
116	117	118	119	120	266	267	268	269	270
121	122	123	124	125	271	272	273	274	275
126	127	128	129	130	276	277	278	279	280
131	132	133	134	135	281	282	283	284	285
136	137	138	139	140	286	287	288	289	290
141	142	143	144	145	291	292	293	294	295
146	147	148	149	150	296	297	298	299	300
151	152	153	154	155	301	302	303	304	305
156	157	158	159	160	306	307	308	309	310
161	162	163	164	165	311	312	313	311	315
166	167	168	169	170	316	317	318	319	320
171	172	173	174	175	321	322	323	324	325
176	177	178	179	180	326	327	328	329	330
181	182	183	184	185	331	332	333	334	335
186	187	188	189	190	336	337	338	339	340
191	192	193	194	195	341	342	343	344	345
196	197	198	199	200	346	347	348	349	350
201	202	203	204	205	351	352	353	354	355
206	207	208	209	210	356	357	358	359	360
211	212	213	214	215	361	362	363	364	365
216	217	218	219	220	366	367	368	369	370
221	222	223	224	225	371	372	373	374	375
226	227	228	229	230	376	377	378	379	380
231	232	233	234	235	381	382	383	384	385
236	237	238	239	240	386	387	388	389	390
241	242	243	244	245	391	392	393	394	395
246	247	248	249	250	396	397	398	399	400

December 1980 • Expires March 1, 1981

creative computing

(Please Print)

Name ______________________

Title ______________________

Address ______________________

City ______________________

State ______________ Zip ________

1. How many children live at home between ages 6 and 18?
☐ A. None ☐ D. Three
☐ B. One ☐ E. Four or more
☐ C. Two

2. How much money do you spend annually on Software
☐ A. Less than $50 ☐ D. $250-500
☐ B. $50-100 ☐ E. over $500
☐ C. $100-250

3. Your annual Income
☐ A. Under $10,000 ☐ D. $20-25,000
☐ B. $10-15,000 ☐ E. $30,000 or over
☐ C. $15-20,000

4. Which type of Printer do you own or operate
☐ A. Thermal ☐ E. Daisy wheel
☐ B. Dot-Matrix Impact ☐ F. Electrostatic
☐ C. Type ball printer ☐ G. At present do not own a printer
☐ D. Print thimble

Is it—
☐ A. Friction Feed ☐ B. Tractor Feed

101	102	103	104	105	251	252	253	254	255
106	107	108	109	110	256	257	258	259	260
111	112	113	114	115	261	262	263	264	265
116	117	118	119	120	266	267	268	269	270
121	122	123	124	125	271	272	273	274	275
126	127	128	129	130	276	277	278	279	280
131	132	133	134	135	281	282	283	284	285
136	137	138	139	140	286	287	288	289	290
141	142	143	144	145	291	292	293	294	295
146	147	148	149	150	296	297	298	299	300
151	152	153	154	155	301	302	303	304	305
156	157	158	159	160	306	307	308	309	31
161	162	163	164	165	311	312	313	314	31
166	167	168	169	170	316	317	318	319	32
171	172	173	174	175	321	322	323	324	32
176	177	178	179	180	326	327	328	329	33
181	182	183	184	185	331	332	333	334	33
186	187	188	189	190	336	337	338	339	34
191	192	193	194	195	341	342	343	344	34
196	197	198	199	200	346	347	348	349	35
201	202	203	204	205	351	352	353	354	35
206	207	208	209	210	356	357	358	359	36
211	212	213	214	215	361	362	363	364	36
216	217	218	219	220	366	367	368	369	37
221	222	223	224	225	371	372	373	374	37
226	227	228	229	230	376	377	378	379	38
231	232	233	234	235	381	382	383	384	38
236	237	238	239	240	386	387	388	389	39
241	242	243	244	245	391	392	393	394	39
246	247	248	249	250	396	397	398	399	40

BSCRIPTIONS TO CREATIVE COMPUTING ☐ New ☐ Renewal

Term	USA	Canada and Foreign surface	Foreign air
rs (36 issues)	☐ $40	☐ $67	☐ $130
rs (24 issues)	☐ 28	☐ 46	☐ 88
r (12 issues)	☐ 15	☐ 24	☐ 45

a change of address, please attach old label

DKS, POSTERS, RECORDS, GAMES

an.	Cat.	Title	List Price	Total
____	3G	Binary Dice	$1.25	____
____	5G	Computer Myth Posters	3.00	____
____	6A	Best of Creative Computing-Vol. 1	8.95	____
____	6B	Best of Creative Computing-Vol. 2	8.95	____
____	6C	Basic Computer Games	7.50	____
____	6C2	More Basic Computer Games	7.50	____
____	6C4	More Basic Games-TRS-80	7.95	____
____	6F	Best of Byte	11.95	____
____	6G	Colossal Computer Cartoon Book	4.95	____
____	6H	Be A Computer Literate	3.95	____
____	6Z	Computer Rage Game	8.95	____
____	9Y	Problems for Computer Solution Teacher's Edition	9.95	____
____	9Z	Problems for Computer Solution	4.95	____
____	10R	Computer Coin Games	3.95	____
____	12A	Katie and the Computer	6.95	____
____	12D	Computers in Mathematics-A Sourcebook of Ideas	15.95	____
____	12E	Impact of Computers on Society and Ethics: Bibliography	17.95	____
____	12C	Best of Creative Computing-Vol. 3	8.95	____
____	12B	Tales of the Marvelous Machine	7.95	____
____	12G	Computers for Kids-Apple	3.95	____
____	12H	Computers for Kids-TRS-80	3.95	____
____	12J	Computers for Kids-Atari	3.95	____
____	CR101	Computer Music Record	6.00	____
____	RWP	Word Processing Reprint	.50	____
____	RSS	Sorting & Shuffling Reprint	.50	____
			SUBTOTAL	____

SOFTWARE T-SHIRTS BACK ISSUES

Quan.	Cat.	Title	Price	Total

Books, Records, Games ________

$2 USA, $4 Foreign Shipping Charge ________

NJ residents add 5% sales tax ________

Magazine subscriptions ________

TOTAL ________

☐ Check or money order enclosed (U.S. funds only)

☐ VISA ☐ Master Charge ☐ American Express

____
Card number

________________ ________________
Expiration Date Signature

Name ______________________

Address ______________________

____

City ______________ State ______ Zip ______

Place Stamp Here

creative computing
P.O. Box 2976
Clinton, Iowa 52735

Place Stamp Here

creative computing
P.O. Box 789-M
Morristown, N.J. 07960

Place Stamp Here

creative computing
P.O. Box 2976
Clinton, Iowa 52735

A New Type of Game

Welcome to an astonishing new experience! **ADVENTURE** is one of the most challenging and innovative games available for your personal computer. This is not the average computer game in which you shoot at, chase, or get chased by something, master the game within an hour, and then lose interest. In fact, it may take you more than an hour to score at all, and will probably take days or weeks of playing to get a good score. (There is a provision for saving a game in progress).

The original computer version of Adventure was written by Willie Crowther and Don Woods in Fortran on a PDP-10 at MIT. In this version the player starts near a small wellhouse. Upon entering the house, he finds food, water, a set of keys and a lamp. Armed with only these items, he must set out to explore the countryside in search of treasure and other objects of play. He must also confront dwarfs, snakes, trolls, bears, dragons, birds, and other creatures during his quest. The game accepts one-or two-word commands such as GET LAMP* SOUTH* or KILL DWARF. Of course, if you don't have the proper tool to carry out an action, or if you do something foolish, you may find yourself in big trouble.

In playing the game you wander thru various 'rooms' (locations), manipulating the objects there to try to find 'treasures'. You may have to defeat an exotic wild animal to get one treasure, or figure out how to get another treasure out of a quicksand bog. You communicate thru two-word commands such as 'go west', 'climb tree', 'throw axe', 'look around'.

MISSION IMPOSSIBLE ADVENTURE (by Scott Adams) - Good Morning, Your mission is to... and so it starts. Will you be able to complete your mission in time? Or is the world's first automated nuclear reactor doomed? This one's well named, its hard, there is no magic but plenty of **suspense**. Good luck.....

THE COUNT (by Scott Adams) - You wake up in a large brass bed in a castle somewhere in Transylvania. Who are you, what are you doing here, and WHY did the postman deliver a bottle of blood? You'll love this Adventure, in fact, you might say it's LOVE AT FIRST BITE.....

ADVENTURELAND (by Scott Adams) - You wander through an enchanted world trying to recover the 13 lost treasures. You'll encounter WILD ANIMALS, MAGICAL BEINGS, and many other perils and puzzles. Can you rescue the BLUE OX from the quicksand? Or find your way out of the maze of pits? Happy Adventuring.....

VOODOO CASTLE (by Scott Adams) - Count Cristo has had a fiendish curse put on him by his enemies. There he lies, with you his only hope. Will you be able to rescue him or is he forever doomed? Beware the Voodoo Man.....

Adventure

For Apple, TRS-80, Sorcerer, PET, CP/M

ORIGINAL ADVENTURE (by Crowther, Woods, Manning and Roichel) - Somewhere nearby is a colossal cave where others have found fortunes in treasures and gold, but some who have entered have never been seen again. You start at a small brick building which is the wellhouse for a large spring. You must try to find your way into the underground caverns where you'll meet a giant clam, nasty little dwarves, and much more. **This Adventure is Bi-Lingual**—you may play in either **English or French**—a language learning tool beyond comparison. Runs in 32K CP/M system (48K required for SAVE GAME feature). Even includes SAM76 language in which to run the game. The troll says "Good Luck."

PIRATE ADVENTURE (by Scott Adams) - "Yo Ho Ho and a bottle of rum..." You'll meet up with the pirate and his daffy bird along with many strange sights as you attempt to go from your London flat to Treasure Island. Can you recover LONG JOHN SILVER's lost treasures? Happy sailing matey.....

sensational software

TRS-80 Level II (16K) Machine language cassettes for only $14.95 each
CS-3007 Adventureland
CS-3008 Pirate Adventure
CS-3009 Mission Impossible
CS-3010 Voodoo Castle
CS-3011 The Count

TRS-80 Disk (32K) Menu-driven machine language disks for only $39.95 each
CS-3516 Adventureland, Pirate Adventure and Mission Impossible
CS-3517 Voodoo Castle, The Count and Ghost Town

Atari
CS-7003 Haunted House (16K Basic cassette, only $11.95)
CS-7502 Haunted House and 4 Outdoor Games (32K disk, $24.95)

Apple II (32K) Machine language cassettes for only $14.95 each
CS-4011 Adventureland
CS-4012 Pirate Adventure
CS-4013 Mission Impossible
CS-4014 Voodoo Castle
CS-4005 Haunted House (In Basic, only $11.95)

Apple II Disk (48K) Menu-driven machine language disks for only $39.95 each
CS-4513 Adventureland, Pirate Adventure and Mission Impossible
CS-4514 Voodoo Castle, The Count and Ghost Town
CS-4504 Haunted House and 4 Outdoor Games (only $24.95)

Pet (24K) Basic cassette
CS-1009 Adventureland and Pirate Adventure, only $19.95

Sorcerer (16K) Machine language cassettes for only $14.95 each
CS-5003 Adventureland
CS-5004 Pirate Adventure
CS-5005 Mission Impossible
CS-5006 Voodoo Castle
CS-5007 The Count

CP/M 8" Disk (48K) for only $24.95 each
CS-9003 Adventureland and Pirate Adventure (requires MBasic)
CS-9004 Original Adventure, bi-lingual with SAM76 language system.

Order directly from **Creative Computing Software** *Dept. AFGG, P.O. Box 789-M,* Morristown, NJ 07960. Send payment plus $1 shipping and handling. For faster service call in your bank card order to (800) 631-8112. In NJ call (201) 540-0445.

CIRCLE 300 ON READER SERVICE CARD

Games, cont'd...

program to make good use of the Shannon-B strategy. The strength of the program in 1967 was extremely impressive, and created considerable publicity for computer chess amongst the computing and chess fraternities. This publicity served as the impetus for many of the groups which started programming around 1967 or '68, for example the Slate/Atkin/Gorlen group at Northwestern University and Newborn at Columbia University. In fact, Greenblatt and his colleagues probably did as much for computer chess in 1967 as Shannon had done almost twenty years earlier.

I should like to offer you two examples of the playing strength of the Greenblatt program. The first is a position which was shown to several strong American chess players, including some Masters, and defeated a number of them.



This position is a win for Black, who has an extra knight for a pawn. But the task is to find a quick win. If White is allowed to survive he might conjure up counterplay based on the exposed position of the black king and the weakness of black's pawns on g6 and a7. How can Black force a quick win?

MacHack discovered the correct continuation:

1 . . . f8–f2+

For the program to play this move it must have been able to see 9-ply ahead, in the crucial variations.

2 f1–g1

The alternative was 2 e2–f2 g4–h2+ 3 f1–e2 (or 3 f1–g1 b4–e1+ 4 g1–h2 e1–f2, when Black is a rook ahead) 3... b4–b2+ 4 e2–d1 b2–b1+ 5 d1–e2 b8–b2 mate.

2 . . . f2–e2
3 g7–h8+ d8–c7
4 h8–f6 e2–e1+
5 Resigns

To show that a computer program is a good chess player, it is not enough to give an example of its tactical prowess. The very best programs are extremely adept at tactical combinations, but are often let down by their poor strategic understanding. So the proof of the whole pudding must lie in an examination of complete games. The following is the first game ever won by a computer program in a chess tournament. Its opponent was rated 1510 on the U.S.A. rating scale, equivalent to a weak club player. The game was played in the Massachusetts State Championship, 1967.

WHITE: MacHack VI
BLACK: Human

1 e2–e4 c7–c5
2 d2–d4 c5–d4
3 d1–d4

MacHack knew no openings at that time, and plays very much as many of today's commercially available machines. This type of opening is bad for White because it allows Black to bring out his pieces "free of charge," by using developing moves to harass the white queen.

3 . . . b8–c6
4 d4–d3 g8–f6
5 b1–c3 g7–g6
6 g1–f3 d7–d6
7 c1–f4 e7–e5

A dubious decision. The human was obviously worried about the possible advance of the white pawn from e4 to e5, but Black should have continued 7 . . . f8–g7, and if e4–e5, then f6–h5, attacking White's bishop.

8 f4–g3 a7–a6
9 e1–c1 b7–b5
10 a2–a4 f8–h6+ ?

An ineffective move that weakens an important central pawn. One gets the impression that the human felt he could take risks against MacHack.

11 c1–b1 b5–b4
12 d3–d6

Black, when making his 10th move, almost certainly overlooked the fact that on the d6 square, White's queen or rook will fork the two black knights on f6 and c6, thereby rendering harmless Black's threat to the white knight on c3.

12 . . . c8–d7
13 g3–f4 h6–g7
14 c3–d5 f6–e4
15 d5–c7+

Black may have overlooked this response, but in any event his position was hopeless.

15 . . . d8–c7
16 d6–c7 e4–c5
17 c7–d6 g7–f8
18 d6–d5 a8–c8
19 f3–e5 d7–e6
20 d5–c6+ !

MacHack spots a simple queen sacrifice that forces mate.

20 . . . c8–c6
21 d1–d8 mate

A Benchmark Chess Program

It is perhaps worth mentioning, in passing, the work performed by Jim Gillogly during the early 1970s on a program designed to serve as a benchmark for other chess programs. Gillogly's program, which he named TECH, had a very simple program structure which could easily be emulated by anyone using a small computer. Rather than perform strategic evaluation on all terminal nodes in the tree, the TECH program only took a close look at the nodes at the first level of look-ahead. It evaluated all these positions, sorted them into order, and only changed this order if a full width search revealed the forced win or loss of material for a root move. Programs with such a structure can play perfectly recognizable chess, and are tactically quite satisfactory, but they are hindered in their overall playing performance by a lack of strategic depth.

Those of you wishing to start writing chess programs for your own machines could do a lot worse than employ Gillogly's approach. Because strategic evaluation is only carried out on the (say) 30-40 root moves, the program can perform quick full-width search, using the alpha-beta algorithm, to detect forcing variations that affect the material status of the board. Such a program is relatively easy to write, and should perform at roughly the same level as a Chess Challenger, provided that your strategic evaluation function is well thought out.

Gillogly argued that to be of any real merit, a chess program must be able to play better than a TEACH type program, given the same amount of time, because the TECH program did not do anything clever. A really good programmer could probably write a TECH type program in little more than 2K of code (assembler), and I would not be surprised to see a program of that size playing better chess than some of the 8K and 16K cassette programs available to personal computer users today.

Deep or Shallow Search

Not entirely unconnected with the previous section is the question of how essential it is to search the game tree as deeply as possible. There are two distinct schools of thought on the subject; programmers usually prefer to search as deeply as possible, on the grounds that they are more likely to notice neat tactical possibilities; but a minority believe that shallow search, with more attention being devoted to each node, can lead to equally good play. Since human chess players look at a very small tree, this second approach is clearly endowed with some merit, but most chess programmers prefer the exhaustive search technique, possibly because of a lack of confidence in their own ability to create an advanced evaluation function that would be sufficiently sophisticated to perform drastic forward pruning.

Up to now almost all of the world's strongest programs have been the "brute force" type — searching enormous trees but performing relatively little sophisticated evaluation at the terminal nodes. The TECH program is possibly the supreme example of this genre, performing only a

material evaluation at the terminal nodes. We do not yet have sufficient experience with intelligent chess programs to be able to determine which approach is superior, but I hope that the following game, despite exhibiting rather passive play by Black, will convince the reader that brute force is not the only possible route to a master strength chess program. For those programming chess on a small computer, the intelligent approach offers much scope for original research, and I would like to hear from readers who have any interesting or fresh ideas on this subject.

This game was played in a computer tournament in Dortmund in 1975.

WHITE: Schach MV 5.6
BLACK: Fischer/Schneider

1	b1–c3	d7–d5
2	d2–d4	c8–g4
3	f2–f3	g4–f5
4	e2–e4	d5–e4
5	f3–e4	f5–d7
6	g1–f3	b8–c6
7	e4–e5	e7–e6
8	c1–g5	f8–e7
9	d1–d2	g7–g6
10	f1–d3	

So far Black has played rather passively, but White has developed its pieces on sensible squares. White's latest move is, in fact, a mistake, which should lose a pawn to 10 . . . c6–d4 11 g5–e7 d4–f3+ 12 g2–f3 g8–e7, but Black was unable to see this far.

10	. . .	b7–b6
11	g5–e7	g8–e7
12	e1–c1	e8–g8
13	d2–h6 !	

Immediately beginning an attack against the black king. The threat is f3–g5, followed by h6–h7 mate.

13	. . .	e7–f5
14	d3–f5	g6–f5
15	f3–g5	d8–g5+

Giving up the queen was the only way to prevent mate. If 15 . . . f8–e8 16 h6–h7+ g8–f8 17 h7–f7 mate.

16	h6–g5+	g8–h8
17	g2–g4	

A fine move, opening up other lines of attack to the black king.

17	. . .	f5–g4
18	g5–g4	f7–f5
19	g4–h4	f5–f4
20	c3–e4	

Here comes the other knight.

20	. . .	f4–f3
21	e4–g5	f8–f7

Again the only way to prevent mate on h7.

22	g5–f7+	h8–g8
23	h4–f6	f3–f2
24	f7–h6 mate	

It would be reasonable to deduce, having played over this game, that the program playing the white pieces had a very good idea of what it was doing; that it planned a king-side attack from early on and then executed this attack in a well planned manner. In fact, White did not employ any look-ahead whatsoever. All of its moves were found as a result of a one-ply search. Its king attack feature was obviously well designed, but there was no tree search — the planning was all implicit in the evaluation function. This should provide some idea of just how much *can* be achieved without a deep look-ahead, and I hope that it will encourage some of you to write intelligent programs rather than programs which perform brute force searches of large trees.

The Northwestern Program

To conclude this survey I shall give a brief description of the famous program, written at Northwestern University, by David Slate, Larry Atkin and (in the beginning) Keith Gorlen. This program has won most of the important computer chess tournaments of the 1970s, and the interested reader would do well to read a more detailed account of this program, which may be found in Peter Frey's outstanding book *Chess Skill in Man and Machine.*

The Northwestern University program, whose successive generations have been named CHESS 2.0, . . . CHESS 3.0, . . . CHESS 4.0, . . . CHESS 4.9 (the first digit represents a working generation, the second digit is a version within that generation), was born in 1968. When the first computer chess tournament took place in 1970, the program proved itself to be the strongest, and it maintained this reputation for most of the decade. Occasionally another program would win an event ahead of the Northwestern program, but such occurrences were the exception rather than the rule. At the time of writing, this program holds the title of World Computer Champion, which it took from the Russian KAISSA in 1977. The forthcoming World Championship contest in Linz, Austria (September 25th-29th, 1980) will probably be the toughest event in which the program has participated, and we may even see a new title holder.

Much of the program's power is due to its great speed. The programmers have devoted much effort to the speeding up of essential processes such as legal move generation, and to this end the program maintains a data base which includes, among other things, a list of every square attacked by each piece. This list is updated whenever a move is made in the game tree, and by updating it rather than recreating it, the programmers reduce the time taken to provide the attack and defense lists for the newly created position. The program also uses a hash table for transpositions, as described in the section on Greenblatt's work.

For some time, the Northwestern program employed a plausible move generator to restrict the number of nodes in the game tree, but various reasons prompted the programmers to change to a full width search. One of the prime reasons for doing so was the fact that they noticed certain moves, which appeared good when examined to a depth of (say) 5-ply, but which ranked too low at the root of the tree to be included in the first plausible move list. Chess masters are not faced with this problem because their plausible move generator is much more sophisticated and accurate, and I suspect that the chess programs of the future may return to the plausibility approach, unless brute force searching produces an electronic chess master within the next 2-3 years.

The program's evaluation function contains a number of terms which quantify the best known chess heuristics. Material is measured in such a way as to encourage the side that is ahead in material to exchange where possible, and to discourage the exchange of material if the program is losing. Another feature gives a bonus for attacking enemy pieces, and this bonus is enhanced when an enemy piece is doubly threatened.

Pawn structure is an important feature of the game of chess at higher levels of skill, and any program which aspires to master strength must understand the finer points of pawn structures. If your pawn formation is rotten your whole position is eventually liable to crack under pressure. This program considers doubled pawns (two or more pawns of the same color on one file); isolated pawns (pawns that cannot be supported by pawns of their own color); backward pawns (pawns which do have adjacent friendly pawns, but which are less far advanced than its neighbors); passed pawns (those which have no enemy pawn impeding their progress to the eight rank); and advanced pawns.

Knights, bishops, rooks and queens are given bonuses according to the values of the squares they attack, particularly if the squares are near the enemy king or the center of the board. Rooks are given bonuses for being situated on open files or on the seventh rank (a rook on the seventh rank usually poses a serious threat to enemy pawns which have not yet moved). The kings are discouraged from moving towards the center of the board, except in the endgame, and there is a safety feature which determines whether or not a king is well sheltered by its own pieces.

The tree searching routines employ all of the techniques that we have encountered in previous articles: the alpha-beta algorithm, with a "window," killer moves, etc. In fact the Northwestern program provides us with an excellent illustration of the power of all these neat tree searching tricks — it plays chess better than more than 99.5% of the world's chess playing population, and has even won some quick games against International Masters and Grandmasters. These outstanding results

have been achieved more through the effects of a cleverly programmed brute force search than as a result of the program's chess knowledge, which is still primitive. The success of the program shows good programming is even more important than an advanced knowledge of the game, when producing a program of the strength currently being exhibited by small computers. Certainly it will be necessary for a human chess expert to be involved in the programming of an electronic Grandmaster, but there is absolutely no reason why the readers of this column should not write a program that can play respectable chess.

To illustrate the prowess of the Northwestern program I shall offer you the following game, which was its first ever win over a human Grandmaster. The game was played at blitz speed, which requires each player to make all of his moves within five minutes. In fact the rules were slightly different for the two participants — Stean was playing in real time but the program was permitted a total of 5 minutes for CPU time and satellite transmission time, with no penalty for the time taken by its human operator to move the pieces.

WHITE: CHESS 4.6
BLACK: Stean

1	e2–e4	b7–b6
2	d2–d4	c8–b7
3	b1–c3	c7–c5
4	d4–c5	b6–c5
5	c1–e3	d7–d6
6	f1–b5+	b8–d7
7	g1–f3	e7–e6
8	e1–g1	a7–a6
9	b5–d7+	d8–d7
10	d1–d3	g8–e7
11	a1–d1	a8–d8
12	d3–c4	e7–g6
13	f1–e1	f8–e7
14	c4–b3	d7–c6
15	g1–h1	

It is peculiar moves such as this one which make it possible to recognize the play of a computer. A strong human player would never move his king onto a diagonal occupied by his opponent's queen and bishop, unless it was forced.

15	. . .	e8–g8
16	e3–g5	b7–a8
17	g5–e7	g6–e7
18	a2–a4	d8–b8
19	b3–a2	b8–b4
20	b2–b3	

If we sum up what has happened so far, it is clear that Black has a dominating position. His pawns control the center while White's e4 pawn attacks only one central square. Black's pieces are active, White's are passive. But the program has one important advantage — his opponent thinks that to all intents and purposes the game is over, and he tries to take the program's position by storm. This is exactly the opposite of the way one should play against a strong program — the tactical search will reveal tricks that the human misses, especially at this breakneck speed.

20	. . .	f7–f5 ?

A mistaken attempt to open up the diagonal to the white king.

21	f3–g5	f5–e4
22	c3–e4	f8–f2

This move appears, at first glance, to be very strong. If now 23 e4–f2, Black's queen immediately gives mate on g2. But the program had seen further in the crucial variation than its opponent.

23 d1–d6 !

When he saw this move Stean exclaimed "Bloody iron monster." The point is that Black's queen is needed to prevent d6–d8 mate, and the queen is attacked. If the queen moves to a square that protects d8, White can then capture the rook on f2. So White must win material.

23	. . .	c6–d6

The best try.

24	e4–d6	f2–g2

Threatening to move the rook to g5, c2 or e2, with check from the bishop on b7. Any of these moves would win for Black, but . . .

25 g5–e4

Blocking the crucial diagonal.

25	. . .	g2–g4
26	c2–c4	

Blocking off another line of attack.

26	. . .	e7–f5
27	h2–h3	

Stean had hoped for 27 d6–f5 e6–f5, when Black wins the other knight which is pinned against the white king. When the computer played h2–h3 Stean cried out "This computer is a genius."

27	. . .	f5–g3+
28	h1–h2	g4–e4
29	a2–f2 !	

Yet another tactical blow. Black had only expected 29 d6–e4 g3–e4, when he has sufficient material to make the program's task quite difficult. But this latest move, threatening mate by f2–f7+ and then f7–f8 mate, forces an even greater material advantage.

29	. . .	h7–h6
30	d6–e4	g3–e4
31	f2–f3	b4–b8
32	e1–e4	b8–f8
33	f3–g4	a8–e4
34	g4–e6+	g8–h8
35	e6–e4	f8–f6
36	e4–e5	f6–b6
37	e5–c5	b6–b3
38	c5–c8+	h8–h7
39	c8–a6	Black Resigns

There was once a time when leading experts in computer science would say that "Computers can't play chess." □

Bibliography:

Frey, Peter W.: *Chess Skill in Man and Machine.* Springer Verlag, 1977.

Gillogly, J.J.: *The Technology Chess Program.* Artificial Intelligence, vol. 3 (1972), pp. 145-163.

Greenblatt, Richard D., Eastlake, Donald E. III, and Crocker, Stephen D.: *The Greenblatt Chess Program.* Proc. Fall Joint Computer Conf. 1967, pp. 801-810.

Reviews

Steve Gray

1001 Things To Do With Your Personal Computer, by Mark Sawusch. TAB Books, Blue Ridge Summit, PA. 335 pages, paperback $7.95. 1980.

If you've run out of ideas on Basic programs to write for your computer, either for your own use or for sale, here are hundreds of ideas and dozens of programs.

In each of a dozen chapters, Sawusch comments on what kinds of programs could be written in each area, and then provides some programs.

For instance, in the chapter on Hobby Applications, he discusses briefly several program possibilities, such as random art patterns, design transformation, graphing functions, and then provides a program that creates crossword poetry by writing words horizontally and vertically.

Then he discusses two dozen hobby applications in a little more detail, including Morse code, animated films, astronomy, railroading, etc., and gives two programs, one for calculating the position of Venus, the other for composing music.

The other chapters are on applications in business, math, science, education, games, control, etc. The book includes about 75 programs, many of them quite short, such as seven multi-statement lines for calculating pulse rate (you hit any key for each beat), a dozen short matrix-manipulation programs, and several long programs: data-base management (8½ pages), Star Challenge game (15 pages), baseball (14½ pages).

The programs all seem to be in Microsoft Basic, and should be a good source of material for programmers who write games, or who like variety, or who have run out of ideas.

TRS-80 Basic, by Bob Albrecht, Don Inman and Ramon Zamora. John Wiley & Sons, Inc., New York. 358 pages, paperback $8.95. 1980.

This is one of the latest in Wiley's three dozen Self-Teaching Guides, which range from money management to flowcharting.

The three authors are editors of *Recreational Computing,* and Albrecht has co-authored three other Wiley Self-Teaching Guides: *Basic, Basic for Home Computers,* and *Atari Basic.*

The gimmick that makes this a self-teaching guide is the division of each chapter into frames. Each frame presents an idea or topic, and ends with questions. You cover the answers, which are just below the questions, and give your own answers before uncovering the authors' answers.

A dozen chapters cover the TRS-80, introduction, simple programs, FOR/NEXT loops, random numbers, Patterns and Games, Entering and Displaying Data, Strings, arrays, editing and debugging, and Graphics, Games and Programs for the Home.

Seven appendixes cover setting up the TRS-80, using the cassette recorder, arithmetic (scientific notation, rounding), error messages, print and graphics layout sheets, reserved words, and ASCII codes.

The book teaches Level II Basic slowly but surely, with many examples and questions. The style is conversational and the writing can easily be understood by a bright pre-teenager, for whom the book seems to have been written, with many little comments from a Kilroy-type character and with some slightly silly remarks here and there.

However, this book does give much help in learning TRS-80 Basic than Radio Shack's Level II manual, which is

actually a reference manual, and, with its many examples and questions, offers about as thorough a grounding as David Lien's excellent book, *Learning Level II.*

The Albrecht-Inman-Zamora book is available from Radio Shack, with a new cover and title, *TRS-80 Level II Basic,* for $9.95.

The S-100 Bus Handbook, by Dave Bursky. Hayden Book Company, Inc., Rochelle Park, NJ. 264 pages, paperback $12.95. 1980.

Although this large paperback contains a great deal of information about the S-100 bus and the boards designed to operate on that bus, the lean meat is concentrated in three chapters and 54 pages in the middle of the book.

These three chapters are on Input/Output Interfaces for the S-100 Bus, Peripheral Storage Devices for Microcomputer Systems, and Interfacing the Microcomputer to Real-World Applications.

The rest is either too compressed for most readers, or too sketchy to be useful, or filler.

The first five chapters are a mixture of too-fast and sketchy. The first chapter, an introduction, goes through the history of computers, what's in a computer, and what's a microprocessor, in 9½ pages, of which over 4½ pages are photos and drawings.

Chapter 2, on binary and Boolean, is all of six pages long. Chapter 3, on electronics and logic functions, squeezes transistors, ICs, gates and flip-flops into 16 pages, of which over 8 pages are photos and drawings, many of which add little to the text.

Chapter 4, on the basic S-100 bus, describes what each pin does, the use of control and signal lines, and has one page on how the CPU works. The chapter on memory, like Chapter 4, contains some good material, but also contains much filler, such as a page of pinouts for several processors.

The big filler is Appendix C, 90 pages of schematics of 31 commonly used S-100 bus boards. The chapter on trouble-shooting is mostly about error messages.

Those three chapters are pretty good, but $12.95 is a lot to pay for 54 good pages out of 264.

The Programmer's Book of Rules, by George Ledin Jr. & Victor Ledin. Lifetime Learning Publications, div. of Wadsworth Publishing Co., 10 Davis Dr., Belmont, CA 94002. 256 pages, paperback $7.95. 1979.

PBR, as the back cover nicknames this book, is a digest of 272 "essential" rules, grouped into 15 chapters. According to the publisher, it covers: knowing the client's needs and solving their problems, choosing the right language for their job, program layout and displaying program output, step-by-step program procedures, encoding and debugging procedures, evaluating the program's performance, and references to latest literature by leading authorities.

The 15 chapters are grouped into three parts. Part I, Do It For Your Client, consists of one chapter, on Know your clients' needs, and includes rules such as "aim your program at the widest circle of users," sub-rules such as "write as general a program as possible," and sub-sub-rules such as "avoid writing programs that serve only single needs or solve single problems."

Part II, Do It With Style, has four chapters, on Solve the problem, Know your programming language, Make your program layout readable, and Make your output meaningful and useful.

Part III, Do It With Substance, has ten chapters, on Proceed step by step, Use decision and repetition structures, Split your program into subprograms, Be careful with variables and expressions, Avoid indiscriminate jumps, Code and debug your program, Test and edit your program, Utilize software tools, Evaluate your program's performance, and Annotate and document your program.

Examples of programming in Basic, Fortran and Cobol, plus many references and a lengthy bibliography make this a highly useful text for any programmer, even if he remembers only a tenth of the rules.

The Computer Age: A Twenty-Year View, edited by Michael L. Dertouzos and Joel Moses. MIT Press, Cambridge, MA. 507 pages, hardcover $25. 1979.

This look into the next 20 years of computer development and the potential impact consists of contributions by 20 computer authorities such as Terry Winograd, who wrote about "convivial computing," Seymour Papert (computers and learning), J.C.R. Licklider (computers and government), Daniel Bell (the social framework of the information society), Roger Noll (regulation and computer services), Robert Noyce (hardware prospects and limitations), Alan Perlis (current research frontiers in computer science), Joseph Weizenbaum (the computer revolution), etc.

"Written for the serious layperson as well as for the professional," the book is divided into five parts: Prospects for the Individual (Winograd, Papert, Licklider, etc.), *Trends in* Traditional Computer Uses (business and scientific), Socioeconomic Effects and Expectations (Bell, Noll, etc.), Trends in the Underlying Technologies (Noyce, Perlis, etc.), and Critiques (Weizenbaum and two replies to his piece).

The book starts with The Computer in The Home, by one of the editors, Moses, who presents current and future glimpses of home computing, and discusses the issues of privacy and government regulation. Computer art is discussed in The Return of the Sunday Painter.

Authors discuss automation, conferences, learning, information services, modelling, economics, sophisticated software, and a dozen other subjects in a language easily understood by anybody interested in getting a wide perspective on the world of computing. This is the best general book I've seen so far on the subject.

The Most Popular Subroutines in Basic, by Ken Tracton. Tab Books, Blue Ridge Summit, PA. 182 pages, paperback $5.95. 1980.

The front cover calls this "A programmer's manual to the most useful and versatile Basic subroutines and how to use them." Most useful, perhaps, to someone working for the National Bureau of Standards, but not for the average computer user, either mainframe or personal.

How often does the average person, or even most specialists, need to compute the future value of an annuity, convert from fluid ounces to milliliters, convert from radians to grads, calculate series capacitance, calculate the rectangular moment of inertia, add vectors, or plot the trajectory of a projectile?

This is a book to put on your reference shelf, for the rare moment when you might need one of these subroutines. However, most of us might need the book only once a year at the most, and most of the subroutines are so simple that they can be worked up on the spot from memory.

For instance, there are 57 pages of conversion routines, every one based on a single programming line, such as LET J=2055*B or LET L=3.785*G. The chapter is padded out with lengthy test runs, but could be condensed to two or three pages.

Some specialists may find a few of these subroutines useful, as in the mathematics or physics sections, but again, most of these are so simple that most of us could write the line or two of required programming from memory in less time than it takes to look them up in this book. All we need is the conversion factor or the formula, most of which in this book are very simple.

Weighting For Baudot and other problems for you and your computer, by F.D. Federighi and E.D. Reilly Jr. Avery Publishing Group Inc., 89 Baldwin Terrace, Wayne, NJ 07470. 249 pages, paperback $9.95. 1978.

The authors, who teach courses in computer science at the State University of New York at Albany, wrote this book of 240 problems to "allow students taking introductory computer courses to make their own choices from a wide problem selection," as well as for other reasons that include organizing a problem-solving seminar, and for solving "problems of interest just for fun on your microcomputer."

The problems are divided into 12 sections of increasingly difficult tasks, from a 1-point problem involving counting the number of parentheses in a text, to a 5-point problem that asks the reader to check a file for duplicate names and addresses, to a 20-point problem that requires "creating, maintaining, and interrogating a small single-thread relational database."

The book provides a great variety of problems, all language and computer independent, each described in detail and written quite simply, although the simplicity is relative, especially in problems involving higher math.

No solutions are provided; the preface ends with "May a happy camel bring you a bag of fortune cookies containing solutions for all your problems." The far-out (far-inside?) title is in the same vein.

"A goodly amount of cross-referencing between problems" is found. The authors "hope the student will enjoy exploring these byways and, as we did, learn something in the process."

The problems involve everything from baseball to Roman numerals, and are recommended to anybody looking for several hundred challenges.



Only Fiction . . . or is it?

Tales of the Marvelous Machine:

35 Stories of Computing

A robot friend. A computer God. Artificial intelligence challenging human intelligence in a life and death struggle. A detective solving a computer murder. Computers tricking people or people tricking people with computers. A computer with a soul. Or power. A lonely computer. Or one in love with its operator.

In thirty-five wonderful stories about computers, authors such as Frederick Pohl, Charles Mosmann, M.V. Mathews, Carol Cail, and George Chesbro depict a life in which computers affect the way people live, think, and relate to each other. Interested in what the effect of computer saturation might be? Only fiction can so wonderously dramatize future life.

The book is fun, and will provide wonderful hours of entertainment. For the reader interested in a structured approach to understanding the potential roles of the computer, or wanting quickly to locate stories that support or challenge his viewpoint, a multiple table of contents is provided. This lists the stories in fourteen different categories.

For example, a list of stories in which the computer takes on the attributes of a human separates them from those in which the computer is only an intelligent machine. The stories are categorized by whether they clarify, improve, or worsen the human lot. Stories in which the computers have capabilities available today are separated from those in which the capabilities could be available in the future. There is a listing of the wildly whimsical stories and those in which the computer is utilized in a unique fashion.

Can criminals be caught by computer? Does computer crime pay? Do computers fall in love? Are we all part of a larger organic computer? Here are 35 tantalizing tales that will open your eyes to a new perspective of computers.

Skillfully drawn illustrations augment the stories, giving glimpses of scenes as envisioned by 20 talented artists. This artwork adds another dimension to the text.

Tales of the Marvelous Machines: 35 Stories of Computing, edited by Robert Taylor and Burchenal Green, is a beautiful big 8½" × 11" softbound anthology of 272 pages. 12B

It is available for $7.95 plus $2.00 shipping and handling per order from Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. NJ residents add 5% sales tax. Visa, MasterCard and American Express orders are welcome. For faster service, call in your bank card order toll free to **800-631-8112** (in NJ call 201-540-0445). Or use the handy order form bound into this magazine.

creative computing press

CIRCLE 350 ON READER SERVICE CARD

Z-80 Microcomputer Design Projects, by William Barden Jr. Howard W. Sams & Co. Inc., Indianapolis, IN. 208 pages, paperback $12.95. 1980.

The title is slightly misleading, because the entire book is about the theory, construction and use of a Z-80-based computer called the EZ-80.

This may be the only book published in 1980 on how to build a computer, and as such should be of great interest to anybody (assuming there are still such people in these days of proliferating off-the-shelf personal computers) who wants to do so from scratch.

A complete set of parts to build the Z-80 "may be purchased for about $50," according to the preface. The EZ-80 consists of five parts: power supply, keyboard, microcomputer board, "applications area," and optional large-digit display. The applications area is for additional hardware such as a relay for the telephone-dialer project, or a resistor network, amplifier chip and speaker for the music-synthesizer project, etc.

The list of parts includes ten ICs, LED display, 14 sockets, a dozen resistors and capacitors, power-supply parts, slope-front chassis, and a 4-by-8-inch perfboard for constructing, via wire-wrapping, the EZ-80 microcomputer board.

Complete and detailed construction details are given, including wire-wrap lists, a chapter on programming the EPROM that tells how to build an EPROM programmer, and a diagnostic program to check out the EZ-80 when completed. Artwork is given for a PC board.

Even a beginner should have little trouble, what with six chapters on theory. Projects include a burglar alarm, timer, and frequency counter, in complete detail. This is a fine book for the do-it-yourselfer.

creative computing book service



Education & Self Teaching

Using BASIC In the Classroom

Donald D. Spencer. A teacher's guide that makes every phase of teaching computer programming more productive and enjoyable. It gives you fresh but proven ideas for presenting computer and programming topics, scheduling terminal time, purchasing a microcomputer or minicomputer, running the secondary school instructional computer facility, and giving assignments that arouse enthusiasm in your students. 224 pp. **$11.95** [10E]



Be A Computer Literate

Marion Ball & Sylvia Charp. This introductory book is extensively illustrated with full-color drawings, diagrams, and photos. Takes the reader through kinds of computers, how they work, input/output, and writing a simple program in BASIC. Aimed at ages 10-14 but beginners of all ages will find it informative. 62 pp. $3.95. [6H]



Problems For Computer Solution

Gruenberg & Jaffray. A collection of 92 problems in engineering, business, social science and mathematics. The problems are presented in depth and cover a wide range of difficulty. Oriented to Fortran but good for any language. A classic. 401 pp. $16.95 [7A].

Problems For Computer Solution

Steve Rogowski. The Student Edition is designed to encourage research and preliminary investigation on the part of the student. The problems are ordered by subject and can be expanded or shortened. Mathematical problems that have never been solved are also posed to challenge and sharpen the student's awareness. 98 pp. **$4.95** [9Z]. Also available is the Teacher's Edition which contains solutions, programs and analysis of the problems. 271 pp. $9.95 [9y]. Both books are highly recommended for any high school or college computer-oriented course.

Problem Solving With The Computer

Ted Sage. Used in conjunction with the traditional high school math curriculum, this book stresses problem analysis in algebra and geometry. This is the most widely adopted text in computer mathematics. 244 pp. **$8.95** [8J].

Sixty Challenging Problems with BASIC Solution

Donald Spencer. This book is a vehicle for computer programmers to measure their skills against some interesting problems that lend themselves to computer solution. It includes games, puzzles, mathematical recreations and science and business problems—some hard, some easy. The book will compliment any computer-oriented course in secondary school or college. BASIC program solutions included. 80 pp. $6.95 [9W].

Getting Started



An Introduction to Microcomputers, Vol 0 - The Beginners Book

Adam Osborne. Parts of a computer and a complete system; binary, octal and hexadecimal number systems; computer logic; addressing and other terminology are discussed in a language the absolute beginner can understand. Hundreds of illustrations and photographs. 220 pp. $7.95 [9T]

An Introduction to Microcomputers, Vol 1 - Basic Concepts

Adam Osborne. Thoroughly explains hardware and programming concepts common to all microprocessors: memory organization, instruction execution, interrupts, I/O, instruction sets and assembly programming. One of the best selling computer texts worldwide. 350 pp. $12.50 [9K]

Vol 2 - Some Real Microprocessors. Vol 3 - Real Support Devices

Adam Osborne. These volumes complement Volume 1. Vol. 2 discusses the operation of each of the following MPUS in detail: F8, SC/MP, 8080A, Z80, 6800, PPS-8, 2650, COS MAC, 9002, 6100 and seven others. Also information on selecting a micro. Vol. 3 discusses various support and I/O chips. 895 pp.
Vol. 2-(9L) $25.00
Vol. 3-(10Q) $15.00

Beginner's Guide To Microprocessors

Charles M. Gilmore. No background in electronics is necessary to understand this book. It was written for those with no prior knowledge whatsoever of microprocessors or personal computing. Gilmore takes you from what a microprocessor is, how it works and what it's used for to how they're programmed to perform desired functions in microwave ovens, TV games, calculators, etc. 175 pp. $5.95 [7U].

Microprocessors: From Chips to Systems

Rodnay Zaks. A complete and detailed introduction to microprocessors and microcomputer systems. Some of the topics presented are: a comparative evaluation of all major microprocessors, a journey inside a microprocessor chip, how to assemble a system, applications, interfacing (including the S-100 bus) and programming and system development. 416 pp. $9.95 [10S]

The First Book of Microcomputers

Robert Moody. Tells what personal computers are and what you can do with them in a light entertaining style. Starts with the basics and then covers the technical aspects such as how a personal computer is constructed and how it works. Includes such things as home protection, keeping track of budgets and bills, game playing, inventory management and tax calculations. 139 pp. $5.35 [10T]

Consumers Guide to Personal Computing and Microcomputers

Freiberger and Chew. Here are two valuable books in one: an introduction to the principles of microcomputers that assumes no previous knowledge on the reader's part, and a review of 64 microcomputer products from over 50 manufacturers. Also, extensive illustrations and best-buy tips for each type of microcomputer product. 176 pp. $8.60 [10U]

Getting Involved With Your Own Computer

Solomon and Viet. One of the first books on microcomputers that requires no previous knowledge of electronics or computer programming. Tells you where to find information, explains basic concepts and summarizes existing systems. Good place for the neophyte to begin. 216 pp. $5.95 [9N].

Games, Tricks and Puzzles For A Hand Calculator

Wally Judd. This book is a necessity for anyone who owns or intends to buy a hand calculator, from the most sophisticated (THE HP65,for example) to the basic "four banger." 110 pp. $4.95 [8D].

CIRCLE 350 ON READER SERVICE CARD

Learn with Computer Games

Basic Computer Games

David Ahl. Here are 101 classic games all in Microsoft Basic for your TRS-80, PET, Apple, Sorcerer, etc. Every one is complete with large legible listing, sample run, and descriptive notes. Has all the best games: Super Star Trek, Football, Blackjack, Lunar Lander, Tic Tac Toe, Nim, Life, Basketball, Boxing, Golf, Hockey, Craps, Roulette, Awari, Bagels, Mastermind, Hammurabi, Fur Trader, Splat and many, many more. Now in its 5th printing. 200 pp. $7.50. [6C]

Game Playing with BASIC

Donald D. Spencer. Enjoy the challenge of competition with your personal computer. Amuse yourself with such computer games and puzzles as 3-D Tic-Tac-Toe, Roulette, Baccarat, and more. Includes rules of each game, how each game works, illustrations and the output produced by each program. The last chapter contains 26 games for reader solution. 176 pp. $8.60 [10D]

Chess and Computers

David Levy. This book is loaded with chess games—computer versus computer and computer versus human. Settle down with this book, set up your chess board, and play the games. As with any good chess book, half the enjoyment is found in playing along, duplicating the moves and reading the authors comments. 145 pp. **$9.95** [10C]



What to Do After You Hit Return

Another collection of games and simulations—all in BASIC—including number guessing games, word games, hide-and-seek games, pattern games, board games, business *and social science* simulations and science fiction games. Large format. 158 pp. **$10.95** [8A].

Fun With Computers and Basic

Donald D. Spencer. Mathematical recreations and games are an excellent medium for teaching computer programming. The reader learns the BASIC programming language during the process of learning to program fun type problems. The book introduces the reader to flowcharting, and the BASIC programming language. Includes many BASIC programs, cartoons, and drawings. Written specifically for use by junior high school students. 96 pp. **$7.95** [10F]

Fun & Games With the Computer

Ted Sage. "This book is designed as a text for a one-semester course in computer programming using the BASIC language. The programs used as illustrations and exercises are games rather than mathematical algorithms, in order to make the book appealing and accessible to more students. The text is well written, with many excellent sample programs. Highly recommended."—*The Mathematics Teacher.* 351 pp. **$8.95** [8B].

Game Playing With Computers (Revised 2nd Edition)

Donald D. Spencer. Now you can sharpen programming skills through a relaxed and radically different approach. Including 70 games, puzzles, and mathematical recreations for a digital computer. It's fully illustrated and includes more than 25 game-playing programs in FORTRAN or BASIC, complete with descriptions, flowcharts, and output. Brand-new "how to" information for applying mathematical concepts to game playing with a computer. 320 pp. $18.30 [10G]

Other Games & Activities

The Way To Play

The newest, most comprehensive encyclopedia of games in the world. Complete rules for over 2000 games and indoor pastimes including race board games, strategic board games, tile games, card games, solitaire games, dice games, table games, casino and gambling games, games of chance and many more. Over 5000 drawings and diagrams in color. The perfect sourcebook for the computer game author. 320 pp. $7.95. [10H]

The i Hate Mathematics Book

Marilyn Burns. This book is for nonbelievers of all ages, but especially for kids who are convinced that mathematics is (1) impossible, (2) only for smart kids, and (3) no fun anyhow. This book shows that mathematics is nothing more (nor less) than a way of looking at the world and is not to be confused with arithmetic. In this book you'll find several hundred mathematical events, gags, magic tricks, and experiments to prove it. 128 pp. $4.95 [11F]



Toybook

Steven Caney. "More than 50 toys and projects have been chosen with imagination and care to provide a high ratio of satisfaction and fun in return for effort invested." —*Parents' Magazine.* It is "... a must for kids and anybody else interested in conjuring up delightful playthings out of odds and ends and scraps of stuff around the house." —*Whole Earth Epilog.* Packed with illustrations, photos, and step-by-step instructions. 176 pp. $3.95 [10J]

Star Games

Razzi, Brightfield and Looney. For *Star Trek* and *Star Wars* fans, here's a book that invites you to "join the Space Force for the greatest galactic battle of your life!" A game book, not a puzzle book, it challenges you to crack space-age binary codes and help your friends escape from the krakon's clutches. $6.95. [10K]



Cross-Sums

Maltby & Fulbrook. The answers are numbers! Vertical columns must total the same as horizontal rows. It's a new puzzle game — constructed by Richard Maltby, Jr., master puzzle-maker for *Harper's* and *New York* Magazines. 30 puzzles including Nursery Rhymes, Children's Hour, Golf, Movies, Famous Dates, and more. 108 pp. $1.95 [10L]

Geometric Cross-Sums

Maltby & Fulbrook. Another puzzle game. This one has 30 puzzles ranging in difficulty from easy to fiendish. Each diagram takes a special shape — Triangles Fun, The Magic Hexagon, Shapes Within Shapes, Literature in 3-D., and more! 108 pp. $1.95 [10M]

Merlin's Puzzlers

Charles Barry Townsend. "Puzzle books are nothing new, and neither are the puzzles in them. But what sets *Merlin's Puzzlers* apart from the crowd is the style and imagination with which the material is presented. In Volume 1 he calls upon Sherlock Holmes to pose the problems to Watson, and the Mad Hatter and Humpty Dumpty (among others) to confuse and confound "Alice in Puzzleland." Richly illustrated with old woodcuts, lithos, prints, and playbills — *Games Magazine.* Each volume 128 pp. large format. Two-volume set $7.50. [10P]

To Order

Use the bound-in order form or send your check for books plus $2.00 shipping and handling per order (Foreign: $1.25 per book) to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. NJ residents add 5% sales tax. Visa or MasterCharge are acceptable also. For faster service, call in your bank card order toll free to:

800-631-8112

(in NJ call 201 540-0445)

creative computing book service

Programming in BASIC

BASIC and the Personal Computer

Dwyer and *Critchfield*. This book will get you involved with personal computing, writing programs and expanding the use of your computer by showing the great diversity of applications possible on any microcomputer. One of the most comprehensive presentations of BASIC ever. As a text or addition to your personal library, this book will tell you all you ever wanted to know about BASIC. 350 pp. $12.95 [9F].

BASIC Programming, 2nd Edition

Kemeny & Kurtz. An introduction to computer programming through the language of BASIC. The authors include in-depth discussions of many applications including files and text processing. 150 pp. $11.95 [7E]

A Guided Tour of Computer Programming In BASIC

Dwyer and Kaufman. This book tops all introductory texts on BASIC. Filled with detail and examples, it includes sample programs for many simulations, several games, reservations systems and payroll. Aimed at the novice, but of value to everyone. 156 pp. $6.15 [8L].



Basic For Home Computers

Albrecht, Finkel, & Brown. This book shows you how to read, write, and understand the BASIC programming language used in the new personal-size microcomputers. Includes detailed descriptions of everything you need to know to make your computer work for you—includes how to get started, numerous applications and games, lists of resources, much more. 332 pp. $6.95 [7G]

To Order

Use the bound-in order form or send your check for books plus $2.00 shipping and handling per order (Foreign: $1.25 per book) to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. NJ residents add 5% sales tax. Visa or MasterCharge are acceptable also. For faster service, call in your bank card order toll free to:

800-631-8112

(in NJ call 201 540-0445)

Programming in Other Languages

Programming in PASCAL

Peter Grogono. This book is an excellent introduction to one of the fastest growing programming languages today. The text is arranged as a tutorial containing both examples and exercises to increase reader proficiency in PASCAL. Contains sections on procedures, files, and dynamic data structures such as trees and linked lists. 359 pp. $11.50 [10A]

PASCAL User Manual and Report (2nd Edition)

Jensen & Wirth. This book consists of two parts: the User Manual and the Revised Report. The Manual is directed to those who have some familiarity with computer programming and who wish to get acquainted with the PASCAL language. The Report is a concise reference for both programmers and implementors. It defines Standard PASCAL, which constitutes a common base between various implementations of the language. $7.90 [10B]

A Fortran Coloring Book

Dr. Roger Kaufman. This book is one of the most entertaining computer programming books around. Learn computer programming the "painfully funny way." Filled with examples and illustrations plus a light sprinkling of jokes. Guaranteed to teach you FORTRAN. 273 pp. $6.95 [4D]

A Simplified Guide to Fortran Programming

Daniel McCracken. A thorough first text in Fortran. Covers all basic statements and quickly gets into case studies ranging from simple (printing columns) to challenging (craps games simulation). 278 pp. $15.50 [7F].

Problem Analysis and Programming Style

How to Solve Problems

Wayne Wickelgren. This helpful book analyzes and systematizes some of the basic methods of solving mathematical problems. Illustrative examples include chess problems, logical puzzles, railroad switching problems and ones from science and engineering. For each, the author provides hints for the reader to tackle the problem and then a complete solution is given. Want to solve a complex problem with a computer? Begin here. 262 pp $8.00 [7Y].

The Thinking Computer: Mind Inside Matter

Bertram Raphael. Artificial intelligence, or AI, is the branch of computer science concerned with making computers "smarter." With a minimum of technical jargon, this book discusses the capabilities of modern digital computers and how they are being used in contemporary AI research. Discusses the progress of AI, the goals, and the variety of current approaches to making the computer more intelligent. $9.95 [7X]

The Little Book of BASIC Style: How To Write a Program You Can Read

John M. Nevison. Learn how to write better, easy-to-follow programs with Nevison's rules of style and turn out legible, correct programs. Two hours of BASIC programming is all that is necessary to profit by this book. Concepts of problem-solving and structured programming are included. 160 pp. $5.95 [9V].

The Art of Computer Programming

Donald Knuth. The purpose of this series is to provide a unified, readable, and theoretically sound summary of the present knowledge concerning computer programming techniques, along with their historical development. For the sake of clarity, many carefully checked computer procedures are expressed both in formal and informal language. A classic series. Vol. 1: Fundamental Algorithms, 634 pp. $23.50 [7R]. Vol. 2: Seminumerical Algorithms, 624 pp. $23.50 [7S]. Vol. 3: Sorting and Searching. 722 pp. $23.50 [7T]

CIRCLE 350 ON READER SERVICE CARD

creative computing book service

Business Applications

Accounts Payable and Accounts Receivable

Poole & Borchers. Includes program listings with remarks, descriptions, discussion of the principles behind each program, file layouts, and complete step-by-step instructions. Covers accounts payable and receivable in regard to invoice aging, general ledger, progress billing, partial invoice payments, and more. 375 pp. $20.00 [10V]

Payroll with Cost Accounting in BASIC

Lon Poole. Includes program listings with remarks, descriptions, discussion of the principles of each program, file layouts, and a complete user's manual with step-by-step instructions, flow charts and sample reports with CRT displays. 356 pp. $20.00 [10W]

How to Profit From Your Personal Computer: Professional, Business and Home Applications

T.G. Lewis. Put your computer to work for you. This new guide describes the use of personal computers in common business applications, including terms, notations, and techniques used by programmers. 256 pp. $9.65 [10X]

Small Computer Systems For Business

Gerald A. Silver. Useful for operators, programmers, teachers, students, etc., this book explores the world of small computers: what they are, how they are used, their internal structure, and our means of communicating with them. Describes assemblers, interpreters, and compilers, as well as operating systems and small computer applications. 254 pp $12.95 [10Y]

Some Common BASIC Programs

Poole & Borchers. This book combines a diversity of practical algorithms in one book : matrix multiplication, regression analysis, principal on a loan, integration by Simpson's rule, roots of equations, chi-square test, and many more. All the programs are written in a restricted BASIC suitable for most microcomputer BASIC packages, and have been tested and debugged by the authors. $12.50 [7M]

BASIC With Business Applications

Richard W. Lott. This book focuses on the BASIC language and its application to specific business problems. Part one introduces the BASIC language and the concept of logical flowcharting. Part two presents problems and possible solutions. Topics include: interest rate calculations, break-even analysis, loan rates, and depreciation. This book is a great aid to the beginner wanting to learn BASIC without having a technical or scientific background. 284 pp. $11.95 [10Z]



Computing Milieu

PCC's Reference Book of Personal and Home Computing

Ever try to find the address of a manufacturer of a cassette interface that a friend told you about 2 weeks ago? Frustrating isn't it? This book will go a long way toward ending that frustration with its comprehensive list of manufacturers, stores and products. Also contains survey articles on software, hardware, kits and applications as well as an index of articles from various hobbyist magazines. Several bibliographies, too. $5.95 [7P].

The Best of Byte, Vol 1

Helmers & Ahl. Contains the majority of material from the first 12 issues of *Byte* magazine. The 146 pages devoted to hardware are crammed full of how-to articles on everything from TV displays to joysticks to cassette interfaces and computer kits. Also 125 pages of software and applications ranging from on-line debuggers to games to a small business accounting system. A section on theory examines the how and why behind the circuits and programs. 386 pp. $11.95 [6F].

The Home Computer Revolution

Ted Nelson. Here is one of the most controversial books on home computers. Nelson takes a look at how the "dinky" computers got here, where they are where they're going and what will become of the big boys like IBM. This thought-provoking and highly opinionated book picks up where *Computer Lib/Dream Machine* left off. 224 pp. $2.00 [9U].

Space and Science Fiction

Star Wars Album

The incredible behind-the-scenes story of the most extraordinary motion picture of our time including over a hundred exclusive photos, special effects secrets, interviews with George Lucas, Carrie Fisher and Mark Hamill, the Anatomy of an Android and a technical glossary. Lots of color. 76 pp. $5.95. [11A]

Masterpieces of Science Fiction

This lavishly illustrated large format book has nine classic stories by Isaac Asimov, Gregory Benford, Ray Bradbury, Arthur C. Clarke, Harlan Ellison, Robert Heinlein, Frank Herbert, A.E. Van Vogt, and Kurt Vonnegut, Jr. Fabulous full color illustrations throughout. 108 pp. $7.95. [11B]



The Star Trek Star Fleet Technical Manual

Franz Joseph. This important resource book is packed with the data you need to create or modify STAR TREK computer games. It includes all Starship operating characteristics, defense and weapon systems, standard orbits, velocity/time relationship, space/war technology, Milky Way galaxy charts, Federation codes, etc., etc. A national best seller. Large format, vinyl binder. 180 pp. $7.95 [8C].

Star Wars Portfolio

Complete technical specifications and engineering drawings of ships, space stations, and 'droids of both The Imperial Empire and the rebels. A vital resource book. 180 pp. $7.95 [11C]

To Order

Use the bound-in order form or send your check for books plus $2.00 shipping and handling per order (Foreign: $1.25 per book) to Creative Computing, P.O. *Box 789-M*, Morristown, NJ 07960. NJ residents add 5% sales tax. Visa or MasterCharge are acceptable also. For faster service, call in your bank card order toll free to:

800-631-8112

(in NJ call 201 540-0445)

•Index to Advertisers•

Reader Service	Advertiser	Page
102	Aardvark Technical Services	75
104	ABM Products	173
101	Acorn Software	31
103	Acorn Software	121
107	Addmaster Corporation	170
210	Adwar Video	175
*	ALF	73
108	Allen Gelder	189
105	American Square Computers	161
121	Ampero Software	189
106	Apple Jack	205
109	ASAP	211
116	ASCII	217
110	Automated Simulations	40
123	Avant-Garde Creations	219
117	Barclay Bridge	132
111	Barton Enterprises	133
150	Banzai Software	103
112	Basics & Beyond	219
114	Beagle Brothers	219
115	Berliner Computer Center	161
*	Beta Computer Devices	161
129	Broderbund Software	109
119	C & S Electronics	217
131	CAP Electronics	21
118	Cavri Systems	68
113	CLOAD Magazine	59
*	Clone Software	109
159	CJM Industries	25
133	Compumart	139
134	Compuserve	12-13
139	CompuSoft Publishing	214
143	Computer City	215
126	Computer Corner of White Plains	161
127	Computer Design Labs	71
124	Computer Information Exchange	161,172,174
148	C.B.A.S.	174
145	Computers "R" Us	93
128	Computer Shopper	215
149	Computer Station	145
271	Computer Systems Design	205
160	Computer Systems International	164
125	Computerware	141
132	Computers Wholesale	125
138	Computronics	51
137	Computronics	198-199
155	Compututor	145
*	Connecticut Microcomputer	61,65,67 141,181
158	Continental Software	162
162	Cornsoft Grou:	143
161	Cottage Softw :	133
171	CPU Shop	79
130	Cromemco	1
173	Cyber-tech	103
122	Dakin5 Corporation	205
120	Dakin5 Corporation	81
178	Data Products Maintenance	161
179	Data Soft	33
180	Disc3/Mart	181
192	Discount Software Group	163
196	Dr. Daley Software	141
198	Dresden Associates	55
136	Dynacomp	147
153	Eaton Corporation	195
181	Eco-soft	211
206	Educational Programs	134
176	Edu-ware	211
164	Edu-ware	103
142	Electronic Specialists	145
208	Epson America	119
195	Esmark	110
270	Exatron	41
211	Farnsworth Computer Center	149
140	Frederick Computer Products	195
*	Galaxy	205
135	H & H Trading	195
197	Hard Hat Software	109
199	Hayden Book Company	213
213	Hayes Microcomputer Products	39
215	Highlands Computer Services	107
201	Bill Hindorff	174
144	Huntington Computing	135
217	Inmac	151
218	Innerglo	134
207	Integral Data Systems	9
141	Interactive Microware	214
209	Iridis	151
219	Krell Software	129
*	Lifeboat Associates	44-45
220	Marway Products	153
221	Med Systems Software	153
154	Micro Ap	115
222	Micro Architect	161
151	Microcomputer Technology, Inc.	149
156	Micro Lab	151
212	MicroLearningware	135
163	Micro Management Systems	193
229	Micro Power & Light	117
168	MicroSoft Consumer Products	15
165	Micro Systems Software	153
233	Microtrend International	105
157	Mini Micro Mart	166
234	Minnesota Software	93
224	Misosys	155
152	Monument Computer Service	155
191	Mountain Computer	16
226	Muse Software	23,77
227	Mytee Music	161
203	Nilonel	155
214	NRI Schools	69
172	Ohio Scientific	Cover 4
174	Omni Communications	157
166	Orion Software	136
167	Osborne/McGraw-Hill	91
169	Pacific Exchanges	57
204	Pacific Exchanges	142
237	Carl B. Page	161
238	PCD Systems	34
177	Percom Data	Cover 2
239	Peripherals Plus	99,123
240	Personal Computing	5
170	Personal Software	2
216	Personalized Computer Consultants	63
262	PGI Publishing	47
242	Pickles & Trout	157
228	Professional Data Systems	165
175	Program Store	87
230	Programma International	42
231	Quality Software	96
243	Quality Software	97
188	Racet Computes	157
244	Racet Computes	136
146	Radio Shack	7
147	Radio Shack	53
186	Radio Shack Sales Center	142
245	RCA	85
232	Real Computing	172
246	Realty Software	170
*	Retail Roster	177
247	S-100 Microsystems	89
235	Scholastic Magazines	174
223	Sebree's Computing	174
248	Shoe String Software	132
*	Sinclair Research Ltd.	111
236	Sirius Systems	167
182	Skyles Electric Works	63
249	Skyles Electric Works	65
194	Small Business Applications	101
250	Small Systems Software	168
251	SofTech Microsystems	37
252	Softronics	165
183	Software Exchange	Cover 3
185	Software Exchange	190-191
253	Software Technology for Computers	169
184	Southwestern Data Systems	169
189	Spectrum Software	169
254	Standard & Poor's	11
255	Stereo House	170
*	Strategem Cybernetics	174
256	Strategic Simulations	19
187	SubLOGIC	137
257	Sync	29
190	Synergistic Software	165
200	Syntonic Software	48
258	Tab Sales	172
259	Tarbell	171
202	Tarbell	173
260	Taso	201
261	Tele-terminals	171
205	Terrapin	173
241	T.H.E.S.I.S.	173
263	3-G Company	201
264	Tiny c	171
193	Total Information Service	65
*	United Software of America	112-113
265	University Microfilm	175
266	Vandata	175
267	Volcetek	175
268	Wessel Software	172
269	X-tra Soft	149

Creative Computing

300	Adventure	209
300	Air Traffic Controller	179
300	Atari Software	57
350	Back Issues	126-127
350	Best of Byte Closeout	83
350	Best of Creative Computing	216
350	Book Service	220-223
350	Computers for Kids	187
350	Computers In Mathematics	176
300	Economic & Ecology Simulations	131
350	Gaggle of Books	158-159
300	Investment Analysis	197
350	More Basic Computer Games	35
300	Space & Sports Games	207
300	Space War/Super Invasion	203
300	Strategy & Brain Games	55
350	Tales of Marvelous Machine	218
350	T-shirts	183

*Write Advertiser Directly

Puzzle Answers

The School Days Puzzle: In each case the letters in the series are the first letter of a series of words. In problem one we have *T*en, *N*ine, *E*ight, *S*even, *S*ix . . . the answer here would be *F*ive, *F*our, *T*hree, *T*wo, *O*ne. In problem two we have the days of the week backwards; *S*aturday, *F*riday, *T*hursday, *W*ednesday, *T*uesday, . . . the answer here would be *M*onday and *S*unday. In problem three we have the months of the year backwards and the answer would be: D,N,O,S,A,J,J,M,A,M,F,J.

The Rich Broth Puzzle: 400 of each.

A Repellent Problem: The answer is ten inches. The answer depends upon the fact that at all times the path of the pursuing bug is always perpendicular to the path of the pursued bug. Because of this the pursued bug never moves closer to, or farther away from the pursuing bug. The pursuing bug then has only to cover the ten inches that originally separated them. The path taken may be spiral, but, it is still only ten inches long.

The Fore And Aft Puzzle: The winning moves are:

1) 11-9	13) 9-7	25) 17-14	37) 6-3
2) 7-11	14) 14-9	26) 15-17	38) 9-6
3) 4-7	15) 16-14	27) 11-15	39) 12-9
4) 9-4	16) 10-16	28) 13-11	40) 10-12
5) 10-9	17) 8-10	29) 10-13	41) 8-10
6) 8-10	18) 5-8	30) 8-10	42) 9-8
7) 6-8	19) 7-5	31) 2-8	43) 14-19
8) 9-6	20) 3-7	32) 4-2	44) 11-14
9) 12-9	21) 1-3	33) 9-4	45) 7-11
10) 15-12	22) 4-1	34) 11-9	46) 9-1
11) 11-15	23) 9-4	35) 7-11	
12) 7-11		36) 3-7	

The Bell And The Durango Kid: When the Durango Kid started hauling on the rope he found himself going up in the air the same distance as the bell was going up. When the bell was four feet off the ground so was Durango. No matter how fast or how slow he hauled on the rope, he went up the same distance above the ground as the bell did on its side. They both arrived at the tower together, which after all is what the Reverend wanted.

Educator, Entertainer, Accountant.

Your Challenger Personal Computer.

Through the miracle of modern technology, a complete computer as powerful as the multimillion dollar room-sized computers of a few years ago can be put in a package the size of a typewriter and sells for as little as a color television set!

Through its years of microcomputer experience, Ohio Scientific has effectively channeled this tremendous computer power into a "friendly" computer with hundreds of personal uses, via a huge software library of programs for a broad range of personal, home, educational and business use.

This available software allows you to use and enjoy your computer without becoming an expert. The Challenger, however, is a powerful, general purpose computer which can be programmed in several languages by those who choose to.

Here are just a few of the popular uses of an Ohio Scientific Challenger Computer:

Education

The personal computer is the ultimate educational aid because it can entertain while it educates. Software available ranges from enhancing your children's basic math, reading and spelling ability, through tutoring high school and college subjects, to teaching the fundamentals of computers and computer programming.

Entertainment

Many of the Challenger's games educate while they entertain, from cartoons for preschoolers to games which sharpen mathematical and logical abilities. But, entertainment doesn't stop here. The Challenger's graphics capabilities and fast operation allow it to display action games with much more detail than the best video games, providing spectacular action in games such as Invaders, Space Wars, Tiger Tank and more! All popular sports such as golf, baseball and bowling are available as simulated computer games as well as many conventional games such as chess where the computer plays the role of a formidable opponent.

Accounting

Your Challenger computer can keep track of your checkbook, savings account, loans, expenses, monitor your calorie intake and your biorythms.

If you are involved in a business, you can use it to do word processing; accounting, inventory control, order processing, customer lists, client records, mailing labels and planning.

And more:

This may seem like a lot of uses, but it's only the tip of the iceberg for a general purpose computer. For example, your Challenger can be expanded to control lights and appliances, manage your energy usage and monitor for fire and break-ins. Furthermore, it can communicate with you, with other computers and the new personal computer information services over the telephone.

In fact, the uses of general purpose, personalized computers are expanding daily as more and more people discover the tremendous capabilities of these new technological wonders.

Ohio Scientific offers you four personalized computer systems starting at just $479.

For a free catalog and the name of the dealer nearest you, call 1-800-321-6850 toll free

OHIO SCIENTIFIC

1333 SOUTH CHILLICOTHE ROAD
AURORA, OH 44202 • (216) 831-5600

CIRCLE 172 ON READER SERVICE CARD