creative computing

the #1 magazine of computer applications and software

November 1981
vol 7, no 11
$2.50
140-44

Six Languages Which Are For You?

Getting Started With an Apple or TRS-80

Atari Color Explained

Evaluations:
- Bridge Challenger
- New Apple Games
- Crypto Machine
- Raster Blaster
- Soundchaser
- Air Combat

Sneak Preview of the Sinclair ZX81

Ted Nelson: Electronic Mail—What's Coming

Authoring Systems

IBM Personal Computer

The Big Blue Giant Makes Its Move

0 76956 14044 11

Commodore Software Encyclopedia

The COMMODORE SOFTWARE ENCYCLOPEDIA is now available from your authorized COMMODORE Dealer, for . . .

$4.95

The next edition of the COMMODORE SOFTWARE ENCYCLOPEDIA will be available in 90 to 120 days. If your software is not listed and you would like to have it listed in the next edition, please submit details to:

Software Department
Commodore Business Machines, Inc.
Computer Systems Division
300 Valley Forge Square, 681 Moore Road, King of Prussia, PA 19406.
HOTLINE Number
1-800-523-5622



commodore

CIRCLE 120 ON READER SERVICE CARD

Mountain Computer CPS MultiFunction Card™

The Only Interface Card You Need!

Connecting a Parallel Printer?

Epson® · Centronics® · IDS Paper Tiger® · CPS handles all these printers and others with on-board intelligence to provide paging and other features found on no other card.

Connecting a Serial Printer?

Diablo® Qume® NEC · TI 800 Series® CPS handles these printers and others with standard RS-232 interface providing selection of baud rates, handshakes, paging, and more.

Connecting a Modem or Terminal?

Hayes Smartmodem® Novation CAT® M & R Pennywhistle® CPS handles these and others with full/half duplex operation, baud rate selection, and even a transparent terminal mode which includes a dual mode feature that permits printing of text to parallel printers while 'on-line' eliminating the need for special terminal software—and more.

Connecting with the Time?

The on-board calendar/clock provides real time and date information including day of week, day, month, year, hours, minutes, and seconds for any application requiring a time stamp—battery backed-up for over two years!

Connecting with The Source?

Used with a modem, CPS provides the connection to information utilities, such as The Source® Dow Jones, and others. Additionally, CPS provides the connection to big-time electronic mail with programs such as Micro Courier® and Micro Telegram®, and other data transfer programs.

Connect with Easy Use!

CPS has no switches to set! All functions on the card are set from a user program. Menu driven screens set up your choice of all functions on CPS and store them on-board in CMOS RAM—battery backed-up (including the clock) for over two years! To change parameters, run the set-up program again—or use special commands from your keyboard. Furthermore, most existing software programs are immediately usable with CPS. *Phantom Slot Capability* permits assignment of CPS' functions to your software's pre-defined slots.

Connect with Your Apple® Dealer

Drop by your Apple dealer and see how the CPS MultiFunction Card provides the most comprehensive capabilities for RS-232C serial interface, parallel output, and real-time calendar/clock of any card available today—*all on one card*—at one low price—competitive with *any one* of the three or more single function cards that it replaces.

Mountain Computer
INCORPORATED

300 El Pueblo Road, Scotts Valley, CA 95066
(408) 438-6650 TWX: 910 598-4504

CIRCLE 191 ON READER SERVICE CARD

®Registered trademarks



THE FIRST SUPER-SIMPLE LETTER QUALITY WORD PROCESSOR IN THE WORLD THAT CAN SIT NEXT TO YOUR SECRETARY— FOR LESS THAN $5,000.

"Wordsworth™" removes the fear and loathing many people have about things called "computers" and "word processing." Because Wordsworth just sits at a desk and does what he's told. With unique new, simplified software, it can tell its typist what to do—step by simple step—to perform even the most complicated tasks.

It can not only "take a letter," but it can revise it, customize it in millions of ways (quite literally), personalize it, print it on your letterhead or business form so you can't tell it from hand-typed . . . in short, everything but put it in an envelope.

Moreover, it can perform all sorts of mundane business functions, like general ledgers and accounting reports, using easily available industry-compatible CP/M™ software.

Installation? Plug it in. (Cable supplied.)

Size? Bigger than a breadbox—but not by much. It's about half as big, or less, than systems that can't do half as much. Definitely desktop—a subcompact 20″ by 40″.

Service? Available everywhere.

Price? About $4,995. Complete and ready to go.

For the name of your nearest dealer—and a free hands-on demonstration—just pick up the nearest telephone.

TOLL-FREE 1-800-343-6833.

In Massachusetts, call collect (617) 828-8150. Telex 951-624.

LEADING EDGE.™

Leading Edge Products, Inc., 225 Turnpike Street, Canton, Massachusetts 02021

DEALERS: For immediate delivery from the Leading Edge Inventory Bank,™ on "Wordsworth" and other of the industry's most popular products, just give us a call.

CIRCLE 182 ON READER SERVICE CARD

in this issue...

evaluations & profiles

14 **The IBM Personal Computer** ..... *Staples*
The perfect computer?

20 **Soundchaser** ..... *Lubar*
Passport to great Apple sound

26 **Sinclair ZX81** ..... *Tebbutt*
New from England

34 **Authoring Systems** ..... *Lubar*
Apple programming made easy?

40 **Applesoft Compilers** ..... *Herman*
A comparative review

50 **Assembly Language Programming** ..... *Greene*
A course from Heath

54 **Home Financial Decisions** ..... *Rowe*
A new module for the TI 99/4

58 **Computer Air Combat** ..... *Archibald*
Monday night at the flights

62 **Raster Blaster** ..... *Archibald*
Flipping out

64 **Bridge Challenger** ..... *Linderholm*

68 **Crypto Machine** ..... *Miller*

77 **Apple/UCSD Pascal 1.1** ..... *Tonkens*
A user's evaluation

78 **Zgrass** ..... *Meeks*
A language for graphics users

89 **New Games for the Apple** ..... *Lubar*

articles

94 **Tower of Babel** ..... *Blank*
A tourist's guide to computer languages

106 **Boxes** ..... *Miller*
A structured spatial language

116 **Pascal, Ada and Computer Literacy** ..... *Ahl*
Interview with Arthur Luehrmann

124 **Three Roads to Pascal** ..... *Lubar*
Learning "the language of the future"

128 **The Magicians, The Snark & The Camel** ..... *Nelson*
Report on the Electronic Mail and Message Conference

158 **Basic and Pascal** ..... *Evans*
A side-by-side comparison

166 **Basic Beats Pascal** ..... *Ever*

174 **Trilingual Tutorial** ..... *Horn*
Basic, Basex, and Z80 Assembly Language

182 **Model I and Model II ROM Look Alikes** ..... *Cesaitas*

applications & software

184 **Periodic Table** ..... *Schmidt*

186 **Grammar** ..... *Rudeen*
A program to create your own

192 **PET Screen Line Length** ..... *Picciotto*
Solving the problems of a 40-character line

200 **Shared Appreciation Mortgage** ..... *Crawford*
Can it save you money?

210 **A World Generator for "Traveller"** ..... *Marvel*

232 **Building a Better Input** ..... *Ashwell*

236 **Short Programs** ..... *Buchanan & Shapiro*
TRS-80 keyboard repeat and Apple disk catalog

238 **How to Solve It** ..... *Piele*
Digital didactics

departments

6 **Notices** ..... *Fee*

10 **Input/Output** ..... *Readers*

24 **Dateline: Tomorrow** ..... *Ahl*
News and views

250 **Apple Cart** ..... *Carpenter*
Getting started: hardware, software, printers

258 **Outpost: Atari** ..... *Small & Small*
How the Atari handles color

262 **TRS-80 Strings** ..... *Gray*
Getting started, CRT filters, and a drunk snake

270 **Puzzles & Problems** ..... *Townsend*

272 **Software Legal Forum** ..... *Bayer*

276 **New Products** ..... *Staples*

288 **Index to Advertisers** .....

the cover

A rumor laid to rest: IBM has announced it's long-awaited entry into the personal computer market. See page 14 for details on the IBM Personal Computer.

NOVEMBER, 1981
VOLUME 7, NUMBER 11

MEMBER MTA

Creative Computing (ISSN 0097-8140) is published monthly by Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. Second Class postage paid at Lincoln, NE 68501.
Editorial offices located at 39 East Hanover Ave., Morris Plains, NJ 07950. Phone (201) 540-0445.
Domestic Subscriptions: 12 issues $20; 24 issues $37; 36 issues $53. Send subscription orders or change of address (P.O. Form 3575) to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. Call 800-631-8112 toll-free (in New Jersey call 201-540-0445) to order a subscription (to be charged only to a bank card).

Copyright ©1981 by Creative Computing. All rights reserved. Reproduction prohibited.

Printed in USA.
Creative Computing is printed by Mid-America Webpress, Lincoln, NE 68501.

staff

Publisher/Editor-in-Chief	David H. Ahl
Editorial Director	George Blank
Editor	Elizabeth Staples
Associate Editor	David Lubar
Managing Editor	Peter Fee
Contributing Editors	Dale Archibald Charles Carpenter Charles W. Dwyer Stephen B. Gray Glenn Hart Stephen Kimmel Harold Novick Peter Payack Alvin Toffler C. Barry Townsend Gregory Yob Karl Zinn
Editorial Assistant	Andrew Brill
Secretary	Elizabeth Magin
Production Manager	Laura MacKenzie
Art Director	Sue Gendzwil
Artists	Diana Negri Chris DeMilta Joanne Fogarty
Typesetters	Jean Ann Vokoun Maureen Welsh
Advertising Sales	Rick Burdett Renee Fox Christman Jeff Horchler Renea Cole
Marketing	Earl Lyon Laura Conboy
Creative Computing Press Managing Editor	Edward Stone
Software Development	William Kubeck Kerry Shetline Eric Wolcott Neil Radick
Software Production	Bill Rogalsky Rita Gerner Heather Everitt
Operations Manager	William L. Baumann
Personnel & Finance	Patricia Kennelly
Bookkeeping	Ethel Fisher
Retail Marketing	Jennifer Burr Laura Gibbons
Circulation	Frances Miskovich Dorothy Staples Moira Fenton Carol Vita Elsie Graff Brian Chamberlain Regina Jones Terri Murphy Sue Guppy
Office Assistants	Rosemary Bender Linda McCathern Diane Feller Mary McNeice
Order Processing	Jim Zecchin Ralph Loveys Gail Harris Linda Blank Mark Smith Karen Brown Susan DeMark
Shipping & Receiving	Ronald Antonaccio Scott McLeod Nick Ninni Mark Archambault Mike Gribbon

advertising sales

Advertising Coordinator
Renee Christman
Creative Computing
P.O. Box 789-M
Morristown, NJ 07960
(201) 540-0445

Western States
Jules E. Thompson, Inc.
1290 Howard Ave., Suite 303
Burlingame, CA 94010
(415) 348-8222
In Texas call (713) 731-2605

Southern California
Jules E. Thompson, Inc.
2560 Via Tejon
Palos Verdes Estates, CA 90274
(213) 378-8361

Mid-Atlantic, Northeast
CEL Associates, Inc.
27 Adams Street
Braintree, MA 02184
(617) 848-9306

Midwest
Ted Rickard
435 Locust Rd.
Wilmette, IL 60091
(312) 251-2541

New York Metropolitan Area
Nelson & Miller Associates, Inc.
55 Scenic Dr.
Hastings-on-Hudson, NY 10706
(914) 478-0491

Southeast
Paul McGinnis Co.
60 East 42nd St.
New York, NY 10017
(212) 490-1021

attention authors

Creative Computing will not be responsible for the return of unsolicited manuscripts, cassettes, floppy disks, program listings, etc. not submitted with a self-addressed, stamped envelope.

OK to reprint

Material in Creative Computing may be reprinted without permission by school and college publications, personal computing club newsletters, and nonprofit publications. Only original material may be reprinted; that is, you may not reprint a reprint. Also, each reprint must carry the following notice on the first page of the reprint in 7-point or larger type (you may cut out and use this notice if you wish):

Copyright © 1981 by Creative Computing, 39 E. Hanover Ave., Morris Plains, NJ 07950. Sample issue $2.50, 12-issue subscription $20.

Please send us two copies of any publication that carries reprinted material. Send to attention: David Ahl.

microform

Creative Computing is available on permanent record microfilm. For complete information contact University microfilms International, Dept. F.A., 300 North Zeeb Road, Ann Arbor, MI 48106 or 18 Bedford Road, London WC1R 4EJ, England.

foreign customers

Foreign subscribers in countries listed below may elect to subscribe with our local agents using local currency. Of course, subscriptions may also be entered directly to Creative Computing (USA) in U.S. dollars (bank draft or credit card). All foreign subscriptions must be prepaid.

Many foreign agents stock Creative Computing magazines, books, and software. However, please inquire directly to the agent before placing an order. Again, all Creative Computing products may be ordered direct from the USA—be sure to allow for foreign shipping and handling.

CANADA	Surface	Air
1-year	C $29	n/a
2-year	55	n/a
3-year	80	n/a

AUSTRALIA	$A	$A
1-year	28	52
2-year	54	101
3-year	78	150

ELECTRONIC CONCEPTS PTY., LTD
Attn: Rudi Hoess
Ground Floor 55 Clarence St.
Sydney, NSW 2000, Australia

ENGLAND	£	£
1-year	12 50	21 00
2-year	24 00	41 00
3-year	34 50	81.00

CREATIVE COMPUTING
Attn: Hazel Gordon
27 Andrew Close
Stoke Golding, Nuneaton CV12 6EL

FRANCE	F	F
1-year	120	201
2-year	229	395
3-year	332	588

SYBEX EUROPE
14/18 Rue Planchat
75020 Paris, France

GERMANY	dm	dm
1-year	52	86
2-year	98	168
3-year	141	250

HOFACKER-VERLAG
Ing. W. Hofacker
8 Munchen 75
Postfach 437, Weal Germany

HOLLAND, BELGIUM	f
1-year	119
2-year	231
3-year	332

2XF COMPUTERCOLLECTIEF
Attn: F. de Vreeze
Amstel 312A
1017 AP AMSTERDAM, Holland

ITALY	IL	IL
1-year	34,000	52,000
2-year	53,000	72,000
3-year	72,000	67,500

ADVEICO S.R.L.
Via Emilia Ovest, 129
43016 San Pancrazio (Parma) Italy
Attn: Guido Bertellini

JAPAN	Y	Y
1-year	8,900	11,800
2-year	13,300	23,100
3-year	19,300	34,400

ASCII PUBLISHING
Aoyama Building 5F
5-16-1 Minami Aoyama, Minato-Ku
Tokyo 107, Japan

PHILIPPINES	P	P
1-year	214	363
2-year	413	716
3-year	596	1059

INTEGRATED COMPUTER SYSTEMS, INC
Suite 205, Limketkai Bldg., Ortigas Ave.
Greenhills P.O. Box 463, San Juan
Metro Manila 3113, Philippines

SWEDEN	Kr	Kr
1-year	123	206
2-year	236	405
3-year	340	603

HOBBY DATA
Attn: Jan Nilsson
Box
S-200 12 Malmo 2, Sweden

OTHER COUNTRIES	US$	US$
1-year	29	50
2-year	55	97
3-year	88	145

CREATIVE COMPUTING
P.O. Box 789-M
Morristown, NJ 07960, USA

WE ARE MOVING TO LARGER QUARTERS!

Thank you . . .

. . . for making our expansion possible and for helping make us the leading distributor of microprocessor systems, terminals and printers.

We are showing our appreciation by producing a special catalog with thousands of items at greatly reduced prices. Call or write today.

Help us move our inventory before we have to move it.

MiniMicroMart, Inc.
943 W. Genesee St.
Syracuse, New York 13204
(315) 422-4467

CIRCLE 157 ON READER SERVICE CARD

tices...notices...notic

Math/Science Conference

Arizona State University is hosting the 10th Annual Math/Science Conference emphasizing the following areas: The microcomputer as a medium for instruction, as a tool for research and as an information manager. A variety of workshops and demonstrations will be offered as well as panel discussions and problem solving groups.

This two day conference will be held on the Arizona State University campus on January 15 and 16, 1982.

Vendors interested in securing a booth are invited to contact Dr. Gary Bitter of Arizona State University, 203 Payne, Tempe, Arizona 85287 or phone (602) 965-3322.

For further information or registration materials write to: Nancy Watson, 203 Payne Hall, Arizona State University, Tempe, AZ 85287.

Price Changes

An investigation, prompted by several reader complaints has revealed that when Atari lowered the price of the Atari 400, and increased the memory to 16K, they also made the Basic cartridge an optional extra at $60. This makes a significant difference in the comparative charts on pages 35 and 189 of our 1981 Buyer's Guide issue, and brings the price of the 16K Atari 400 with Basic to approximately $450.

The price quoted for the 16K Apple II Plus should have been $1330. The 32K machine is priced at $1430, and the 48K at $1530.

"We must beware of what I call 'inert ideas'—ideas that are merely received into the mind without being utilized, or tested, or thrown into fresh new combinations."

Alfred North Whitehead

Additional Information

The program MyChess, mentioned in the article, "Of Cabbages and Kings" (August, 1981), is also available for the H-89 and Z-89 computers. This version, with graphics, can be obtained from The Software Toolworks, 14478 Glorietta Dr., Sherman Oaks, CA 91423 (213-986-4885). The disk costs $34.95 plus $2 postage and handling (specify HDOS or CP/M).

The illustration on page 68 of the September 1981 *Creative Computing* was "Moon and Sun" from *Micro Painter*, and is copyright 1981, Datasoft, Inc.

Additional ordering information for the book *Understanding Computer Systems* from which "Explaining Computer Related Concepts and Terminology" was excerpted in the October issue of *Creative Computing* was received too late to appear with the article.

In the U.S., *Understanding Computer Systems* can be ordered from Computer Science Press, 11 Taft Court, Rockville, MD 20850. In England and Ireland, order from Chartwell-Bratt, Old Oxchard, Bickley, Bromley, England. In Scandinavia and for other information contact Firma Lawson, Gustav Adolfsgatan 9, 582 20 Linkoping.

Cybernetics Conference

A conference sponsored by the American Society for Cybernetics will be held at the Marvin Center, George Washington University, Washington D.C. from Thursday, October 29 to Sunday, November 1, 1981.

The theme of the conference will be a redefinition of the field of cybernetics—both its intellectual and practical content.

For further information contact Dr. Laurence D. Richards, Department of Administrative Science, Colby College, Waterville, ME 04901; (207) 873-1131.

Computer Game of the Year

From among the multitude of computer games available, gamers from all over the U.S. recently chose their favorite computer game, and the honor went to Automated Simulations, Inc. for its fantasy role-playing game, "Temple of Apshai."

Each year the Academy of Adventure Gaming Arts and Design, a group of hobby industry manufacturers, wholesalers, publishers and others, sponsors the "Charles Roberts" awards for excellence in game design. This is the first year the awards included a category for computer games.

Call for Papers

The Journal of Computer-Based Instruction is seeking papers on quality studies that deal with a variety of computer uses in health sciences education. The following areas are representative but not inclusive: innovative uses of the computer for education, studies that use the computer for stimulus presentation and data recording, integration of computer based education (CBE) into the curriculum, and models for utilizing CBE in the health sciences curriculum.

Papers from all health sciences are desired, including medicine, dentistry, nursing and allied health. It is expected that this issue will represent "state-of-the-art" research in computer-based education. Outlines of papers should be received by October 30, 1981.

For further information and guidelines for submission of outlines and papers contact: David P. Yens, Ph.D., Special Issue on Health Sciences Education Editor, JCBI, Mount Sinai School of Medicine, Annenberg Building 5-16, One Gustave L. Levy Place, New York, NY 10029.

"Thoughts are but dreams till their effects be tried."

Shakespeare

Turn your Apple into the world's most versatile personal computer.

The SoftCard™ Solution. SoftCard turns your Apple into two computers. A Z-80 and a 6502. By adding a Z-80 microprocessor and CP/M to your Apple, SoftCard turns your Apple into a CP/M based machine. That means you can access the single largest body of microcomputer software in existence. Two computers in one. And, the advantages of both.

Plug and go. The SoftCard system starts with a Z-80 based circuit card. Just plug it into any slot (except 0) of your Apple. No modifications required. SoftCard supports most of your Apple peripherals, and, in 6502-mode, your Apple is still your Apple.

CP/M for your Apple. You get CP/M on disk with the SoftCard package. It's a powerful and simple-to-use operating system. It supports more software than any other microcomputer operating system. And that's the key to the versatility of the SoftCard/Apple.

CIRCLE 168 ON READER SERVICE CARD

BASIC included. A powerful tool, BASIC-80 is included in the SoftCard package. Running under CP/M, ANSI Standard BASIC-80 is the most powerful microcomputer BASIC available. It includes extensive disk I/O statements, error trapping, integer variables, 16-digit precision, extensive EDIT commands and string functions, high and low-res Apple graphics, PRINT USING, CHAIN and COMMON, plus many additional commands. And, it's a BASIC you can compile with Microsoft's BASIC Compiler.

More languages. With SoftCard and CP/M, you can add Microsoft's ANSI Standard COBOL, and FORTRAN, or Basic Compiler and Assembly Language Development System. All, more powerful tools for your Apple.

Seeing is believing. See the SoftCard in operation at your Microsoft or Apple dealer. We think you'll agree that the SoftCard turns your Apple into the world's most versatile personal computer.

Complete information? It's at your dealer's now. Or, we'll send it to you and include a dealer list. Write us. Call us. Or, circle the reader service card number below.

SoftCard is a trademark of Microsoft. Apple II and Apple II Plus are registered trademarks of Apple Computer. Z-80 is a registered trademark of Zilog, Inc. CP/M is a registered trademark of Digital Research, Inc.

MICROSOFT
CONSUMER PRODUCTS

Microsoft Consumer Products, 400 108th Ave. N.E., Bellevue, WA 98004. (206) 454-1315

TWELVE STRONG HEATH/ZENITH YOUR

Pick a strong partner

A computer purchase is the beginning of a long term partnership between you and the people you buy from. Your ongoing need for software and accessories requires a partner who will stand by you with a growing line of products. And nowhere will you find a more complete line of hardware, software and accessories than at your Heathkit Electronic Center. Here are twelve strong reasons to make Heath/Zenith your partner.

1. The All-In-One Computer

The heart of the Heath/Zenith line is the stand-alone *89 Computer*. It's a complete system with built-in 5¼-inch floppy disk drive, professional keyboard and keypad, smart video terminal, two Z80 microprocessors, and two RS-232C serial I/O ports. It comes with 16K RAM, expandable to 64K.

2. Peripherals

These include the popular *Heath/Zenith 19 Smart Video Terminal*, loaded with professional features. And the *14 Line Printer*, priced as low as $495. Other printer brands are on display, including high-speed, typewriter-quality printers.

3. Software

Word processing, includes reliable, easy-to-use Zenith Electronic Typing and powerful, full-featured WORDSTAR.

Small Business Programs, feature General Ledger and Inventory Control.

HUG, Heath Users' Group, offers members a library of over 500 low-cost programs for home, work or play.

4. Programming Languages

For your own custom programs, Microsoft languages are available in BASIC (compiler and interpreter), FORTRAN and COBOL.

5. Operating Systems

Three versatile systems give you the capability to perform your specific tasks.

CP/M by Digital Research makes your system compatible with thousands of popular CP/M programs.

UCSD P-System with Pascal is a complete program development and execution environment.

HDOS, Heath Disk Operating System gives you a sophisticated, flexible environment for program construction, storage and editing.

6. Utility Software

Expand the performance range of your computer with a broad selection of utility tools, including the best of *Digital Research* and the complete line of innovative *Softstuff* products.

7. Disk Systems

The 8-inch Heath/Zenith 47 Dual Disk System adds over 2 megabytes of storage to your 89 Computer. Diskettes are standard IBM 3740 format, double-sided, double-density.

The 5¼-inch 87 Dual Disk System adds 200K bytes of storage to your 89. Both disk systems feature read/write protection and easy plug-in adaptability.

8. Self-Study Courses



Learn at your own pace with *Programming Courses* that teach you to write and run your own programs in Assembly, BASIC, Pascal or COBOL.

A course on *Computer Concepts for Small Business* gives you the understanding to evaluate the ways a computer can benefit your business.

Personal Computing is a complete introduction to the fundamentals for the novice. Every Heathkit/Zenith course is professionally designed for easy, step-by-step learning.

All Heath/Zenith Computer Products are available completely assembled and tested for commercial use. Or in easy-to-build, money-saving kits.

REASONS TO MAKE COMPUTER PARTNER

9. Expansion Options

Communicate with the outside world through a *Three-port EIA RS-232C Serial Interface*.

Expand RAM to 64K with easy-to-install *expansion chips*.

10. Accessories

Your Heathkit Electronic Center has the latest in modems, black-and-white and color video monitors, computer furniture and a full line of supplies, accessories, books and parts.

11. Service



No one stands by you like Heath/Zenith. We help you get your system up and running smoothly. Service is available from trained technicians, over the phone or at one of 56 Heathkit Electronic Centers.

12. Value

Your money buys you more because Heath/Zenith prices are among the industry's most competitive. Make your own comparison and find out how much you can save.

Complete, integrated computer hardware and software, designed to serve you and to grow with you – that's what to look for in a strong partner. And with Heath/Zenith you get it all under one roof.

All at your Heathkit Electronic Center

Pick the store nearest you from the list at right. And stop in today for a demonstration of the Heath/Zenith 89 Computer System. If you can't get to a store, send $1.00 for the latest Heathkit® Catalog and the new Zenith Data Systems Catalog of assembled commercial computers. Write to Heath Co., Dept. 355-834, Benton Harbor, MI 49022.

Visit Your Heathkit Electronic Center*

where Heath/Zenith Products are displayed, sold and serviced.

PHOENIX, AZ
2727 W. Indian School Rd.
602-279-6247

ANAHEIM, CA
330 E. Ball Rd.
714-776-9420

CAMPBELL, CA
2350 S. Bascom Ave
408-377-8920

EL CERRITO, CA
6000 Potrero Ave
415-236-8870

LA MESA, CA
8363 Center Dr.
714-461-0110

LOS ANGELES, CA
2309 S. Flower St.
213-749-0261

POMONA, CA
1555 N. Orange Grove Ave
714-623-3543

REDWOOD CITY, CA
2001 Middlefield Rd
415-365-8155

SACRAMENTO, CA
1860 Fulton Ave
916-485-1575

WOODLAND HILLS, CA
22504 Ventura Blvd.
213-883-0531

DENVER, CO
5940 W. 38th Ave.
303-422-3408

AVON, CT
395 W. Main St (Rt. 44)
203-678-0323

HIALEAH, FL
4705 W. 16th Ave
305-823-2280

PLANTATION, FL
7173 W. Broward Blvd.
305-791-7300

TAMPA, FL
4019 W. Hillsborough Ave.
813-886-2541

ATLANTA, GA
5285 Roswell Rd.
404-252-4341

CHICAGO, IL
3462-66 W. Devon Ave
312-583-3920

DOWNERS GROVE, IL
224 Ogden Ave.
312-852-1304

INDIANAPOLIS, IN
2112 E. 62nd St.
317-257-4321

MISSION, KS
5960 Lamar Ave.
913-362-4466

LOUISVILLE, KY
12401 Shelbyville Rd.
502-245-7811

KENNER, LA
1900 Veterans
Memorial Hwy.
504-467-6321

BALTIMORE, MD
1713 E. Joppa Rd.
301-661-4446

ROCKVILLE, MD
5542 Nicholson Lane
301-881-5420

PEABODY, MA
242 Andover St.
617-531-9330

WELLESLEY, MA
165 Worcester Ave.
617-237-1510

DETROIT, MI
18645 W. Eight Mile Rd.
313-535-6480

E. DETROIT, MI
18149 E. Eight Mile Rd.
313-772-0416

HOPKINS, MN
101 Shady Oak Rd.
612-938-8371

ST. PAUL, MN
1645 White Bear Ave.
612-778-1211

BRIDGETON, MO
3794 McKelvey Rd
314-291-1850

OMAHA, NE
9207 Maple St.
402-391-2071

ASBURY PARK, NJ
1013 State Hwy. 35
201-775-1231

FAIR LAWN, NJ
35-07 Broadway (Rt. 4)
201-791-6935

AMHERST, NY
3476 Sheridan Dr.
716-835-3090

JERICHO, L.I. NY
15 Jericho Turnpike
516-334-8181

ROCHESTER, NY
937 Jefferson Rd.
716-424-2560

N. WHITE PLAINS, NY
7 Reservoir Rd.
914-761-7690

CLEVELAND, OH
28100 Chagrin Blvd.
216-292-7553

COLUMBUS, OH
2500 Morse Rd.
614-475-7200

TOLEDO, OH
48 S. Byrne Rd.
419-537-1887

WOODLAWN, OH
10133 Springfield Pike
513-771-8650

OKLAHOMA CITY, OK
2727 Northwest
Expressway
405-848-7593

FRAZER, PA
630 Lancaster Pike
(Rt. 30)
215-647-5555

PHILADELPHIA, PA
6318 Roosevelt Blvd.
215-288-0180

PITTSBURGH, PA
3482 Wm. Penn Hwy.
412-824-3564

WARWICK, RI
558 Greenwich Ave.
401-738-5150

DALLAS, TX
2715 Ross Ave
214-826-4053

HOUSTON, TX
1704 W. Loop N.
713-869-5263

SAN ANTONIO, TX
7111 Blanco Road
512-341-8876

MIDVALE, UT
58 East 7200 South
801-566-4626

ALEXANDRIA, VA
6201 Richmond Hwy.
703-765-5515

VIRGINIA BEACH, VA
1055 Independence Blvd.
804-460-0997

SEATTLE, WA
505 8th Ave. N
206-682-2172

TUKWILA, WA
15439 53rd Ave. S.
206-246-5358

MILWAUKEE, WI
5215 W. Fond du Lac
414-873-8250

*Units of Veritechnology Electronics Corporation in the U.S.

Prices and specifications subject to change without notice.

HEATH/ZENITH

Your strong partner

SOFTWARE for the ATARI 800* and ATARI 400* from QUALITY SOFTWARE

STARBASE HYPERION™
By Don Ursem

Become absorbed in this intriguing, original space simulation of war in the far future. Use strategy to defend a front line Star Fortress against invasion forces of an alien empire. You create, deploy, and command a fleet of various classes of space ships, while managing limited resources including power generators, shields and probes. Real time responses are sometimes required to take advantage of special tactical opportunities. Use of color, sound, and special graphics add to the enjoyment of this program. At least 24K of RAM is required

On Cassette — $19.95 On Diskette — $22.95

NAME THAT SONG
By Jerry White



Here is great entertainment for everyone! Two players listen while the Atari starts playing a tune. As soon as a player thinks he knows the name of the song, he presses his assigned key or joystick button. There are two ways to play. The first way requires you to type in the name of the song. Optionally, you can play multiple choice, where the computer asks you to select the title from four possibilities. The standard version requires 24K of RAM (32K on diskette) and has over 150 songs on it. You also get a 16K version that has more than 85 songs. The instructions explain how you can add songs to the program, if you wish. Written in BASIC.

On Cassette — $14.95 On Diskette — $17.95

QS FORTH
By James Albanese

Want to go beyond BASIC? The remarkably efficient FORTH programming language may be just for you. We have taken the popular fig-FORTH model from the FORTH Interest Group and expanded it for use with the Atari Personal Computer. Best of all we have written substantial documentation, packaged in a three ring binder, that includes a tutorial introduction to FORTH and numerous examples. QS FORTH is a disk based system that requires at least 24K of RAM and at least one disk drive. Five modules that may be loaded separately from disk are the fig-FORTH kernel, extensions to standard fig-FORTH, an on-screen editor, an I/O module that accesses Atari's operating system, and a FORTH assembler.

Diskette and Manual — $79.95 Manual Only — $39.95

FOR OUR COMPLETE LINE OF ATARI SOFTWARE
PLEASE WRITE FOR OUR CATALOG

QS QUALITY SOFTWARE
6660 Reseda Blvd., Suite 105, Reseda, CA 91335
(213) 344-6599

ASK FOR QUALITY SOFTWARE products at your favorite computer store. If necessary you may order directly from us. MasterCard and Visa cardholders may place orders by calling us at (213) 344-6599. Or mail your check or bankcard number to the address above. California residents add 6% sales tax. *Shipping Charges:* Within North America orders must include $1.50 for shipping and handling. Outside North America the charge for airmail shipping and handling is $5.00. Pay in U.S. currency.

*Indicates trademarks of Atari.

..input/output..

Cerf's Up

Dear Editor:

We enjoyed your recent articles on computer Othello. We are concerned, however, that some of the square ranking recommendations contained in these articles may lead programmers astray. A recent informal survey of the best players and programmers in the United States Othello Association produced a virtually unanimous judgment: programs based upon the old idea of "square values" suffer from an inherent weakness which severely limits their potential. They may be quite effective against random play or against programs which maximize disc-count at each move, but they will be no match for programs based on more up-to-date strategies.

Today's best Othello players (be they human or machine) are not particularly concerned with occupying the so-called "good" squares. Rather they seek to gain control of the game by so restricting their opponent's flexibility (that is, their opponent's store of legal options at each turn) they can for all practical purposes dictate where their opponent must move. It is sometimes possible to engineer this type of advantage relatively early in the game, and properly handled, it can often be perpetuated until such time as the controlling player can begin to accumulate stable (permanently unflippable) discs.

Given the above, we believe that the strategy advice offered by Stephen Kimmel (which leans heavily on Goro Hasegawa's lamentable "How to Win at Othello") is extremely unreliable, and that the algorithm offered by David Levy could be improved in two ways.

First, "structural" factors (square rankings) should be all but eliminated, perhaps retaining only a slight positive value for unoccupied corners and negative values for the contiguous squares. Second, the computer should monitor the opposition's "mobility" as well as its own, striving to minimize the former and maximize the latter. This will insure that the program thinks offensively as well as defensively.

The quality of Othello programming is improving rapidly, and some excellent work has recently been done by Paul Rosenbloom, Charlie Heath, Dan and Kathe Spracklen, and Peter Frey and Larry Atkin, to name only a few. In order to stimulate further improvement, the United States Othello Association is currently organizing a 1982 computer Othello tournament; anyone interested in participating should write: USOA, P.O. Box 342, Falls Church, VA 22046.

Jonathan Cerf
World Othello Champion
George Sullivan
Editor, *Othello Quarterly*
Post Office Box 342
Falls Church, VA 22046

When it comes to microcomputer software we wrote the book.



How do you stay up-to-the-minute with the rapidly changing world of microcomputer software? Get the Lifeboat Catalog.

The Latest Innovations

The new Lifeboat Catalog is packed with the latest state-of-the-art software. And if we publish a new program after the latest catalog has gone to press, we enclose a flash bulletin in your copy.

The Greatest Selection

Because Lifeboat is the world's largest publisher of microcomputer software, our catalog offers you the greatest selection of programs for business, professional and personal use. Our more than 200 programs range from integrated accounting and professional practice systems to office tools for bookkeepers and secretaries to sophisticated tools for programmers. Included are business systems, word processors, programming languages, database management systems, application tools and advanced systems utilities.

We specialize in software that runs on most small business computers. Our more than 60 media formats, including floppy disks, data cartridges, magnetic tape and disk cartridges, support well over 100 computer brands of domestic and foreign manufacture.

Get Full Support

We give the crucial dimension of after-sales service and full support to everything we sell. That includes:

- A telephone hotline where technical and customer service representatives will answer your questions 11 hours a day.
- An update service for software and documentation.
- Telephone, telex and mail-order service at the New York headquarters and at overseas offices in England, France, Switzerland, West Germany and Japan.
- Export service providing software delivery to six continents.
- Subscriptions to *Lifelines*™, the monthly magazine that offers comparative reviews, tips, techniques, identified bugs and updates that keep you abreast of change.

Get It Now

Lifeboat now serves tens of thousands of satisfied customers with our breadth of up-to-date, fully tested, fully supported and competitively priced software.

You may not need all we offer, but we offer just what you need. After all, we wrote the book.

LIFEBOAT WORLDWIDE offers you the world's largest library of software. Contact your nearest dealer or Lifeboat:

Lifeboat Associates
1651 Third Ave
New York N Y 10028
Tel: (212) 860-0300
Telex 640693 (LBSOFT NYK)
TWX 710 581 2524

Lifeboat Inc
OK Bldg. 5F
1-2-8 Shiba-Daimon
Minato-ku Tokyo 105, Japan
Tel 03-437-3901
Telex 7423296 (LBJTYO)

Lifeboat Associates Ltd
PO Box 125
London WC1N 3LU England
Tel 01 836 9028
Telex 893709 (LBSOFTG)

Lifeboat Associates GmbH
PO Box 868 Aegenstrasse 35
CH 5340 Baar Switzerland
Tel 042 31 2931
Telex 865765 (MICO CH)

Intersoft GmbH
Schloss gartenweg 5
D 8045 Ismaning W Germany
Tel 089 966 444
Telex 5213043 (DSFD)

Lifeboat Associates SARL
10 Grande Rue Charles de Gaulle
93100 Aunemes, France
Tel 1-733 08 04
Telex 250303 (PUBLIC X PARIS)

Lifeboat Associates

Software with full support

CIRCLE 216 ON READER SERVICE CARD

Mail coupon to: Lifeboat Associates, 2604
1651 Third Avenue, New York, New York 10028
or call (212) 860-0300.

☐ **Please send me a free Lifeboat Catalog.**

☐ **Please send me *Lifelines* subscription information.**

Name _____ Title _____

Company _____

Street _____

City _____ State _____ Zip _____

Lifelines is a trademark of Lifelines Publishing Corporation.



Square Deal

Dear Editor:

I enjoyed Stephen Kimmel's article on the computer Othello tournament (*Creative Computing*, July, 1981). The author provided a delightful blow-by-blow account and the ultimate outcome was very satisfying—the good guy won.

I would like to inform your readers that the winning program is no longer available. I have recently finished a new Othello program which is written in assembly language for both the TRS-80 and Apple and is packed with user features.

It is available from Odesta Publishing, 920 Pitner Ave., Evanston, IL 60201.

I believe my new program, like its predecessor, is more than equal to the competition, and would welcome another tournament which pits my new program against all comers, including those which have recently been advertised as champions.

Peter W. Frey
Visiting Professor
University of California, Santa Cruz
Santa Cruz, CA 95064

Where Are You When We Need You?

Dear Editor:

I own an Ohio Scientific Challenger 1P, and I believe that my computer, and all OSI computers in general, are frequently misrepresented. OSI computers are continually left out of comparison lists of "Popular Computers" whether the article is about hardware, Basic, or other software. The annoying fact is that OSI is not there.

When an article does include OSI, i.e. "What can you buy for under $1000" (Vol. 7, No. 9) The facts sometimes get distorted. "The challenger format which includes a disk drive, C1PMF, offers 30K initially which can be expanded to 62K." Neither of the memory figures is correct. Due to I/O allocations, the C1P series cannot be expanded beyond 32K, expanding to 62K would mean pulling out the Basic ROMs, as they and the Monitor constitute the upper 10K of memory. (The 6502 can address only 64K of memory.)

With the new C1P series II, it is necessary to add a 630 expander board to the computer to get the new options: sound, joysticks, keypads and an important option you *didn't* include, VIC-like (or actually C4P-like) color.

Finally, you didn't bother to include OSI's C4P and C8P cassette-based computers in your article. These are still below $1000 before disks are added. As an OSI owner, I rarely see any articles pertaining to my computer, though I intend to write some. But I would like to see my computer get its fair share in general articles. Please try to help me out.

Howard Ship
P.O. Box 103
Randolph, MA 02368

We would like to print articles on the C1P, C4P, and C8P, but receive very few submissions. We need good articles and programs.—GB

Password Plus

Dear Editor:

In the August 1981 issue of *Creative Computing* a reader was puzzled over how to include passwords in a program, and keep them secret.

Here is one solution that I have found. The only way to do this is with a line editor, as you mentioned. A good one, is the "Progam Line Editor" (PLE) from Synergistic Software.

In a checkbook program I am developing I hide the password behind a REMark statement. Using the PLE, insert control-Hs within the remark statement to backspace over the line. For example, the following line is from my program:

```
3 PW$ = "HOBBIT":REM hhhhhhhhhhhhhhPASSWORD
CODE \\\\
```

The "h" is a control-H and the "\" is a space. The line will be listed as:

```
3 PW$ = PASSWORD CODE
```

The control-Hs will backspace over the Rem and the password, then "PASSWORD CODE" will be printed over the line that you do not wish to be seen. It is important to include spaces at the end of the line so that any characters not covered by the message will be erased. You could wipe out the entire line if you wish; just include enough control-Hs and spaces to cover the line. You can even use control-Js to issue line feeds or control-Ks to move the cursor up a line or two.

Randy Reeves
13451 Little Ranch Rd.
Cypress, TX 77429

Buzzy — **Hal Gerhardt**





$30 lets you take advanced VisiCalc™ lessons from VisiCalc's creators.

Introducing SATN from Software Arts, Inc., the creators of the VisiCalc program. SATN (Software Arts Technical Notes) is a publication offering on-going support to all VisiCalc users—from novice to expert.

Each issue of SATN is filled with techniques and information to help you expand your present understanding of VisiCalc functions as well as learn advanced methods to help in developing *your own* VisiCalc applications.

Benefit immediately from highly informative articles:

- **Complete Applications in Detail:**
  - **—Payroll Tax Calculation using @LOOKUP**
  - **—Mortgage Decision Calculation**
- **In Depth Descriptions of VisiCalc Features:**
  - **—Contents of a Saved Sheet**
  - **—Uses of DIF™ data file format**
- **Unusual Applications and Techniques:**
  - **—Date Arithmetic**
  - **—Recreational Mathematics**

SATN is your personal pipeline to the people at Software Arts who invented and developed VisiCalc. Their knowledge and experience with VisiCalc is available to you in each and every issue.

Special Charter Subscription Offer

Get 7 SATN issues for the price of 6, if you subscribe by December 31, 1981. We'll send you a FREE copy of SATN when you return the coupon, or call our toll-free number 800-257-7850 to order a year's subscription at our special introductory rate of $30.

Full Refund Policy

If you are not completely satisfied with your first issue of SATN, let us know within one month, and we will refund your money. Your free SATN issue is yours to keep.

Act today!

FOR FAST DELIVERY CALL TOLL-FREE 800-257-7850 Op. 737. (In N.J. 800-322-8650)

Software Arts, Inc.
SATN SUBSCRIPTIONS
P.O. BOX 815
QUINCY, MA 02169

☐ Yes, I'd like to receive advanced lessons in VisiCalc. Please send me seven issues at the regular subscripiion rate, $30. (Outside US—$50)

☐ Check enclosed ☐ MasterCard
☐ Visa ☐ Bill me

Credit Card # Expiration Date Interbank #

Name Signature

Address

City State/Country Zip/Postal Code

On what computer(s) do you run VisiCalc?_____

Please allow 6-8 weeks for delivery. CC4

SATN. The Journal for VisiCalc Users

The VisiCalc program is copyrighted by Software Arts, Inc. DIF is a trademark of Software Arts, Inc.
VisiCalc is a trademark of Personal Software Inc., which is the exclusive world-wide publisher and distributor of the VisiCalc program.

IBM Personal Computer

The Big Blue Giant Makes Its Move

Betsy Staples

"Didn't they make any mistakes?" asked one of our staff members in disbelief upon hearing our description of the new IBM Personal Computer.

"Not that we could see," was the response.

The long-awaited, much-heralded, frequently-leaked IBM Personal Computer was introduced by IBM on August 12, 1981 at the largest press conference the company has hosted since the introduction of the 360 in the mid-1960s.

And, indeed, it appears that IBM has done just about everything right. Upon first inspection, the machine seems to have everything a personal computer user could want: high resolution graphics, sound, disk drives, printer, lots of memory, system software, business applications software, word processing software, game software, a reasonable price and the IBM name.

The new computer, which uses a 16-bit 8088 mpu, is designed for business, school and home use and, unlike other IBM products, doesn't even have a number. It is aimed squarely at the consumer market, as evidenced in another departure from IBM tradition, the decision to sell through retail stores. Beginning in October, the Personal Computer will be sold through participating ComputerLand dealers and Sears, Roebuck, and Co.'s new business machine stores. It will also be available through IBM Product Centers and a special sales unit in the Data Processing Division.

The price of the basic unit is $1565. A system with 64K of memory, monitor and disk drive would be around $3000, and an expanded system for business use with color graphics, two disk drives and printer would cost about $4500.

Hardware

The complete system consists of the "system unit" which houses the mpu, memory and optional disk drives; a 20" x 8" x 2" keyboard which attaches to the system unit with a 6' spiral cable; a monochrome display for which a black and white or color television may be substituted; and a dot matrix printer.

The printer bears a striking resemblance to the Epson MX-80, but members of the press were told that it could not possibly be an MX-80 since it has a two-tone case and the IBM logo on the front. Whatever its name, it prints at 80 cps bidirectionally, and features a 9 x 9 character matrix; 12 type styles; a choice of 40, 66, 80 or 132 characters per line; and page spacing and column skip for word processing. (A complete evaluation of the MX-80 can be found in *Creative Computing*, July 1981.)

It appears that IBM has done just about everything right.

A spokesman for IBM would not speculate on plans to offer a letter-quality printer, but added that the computer has a standard RS-232 interface and may be used with many of the printers currently on the market.

The memory is divided into 40K of ROM and 16K of user memory which may be expanded by combining plug-in chips and boards to 256K. The optional one or two disk drives acccomodate the 5 1/4" diskettes with a storage capacity of 160K bytes each. The system unit also contains five system expansion slots through which other peripherals, including communications devices and joysticks or paddles, may be connected.

The monochrome display offers 25 lines of 80 characters of text on an 11 1/2" screen, upper and lower case, underlining, high intensity blinking characters, and reverse image.

One of the nicest components of the system is the 83-key, typewriter-like keyboard, which offers access to 256 characters, including APL symbols and foreign punctuation marks. It includes a numeric keypad and 10 function keys, and features "tactile feedback" (IBMese for "very nice touch").

Graphics and Sound

Although the demonstration at the press conference was geared to the general press and did not provide much detail regarding the graphics and sound systems, it was quite apparent that these features will set it apart from its competition.

The color graphics system can display any of the 256 characters in any of 16 foreground and 8 background colors. There are two levels of resolution: medium, which is 320 x 200 pixels, and high, which is 640 x 200 pixels.

We were very impressed with the high speed animation with simultaneous sound (all in Basic) which composed part of the demonstration, and with the ability of the machine to create "business graphics"—graphs, pie charts, etc.—in color.

System Software

The "cassette level" of the Basic Interpreter is included in ROM on the basic system. It is based on Microsoft Basic; provides I/O instructions for entry and retrieval of data; and supports the keyboard, display, light pen and printer as well as a full complement of editing and mathematical functions.

The "diskette and advanced levels" are optional. The diskette extension supports the use of disk drives, while adding date, time of day and communications capabilities to the system. The advanced extension enchances the display graphics to include features such as point, circle and get/put display, while increasing light pen and joystick support for design work and home entertainment.

The IBM Personal Computer DOS supports the disk drives, allowing the user to write or read from disk, display a directory, and rename, erase, display or copy files.

Also available are a Pascal compiler and UCSD p-System, as well as CP/M-86 from Digital Research, all designed to allow easy transfer of currently available

Amdek

From picture perfect.
To letter perfect.

Amdek
Color-I
FCC/UL approved

Amdek
Video-300

At Amdek, we make monitors for people who demand state-of-the-art color. And for people who know that crisp, clear text display is an art in itself.

Our versatile Color-I 13" video monitor features standard NTSC composite input, front-mounted controls and a built-in speaker with audio circuit. Our popular Video-300 12" Green Phosphor monitor has an easy-to-read, non-glare screen, 18 MHZ band width and 80 x 24 character display.

Both offer easy portability, with lightweight cabinetry and molded-in handles. And both are fully compatible with most computer and word processing systems. So compare our performance with other monitors. Then compare prices. For quality and value, you'll choose Amdek.

NEW THIS FALL, our advanced high resolution Color-II monitor with interface board for Apple II compatibility. Color-II features RGB, TTL input and 560(H) x 260(V) resolution for crisp 80 x 24 character display and exceptionally sharp color graphics. Ask your dealer about an Amdek Color-II, Color-I, or Video-300 monitor today.

AMDEK

2420 E. Oakton Street, Suite "E," Arlington Heights, Illinois 60005 (312) 364-1180 TLX. 25-4786

Come see our complete line of color, green phosphor and black/white monitors at the COMDEX Show (Booth 386-8) in Las Vegas, November 19-21.

CIRCLE 117 ON READER SERVICE CARD



A great cast of characters.
248 in all. Plus 10-key numeric pad.



State of the chart.
Easy to mix text and graphics.

The NEC neighborhood,
seen via 160 · 100 graphics matrix.



Powerful N-BASIC by Microsoft.®
Z80A equivalent chip. CP/M™ access

A good right hand at work.
Five programmable function keys.



Text processing in up to 8 colors.
And 36, 40, 72, and 80 columns.

The image is the reality.

These are unretouched photos of monitor screen images produced by the NEC PC-8000 Series microcomputer system.

In addition to this dramatic and easy-to-use graphics capability, the system also supports CP/M®, so you can gain immediate access to that vast, diverse, and well-established library of business and professional software.

All of which is over and above our own NEC general accounting, accounts receivable, inventory control, data base management, and word processing systems software available right now.

In fact, the entire PC Series story is a very impressive one. To see the picture for yourself, visit your nearest NEC America dealer. If you don't know who that is yet, call one of our distributors, and they'll tell you.

Comput Distributing
Detroit, MI
313/288-0000

High Technology
St. Louis, MO
314/838-6502

Micro Distributors
Rockville, MD
301/468-6450

Microamerica
Needham, MA
617/449-4310

Renaissance Technology
Pleasant Hill, CA
415/930-7707

Sigma Distributing
Seattle, WA
206/454-6307

Waybern Corporation
Garden Grove, CA
714/554-4520

Productivity at your fingertips

NEC

NEC America, Inc.
Personal Computer Products
1401 Estes Avenue
Elk Grove Village, IL 60007

CIRCLE 221 ON READER SERVICE CARD

CONTEXT
CONNECTOR

context

MAKE
VISICALC™
COMMUNICATE

- Communicate with other computers
- Receive or transmit data
- Link VISICALC models

- Transfer stock price history from Dow Jones into VISICALC models.
- Put FOCUS reports into VISICALC.
- Use DATADEX files in VISICALC models.
- Link VISICALC P & L models too big to fit into memory.
- Put economic data from I.D.C. into VISICALC models.
- Other uses as creative as VISICALC itself!

Requires Apple II, Disk, Communications

WRITE
FOR FURTHER
INFORMATION
AND STORE
NEAREST YOU
(213)
375-3350

context

632
Via Del Monte
Palos Verdes Estates
California, 90274

CIRCLE 319 ON READER SERVICE CARD

applications software to the new computer.

Applications Software

Undoubtedly the most useful of the optional applications packages offered by IBM is the familiar and popular VisiCalc from Personal Software. (See *Creative Computing*, August 1980).

Also available for business users are General Ledger, Accounts Receivable and Accounts Payable by Peachtree Software. And Easywriter from Information Unlimited Software has been chosen to provide word processing capabilities on the machine. (See *Creative Computing*, October 1980.)

Communications software allows users to access such data sources as Dow Jones New/Retrieval and The Source. IBM also intends to offer a full subset of 3270 emulation capabilities.

Finally, we were surprised to note that the bastion of "serious computing" lists Microsoft Adventure among the available applications for it newest computer.

So serious, in fact, does IBM appear to be about offering a library of interesting and useful applications software packages to their customers, that they have formed a new Personal Computer Software Publishing Department which will review and consider for publication software submitted by outside authors. Software information packets detailing the submission procedure may be obtained by writing: IBM Personal Computer Software Submissions, Dept. 765, Armonk, NY 10504.

Documentation

A cursory glance at the documentation in the demonstration area revealed several feet of manuals describing all aspects of the machine. Each is color coded and comes in a tidy little box. There was not a trace of a mimeographed or photocopied page in any of the books; they appear complete and ready for distribution.

Several of the manuals provide design specifications and information intended to encourage third party software and peripheral vendors to support the machine.

Service

Service is one of the things upon which IBM has built its reputation, and the company shows no signs of slacking off when it comes to the Personal Computer. The machines may be serviced at any of the retail outlets mentioned above, or the user may purchase an annual maintenance contract for between 10% and 15% of the price of the equipment. Under the maintenance contract, the customer calls IBM and specifies which part of the system is not working. Within 48 hours, a courier appears at the customer's door with a replacement for the defective unit.

The above information is based on observations made during demonstrations presented by IBM personnel and on literature provided by them. Watch these pages for an in-depth evaluation in which we will let you know if, indeed, IBM has succeeded in producing the perfect personal computer. □

We were very impressed with the high speed animation with simultaneous sound.

Can a Small Computer Really Save You Time?

Time is Money

Theophrastus said time was the most valuable thing a man could spend. Fifteen centuries later Haliburton agreed saying, "we reckon hours and minutes to be dollars and cents." Today, time is more valuable than ever—and more fleeting.

About the only way to gain time is to use it more efficiently and effectively. That's where we come in.

Small Business Computers—by the way, the "small" refers to computers, not to business—will dramatically increase your effectiveness and help save you time and money. How so?

You get flagrantly honest evaluations and reviews of computers and software. We don't just tell you what a program can do; we tell you what it doesn't do, what it does poorly, and what it should do for the price. If advertisers don't like that, we don't want their business, and you're better off without them. Fortunately, most companies appreciate our honesty. In fact, one of our reviewers has gained a reputation because of the many software houses that have incorporated his suggestions into their products. We're proud of that.

Photo courtesy of Alamitos Data Communications Corp.

Plain Talk

Small Business Computers explains the complexity of today's computerized business world without the technical jargon and doubletalk that may have held you back before. In its easily comprehensible "how-to" style, *Small Business Computers* answers your questions while providing the information you need to make some tough decisions. As you select, purchase, and install your computer system, *Small Business Computers* will guide you through each step calmly and comfortably—helping you to evaluate your computer needs and avoid unnecessary pitfalls. As you use your computer, be it mini or micro, *Small Business Computers* will be there to help you do so efficiently and with confidence while informing you of the latest developments and future possibilities of computers in business.

For Example

You have just purchased a mailing list program. Everything is fine until the file has to be sorted by zip code. If the program has that capability, all is well. If not, you have a big problem. If you had just invested a few hours reading *Small Business Computers*, you would have known what functions to look for before buying the program; you would have known how to plan for future needs. That's just one example. Expand this concept into other areas, other programs and systems, and you can see what you get for your investment.

Added Expertise

As the newest member of the Creative Computing family of fine computer publications, *Small Business Computers* will be expanding to offer subscribers more valuable information than ever before. *Creative Computing* editors and contributors will be unleashing their business expertise in *Small Business Computers* through articles, evaluations and applications of particular interest to the business person. *Creative Computing* has a reputation of editorial excellence and integrity built on unbiased, in-depth product evaluations; articles by top thinkers in the field; and pragmatic, innovative applications.

One management consulting firm, for example, used the Shell-Metzner sort described in *Creative*, and saved $3000 a month, and we still receive letters thanking us for the hardhitting, candid, evaluation of word processing printers we published over a year ago, and which, incidentally, cost us several advertisers.

All this knowledge and experience will now be available to business people in *Small Business Computers*.

So, don't let anyone give you that old story about how complicated and difficult computers are. We don't buy that. Our magazine—our whole philosophy—revolves around the sharing of honest information. If you don't know where to start, we'll put you on the right track. If you're already on the road, we'll show you the best route.

For Any Size Business

Whatever your business—manufacturing or banking, retail or research—*Small Business Computers* will increase your efficiency and help save you time and money.

Subscribe today; *Small Business Computers* is the best consultant your business will ever have.

Order Today

To order your subscription to *Small Business Computers* send $12.00 for 1 year (6 issues). If you prefer, call our toll free number **800-631-8112** (in N.J. 201-540-0445) to put your subscription on your Master Card, Visa, or American Express card. Canadian and other foreign surface subscriptions are $18.00 per year and must be pre-paid. We guarantee that you will be completely satisfied or we will refund the remaining portion of your subscription.
Send orders to:

Small Business Computers Magazine

39 E. Hanover Ave.
Morris Plains, NJ 07950
800-631-8112
(In NJ 201-540-0445)

CIRCLE 290 ON READER SERVICE CARD

Passport to Great Sound



creative computing equipment evaluation

David Lubar

Passport Designs has given Apple owners a chance to become musicians, and musicians a reason to buy Apples. The Soundchaser Computer Music system integrates a keyboard, synthesizers, and software, producing a very nice package. The keyboard is a beauty, housed in wood and well made. The three-voice synthesizers are versatile, and contain dip switches for various settings. The software is easy to use and visually excellent. Set-up is fairly simple; the keyboard attaches by ribbon cable to a card in slot seven. Two synthesizer boards go into slots two and four. After connecting the cards to a speaker using standard RCA plugs (not included), the system is ready to run.

Upon booting the disk, the software brings in an orchestra. The orchestra consists of four instrument definitions and four sequences. A sequence is a series of notes and chords which can be cycled repeatedly, producing backup, rhythm, or half of a duet. The opening menu gives a choice of HELP, DISK, EDIT, or SEQ(uence). HELP provides a summary of the system. DISK allows the user to load or save files. EDIT is where instruments are created or altered. And SEQUENCE allows recording and playback of sequences.

The EDIT section presents a split graphics screen, beneath which are text items. The top half of the screen is used for displaying waveforms. The lower half contains a graphic representation of various slides and switches. The creation of instruments is rather fascinating, and can be educational as well. For instance, E1 is the amplitude envelope. Using one of the game paddles, the user can draw a new envelope, then mark the sustain portion. He can then immediately give a PLAY command, go to the keyboard, and hear the results of the change. With two envelopes (one for amplitude and one that modulates the pitch of the oscillator) and two low frequency oscillators under software control, the user can define a broad range of instrument sounds, and create special effects. It's quite interesting to hear the changes produced by relocating the sustain point or changing the shape of an envelope.

More control is offered through the voice panel. One switch changes the range of octaves available from the keyboard. With four positions on the switch, and four octaves on the keyboard, this produces a range of seven octaves, though, of course, the user is limited to four at any one time. Other switches assign the second envelope to the oscillator or filter. The slides control filter range, filter resonance, envelope time, and filter time. Adding to the options, dip switches on the synthesizer card select between square and triangle waves. There is enough power here for serious work, and plenty of flexibility for fun experimentation.

The EDITOR was tackled by a combined group of musicians and programmers. We were able to produce a variety of effects, ranging from pleasing organ tones to bizarre instruments that played one note when a key was pressed, followed by an octave scale after the key was released. The visual nature of the display greatly aided instrument development. Needless to say, both the musicians and the programmers had a good time.

Moving to the SEQUENCER, the instruments can be put through their paces. The first step is to select one of four instruments, assign it to a sequence, then lay down a track. The computer will record

HUNTINGTON COMPUTING

ONE OF THE WORLD'S LARGEST INVENTORIES

Now Selling Atari, PET, TRS-80 Software

Atari

ADVENTURE INTERNATIONAL

Adventureland (cass)	$19.95	now	**$16.74**
Pirate's Adventure (cass)	$19.95	now	**$16.74**
Mission Impossible (cass)	$19.95	now	**$16.74**
Voodoo Castle (cass)	$19.95	now	**$16.74**
The Count (cass)	$19.95	now	**$16.74**
Strange Odyssey (cass)	$19.95	now	**$16.74**
Mystery Fun House (cass)	$19.95	now	**$16.74**
Pyramid of Doom (cass)	$19.95	now	**$16.74**
Ghost Town (cass)	$19.95	now	**$16.74**
Savage Island I (cass)	$19.95	now	**$16.74**
Savage Island II (cass)	$19.95	now	**$16.74**
Angle Worms/Crolon Dv (cass)	$9.95	now	**$8.34**
Deflection (cass)	$9.95	now	**$8.34**
Mountain Shoot (cass)	$9.95	now	**$8.34**
Sunday Golf (cass)	9.95	now	**$8.34**
Galactic Empire (cass)	$19.95	now	**$16.74**
Star Trek 3.5 (cass)	$19.95	now	**$16.74**
Lunar Lander (cass)	$19.95	now	**$16.74**

ARTSCI

Poker Solitaire (cass)	$14.95	now	**$12.74**
Gomoku (cass)	$19.95	now	**$16.94**
Reversi (cass)	$19.95	now	**$16.94**
Cypher Bowl (cass)	$29.95	now	**$23.44**

AUTOMATED SIMULATIONS

Rescue at Rigel (cass)	$29.95	now	**$23.44**
Star Warrior (cass)	$39.95	now	**$32.94**
Invasion Orion (cass)	$24.95	now	**$21.34**
Datestones of Ryn (cass)	$19.95	now	**$16.94**

AVALON HILL GAME COMPANY

Empire of the Overmind (cass)	$35.00	now	**$29.74**
Conflict 2500 (cass)	$15.00	now	**$12.74**
Empire of the Overmind (cass)	$35.00	now	**$29.44**
Tanktics (cass)	$24.00	now	**$20.44**

DATASOFT

Atari Mailing List (disk)	$24.95	now	**$21.34**
Atari Character Generator (disk)	$19.95	now	**$16.94**
Text Wizard (disk)	$99.95	now	**$84.44**
Atari Character Gen (cass)	$15.95	now	**$13.54**
Le Stick	$39.95	now	**$22.94**

ON-LINE SYSTEMS

HI-RES Adv #2 - Wiz & Princess (disk)	$32.95	now	**$27.94**

PERSONAL SOFTWARE

Visicalc (disk)	$199.95	now	**$164.44**
Checker King (cass)	$19.95	now	**$16.94**
MicroChess (cass)	$19.95	now	**$16.94**

UNITED SOFTWARE OF AMERICA

Survival/Adventure (disk)	$24.95	now	**$21.34**
3-D Supergraphics (disk)	$39.95	now	**$32.94**
3-D Supergraphics (cass)	$39.95	now	**$33.94**

OTHER

Mind-Bogglers I (disk)	$19.95	now	**$16.94**
Mind-Bogglers I (cass)	$15.95	now	**$13.54**
VersaWriter Graphics Tablet	$300.00	now	**$264.44**
Hidden Words	$17.50	now	**$13.44**
Spatial Relations	$17.50	now	**$13.44**
Word Scramble	$15.00	now	**$12.74**
Preschool Fun	$15.00	now	**$13.34**
Fastgammon (cass)	$19.95	now	**$16.94**
Assembler (cass.)	$24.95	now	**$21.14**
6502 Disassembler (cass)	$11.95	now	**$10.14**
6502 Disassembler (disk)	$14.95	now	**$12.44**
Tank Trap (cass.)	$11.95	now	**$10.14**
Tank Trap (disk)	$14.95	now	**$12.44**
Tari Trek (cass)	$11.95	now	**$10.14**
OS Forth (disk)	$79.95	now	**$67.94**
Starbase Hyperion (disk)	$22.95	now	**$19.44**
Name That Song (cass)	$14.95	now	**$13.44**

Pet

AVALON HILL GAME COMPANY

B-1 Nuclear Bomber (cass)	$15.00	now	**$12.77**
Midway Campaign (cass)	$15.00	now	**$12.77**
No Atlantic Convoy Raider (cass)	$15.	now	**$12.77**
Nukewar (cass)	$15.00	now	**$12.77**
Conflict 2500 (cass)	$15.00	now	**$12.77**
Planet Miners (cass)	$15.00	now	**$12.77**
Computer Acquire (cass)	$20.00	now	**$16.97**
Lords of Karma (cass)	$20.00	now	**$16.97**

AUTOMATED SIMULATIONS

Introductory 3-Pack (disk) (Rescue, Moriocs, and Datestones)	$49.95	now	**$39.97**
Rescue at Rigel (cass)	$29.95	now	**$25.47**
Temple of Apshai (cass)	$39.95	now	**$32.97**
Hellfire Warrior (cass)	$39.95	now	**$32.97**
Starfleet Orion (cass)	$24.95	now	**$21.27**
Invasion Orion (cass)	$24.95	now	**$21.27**
Moriocs Tower (cass)	$19.95	now	**$16.97**
Datestones of Ryn (cass)	$19.95	now	**$16.97**

PERSONAL SOFTWARE

VisiCalc (disk)	$199.95	now	**$167.77**
Checker King (cass)	$19.95	now	**$16.97**
Gammon Gambler (cass)	$19.95	now	**$16.97**
MicroChess (cass)	$19.95	now	**$16.97**
Bridge Partner (cass)	$19.95	now	**$16.97**
Time Trek (cass)	$19.95	now	**$16.97**

UNITED SOFTWARE OF AMERICA

KRAM (disk)	$99.95	now	**$84.97**
Super KRAM (disk)	$175.00	now	**$148.77**
Request (disk)	$225.00	now	**$191.27**
Thinker (disk)	$495.00	now	**$420.77**
Space Intruders (cass)	$19.95	now	**$16.97**
All MICRO-ED			**10% Off List**
All Microcomputer Workshops			**15% Off List**

VISICALC
Special for Pet, Atari & Apple
Regular $200.00 List
$149.00

TRS-80

BIG FIVE SOFTWARE

Super Novs (cass)	$15.95	now	**$13.58**
Galaxy Invasion (cass)	$15.95	now	**$13.58**
Attack Force (cass)	$15.95	now	**$13.58**
Cosmic Fighter (cass)	$15.95	now	**$13.58**
Meteor Mission II (cass)	$15.95	now	**$13.58**

BRODERBUND SOFTWARE

Galactic Trilogy (disk)	$39.95	now	**$23.98**
Galactic Empire (cass)	$14.95	now	**$12.68**
Galactic Trader (cass)	$14.95	now	**$12.68**
Galactic Revolution (cass)	$14.95	now	**$12.68**
Tswala s Last Redoubt (cass)	$19.95	now	**$16.98**

DATASOFT

Iago (disk)	$24.95	now	**$21.18**
Football Classics (disk)	$24.95	now	**$21.18**
Arcade-80 (disk)	$24.95	now	**$21.18**
Iago (cass)	$19.95	now	**$16.98**
Football Classics (cass)	$19.95	now	**$16.98**
Arcade-80 (cass)	$19.95	now	**$16.98**
Sagron (COLOR) (cass)	$29.95	now	**$25.38**
SECS (COLOR) (cass)	$29.95	now	**$25.38**

ACORN SOFTWARE

Invaders From Space (disk)	$20.95	now	**$17.78**
Duel-N-Droids (disk)	$20.95	now	**$17.78**
Pinball (disk)	$20.95	now	**$17.78**
Pigskin (disk)	$20.95	now	**$17.78**
Quad (disk)	$20.95	now	**$17.78**
Basketball (disk)	$20.95	now	**$17.78**
Gammon Challenger (disk)	$20.95	now	**$17.78**
Everest Explorer (disk)	$20.95	now	**$17.78**
SuperScript (disk)	$29.95	now	**$25.38**
System Savers (cass)	$14.95	now	**$12.68**
Invaders From Space (cass)	$14.95	now	**$12.68**
Duel-N-Droids (cass)	$14.95	now	**$12.68**
Pinball (cass)	$14.95	now	**$12.68**
Pigskin (cass)	$14.95	now	**$12.68**
Quad (cass)	$14.95	now	**$12.68**
Basketball (cass)	$14.95	now	**$12.68**
Gammon Challenger (cass)	$14.95	now	**$12.68**
Everest Explorer (cass)	$14.95	now	**$12.68**
All Adventure International			**15% Off List**
All Automated Simulations			**15% Off List**
All Avalon Hill			**15% Off List**
All Hayden			**15% Off List**
All Microsoft			**15% Off List**

Apple

Gorgon	$39.95	now	**$23.99**
Word Star	$375.00	now	**$289.00**
Mail Merge	$125.00	now	**$106.19**
Super Sort	$200.00	now	**$169.99**
VisiCalc 3.3	$200.00	now	**$149.00**
Wurst of Huntington Computing			**$19.99**
Noble Express	$12.95	now	**$11.99**
Soft Porn Adventure	$29.95	now	**$23.29**
Time Lord	$29.95	now	**$23.29**
French Hangman	$29.95	now	**$23.29**
Alicia-Sp bilingual reader	$29.95	now	**$23.29**
H&H Stock Trader	$190.00	now	**$161.49**
Grow (CIA)	$35.00	now	**$31.49**
Spelling Bee			**15% Off List**

VersaCalc	$100.00	now	**$84.99**
Hebrew	$60.00	now	**$58.99**
All Serendipity			**15% Off List**
Sneakers			**15% Off List**
All Sybex Courses			**15% Off List**
Win at the Races	$39.95	now	**$32.99**
Super Prep	$25.00	now	**$21.19**
PLE Chip	$60.00	now	**$58.99**

We maintain a huge inventory of Apple software and hardware. Call us toll free (outside Calif.) for the latest programs. We also stock a large supply of computer books. Visit us in person at our new 3300-square foot store at 1945 South Dairy in Corcoran, Calif.

Call Toll-Free 800-344-4111 (Outside California)

HUNTINGTON COMPUTING
Post Office Box 1235
Corcoran, California 93212

Order by Phone 800-344-4111
In California (209) 992-5411

SUPER DISCOUNTS

apple SOFTWARE

VISA

We have MasterCard or VISA (include card # and expiration date). California residents add 6% tax. Include $2.95 for postage, handling, and hardware extra. Send for free catalog. Prices subject to change.

CIRCLE 144 ON READER SERVICE CARD

FREE with software purchase One CPM Handbook

DISCOUNT SOFTWARE

Ad#18

ULTIMATE SOFTWARE PLAN

We'll match any advertised price on any item that we carry. And if you find a lower price on what you bought within 30 days of buying it, just show us the ad and we'll refund the difference.
It's that simple.

Combine our price protection with the availability of full professional support and our automatic update service and you have the Ultimate Software Plan.
It's a convenient, uncomplicated, logical way to get your software.

✓ (New Items or new prices)
CP/M users: specify disk systems and formats. Most formats available

DISK WITH MANUAL PLUS ONLY

CP/M

ARTIFICIAL INTELLIGENCE
Medical(PAS-3) $849/$40
Dental (PAS-3) $849/$40

ASYST DESIGN
Prof Time Accounting $549/$40
✓ General Subroutine $289/$40
✓ Application Utilities $439/$40

COMPLETE BUS. SYSTEMS
Creator $269/$25
Reporter $169/$20
Both $399/$45

COMPUTER CONTROL
Fabs (B-tree) $159/$20
UltraSort II $159/$25

COMPUTER PATHWAYS
Pearl (level 1) $ 99/$25
Pearl (level 2) $299/$40
✓ Pearl (level 3) $549/$50

DIGITAL RESEARCH
CP/M 2.2
NorthStar $149/$25
TRS-80 Model II (P+T) $159/$35
Micropolis $189/$25
Cromemco $189/$25
PL/I-80 $459/$35
✓ BT-80 $179/$30
Mac $ 85/$15
Sid $ 85/$15
Z-Sid $ 90/$15
Tex $ 90/$15
DeSpool $ 50/$10

D.M.A.
Ascom $149/$15
DMA-DOS $179/$35
CBS $369/$45
Formula $539/$45

GRAHAM-DORIAN
General Ledger $729/$40
Acct Receivable $729/$40
Acct Payable $729/$40
Job Costing $729/$40
Payroll II $729/$40
Inventory II $729/$40
Payroll $493/$40
Inventory $493/$40
Cash Register $493/$40
Apartment Mgt $493/$40
Surveying $729/$40
Medical $729/$40
Dental $729/$40

MICRO-AP
S-Basic $269/$25
Selector IV $489/$35

MICRO DATA BASE SYSTEMS
HDBS $269/$35
MDBS $795/$40
✓ DRS or QRS or RTL $269/$10
MDBS PKG $1295/$60

MICROPRO
WordStar $319/$60
Customization Notes $ 29/$na
Mail-Merge $109/$25
WordStar/Mail-Merge $419/$65
DataStar $249/$60
WordMaster $119/$40
SuperSort I $199/$40
✓ Spell Star $175/$40

MICROSOFT
Basic-80 $289/$na
Basic Compiler $329/$na
Fortran-80 $349/$na
Cobol-80 $574/$na
M-Sort $124/$na
Macro-80 $144/$na
Edit-80 $ 84/$na
MuSimp/MuMath $224/$na
MuLisp-80 $174/$na

ORGANIC SOFTWARE
TextWriter III $111/$25
DateBook II $269/$25
✓ Milestone $269/$30

OSBORNE
General Ledger $ 59/$20
Acct Rec/Acct Pay $ 59/$20
Payroll w/Cost $ 59/$20
All 3 $129/$60
All 3 + CBASIC-2 $199/$75

PEACHTREE®
General Ledger $399/$40
Acct Receivable $399/$40
Acct Payable $399/$40
Payroll $399/$40
Inventory $399/$40
Surveyor $399/$40
Property Mgt $799/$40
CPA Client Write-up $799/$40
PS Version Add $129

SOFTWARE WORKS
Adapt (CDOS to CP/M) $ 69/$na
Ratfor $ 86/$na

SOHO GROUP
MatchMaker $ 97/$20
WorkSheet $177/$20

STRUCTURED SYSTEMS
GL or AR or AP or Pay $599/$40
Inventory Control $599/$40
Analyst $199/$25
Letterright $179/$25
QSort $ 89/$20

SUPERSOFT
Diagnostic I $ 49/$20
Diagnostic II $ 84/$20
Disk Doctor $ 84/$20
✓ Forth (8080 or Z80) $149/$30
Fortran $219/$30
Fortran w/Ratfor $289/$35
Other less 10%

TCS
GL or AR or AP or Pay $ 79/$25
All 4 $269/$99

UNICORN
✓ Mince $149/$25
✓ Scribble $149/$25
✓ Both $249/$50

WHITESMITHS
C Compiler $600/$30
Pascal (incl "C") $850/$45

"DATA BASE"
PMS-80 $649/$45
dBASE II $629/$50
Condor II $899/$50
Access/60 $749/$50

"PASCAL"
Pascal/MT+ $429/$30
Pascal/Z $349/$30
✓ Pascal/UCSD 4.0 $429/$50
✓ Pascal/M $189/$20

"WORD PROCESSING"
✓ WordSearch $179/$50
SpellGuard $229/$25
VTS/80 $259/$65
Magic Wand $289/$45
Spell Binder $349/$45

"OTHER GOODIES"
The Last Word $540/$05
SuperCalc $269/$50
Target $169/$30
BSTAM $149/$15
BSTAT $149/$15
Tiny "C" $ 69/$50
Tiny "C" Compiler $229/$50
CBASIC-2 $ 98/$20
Nevada Cobol $129/$25
✓ MicroStat $224/$25
Vedit $105/$15
MimModel $449/$50
SitePlak $449/$40
Micro B+ $229/$20
Raid $224/$35
String/80 $ 84/$20
String/80 (source) $279/$na
ISIS II $199/$50
✓ Plan 80 $269/$30

APPLE II

INFO UNLIMITED
EasyWriter $224
Datadex $349
Other less 15%

MICROSOFT
Gotoxy (Z-80 CP/M) $259
Fortran $179
Cobol $499

MICROPRO
Wordstar $269
MailMerge $ 99
Wordstar/MailMerge $349
SuperSort I $159

PERSONAL SOFTWARE
Visicalc 3.3 $159
CCA Data Mgr $ 84
Desktop/Plan II $159
Visiterm $129
Visidex $159
Visiplot $149
Visitrend/Visiplot $229
Zork $ 34

PEACHTREE®
General Ledger $224/$40
Acct Receivable $224/$40
Acct Payable $224/$40
Payroll $224/$40
Inventory $224/$40

"OTHER GOODIES"
dBASE II $329/$50
✓ VU 83R
(use w/Visicalc) $ 79
Super-Text II $127
Data Factory $134
DB Master $184
Charles Mann less 15%
STC less 15%

ORDERS ONLY—CALL TOLL FREE VISA • MASTERCHARGE
1-800-854-2003 ext. **823** • **Calif. 1-800-522-1500** ext. **823**

Overseas—add $10 plus additional postage • Add $2.50 postage and handling per each item • California residents add 6% sales tax • Allow 2 weeks on checks, C.O.D. ok • Prices subject to change without notice
All items subject to availability • ® – Mfgs. Trademark

THE DISCOUNT SOFTWARE GROUP
6520 Selma Ave. Suite 309 • Los Angeles, Ca. 90028 • (213) 666-7677
Int'l TELEX 499-0032 BVHL Attn: DiscSoft • USA TELEX 194-634 BVHL Attn. DiscSoft •
TWX 910-321-3597 BVHL Attn: DiscSoft

CIRCLE 131 ON READER SERVICE CARD

what is played, and replay it exactly, so timing is important. If the player makes a mistake, he has to do the whole thing over again. Not hard for a musician, but a task for those programmers who barely remember the bass line for *Heart and Soul*. With a sequence recorded, the fun starts. It can be replayed while something different is done line on the keyboard. A tempo control allows sequences to be replayed at sixteen different speeds. The new tempo is relative to the one used when the sequence was defined. Thus a sequence recorded at tempo eight can be played slower or faster. A sequence recorded at sixteen (the slowest tempo) can be speeded up but not played slower. The disk contains a good selection of sequences, mostly of the backup-rhythm sort. Pleasing sequences and instrument definitions can be saved to disk.

At the moment, the system is limited to six voices, though there is talk of interfacing it with the Mountain Card. Using two oscillators per voice, this would provide an eight-voice system. When playing live music along with a sequence, the keyboard has priority. Thus, if more than six notes are played simultaneously, notes will be dropped from the sequence.

The manual contains clear descriptions of all operations, accompanied with diagrams of the screen. An appendix on synthesizer functions includes good background information on the technical aspects of sound generation. For those with a bent toward machine language, the manual provides a sample assembler routine to access the Soundchaser keyboard.

The Soundchaser keyboard costs $650. Synthesizer boards are $350 each. Software is provided free of charge to customers purchasing the keyboard and at least one synthesizer. The software requires a 48K Apple with Applesoft and one disk drive.

Passport Designs, Inc., 785 Main St., Suite E, Half Moon Bay, CA 94109. □



©CREATIVE COMPUTING

Introducing STC's Low-Cost Coloring Board

Put some color in your Apple for only $60.

$60. vs. 800.
Introducing low-cost color graphics for Apple computers.

To our knowledge, many other color graphic capabilities for the Apple cost at least $800. Now you can create, change, store and retrieve colored drawings for only $60. with STC's new Coloring Board program.

For Education, Business, Industry, Entertainment.
There are virtually unlimited uses for the Coloring Board, any situation that can benefit from graphic displays: classroom instruction, sales meetings, engineering parts drawings, home entertainment, you name it. You get high resolution and six colors: black, blue, white, green, orange and violet. You can combine graphics with alphanumerics of various sizes and colors, upper and lower case.

Easy and Fun To Use.
The Coloring Board is easy to learn and fun to use. No special equipment is needed, just your standard Apple game paddles (or joystick) and keyboard. And we've made it even easier. You can automatically generate arcs, circles, squares, rectangles, ellipses, triangles and other shapes. In addition, the basic package comes with a map of the world, a map of the U.S., a space shot and more. What's more, you can directly output your graphics to a printer.

All for only $60.

Contact Your Local STC Dealer.
We'll be happy to direct you to your local STC Coloring Board dealer. Just write or call Software Technology for Computers, P.O. Box 428, Belmont, Ma. 02178. (617) 923-4334.

Be sure to look at our other business packages as well.

Dealer inquiries invited.

(Apple is a trademark of Apple Computer Company)

SOFTWARE TECHNOLOGY for COMPUTERS
P.O. Box 428, Belmont, MA 02178 (617) 923-4334

CIRCLE 281 ON READER SERVICE CARD

David H. Ahl

BELL LABS' 32-BIT MPU RUNS C AND UNIX

Bell Labs' MAC-32 is a true 32-bit mpu with every data and address bus, CPU register and instruction having 32 bits. With an effective clock rate of 32 MHz, the MAC-32 should grossly outperform virtually every other 16 and 32 bit mpu currently available.

Since the MAC-32 was designed for use in AT&T telecommunictions applications, it is optimized for data manipulation using C and Unix. As a result, it has many data types including words, half words, bytes, bit fields and blocks; split CPU control with separate fetch and execute units; and 16 on-chip registers of 32 bits each.

Although currently not intended for use outside of the Bell System, that could change with the advent of commercial marketing through the unregulated "Baby Bell" subsidiary.

CAN ACORN BECOME AN OAK TREE OVERNIGHT?

Acorn, a British firm founded in 1978 was doing nicely with their Atom kit computer. However, founder Christopher Curry convinced the BBC early this year that a new Acorn computer could meet the BBC's requirements for their TV educational courses.

Simultaneously, Acorn was negotiating with the Dept. of Industry to have an Acorn ccomputer approved for the Government 50% grant for secondary schools which install computers for teaching purposes.

Now, approved for both programs, Acorn has contracted for manufacturing at three plants in the U.K. as well planning additional production in Hong Kong, Australia and the United States

Cost of the Acorn BBC machine is about $500. Sure, apples are bigger than acorns. But oak trees are much bigger than apple trees.

THE MEDIA DISCOVERS COMPUTER SIMULATIONS

For news stories that last more than a week or so, media people start looking for new angles to keep the public interested. Lately these angles have involved several small computer software packages.

Creative Computing's Air Traffic Controller package was featured on the AP newswire which led to TV spots on NBC, ABC and PBS; ten radio interviews and numerous newspaper and magazine mentions including articles in Time and the Wall St. Journal (in which it shared the spotlight with Instant Software's Flightpath).

The persistent Medfly led Dick Milewski of The Software Works to quickly bring to market MedFly Mania, a simulation which explores ways to bring the fly under control. It, along with Creative Computing's STERL program (on the Ecology Simulations I package) were featured on many radio and TV shows in August and September. At the rate the flies are spreading, these two packages could have a long media life.

A year ago, Muse's Three-Mile Island program enjoyed similar attention.

Although it's nice to get free publicity, we'd just as soon avoid this kind for our rats infestation and malaria epidemic programs.

BUSINESSMEN, MANAGERS ARE BIGGEST ON-LINE USERS

Three times as many businessmen and managers are likely to use "The Source" information service than engineers, scientists, professionals or even people in a computer-related job. Among the most popular services are research, electronic mail, business planning and forecasting, financial market monitoring, personal portfolio maintenance and home education. Fifty-six percent of Source users "sign on" three times a week or more.

THE GRAPHIC DIFFERENCE

BETWEEN ATARI® COMPUTERS AND ALL OTHERS.

3.7 million reasons why the ATARI Personal Computer is something to see.
The display screen used with our computers is composed of 192 horizontal lines, each containing 320 dots. Delivering color and luminosity instructions to each dot for a second requires 3.7 million cycles...a lot of work for the normal 6502 processor.

That's why the ATARI computer has equipped its 6502 with its own electronic assistant. It's called ANTIC, and it handles all the display work, leaving the 6502 free to handle the rest. What this means to you is uncompromisingly spectacular display capabilities without loss of computer power needed to carry out the demands of your program.

That's a quality you just don't find in ordinary personal computers. And it's one of the reasons some computer experts say that ATARI computers are so far ahead of their time.

There's more...which is what you'd expect from ATARI.

Language. The ATARI Personal Computer uses several programming languages to give the user maximum control of its extraordinary capabilities. PILOT, Microsoft BASIC,* and ATARI BASIC are understood and spoken by the ATARI computer. You'll also find our Assembler Editor cartridge indispensable for machine language programming.

Sound. An ATARI computer has four sound generators, or voices, activated by a separate microchip. This leaves the principal microprocessor chips free to perform other tasks. And you can take full advantage of this capability which is designed for easy programming.

Change. ATARI Personal Computers have been designed to make change and expansion easy. The ATARI computer has a modular operating system* that can be easily replaced as new technology develops. If you need it, memory expansion requires no more than inserting additional RAM modules.* And the ATARI ROM cartridge system also makes it easy to change languages. In short, your ATARI computer won't be obsoleted by future developments...*because it already incorporates the future.*

Sharing. To learn more about the amazing capabilities of ATARI computers, visit your local computer store for a demonstration. Or send for our Technical User's Notes, intended for the serious programmer. They are only $27 and contain a lot more information about our computers' special capabilities than most companies could tell. See your ATARI dealer, or send $30 ($27 plus $3 postage and handling), payable to ATARI, to Technical User's Notes, c/o ATARI Customer Service, 1340 Bordeaux Avenue, Sunnyvale, CA 94086.

*ATARI 800™ computer only

ATARI®

Computers for people.™

©1981 Atari, Inc.

A Warner Communications Company

CIRCLE 123 ON READER SERVICE CARD

'The ZX81 is cased in sturdy black ABS plastic. And very nice it looks, too.'

'The machine offers no colour facilities and my guess is you shouldn't hold your breath waiting for them.'

'The basic ZX81 contains four chips... It's so simple, I think even I could build it.'

'Uncle Clive has come up with a lovely product with enormous appeal and which won't cost an arm and a leg.'

'...you'll have to be careful not to have your PAUSEs too close together, unless you enjoy watching the screen go absolutely bananas.'

'Finding your way round the keyboard is a real hoot — some of the keys have five functions.'

'...the single stroke keyword entry is a joy to use...'

'Hardly high resolution but better than a poke in the eye with a sharp stick!'

'Kids will love it (so will Dads)...'

'The idea of producing a superior machine to the ZX80 and selling it for a lower price is absolutely wonderful.'

'...I suspect that more than a few people who are already familiar with computers will buy one, just to have a bit of fun.'

'When loading a program, the pattern on the screen shows you when data is being recognized.'

This review of the Sinclair ZX81 is reprinted from our 'sister' publication, Personal Computer World in England. Although the ZX81 was not yet available in the U.S. at the time this issue went to press (August 1981), we anticipate that if it has not been introduced by the time you read this, it will be in the near future. Prices mentioned have been converted to their approximate equivalents in U.S. dollars, and we expect that certain features peculiar to Britain (such as programs referring to pounds, shillings and pence) will be modified for the U.S. model.—EBS

SINCLAIR ZX81

David Tebbutt

Right from the start, I had better explain that the ZX81 costs $100 in kit form and $150 ready-built and, as such, represents absolutely amazing value for money. Whatever shortcomings are highlighted in this Benchtest must be weighed against this fact.

Like the ZX80, its predecessor, the ZX81 will be available by mail-order and, by the time you read this, deliveries should be coming through. Clive Sinclair tells me that he plans to up production to 10,000 units per month starting in April and that he'll be producing 10,000 ZX80s to satisfy overseas demand, so, providing that 10,000 or fewer of you order the new machine per month, delivery should be swift.

Sinclair has been a bit cheeky in his advertisements. Under a column entitled 'New, improved features', he proceeds to mention three things that were included in the ZX80 when it was launched over a year ago!

For the benefit of those unfamiliar with the ZX80, it was the first ready-built computer to break the psychological $200 price barrier. It was well-made but looked slightly cheap in its lightweight plastic case and with its shiny keyplate. The 'keys' were printed on a plastic membrane with a metallised back; when each 'key' was pressed, the metallic back came in contact with PCB tracks, shorting them to complete the appropriate circuit. The system plugged into the domestic television to give an extremely clear display, and program storage could be made onto the home cassette recorder. The ZX80 came with 1k of user memory (RAM) and a 4k operating system/Basic language chip.

The main limitations of the ZX80 were the fact that it could not handle floating point numbers or cassette files. Also, when first launched, memory expansion came a bit expensive but this changed when the 16k plug-in RAM became available. The ZX80 certainly represented a great step forward and offered excellent value for money for people wanting to learn about computing.

So what in the ZX81 is new, compared with the ZX80? First, an extra 4k of ROM is provided, which allows 30-odd additional functions to be incorporated. This will also drive the printer (expected in the summer). I couldn't test this, but I have seen it working. It is an electrosensitive printer requiring aluminised paper, the surface of which is burnt off by an electrical discharge to reveal the black paper underneath. Don't study the photos too closely, because they show a model, not the real thing. The ZX81 costs an amazing $50 less than the ZX80, thanks to some neat design consolidation in a Ferranti chip custom-built to Sinclair's requirements. The total number of chips in the basic system is four, against the ZX80's 21. The ZX81 and its peripheral products are all cased in sturdy black ABS plastic. And very nice it looks, too.

Hardware

Although physically smaller than the ZX80, the new machine weighs in at 13oz, about 2oz heavier than its predecessor. The system needs a UHF television, a cassette recorder and a power supply to make it usable.

On my colour television the screen is a pleasant green and all characters are displayed in black. The machine offers no colour facilities and my guess is that you shouldn't hold your breath waiting for them. I suspect that a projection system based on three of Uncle Clive's miniature TV tubes might appear one day but, then again, I also suspect that he'd introduce another computer to take advantage of this. The display is 24 lines of 32 characters of which two lines are reserved for system messages and commands. Low resolution graphics are provided to give 64 by 44 plotting points. As with the ZX80, the display is very clear and rock-steady.

I'm pleased to see that the new power supply has its own flying lead for the attachment of a normal mains plug. (The ZX80 was awkwardly designed with an integral plug which often needed an additional socket or extension lead.) This power supply must give 600 mA at 9V but, since the ZX81 draws close to this, the standard power supplies actually give 700 mA and I would recommend that readers using their own supplies go for the higher rating, too.

Once again, the keyboard is formed by an underprinted plastic membrane which is everything-proof (water, chemicals, Coca-Cola, cigarette ash, monkeys, editors, etc). The keyboard layout is different from the ZX80's so, if you're upgrading, prepare to make a few mistakes at first. At the same time it is an improvement, since each keyword is frequently placed at or near its initial letter. (All you have to do now is learn the qwerty layout!)

Here are a few ideas for Uncle Clive: a plug-in battery pack, a plug-in single-line LCD display and a remote (infra-red or ultrasonic) facility so that you can sit in your armchair beaming the display information at an aerial adaptor on the television.

Compared with the ZX80, the ZX81 looks very smart indeed — one could almost say tasteful. It has a nice shape and texture and the keyboard is made of a non-reflective material, a definite improvement.

The plug-in 16k RAM pack fits to the edge of the PCB where it protrudes from the rear of the casing. The cursor takes a while to appear at switch-on, because the system is checking to see how much memory is present in order to set certain system variables. If you're a machine code freak you can reset the RAMTOP variables in order to give you somewhere safe to tuck your precious program.

Five screws hold the ZX81 together, three of them are hidden under the pads on which the machine stands (footpads? surely not). You know what I mean —

Reprinted with the permission of *Personal Computer World*, 14 Rathbone Place, London W1P 1DE.



those non-skid things. There's a substantial heat sink for the regulator under the rear of the keyboard — it's a good place to warm your hands on a chilly morning. The PCB is held into the casing by two screws. The keyboard is separate from the main PCB and is connected to it by a couple of flat printed cables. The main PCB is well designed and neatly made. Assembly of the ZX81 is done very professionally by the Timex Corporation in Scotland (the same people that are making Sinclair's latest miniature television).

The basic ZX81 contains four chips — ROM, 3.5 MHz Z80A CPU, 1k memory and the Ferranti custom-made chip — plus a limited assortment of bits and pieces. It's very, very simple — I think even I could build it. A few spare positions on the board give the manufacturer a certain amount of flexibility to tweak the machine to the requirements of different television systems and to be prepared in case a memory chip famine occurs. The Ferranti chip handles all the I/O and control signals between the various elements of the machine. Nosing around inside, I notice that it has a very cosmopolitan flavour, with memory from Malaysia, the CPU and ROM from Japan, a UHF modulator from the Philippines, a regulator from El Salvador and the custom chip from Britain. The edge connector is not gold-plated (what do you expect for $150?); it's just the PCB printing taken out to the edge. The 16k RAM pack contains two boards connected at the edge. One board contains eight 4116s which are driven by the other board's assortment of seven chips which handle the memory addressing and refreshing.

Software

The ZX81 syntax-checking is excellent because, unlike the ZX80's, instead of operating on each character as it's entered, the system waits until NEWLINE is hit. Finding your way around the keyboard at first is a real hoot — some of the keys have five functions. As before, the single stroke keyboard entry is a joy to use and the automatic spacing inserted by the system makes program listings clearly legible. For example, if you tried to enter 10FORN=1TO10, it would appear as 10 FOR N=1 TO 10. Pretty neat, huh?

Editing is very simple. You position the cursor on the line to be modified, hit the EDIT key and then make your corrections. Additional characters and functions are automatically inserted at the cursor position within the line while RUBOUT deletes the character or function to the cursor's left. A touch on the NEWLINE key confirms the changes.

The machine can be used as a calculator but shouldn't be bought for that purpose since the precision is less than one would expect of such a device. It is, however, far better than the integer-only ZX80, offering $+/-10^{+/-38}$. If numbers get out of hand it presents results in standard scientific notation. For those who can't readily visualise this level of accuracy, it means numbers up to 4,294,967,295 can be represented with complete accuracy. That's $2^{32}-1$. The smallest positive number is about 4×10^{-39}. Five bytes are needed to store a number, which goes a long way to explaining why the Benchmark timings are slower than with the ZX80, which only required two.

An enormous number of functions have been crammed onto this rather small keyboard. This has been achieved by using two special keys: graphics, which allows the user to key all the graphic characters as well as the normal characters as white on black; and function, which allows the user access to (surprise, surprise!) special functions. A normal mode of operation also exists. In addition to all this, the keyboard has a bog-standard shift key, thus increasing the range of options for each key still further.

The character set is a one-off — it's not ASCII or anything I recognise. I think we'd be safe if we called it Clive code. The TV display isn't exactly memory-mapped — it tends to move around and change its size depending on what's going on. It is, however, possible to find the start of the screen area and then to access the screen by PEEKing and POKEing the screen locations in the buffer.

Basic

All but one of the ZX80's Basic functions, plus a substantial number of additions, have been incorporated into the 8k ROM which drives the ZX81. The following commands and statements are provided over and above the old ZX80 repertoire: ASN, ACS, ATN, COS, EXP, INKEYS, PI, SGN, SIN, SQR, INT, LEN, LN, TAN, VAL, <=, >=, <>, COPY, DIMAS, FAST, FOR...

COMPUTER CENTER
SUPER SELECTION & DISCOUNT PRICES

ATARI

ATARI 800 $775.

ATARI 400 $319.

16K RAM	$ 90.
810 DISK DRIVE	489.
410 RECORDER	70.
850 INTERFACE	160.

CROMEMCO

CS-0/0 SYSTEM ZERO W/64K, 16 FDC $2399.

Z-2H HARD DISK SYSTEM	$7899.
CS-3 SYSTEM THREE	6399.
CS-2 SYSTEM TWO	3799.
DDF ADD ON 5-1/4" DUAL DRIVE	1099.

APPLE

APPLE II PLUS (48K)	$1200.
DISK II W/3.3 CONTROLLER	575.
DISK II W/O CONTROLLER	499.

HEWLETT-PACKARD

HP-85 $2750.

HP-83	$1915.
16K RAM	260.
5-1/4" DUAL MASTER DISK DRIVE	2125.
HP-IB INTERFACE	340.
ROM DRAWER	39.
MASS STORAGE ROM	122.
VISICALC (TM) PLUS	180.

RADIO SHACK TRS-80

TRS-80 MODEL II 64K	$3699.
TRS-80 MODEL II HARD DISC*	4200.
TRS-80 MODEL III W/2 DRIVES 48K	2200.

*Available Soon

TRS-80 is a trademark of Tandy Corp.

COMPUTER CENTER
DigiByte Systems Corp.
31 East 31st Street, New York, N.Y. 10016
OUTSIDE NEW YORK CALL TOLL FREE:
(800) 221-3144
IN NEW YORK CALL: (212) 889-8130

CIRCLE 173 ON READER SERVICE CARD

COMPUTER CENTER

31 East 31st Street • New York, N.Y.
(between Madison & Park Avenue)

480 Lexington Avenue • New York, N.Y.
(American Brands Bldg., between 46th & 47th St.)

presenting the LARGEST SELECTION OF SOFTWARE EVER ASSEMBLED...

for ATARI® • APPLE® • PET® • TRS-80® and other Microcomputers

at SUPER DISCOUNT PRICES!

ATARI

- ☐ MISSILE COMMAND (AT) ... 35.95
- ☐ ASTEROIDS (AT) ... 35.95
- ☐ SPACE INVADERS (AT) ... 17.95
- ☐ ASSAULT BIRDS (AT) ... 53.95
- ☐ BASKETBALL (AT) ... 35.95
- ☐ VIDEO EASEL (AT) ... 35.95
- ☐ SUPER BREAKOUT (AT) ... 35.95
- ☐ MUSIC COMPOSER (AT) ... 53.95
- ☐ COMPUTER CHESS (AT) ... 28.00
- ☐ 3-D TIC TAC TOE (AT) ... 35.95
- ☐ STAR RAIDERS (AT) ... 35.95
- ☐ PACMAN (AT) ... 17.95
- ☐ JOYSTICKS (AT) ... 17.95

ADVENTURE INTERNATIONAL

- ☐ ADVENTURE #0 (T) ... 8.25
- ☐ ADVENTURE (1.2.3) (D) (AP.T) ... 35.95
- ☐ ADVENTURE (4.5.6) (D) (AP.T) ... 35.95
- ☐ ADVENTURE (7.8.9) (D) (AP.T) ... 35.95
- ☐ ADVENTURE (specify 1-12) (AP.T.AT) ... 17.95
- ☐ PROJECT OMEGA (T) ... 17.95
- ☐ PROJECT OMEGA (T) (D) ... 22.50
- ☐ PLANETOIDS (D) (AP) ... 17.95
- ☐ MEAN CHEQERS MACHINE (T) ... 17.95
- ☐ DR. CHIPS (T) ... 17.95
- ☐ KID-VENTURE I (AP.T) ... 17.95
- ☐ LUNAR LANDER (T.AT) ... 17.95
- ☐ MOUNTAIN SHOOT (AT) ... 13.45
- ☐ SLAG (T) ... 17.95
- ☐ STAR TREK 35 (AT.T) ... 17.95
- ☐ STAR TREK 35 (D) (T) ... 17.95
- ☐ SUNDAY GOLF (AT) ... 13.55
- ☐ ZOSSED IN SPACE ... 17.95
- ☐ SILLY FLIGHT (AT) ... 17.95
- ☐ SILVER FLASH (D) (T) ... 17.95
- ☐ MISSILE ATTACK (T) ... 17.95
- ☐ STAR SCOUT (T) ... 17.95
- ☐ GALACTIC EMPIRE (AT) ... 17.95

AVALON HILL

- ☐ MIDWAY (AT.AP.P.T) ... 13.50
- ☐ NUKE WAR (AT.AP.P.T) ... 13.50
- ☐ PLANET MINERS (AT.AP.P.T) ... 13.50
- ☐ CONVOY RAIDER (AT.AP.P.T) ... 13.50
- ☐ B1 BOMBER (AT.AP.P.T) ... 13.50
- ☐ LORDS OF KARMA (AT.AP.P.T) ... 18.00
- ☐ CONFLICT 2500 (AT.AP.P.T) ... 13.50
- ☐ COMPUTER ACQUIRE (AP.P.T) ... 18.50

ACORN SOFTWARE

- ☐ ATERM (T) ... 17.95
- ☐ SYSTEM SAVERS (T) ... 13.55
- ☐ DISASSEMBLER (T) ... 13.55
- ☐ DISK TAPE UTILITY (T) ... 17.95
- ☐ STAR TREK SIMULATION (T) ... 8.95
- ☐ GAMMON CHALLENGER (T) ... 13.55
- ☐ PIGSKIN (T) ... 13.55
- ☐ ULTRA TREK (T) ... 13.55
- ☐ SPACE WAR (T) ... 8.95
- ☐ WARGAMES (T) ... 8.95
- ☐ BASKETBALL (D) (T) ... 18.95
- ☐ BASKETBALL (T) ... 13.55
- ☐ DUEL-N-DROIDS (D) (T) ... 18.95
- ☐ DUEL-N-DROIDS (T) ... 13.55
- ☐ INVADERS FROM SPACE (T) ... 13.55
- ☐ INVADERS FROM SPACE (D) (T) ... 18.95
- ☐ PIGSKIN (D) (T) ... 18.95
- ☐ PINBALL (T) ... 13.55
- ☐ PINBALL (D) (T) ... 18.95
- ☐ SUPERSCOUT (D) (T) ... 28.95
- ☐ EVEREST EXPLORER (T) ... 13.55
- ☐ EVEREST EXPLORER (D) (T) ... 18.95

EPYX-AUTOMATED SIMULATIONS

- ☐ TUESDAY QUARTERBACK (D) (AP) ... 26.95
- ☐ STAR WARRIOR (C.D) (AP.T) ... 35.95
- ☐ THREE PACK (D) (AP.P.T) ... 45.00
- ☐ STARFLEET ORION (C.D) (AP.T) ... 22.50

If you don't see it listed, write, we probably have it in stock!

Check program desired. Complete ordering information and mail entire ad. Immediate Shipments from stock.

KEY:
AT-Atari
AP-Apple
P-Pet
T-TRS-80
C-Cassette
D-on Disc
If not marked-Cassette

ATARI is a trademark of ATARI INC.
APPLE is a trademark of APPLE COMPUTER INC.
TRS-80 is a trademark of TANDY CORP.
PET is a trademark of COMMODORE BUSINESS MACHINES

Prices subject to change without notice

EPYX-AUTOMATED SIMULATIONS

- ☐ STARFLEET ORION (C) (P.AT) ... 22.50
- ☐ INVASION ORION (C.D) (AP.T) ... 22.50
- ☐ INVASION ORION (C) (P.AT) ... 22.50
- ☐ TEMPLE OF APSHAI (D) (AP.T) ... 35.95
- ☐ TEMPLE OF APSHAI (C) (P.T) ... 35.95
- ☐ DATESTONES OF RYN (D.C) (AP.T) ... 17.95
- ☐ DATESTONES OF RYN (C) (P.AT) ... 17.95
- ☐ MORLOC TOWER (C.D) (AP.T) ... 17.95
- ☐ MORLOC TOWER (C) (P.AT) ... 17.95
- ☐ RESCUE AT RIGEL (C.D) (AP.T) ... 26.95
- ☐ RESCUE AT RIGEL (C) (P.AT) ... 26.95
- ☐ HELLFIRE WARRIOR (D) (AP.T) ... 35.95
- ☐ HELLFIRE WARRIOR (C) (P) ... 35.95

BIG FIVE SOFTWARE

- ☐ ATTACK FORCE (T) ... 14.30
- ☐ GALAXY INVASION (T) ... 14.30
- ☐ METEOR MISSION II (T) ... 14.30
- ☐ SUPER NOVA (T) ... 14.30
- ☐ COSMIC FIGHTER (T) ... 14.30

MED SYSTEMS

- ☐ DEATH MAZE 5000 (AP) (D) ... 15.30
- ☐ DEATH MAZE 5000 (T) ... 11.65
- ☐ LABYRINTH (T) ... 11.65
- ☐ RATS REVENGE (T) ... 11.65
- ☐ REALITY ENDS (T) ... 11.65

CALIF. PACIFIC

- ☐ 3-D GRAPHICS (AP) (D) ... 35.95
- ☐ AKALABETH (AP) (D) ... 31.50
- ☐ APPLE (AP) (D) ... 26.95
- ☐ FENDER BENDER (AP) (D) ... 22.50
- ☐ RASTER BLASTER (AP) (D) ... 24.00
- ☐ BUDGE'S SPACE ALBUM (AP) (D) ... 35.95
- ☐ BUDGE'S TRILOGY (AP) (D) ... 26.95

MICRO LAB

- ☐ CROWN OF ARTHUR (AP) (D) ... 31.50
- ☐ DATA FACTORY (AP) (D) ... 130.00
- ☐ MINI FACTORY (AP) (D) ... 85.95
- ☐ DOG FIGHT (AP) (D) ... 26.95
- ☐ MAD VENTURE (AP) (D) ... 22.50

SIRIUS SOFTWARE

- ☐ STAR CRUISER (AP) (D) ... 22.50
- ☐ GORGON (AP) (D) ... 33.00
- ☐ CYBER STRIKE (AP) (D) ... 36.00
- ☐ PHAN TOM FIVE (AP) (D) ... 26.95
- ☐ SPACE EGGS (AP) (D) ... 24.00
- ☐ ORBITRON (AP) (D) ... 26.95

QUALITY SOFTWARE

- ☐ 3D TIC TAC TOE (T) ... 13.55
- ☐ 6502 DISASSEMBLER (AT) ... 10.55
- ☐ ATARI ASSEMBLER (AT) ... 22.50
- ☐ ASTEROIDS IN SPACE (D) (AP) ... 17.95
- ☐ BATTLESHIP COMMANDER (AP) ... 13.55
- ☐ BATTLESHIP COMMANDER (D) (AP) ... 17.95
- ☐ FASTGAMMON (D) (AP.T) ... 22.50
- ☐ FASTGAMMON (AP.T.AT) ... 17.95
- ☐ FRACAS ARITHMETIC (D) (AP) ... 22.50
- ☐ OSI LIGHT PEN (T) ... 17.95
- ☐ SKETCH 80 (T) ... 13.55
- ☐ FORTH (AT) (D) ... 69.00

STRATEGIC SIMULATIONS

- ☐ COMPUTER AMBUSH (D) (AP) ... 51.50
- ☐ COMPUTER BISMARCK (D) (AP.T) ... 51.50
- ☐ MAJOR LEAGUE BASEBALL (D) (AP) ... 31.50
- ☐ COMPUTER CONFLICT (D) (AP) ... 35.00
- ☐ COMPUTER NAPOLEONICS (D) (AP) ... 51.50
- ☐ COMPUTER QUARTERBACK (D) (AP) ... 35.00
- ☐ COMPUTER AIR COMBAT (D) (AP) ... 51.50
- ☐ WARP FACTOR (D) (AP) ... 35.00
- ☐ CARTELS & CUTTHROATS (D) (AP) ... 51.50
- ☐ OPERATION APOCALYPSE (D) (AP) ... 51.50
- ☐ TORPEDO FIRE (D) (AP) ... 51.50

SUB-LOGIC

- ☐ 3D GRAPHICS (AP) ... 45.00
- ☐ 3D GRAPHICS (D) (AP) ... 53.00
- ☐ A-2-FS1 FLIGHT SIMULATOR (AP) ... 22.00
- ☐ A-2-FS1 FLIGHT (D) (AP) ... 29.00
- ☐ T-80-FS1 FLIGHT SIMULATOR (T) ... 22.00
- ☐ 3D GRAPHICS (T) ... 26.50

PERSONAL SOFTWARE

- ☐ CCA MGMT (D) (P.AT) ... 90.00
- ☐ DESK TOP PLAN II (D) (AP) ... 175.00
- ☐ MONTY MORCROFT (D) (AP) ... 31.00
- ☐ VISICALC (D) (AT.P.AP) ... 170.00
- ☐ ZORK (T) (D) ... 32.95
- ☐ VISIDEX (AP) (D) ... 170.00
- ☐ VISIPLOT (AP) (D) ... 162.00
- ☐ VISITERM (AP) (D) ... 135.00
- ☐ VISITREND (AP) (D) ... 210.00

MICROSOFT SOFTWARE

- ☐ ADVENTURE (D) (AP.T) ... 25.50
- ☐ ASSEMBLY DEVELOPMENT (D) (T) ... 80.00
- ☐ BASIC COMPILER (D) (T) ... 175.00
- ☐ EDITOR-ASSEMBLER (T) ... 25.50
- ☐ FORTRAN COMPILER (D) (T) ... 80.00
- ☐ LEVEL III BASIC (T) ... 44.00
- ☐ MoMATH (D) (T) ... 64.00
- ☐ OLYMPIC DECATHALON (D) (T.AP) ... 25.00
- ☐ OLYMPIC DECATHALON (T) ... 25.00
- ☐ TYPING TUTOR (AP.T) ... 13.55
- ☐ TYPING TUTOR (D) (AP) ... 17.95
- ☐ Z-80 SOFTCARD (D) (AP) ... 315.00
- ☐ 16k RAM BOARD (AP) ... 165.00

ON LINE SYSTEMS

- ☐ HI-RES ADVEN #0 (D) (AP) ... 17.95
- ☐ HI-RES ADVEN #1 (D) (AP) ... 22.50
- ☐ HI-RES ADVEN #2 (D) (AP.AT) ... 29.00
- ☐ HI-RES ADVEN #3 (D) (AP) ... 31.00
- ☐ HI-RES FOOTBALL (D) (AP) ... 36.00
- ☐ HI-RES SOCCER (D) (AP) ... 26.95
- ☐ HI-RES CRIBBAGE (D) (AP) ... 22.50
- ☐ MISSILE DEFENSE (D) (AP) ... 26.95
- ☐ SUPERSCRIBE (D) (AP) ... 78.00

BRODERBUND SOFTWARE

- ☐ GALACTIC EMPIRE (AP) (D) ... 22.50
- ☐ GALACTIC TRADER (AP) (D) ... 22.50
- ☐ GALACTIC REVOLUTION (AP) (D) ... 22.50
- ☐ GALACTIC TRIOLOGY (T) (D) ... 35.95
- ☐ TAWALA'S REVENGE (AP) (D) ... 26.95
- ☐ HYPER HEAD ON (AP) (D) ... 22.50
- ☐ GALAXY WARS (AP) (D) ... 22.50
- ☐ ALIEN RAIN (AP) (D) ... 20.00
- ☐ TANK COMMAND (AP) (D) ... 13.55
- ☐ GOLDEN MOUNTAIN (AP) (D) ... 17.95
- ☐ SNOGGLE (D) (AP) ... 22.50

SYNERGISTIC SOFTWARE

- ☐ DUNGEON & WILDERNESS (D) (AP) ... 29.00
- ☐ DUNGEON (D) (AP) ... 15.75
- ☐ ODYSSEY (D) (AP) ... 25.00
- ☐ WILDERNESS (D) (AP) ... 18.00
- ☐ PROGRAM LINE EDITOR (D) (AP) ... 36.00
- ☐ THE LINGUIST (AP) (D) ... 36.00
- ☐ HIGHER GRAPHICS II (AP) (D) ... 31.00
- ☐ HIGHER TEXT II (AP) (D) ... 31.00

SOFTWARE PUBLISHING

- ☐ PERSONAL FILING SYSTEM (AP) (D) ... 85.50
- ☐ PFS REPORT (AP) (D) ... 85.50

SENTIENT SOFTWARE

- ☐ 00-TOPOS (AP) (D) ... 29.70

TG PRODUCTS

- ☐ PADDLES (AP) ... 38.00
- ☐ JOYSTICKS (AP) ... 56.00

Ship the above programs as checked to _____

Mr / Mrs _____

Address _____

City _____

State _____ Zip _____

I have a _____
Name of Computer

with _____ K memory

CREAT COMP/NOV 1981

Number of Programs Ordered _____

Amount of order _____

N.Y. residents add Sales Tax _____

Add shipping anywhere in the U.S. **2.00**

Total amount enclosed _____

Charge my ☐ Master Charge ☐ Visa

Signature _____

Card No _____ Expires _____

Personal Checks please allow 3 weeks

Mail to: **DIGIBYTE SYSTEMS CORP.**
31 East 31st Street, New York, N.Y. 10016

OUTSIDE NEW YORK CALL TOLL FREE (800) 221-3144
IN NEW YORK CALL (212) 889-8975

CIRCLE 173 ON READER SERVICE CARD

TO...STEP, LLIST, LLIST n, LPRINT, PAUSE, PLOT, PRINT AT, PRINT TAB, SCROLL, SLOW, UNPLOT. The missing function is TLS, which was used to return a string minus its first character. This ROM plus an appropriate keypad overlay is available to existing ZX80 users who wish to upgrade their machine. They should note, however, that even with the new ROM they will continue to get the screen flicker which, I'm sure, they've grown to know and love by now.

The machine can be operated in two modes — SLOW (sometimes called 'compute and display'), and FAST. FAST mode offers the world famous screen flicker every time you hit a key, while SLOW mode keeps the screen refreshed at all times, resulting in a nicer display, moving graphics and a lot of irritating delays: see the Benchmarks for comparisons. If you need to see the screen continuously then SLOW mode is a boon. If you don't, say if you were doing lots of calculations, then it's better to use the FAST mode. The two can be called from within a program, thus offering the best of both worlds. The SCROLL feature removes the top line from the screen and moves each line up, leaving a blank bottom line. Without SCROLL, the display freezes when the bottom line is reached. A PAUSE instruction is provided which suspends a program's operation for a user-defined period or until a key is depressed. The screen is visible when in PAUSE mode, regardless of whether the program is running FAST or SLOW. In SLOW mode the screen flickers slightly when the PAUSE takes effect but in FAST mode it has to come on altogether. This means that you'll have to be careful not to have your PAUSEs too close together, unless you actually enjoy watching the screen going absolutely bananas. The INKEY$ function is welcome since it can be tested to see if a key is being depressed and, if so, which key it is. This feature is great for fast-moving games since you need only hit the key you're interested in — there's no need to hit NEWLINE.

There are no DATA or READ instructions but this can be circumvented by saving a program with all its associated variables and then using a GOTO to kick the program off when it's reloaded. (RUN automatically clears any variables.) Pressing CONT, not surprisingly, allows you to continue the program. PLOT and UNPLOT functions (0,0 is in the bottom left-hand corner) are provided, giving a graphics capability of 44 by 64 points. Each point, or pixel (picture element), is a quarter the size of a normal character. Hardly high resolution but better than a poke in the eye with a sharp stick!

The cassette needs either 35mm sockets or an appropriate adaptor. SAVE is offered but no VERIFY, so saving a long program can be a bit worrying. I suggest you first save a few short programs, just to make sure the controls are set properly. When loading a program, the pattern on the screen shows you when data is being recognised. The theory of cassette adjustment is that you play a data tape, gradually turning the volume up until the pattern appears. Then you turn it up a little more and it should be ready for use.

The printer, when it arrives, will allow you to LPRINT and LLIST data and programs respectively. Even better, it will allow you to dump the screen contents to the printer using the COPY command either within the program or as an immediate instruction. Such a screen copy takes about 12 seconds to produce.

The only function to disappear is the TL$ command mentioned earlier. The same thing can be accomplished using the LEN and TO instructions. All trigonometric stuff is in radians and PI is provided to help you unravel the results. SGN = signum which can possess one of three values: −1, 0 and +1. At one stage the new ROM (for the ZX80 and, subsequently, for the ZX81) was expected to offer DRAW, UNDRAW, DATA, READ and RESTORE features. Instead I think the idea of adding printing facilities became more important. After all, these features can be realised using the existing range of commands.

A character string of any length may be used as a numeric variable name, providing it starts with a letter. String variable names are restricted to A$ to Z$. String and numeric arrays may be any number of dimensions — the limit is dictated by the amount of free memory available. String arrays are character arrays really, with the last entry in a DIM statement being the number of characters per array element. With a full 16k RAM and a small program (it fitted on the screen) I set up a string array 100 x 6 x 25 characters long. I used this since each element would be about the size of a name and address record, allowing extra information like telephone number and birthday, for example. Substrings are handled using the TO function. LET A$=B$ (3 TO 5) would make A$ a three character string comprising the third to fifth characters of string B$. This open up possibilities for giant strings and the use of string slicing to extract variable length fields.

Documentation

A programming book is provided with the system: *ZX81 Basic Programming* by Steven Vickers. The cover is a very odd photo (montage?) of what appears to be a couple of model delta-wing jets on top of a solitary skyscraper at night. Two red windows peer at you from the upper floors. It must be full of deep meaning which totally escapes me. Sinclair Research specially commissioned it. Can any psychologist readers tell us what it's all about, please?

Technical Specification

CPU:	NEC Z80A, 3.5 MHz
Memory:	1k RAM expandable to 16k
Keyboard:	Plastic membrane under-surface printed
Screen:	Domestic UHF television
Cassette:	Domestic audio recorder
Firmware:	8k ROM containing Basic and operating system

Binary Operations

+ − * / ** = > < <= >= <>

Statements (all except INPUT may be used as commands)

CLEAR	CLS	CONT	COPY	DIM	FAST	FOR..TO..(STEP)		GOSUB
GOTO	IF..THEN		INPUT	LET	LIST	LLIST	LOAD	LPRINT
NEW	NEXT		PAUSE	PLOT	POKE	PRINT (TAB)		(AT)
RAND	REM	RETURN		RUN	SAVE	SCROLL		SLOW
STOP	UNPLOT							

Functions

ABS	ACS	AND	ASN	ATN	CHR$	CODE	COS	EXP	INKEY$
INT	LEN	LN	NOT	OR	PEEK	PI	RND	SGN	SIN
SQR	STR$	TAN	USR	VAL					

Benchmark Timings (in seconds)

	Slow	Fast	ZX80
BM1	17.7	4.5	1.5
BM2	27.2	6.9	4.7
BM3	65.3	16.4	9.2
BM4	63.0	15.8	9.0
BM5	74.2	18.6	12.7
BM6	199.3	49.7	25.9
BM7	275.6	68.5	39.2
BM8	91.6	22.9	couldn't be done

The *pfs*: software series

A Personal Information Management System.

Your APPLE* computer really can track purchase orders and inventory, analyze your investment records, maintain client and patient histories, or even catalog magazine abstracts and your stereo collection. Software Publishing Corporation has the answer and it doesn't require programming!

We call it the PFS software series—an easy to use yet powerful set of programs that let you design a system that's versatile enough to manage almost any kind of information.

PFS, the personal filing system, lets you design your own form on the screen for organizing information. Once it's created you just fill in the blanks. Looking up what you've filed is just as easy. PFS can search for a number, a single piece of data, a word within a page of text, or any combination. All forms that match are displayed on the screen for browsing, updating, expanding, or printing. PFS can even create mailing labels.

PFS: REPORT, the personal report system, uses the files PFS creates to produce a report tailored to your specifications. Just mark the information you want listed and PFS: REPORT will sort it and let you specify headings, totals, averages, counts, and calculations. You can save your report design for use on a regular basis.

*requires a 48K, 16-sector disk based APPLE II system

PFS and PFS: REPORT come with simple self teaching manuals plus a support plan that includes program updates and factory experts ready to answer your questions. And all of this at an affordable price. Each program is priced below $100.

The PFS software series is different. It is not a specialized application package nor a complex programmer oriented data base manager. It's a personal information management system that lets you store, retrieve, and report information your way without programming. The PFS software series is available through your local dealers. If they don't carry it have them give us a call at (415) 962-8911 or write to us at Software Publishing Corporation, 2021 Landings Drive, MtnView, CA 94043.

PFS is a trademark of Software Publishing Corporation.

APPLE* is a registered trademark of Apple Computer, Inc.

Software Publishing Corporation

CIRCLE 269 ON READER SERVICE CARD

Oo-Topos, the first and only adventure program written directly for Microcomputers by a science fiction writer. Now, Michael Berlyn, author of Crystal Phoenix and Integrated Man transports you to the truly distant, alien world of Oo-Topos. It's an original science fiction tale programmed for adventure.

See your local software dealer and discover Oo-Topos.

Requires DOS 3.3 Applesoft* in ROM

From

SENTIENT SOFTWARE

P.O. Box 4929, Aspen, Colorado 81612
(303) 925-9293

CIRCLE 230 ON READER SERVICE CARD

©1981 by Sentient Software, Inc. Design and Art by Graformations, Inc.

"...deserves a top spot in the realm of adventuring."
— Softalk Magazine

Exclusively distributed by

SOFTSEL
4079 Glencoe Ave.
Marina del Rey, CA 90291
(800) 421-0180
In CA (213) 822-8933

*Applesoft is a registered trademark of Apple Computer Inc.

The book is written for the novice, and it does a pretty reasonable job. It is infinitely better than the book given out with the ZX80. What a pity, then, that just as the reader is about to key something in for the first time, he encounters the most off-putting (and unnecessary) paragraph in the whole book: 'A message like this, telling the computer to do something straight away, is a command; this particular one is a PRINT command, but also a PRINT statement. Calling it a PRINT statement just specifies its form without referring to how the computer is going to use it. Thus every command takes the form of a statement, but so do some other things — program lines do, as we shall see in Chapter 8.'

The style of the book isn't really to my taste although Steven reveals a lot about himself with his talk of dead tax collectors and expressions like 'Lor', love a duck'. *Eye* fans will be delighted with his reference to *Talbot?* on page 38 (I find the question-mark rather becoming, don't you?). Oddly, error codes are referred to as report codes. Perhaps the idea of associating errors with the machine was just too abhorrent, even if they do happen and even if they are usually the user's fault. Ho hum — more psychologist fodder. There are the usual typographical errors which didn't get cleared up but I couldn't find too many. The only other thing in the manual which actually troubled me was the reference to pounds, shillings and pence in one programming example. My kids (aged ten, eight and six months) didn't know what it was all about and, let's face it, a lot of these machines are going to be bought by, and for, kids.

Potential use

Who would use this machine? Kids will love it (so will Dads) and, at this price, I can't think of a better way of introducing them to the subject. Most courses on computers and especially on Basic programming cost more than the ZX81. In my view you can buy a ZX81, have a lot of fun, learn a bit about computers and Basic programming and decide whether you like it or not. If you don't like it or if you decide to move on to bigger and better things, you can always sell the machine (or give it to ComputerTown). The 16k RAM pack is a must for anyone doing anything remotely serious. The printer, when it arrives, will give you the chance to keep a record of all that interesting stuff you've got locked in the machine. The floating point arithmetic certainly makes the ZX81 a far more useful machine than the ZX80 and I suspect that many people will give it serious consideration as a result. You must bear in mind the sort of limitations imposed by the ZX81's inability to handle files. You can save a program with all its variables on tape, which gives you 16k for both programs and data. In my earlier example, I managed to get 100 records of 150 characters each into memory with a short program of 20 lines or so. There's no reason why you shouldn't record the program again with another 100 records, which would overcome this particular limitation. The only problem you'd be left with, then, is the fact that other programs cannot access the same data. I think that if you're really worrying about this sort of thing then maybe you require a more substantial system.

Expansion possibilities for the ZX81 are limited at the moment to the printer and the 16k RAM pack. I asked Clive Sinclair if there was any chance of disks being developed and he gave the same enigmatic answer he gave a year ago when I asked the same question about the ZX80: 'We're working on it.' Draw your own conclusions.

Conclusions

He's done it again. Uncle Clive has come up with a lovely product which will have enormous appeal to people wanting to find out more about computers, but without it costing them an arm and a leg. The idea of producing a superior machine to the ZX80 and selling it for a lower price is absolutely wonderful. I'm full of admiration for the man. Most people would have upped the spec and held the price ('It really hurts me to do this') or even increased it slightly. The product is clearly aimed at the home market and I'm sure that it will do extremely well there, far better in fact than the ZX80. And *that's* rapidly becoming the biggest selling micro in the world!

People who are wondering about its relevance to business or serious work at home ought to sit down and do a few calculations on just how much information they need to hold and how they wish to access it. You could hold 100 or so names and addresses or keep track of around 600 financial transactions in one load of the 16k memory. These figures allow for a fairly simple entry and enquiry program in each case. By abbreviating information you can clearly cram more in. By splitting your information across several tapes you can build a substantial file of information but each tape would have to be managed by a separate version of the program.

If you know nothing about computers and you want to enjoy finding out about them, then this machine offers a value for money way of doing just that. Children will love the ZX81, there can be no question about that, and I suspect that more than a few people who are already familiar with computers will buy one, just to have a bit of fun. □

We don't play hard to get.

Fast, reliable delivery of personal computer software programs.

If you have an Apple or TRS-80 computer, Minnesota Software Inc. has hundreds of programs — in stock and available right now by mail order.

Choose from entertainment, learning or home-application programs. All software is immediately available and features a money back guarantee.

TO GET A COPY OF OUR NEW CATALOG, CONTACT JOHN WEST. PHONE 612/426-0916. SOURCE — TCH122. MICRONET — 70040,555. OR DROP US A NOTE.

MINNESOTA SOFTWARE, INC.

5422 Fisher St. White Bear Lake, MN 55110

Apple is a registered trademark of Apple Computers. TRS-80 is a registered trademark of Radio Shack, A Tandy Corp.

CIRCLE 166 ON READER SERVICE CARD

← CIRCLE 230 ON READER SERVICE CARD

Authoring Systems for the Apple

David Lubar

Recognizing that many teachers aren't satisfied with the limited flexibility of many of the available software packages, and that most teachers don't have time to develop their own programs, several companies have produced authoring systems. This is a rather fascinating concept: the programs are designed to write programs. We recently received four authoring systems for the Apple. The crucial factors in evaluating them were ease of use, flexibility, and quality of the end product. On these and other criteria, the programs ranged from good to abominable.

Zenith Educational System

The Zenith Educational System (no relation to Heath/Zenith), is highly flexible but, as a result of this, complicated to use. In essence, the user builds lessons from modules, combining text pages, graphs, and graphics. For each question in a test, up to four possible answers are allowed. In other words the teacher can enter a question such as "If you had three pencils and gave two away and lost one, how many would you have?" and enter as correct answers "0," "zero," "none," and "nothing." Graphics can be tied into any frame of a lesson, and animated sequences can be set up, adding life to lessons. The program also allows the teacher to enter a hint for each question, and a response for correct answers.

Another feature of the Z.E.S. system is revision questions. These are inserted between regular questions, and are only asked if the student fails on the regular question. Incorrect answers to revision questions cause the program to print a message telling the student to call the teacher. The teacher has the option to continue or terminate the session. There are also automatic questions which are similar to revision questions except that they don't cause the program to halt.

creative computing
SOFTWARE PROFILE

Name: Zenith Education System
Type: Authoring System
System: 48K Apple, Applesoft, Disk drive
Format: 3 Disks
Language: Basic
Summary: Complex, but versatile
Price: $250
Manufacturer:
Avant-Garde Creations
P.O. Box 30160
Eugene, OR 97403

The graphics disk contains a selection of pre-defined shapes, and a program for creating shapes. Once shapes are created, they can be used in frames of the lesson. As a bonus, the flip side of the graphics disk contains a program that quickly initializes multi-boot disks.

The Z.E.S. system also keeps student records that contain such information as number of questions attempted, number correct, and time taken to answer each question.

COMPETENCY EXAM PREPARATION SERIES

This comprehensive set of programs consists of simulated exam modules, a thorough diagnostic package, and a complete set of instructional programs. It is designed to teach concepts and operations, provide drill and practice and assess achievement levels through pre and post testing. The Competency Exam Preparation Series provides a structured, sequential, curriculum encompassing mathematical, reading and writing instruction.

The C.E.P.S. program is designed for individual student use or use in a classroom setting. Programs provide optional printer capability covering worksheet generation and performance monitoring. C.E.P.S. are available in three software formats.

National Proficiency Series	$1,299.00
N.Y.S. Regents Competency Test, Preparation Series	$1,299.00
California Proficiency Assessment Test Preparation Series	$1,299.00

If desired separate Mathematics and Verbal packages are available for $799.00 ea. A Spanish language version of the Mathematics Instruction Package is available at no extra charge.

COLLEGE BOARD PREPARATION SERIES 81/82

for TRS-80 PET, APPLE — NORTHSTAR™ OSI

Each program confronts the user with a virtually limitless series of questions and answers. Each is based on past exams and presents material of the same level of difficulty and in the same form used in the S.A.T. Scoring is provided in accordance with the formula used by College Boards.

S.A.T., P.S.A.T., N.M.S.Q.T., set includes 25 programs covering Vocabulary, Word Relationships, Reading Comprehension, Sentence Completion, and Mathematics. Price $149.95

EDUCATOR EDITION - includes all of the above programs plus detailed solutions and explanations. Price $229.95

Independent Tests of S.A.T. series performance show a mean total increase of 70 points in students' scores.

Update Pack to 81/82 specs. Available to previous owners. Price $69.95

ODYSSEY IN TIME

This spectacular adventure game adds a new dimension of excitement and complexity to **Time Traveler.** Players must now compete with the powerful and treacherous adversary in their exacting quest for victory.

To succeed they must vanquish this adversary in combat that rages across 24 time periods.

Odyssey In Time includes all the challenges of Time Traveler plus 10 additional eras, including those of Alexander the Great, Emperor Asoka of India, Attila the Hun, Genghis Khan. Each game is unique, and may be **interupted and saved** for later play.

available for APPLE & TR-80 PET, 32K - $39.95

ISAAC NEWTON

Perhaps the most fascinating and valuable educational game ever devised — ISAAC NEWTON challenges the players to assemble evidence and discern the underlying "Laws of Nature" that have produced this evidence. ISAAC NEWTON is an inductive game that allows players to intervene actively by proposing experiments to determine if new data conform to the "Laws of Nature" in question. Players may set the level of difficulty from simple to fiendishly complex.

In a classroom setting the instructor may elect to choose "Laws of Nature" in accordance with the complete instruction manual provided.

For insight into some of the basic principles underlying **ISAAC NEWTON** see GODEL, ESCHER, BACH by Douglas R. Hofstadter, Chapter XIX and Martin Gardner's MATHEMATICAL GAMES column in **Scientific American,** October, 1977 and June, 1959 $24.95.

TIME TRAVELER

Confronts players with complex decision situations and the demand for real time action. Using the **Time Machine**, players must face a challenging series of environments that include; The Athens of Pericles, Imperial Rome, Nebuchadnezzar's Babylon, Ikhnaton's Egypt, Jerusalem at the time of the crucifixion, The Crusades, Machiavelli's Italy, The French Revolution, The American Revolution, and The English Civil War. Deal with Hitler's Third Reich, Vikings, etc. At the start of each game players may choose a level of difficulty . . . the more difficult, the greater the time pressure. To succeed you must build alliances and struggle with the ruling powers. Each game is unique.

$24.95

Send $2.00 for complete Catalogue.

$5.00 Discount Coupon included in Catalogue.

PROGRAMS AVAILABLE FOR TRS-80, APPLE II & PET (unless otherwise indicated)

☐ disk or ☐ cassette (please specify)

All programs require 16K. TRS-80 programs require LEVEL II BASIC. APPLE programs require APPLESOFT BASIC

Krell Software Corp.

Send check or money order to
21 Milbrook Drive, Stony Brook, NY 11790
(516) 751-5139

NY State Residents Add Sales Tax

CIRCLE 219 ON READER SERVICE CARD

Authoring Systems, continued...

As mentioned, there is a price for this flexibility. The user can't just sit down and create a lesson. Modules have to be designed part by part. Different disks are required for creating text and graphics. The user must cope with a program disk, a module disk, and a graphics disk, doing a fair amount of disk swapping during the creation of a program. Even if the user has a dual-drive system, he must still use drive one for almost everything.

In essence, the Z.E.S. system allows teachers to create useful programs, but demands planning and effort on the part of the teacher/author.

The Learning Lab

The Learning Lab allows the creation of fill-in, column matching, and multiple-choice tests. The teacher can also create compositions which can be linked to tests.



These compositions are used to provide background on the questions in the test. This system also uses several disks, but takes advantage of a second drive if present. The Master Disk is the entry point for creating tests and viewing student scores. Tests are stored on another disk, and student records kept on a third.

The fill-in test format allows a question, a preferred and alternate answer, and one hint. Column-matching allows ten pairs of phrases and two unmatched phrases for padding out the answer column. Multiple choice allows five answers, the fourth and fifth of which can be "all of the above" and "none of the above."

creative computing
SOFTWARE PROFILE

Name: The Learning Lab

Type: Authoring System

System: 48K Apple, Applesoft, Disk Drive

Format: 2 Disks

Language: Basic

Summary: Constructs fill-in, multiple-choice, and column-matching tests.

Price: $150

Manufacturer:
Micro Lab
2310 Skokie Valley Rd.
Highland Park, IL 60035



Once a test is created, the student can take it in either test or instruction mode. The instruction mode first presents a composition, if one exists for this test, then gives the student several chances to answer the questions, greeting right and wrong answers with canned comments. These comments may not appeal to everyone, but they are part of the program and cannot be changed.

The Learning Lab keeps track of student scores, storing the information on a separate disk. It can also give the teacher statistics about a test, such as the number of times a test was taken, the average score, and the number of questions in the test.

There seems to be one slight bug in the tests. The one we created crashed if the student hit the right arrow followed by return; perhaps the error traps need a bit of work. Aside from this problem and the canned comments, *The Learning Lab* could be fairly useful in a classroom.

Bell & Howell Courseware Development System

Courseware Development System I was the easiest system to use and, though fairly fixed in the format of tests, allowed a surprising amount of flexibility. The system could be used with almost no reference to the documentation. The system is on







creative computing
SOFTWARE PROFILE

Name: Courseware Development Systems I

Type: Authoring System

System: 48K Bell & Howell computer or Apple with Applesoft, Disk Drive

Format: Disk

Language: Basic

Summary: Easy to use

Price: $300

Manufacturer:
Bell & Howell
Audio-Visual Division
Dept. 8876, 7100 McCormick Rd.
Chicago, IL 60645

Now NRI takes you inside the new TRS-80 Model III microcomputer to train you at home as the new breed of computer specialist!



NRI teams up with Radio Shack advanced technology to teach you how to use, program and service state-of-the-art microcomputers...

It's no longer enough to be just a programmer or a technician. With microcomputers moving into the fabric of our lives (over 250,000 of the TRS-80™ alone have been sold), interdisciplinary skills are demanded. And NRI can prepare you with the first course of its kind, covering the complete world of the microcomputer.

Learn At Home in Your Spare Time

With NRI training, the programmer gains practical knowledge of hardware, enabling him to design simpler, more effective programs. And, with advanced programming skills, the technician can test and debug systems quickly and easily.

Only NRI gives you both kinds of training with the convenience of home study. No classroom pressures, no night school, no gasoline wasted. You learn at your convenience, at your own pace. Yet you're always backed by the NRI staff and your instructor, answering questions, giving you guidance, and available for special help if you need it.

Training includes new TRS-80 Model III microcomputer, 6-function LCD Beckman multimeter, and the NRI Discovery Lab with hundreds of tests and experiments.

(TRS-80 is a trademark of the Radio Shack division of Tandy Corp.)

Circle No. 288 on Readers' Service Card

You Get Your Own Computer to Learn On and Keep

NRI training is hands-on training, with practical experiments and demonstrations as the very foundation of your knowledge. You don't just program your computer, you go inside it...watch how circuits interact...interface with other systems... gain a real insight into its nature.

You also work with an advanced liquid crystal display hand-held multimeter and the NRI Discovery Lab, performing over 60 separate experiments. You learn troubleshooting procedures and gain greater understanding of the information. Both microcomputer and equipment come as part of your training for you to use and keep.

Send for Free Catalog... No Salesman Will Call

Get all the details on this exciting course in NRI's free, 100-page catalog. It shows all equipment, lesson outlines, and facts on other electronics courses such as Complete Communications with CB, TV, Audio and Video, Digital Electronics, and more. Send today, no salesman will ever bother you. Keep up with the latest technology as you learn on the latest model of the world's most popular computer. If coupon has been used, write to NRI Schools, 3939 Wisconsin Ave., Washington, D.C. 20016.

NRI SCHOOLS

NRI Schools
McGraw-Hill Continuing Education Center
3939 Wisconsin Avenue
Washington, D.C. 20016

NO SALESMAN WILL CALL.
Please check for one free catalog only

All career courses approved under GI bill
☐ Check for details

☐ Computer Electronics including Microcomputers
☐ Color TV, Audio, and Video System Servicing
☐ Electronics Design Technology
☐ Digital Electronics
☐ Communications Electronics • FCC Licenses • Mobile CB • Aircraft • Marine
☐ Basic Electronics
☐ Small Engine Servicing
☐ Appliance Servicing
☐ Automotive Servicing
☐ Auto Air Conditioning
☐ Air Conditioning, Heating, Refrigeration, & Solar Technology
☐ Building Construction

Name (Please Print) Age

Street

City State Zip

Accredited by the Accrediting Commission of the National Home Study Council

175-111

Authoring Systems, continued...

one disk, and tests are stored on other disks. Each exercise is made up of units that begin with one or more text pages. The teacher doesn't have to worry about formatting the text; wraparound is automatically avoided during presentation of the test. The text pages, which are optional, can contain background information, lessons, or whatever else the teacher desires. Next comes the question, followed by the first correct-answer group. There can be several correct-answer groups. For each group, the teacher can specify a response to be given if the answer given by the student matches a member of the group. Next, the teacher can specify one or more wrong-answer groups. Again, responses can be entered for when the student matches a member of the group. This could be very useful for questions that many students are likely to answer with specific incorrect replies. The system next asks for a comment to be given for unexpected answers, a message in case the student fails to answer the question, and for any hints the teacher wishes to supply.

```
CORRECT ANSWER GROUP 1

ANSWER #1 EITHER PENDRAGON
ANSWER #2 EITHER
ANSWER #3

WHAT RESPONSE DO YOU WANT TO GIVE IF THE
STUDENT'S ANSWER IS IN THIS GROUP?
VERY WELL DONE!
```

This process continues for as many units as the teacher requires. The test is now ready to use. Earlier, at creation time, the teacher specifies how many incorrect answers should be allowed before the program presents the failure message. Now the teacher has the option of opening the test to all students or creating a roster. If a roster is used, student records are kept. The records show the student's scores for a test, and the aggregate results for each question in an exercise.

```
DO YOU WANT ANOTHER
CORRECT ANSWER GROUP (Y/N)? N
** CORRECT ANSWERS COMPLETE **
DO YOU WANT A
WRONG ANSWER GROUP (Y/N)? Y
WRONG ANSWER GROUP 1
ANSWER #1 MERLIN
ANSWER #2

WHAT RESPONSE DO YOU WANT TO GIVE IF THE
STUDENT'S ANSWER IS IN THIS GROUP?
NO, MERLIN WAS A FRIEND OF ARTHUR'S FATH
ER
```

```
** CORRECT ANSWERS COMPLETE **
** WRONG ANSWERS COMPLETE **
MESSAGE FOR AN UNEXPECTED ANSWER:
SORRY  THAT'S NOT RIGHT
```

```
** CORRECT ANSWERS COMPLETE **
** WRONG ANSWERS COMPLETE **
MESSAGE FOR AN UNEXPECTED ANSWER:
SORRY, THAT'S NOT RIGHT
MESSAGE IF THE STUDENT DOES NOT ANSWER
CORRECTLY IN THE TWEO ALLOWED
YOU BETTER REVIEW CHAPTER SEVEN
```

```
DO YOU HAVE ANY HINTS (Y/N)? Y

HINT #1 HE WAS THE WIFE OF IGRAINE
```

CDS I earns high marks. As mentioned, it was easy to use, and flexible. By using various combinations of the available entry options, a teacher could produce a good lesson disk.

Eureka Learning System

In an attempt to produce a flexible system, the *Eureka Learning System* forces users into a syntax with all the charm and grace of Cobol. Test material is entered in a bizarre fashion in which the teacher must deal with entities and attributes, producing input that resembles code. This is just a part of the problem. These entities and attributes are organized into sentences, using a numbering system. The entry by the teacher at this point resembles an alphanumeric cryptogram. The end result of all this is that sentences can be presented in various ways with varying syntax. Once the teacher manages to create a quiz, it can be presented in several modes. The Practice mode allows one chance, then supplies the correct answer if the student is wrong. No hint or reinforcement is available. The Evaluate mode presents the questions as a test.

The program allows for graphics and hi-res fonts. No shape utility is provided. Instead, the documentation suggests that the teacher should buy one of the commercially available programs for creating shape tables. This is but one of the absurdities and problems in this package. Rarely have we seen software that has no redeeming qualities. Unfortunately, this is one case where there is nothing good to say. To put it bluntly, we cannot recommend this program to anyone.

```
SPACE LEFT     3297

 1-LIST NAMES        2-MODIFY NAME
 3-LIST ENTITIES     4-MODIFY ENTITY
 5-LIST ATTRIBUTES   6-MODIFY ATTRIBUTE
 7-LIST SHAPES       8-MODIFY SHAPE
 9-LIST TEXT         10-MODIFY TEXT
 11-RUN TEST         12-RUN PRACTICE
 13-RUN EVALUATE     14-RUN TEST
 15-RUN TEXT         16-RUN TEST
 17-INSTALL SHAPES   18-EXIT

OPTION ?2

NAME TEXAMPLE
GO TO ADD ?A
ENTER NAME = EXAMPLE
TYPE ?
CLOSE ?

TYPE ?
EXAMPLE
GRAPHIC = 90
?
```

Parting Thoughts

At present, authoring systems have the advantage of allowing teachers to create tailor-made software. The disadvantage is that the structure of the created software is still within the drill-and-practice area. While this type of program can be useful, it pales before some of the professionally produced educational programs on the market. Still, a teacher can get a lot of mileage from an authoring system. For a look at another inexpensive, flexible system, see the review of *Aristotle Apple* from Stoneware (*Creative Computing* Oct., 1980, p. 56). □

creative computing
SOFTWARE PROFILE

Name: Eureka Learning System
Type: Authoring System
System: 32K Apple, Applesoft, cassette or disk
Format: Tape or Disk
Language: Basic
Summary: Not very good
Price: $995
Manufacturer:
Eiconics, Inc.
200 Cruz Alta
Taos, NM 87571

The A2-GE1 Graphics Editor

for the Apple II

You bought your Apple for its graphics capabilities. Now with the **A2-GE1**, you can use those capabilities to the fullest.

With **Object Editor** you can create whatever objects you want in the colors of your choice. You can also type in whatever 3D text you want and in different sizes. And saving an object is as easy as naming it.

Then give the object names to **Motion Programmer** and see how the beautifully laid out keyboard controls will let you switch objects on or off, animate them or add upper or lower case 2D text mixed right in. It's remarkably easy.

You can also record your entire presentation, animation and all, for later use with **Motion Playback**, or just take computer snapshots of scenes with **Slide Show Playback**.

The **A2-GE1 Graphics Editor** requires the A2-3D1 or 3D2 and includes **Object Editor**, **Motion Programmer**, **Motion Playback**, and **Slide Show Playback**. It also includes a special A2-3D2 interface for BASIC programmers.

See your dealer for a demonstration.

Graphics power for the non-programmer!

Video of the Motion Programmer being [illegible] on the Apple II

A2-GE1 Graphics Editor
$34.95 on disk (48K and A2-3D1 required)

A2-3D1 Graphics Package
$59.95 on disk (32K required)

A2-3D2 Enhancement
for color and independent object manipulation
$24.95 on disk (48K and A2-3D1 required)

A2-3D/A Saturn Navigator
a 3D adventure program
$24.95 on disk (48K, A2-3D1 and Applesoft in ROM required)

subLOGIC
Communications Corp.
713 Edgebrook Drive
Champaign, IL 61820
(217) 359-8482
Telex: 206995

For direct order, include $3 for UPS or $5 for first class mail delivery. Illinois residents add 5% sales tax. Visa and Master Card accepted.

Apple is the registered trademark of Apple Computer Inc

CIRCLE 187 ON READER SERVICE CARD

Applesoft Compilers:
A Comparative Evaluation

Helmar Herman

Many Apple owners have waited with great anticipation for an Applesoft Basic compiler. Now, within a span of a few months, four companies have released Applesoft compilers.

Why this interest in Applesoft compilers? And what is an Applesoft compiler anyway?

To understand what a compiler is, and what it can do for you, you must first understand how your Applesoft Basic works.

Interpreter

Applesoft is an interpretive language. Each time a Basic statement is to be executed by Applesoft, Applesoft must re-examine the statement to determine what to do. (Please refer to the sample program in Listing 1.)

```
10 INPUT 'ENTER A NUMBER';NUM
20 PRINT SQR(NUM)
30 GOTO 10
```

Listing 1. Sample Applesoft program.

Every time the program logic goes to a new line, Applesoft must examine the statement. For example, in line 10, Applesoft must determine that it is an INPUT request, that ENTER A NUMBER is to be displayed prior to prompting the operator, and that the response is to be placed in NUM.

When a number is entered, Applesoft will then examine statement 20 and perform the specified action (PRINT). Applesoft will then examine the next statement, 30, and perform the GOTO request.

Whenever a new line is encountered, Applesoft must re-examine the line as though it has never seen it before. It is because of this constant re-examination of statements that interpretive languages are slow.

Another problem with interpretive languages is that whenever program control is to transfer to a new statement (statement 30), Applesoft must spend time looking for the statement to which transfer is to be made. In a large program, this can take a considerable amount of time.

Compiler

A compiler transforms the Basic program into a machine language program. Each statement is examined by the compiler and is converted (compiled) into machine language instructions that perform the specified action.

When the program is run, the compiled machine language program is executed directly by the hardware, without a software interpreter having to examine each line.

When program control is to be transferred to a new statement, the address of the new statement is compiled into the machine language program, thus eliminating the need to search for the statement to which transfer is to be made.

Advantages and Disadvantages

There are various trade-offs with interpreters and compilers. See Figure 1 for a list.

In general, interpreters are much better when developing programs because of the ease and speed of program modification and debugging. Compilers are better when the program is ready for production work because of the speed advantage.

Four Systems Examined

The four systems being examined are Expediter II from On-line Systems, TASC from Microsoft Inc., Applesoft Compiler from Hayden Publications, and Speed Star from Southwestern Data Systems.

In examining these systems, important items to look for are:

1. *Accuracy*. The compiled programs should run *exactly* as the interpreted programs do.
2. *Compatibility*. All functions of the Applesoft interpreter should be supported.
3. *Program Optimization*. The faster and smaller the compiled program, the better.
4. *Communication*. Compiled programs should be able to pass information to and from other compiled programs.
5. *Program Size*. Compiled programs will normally be larger than the interpreted version. If the compiler generates excessively large programs, its usefulness may be limited.

Item	Interpreter	Compiler
Ease of program development	Here the interpreter is far superior. A change to a program can be made and the results tested in just a few seconds.	Whenever a change is made to a program, the program must be recompiled before testing can proceed.
Speed	Interpreted programs run relatively slowly.	Compiled programs run relatively fast.
Size	In general, interpreted programs are smaller.	Compiled programs are generally two to three times larger than interpreted programs.
Remarks	Remarks are to be avoided because they make the program larger and slower. On the other hand, programs without remarks are very difficult to modify.	Since remarks are removed during the compilation process, they may be used as needed.

Figure 1. Tradeoffs between interpreters and compilers.

Helmar Herman, Creative Computer Applications, 19 Shadwell Rd., Nashua, NH 03062.

CRYSTALWARE

APPLE

48K-w/disk

THE FINEST IN FANTASY GAME SOFTWARE

ATARI

40K-w/disk

At Crystal we are doing our best to provide the finest state-of-the-art graphic adventure software in the world. Our list of credits include the first indoor-outdoor graphic adventure, the first multi-disk graphic adventure, and now for the Atari, the first graphic adventure in the world which includes screen scrolling and animation. The era of the text adventure and games which are simple combinations of static graphics and text is rapidly drawing to a close. We attempt to utilize the full potential of your computer. True, many of our games use up to 48K and we only deal in disk products, but there are a lot of users out there who have worked hard to upgrade their systems to the max and we think they deserve games that will give their computer system a run for its money.

★★★ ADVENTURE GAMES ★★★

1-THE HOUSE OF USHER- Haunted house type adventure game with scrolling in the Atari version. Wander the creepy hallways of the three story castle based on Edgar Allen Poe's short story of the same name. Written in graphics, of course, with animation and sound. We have introduced a new mystery for another $100 prize. $29.95/1 disk

2-FANTASYLAND 2041 A.D.- The largest disk based adventure game in the world (that we know of). Enter the Hall of Heroes and prepare yourself for the greatest fantasy-role-playing game you will see for years to come. To win you must survive Congoland, Arabia, King Arthur, Captain Nemo, Olympus (a sea voyage), and Dante's Inferno (Hell itself). In both the Atari and Apple versions it takes up more than 400,000 bytes of memory and uses more than 400 hires screens. The winner of the contest described in the manual with this game will receive $1000.00 and a bronze trophy. We have pushed the award date forward to February 1982 to allow more people to participate in the contest. $59.95/6 disks

3-GLAMIS CASTLE- Yes, Pat and I are on our way to Britain to stay in the dreaded Glamis Castle. If we survive our real life adventure, we'll be measuring it and will be able to provide you with a 3-D game based on this ancient haunted site where King Duncan met his end at the hands of Macbeth. Our good friend, Mark Benioff, after much research, said there's a mystery room that has never been found in this castle and a half beast, half-man creature that guards a treasure therein. Our stay will be covered by the British media and we hope to share our experience with you through the writing of this game. $49.95/2 disks

4-BENEATH THE PYRAMIDS- You are an archaeologist in 1932 and must find your way through the perilous chambers beneath the pyramids to discover a golden statue of the cat goddess Bast. This game is in hires graphics, includes sound, your little man actually moves through the corridors which you can see on the screen. The monsters are animated and very agressive. There is a new $100 prize for the first to solve the mystery, which is a toughie! $29.95/1 disk

★★★ SPACE GAMES ★★★

5-GALACTIC QUEST- An excellent combination of Star Trek and Space Trader. Battle the animated Vegan fighters as you warp from galaxy to galaxy. At the same time, you may land on and trade with hundreds of planets. Super hires graphics and lots of sound. This has been one of our most popular games. $29.95/1 disk

6-SANDS OF MARS- Take an exciting voyage to the planet Mars via the Starship Herman. This game compared to the rest, is second only to Fantasyland 2041 A.D. It includes scrolling on the Atari and hundreds of full screen graphics. You can move your little man through the terrain of Mars; if, of course, you survive the exciting journey to Mars, which occupies the whole first disk. There is a new mystery and another $100 prize just waiting for some clever adventurer out there. Good luck! $39.95/2 disks

★★★ WAR GAMES ★★★

7-WORLD WAR III- You Atari gamers will have to see this in the Atari version to believe it! If your tired of war games which take 15 minutes a move and have a manual the size of a telephone book; but still want a complex, real-time action war game-this is it! It is designed for two arm-chair generals which may manuever up to 128 seperate type of units at a time. The game displays a map of Iran & Iraq in the first scenario and later on you will find yourself moving nuclear submarines and battleships through two world wars. This is not a boring copy of a board based game but an original war game which takes a lot of skill and may take weeks to play. $29.95/1 disk

8-WATERLOO II- If you had been Napolean would you have done a few things differently? Well as you approach this final battle you are equipped with the same forces, face the same opposition, and survey the same terrain which he did. We have done a great deal of research to make this historically accurate as well as extremely complex. Even the angle of sight, fatigue of the individual soldier, and his psychological profile are included in the calculations. Oh by the way, your opposition is no slouch. You may find it more difficult to change the course of history than you think! $49.95/2 disks

★★★ ARCADIA ★★★

9-LASAR WARS- Hires-3d space war simulation. Protect the earth from alien invaders. $29.95

10-LITTLE CRYSTAL- The first of our line of education software, which will be completed by December. It includes a very fine version of Hangman, Mr. Music; which transforms the computer into a piano, Gunk-a hilarious shoot-em up game, and Storytime- an anthology of bedtime stories featuring Herman, the cat, Oscar, the Hamster, and of course, Little Crystal. $39.95

11-IMPERIAL WALKER- A fine game pack written by our Atari programmer, Michael (graphics) Potter. Includes the Walker animation which is superb, Gunfight, and Lasar Nim, a game of 'how many robots'. $29.95

12-ADVENTURE PACK- (#1-4) $112

13-SPACEOUT- (#5-6) $58

14-THE WARRIOR- (#7-8) $64

15-ARCADE- (#9-11) $60

Special Note! For those of you who live near beautiful scenic Silicon Valley, we'll be opening up a store called Country Computer at 7453 Monterey St. in Gilroy. Hopefully, we'll be carrying a full line of Apple and Atari products and invite you to drop in for our Grand Opening ii on September 15.

V/SA

Our order lines are open 24 hrs. a day 7 days a week.

master charge

(408) 778-2966 **CRYSTAL COMPUTER** **17429 Bluejay Dr., Morgan Hill, CA 95020**

CIRCLE 165 ON READER SERVICE CARD

Slightly less important items of interest are:

1. *Speed of Compilation.* Since (in theory) compilation is performed only after the program has been debugged, the program won't be compiled very often. A fast compile is nice, but not a critical factor.

2. *Ease of Use.* The compiler should be easy to use and forgiving in nature. It should be fairly safe to assume, however, that most persons using an Applesoft compiler must be familiar with Applesoft and know how to program.

Also of interest to software authors who may want to market compiled programs is the policy of the compiler company toward distribution of compiled code.

```
5 REM TEST A
10 REM STRING MINIPULATION TEST AND TRY TO CAUSE APPLESOFT FR
20  HOME : INPUT "HIT RETURN TO BEGIN TEST";X$
100  REM  FILL THE STRINGS
105 TEST$ = "A"
110 X$ = "X":Y$ = "X":Z$ = "X"
140  FOR COUNT = 0 TO 250
150 X$ = X$ + "X"
160 Y$ = Y$ + "X"
170 Z$ = Z$ + "X"
175  GOSUB 2000
180  NEXT COUNT
200  REM  FILL ARRAYS WITH THE STRINGS
201  VTAB 12: HTAB 15: PRINT "        ";
205 TEST$ = "B"
210  DIM X$(20),Y$(20),Z$(20)
220  FOR COUNT = 0 TO 19
230 X$(COUNT) = X$
240 Y$(COUNT) = Y$
250 Z$(COUNT) = Z$
255  GOSUB 2000
260  NEXT COUNT
300  REM  STEP DOWN THE CHARACTERS
301  VTAB 12: HTAB 15: PRINT "        ";
305 TEST$ = "C"
307  FOR COUNT = 1 TO  LEN (X$)   1
310 X$ =  LEFT$ (X$, LEN (X$) - 1)
320 Y$ =  LEFT$ (Y$, LEN (Y$) - 1)
330 Z$ =  LEFT$ (Z$, LEN (Z$) - 1)
335  GOSUB 2000
340  NEXT COUNT
1000  PRINT "TEST COMPLETE"
1010  END
2000  REM  ROUTINE TO DISPLAY CURRENT TEST AND COUNT
2010  VTAB,12: HTAB 15
2020  PRINT TEST$,COUNT;
2030  RETURN
```

Listing 2. String manipulation test.

```
5  REM  TEST C
10  REM  TEST OF A BUBBLE SORT
20  HOME : INPUT "HIT RETURN TO BEGIN TEST";X$
30  DIM A(100)
100  REM  FILL THE ARRAY
105 TEST$ = "A"
110  FOR COUNT = 1 TO 100
120 A(COUNT) = 101 - COUNT
125  GOSUB 2000
130  NEXT COUNT
200  REM  SORT THE ARRAY
201  VTAB 12: HTAB 15: PRINT "        ";
205 TEST$ = "B"
210  FOR X = 99 TO 1 STEP - 1
215 COUNT = X: GOSUB 2000
220  FOR Y = 1 TO X
230  IF A(Y)        A(Y + 1) THEN 270
240 A = A(Y)
250 A(Y) = A(Y + 1)
260 A(Y + 1) = A
270  NEXT Y
280  NEXT X
1000  PRINT "TEST COMPLETE"
1010  END
2000  REM  ROUTINE TO DISPLAY CURRENT TEST AND COUNT
2010  VTAB 12: HTAB 15
2020  PRINT TEST$,COUNT;
2030  RETURN
```

Listing 4. Bubble sort test.

```
5 REM TEST D
10  REM  SPEED TEST FOR HEAVY DISK I/O PROGRAM
20  HOME : INPUT "HIT RETURN TO BEGIN TEST";A$
30 D$ = CHR$ (4)
40 TEST$ = "A"
100  REM  OUTPUT THE FILE
110  PRINT D$;"OPEN TESTFILE,D1"
150  FOR COUNT = 1 TO 100
160  PRINT D$;"WRITE TESTFILE"
165  PRINT "THIS IS THE SAMPLE RECORD";COUNT
170  GOSUB 2000
180  NEXT COUNT
190  PRINT D$;"CLOSE TESTFILE"
200  REM  READ THE FILE BACK
210 TEST$ = "B"
220  PRINT D$;"OPEN TESTFILE"
230  FOR CCOUNT = 100 TO 1 STEP - 1
240  PRINT D$;"READ TESTFILE"
250  INPUT Z$,COUNT
260  GOSUB 2000
270  NEXT CCOUNT
280  PRINT D$;"CLOSE TESTFILE"
1000  PRINT "TEST COMPLETE"
1010  END
2000  REM  ROUTINE TO DISPLAY CURRENT TEST AND COUNT
2005  PRINT D$
2007  VTAB 12: HTAB 17: PRINT "        ";
2010  VTAB 12: HTAB 15
2020  PRINT TEST$,COUNT
2030  RETURN
```

Listing 5. Speed test for heavy disk I/O program.

Expected Problems

Programs that call other programs that have been compiled will have to be changed to do a BRUN XXXXXXXX (or BLOAD XXXXXXXX:CALL YYYY) instead of a RUN XXXXXXXX.

Programs that depend on timing loops will have to be modified. For example, suppose a program uses the following statement to pause for a few seconds: 10 FOR X=1 TO 1000:NEXT X. With an interpreted version, this may take 2-3 seconds. With a compiled version, however, it may take only a fraction of a second.

Real-time games will have to be modified to adjust for the speed increase. How would you like it if all of a sudden the balls in your favorite game started whizzing by at five times the speed you're used to?

```
 5 REM TEST B
10 REM PROGRAM SIZE TEST
100 A=1
1010 END
```

Listing 3A. Program size test.

```
 5 REM TEST B
10 REM PROGRAM SIZE TEST
100 A=1
110 B=2
1010 END
```

Listing 3B. Program size test.

The Evan's Report Is In There—Somewhere!

The old-fashioned mess of paper filing systems can drive you over the edge. You waste time and money in inefficient searching and manual sorting. In today's business environment, this is both outdated and unnecessary.

DATADEX, the information organization system from IUS, hands you your valuable information immediately — when you need it from your APPLE II desktop computer.

You view your stored information on the APPLE™ screen or create reports with simple commands. DATADEX provides just the detailed and professional looking reports needed in today's business world.

With DATADEX, management performance is improved using faster, more accessible information and, best of all, DATADEX has been shown to pay for itself in two months of normal secretarial time. Visit your local dealer and experience DATADEX yourself. IUS, 281 Arlington Ave., Berkeley, CA 94707 (415) 525-9452.

DATADEX The Information Organization System. **IUS**

CIRCLE 151 ON READER SERVICE CARD

The Tests

Test A (Listing 2) is a string manipulation test. Being tested is the speed of the compiled version and its vulnerability to Applesoft frees. Since string manipulation requires a fair amount of work by the computer, I would expect a significant time improvement in this test. An Applesoft free, by the way, is a problem that arises in large programs that do a great deal of string manipulation. As the area reserved for strings fills up, Applesoft periodically condenses the strings (also called garbage collection) to free up room at the end for more strings.

Test B (Listings 3A and 3B) is a test to see how large a single statement program is and how much it grows by adding one simple statement. Listing 3A will show you how much overhead each program will have. To this overflow you then add the amount of storage taken by each compiled program statement. The lower the overhead, the better.

Test C (Listing 4) is a general speed test. It uses a bubble sort (one of the slowest) to test the speed of a logic-bound program.

Test D (Listing 5) tests the speed of a heavy disk I/O program. I expect that compiled programs will run at about the same speed as interpretive programs.

See Figure 2 for the results of the tests.

All the compilers tested shared the following features:

1. The compilers produce machine language object code that can be loaded and run with the BRUN command.
2. The compiled program can be placed anywhere in memory. Once compiled for a particular place, it can only run there.
3. Figure 3 shows what commands are not supported by which compilers.
4. Special compiler directive commands are supported via REM statements.
5. Compiled programs cannot be interrupted with Ctl-C.
6. They support local or global variables. Global variables allow you to pass information from one compiled program to another (but not from an un-compiled program to a compiled one).
7. Once started, the compilers can only be interrupted with the Reset key.

TEST	LENGTH	SPEED (C1)	SPEED (C2)	
A(I)	717	23	••	Listing 2.
A(O)	3465	30!	33	
A(M)	4797	13	98	
A(H)	2500	(*1)	14	
A(S)	3222	17	1	
B(I)	38	••	••	Listing 3A.
B(O)	2362	••	11	
B(M)	4028	••	62	
B(H)	376	••	10	
B(S)	2101	••	1	
B(I)	46	••	••	Listing 3B.
B(O)	2384	••	11	
B(M)	4048	••	62	
B(H)	395	••	10	
B(S)	2124	••	1	
C(I)	464	124	••	Listing 4.
C(O)	2964	27	23	
C(M)	5049	40	94	
C(H)	2622	24	15	
C(S)	3070	53	1	
D(I)	594	36	••	Listing 5.
D(O)	3275	32	27	
D(M)	4642	30	94	
D(H)	1937	30	13	
D(S)	2730	30	1	

The top numbers (I) are the interpreter figures;
(O) are the On-Line compile figures;
(M) are the Microsoft compiler figures;
(H) are the Hayden compiler figures;
(S) are the Southwestern compiler figures.

Note—the compiled lengths for each compiler are calculated differently. Length comparisons may not be completely accurate.

(O) compiled length excludes variables.
(M) compiled length includes variables.
(H) compiled length includes non-string variables.
(S) compiled length includes variables.

(C1) is the program run speed.
(C2) is compilation speed (how long does it take the compile).

*When Listing 2 was compiled and run on the Hayden compiler, an error occurred after the 147th loop of test A. The error was OUT OF MEMORY ERROR IN MODULE $0803. In accordance with a suggestion from the manual, I added the following line the program: 145 X=FRE(0). The program then ran in 15 seconds.

Figure 2. Test results.

Expediter II

Expediter II comes with two disks. One for DOS 3.2, and the other for DOS 3.3. The disks are copy protected.

Rather than just producing a machine language program which is then BRUN, the compiler produces a one statement Applesoft program. The one statement is usually 1 CALL 4352. The machine language portion of the program is attached to this single line Basic program. You can thus SAVE, LOAD, and RUN the program exactly as you would any other Basic program.

If you *must* have a BLOADable version of the compiled code, there are instructions on how to accomplish this.

You can also leave "holes" in your compiled code to provide room for such things as the hi-res areas.

One potentially difficult problem is in the method used for string manipulation. Applesoft treats all strings as variable length strings. Thus a 5-byte string and a 60-byte string would take 65 bytes (plus overhead). Expediter treats all strings as fixed length strings. Before compilation you must specify how long the strings are to be. All strings will then be that length. Thus a 5-byte string would still occupy 60 bytes (or whatever string length was specified).

The Ultimate Application Development System

Nothing can compete with the brain when it comes to information storage capacity and speed of data entry and recall — but we're working at it.

Our **SELECTOR-IV™** data base management system will let your microcomputer operate with the flexibility available (up to now) only on larger systems. You can create, maintain and report on files limited in size only by your *CP/M™ compatible operating system or disk storage capacity.

The basis of the power of **SELECTOR-IV™** is our unique method of cross-indexing the information in your files. You can immediately recall records by the contents of any piece of information required — from account numbers to ZIP codes to the date of your last audit. You can update records, individually or all at once. You can create new, uniquely, selected sub-files from existing ones (in the same or a different format), and perform computations in the process. You can define procedures to generate computed invoices, personalized letters, or gummed labels with the information coming from several files at once, and invoke them whenever needed. You can add new items to a record definition and change or delete them at will.

We've come a long way since we released the first information management system in microcomputers. We've listened to your suggestions and incorporated the best of them. We've built screen editing functions into the system which make operating the system as convenient as possible. We've had **SELECTOR-IV's™** documentation produced by our experts emphasizing its use for the novice, the applications developer, as well as, the retailer. Our applications specialists can provide you with a "turnkey" **SELECTOR-IV™** system customized for virtually any requirement.

With **SELECTOR-IV™** and a good word processor program, chances are you won't need any other software.

Look for SELECTOR-IV™ at your local computer retailer, or call:

MICRO•AP

7033 Village Parkway
Dublin, CA 94566
Telephone (415) 828-6697

*CP/M is a registered trademark of Digital Research.

CIRCLE 167 ON READER SERVICE CARD

The good part of this is that there is never any garbage collection. Also, in theory, string operations should be faster. In practice, however, they appear to be slower.

The bad part is that if you have many strings, they must all be as long as the longest one, which may cause a storage problem.

Worse, is that you are not notified if you exceed a string length. The program just keeps on running, wiping out who knows what variables until eventually something vital is destroyed and the program fails.

There is an unusual restriction with this system. All arrays must be defined in the program *physically* ahead of the first use rather than *logically* ahead of the first use. Thus the following program is invalid:

```
10 GOSUB 100
20 A(20)=5
30 END
100 DIM A(20)
110 RETURN
```

The DIM statement at 100 must physically precede the first use at statement 20 even though statement 100 will be executed before statement 20.

Because of this restriction, and because of the common practice of placing DIM statements at the end of programs (for speed), inexperienced users may have trouble with Expediter when compiling off-the-shelf programs.

As far as speed and length of programs, the Expediter sits comfortably between the extremes produced by the tests, though it created the slowest code for the string program. On the other hand it has the fewest unsupported Basic statements of any of the compilers tested.

An annual charge of five times the list price is charged for distribution of compiled code.

On-line Systems, 36575 Mudge Ranch Rd., Coarsegold, CA 93614. $99.

Unsupported Statement	On-line	Microsoft	Hayden	Southwestern
CONT	U	U	S	U
DEF FN	S	*	*	S
DEL	U	U	U	U
HIMEM	U	S	S	S
IF X$ THEN	S	***	S	S S
LIST	U	U	U	U
LOAD	S	U	U	U
LOMEM	U	U	S	S
NEXT	**	S	S	S
NOTRACE	S	U	U	S
RECALL	U	U	U	U
RESUME	U	S	S	U
SAVE	S	U	U	U
SHLOAD	S	U	U	S
STORE	U	U	U	U
TRACE	S	U	U	S
&	S	U	S	****

U = Unsupported
S = Supported

*DEF FN may be defined, but not re-defined.

**A FOR may have one and only one corresponding NEXT.
The following program would be invalid:

```
10 FOR X=1 TO 10
20 IF X=5 THEN NEXT X:GOTO 40
30 PRINT X:NEXT X
40 END
```

***Strings may not be used as a logical argument.
Statements such as IF A$+B$ THEN 100 are illegal.
Statements such as IF A+B THEN 100 are legal.

****Makes the compiler crash.

Figure 3. Unsupported Applesoft statements.

TASC (The AppleSoft Compiler)

The version of TASC that I tested was a pre-release Beta test version, and all test results should be viewed in that light.

TASC is distributed on a DOS 3.2 disk. It can be muffin'd to produce a DOS 3.3 version. The disk I have is not copy protected, and Microsoft has indicated that they have not yet decided whether or not they will copy protect the final production version.

TASC was written in Basic and then used to compile itself—a very intriguing concept.

The output from TASC is a relatively small BLOADable file. The size of the object program is deceptive, however, because in order to run the program, you must first BLOAD the file RUNTIME. RUNTIME contains execution time subroutines which are called by your compiled program. It is approximately 4K long.

It is a slight inconvenience to have to BLOAD RUNTIME every time you want to run a compiled program. On the other hand, the amount of disk space required for each program is reduced.

For frequently used programs, you can simply write an Applesoft program that BLOADs the runtime package and then BRUNs your compiled program.

Unlike the other compilers, TASC can be gracefully interrupted while compiling.

Whenever the program pauses for user information, such as program name, you can enter DOS command by prefixing the response with a Ctl-D.

TASC fared worst in compilation speed, but did reasonably well in execution time. While the runtime routines take a fair chunk of space, the compactness of the compiled code could make up for this in long programs. TASC had more unsupported statements than any of the other compilers.

Microsoft, Inc., 10800 NE Eighth Suite 819, Bellevue, WA 98004. (206) 455-8080. $150.

Hayden Applesoft Compiler

The Hayden compiler is currently available only in 3.2.1 format. Hayden indicates that a 3.3 version is coming and will be shipped free to users who have returned their warranty cards.

Although the disk is not copy protected, the system is shipped with a special "protection device" that must be installed in the game I/O socket.

Hayden was not specific about charges for re-distribution of compiled code. The impression I got was that each request will be handled on an individual basis.

Two extra programs are supplied with the system. The first is the only full color, low-res, single disk copy program I've ever seen. It's quite entertaining. Second is a program to "de-muffin" programs from DOS 3.3 to DOS 3.2. I expect that the second program will disappear on DOS 3.3 versions.

This compiler was the second fastest in compilation and registered favorable execution speeds. On the other hand, each time you want to re-compile a program, you must re-boot! If you are already booted, there is no way to invoke the compiler without booting again. Also, when the compile is done, you must hit the Reset key to exit—a rather strange idea.

The ability to pass data from compiled program to compiled program is limited. All numeric variables must be referenced in the respective programs in exactly the same order. If string variables are shared, then FRE() statements must be inserted into the programs at strategic points.

Like the Microsoft compiler, this one also generates a set of runtime subroutines. These subroutines can either be included in the program or be declared EXTERNAL. If they are external, then they must be BLOADed before execution.

Speed Star

The version of Speed Star that I tested was also a pre-released test version. All test results should be viewed in that light.

Like the Hayden compiler, this one is protected by a device inserted into the game socket. According to Southwestern, the final version will allow you to plug your game paddles into the protection device, thus allowing both to be attached at the same time.

This compiler is lightning fast. The test compiles were done almost instantaneously. Also, repeat compiles are quick because you don't have to reload the compiler each time. However, comparative execution speed varied considerably from test to test. The compiler locates itself at location X'7200' and is invoked with the "8" key.

The address at which Speed Star runs is HIMEM for a 32K system. Unfortunately, it still loads there on a 48K system. The extra 16K does not appear to be useable during the compile process, thus limiting the size of your program.

One nice feature is the ability to include Ctl-C checking logic in the object program automatically. Also, you can have the system check subscripting ranges. These checks, of course, do not come free. They result in a decrease in storage and a slight speed degradation.

There are many times when a significant speed increase can be accomplished just by having one or two Applesoft sub-routines converted to machine language and leaving the rest of the program interpretive. This was the only compiler that allowed interpreter programs to call and pass variables to and receive variables from compiled programs. Although I didn't actually try this feature, it seemed fairly simple, based on the documentation.

Southwestern Data Systems, P.O. Box 582-S, Santee, CA 920071 (714) 562-3670. $85 (introductory price).

Conclusions

I ran one other test on all four of the compilers in which I tried to compile the menu program from The CCA Data Management System. The program works perfectly in interpretive mode. After compiling, I got the following results:

Microsoft: It worked for a while. I was able to define the system configuration, but then it crashed into the monitor.

Online: The screen went blank and then nothing.

Hayden: The menu was displayed, but whenever I tried to enter a number for a valid function, the system beeped and rejected it. Then when I entered an invalid function, the program got an Applesoft error.

Southwestern: The configuration portion ran, but instead of displaying the menu, the program terminated.

Just as an educated guess, I suspect that the compilers are having trouble with the ONERR routines.

I recompiled with the Microsoft compiler and specified inclusion of the RESUME logic. The program worked much better and operated correctly with one minor exception.

At about this time, Microsoft sent me some fixes to their compiler, and wonder of wonders, the problem was solved. The menu now worked perfectly.

I was encouraged by this and tried compiling the SORT portion of the system. A dramatic success. The compiled program ran perfectly and was substantially faster than the interpretive program. I did have to modify the program to change the dynamically dimensioned arrays to statically dimensioned arrays.

The above experience illustrates my concluding statements and conclusions:

The larger and more complex a program is, the less likely it will compile successfully without modification (for example, dynamic arrays).

For one reason or another, off-the-shelf programs will probably not compile successfully without modification and effort.

Recommendation

Before I applied the patches to the Microsoft compiler, I was not ready to recommend any of the compilers.

After running the fixed program, however, the Microsoft compiler would be my recommendation. Although it is by far the slowest, the programs it compiles seem more likely to run successfully. It appears that once again, the tortoise has beaten the hares!

If you have programs that are too large to compile, you may want to consider the Southwestern compiler. It is the only one to support the compilation of subroutines with full data transfer capabilities. As was evidenced with the CCA DMS main menu, however, you may have to fiddle with your program to get it to work. □

POWER
FOR YOUR APPLE



FASTEST- SIX TO SIXTY TIMES FASTER THAN APPLESOFT
MOST POWERFUL- MORE POWER THAN BASIC PASCAL or FORTRAN
EXPANDABLE LANGUAGE BASED
CREATIVE- GROW YOUR OWN LANGUAGE
USER-FRIENDLY- EASIEST FOR YOU TO LEARN



REQUIRES
48K APPLE II or II+ SINGLE DISK
SEE YOUR DEALER OR CONTACT:

applied analytics incorporated
8910 Brookridge Dr. Suite 503 Upper Marlboro, Md. 20870
(301) 627-6650

I'm Interested. Please Send
☐ 160 Page Manual $35.00
☐ Detailed Information

Name _____
Address _____
City _____
State _____ Zip _____

CIRCLE 121 ON READER SERVICE CARD

ATARI™ APPLE™ TRS-80™ PET™

UTILITY MAN — A fantastic collection of 21 super utility programs for the ATARI 400/800™. Included in this series is the now famous MIRROR IMAGE. Retail $99.95. 32K required.

COMMUNICATIONS PACKAGE — Now available for the first time a full modem communications package for the ATARI 400/800™ PERSONAL COMPUTER. This package will allow the user to send or receive BASIC as well as binary files (user to user). It will also allow the down loading of text from any major data base, such as the SOURCE or COMPUSERVE. All kinds of fantastic features are built in: free sectors, auto file unlocking, message received. Retail $49.95. 32K required.



NITE FLYER — A real-time flight simulator. You're flying at night with only your instruments to guide you. Somewhere far in the distance you see a tiny dot: it's the air field! You must successfully land your plane in a given amount of time. Your complete working instrument cluster will help guide you in. Brakes screech, motor drones. This is not a text game, but a real-time flight simulator for the ATARI 400/800™. Joystick required. Retail $24.95. 24K required.

FRAZZLE — This one will really 'frazzle' your nerves. Drive through the maze and avoid touching any of the walls because if you do... ATARI 400/800™ 16K required. Disk only. Retail $9.95.

MAZE ENCOUNTER — You're lost in a 3-dimensional maze. It's up to you to find your way out — which turn to take, which corridor to go down. ATARI 400/800™. Disk only. Retail $9.95. 16K required.

MASTER DISK — Here is the disk filing system you've been waiting for. Store up to 125 disks per directory. Search, list, delete, all in RAM. Have you forgotten what the name of that program was? Enter the first letter and all programs with that first letter will be displayed. (Wild card is automatic). Master Disk contains super fast in RAM sort. ATARI 400/800™. Retail $24.95. 16K required.

INTEL TERM — The intelligent terminal program. Full function interactive terminal, upload files from disk or cassette to remote computer. Down load files from disk, printer, or cassette from a remote computer. Choice of 40-60 column display formats. Changeable while on-line. Single-character codes to transmit frequently-used words or phrases. Displays disk-directory while on-line. Joy stick input. Compatable with MicroNet. "Space War" Written in all machine language. ATARI 400/800™. Disk only. Retail $49.95. 32K required.

THE BROKER — The most comprehensive stock charting and evaluation program ever designed for the ATARI™ Computer System. This package is by far the most professional of its kind. A 30-page instruction manual is included. Two disk drives and 48K required. Retail $99.95. Soon available for the APPLE™.

PACKMAN — No more need be said. If you're not an addict now, you will be shortly. Just like the arcade version. PET/CBM™ on cassette. Retail $24.95. 32K required.

SUPER GALAXCIAN — As the invaders break off and swoop down, you must defend your position. PET/CBM™ on cassette. Retail $24.95. 32K required.

NIGHT DRIVE — You're racing down the highway as the road posts slip by. PET/CBM™. Retail $19.95. 32K required.

ULTRA INVADER — The enemy is lining up for attack and marching toward your position. Defend it to the best of your ability. PET/CBM™. Retail $19.95. 32K required.

PORNOPOLY — You've seen or heard about it on nationwide television or radio and read about it in the newspapers. This is a triple X-Rated adult party game. Requires 2 to 4 players. Hi-Res graphics, board, property, and all transactions handled by the computer. Available for the ATARI™, APPLE™, TRS-80™, and PET/CBM™ Computers. Retail $29.95.

Atari is a trademark of Atari, Inc.
Apple is a trademark of Apple Computer, Inc.
TRS-80 is a trademark of Tandy Corp.
PET/CBM is a trademark of Commodore Business Machines

Computer Consultants of Iowa Ltd.

Computer Consultants of Iowa Ltd.
P. O. Box 427
Marion, Iowa 52302
319-373-1306

CIRCLE 217 ON READER SERVICE CARD

AMMC
ATARI BULLETIN BOARD SYSTEM

THE ATARI™ MASTER MESSAGE CENTER

The Complete and Total Bulletin Board Service for the Atari 800™/Hayes™ Smart Modem.

No additional modules to purchase.

Here are just some of the many features: Mail, Post, Registered Users, Purge Post, Password Log-on, Text and Program Post, All Mail and Post (Time - And - Date Stamped as Sent), Use up to four 810 Disk Drives as one pool of sectors allocated to user-profiles, Mail Pieces, or Post Entries, Dynamically.

We've taken the best of all the bulletin board systems and designed the ultimate program for your Atari™. Written completely in 6502. Plus many more features. All users of the 'AMMC'™ Bulletin Board systems will be checked regularly by CCI, LTD. Any unauthorized use of the 'AMMC'™ by a non-registered user will be prosecuted to the fullest extent of the law.

Computer Consultants Iowa Ltd

Computer Consultants of Iowa Ltd.
P. O. Box 427
Marion, Iowa 52302
319-373-1306

$129.95
48K Minimum
Free Updates

ATARI IS A TRADEMARK OF ATARI, INC
'AMMC' IS A TRADEMARK OF COMPUTER CONSULTANTS OF IOWA
HAYES IS A TRADEMARK OF HAYES MICROCOMPUTER PRODUCTS INC

R.P.M.*

'SNUFF' THE ATARI RPM TESTER

Well ... it's finally arrived! The RPM Tester for the ATARI #810™ disk drive. How would you like to 'SNUFF' out all of those 138,144 errors due to speed? Here is the solution all of you have been waiting for. All it takes is 'SNUFF,' a screw driver, and a few minutes to bring your drive up to factory spec. Hi-res graphics display a working tachometer on the screen that you can adjust to (1) one rpm. Complete with documentation. So easy a child can do it!

$29.95
Diskette

Atari is a trademark of Atari Inc

3M DISKETTES

	Lots of 10	Lots of 50	Lots of 100
740 0 8 SS-SD	3 50 Ea	3 25 Ea	3 00 Ea
744 0 5 • SS SD	2 50 Ea	2 40 Ea	2 19 Ea

Prices subject to change without notice Add 3% shipping and handling Iowa residents please add 3% sales tax Please allow time for checks to clear Prices good in continental U S A

Computer Consultants Iowa Ltd

Computer Consultants of Iowa Ltd.
P. O Box 427
Marion, Iowa 52302
319 373 1306

HEATH

ASSEMBLY LANGUAGE PROGRAMMING

A Continuing Education Course

Greg Greene

I have a friend by the name of Jack Brown. Jack is a software type, that is, he would rather work on problems in software than problems in hardware. "Nothing special about that," you may say, "after all, don't we all have the same affliction? Do we not all pursue the ultimate program? Do we not expound upon the virtues of Basic vs Pascal vs Fortran?"

Each unit has quick 'self-tests' at appropriate places, and an exam at the end.

Well yes we do, but Jack is not content to do things the "easy" way. Jack would rather do it in assembly language. His enthusiasm for bits and bytes knows no bounds and his never-ending zeal to gather converts to his cause brought me to the realization that there must be something to this mysterious way of programming. Therefore I set upon the path of knowledge in search of enlightenment.

Greg Greene, 207-885 Craigflower Rd., Victoria, B.C. Canada V9A 2X4.

It is one thing to seek knowledge, and quite another to gain it. In search of a course of action which would enable me to learn, I looked at several books on assembly language programming for the 8080 microprocessor which my H-8 uses. I found there were quite a few books which explained the instruction set, but few which would enable me to learn how to program. What I needed was something that would give me experience in a controlled fashion so that I could actually do something, rather than just read it from a book. Alas, none of the books could penetrate my thick skull and deposit their knowledge therein.

At this point I noticed that the Heath Company was putting out a home study course in assembly language programming to complement their course in Basic. At the same time I also heard from several friends who had purchased the course that it was not all that good. My friends complained that there were many errors in the printing, and that the course was not organized very well. Also, I was told, the programs presented would not run as they were written on the H-8.

Therefore, I did not buy the course until a local store had it on sale and my continuing search for an alternative had proved fruitless.

The first thing I noticed about "Assembly Language Programming, a Continuing Education Course" was that it was written in an easy, conversational style. Author Willard Nico assumes that the reader knows little of assembly language programming and starts from there. This, for me, was exactly the case. The author also takes the trouble to tell those who have had some experience why he takes this approach. Thus, I believe that even those with experience will not be put off by the way the course is presented. Indeed, they should find it refreshing and a helpful brush-up on some points they may have been overlooking. The introduction clearly states, as all instructional material should, the objectives of the course and the method of achieving them.

MOUNTAIN SOFTWARE

SPECIAL: "THE BOOK"
OF APPLE COMPUTER SOFTWARE.
A MUST FOR ALL APPLE OWNERS.
19.95 SALE 15.50

EXCITING DISCOUNTS
apple® SOFTWARE

FREE OFFER

WITH PURCHASE OF ANY 3 PROGRAMS, YOU WILL RECEIVE FREE THE ORIGINAL ADVENTURE GAME, CONVERTED TO LOAD ENTIRELY INTO 48K RAM ON APPLE. NOTHING LEFT OUT. AMAZING!

SAVE UP TO 40%

☐ CRUSH, CRUMBLE AND CHOMP	29.95	SALE	24.50
☐ POOL 1.5	34.95	SALE	29.50
☐ PULSAR II	29.95	SALE	24.50
☐ ROBOT WARS	39.95	SALE	33.50
☐ GAMMA GOBLINS	29.95	SALE	24.50
☐ GORGON	39.95	SALE	33.50
☐ CARTELS AND CUTTHROATS	39.95	SALE	33.50
☐ SNEAKERS	29.95	SALE	24.50
☐ SABOTAGE	24.95	SALE	20.50
☐ SPACE RAIDERS	29.95	SALE	25.50
☐ WIZARD AND THE PRINCESS	32.95	SALE	30.50
☐ ULTIMA	34.95	SALE	29.50
☐ MYSTERY HOUSE	24.95	SALE	20.50
☐ EPOCH	34.95	SALE	28.50
☐ SPACE EGGS	29.95	SALE	24.50
☐ HI-RES SOCCER	29.95	SALE	24.50
☐ PHANTOMS FIVE	29.95	SALE	24.50
☐ GALACTIC EMPIRE	24.95	SALE	19.50
☐ GALACTIC TRADER	24.95	SALE	19.50
☐ GALACTIC REVOLUTION	24.95	SALE	19.50
☐ SHATTERED ALLIANCE	59.95	SALE	49.50
☐ STARMINES	29.95	SALE	24.50
☐ WARP FACTOR	39.95	SALE	33.50
☐ ZORK	39.95	SALE	33.50
☐ TEMPLE OF APSHAI	39.95	SALE	32.50
☐ REVERSAL	34.95	SALE	29.50
☐ SARGON II	34.95	SALE	29.50
☐ HAYDEN COMPILER	200.00	SALE	165.50
☐ SNOGGLE	24.95	SALE	20.50
☐ DRAGON'S EYE	24.95	SALE	20.50
☐ ALIEN RAIN	24.95	SALE	20.50
☐ ALIEN TYPHOON	24.95	SALE	20.50
☐ HELLFIRE WARRIOR	39.95	SALE	32.50
☐ RASTER BLASTER	29.95	SALE	24.50
☐ STAR WARRIOR	39.95	SALE	29.50
☐ A.B.M.	24.95	SALE	21.50
☐ RESCUE AT RIGEL	29.95	SALE	22.50
☐ ORBITRON	29.95	SALE	21.50
☐ ALKABETH	34.95	SALE	30.50
☐ DEMON DERBY	24.95	SALE	20.50
☐ 3-D SKIING	24.95	SALE	20.50
☐ L.A. LAND MONOPOLY	29.95	SALE	22.50
☐ THE GOLDEN MOUNTAIN	19.95	SALE	14.50
☐ ADVENTURE 1, 2, 3	39.95	SALE	32.50
☐ ADVENTURE 4, 5, 8	39.95	SALE	32.50
☐ ADVENTURE 7, 6, 9	39.95	SALE	32.50
☐ HYPERSPACE WARS	29.95	SALE	25.50
☐ THE PRISONER	29.95	SALE	23.50
☐ THREE MILE ISLAND	39.95	SALE	34.50
☐ FASTGAMMON	24.95	SALE	20.50
☐ HI-RES FOOTBALL	39.95	SALE	32.50
☐ AUTOBAHN	29.95	SALE	23.50
☐ CRANSTON MANOR	39.95	SALE	32.50
☐ CYBER STRIKE	39.95	SALE	32.50
☐ WINDFALL	19.95	SALE	18.50
☐ BRIDGE PARTNER	24.95	SALE	21.50
☐ FRACAS	24.95	SALE	21.50
☐ FLIGHT SIMULATOR	35.95	SALE	29.50
☐ TERRORIST	29.95	SALE	23.50
☐ COMPUTER QUARTERBACK	39.95	SALE	32.50
☐ GAMMON GAMBLER	24.95	SALE	21.50
☐ ODYSSEY	30.00	SALE	26.50
☐ WILDERNESS CAMPAIGN	20.00	SALE	17.50
☐ ESCAPE FROM ARCTURUS	30.00	SALE	26.50
☐ HEAD ON	24.95	SALE	21.50
☐ MONTY PLAYS MONOPOLY	34.95	SALE	31.50

☐ COMPU-SPELL (REQ. DATA DISK)	29.95	SALE	25.50
☐ DATA DISK LEVEL 4	19.95	SALE	18.50
☐ DATA DISK LEVEL 5	19.95	SALE	18.50
☐ DATA DISK LEVEL 6	19.95	SALE	16.50
☐ DATA DISK LEVEL 7	19.95	SALE	18.50
☐ DATA DISK LEVEL 8	19.95	SALE	18.50
☐ DATA DISK SECRETARIAL	19.95	SALE	18.50
☐ COMPU-MATH ARITHMETIC SKILL	49.95	SALE	39.50
☐ COMPU-MATH FRACTIONS	39.95	SALE	33.50
☐ COMPU-MATH DECIMALS	39.95	SALE	33.50
☐ ALGEBRA I	39.95	SALE	33.50
☐ STATISTICS 3.0	29.95	SALE	25.50
☐ COMPU-READ 3.0	29.95	SALE	25.50
☐ SPELLING BEE	29.95	SALE	25.50
☐ PERCEPTION	24.95	SALE	22.50
☐ PRO FOOTBALL PT. PRED	26.95	SALE	21.50
☐ COLLEGE FOOTBALL PT. PRED	26.95	SALE	21.50
☐ WIN AT RACES	39.95	SALE	34.50
☐ WIN AT RACES BOOK	21.95	SALE	19.50
☐ MULTIPLE REGRESSION	29.95	SALE	25.50
☐ THE FORECASTER	26.95	SALE	22.50
☐ STAR GAZER'S GUIDE	30.00	SALE	26.50
☐ LINGUIST	40.00	SALE	30.50
☐ HIGHER TEXT	35.00	SALE	31.50
☐ PROGRAM LINE EDITOR	40.00	SALE	31.50
☐ CROSSWORDS	29.95	SALE	25.50
☐ SUB LOGIC ANIMATION	54.95	SALE	45.50
☐ MICROSOFT COMPILER	395.00	SALE	324.50
☐ MICROSOFT FORTRAN	195.00	SALE	175.50
☐ GEN. LEDGER (CONT.)	250.00	SALE	140.50
☐ ACT. RCVBLE. (CONT.)	250.00	SALE	140.50
☐ ACCT. PAYABLE (CONT.)	250.00	SALE	140.50
☐ MODIFIABLE DATA BASE	79.95	SALE	69.50
☐ MAILING LIST DATABASE	50.00	SALE	40.50
☐ D.B. MASTER (NEW)	229.00	SALE	189.50
☐ VISICALC 3.3	199.95	SALE	169.50
☐ PERSONAL FILING SYS.	97.00	SALE	67.50
☐ PERSONAL REPORT SYS.	97.00	SALE	87.50
☐ VISIPLOT	179.95	SALE	149.50
☐ VISITERM	149.95	SALE	125.50
☐ VISIDEX	199.95	SALE	165.50
☐ VISITREND	259.95	SALE	215.50
☐ PAYROLL BRODERBUND	395.00	SALE	325.50
☐ HOME MONEY MINDER	34.95	SALE	29.50
☐ SUPERSCRIBE	34.95	SALE	29.50
☐ THE ADDRESS BOOK	49.95	SALE	44.50
☐ MAGIC WINDOW	99.95	SALE	84.50
☐ SUPERSCRIBE	89.95	SALE	79.50
☐ APPLE PIE	129.95	SALE	99.50
☐ EASY WRITER PRO	250.00	SALE	199.50
☐ WORD STAR	349.95	SALE	295.50
☐ MAGIC WAND	395.005	SALE	299.50
☐ VIDEX 80 COL.	350.00	SALE	289.50
☐ VIDEX KEY ENHANCER	129.95	SALE	109.50
☐ SUPERTERM 80 COL.	375.00	SALE	309.50
☐ MICROSOFT 16K BOARD	195.00	SALE	150.50
☐ C.P.S. MULTIFUNCTION	239.95	SALE	199.50
☐ MEMOREX DISKETTES	39.95	SALE	24.50
☐ Z-80 CARD	349.95	SALE	289.50
☐ APPLECRATE	59.95	SALE	49.50
☐ HAYES SMARTMODEM	279.00	SALE	249.50

DEDUCT 3% IF PAYMENT ACCOMPANIES ORDER. WE PAY SHIPPING AND IF YOU PHONE YOUR ORDER WE WILL CREDIT $1.00 FOR CALL. CALIFORNIA RESIDENTS ADD 6% SALES TAX. ALL ORDERS SHIPPED FROM STOCK WITHIN 48 HOURS. WE ACCEPT MASTER CARD AND VISA. C.O.D. $ ADD $5.00

NAME _____

STREET _____

CITY _____ STATE _____ ZIP _____

CARD # _____

EXP. DATE _____ SIGNATURE _____

4518 E. ECHO CT., SAN BERNARDINO, CA 92404
PHONE ORDERS (714) 886-0781

★EDU-WARE SPECIAL!

BUY COMPU-SPELL WITH DATA DISK AND RECEIVE 2ND DATA DISK FREE

CIRCLE 244 ON READER SERVICE CARD

Language Course, continued...

There are ten sections, or units, in the course. They start with an explanation of what digital computers are, and what they can do. The course proceeds from the basics of input/output in the beginning units, to the completion of a program that emulates the instructions of the 8080 and shows how each affects the various registers and flags.

This program is called Wise and is worth the price of the course. Each unit has quick "self-tests" at appropriate places, and an exam at the end. Also included is a separate workbook that acts as a test to see if you have absorbed the information, and little drills that require you to write sections of the program by yourself. This technique, together with the introduction of new instructions as they become useful to the program ensure that you progress in a controlled manner. Let's take a look at the units and see what they offer and how they offer it.

First, let me note that there are two appendices, one is a copy of the Heath assembler book, which lists all the mnemonics and the instruction set. The other is a lesson on number sets. You will be directed to these at appropriate spots in the course.

Unit one covers some common definitions which would be new to the novice computerist. These include such things as RAM, ROM, RWM, and a lesson on how to express numbers in binary or hex and convert between them and decimal. This unit also discusses the various registers and flags of the 8080.

Unit two introduces you to programming, explaining what an assembler does, use of the IN, OUT, HLT, JMP, JZ, ANI and MOV instructions. This section shows how, in a typical 8-bit computer, IN and OUT operations are accomplished. These are the basic 'building blocks' of all the programs included in the course.

Unit three introduces such terms as "assembler directives," "source code," "parity," and "stacks." The directives covered are ORG, EQU, END, DB, DS and '*.' New instructions introduced are INX, CPI, JNZ, MVI, DCR, CALL and RET. The section also provides a tour of a typical memory map so you can figure out where to originate your first program. The program you are invited to try is called, "Type My Name Ten Times." You are led through the development of the program, and it is clearly explained why the particular instructions are used.

I think the best way to describe the feeling I had is to ask you to remember how it was when you got your first program—in any language—to run correctly.

At the end of the unit you are invited to try the program on your own computer. I did, and it wouldn't work. The author warns you this might happen, and explains why. I simply followed the directions of the workbook and presto! I had my first assembly language program. I think the best way to describe the feeling I had is to ask you to remember how it was when you got your first program—in any language—to run correctly. I have to admit that making the changes necessary to get it to run on the H-8 taught me a great deal, and that is what I wanted.

Units four, five and six take you through another program, "All Base Conversion," which converts hex to octal, split-octal, decimal and binary. The author uses this program as an example of how to use new instructions and different techniques. Unit six wraps it up with methods for de-bugging and little tricks to make the program run quicker and use less space. Since the conversion program uses different number systems, you learn them also. The author stresses throughout the course, that there are many ways to accomplish the same end and even if yours may take a different route, as long as it gets there it's OK. I found his constant urging to "try it alone" to be just what I needed. My All Base Conversion may not be as short as the author's, but it works!

Units seven to ten, bring you to the Wise program and show you how to use it. Along the way you learn additional instructions and ways to give your programs that professional touch. I must say that despite the clear style and explanations given in the earlier units, I would have understood the various instructions better had I been able to use the Wise program at the start. But you have to walk before you can run, and in a course like this you can always start over if you want. Each time you do, things become a little clearer and you understand a little more.

When you feel that you have it all down pat, you can take the final exam and mail it back to Heath. This is optional, but if you're like me, you'll want that certificate as a mark of your achievement.

A word to the wise: in this course, as in all others, you get out of it only what you put in. So do not skip any of the questions on the self-tests or exams. If you cannot answer them, you have not yet absorbed the material. Go back and try again. If you are really stuck, the answers are all included, but if you have to peek at the answer, make a point of going back and ensuring that you really understand what's going on. Since each unit builds on the information in the previous ones, you will only get further behind if you try to go too fast. I had to go back many times on some of the parts, but I attribute this to the thickness of my skull, rather than to any fault of the course.

Some of the criticisms cited above are valid. There are some mistakes in this book that should not be there. For instance, all of the answer choices for some questions are incorrect, and only the answer sheet has the right one. This is unforgivable in any course, as it creates confusion and resentment on the part of the student.

In some cases, the workbook asks questions that are not covered until the next unit, a very aggravating habit.

All of the programs, when adapted to the particular I/O of your computer, will work. Since you take part in the creation of the programs, you learn, and that's what the course is about. Having completed the course I now understand a lot more about how my computer works. Although I can in no way approximate the "Great Canadian Computer Program," I can see beyond Basic, Pascal and Fortran, and the future is bright indeed. $49.

Heath Co., Benton Harbor, MI 49022. □

NEW From RELIANCE

END YOUR COMPUTER CLUTTER



Available from Stock or Custom Imprinted

For complete catalog write or phone:
RELIANCE Plastics & Packaging Division
225 Belleville Avenue
Bloomfield, N.J. 07003 (201) 748-2222

CIRCLE 299 ON READER SERVICE CARD

FREE SHIPPING

(ONLY IN CONTINENTAL U.S.)

MODEL III DISK KITS

TWO 40/track drive kit and hardware Comes complete with all the necessary hardware and 2 drives of your choice, (MPI or TANDON 40 track) NO SOLDERING OR TRACE CUTTING REQUIRED! COMPLETE EASY TO FOLLOW INSTRUCTIONS INCLUDED 875.95

TWO 80/track drive kit and hardware Same as above 1,095.00

ONE 40/track drive kit with all hardware and your choice of MPI or TANDON 40/track drive (INSTRUCTIONS INCLUDED) 599.99

ONE 80/track drive kit with all hardware and one MPI 80/track drive No soldering! (INSTRUCTIONS INCLUDED) 999.99

TRS-80 MODEL III, 48K, 2 40 Track TANDON or MPI drives 2,095.99

TRS-80 MODEL III, 48K, 2 80 Track MPI drives 2,325.99

1 YEAR WARRANTY

16 K MEMORY 19.95

MODEL I, III APPLE AND EXIDY. Instructions included. (MOD 1 Keyboard requires jumpers. $2.00 extra)

ARCHBOLD SPEED-UP MODIFICATION FOR MOD I TRS-80. RUN UP TO 300% FASTER CPU SPEED! SPEED UP SLOW PROGRAMS WITHOUT SOFTWARE! 45.00

MONITORS

Black and White Monitors 12" (TECO) 129.95

Green Phospher Monitors 12" (TECO) 159.95

AMDEK Black and White 12" Monitor 159.95

AMDEK Green Phopher 12" Monitor 100G 189.95

MODEL I DISK DRIVES

These drives come complete with power supply and chassis. 90 day warranty on disk drives. ALL DRIVES COMPLETELY TESTED PRIOR TO SHIPPING! 40 track drives are fully compatible with TRSDOS, NEWDOS-80, LDOS etc. Fully compatible with the PERCOM DOUBLER and Double density! 80 track drives require MAKE-80 program to run regular software. (SPECIAL! GET A FREE 2 DRIVE CABLE WHEN BUYING 2 or more DRIVES!)

40 TRACK MPI or TANDON DRIVES 319.95

80 TRACK MPI 439.95

DOUBLE SIDED 80 TRACK MPI 579.95

2 DRIVE CABLES 25.95

4 DRIVE CABLES 35.95

SPECIAL DOUBLE SIDED CABLES ..... (CALL $)

MAKE-80 CONVERT 40 TRACK TO 80 TRACK. (SPECIFY MOD I, III) 29.95

DISKETTES

SPECIAL: Brown Bag Diskettes (Verbatim) Bag of 20 . 49.95

SPECIAL: Brown Bag Diskettes 100 Quantity 214.00

VERBATIM DATALIFE DISKETTES Box of 10 ..... 32.50

VERBATIM DATALIFE DISKETTES 100 Quantity 275.00



SPECIAL DISK HOLDER

Holds 50 Diskettes

Reg. Price $35.95

SPECIAL $21.95

PERCOM DOUBLER II (Includes DBLDOS) Doubles storage on Model I disk drives. Installs in Exp. Int. in minutes! Will not effect normal operation! 169.95

NEWDOS-80 (New Version 2) 139.95

LDOS 139.95

DOSPLUS 3.3 ..... 89.95

(Specify Mod I or III)

LYNX TELEPHONE MODEM

AUTO/DIAL AUTO/ANSWER COMPLETE WITH SOFTWARE AND HARDWARE FOR MODELS I AND III

The RS-232 is not needed! Completely assembled. LYNX MODEMS are compatible with ST-80 III also 299.95

ST-80 III: Smart terminal program. Allows saving data to disk or sending data from disk and more! Mod I or III 149.95

PRINTERS

SPECIAL: FREE CABLES AND FREE SHIPPING WITH ALL PRINTERS!

CABLES FOR MODEL I EXPANSION INTERFACE, MOD III, or PMC-80 EXP 100 or PIF-40 only.)

PLEASE SPECIFY WHICH COMPUTER!

HIGH QUALITY DOT MATRIX

EPSON MX-80 (Tractor feed only) 539.95

EPSON MX-80 FT (Tractor and Friction feed) 639.95

EPSON MX-70 (Tractor feed only) 419.95

EPSON MX-100 (Tractor and Friction feed 14.5 wide) . 895.95

EPSON MX-80 Hi-Res Graphics Option 80.95

Add-On Friction Feed Adaptor for MX-80 or MX-70 59.95

OKIDATA MICROLINE 80 (Friction and Pin feed) .. 414.95

OKIDATA MICROLINE 82 (Friction and Pin feed) .. 597.95

OKIDATA MICROLINE 83 ..... 897.95
(Friction, Pin and Tractor feed 14.5")

OKIDATA MICROLINE 82A, 120 cps 625.00
(9x9 matrix w/descenders)

OKIDATA MICROLINE 83A, 120 cps 925.00
(9x9 matrix w/descenders)

TRACTOR FEED ADAPTOR for 80 and 82 ..... 75.00

LETTER QUALITY PRINTERS

The C-itoh Daisy wheel printer is one of the finest Letter Quality printers we've seen. WHY PAY MORE FOR LESS??? Exchange Daisy wheels to get the kind of printing fonts you need. 12-10 pitch. Excellent with Scripsit or Electric pencil. Let's face it, sometimes dot matrix doesn't hack it! (You can use standard Diablo Carbon ribbons with the C-itoh to get crisp "COPY READY" printouts!)

C-ITOH DAISY WHEEL 25 CPS 1,795.25

C-ITOH DAISY WHEEL 45 CPS 1,995.25

C-ITOH TRACTOR FEED 219.95



PMC-80 COMPUTER

16K LEVEL II Fully compatible with all TRS-80 Mod I Software 595.95

PMC-81 COMPUTER 16K LEVEL II with upper/lower case Upper/lower case driver in ROM. Auto key repeat Numeric keypad 4 programmable keys Built in speaker 100% Mod I software compatible 879.99

EXPANDER 100 PMC's expansion interface 32K, disk controller, printer interface (Expands PMC-80/81 to 48K) 499.99

RF-MODULATOR for PMC or TRS-80 to TV Hook-up Completely assembled and tested (Plugs in Video port) UHF CH 33 ..... 39.95

TRS-80 Dak and Other Mysteries Book, 132 pp 22.50

Microsoft Basic Decoded and Other Mysteries, 312 pp 29.95

Custom TRS-80 and Other Mysteries, 300 pp 29.95

CALL TOLL FREE: 800-528-1149

NO SURCHARGE FOR VISA, MASTER CARD OR AMERICAN EXPRESS!!! (10% DEPOSIT REQUIRED ON C O D'S OVER $200.00) Send Certified Check, Money Order or Check

SIMUTEK COMPUTER PRODUCTS INC.

4877 E. SPEEDWAY
TUCSON, AZ 85712
(602) 323-9391

CALL FOR FREE 100+ PAGE CATALOG!!!

TRS-80 IS A TM OF TANDY CORP. PMC-80 IS TM OF PERSONAL MICROCOMPUTERS
PRICES AND SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE

CIRCLE 263 ON READER SERVICE CARD

Home Financial Decisions for the TI 99/4

Irving Rowe

Until a few weeks ago, I had no interest in computers or in programming. All I knew about computers was that when I got a bill from a store which contained an error, it was devilishly difficult to get it corrected.

All that changed suddenly when I was given a TI 99/4 home computer as a surprise gift. Suddenly I burned with a fervor to utilize it to the hilt and to learn how to program it.

When I looked through the Beginner's Basic manual which came with the machine, I felt sure that I would have no difficulty in learning the language, but it would take me some time to become fluent in it. What to do to get started sooner?

I decided to obtain one of the TI Solid State Software Command Modules so that I could quickly use the computer. The *Home Financial Decisions* module seemed like a good one with which to start, since the calculations that it performed should be useful to everyone.

When I plugged the module into the machine, I found that it took over complete control of the computer. This will probably not surprise any of the readers of this magazine, but at first I was a bit miffed that I could not use any of the Basic commands in combination with the module program.

Nevertheless, I proceeded to investigate what the module could do. I found that *Home Financial Decisions* covers four major areas: Loans, Savings, Residence and Car. Each of these areas has from four to six different programs, for a total of 21 individual programs.

I was not convinced that it would be easier to use than a hand-held calculator.

Some of the programs in the Residence and Car sections involve comparisons of different choices and permit analyses over different periods of time. In order to permit a fair comparison of these different conditions, all of the resulting figures are automatically reduced by the module program to present value, the amount of money which, if invested today at a given rate of interest (either in a savings bank or other type of available investment) would equal the value of a financial transaction at the specified future time.



I must admit that I approached the use of the *Home Financial Decisions* with a certain amount of skepticism. Since this was the first time I was about to use the computer, I was not sure how accurate the results would be, nor was I convinced that it would be easier to use than a hand-held calculator. Several years ago, in my pre-computer days, I had purchased an inexpensive hand calculator, the TI Money Manager, which is pre-programmed to calculate annuity and compound interest

Irving Rowe, 35 Ridge Drive, Port Washington, NY 11050.

4MHZ, DOUBLE DENSITY, COLOR & B/W GRAPHICS . . THE LNW80 COMPUTER

When you've compared the features of an LNW80 Computer, you'll quickly understand why the LNW80 is the ultimate TRS80 software compatible system. LNW RESEARCH offers the most complete microcomputer system at an outstanding low price.
We back up our product with an unconventional 6 month warranty and a 10 days full refund policy, less shipping charges.

LNW80 Computer $1,450.00
LNW80 Computer w/B&W Monitor & one 5" Drive $1,914.00
All orders must be prepaid. CA residents please include 6% sales tax.
Contact us for shipping charges

* TRS80 Product of Tandy Corporation.
** PMC Product of Personal Microcomputer, Inc.

COMPARE THE FEATURES AND PERFORMANCE

FEATURES	LNW80	PMC-80**	TRS-80* MODEL III
PROCESSOR	4.0 MHZ	1.8 MHZ	2.0 MHZ
LEVEL II BASIC INTERP.	YES	YES	LEVEL III BASIC
TRS80 MODEL 1 LEVEL II COMPATIBLE	YES	YES	NO
48K BYTES RAM	YES	YES	YES
CASSETTE BAUD RATE	500/1000	500	500/1500
FLOPPY DISK CONTROLLER	SINGLE/ DOUBLE	SINGLE	SINGLE/ DOUBLE
SERIAL RS232 PORT	YES	YES	YES
PRINTER PORT	YES	YES	YES
REAL TIME CLOCK	YES	YES	YES
24 X 80 CHARACTERS	YES	NO	NO
VIDEO MONITOR	YES	YES	YES
UPPER AND LOWER CASE	YES	OPTIONAL	YES
REVERSE VIDEO	YES	NO	NO
KEYBOARD	63 KEY	53 KEY	53 KEY
NUMERIC KEY PAD	YES	NO	YES
B/W GRAPHICS, 128 X 48	YES	YES	YES
HI-RESOLUTION B/W GRAPHICS, 480 X 192	YES	NO	NO
HI-RESOLUTION COLOR GRAPHICS (NTSC), 128 X 192 IN 8 COLORS	YES	NO	NO
HI-RESOLUTION COLOR GRAPHICS (RGB), 384 X 192 IN 8 COLORS	OPTIONAL	NO	NO
WARRANTY	6 MONTHS	90 DAYS	90 DAYS
TOTAL SYSTEM PRICE	$1,914.00	$1,840.00	$2,187.00
LESS MONITOR AND DISK DRIVE	$1,450.00	$1,375.00	---

LNW80

- BARE PRINTED CIRCUIT BOARD & MANUAL $89.95

The LNW80 - A high-speed color computer totally compatible with the TRS-80*. The LNW80 gives you the edge in satisfying your computation needs in business, scientific and personal computation. With performance of 4 MHz, Z80A CPU, you'll achieve performance of over twice the processing speed of a TRS-80*. This means you'll get the performance that is comparable to the most expensive microcomputer with the compatibility to the world's most popular computer (TRS-80*) resulting in the widest software base.

FEATURES:

- TRS-80 Model 1 Level II Software Compatible
- High Resolution Graphics
  - RGB Output - 384 x 192 in 8 Colors
  - NTSC Video or RF MOD - 128 x 192 in 8 Colors
  - Black and White - 480 x 192
- 4 MHz CPU
- 500/1000 Baud Cassette
- Upper and Lower Case
- 16K Bytes RAM, 12K Bytes ROM
- Solder Masked and Silkscreened

LNW SYSTEM EXPANSION

- BARE PRINTED CIRCUIT BOARD
  AND MANUAL $69.95
  WITH GOLD CONNECTORS $84.95

The System Expansion will allow you to expand your LNW80, TRS-80*, or PMC-80** to a complete computer system that is still totally software compatible with the TRS-80* Model 1 Level II.

FEATURES:

- 32K Bytes Memory
- 5" Floppy Controller
- Serial RS232 20ma I/O
- Parallel Printer
- Real Time Clock
- Screen Printer Bus
- On Board Power Supply
- Solder Masked and Silkscreened

LNW RESEARCH
CORPORATION

2620 WALNUT
TUSTIN CA. 92680

CIRCLE 278 ON READER SERVICE CARD

ORDERS & INFO. NO. 714-544-5744
SERVICE NO. 714-641-8850

LNDoubler & DOS PLUS 3.3D

- Assembled and Tested W/DOS PLUS 3.3D.....$175.00

Double-density disk storage for the LNW Research's "System Expansion" or the Tandy's "Expansion Interface". The LNDoubler™ is totally software compatible with any double density software generated for the Percom's Doubler***. The LNDoubler™ provides the following outstanding features.

- Store up to 350K bytes on a single 5" disk
- Single and double density data separation
- Precision write precompensation circuit
- Software switch between single and double density
- Easy plug in installation requiring no etch cuts, jumpers or soldering
- 35, 40, 77, 80 track 5" disk operation
- 120 day parts and labor warranty

*** Doubler is a product of Percom Data Company, Inc.

DOS PLUS 3.3D

Micro Systems software's double density disk operating system. This operating system contains all the outstanding features of a well developed DOS, with ease in useability.

KEYBOARD

LNW80 KEYBOARD KIT $94.95

The Keyboard Kit contains a 63 key plus a 10 key, P.C. board, and remaining components.

CASE

LNW80 CASE $84.95

The streamline design of this metal case will house the LNW80, LNW System Expansion, LNW80 Keyboard, power supply and fan. LNDoubler™, or LNW Data Separator. This kit includes all the hardware to mount all of the above. Add $12.00 for shipping

PARTS AVAILABLE FROM LNW RESEARCH

4116 - 200ns RAM
- 6 chip set $26.00
- 8 chip set $33.50
- 16 chip set $64.00
- 24 chip set $94.00
- 32 chip set $124.00

- LNW80 "Start up parts set" LNW80-1 . . . . . $82.00
- LNW80 "Video parts set" LNW80-2 . . . . . $31.00
- LNW80 Transformer LNW80-3 . . . . . $18.00
- LNW80 Keyboard cable LNW80-4 . . . . . $16.00
- 40 Pin computer to expansion cable $15.00
- System Expansion Transformer $19.00
- Floppy Controller (FD1771) and UART (TR1602) . . . $30.00

VISA MASTER CHARGE ACCEPTED

UNLESS NOTED ADD $3 FOR SHIPPING

problems. I worked out numerical solutions for each of the 21 programs in the *Home Financial Decisions* module and then compared the results obtained by using the Money Manager.

The first four programs in the Loan area of the module yield (a) the amount of money you can borrow at a given interest rate if you specify the size and number of monthly payments you are willing to make; (b) the size of monthly payments required to repay a given loan in a specified number of months; (c) conversely, the number of months required to pay off a loan if you indicate the size of each monthly payment; and (d) the size of the down payment which is needed for a particular purchase if you specify both the size and the number of monthly payments to be made.

I found that I could do the same calculations on my hand-held calculator almost as quickly as with the computer, since these are relatively simple compound interest problems.

The fifth program in this area tells the user how much money is needed to pay off a loan early, before the specified number of payments has been made. This requires two separate operations on the Money Manager, so here the computer clearly has the advantage. Furthermore for each of these programs the computer gave the total amount of interest paid under the indicated conditions. This would have been another operation on the calculator. I obtained the same answers with both devices.

The Savings area of the module solves four problems: (a) how much money will accumulate in a savings account, given the present balance in the account and a given number of regular deposits when the annual interest rate and rate of compounding interest is known; (b) how much must be deposited each year to accumulate a given amount of money in a given length of time; (c) how long it will take to reach a financial goal if the other factors are indicated; and (d) how much money must be deposited in a savings account to permit a regular series of withdrawals to be made before the account is exhausted. The last program is really an annuity calculation. As in the case of the Loan area, these saving programs are very useful, but I could solve the problems quite easily on the Money Manager calculator.

The Residence section of the module gives analyses related to (a) buying a house; (b) the relative costs of buying house A versus house B; (c) the financial advantages of buying a house versus renting one; (d) the comparative cost of remaining in your present house versus buying a new one; (e) the comparative cost of remaining in your present house versus renting a house or apartment; and (f) the cost of refinancing the mortage on your present house.



When I first performed one of these analyses and compared the results I obtained on the hand calculator, I found serious discrepancies. I soon discovered that the computer module performed a more sophisticated analysis and took more factors into account than I had considered. For example, the computer module considered not only the cost of the mortgage, but also the cost of utilities, insurance and property taxes. It also takes into account the savings due to income tax deductions for mortgage interest payments and for property taxes. Futhermore it shows the effect of an assumed rate of inflation on the future market value of the house and it indicates the owner's equity in the house at any given time.

The final section of the module deals with the purchase and cost of owning an automobile. As is the case for the Residence area, there are six separate programs: (a) the cost of buying a car (b) comparison of buying car A or car B; (c) a comparison of the cost of leasing versus purchasing a car; (d) a comparison of the cost of keeping your present car versus buying a new one; (e) a comparison of the cost of keeping your present car versus leasing a new one; and (f) the amount needed to pay off the loan early, and the total amount of interest paid up to that point. The last program is identical to the "Early Payoff" in the Loan area of the module.

These programs are about as complicated at those in the Residence group. However, here the programs consider depreciation instead of appreciation. The programs also factor in maintenance costs, insurance and the tax savings due to interest payments. The resale value of the automobile is also considered. These factors cannot be predicted accurately, so to this extent, the results of these analyses are estimates rather than exact calculations.

In summary, I believe the *Home Financial Decisions* module is very valuable if you are interested in the costs of owning or purchasing a house. It is perhaps even more valuable in considering the costs involved in purchasing or leasing an automobile, since this is likely to occur more often. If even a very small fraction of the cost of either of these large expenditures can be saved through these calculations, it will more than pay the $29.95 price of the module. The Loan and Savings program are also useful but they do not provide as clear-cut an advantage over a hand-held calculator, particularly one which has financial functions programmed in. It would be useful for a real estate office where the displays in the Residence section could be used to help customers choose between available houses.

Texas Instruments, P.O. Box 5012, Dallas, TX 75222. □



"Hi, Frank Carter's the name, data's my game!"

WHY THE MICROSOFT RAMCARD™ MAKES OUR SOFTCARD™ AN EVEN BETTER IDEA.

Memory — you never seem to have quite enough of it.

But if you're one of the thousands of Apple owners using the SoftCard, there's an economical new way to expand your memory dramatically.

16K ON A PLUG-IN CARD.

Microsoft's new RAMCard simply plugs into your Apple II,® and adds 16k bytes of dependable, buffered read/write storage.

Together with the SoftCard, the RAMCard gives you a 56k CP/M® system that's big enough to take on all kinds of chores that would never fit before (until now, the only way to get this much memory was to have an Apple Language Card installed).

GREAT SOFTWARE: YOURS, OURS, OR THEIRS.

With the RAMCard and SoftCard, you can tackle large-scale business and scientific computing with our COBOL and FORTRAN languages. Or greatly increase the capability of CP/M applications like the Peachtree Software accounting systems. VisiCalc™ and other Apple software packages can take advantage of RAMCard too.

And RAMCard gives you the extra capacity to develop advanced programs of your own, using the SoftCard and CP/M. *Even with the RAMCard in place, you can still access your ROM BASIC and monitor routines.*



JOIN THE SOFTCARD FAMILY.

The RAMCard is just the latest addition to the SoftCard family — a comprehensive system of hardware and software that can make your Apple more versatile and powerful than you ever imagined.

Your Microsoft dealer has all the exciting details. Visit him soon, and discover a great idea that keeps getting better.

Microsoft Consumer Products, 400 108th Ave. N.E. Suite 200, Bellevue, WA 98004. (206) 454-1315.

MICROSOFT

CIRCLE 172 ON READER SERVICE CARD

Monday Night at the Flights

SOFTWARE PROFILE

Name: Computer Air Combat

Type: Strategic Air Combat Simulation

System: 48K Apple II+ or II with Applesoft in ROM, one disk drive

Format: Mixed graphics and text

Language: Applesoft

Summary: Great

Price: $59.95

Manufacturer:
Strategic Simulations, Inc.
450 San Antonio Rd.
Suite 62
Palo Alto, CA 94306

Dale Archibald

My regular Monday night wargaming opponent and I had finished playing a computer game about 10:00. Basking in the warm glow of victory for a change, I decided to unwrap my brand new copy of Computer Air Combat, from Strategic Simulations, Inc. (SSI). I jammed the floppy into the disk drive without even looking at the 18-page 8 1/2" by 11" instruction book, game selection card, map boards, aircraft data cards, or any of the other items in the box. After all, we were experienced computer gamers. Only beginners read instructions.

Dale Archibald, 1817 Third Ave. N., Minneapolis, MN 55405.

The screen prompted us to select among multi-player Air Race, solitaire-only V-1 Intercept and Night Fighter, or solitaire/two-player Bomber Intercept, and Dogfight. Since it was late, we decided the V-1 scenario would be best: fast and easy.

We watched the screen and waited for the first V-1 to fly into sight while the lone aircraft flew north forever. My friend left at 10:30 without seeing anything appear, so I grudgingly decided to thumb through the instruction book before I went off to bed. Then I unearthed the game selection card from the assortment of literature in the box. "Eureka," I should have cried.

I finally got to bed about 1:30 a.m. after several unsuccessful V-1 chases. As a writer about computers and games, I have to understand totally how they work, you see. Er, at any rate, I decided to take another little shot at the V-1s after breakfast. Just a few minutes, just to be able to write about the game.

I quit to eat lunch, but didn't turn my Apple II off. In fact, I brought a sandwich to it (first time that's happened). I finally summoned the willpower to shut it down at dinnertime.

It took me the better part of a week to get my mania under control.

By now, you know I like it, of course. SSI and the game designers, Charles Merrow and Jack T. Avery, have come up with a real winner.

Those of you who have played other SSI titles are familiar with the firm's attention to detail. Computer Bismarck, for example, was based on the Nazi pocket battleship Bismarck's attempt to smash through the British Home Fleet. Computer Ambush took a squad step-by-step through a bombed-out village in Occupied France.

Computer Air Combat combines the best features of those games and adds many new twists of its own, particularly the third dimension of altitude.

In Bismarck, the entire game was spent trying to find the enemy. The combat itself was secondary. Not so here.

In Ambush, there were so many factors to consider that it took a long time for the computer to determine what happened. Not so here.

The program uses the flight characteristics of 36 different WWII aircraft as a foundation. These range from the British Spitfire I to the American B-29 Superfortress, the Japanese A6M2 Zero Sen (Zeke) to the German Me 262A-1 jet fighter.

In the Bomber Intercept scenario, for

TWO NEW GAMES FROM SSI FOR THE APPLE AND THE TRS-80!

THE BATTLE OF SHILOH:

TIGERS IN THE SNOW

We know it hasn't been easy for you TRS-80® owners to see so many great made-for-Apple-only games from SSI pass you by. But then, it hasn't been easy for us to design games for a 16K cassette format good enough to meet our critical standards.

After all, we've got a reputation to protect, a reputation in strategy gaming for unsurpassed sophistication, innovation, realism, and playability.

Well, our designers have been hard at work, and we've not only met but surmounted the challenge. We're delighted to announce two historical wargames — deserving of the SSI label — for both the Apple® and the TRS-80® (16K cassette for the TRS-80 Model I and III; 48K disc for Apple II with Applesoft ROM card).

Combining our extensive wargame-design experience and superior programming techniques, we've given a fresh new look and feel to these favorite classic battles.

At $24.95 each for TRS-80 cassette and $39.95 each for Apple disc, these are extraordinary games at quite an ordinary price.

So head on down to your local store and check them out today!

VISA and M/C holders can order by calling 800-227-1617, ext. 335 (toll free). In California, call 800-772-3545, ext. 335.

To order by mail, send your check to: Strategic Simulations Inc. Dept. CC6, 465 Fairchild Drive, Suite 108, Mountain View, California 94043.

All our games carry a 14-day money-back guarantee.

SSI

STRATEGIC SIMULATIONS INC.

As part of our demanding standards of excellence, we use maxell floppy discs.

Apple is a registered trademark of Apple Computer Inc. TRS-80 is a registered trademark of the Tandy Corporation.

CIRCLE 245 ON READER SERVICE CARD

The Newest NEWDOS/80 Version 2.0 For Model I And Model III

THE HOTTEST DISK OPERATING SYSTEM FOR THE TRS-80® COMPUTER IS NOW READY FOR THE MODEL III AND VERSION 2.0 IS READY FOR THE MODEL I. MANY ENHANCEMENTS AND ADDED FEATURES SUCH AS NEW COMMANDS MAKE YOUR COMPUTER MORE POWERFUL!

- **DOUBLE DENSITY ON MODEL I**
  Use of the LNW DOUBLER or the PERCOM DOUBLER to expand storage 80% under NEWDOS/80 Version 2.0, mixing single and double density specifications without any patches.
- **SINGLE DENSITY ON MODEL III**
  Will allow the MODEL III to read disks from MODEL I and to write disks the MODEL I can read, making it easy to move programs between the two machines.
- **EXPANDED DIRECTORIES**
  Directories can be expanded three times the normal number of available entries, even on DOS disks. This is extremely useful when using double density.
- **DYNAMICALLY MERGE IN BASIC**
  To allow sections of BASIC programs to be deleted and replaced with lines from a disk file during program execution. Also allows merging of non-ASC II format files.
- **SELECTIVE VARIABLE CLEARING**
  Allows the programmer to keep some variables and release the space used by the rest; also, specific variables may be erased releasing the space they use.

(CALL OR WRITE FOR MORE INFORMATION ON OUR COMPLETE LINE OF PRODUCTS AND HARDWARE REPAIR SERVICES FOR YOUR TRS-80 COMPUTER)

- **PAGE SCROLLING IN BASIC**
  Scrolling has been modified to allow the user to display programs page by page, in addition to the regular line scrolling.
- **REPEAT FUNCTIONS**
  Keys in MODEL I repeat when held down. Entering "R" as a DOS command causes the previous DOS command to be repeated.
- **ROUTING FOR DEVICE HANDLING**
  To send input and output from one device (display, printer, keyboard, etc.) to others or to a routine in main memory.
- **DISASSEMBLER OUTPUT TO DISK**
  The Disassembler will now write a source code file to disk, which the editor assembler can read and edit.
- **CHAINING ENHANCEMENTS**
  Features to allow chain files to be written from SCRIPSIT; also, chaining may be switched on and off without changing chain file positioning, and may be executed via CMD "xxx" and DOS-CALL
- **SUPERZAP**
  has the ability to scan diskettes or disk files to find the occurences of specific values. Also will generate disk file passwords and hashcode.

MASTER CHARGE AND VISA
WELCOME

Send your card number and expiration date with your order

Apparat, Inc. **$149.00**

4401 South Tamarac Parkway
Denver, Colorado 80237

(303) 741-1778

"On-going Support for Microcomputers"

TRS-80 is a registered trademark of Tandy Corporation

CIRCLE 118 ON READER SERVICE CARD

instance, the player and opponent may choose a total of 16 aircraft of four types (interceptors against bombers and fighter escort) to be deployed. Dogfight matches fighter against fighter, again either randomly or with starting location, altitude, speed, etc., determined by the players. (Even a scramble from ground level is possible.) Yet when I matched five aircraft against the Apple's five, it took just a little over two minutes before it was time for me to move again.

There are general commands for the total flight, and specific commands for the individual planes. Global Plot, for instance, shows all sighted ships, friendly and enemy, as if you were looking down from above. But if an enemy aircraft can't be spotted by one of your pilots, it won't show on the screen until it can be.

The general command Position Report lists all information on sighted aircraft, including X and Y coordinates. You mark these on the map boards in grease pencil.

Status Report describes the damage a friendly aircraft has sustained, and the amount of ammunition remaining.

Movement shows a graphic plot from above of all aircraft 6,000 feet ahead, 2,000 feet behind, and 7,000 feet to the sides of the subject aircraft, at the beginning of the move. Listed underneath is the speed, altitude, and other information about the plane.

Tactical plot shows the same view after movement of all ships of both players.

If an enemy craft is within firing range *and* at the right altitude, *and* if the nose of the ship is at the right angle *and* you have ammunition left, you can fire. Combat can be selected after the Tactical plot. You are asked if you want to fire at possible targets, given the distances, etc.

Of course, there is a Quit and save game feature.

Movement

Moving aircraft to get them into battle is the most complex part of the game, and rightly so. Among other elements, movement depends upon the type of aircraft, speed, direction, altitude, bank and nose attitude. Both players' ships move at the same time, even though they enter their maneuver orders at different times.

There are nine possible maneuvers:

ST-Straight ahead

RR-Roll Right (a selected 45-180 degrees)

RL-Roll Left (same selection)

TR-Turn Right (45-degree direction change)

TL-Turn Left (same change left)

SR-Sideslip Right (move to right without changing heading)

SL-Sideslip Left

NU-Nose Up

ND-Nose Down.

Each maneuver requires a certain distance change, depending upon type, speed, and altitude.

Speed is reduced with every maneuver except ST. It can be altered by throttling back in level flight, climbing, or diving. Go into a climb at too slow a speed, and your ship will stall. When it recovers from its out-of-control dive, your direction and altitude will have changed.



The roll maneuvers are perhaps the most important submaneuvers. (See Figure 1.) These change the bank altitude of the individual aircraft, and that affects turns, sideslips, climbs and dives.

Under the graphic during Movement mode are various listings, such as speed, altitude, present maneuver, etc., and bank. A bank of LV signals that the craft is level. A description of R1 (right roll, one point) means the ship is at a 45-degree angle to the horizon. R2 signals the wings are straight up and down at 90 degrees. The IR designation means the ship is inverted 135 degrees from the horizon, to the right. When it's level, but upside down, the caption is IV.

The ship continues through IL, L2, and L1 back to LV again. On the screen, each position is symbolized by a different graphic. Asking for an ID of any aircraft on the screen elicits its nationality, type, speed, heading, altitude, bank attitude, etc.

One last command is CK for Check capabilities. This gives a three-line summary of the capabilities of the aircraft you're flying, updated as you perform maneuvers.

Other factors in the game are Visibility, Combat Damage, and Ammunition Supply.

Joel Billings, president of SSI, said the company plans to bring out a supplementary disk of other aircraft from other fronts. It will be possible to arrange some very exotic matchups when that comes on the market.

Nevertheless, even with the present game, it will be difficult to exhaust the possibilities. Pilots can be aces, average, or inexperienced; matchups of combatants can be changed; scenarios can be tailored to actual air battles, and so on.

Weak spots? The instructions could be a bit clearer to emphasize certain key points. I'd also like to see illustrations on maneuvers. My friend would enjoy seeing action when moves are made, instead of just a listing of hits. But these are minor complaints.

Overall, I consider this one of the finest computer games of its type I've yet played. It is expensive but well worth $59.95 to those who like this type of strategic, thought provoking pastime. Detailed and comparatively fast-paced, Computer Air Combat is a marvelous game. □

"Thomas! We erase with the DEL Key, not our Pink Pearl!"

MEMOREX
FLEXIBLE DISCS

BUY THE BEST FOR LESS. Lowest prices. **WE WILL NOT BE UNDERSOLD!!** Buy any quantity. Call free (800) 235-4137 for prices and information. Dealer inquiries invited and C.O.D.'s accepted.

VISA

PACIFIC EXCHANGES
100 Foothill Blvd
San Luis Obispo, CA
93401 In Cal. call
(800)592-5935 or
(805)543-1037

CIRCLE 169 ON READER SERVICE CARD

FLIPPING OUT

Dale Archibald

SOFTWARE PROFILE

Name: Raster Blaster
Type: Pinball machine
System: 48K Apple II or II Plus, single disk drive
Format: Graphics
Language: Machine
Summary: Super graphics
Price: $29.95
Manufacturer:
BudgeCo.
428 Pela Ave.
Piedmont, CA 94611

Apple owners who aren't familiar with Bill Budge should make his acquaintance. He was one of the first—and one of the best—at using the color graphics of the Apple to their greatest advantage. Some of his past works include Tranquility Base for Stoneware, and Space Album and Game Trilogy for California Pacific.

With Raster Blaster, Budge has added pinball wizardry to his repertoire. I didn't appreciate how good he was until I saw this game. The color, sound effects, and action are all superb.

As many as four people can play on two difficulty levels. I've only played on the easy level, with ball-saving shields always in place. On hard, the six center targets have to be hit before the shields come on; then, they only last for one ball.

There are two flippers operated by the game paddles, a force gauge to select how hard to shoot the ball, a tilt selector, four lane lights, three side targets, six center targets (small apples), four round center bumpers (large Apples), two side bumpers, Raster Blaster claws that grab a ball once you've hit all six center targets, and spinners.

All these features combine to create an almost perfect pinball game...perfect enough to form calluses on your flipper-pushing thumbs. Lights flash, noises sound, and the ball flips, bumps, and rolls just right.

Extra points are earned for completing all the lane lights, hitting all three side targets, hitting the six center targets and grabbing three balls in the claws (at which point all are dropped for four-ball play).

The "almost perfect" has to do with the operation of the flippers. At times, a ball traveling down the channel toward the flipper will speed up without warning. Also, if a ball is caught on the flipper after rolling down the channel, it doesn't bounce away; it just keeps bouncing off the flipper. But these are minor flaws.

I'm not much of a pinball player myself, but I can see where a person could save a lot of money with this program and a large color TV. For parties it's a natural awe-striker; the graphics are so impressive. It's also a great way to keep the kids away from those nasty folks down at the pinball parlor. Unless, of course, the kids invite them home to help. □

Dale Archibald, 1817 Third Ave. N., Minneapolis, MN 55405.

NEW...FOR APPLE II[1]

FROM PROMETHEUS

VERSAcard

NEW 4 in 1 CARD

1. Serial Input/Output Interface
2. Parallel Output Interface
3. Precision Clock/Calendar
4. BSR Control

ALL ON ONE CARD

with true simultaneous operation . . .at a down-to-earth price!

CHECK THESE FEATURES: True simultaneous operation! VERSAcard's unique hardware selection circuitry makes your Apple "think" that separate cards are installed. This allows VERSAcard interface ports to be compatible with existing software such as APPLE PASCAL, Microsoft Softcard[1,2], and most other Apple software.

The Serial Input/Output port is RS-232C standard. Features include accurate crystal controlled baud rates, half/full duplex operation, and interrupt capability.

The versatile **Parallel Output Interface** is configured for the Centronics standard and is easily configured for other standards. Firmware is available to utilize the graphic features of popular printers such as the Epson.

Precision Clock/Calendar. All standard real-time clock/calendar functions. One second to 99 years time keeping. Battery back-up supplied.

BSR Control. Add an ultrasonic transducer or the Prometheus Direct Connect Option and VERSAcard provides you with BSR remote control. By utilizing the on-board real-time clock and the Prometheus Time and Event Schedular – you can remotely control various accessories in your home and office.

VERSAcard is shipped complete with SOFTWARE for each function contained in an industry standard EPROM. Versatile device drivers permit connection to virtually any standard peripheral. The Prometheus engineering staff is available to help you with any peripheral and special device interface problems. Call us, we'd like to talk with you.

VERSAcard – the only Apple peripheral card you're likely to ever need!

Order: PP-VCD-1 VERSAcard @ $249.00 each.

Compare Key Features	VERSAcard	CPS MultiFunction Card
Parallel, Serial and Realtime Clock Interfaces?	YES	YES
BSR Control Interface?	YES	NO
Compatible w/ Apple Pascal?	YES	NO Special Pascal disk required
Compatible with CP/M?	YES	NO. Special CP/M disk required
Cable Included?	YES. One cable of choice free with each order – through 1981	NO. Must be purchased separately
Apple Modification?	NO	YES

NOTE!

Dealer inquiries invited.

All Prometheus boards are completely tested and burned-in prior to shipment. A one-year warranty covers parts and labor.

Registered Trade Marks (1) Apple Computers, Inc. (2) Microsoft Consumer Products

PROMETHEUS

PROMETHEUS PRODUCTS INCORPORATED

42577 Fremont Blvd. • Fremont, CA 94538 • (415) 490-2370

CIRCLE 282 ON READER SERVICE CARD

creative computing software evaluation

An Old Challenger Bridges New Waters

Dynacomp Bridge Challenger

Owen Linderholm

creative computing

SOFTWARE PROFILE

Name: Bridge 2.0

Type: Bridge-playing game

System: 8K Apple, Atari, Pet, TRS-80, CPM and Disk Drive or cassette

Format: Disk/Cassette

Language: Basic

Summary: Reasonable bridge-playing program

Price: $17.95 for cassette, $21.95 for diskette

Manufacturer:
Dynacomp, Inc.
1427 Monroe Avenue
Rochester, NY 14618

In the December issue of the magazine we carried a review of the "only" two bridge playing programs or machines on the market. One other program that has been available for a year or so was inadvertently left out of the review, so it is presented here. The program is *Bridge 2.0* from Dynacomp; it costs $17.95 on cassette and $21.95 on diskette and is available for almost all the popular microcomputers, including Apple II, Atari, TRS-80, Commodore Pet and CP/M systems. The program itself is of a standard in between that of the two Bridge Challengers mentioned in the earlier article. It bids and plays three of the four hands, thus allowing only one human player.

This program is not a Master player, nor is it especially fast and it will never replace the company of even one other human player, but it could be useful when you are alone and feel like practicing a few hands. The program should also prove useful in training beginning players since it will probably not lose its temper or scream about incompetent, idiotic partners.

The program is written in Basic which means that the impatient card player will have to learn a little patience. In the actual play of the hand the delays are hardly noticeable, but during dealing and sorting the computer can hold up play for as long as twenty seconds. Bidding is somewhat limited since the computer only understands very basic bids. It takes an opening of a suit at the one level as showing 13+ HCP and a strong suit, an opening of two of a suit as 22+ HCP and a strong suit, a INT opening as a balanced hand with 16-18 points. Responses are totally natural and mean exactly what one would expect. No conventions are used at all, so the partners have little information about one another's hands, although they usually end up in the correct contract.

The program plays quite well, especially when it is defending against your contract. It plays less well when it has to defend against a contract. One of the best features of the program is the way it keeps track of the cards and deduces where voids are and who has the high cards in a certain suit. This means that it almost always knows when to pull trumps, ruff tricks and lead to its partner. Nevertheless the program only knows very straightforward tactics during play and cannot finesse or understand conventional leads. I also noticed it leading away from an ace on a few occasions. The program does seem to know how to make a squeeze, but only by using trumps and does so only on occasion.

The program has several disadvantages not directly related to the way it plays bridge. You cannot set up hands to play yourself, so experimentation with interesting hands is practically impossible. It is possible to repeat a hand or a certain series of hands, but the method used to achieve this is very clumsy. There are no graphics in the program, only text. This makes the program less convenient than it could be. One unusual feature of the program is that when you end up as dummy, you play your partner's hand, which lets you practice a bit more than you otherwise might.

```
                BRIDGE 2.0

        (C) 1981 BY DYNACOMP,INC.

ENTEP ANY POSITIVE NUMBER:12
SHUFFLING
DEALING
SORTING


YOUR HAND (SOUTH):
   S: T6
   H: T865
   D: AQJ32
   C: J8

YOU ARE THE DEALER,
WHAT DO YOU BID?

SOUTH?1D
 WEST: 2C
NORTH: PASS
 EAST: 2H
SOUTH?PASS
 WEST: 3C
NORTH: PASS
 EAST: 3H
SOUTH?PASS
 WEST: 4H
NORTH: PASS
 EAST: PASS
SOUTH?PASS


THE CONTRACT IS: 4H
THE DECLARER IS:  EAST


REVIEW OF THE BIDDING:

SOUTH  WEST   NORTH  EAST
1D     2C     PASS   2H
PASS   3C     PASS   3H
PASS   4H     PASS   PASS
PASS


READY TO PLAY?YES


    ROUND:1
    ********
    4H     WE:0   THEY:0
                SOUTH:
                   S: T6
                   H: T865
                   D: AQJ32
                   C: J8
    SOUTH PLAYS 7KS
     WEST PLAYS: 6S
    NORTH PLAYS: 2S
     EAST PLAYS: 4S

    ROUND:2
    ********
    4H     WE:0   THEY:1
     WEST:
        S: QJT
        H: 73
        D: 7
        C: AKT632
                SOUTH:
                   S: 6
                   H: T865
                   D: AQJ32
                   C: J8
     EAST PLAYS: 3S
    SOUTH PLAYS 9KS
     WEST PLAYS: TS
    NORTH PLAYS: 4S

    ROUND:3
    ********
    4H     WE:1   THEY:6
     WEST:
        S: QJ
        H:
        D: 7
        C: AKT
                SOUTH:
                   S:
                   H:
                   D: AQJ32
                   C: J
    SOUTH PLAYS 9ADS
    ERROR IN LEAD, TRY AGAIN.
    SOUTH PLAYS 9AD
     WEST PLAYS: 7D
    NORTH PLAYS: 9D
     EAST PLAYS: 4D

    ROUND:9
    ********
    4H     WE:2   THEY:6
     WEST:
        S: QJ
        H:
        D:
        C: AKT
                SOUTH:
                   S:
                   H:
                   D: QJ32
                   C: J
    SOUTH PLAYS 7ID
     WEST PLAYS: TC
    NORTH PLAYS: KD
     EAST PLAYS: 5D
```

This shows you exactly how the computer plays a certain hand. In the listing is given an example of the way the computer deals and handles the bidding. A few of the rounds played are shown as well. As you can see the final contract was 4H by East which is too high since in another run of this hand I managed to set the contract by three tricks by leading the ace of diamonds followed by a low diamond which is ruffed in dummy. We were then allowed to take two spade tricks, one heart trick and two more diamond tricks. In this example I led the king of spades which was a very poor lead since it lost us the two spade tricks. Later my partner, the computer, lost us one of the diamond tricks by holding on to the king of diamonds and playing it when he had no way of getting back into my hand for the other diamond trick. This happened in rounds eight and nine shown in the listing. My computer partner, North, should have played the king on the ace, leaving me with two more diamond tricks. These mistakes meant that the computer made the contract which could have been set by at least two tricks.

As you can see, the computer plays less well when trying to stop a contract but it does play an adequate game and one that beginners will find challenging. A person who takes bridge seriously would probably have little to gain from the program, but it represents a reasonable value to the casual player or to the beginner. □

CHOOSE...

Choose an Apple Desk

Ideal for an Apple computer system, our bi-level desk has a micro shelf to hold two Apple disk drives. Top level holds monitor, TV, or manuals. 42"w x 29½"d x 35"h.

Choose a Micro Desk

Our Designer Series desk with micro shelf is suitable for the North Ster, Dynabyte, Vector Graphics, and Altos computers. A variety of sizes and colors available.

Choose a Mini Rack

Mini racks and mini micro racks have adjustable Retma rails, standard venting, and cable cut outs. Choose a stand alone bay or desk model. A custom rack is available for the Cromemco.

Choose a Printer Stand

The Universal printer stand fits:

Centronics 700's	Diablo 1600's & 2300's
Dec LA 34	T.I. 810 & 820
NEC Spinwriter	Okidata Slimline
Laar Siegler 300	Anadex 9500's

Delivery in days. 200 styles and colors in stock. DEALER INQUIRIES INVITED.

ELECTRONIC SYSTEMS FURNITURE COMPANY
17129 S. Kingsview Avenue
Carson, California 90746
Telephone: (213)538-9601

CIRCLE 254 ON READER SERVICE CARD

DYNACOMP

Quality software for:*

ATARI	**TRS-80 (Level II)****
PET	**NORTH STAR**
APPLE II Plus	**CP/M Disks/Diskettes**

CARD GAMES

BRIDGE 2.0 (Available for all computers) — Price: $17.95 Cassette/$21.95 Diskette
An all inclusive version of this most popular of card games. This program both BIDS and PLAYS either contract or duplicate bridge. Depending on the contract, your computer opponents will either play the offense OR defense. If you bid too high, the computer will double your contract! BRIDGE 2.0 provides challenging entertainment for advanced players and is an excellent learning tool for the bridge novice. See the software review in 80 Software Critique. Rated #1 by Creative Computing.

HEARTS 1.5 (Available for all computers) — Price: $15.95 Cassette/$19.95 Diskette
An exciting and entertaining computer version of this popular card game. Hearts is a trick-oriented game in which the purpose is not to take any hearts or the queen of spades. Play against two computer opponents who are armed with hard-to-beat playing strategies. HEARTS 1.5 is an ideal game for introducing the uninitiated (your spouse) to computers. See the software review in 80 Software Critique.

STUD POKER (Atari only) — Price: $11.95 Cassette/$15.95 Diskette
This is the classic gambler's card game. The computer deals the cards one at a time and you (and the computer) bet on what you see. The computer does not cheat and *usually* bets the odds. However, it sometimes bluffs! Also included is a five card draw poker betting practice program. This package will run on a 16K ATARI. Color, graphics, sound. See review in COMPUTE.

POKER PARTY (Available for all computers) — Price: $17.95 Cassette/$21.95 Diskette
POKER PARTY is a draw poker simulation based on the book, POKER, by Oswald Jacoby. This is the most comprehensive version available for microcomputers. The party consists of yourself and six other (computer) players. Each of these players (you will get to know them) has a different personality in the form of a varying propensity to bluff or fold under pressure. Practice with POKER PARTY before going to that expensive game tonight! Apple Cassette and diskette versions require a 32K (or larger) Apple II.

CRIBBAGE 2.0 (TRS-80 only) — Price: $14.95 Cassette/$18.95 Diskette
This is simply the best cribbage game available. It is an excellent program for the cribbage player in search of a worthy opponent as well as for the novice wishing to improve his game. The graphics are superb and assembly language routines provide rapid execution. See the software review in 80 Software Critique.

THOUGHT PROVOKERS

MANAGEMENT SIMULATOR (Atari, North Star and CP/M only) — Price: $19.95 Cassette, $23.95 Diskette
This program is both an excellent teaching tool as well as a stimulating intellectual game. Based upon similar games played at graduate business schools, each player or team controls a company which manufacturers three products. Each player attempts to outperform his competitors by setting selling prices, production volumes, marketing and design expenditures etc. The most successful firm is the one with the highest stock price when the simulation ends.

FLIGHT SIMULATOR (Available for all computers) — Price: $17.95 Cassette/$21.95 Diskette
A realistic and extensive mathematical simulation of take-off, flight and landing. The program utilizes aerodynamic equations and the characteristics of a real airfoil. You can practice instrument approaches and navigation using radials and compass headings. The more advanced flyer can also perform loops, half-rolls and similar aerobatic maneuvers. Although this program does not employ graphics, it is exciting and very addictive. See the software review in COMPUTRONICS. Runs in 16K Atari.

VALDEZ (Available for all computers) — Price: $15.95 Cassette/$19.95 Diskette
VALDEZ is a computer simulation of supertanker navigation in the Prince William Sound, Valdez Narrows region of Alaska. Included in this simulation is a realistic and extensive 256 × 256 element map, portions of which may be viewed using the ship's alphanumeric radar display. The motion of the ship itself is accurately modelled mathematically. The simulation also contains a model for the tidal patterns in the region, as well as other traffic (ongoing tankers and drifting icebergs). Chart your course from the Gulf of Alaska to Valdez Harbor! See the software review in 80 Software Critique.

BACKGAMMON 2.0 (Atari, North Star and CP/M only) — Price: $14.95 Cassette/$18.95 Diskette
This program tests your backgammon skills and will also improve your game. A human can compete against a computer or against another human. The computer can even play against itself. Either the human or the computer can double or generate dice rolls. Board positions can be created or saved for replay. BACKGAMMON 2.0 plays in accordance with the official rules of backgammon and is sure to provide many fascinating sessions of backgammon play.

CHECKERS 3.0 (PET only) — Price: $16.95 Cassette/$20.95 Diskette
This is one of the most challenging checkers programs available. It has 10 levels of play and allows the user to change skill levels at any time. Although providing a very tough game at level 4-8, CHECKERS 3.0 is practically unbeatable at levels 9 and 10.

CHESS MASTER (North Star and TRS-80 only) — Price: $19.95 Cassette/$23.95 Diskette
This complete and very powerful program provides five levels of play. It includes castling, en passant captures and the promotion of pawns. Additionally, the board may be preset before the start of play, permitting the examination of "book" plays. To maximize execution speed, the program is written in assembly language (by SOFTWARE SPECIALISTS of California). Full graphics are employed in the TRS-80 version, and two widths of alphanumeric display are provided to accommodate North Star users.

LEM LANDER (32K Apple Disk only) — Price: $18.95 Diskette
Pilot your LEM LANDER to a safe landing on any of nine different surfaces ranging from smooth to treacherous. The game paddles are used to control craft attitude and thrust. This is a real time high res challenge!

FOREST FIRE! (Atari only) — Price: $16.95 Cassette/$20.95 Diskette
Using excellent graphics and sound effects, this simulation puts you in the middle of a forest fire. Your job is to direct operations to put out the fire while compensating for changes in wind, weather and terrain. Not protecting valuable structures can result in startling penalties. Life-like variables are provided to make FOREST FIRE! very suspenseful and challenging. No two games have the same setting and there are 3 levels of difficulty.

NOMINOES JIGSAW (Atari, Apple and TRS-80 only) — Price: $16.95 Cassette/$20.95 Diskette
A jigsaw puzzle on your computer! Complete the puzzle by selecting your pieces from a table consisting of 60 different shapes. NOMINOES JIGSAW is a virtuoso programming effort. The graphics are superlative and the puzzle will challenge you with its three levels of difficulty. Scoring is based upon the number of guesses taken and by the difficulty of the board set up. See review in ELECTRONIC GAMES.

MONARCH (Atari only) — Price: $11.95 Cassette/$15.95 Diskette
MONARCH is a fascinating economic simulation requiring you to survive an 8 year term as your nation's leader. You determine the amount of acreage devoted to industrial and agricultural use, how much food to distribute to the populace and how much should be spent on pollution control. You will find that all decisions involve a compromise and that it is not easy to make everyone happy.

CHOMPELO (Atari only) — Price: $11.95 Cassette/$15.95 Diskette
CHOMPELO is really two challenging games in one. One is similar to NIM: you must bite off part of a cookie, but avoid taking the poisoned portion. The other game is the popular board game REVERSI. It fully uses the Atari's graphics capability, and is hard to beat. This package will run on a 16K system.

**ATARI, PET, TRS-80, NORTHSTAR, CP/M and IBM are registered tradenames and/or trademarks*

***Except where noted, all model I software is available for the Model III. TRS-80 diskettes are not supplied with DOS or BASIC*

DYNACOMP OFFERS THE FOLLOWING

- Widest variety
- Guaranteed quality
- Fastest delivery
- Friendly customer service
- Free catalog
- 24 hour order phone

AND MORE...

STARTREK 3.2 (Available for all computers) — Price: $11.95 Cassette/$15.95 Diskette
This is the classic Startrek simulation, but with several new features. For example, the Klingons now shoot at the Enterprise without warning while also attacking starbases in other quadrants. The Klingons also attack with both light and heavy cruisers and move when shot at! The situation is hectic when the Enterprise is besieged by three heavy cruisers and a starbase S.O.S. is received! The Klingons get even! See the software reviews in A.N.A.L.O.G., 80 Software Critique and Game Merchandising.

BLACK HOLE (Apple only) — Price: $14.95 Cassette/$18.95 Diskette
This is an exciting graphical simulation of the problems involved in closely observing a black hole with a space probe. The object is to enter and maintain, for a prescribed time, an orbit close to a small black hole. This is to be achieved without coming so near the anomaly that the tidal stress destroys the probe. Control of the craft is realistically simulated using side jets for rotation and main thrusters for acceleration. This program employs Hi Res graphics and is educational as well as challenging.

SPACE TILT (Apple and Atari only) — Price: $10.95 Cassette/$14.95 Diskette
Use the game paddles to tilt the plane of the TV screen to "roll" a ball into a hole in the screen. Sound simple? Not when the hole gets smaller and smaller! A built-in timer allows you to measure your skill against others in this habit forming action game.

MOVING MAZE (Apple and Atari only) — Price: $10.95 Cassette/$14.95 Diskette
MOVING MAZE employs the games paddles to direct a puck from one side of a maze to the other. However, the maze is dynamically (and randomly) built and is continually being modified. The objective is to cross the maze without touching (or being hit by) a wall. Scoring is by an elapsed time indicator, and three levels of play are provided.

ALPHA FIGHTER (Atari only) — Price: $14.95 Cassette/$18.95 Diskette
Two excellent graphics and action programs in one! ALPHA FIGHTER requires you to destroy the alien starships passing through your sector of the galaxy. ALPHA BASE is in the path of an alien UFO invasion; let five UFO's get by and the game ends. Both games require the joystick and get progressively more difficult the higher you score! ALPHA FIGHTER will run on 16K systems.

THE RINGS OF THE EMPIRE (Atari only) — Price: $16.95 Cassette/$20.95 Diskette
The empire has developed a new battle station protected by rotating rings of energy. Each time you blast through the rings and destroy the station, the empire develops a new station with more protective rings. This exciting game runs on 16K systems, employs extensive graphics and sound and can be played by one or two players.

INTRUDER ALERT (Atari only) — Price: $16.95 Cassette/$20.95 Diskette
This is a fast paced graphics game which places you in the middle of the "Dreadstar" having just stolen its plans. The droids have been alerted and are directed to destroy you at all costs. You must find and enter your ship to escape with the plans. Five levels of difficulty are provided. INTRUDER ALERT requires a joystick and will run on 16K systems.

GIANT SLALOM (Atari only) — Price: $16.95 Cassette/$20.95 Diskette
This real-time action game is guaranteed addictive! Use the joystick to control your path through slalom courses consisting of both open and closed gates. Choose from different levels of difficulty, race against other players or simply take practice runs against the clock. GIANT SLALOM will run on 16K systems.

TRIPLE BLOCKADE (Atari only) — Price: $16.95 Cassette/$20.95 Diskette
TRIPLE BLOCKADE is a two-to-three player graphics and sound action game. It is based on the classic video arcade game which millions have enjoyed. Using the Atari joysticks, the object is to direct your blockading line around the screen without running into your opponent(s). Although the concept is simple, the combined graphics and sound effect lead to "high anxiety".

GAMES PACK I (Available for all computers) — Price: $10.95 Cassette/$14.95 Diskette
GAMES PACK I contains the classic computer games of BLACKJACK, LUNAR LANDER, CRAPS, HORSERACE, SWITCH and more. These games have been combined into one large program for ease in loading. They are individually accessed by a convenient menu. This collection is worth the price just for the DYNACOMP version of BLACKJACK.

GAMES PACK II (Available for all computers) — Price: $10.95 Cassette/$14.95 Diskette
GAMES PACK II includes the games CRAZY EIGHTS, JOTTO, ACEY DUCEY, LIFE, WUMPUS and others. As with GAMES PACK I, all the games are loaded as one program and are called from a menu. You will particularly enjoy DYNACOMP's version of CRAZY EIGHTS.

Why pay $7.95 or more per program when you can buy a DYNACOMP collection for just $10.95?

MOON PROBE (Atari and North Star only) — Price: $11.95 Cassette/$15.95 Diskette
This is an extremely challenging "lunar lander" program. The user must drop from orbit to land at a predetermined target on the moon's surface. You control the thrust and orientation of your craft plus direct the rate of descent and approach angle.

SPACE LANES (North Star only) — Price: $14.95 Diskette
SPACE LANES is a simple but exciting space transportation game which involves up to four players (including the computer). The object is to form and expand space transportation companies in a competitive environment. The goal is to amass more net worth than your opponent. The economics include stock purchases and company mergers. Watch your wealth grow!

ADVENTURE

CRANSTON MANOR ADVENTURE (North Star and CP/M only) — Price: $21.95 Diskette
At last! A comprehensive Adventure game for North Star and CP/M systems. CRANSTON MANOR ADVENTURE takes you into mysterious CRANSTON MANOR where you attempt to gather fabulous treasures. Lurking in the manor are wild animals and robots who will not give up the treasures without a fight. The number of rooms is greater and the associated descriptions are much more elaborate than the current popular series of Adventure programs, making this game the top in its class. Play can be stopped at any time and the status stored on diskette.

SPEECH SYNTHESIS

DYNACOMP is now distributing the new and revolutionary TYPE 'N TALK™ (TNT) speech synthesizer from Votrax. Simply connect TNT to your computer's serial interface, enter text from the keyboard and hear the words spoken. TNT is the easiest-to-program speech synthesizer on the market. It uses the least amount of memory and provides the most flexible vocabulary available anywhere!

Price: $329.95 (Please add $4.00 for shipping and handling)

TNT Software

The following DYNACOMP programs are available for use with TNT

STUD POKER (Atari, 24K)
NOMINOES JIGSAW (Atari, 24K)
TEACHER'S PET I (Atari and North Star)
BRIDGE 2.0 (North Star)
CHOMPELO (Atari, 24K)

Please specify "TNT" versions when ordering

ABOUT DYNACOMP

DYNACOMP is a leading distributor of small system software with sales spanning the world (currently in excess of 40 countries). During the past two years we have greatly enlarged the DYNACOMP product line, but have maintained and improved our high level of quality and customer support. The achievement in quality is apparent from our many repeat customers and the software reviews in such publications as COMPUTRONICS, 80 Software Critique and A.N.A.L.O.G. Our customer support is as close as your phone. It is always friendly. The staff is highly trained and always willing to discuss products or give advice.

BUSINESS and UTILITIES

SPELLGUARD™ (CP/M only) — Price: $219.95 Disk

SPELLGUARD is a revolutionary new product which increases the value of your current word processing system (WORDSTAR, MAGIC WAND, ELECTRIC PENCIL, TEXTED EDITOR II and others). Written entirely in assembly language, SPELLGUARD™ rapidly assists the user in eliminating spelling and typographical errors by comparing each word of the text against a dictionary (expandable) of over 20,000 of the most common English words. Words appearing in the text but not found in the dictionary are "flagged" for easy identification and correction. Most administrative staff familiar with word processing equipment will be able to use SPELLGUARD™ in only a few minutes.

MAIL LIST 2.2 (Apple, Atari and North Star diskette only) — Price: $34.95

This program is unmatched in its ability to store a maximum number of addresses on one diskette (minimum of 1100 per diskette, more than 2300 for "double density" systems!). Its many features include alphabetic and zip code sorting, label printing (1, 2, or 3 up), merging of files and a unique keyword sorting routine which retrieves entries by a virtually limitless selection of user defined codes. Mail List 2.2 will even find and delete duplicate entries. A very valuable program!

FORM LETTER SYSTEM rel. 2 (Atari, North Star and Apple Diskettes only) — Price: $34.95

FORM LETTER SYSTEM (FLS) is the ideal program for creating and editing form letters and address lists. It contains an easy-to-use text editor which produces fully justified text. Special codes are used in the address list to obtain personalized salutations. Form letters are produced by automatically inserting each address into a predetermined portion of your letter. FLS is completely compatible with MAIL LIST 2.2, which may be used to manage and sort your address files.

FLS and MAIL LIST 2.2 are available as a combined package for $59.95.

SORTIT (North Star only) — Price: $29.95 Diskette

SORTIT is a general purpose sorting program written in 8080 assembly language. This program will sort sequential data files generated by NORTH STAR BASIC. Primary and optional secondary keys may be numeric or one to nine character strings. SORTIT is easily used with files generated by DYNACOMP's MAIL LIST program and is very versatile in its capabilities for all other BASIC data file sorting.

PERSONAL FINANCE SYSTEM (Atari and North Star only) — Price: $34.95 Diskette

PFS is a single diskette, menu-oriented system composed of ten different programs. Besides recording your expenses and tax deductible items, PFS will sort and summarize expenses by payee, and display information on expenditures by any of 26 user defined codes by month or by payee. PFS will even produce monthly bar graphs of your expenses by category! This powerful package requires only one disk drive, minimal memory (24K Atari, 32K North Star) and will store up to 600 records per disk (and over 1000 records per disk by making a few simple changes to the programs). You can record checks plus cash expenses so that you can finally see where your money goes and eliminate guesswork and tedious hand calculations.

FAMILY BUDGET (Apple only) — Price: $34.95 Diskette

FAMILY BUDGET is a very convenient financial record-keeping program. You will be able to keep track of cash and credit expenditures as well as income on a daily basis. You can record tax deductible items and charitable donations. FAMILY BUDGET also provides a continuous record of all credit transactions. You can make daily cash and charge entries to any of 21 different expense accounts as well as to 5 payroll and tax accounts. Data are easily retrieved giving the user complete control over an otherwise complicated (and unorganized!) subject.

INTELINK (Atari only) — Price: $49.95 Diskette

This software package contains a menu-driven collection of programs for facilitating efficient two way communications through a full duplex modem (required for use). In one mode of operation you may connect to a data service (e.g., The SOURCE or MicroNet) and quickly load data such as stock quotations onto your diskette for later viewing. This greatly reduces "connect time" and thus the service charge. You may also record the complete contents of a communications session. Additionally, programs written in BASIC, FORTRAN, etc. may be built off-line using the support text editor and later "uploaded" to another computer, making the Atari a very smart terminal. Even Atari BASIC programs may be uploaded. Further, a command file may be built off-line and used later as controlling input for a time share system. That is, you can set up your sequence of time-share commands and programs, and the Atari will transmit them as needed: batch processing. All this adds up to saving both connect time and your time.

TEXT EDITOR II (CP/M) — Price: $29.95 Diskette/$33.45 Disk

This is the second release version of DYNACOMP's popular TEXT EDITOR I and contains many new features. With TEXT EDITOR II you may build text files in chunks and assemble them for later display. Blocks of text may be appended, inserted or deleted. Files may be saved on disk/diskette in right justified, centered format to be later printed by either TEXT EDITOR II or the CP/M ED facility. Further, ASCII CP/M files (including BASIC and assembly language programs) may be read by the editor and processed. In fact, text files can be built using ED and later formatted using TEXT EDITOR II. All in all, TEXT EDITOR II is an inexpensive, easy to use, but very flexible editing system.

DFILE (Atari and North Star diskettes only) — Price: $19.95

This handy program allows North Star and Atari disk users to maintain a specialized data base of all files and programs in the stack of disks which inevitably accumulates. DFILE is easy to set up and use. It will organize your disks to provide efficient locating of the desired file or program.

FINDIT (North Star only) — Price: $19.95

This is a three-in-one program which maintains information accessible by keywords of three types: Personal (eg. last name), Commercial (eg. plumbers) and Reference (eg. magazine articles, record albums, etc). In addition to keyword searches, there are birthday, anniversary and appointment searches for the personal records and appointment searches for the commercial records. Reference records are accessed by a single keyword or by cross-referencing two or three keywords.

SHOPPING LIST (Atari and North Star only) — Price: $12.95 Cassette/$16.95 Diskette

SHOPPING LIST stores information on items you purchase in the supermarket. Before going shopping, it will remind you of all the things you might need, and then display (or optionally print) your shopping list and the total cost. Adding, deleting, changing and storing data is very easy. Runs with 16K.

TAX OPTIMIZER (North Star only) — Price: $99.95 Diskette

The TAX OPTIMIZER is an easy-to-use, menu oriented software package which provides a convenient means for analyzing various income tax strategies. The program is designed to provide a quick and easy data entry. Income tax is computed by all tax methods (regular, income averaging, maximum and alternate minimum tax). The user may immediately observe the tax effect of critical financial decisions. TAX OPTIMIZER has been thoroughly field tested in CPA offices and comes complete with the current tax tables in its data files.

EDUCATION

HODGE PODGE (Apple only, 48K Applesoft or Integer BASIC) — Price: $19.95 Cassette/$23.95 Diskette

Let HODGE PODGE be your child's baby sitter. Pressing any key on your Apple will result in a different and intriguing "happening" related to the letter or number of the chosen key. The program's graphics, color and sound are a delight for children from ages 1½ to 9. HODGE PODGE is a non-intimidating teaching device which brings a new dimension to the use of computers in education.

TEACHER'S PET I (Available for all computers) — Price: $11.95 Cassette/$15.95 Diskette

This is the first of DYNACOMP's educational packages. Primarily intended for pre-school to grade 3, TEACHER'S PET provides the young student with counting practice, letter-word recognition and three levels of math skill exercises.

MISCELLANEOUS

CRYSTALS (Atari only) — Price: $ 9.95 Cassette/$13.95 Diskette

A unique algorithm randomly produces fascinating graphics displays accompanied with tones which vary as the patterns are built. No two patterns are the same, and the combined effect of the sound and graphics are mesmerizing. CRYSTALS has been used in local stores to demonstrate the sound and color features of the Atari.

NORTH STAR SOFTWARE EXCHANGE (NSSE) LIBRARY

DYNACOMP now distributes the 23 volume NSSE library. These diskettes each contain many programs and offer an outstanding value for the purchase price. They should be part of every North Star user's collection. Call or write DYNACOMP for details regarding the contents of the NSSE collection.

Price: $9.95 each/$7.95 each (4 or more)
The complete collection may be purchased for $149.95

AVAILABILITY

DYNACOMP software is supplied with complete documentation containing clear explanations and examples. Unless otherwise specified, all programs will run within 16K program memory space (ATARI requires 24K). Except where noted, programs are available on ATARI, PET, TRS-80 (Level II) and Apple (Applesoft) cassette and diskette as well as North Star single density (double density compatible) diskettes. Additionally, most programs can be obtained on standard (IBM format) 8" CP/M floppy disks for systems running under MBASIC.

STATISTICS and ENGINEERING

DIGITAL FILTER (Available for all computers) — Price: $39.95 Cassette/$43.95 Diskette

DIGITAL FILTER is a comprehensive data processing program which permits the user to design his own filter function or choose from a menu of filter forms. The filter forms are subsequently converted into non-recursive convolution coefficients which permit rapid data processing. In the explicit design mode the shape of the frequency transfer function is specified by directly entering points along the desired filter curve. In the menu mode, ideal low pass, high pass and bandpass filters may be approximated to varying degrees according to the number of points used in the calculation. These filters may optionally also be smoothed with a Hanning function. In addition, multi-stage Butterworth filters may be selected. Features of DIGITAL FILTER include plotting of the data before and after filtering, as well as display of the chosen filter functions. Also included are convenient data storage, retrieval and editing procedures.

DATA SMOOTHER (Not available for Atari) — Price: $19.95 Cassette/$23.95 Diskette

This special data smoothing program may be used to rapidly derive useful information from noisy business and engineering data which are equally spaced. The software features choice in degree and range of fit, as well as smoothed first and second derivative calculation. Also included is automatic plotting of the input data and smoothed results.

FOURIER ANALYZER (Available for all computers) — Price: $19.95 Cassette/$23.95 Diskette

Use this program to examine the frequency spectra of limited duration signals. The program features automatic scaling and plotting of the input data and results. Practical applications include the analysis of complicated patterns in such fields as electronics, communications and business.

TFA (Transfer Function Analyzer) — Price: $19.95 Cassette/$23.95 Diskette

This is a special software package which may be used to evaluate the transfer functions of systems such as hi-fi amplifiers and filters by examining their response to pulsed inputs. TFA is a major modification of FOURIER ANALYZER and contains an engineering-oriented decibel versus log frequency plot as well as data editing features. Whereas FOURIER ANALYZER is designed for educational and scientific use, TFA is an engineering tool. Available for all computers.

HARMONIC ANALYZER (Available for all computers) — Price: $24.95 Cassette/$28.95 Diskette

HARMONIC ANALYZER was designed for the spectrum analysis of repetitive waveforms. Features include data file generation, editing and storage/retrieval as well as data and spectrum plotting. One particularly unique facility is that the input data need not be equally spaced or in order. The original data is sorted and a cubic spline interpolation is used to create the data file required by the FFT algorithm.

FOURIER ANALYZER, TFA and HARMONIC ANALYZER may be purchased together for a combined price of $49.95 (three cassettes) and $59.95 (three diskettes).

REGRESSION I (Available for all computers) — Price: $19.95 Cassette/$23.95 Diskette

REGRESSION I is a unique and exceptionally versatile one-dimensional least squares "polynomial" curve fitting program. Features include very high accuracy, an automatic degree determination option, an extensive internal library of fitting functions, data editing, automatic data and curve plotting, a statistical analysis (eg. standard deviation, correlation coefficient, etc.) and much more. In addition, new fits may be tried without reentering the data. REGRESSION I is certainly the cornerstone program in any data analysis software library.

REGRESSION II (PARAFIT) (Available for all computers) — Price: $19.95 Cassette/$23.95 Diskette

PARAFIT is designed to handle those cases in which the parameters are imbedded (possibly nonlinearly) in the fitting function. The user simply inserts the functional form, including the parameters (A(1), A(2), etc.) as one or more BASIC statement lines. Data and results may be manipulated and plotted as with REGRESSION I. Use REGRESSION I for polynomial fitting and PARAFIT for those complicated functions.

MULTILINEAR REGRESSION (MLR) (Available for all computers) — Price: $24.95 Cassette/$28.95 Diskette

MLR is a professional software package for analyzing data sets containing two or more linearly independent variables. Besides performing the basic regression calculation, this program also provides easy to use data entry, storage, retrieval and editing functions. In addition, the user may interrogate the solution by supplying values for the independent variables. The number of variables and data size is limited only by the available memory.

REGRESSION I, II and MULTILINEAR REGRESSION may be purchased together for $51.95 (three cassettes) or $63.95 (three diskettes).

ANOVA (Available for all computers) — Price: $29.95 Cassette/$43.95 Diskette

In the past the ANOVA (analysis of variance) procedure has been limited to the large mainframe computers. Now DYNACOMP has brought the power of this method to small systems. For those conversant with ANOVA, the DYNACOMP software package includes the 1-way, 2-way and N-way procedures. Also provided are the Yates 2^{K-P} factorial designs. For those unfamiliar with ANOVA, do not worry. The accompanying documentation was written in a tutorial fashion (by a professor in the subject) and serves as an excellent introduction to the subject. Accompanying ANOVA is a support program for building the data base. Included are several convenient features including data editing, deleting and appending.

BASIC SCIENTIFIC SUBROUTINES, Volume I (Not available for Atari)

DYNACOMP is the exclusive distributor for the software keyed to the popular text *BASIC Scientific Subroutines, Volume I* by F. Ruckdeschel (see the BYTE McGraw Hill advertisement in BYTE magazine, January 1981). These subroutines have been assembled according to chapter. Included with each collection is a menu program which selects and demonstrates each subroutine.

Collection #1 — Chapters 2 and 3 — Data and function plotting, complex variables
Collection #2 — Chapter 4 — Matrix and vector operations
Collection #3 — Chapters 5 and 6 — Random number generators, series approximations

Price per collection: $14.95 Cassette/$18.95 Diskette

All three collections are available for $39.95 (three cassettes) and $49.95 (three diskettes).

Because the text is a vital part of the documentation, *BASIC Scientific Subroutines, Volume I* is available from DYNACOMP for $19.95 plus 75¢ postage and handling. See review in Dr. Dobbs.

ROOTS (Available for all computers) — Price: $10.95 Cassette/$14.95 Diskette

In a nutshell, ROOTS simultaneously determines all the zeroes of a polynomial having real coefficients. There is no limit on the degree of the polynomial, and because the procedure is iterative, the accuracy is generally very good. No initial guesses are required as input, and the calculated roots are substituted back into the polynomial and the residuals displayed.

ACTIVE CIRCUIT ANALYSIS (ACAP) (48K Apple only) — Price: $25.95 Cassette/$29.95 Diskette

ACAP is the analog circuit designer's answer to LOGIC SIMULATOR. With ACAP you may analyze the response of an active or passive component circuit (e.g., a transistor amplifier, band pass filter, etc.). The circuit may be probed in equal steps in frequency, and the resulting complex (i.e., real and imaginary) voltages at each component juncture examined. By plotting the magnitude of these voltages, the frequency response of a filter or amplifier may be completely determined with respect to both amplitude and phase. In addition, ACAP prints a statistical analysis of the range of voltage responses which result from tolerance variations in the components. ACAP is easy to learn and use. Simply describe the circuit in terms of the elements and their placement, and execute. Circuit descriptions may be saved onto cassette or diskette to be recalled at a later time for execution or editing. ACAP should be part of every circuit designer's program library.

LOGIC SIMULATOR (Apple only; 48K RAM) — Price: $24.95 Cassette/$30.95 Diskette

With LOGIC SIMULATOR you may easily test your complicated digital logic design with respect to given sets of inputs to determine how well the circuit will operate. The elements which may be simulated include multiple input AND, OR, NOR, EXOR, EXNOR and NAND gates, as well as inverters, J-K and D flip flops, and one shots. The response of the system is available every clock cycle. Inputs may be clocked in with varying clock cycle lengths; displacements and delays may be introduced to probe for glitches and race conditions. At the user's option, a timing diagram for any given set of nodes may be plotted using HIRES graphics. Save your breadboarding until the circuit is checked by LOGIC SIMULATOR.

LOGIC DESIGNER (North Star and CP/M only) — Price: $34.95 Diskette

LOGIC DESIGNER is an exceptional Computer Aided Design (CAD) program. With it you may convert a large and complicated digital truth table (the functional specification) into an optimized Boolean logic equation. This equation may then be easily converted into a circuit design using either NAND or AND/OR gates. Operationally, LOGIC DESIGNER is composed of a BASIC program which calls in a machine language routine to reduce execution time. Example: For a 7 variable by 127 line table, the processing time is only two minutes. LOGIC DESIGNER is clearly a fast and powerful tool for building digital circuitry.

ORDERING INFORMATION

All orders are processed and shipped within 48 hours. Please enclose payment with order and include the appropriate computer information. If paying by VISA or Master Card, include all numbers on card.

Shipping and Handling Charges
Within North America: Add $1.50
Outside North America: Add 10% (Air Mail)

Delivery
All orders (excluding books) are sent First Class

Quantity Discounts
Deduct 10% when ordering 3 or more programs. Dealer discount schedules are available upon request.

8" CP/M Disks
Add $2.50 to the listed diskette price for each 8" floppy disk (IBM soft sectored CP/M format). Programs run under Microsoft MBASIC or BASIC-80.

5¼" CP/M Disks
All software available on 8" CP/M disks is also available on 5¼" disks, North Star format.

Ask for DYNACOMP programs at your local software dealer. Write for detailed descriptions of these and other programs from DYNACOMP.

DYNACOMP, Inc.
1427 Monroe Avenue
Rochester, New York 14618
24 hour order phone: (716)586-7579 recording
Office phone (9AM-5PM EST): (716)442-8960

New York State residents please add 7% NYS sales tax

CIRCLE 136 ON READER SERVICE CARD

MICRO LEARNINGWARE

EDUCATIONAL SOFTWARE

3 For 2 Special
For every two program purchased choose an additional program at no extra charge

A = Apple C = Color Computer
T = TRS-80 P = Pet

MATH

☐ AT P	Place Value		7.95
☐ AT P	Number Strings		7.95
☐ ATCP	Math Drill		7.95
☐ T P	Division Drill		7.95
☐ AT	Speed Drill		7.95
☐ ATCP	Fractions		7.95
☐ ATCP	Decimals		7.95
☐ ATCP	Bagels Number Game		7.95
☐ ATCP	Stones Math Game		7.95
☐ ATCP	Factors		7.95
☐ T	Metric Blackjack		7.95
☐ T	Metric Roadrunner		7.95

BUSINESS ED

☐ T	Accounting Tutorial I		7.95
☐ T	Accounting Tutorial II		7.95
☐ AT P	Depreciation		7.95
☐ AT P	Loan Amortization		7.95
☐ AT P	Bank Reconciliation		7.95
☐ AT P	Stock Market Game		7.95
☐ AT	Disk General Ledger		7.95

HISTORY & GEOGRAPHY

☐ ATCP	Revolutionary War Quiz		7.95
☐ ATCP	Regions of U S		7.95
☐ ATCP	States & Capitals		7.95
☐ ATCP	Presidents		7.95
☐ ATC	Countries		7.95

SCIENCE

☐ T	Electronics (OHMs & Law)		7.95
☐ T	Club the ball physics lab		7.95
☐ TC	Valence drill		7.95
☐ TC	Elements classification drill		7.95
☐ TC	Chemical symbols		7.95
☐ TC	Atomic Weight drill		7.95
☐ TC	Atomic Number drill		7.95

GRAMMAR/ENGLISH

☐ ATC	Adjective recognition		7.95
☐ ATC	Adverb recognition		7.95
☐ ATC	Noun recognition		7.95
☐ ATC	Verb recognition		7.95
☐ ATC	Pronoun recognition		7.95
☐ ATC	Person place thing		7.95
☐ T	Contractions		7.95
☐ T	Possesives		7.95
☐ T	Prefixes		7.95
☐ T	Spelling rules/drills		7.95
☐ ATCP	Spelling drill		7.95
☐ TCP	Word Scramble		7.95
☐ T	Subject Verb Agreement		7.95

MISCELLANEOUS

☐ AT P	Hangman word game		7.95
☐ TCP	Change maker		7.95
☐ A	Money counter		7.95
☐ A	Reading Thermometers		7.95

GERMAN LANGUAGE

☐ T	Adverbs & Conjunctions		7.95
☐ T	Personal Pronouns		7.95
☐ T	Possessive Pronouns		7.95
☐ T	Relative Pronouns		7.95
☐ T	Relative Pronouns		7.95
☐ T	Separable Prefix with Strong Verb Parts		7.95
☐ T	Sein and Haben		7.95
☐ T	Nouns		7.95
☐ T	Adjectives		7.95
☐ T	Comparative and Superlative Prefixes		7.95
☐ T	Basic Verbs		7.95
☐ T	Strong & Irregular Verbs		7.95

Didn't find it? Send for free catalog

ORDERING INFORMATION

Place a check mark next to the programs you would like to order

Cost of programs: $_____ + 1.50 handling = $_____

Type of Machine (check one)

☐ TRS-80 Model I or III cassette
☐ TRS-80 Color Computer cassette
☐ TRS-80 Model I disk
☐ TRS-80 Model III disk
☐ Apple II 3.2 DOS disk
☐ Apple II 3.3 DOS disk
☐ Commodore cassette

Terms (check one)

☐ Master Card
☐ Visa
☐ Money Order
☐ Check
☐ COD
☐ School Purchase Order

Ship to

NAME _____
ADDRESS _____
CITY/STATE/ZIP _____
MASTER CARD or VISA _____
EXPIRES _____

Mail to:
Micro Learningware
P O Box 2134
North Mankato, MN 56001
(507) 625-7205

CIRCLE 185 ON READER SERVICE CARD

creative computing software evaluation

Crypto Machine

George A. Miller

creative computing SOFTWARE PROFILE

Name: Crypto Machine
Type: Puzzle
System: 48K Apple II, Disk Drive
Format: Disk
Language: Applesoft
Summary: Good for cryptogram addicts
Price: $40
Manufacturer:
Shafer Software
465 South Matilda Suite #202
Sunnyvale, CA 94086

Crypto Machine by Dan Shafer is not your gut wrenching, nail biting, edge-of-the-chair action game but rather a game of pure intellect in which 10 minutes is rated super fast.

Crypto Machine is a mechanical aid for solving the cryptograms found below the crossword puzzles in your daily newspaper. The puzzle involves a sentence or saying which has been encrypted using a simple substitution cipher in which each letter used stands for another. If you think that T equals A, it will equal A throughout the puzzle. An example of such a puzzle is:

PVSL HCGVSM FBWGCLC GLSTLGLT FBWVSC PBMBLH

The Crypto Machine runs on an Apple II and will display a cryptogram on the screen. Below each letter is a dash. You can position the cursor under any letter and replace a dash with your guess of the substitution letter. The program will automatically make all equivalent substitutions. This allows you to change your mind and try many different solutions before homing in on the correct one.

George A. Miller, 2426 Bush Street, San Francisco, CA 94115.

Crypto Machine also has a library of sayings from which it can create its own random cryptograms. You may also add your own sayings to the library. There are five levels of difficulty, the hardest being given just 10 minutes to solve a cryptogram that has had all the words strung together and then split into five character groups to eliminate word length hints. (I can't imagine anyone ever being able to do level five!)

There were some areas where this game could be improved. When I first played the game I could not figure how to move the cursor up and managed to lose it. After about five minutes of random keystrokes, the cursor magically appeared on the screen and I was able to continue where I left off (a left arrow hit at the left hand margin of the screen will cause the cursor to rise).

Once I substituted a letter, I could change the letter but never go back to the dash. It would be nice if I could do this since once all the dashes are gone the computer asks if you are finished.

It takes about eight seconds for the program to make a single letter substitution. This is too slow. My tolerance is about one second.

Finally, the library contains just nine sayings. This could be greatly enriched. Of course you can add your own, but then you always remember what you have typed in. It seems much could have been added by including a library of about one thousand sayings.

Finally, I must allow my own biases to enter into the review and state that I enjoy giving the difficult work to the computers and saving the simple stuff for myself. Here is a case where the computer is giving the hard work to the human. ("Here, Buster, see if you can solve this in 10 minutes.") A more interesting computer program might be one to *solve* cryptograms. Nonetheless, Crypto Machine will definitely be enjoyable for the confirmed cryptogram addict. □

Play Copts & Robbers
In The Tombs Of Ancient Egypt

Copyright 1981 by Atlantis Software, Inc.

CIRCLE 238 ON READER SERVICE CARD

Where your secret weapon is the fourth dimension...

Copyright 1981 Epoch Software Inc.

CIRCLE 238 ON READER SERVICE CARD

In the center of an orbiting space station you are protected only by a revolving force shield. Enemy forces are advancing from all directions and begin to place killer satellites in orbit around your station. And then, look out for the meteors!

Copyright 1981 By Sirius Software, Inc.

A "bloody" good game for the true-blue game freak. Your mission in this exploratory operation is to deliver whole blood to Hemophilia, a city in the sky, and return to Anemia Base before the Gamma Goblins overcome you. A real heart stopper!

Copyright 1981 By Sirius Software, Inc.

CIRCLE 238 ON READER SERVICE CARD

What say we go out and stomp a few???

Endless Excitement Stomping Sneakers And A Swarm Of Other Creatures

Copyright 1981 By Sirius Software, Inc.

CIRCLE 238 ON READER SERVICE CARD

Phantoms Five simulates a fighter-bomber mission in real time, three dimensional color graphics While you try to make your bombing run, you have to avoid being hit by anti-aircraft fire and fight off enemy aircraft as well

Copyright 1980 By Sirius Software, Inc

Hatch some fun with the Spiders, Wolves, Lips, and Fuzzballs. Space Eggs will crack you up! Each package includes a multi-color T-shirt iron-on that says "I FRIED THE SPACE EGGS."

Copyright 1981 By Sirius Software, Inc.

CIRCLE 238 ON READER SERVICE CARD



This is the graphics editing package we based our business on. Includes the Higher Text Character Generator by Ron & Darrell Aldrich and over 20 original and imaginative type styles.

Copyright 1980 By Sirius Software, Inc.



The professional graphics editing package for use within the Pascal environment

Copyright 1981 By Sirius Software, Inc

CIRCLE 238 ON READER SERVICE CARD

GORGON is here...

THE EARTH HAS ENTERED A TIME WAVE AND THE BATTLE HAS JUST BEGUN

Copyright 1991 by Sierra Semiconductor

CIRCLE 238 ON READER SERVICE CARD

BOTH BARRELS

A two game pack featuring "High Noon" and "Duck Hunt". You'll love the bad guy that falls off the roof and the dogs fighting over the ducks. Fun for the young and the young at heart.
Copyright 1980 By Sirius Software, Inc.

STAR CRUISER

Save yourself from the swooping aliens! This is a fast action arcade style game that can be played from ages three and up, but beware, the difficulty increases with each new wave of aliens.
Copyright 1980 By Sirius Software, Inc.

CYBER STRIKE

Interstellar challenge for the dedicated arcade gamer. You are in command of a light transport ship equipped with Hyperspace Drive, Antimatter Torpedoes, Local and Galactic Sensors, Meteor Shields, and an Instrument Panel which continually tabulates all information vital to your mission. You alone can prevent the clone take over of the allied settlement bases. WARNING . . . this game requires practice to play successfully.
Copyright 1980 By Sirius Software, Inc.

AUTOBAHN

Hair raising excitement at 120, 160, and 200 kilometers per hour! Drive through heavy traffic, oil slicks, narrow roads, and dark tunnels (with headlights). Watch out for the fire trucks! Only on the Autobahn can you drive this fast.
Copyright 1981 By Sirius Software, Inc.

PULSAR II

A unique two game series that provides scoring options for separate or combination game play. To destroy the "Pulsar" is no easy task. It is surrounded by spinning shields that send out orbs of energy aimed directly at you. "The Wormwall" places you in one of the strangest mazes ever created. The walls do not connect. Openings only occur temporarily as moving colored segments in the walls cross. In addition, there are munching mouthers in each level of the maze ready to gobble you up should you misjudge the time and location an opening will occur.
Copyright 1981 By Sirius Software, Inc.

Contact Your Local Computer Dealer For More Information • Dealer Inquiries Invited

Sirius Software, Inc.

2011 Arden Way #2, Sacramento, California 95825

PROGRAMMING: Cyber Strike was programmed by Alan Merrell and Jim Knopp. Pulsar was programmed by Jerry Mills. Star Cruiser was programmed by Alan Merrell and Joseph Santoro. Autobahn was programmed by Jim Knopp. Pulsar II Game was programmed by Nick Wilson and Jerry Mills. Jawbreaker was programmed by Jerry Mills. Autobahn was programmed by Mark Turner. Graphics for the "Duck Hunt" game were done by Cyber Strike programmer and Pulsar II were programmed by [illegible].

SOFTWARE INFORMATION: All software mentioned in this advertisement are copyrighted software and software [illegible] rights reserved. Apple and Applesoft are registered trademarks of Apple Computer Inc. Higher Text is a copyrighted product of Synergistic Software. We use Control Data diskettes the highest quality.

SYSTEM REQUIREMENTS: All software mentioned in this advertisement require an Apple II or II+ with 48K with the following exceptions: E.T. Draw requires 48K Apple with Applesoft in ROM or a 64K Apple II+. Pulsar Graphics Editor requires an Apple II or II+ with Language System.

CIRCLE 238 ON READER SERVICE CARD

Apple/UCSD Pascal 1.1: A User's Evaluation

Ross M. Tonkens

Having lived with Apple's newly updated version of UCSD Pascal (Pascal Ver. 1.1) for over a month, now, I feel a few observations are in order.

First, let me say that the manuals alone are worth the $60 update cost, for those of us who have had to live with the infamous "White Book" for the last year and a half. Just the sight of a real index (spanning more than seven pages!) brought tears of joy to my eyes.

In fact the system consists of over two manuals and four disks. I say "over two" manuals because there are two full-fledged reference manuals, one for the operating system, and one for Apple's implementation of UCSD Pascal. Both manuals are of the outstanding glossy quality to which we have become accustomed from Apple. I might add in passing that the graphic artwork gracing the covers of the manuals would sell briskly as poster art. In addition, three 9- to 16-page pamphlets are included. One describes differences between the old and new versions of Apple/UCSD Pascal; one is an addendum to the new operating system reference manual; and the third is an addendum to the new Pascal language reference manual.

Perhaps the best features of the current update are found only in these addenda. Among them were EXEC files, chaining capability, built in upper and lower case text generation without hardware add ons, much faster compile times, new compiler options, and an explicit list of previous bugs, fixed in this new version. Also contained in one of these little pamphlets is, at last, a lucid description of how program segmentation is accomplished by the compiler which clears up many mysteries left unresolved by even monk-like study of previous documentation.

This is all fine, but "how well does it wear?" as the saying goes. In short, "very well, indeed." All of the inconsistencies in how the operating system previously handled files with the special suffixes, ".text" and ".code" have been resolved. Combined with the addition of EXEC file capability, this has increased my productivity by at least 100%.

Now the user can define a common sequence of operating system commands, for example, those steps taken to compile and link a UNIT and install it in a library, or the commands issued to compile, link, and run a program, and have the computer perform them automatically in sequence, rather like a job control language. Instead of having to watch the computer full time, I now simply call up an EXEC file and take a break while the boring processes of compilation, linking, and test running all take place unattended.

EXEC files almost make up for my lack of a hard disk drive in terms of the increase in throughput achieved. About the only new problem the changes have created is temporary obsolescence of any memory-sensitive software, since the old memory map on which such software would have been based has been changed. This problem should be only temporary, as the update will involve simply altering the CONSTANT declarations of any Pascal 1.0 program which referenced memory directly once the new memory map is published by Apple. This brings me to my only complaint, namely that the new Pascal 1.1 manual did not already contain this information.

While the new Apple/UCSD Pascal Ver. 1.1 still has its idiosyncrasies, Apple seems to have distilled out those problems which were truly intolerable, while adding numerous conveniences which make it a truly serious software development system at last.

Now if I could just save the money for that hard disk.... □

Ross M. Tonkens, M.D., 6221 Wilshire, Suite 607, Los Angeles, CA 90048.

Lowest Prices on Personal Computers

ATARI 800™...$789
ATARI® List $1080
NEW LOW PRICE!
ATARI® 400...$359

HEWLETT PACKARD HP-85
$2795

HP-85 Accessories

5¼" Dual Master Disc Drive List $2500	$2125
5¼" Single Master Disc Drive List $1500	$1275
HP 7225A Graphics Plotter List $2050	$1845
HP-85 16K Memory Module List $395	$355
HP-85 Application Pacs Standard List $95	$86
Serial (RS-232C) Interface Module List $395	$355
GPIO Interface Module List $495	$445

new HP-83 List $2250 $1895

NEW! HP-41CV with five times more memory built in. List $325 $249
HP-41C List $250 $199

HP-32E Scientific w/Statistics	$3.95
HP-33C Scientific Programmable	$79.95
HP-34C Advanced Scientific Programmable	123.95
HP-37E Business Calculator	$49.95

Personal Computer Systems
303
609 Butternut Street
Syracuse, N.Y. 13208
(315) 475-6800
Prices do not include shipping by UPS. All prices and offers subject to change without notice.

CIRCLE 280 ON READER SERVICE CARD

ZGRASS GRAPHICS LANGUAGE

In a few short months, I am able to do things I never thought possible while programming in Basic.

Tom Meeks

There is an aura of mystery surrounding any new language. Perhaps the names of the languages have something to do with it. That old familiar language, Basic, just *sounds* so easy! But, does "easy" come to mind when we first hear the names Pascal, Smalltalk, Forth or Zgrass? Probably not. Yet, once we get behind the names and esoteric jargon we find that, in fact, some of these strange sounding names hide languages that are quite easy to learn and, for many applications, far simpler than Basic to implement.

Since most of us are, by nature, ruled by the laws of inertia we tend to resist the new in favor of the familiar. In my own case, it took a great deal of frustration with the limited ability of Basic to produce animated graphics in a reasonable amount of programming time to initiate a search for an alternative. As luck would have it, I stumbled onto Zgrass, a thoroughly enjoyable graphics language.

My company, Communication Resource Management Systems, is a small video company involved in producing training materials for government and industry. When it became evident that we would have to know about computers if we were to remain competitive in video I began to shop around.

Tom Meeks, 11004 Stillwater Ave., Kensington, MD 20795.

After careful search a system was selected and the business of learning Basic was begun.

If my primary objective had been to write checkbook programs or play number games I might still be programming in Basic. However, my goal was to produce computer graphics to enhance the educational value of the video tapes we produce. Frankly, Basic was totally frustrating.

The hardware was fully capable of everything we wanted; Basic just couldn't access that power in anything approaching a reasonable amount of time. Just when I had almost given up computer animation as a lost cause I read a report about SIGGRAPH'80 (*Creative Computing*, January '81) which mentioned a new computer featuring Zgrass, a language specifically designed for animation and video graphics. Taking a chance, I purchased one of the first Datamax UV-1s produced. The results have far exceeded any expectations I may have had. Zgrass is easier than Basic . . . and it works!

Perhaps some perspective can be added to the last statement if I point out that when my Datamax UV-1 was delivered in February 1981, I had never even seen the Zgrass program, and the nearest Zgrass programmer was in Chicago, over 800

High-Resolution Color Graphics for the Apple and Atari

Graphics Breakthrough

How many programs have you written that would benefit from animated high-resolution graphics? Probably several. It is this kind of dramatic graphics that distinguish outstanding programs from ordinary ones. But if you've ever agonized for hours or days just to get one image perfected, you're probably not anxious to do it again. Now there's a better way.

New Graphics Entry System

Today there is a new graphics system available that is not only amazingly user-oriented but surprisingly economical. Called VersaWriter, it starts with an ingeniously simple entry board consisting of a 14" X 12" high impact plastic bed with a tough clear plastic overlay sheet. The original drawing or diagram is fastened with masking tape to the plastic bed and then covered with the clear sheet. Instead of using a light pen or complicated electronic X-Y head, the VersaWriter uses a double jointed arm attached to the top of the entry board at one end and a magnifying lens with crosshairs at the other end. The VersaWriter resembles a draftsman's pantograph on a smaller scale.

At each joint in the arm of the VersaWriter is a potentiometer. A cable from these pontentiometers connects to the paddle input of the computer. No special interface electronics or board is needed. Since the arm of the VersaWriter bends only in one direction, each point on the plotting head corresponds to a unique set of resistances on the potentiometers. All that's needed now is software to translate these resistances into usable screen coordinates.

Exceptionally powerful software

It is in the software where VersaWriter really stands out. VersaWriter comes with two full disks of user-oriented software. First it has sets of "low level" commands for entering, creating and copying drawings and diagrams. Secondly, it has extensive sets of application routines for moving, enlarging, rotating, coloring or animating drawings that the user has created.

Of course the basic commands let you enter a drawing freehand or by tracing it. Want a wider brush stroke? Six widths are available. Drawings can be independently scaled in both the vertical and horizontal directions. An enclosed shape may be filled in with any of 106 colors. No, that is not a misprint—By the same technique that a printing press can create hundreds of colors from the three primary ones, so can VersaWriter.



Here a shape (the letter A) is being scanned. After putting it in a shape table it may be used in other programs.



From the shape table, a shape (the letter A) may be enlarged, rotated, colored or moved about the screen.

Create Animation for Other Programs

The shapes you create with VersaWriter can be used and manipulated with ease in other programs. Up to 255 shapes can be entered into a shape table. These shapes may then be placed on the screen in any position or may be overlaid on a full or partial screen image. Animation is produced easily by moving about a portion of the image created by VersaWriter. For example, by alternating between two images of an airplane propeller it will appear to be spinning.

Other VersaWriter software includes text-writer with which text can be added to graphics. Upper and lower case, choice of color, text size, direction and starting point all may be specified.

The Area/Distance program lets you calculate distances (or perimeters) by entering a scale and tracing a shape or map route with the drawing arm. Areas of figures, open and irregular, can be similarly calculated.

The software also includes sets of electronic and computer logic shapes. In addition, an entire disk of dramatic demonstration graphics is included. These twelve full-screen graphics run the gamut from a fully labeled cross section of a human skull to colored maps to animated cartoons to an electronics schematic.

Software Updates

You may have read a review of VersaWriter that indicated that the color fill routine was slow. It was. But not any more. Several routines and improvements were added to the VersaWriter software since its introduction. An added feature, the Expansion Pac, is also now available. This third disk of software contains an area distance program, a microscope feature, and will save your graphics in the exact colors you prefer. It also includes shape tables for architecture, plumbing, electrical, circuit boards, landscape, chemistry, games, and more; 350 predefined shapes in all.

At Peripherals Plus, we evaluated every graphics device. We wanted to handle the best one regardless of price. VersaWriter has the best performance bar none. Surprisingly, it also has the lowest price, just $299.00 for the Apple version. It requires an Apple II Applesoft in Rom (or an Apple II Plus), disk, and 48K memory. VersaWriter comes complete with two disks of software, a comprehensive instruction manual, and a 90-day limited warranty. The additional Expansion Pac is available for $39.95.

The Atari version, which varies slightly from the Apple version in number and types of functions performed, is available for $299.00. As new updates are developed for the Atari, Peripherals Plus will furnish them free to all customers—just send us the disk and we'll supply the updated material. We make this unique offer because it is in our best interest to have you make the best use of your computer. We're also convinced that if other people see your VersaWriter in use they'll want one too.

Try VersaWriter for 30 days. If you are not completely satisfied we'll give you a prompt and courteous refund of the full price plus shipping both ways.

To order, specify Apple or Atari version, send payment plus $3.00 shipping and handling to Peripherals Plus, 39 East Hanover Ave., Morris Plains, NJ 07950. (New Jersey residents please add 5% Sales tax.) Credit card customers should include card number and expiration date of Visa, MasterCard or American Express card. Credit card customers may also call toll-free 800-631-8112 (in NJ 201-540-0445).

For spectacular graphics on your computer, order VersaWriter today.

Graphics Systems

Versa Writer	**$249.00**
Kurta Graphics Tablet	**695.00**
Summagraphics Digitizer	**745.00**
Houston Instruments Hi Pad	**795.00**
Apple Graphics Tablet	**795.00**

Peripherals Plus

39 E. Hanover Ave.,
Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)
CIRCLE 239 ON READER SERVICE CARD

Apple is the registered trademark of Apple Computer Inc

miles away. Yet, in a few short months, I am able to do things I never thought possible while programming in Basic—even with the generous help of scores of experts in the Washington D.C. area.

First Impressions of a Basic Programmer

My first contact with Zgrass came in the form of a video tape demonstrating Zgrass animation and video art. It's a good thing I had seen the tape, too, for it carried me through the initial shock of my first contact with the language itself. This shock only lasted for an hour or so, but it was severe! There were no line numbers, no FOR-NEXT loops and more than one program could be stored and run at the same time.

number ten (a good safe start) and work our way to the end of the program with side trips in GOSUBs and GOTOs. Programs for the simplest animations can become enormous and complex with FOR-NEXT loops rested inside nested FOR-NEXT loops. Fine tuning is difficult and often results in bugs.

Zgrass, on the other hand, is more modular in concept. Perhaps the difference can be best illustrated by our fictional space game. In Basic we would write one long program containing every element needed to play the game. Any changes would have to be squeezed into the spaces of the long existing lines. Since the program may be several hundred lines long, finding the particular lines that need to be changed can be difficult.

My Basic programmer's head reeled! Build programs and routines without line numbers? Impossible! Produce graphics with no FOR-NEXT loops? Absolutely impossible! As for the multiple programs, I had already had more than my share of trouble trying to get one at a time to run.

With the vision of the taped animation firmly fixed in my mind, I delved deeper into the language. Gradually it became evident that Zgrass was different. The commands and syntax seemed to make good sense. Common sense. This was in sharp contrast to the graphic statements with which I was familiar when plotting in Basic.

Fundamental Conceptual Differences

Now that I have had several months to explore Zgrass and implement it under the pressure of deadlines and the budget restraints of my clients, I am more than happy to share what I have already learned about this graphics tool. The concepts upon which this language is built deserve to be discussed before the actual coding structure is introduced. Animation, whether by brush or by computer, is dependent on timing for its dramatic effect. This means that the developmental phase must remain fluid so that fine tuning of the animation can be accomplished.

For instance, it's very difficult to anticipate the effect of an explosion of a space ship in a game. It isn't until the explosion is seen, not once but over and over that the real effect can be felt. Not being able to easily isolate and experiment with individual elements of an animated graphic was one of the major frustrations I experienced while programming in Basic.

Basic tends to be linear by nature. We begin at line

This same game written in Zgrass would have an entirely different structure. Each element of the game would have its own program, called a macro. Each macro would be assigned a name—usually descriptive of its function—that may be used to call the macro when that particular element is needed. For instance, we might have a macro called BUILDSHIP which draws a spaceship. This macro could be called any time a new space ship is needed on the screen—at the beginning, after a crash, after an enemy victory, etc. In Basic, since only one program is in the memory at one time, we enter the command RUN whenever we want the program to execute. In Zgrass we simply enter the macro name to execute it. This can be done from the keyboard or *as a statement in another macro*.

While this is deceptively similar to a standard Basic GOSUB statement there are some very important differences. The first is the ease with which BUILDSHIP is edited. The simple command EDIT BUILDSHIP brings only those lines used to build our spaceship to the full screen editor.

Second, we can execute BUILDSHIP independent of all of the other elements in the space game. There is no need to run the entire game to check on changes. This allows us to focus our entire attention on the details and timing of each element of the game individually.

Third, since Zgrass is modular, this same macro can be used in other games needing a space ship. In Basic, if we wanted to use a subroutine from one game in another, we would normally have to re-enter all the lines through the keyboard. Since Zgrass macros can be saved on tape or disk there is no need to re-enter the shipbuilding routine manually. Simply recall BUILDSHIP and it's ready to use.

ADD POWER TO YOUR COMMODORE COMPUTER

$89.95

POWER produces a dramatic improvement in the ease of editing BASIC on Commodore's computers. POWER is a programmer's utility package (in a 4K ROM) that contains a series of new commands and utilities which are added to the Screen Editor and the BASIC Interpreter. Designed for the CBM BASIC user, POWER contains special editing, programming, and software debugging tools not found in any other microcomputer BASIC. POWER is easy to use and is sold complete with a full operator's manual written by Jim Butterfield.

POWER's special keyboard 'instant action' features and additional commands make up for, and go beyond the limitations of CBM BASIC. The added features include auto line numbering, tracing, single stepping through programs, line renumbering, and definition of keys as BASIC keywords. POWER even includes new "stick-on" keycap labels. The cursor movement keys are enhanced by the addition of auto-repeat and text searching functions are added to help ease program modification. Cursor UP and cursor DOWN produce **previous** and next lines of source code. COMPLETE BASIC program listings in memory can be displayed on the screen and scrolled in either direction. POWER is a must for every serious CBM user.

Call us today, for the name of the Professional Software dealer nearest you.

Professional Software Inc.
166 Crescent Road
Needham, MA 02194
Tel: (617) 444-5224 Telex #951579

Zgrass, continued...

This modular format is not the only conceptual difference between Basic and Zgrass. While Basic has evolved with the development of more powerful hardware, it isn't usually considered a user expandable language. On the other hand, Zgrass is definitely expandable. Most commands are contained in ROM. However, additional commands can be loaded into memory when needed, and entirely new commands can be created. As a matter of fact, in the few months since I purchased my Datamax, several new commands have been added to the Zgrass library.

The difference that I most appreciate, however, is the concept that the user should have easy access to *all* of the capabilities of the hardware. It is clear from the articles in *Creative Computing* and other computer magazines that this is not a common philosophy. Zgrass seems to open the entire graphics repertoire of the computer for the user. If you have been disappointed by the performance of Basic compared to what you saw in the manufacturer's demonstration then you'll find Zgrass refreshing.

Additional commands can be loaded into memory when needed, and entirely new commands can be created.

Getting Started

The quality of documentation is usually the first hint about the overall quality of any system. The documentation that arrived with my Zgrass computer system was packaged in two booklets. The first of these is the *Zgrass Glossary of Buzzwords, Commands, Functions, Idiosyncrasies, Swap Commands, Swap Functions, Switches and Esoterica*. The contents are just as thorough as the title.

One of the drawbacks of working with a high level language is that it is possible to do things without ever understanding the basics of computer logic. Truth tables had never really seemed to be worth the effort to learn until I came across the explanations about OR, XOR, and AND in the Zgrass Glossary.

Whoever wrote the glossary appreciates the fact that there are people who want to use a computer but don't want to earn a mathematics degree to do so. The explanations are clear and concise. Often there are short programs that can be entered and run in a few minutes that graphically illustrate the logical operations. All of the entries are in alphabetical order which makes finding them a snap.

The second booklet is a self-teaching guide. I had some troubles with this one—mostly due to my own impatience. I would begin a lesson dutifully reading and working the examples until something would click inside my head—the old "Hey! That was great . . . I wonder if . . ." and off I'd go on with some wild experimentation until I found myself stuck.

Then grabbing the phone I'd make a plea for help, only to find that the answer was two or three pages further along in the book. After doing this two or three times (and receiving the same courteous "It's on page. . . reply), it finally began to dawn on me that patience really is a virtue. Once that point was reached the self-teaching guide worked fine.

The System Supports the Graphics

Simple graphics commands do not necessarily guarantee easy graphics generation and animation. Zgrass commands such as POINT, BOX, LINE and ELLIPSE (an expanded circle command) would certainly be useful in any language; but, Zgrass goes beyond these in providing the tools needed to produce sophisticated graphics easily.

While a complete explanation of the Zgrass operating system is beyond the scope of this article, I just can't resist mentioning some of the features that make the job of the programmer or animator so much more enjoyable.

There are four features that I especially appreciate: the full-screen editor, the sophisticated cassette tape interface, the program flow control commands and the priority execution controls that allow for truly interactive program control.

Perhaps nothing relieves the tedious aspects of programming better than a good full screen editor. Zgrass supports, through the EDIT command, a full screen editor that comes remarkably close to being a true word processor. The cursor can be located using keyboard commands or a joystick. Lines can be altered, deleted, duplicated or moved. Obviously, this speeds up the process of building or modifying a macro.

At first glance, it may seem out of place to bring up a cassette tape interface in a discussion devoted to an easy graphics language. But, the key word is *easy*. Anything that takes the hassle out of programming deserves to be recognized. The Zgrass tape handling system certainly qualifies.

One of the frustrations encountered when using cassette tape with most of the popular micros is that once the computer

Lynn Busby, president of the Computer Station, as seen by the Dithertizer II.

You and your Apple can have a new view of the world.

Dithertizer!

Dithering. Developed at Bell Labs and MIT, dithering was originally an approach to picture transmission. Compared to other methods, dithering is fast and accurate.

The Dithertizer II was designed for the Apple computer by David K. Hudson, a researcher at MIT. Design goals were high accuracy, fast scanning, maximum reliability and an economical price.

High Quality Images

The resolution is of the Dithertizer is the maximum the Apple can handle in the high-resolution mode, i.e., 280 x 192 (53,760) pixels.

To produce an image, a video camera is focused on the subject. Peripherals Plus furnishes a Sanyo VC161OX camera, a laboratory/industrial unit with an f 1.6 lens. This camera has a focus range of 18" (for extreme close ups) to infinity (for distant subjects).

The camera scans an entire frame in 1/60th of a second. Two frames are scanned, of course, in 1/30th of a second. By adjusting the blackness control (with Paddle 0) to any one of 255 levels you can determine the threshold of gray between the two frames.

A 1/30th second, two-frame scan has two levels of gray and produces a high-contrast but quite recognizable image.

Pictures or Contours

Using the "Contour" software routines and contrast control (Paddle 1), it is possible to subtract one image from another. If the blackness thresholds of the two images are close, say 125 and 127, the resulting image will show just the outlines or highlights of an object.

Another possibility is to reduce the contrast to zero which results in a nearly blank screen except for movement in the area scanned. This type of movement detector is much faster (1/30th second) and more precise than other much more expensive systems. It is currently being used to detect and record movement of laboratory animals. It is also used in security installations.

The "Dithering" software routines use the contrast control to divide an image into gray tones. As mentioned above, two levels (usually white and black) result in a high contrast image. Four gray levels provide additional definition while sixteen levels produce a highly detailed image in just over 1/4th of a second. Extremely high detail is possible using the highest 64-gray level setting. At this level, an image is produced in 64/60ths of a second or just over one second. The quality of this image is close to that of a halftone photograph found in a newspaper or magazine.

Using Dithered Images

What can one do with a dithered image? Upon completion it can be stored automatically in either page 1 or 2 of the high-resolution graphics area of the Apple. Hence, it can be printed out on practically any printer. To print it on an Apple Silentype printer or equivalent requires no additional software.

To take advantage of the automatic print routines in the Dithertizer itself does require additional software tailored to a specific printer. Software packages are available at $44.95 each for the following printers: IDS 440, 445, 460, and 560; IP225; Anadex DP9500 and DP9501; Spinwriter 5510 and 5520.

Individual images or series of images may also be incorporated in other programs in the same way that other hi-res graphics are used. Using VersaWriter software, for example, text may be added to images. An image may be shown on the screen while a disk is loading or while the computer is completing a time-consuming calculation in another program.

With the proper software, the Dithertizer can be used to perform image enhancement, to identify features, detect motion, track a moving target or create a detailed picture for display. The possibilities are limited only by your imagination.

Quality Construction

The dithertizer is manufactured to exacting specifications by Computer Station. It consists of the Dithertizer II board which plugs into Slot 7 in the Apple II, a cable which connects between the Dithertizer and motherboard and a 10 foot cable to the camera. The system requires a 48K Apple disk system.

The software package consists of three routines on disk: "Dither" to build a gray scale picture, "Contour" to produce an edge scan using image subtraction, and "Dscan" to store a binary image in either page 1 or 2 of the high-resolution graphics area.

Peripherals Plus also includes a Sanyo VC161OX video camera with external horizontal and vertical sync input.

The components of the packge—hardware, software and camera—are warranteed by the manufacturers against defects in material and workmanship for 90 days. In addition, Peripherals Plus guarantees that if you are not completely satisfied you may return the system for a prompt and courteous refund.

Order Today

The entire Dithertizer system consisting of the Dithertizer board, Sanyo camera, cables and software costs only $650 plus $6 shipping and handling in the continental United States. Customers in other loctions should write for shipping rates. Price for the board and software alone is $300 while the camera alone is $410. To order your system, send payment or Visa, MasterCard or American Express card number and expiration date to the adress below. Credit card customers may also call orders to our toll-free number.

Don't put it off. Remember, your system is backed by both manufacturer warranties and a complete moneyback guarantee of satisfaction from Peripherals Plus.

Give your Apple a new view of the world with a Dithertizer. Order today.

Peripherals Plus

39 East Hanover Avenue
Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)

CIRCLE 239 ON READER SERVICE CARD

Zgrass, continued...

has been instructed to load tape you have no idea what's happening—all you can do is sit and wait—and hope. Zgrass eliminates this problem beautifully by including a file directory system with the PUTTAPE and GETTAPE commands. The syntax for PUTTAPE is:

PUTTAPE NUMBER,FILENAME,DESCRIPTION
PUTTAPE 2,FLYINGSAUCERSHOOTER,{Creates a slingshot for CRASHNSMASH}

The NUMBER tells how many times the file should be put on the tape, the FILENAME (which can be any length) is the file to be copied and the DESCRIPTION is anything that helps you identify the file.

GETTAPE FLYINGSAUCERSHOOTER would initiate a search through the tape for the proper file, printing out the directory information of all the files it passes. The directory for our example would look like this:

STR NAME:FLYINGSAUCERSHOOTER LEN:324 NOTE:
Creates slingshot for CRASHNMASH

This directory information plus status messages like BAD DATA and BAD-AUTORETRY save a tremendous amount of programming time. Furthermore, the tape interface is extremely tolerant of random user tape searches. We are constantly skipping back and forth through the tapes with multiple files, using the directories to tell us where we are. The poor man's external random access memory!

The simplicity of the commands used to control program flow in Zgrass, while not actual graphics commands, are a third feature of the the overall operating system that contributes directly to making the job of creating graphics easy.

The most commonly used program flow control features used in Basic are line numbers, GOTO, GOSUB and the ever popular FOR-NEXT loop. As mentioned earlier, Zgrass is conspicuous for the absence of most of these features in normal use. Line numbers and GOTO statements can be used by the programmer, but other means of controlling the flow of the program are so easy and efficient that I have not used a single line number or GOTO statement the entire time I have used the Zgrass language.

The SKIP command is the major program flow control statement. SKIP -2 would tell the computer to go back two lines of code, SKIP 6 tells the computer to go forward six lines. Most often these skips are used in conjunction with an IF statement. The IF statement in Zgrass is far more versatile than it is in Basic. Consider the following comparisons:

```
BASIC:   1910 IF A > 10 THEN 1860
ZGRASS:  IF (A=A-5) > 10,SKIP -5

BASIC:   340 IF A < 10 THEN GOSUB 5000
ZGRASS:  IF (A=A-5) < 10,BUILDSHIP
```

Notice that the Basic IF statement is simply a testing step. The process of arriving at the variable A is performed outside of the IF statement, usually in a FOR-NEXT loop.

In Zgrass the IF statement is used not only for testing conditions, but for performing the actual calculations to test. I hope it is also evident that Zgrass programs are easier to follow because subroutines are actually small independent macros which *have names*! In spite of my initial fears, I have found the Zgrass systems for program flow control to be far better than the old FOR-NEXT loops I left behind.

The fourth feature that I appreciate is the ability to run more than one program at a time and assign priority levels to them. If we use .F after a macro name we are saying that this macro has the highest or FOREGROUND priority. If we use .B we are saying that the macro has BACKGROUND priority. It is the BACKGROUND mode that I find most useful. The keyboard remains active while macros are running in the background mode and can even be used to modify the programs as they run. Ever wanted to try out different colors on that hyperspace explosion? You can in Zgrass. Simply run the explosion macro in the background mode and experiment with colors while the explosion repeats indefinitely. This is another example of the superior fine-tuning abilities of Zgrass.

When I first purchased the Datamax UV-1, I was looking for a machine with simple graphics commands. Now I realize that just having simple graphics primitives is not enough. The power of Zgrass begins with the fundamental concepts which underlie the language control structure and moves from there to the commands dedicated to graphics manipulation. The reason that I have placed so much emphasis on these features is that, while I am amazed at the power of some of the graphics commands in Zgrass, I doubt that a linear language with these same commands would be as flexible or easy to use.

Graphics Manipulation Features

The function of the graphics primitives POINT, LINE, BOX and ELLIPSE are self explanatory and not so different from some found in newer expanded Basic interpreters. Other commands used to scroll screen areas, create windows and fill bordered areas with solid colors are also fairly common. There are, however, some provisions for manipulating colors, special commands for manipulating picture elements and remarkable picture arrays called "snaps."

Dr. Tom DeFanti, the originator of Zgrass, borrowed a concept from box camera days and allows us to save individual pictures from the screen with the SNAP command (short for snapshot). Suppose we wanted to create a little creature to be used in a game. With Zgrass you would simply draw it on the screen and "snap" it off. The SNAP command saves the creature and the area around it in a box called a "snap array." The SNAP syntax and an example are:

```
SNAP Snapname,Xcenter,Ycenter,Xsize,Ysize
SNAP ALIEN1,0,0,15,25
```

To retrieve our creature from memory and display it on the screen we use the Display command. Its syntax and an example are:

```
DISPLAY Snapname,Xcenter,Ycenter,Displaymode
DISPLAY ALIEN1,50,25,0
```

The SNAP and DISPLAY combinations are the keys to the rapid animation possible with Zgrass. This macro sends an alien with moving legs across the screen.

```
CRAWLYCREATURE={A=-190
DISPLAY ALIEN1,A,0,0
DISPLAY ALIEN2,A+1,0,0
IF (A=A+2) < 190,SKIP -2}
```

I've just finished the 4th edition of our catalog, featuring A RAINBOW OF APPLICATIONS for your Apple* Computer...

Now I can play Super Stellar Trek...

PRO-PADDLE
for your Apple II
at last... A compact, heavy-duty paddle featuring sturdy metal construction, long-life switches with large buttons and tactile feedback, high accuracy paddle movement, shielded coaxial cables, and a molded plug.
End your paddle problems for good
$39.95

FROM APPLE COMPUTER
for your Apple II
DOS 3.3 KIT will increase the capacity of your diskette. You can still boot S.2 programs. Includes manual, 16-sector recipes for the disk interface, and utility disks
$60.00

DOS TOOL KIT includes an Editor/Assembler with a relocating loader, with a Character Generator, Hi-Res Applesoft programmer's assistant. Requires 48K Applesoft and DOS 3.3
Manuals and Disk
$75.00

SUPER STELLAR TREK
for your Apple II and Apple /// (emulation mode)
A dramatic successor to the already popular "Stellar Trek." Tom Burlew has created Super Stellar Trek as a high-speed, Hi-Res, Real-time action game that will challenge even the most skilled starship commander. In color. Complete manual.
DOS 3.2 / 3.3
48K Applesoft
Disk $39.95

STATISTICS with DAISY
for your Apple II
excels on user convenience and offers a full range of statistical capabilities. Basic stats: correlations, hypothesis testing, multiple regression is procedures: non-parametric stats, data and time series transforms, and analysis of variance
DOS 3.3
48K Applesoft
Disk $79.95

FIRST MAPS CONTROLLER

Our catalog contains many more products for your Apple computer. Please request a FREE catalog with any purchase. If you only want a copy of our catalog at this time, please send $2.00 for shipping. Thank you.

RAINBOW COMPUTING INC.

apple computer inc.

*Apple is the registered trademark of Apple Computer Inc.

Open Tues - Fri

Mail Order Dept. No. CC11 • 19517 Business Center Dr. • Northridge, CA 91324 • Phone orders only (Need Mastercard or Visa) U.S.A. (except Calif.) (800) 423-5441 • Calif. and Foreign (213) 349-0300 • For information or technical questions (213) 349-5560
Add $2.50 U.S. / $10.00 Foreign for shipping • Calif. residents add 6% sales tax.

Zgrass, continued...

ALIEN2 would be created by displaying ALIEN1, making the changes to the leg positions and "snapping" it off again with the snapname ALIEN2. By alternating between ALIEN1 and ALIEN2 and moving the display center slightly each time a snap is displayed, we create the appearance that the creature is really crawling. Small snaps can be displayed so fast that you may have to use a timing loop to keep them from being a blur.

Snaps are great. They are fast and easy—no PEEKing or POKEing—just draw and SNAP! Furthermore, they can be manipulated to create a variety of effects. For instance, the PATTERN command lets us fill a bordered area with a pattern of repeated snaps. This is great for fabric design. I have used it to build large brick walls from a small snap of a few bricks. Snaps are central to Zgrass. Each of our three examples relies on snaps as its central graphic element.

Figure 1 is a still representation of an animation showing the space shuttle landing. On videotape the lander would descend, land and roll to a stop. Note the dust which is a snap also.

Figure 2 demonstrates how snaps can be manipulated. Note the various sizes of the dollars. The SCALE command can be used to stretch, squeeze and reverse snaps both horizontally and vertically.

Figure 2. This picture demonstrates a snap being displayed many times on the screen. The SCALE command is used to vary the size of the snap. By Jane Veeder.

The DISPLAY command is greatly enhanced by the rich color manipulation alternatives provided. These include a complete color filtering system, as well as, automatic OR, AND and XOR. I never really understood these logical operations before working in Zgrass; they seemed far too complicated to be bothered with. Now, I couldn't get along without them. Not only are they useful for dramatic effect, but they save programming time. If we were to program a football game only one team would have to be drawn. The other would be a duplication of the first using the XOR mode and color filters.

The weather map in Figure 3 demonstrates how the color filters can be used. The color filters trim away unwanted colors when snaps are displayed. Notice that the snaps at the bottom of the screen (sun, clouds, etc.) each have a colored border area. Obviously, that border would be unacceptable on the map so the special display mode color filters are used to eliminate it. By the way, this picture (and Figure 1) illustrate user-defined typefonts made possible in this versatile language.

Figure 3. This picture shows a menu-driven program to place weather symbols on a map. This program makes use of the special color filters provided by Zgrass. By Copper Gilroth.

Figure 1. Video animation of the Space Shuttle landing by Jane Veeder.

Conclusions

The ability to draw points, lines, boxes, and even circles in color doesn't guarantee fast, easy animated graphics. Now that I have had the opportunity to work with Zgrass and compare it with Basic, I realize that the underlying concepts and language structure are the most important elements for truly easy graphics generation. Zgrass has been a pleasure to use. It is faster and far easier than Basic to learn and implement. Best of all, it gives me access to graphics power that had always seemed elusive before.

For me, the bottom line is cost-effective animation for professional video production. For others, it may be faster paced and more realistic games or more effective computer aided instruction. If your application involves graphics—particularly real-time animation—then Zgrass deserves a good hard look. □

In Language Lies The Future.

Paul Lutus creates language. Language for the future.
From him we have Apple Writer, Apple World and MusiComp.
His software was used by the Viking Mars Lander team and other advanced space programs.
For the past three years he has applied himself to the development of more efficient and powerful computer languages to help him with his work. These new languages of the future are now available for your use exclusively from Insoft.

See the new world of programming from Insoft at your Apple dealer.

Each package introductory price $125.00

insoft

Apple is a registered trademark of Apple Computer, Inc.

259 Barnett Rd. | Unit 3 | Medford, Or 97501 (503) 779-2466

TransFORTH II

The first [illegible] Apple [illegible] A [illegible] extension of FORTH

- Fully compiled
- Floating point
- Transcendental functions
- Strings and arrays
- Hires, Lores and Turtlegraphics
- Music

Far more compact and approachable than Apple. TransFORTH II is both recursive and structured and easier to use than BASIC.

Over three years in development, this high level language enables you to program in English with far greater speed and convenience than ever before possible.

TransFORTH II. A transformation in computer programming. Available today.

ALD System II

The Applesoft Language Development System, formally the preferred easy way for professional software developers.

- Object files up to 8K
- Source files to 16K
- Cursor based screen editor
- Upper and lower case text entry
- Nested macro instructions
- Local, global and universal labels
- Comprehensive error trapping

The engineering file capacity of ALD System II assures you of the ability to develop virtually any imaginable software system. And you can do so with ease since ALD System II edits with the simplicity of a word processor.

ALD System II. Powerful yet convenient.
*The first choice of professionals.

The best comes last. Both new programs are available for the Apple II or Apple III.

CIRCLE 152 ON READER SERVICE CARD

Please call (213) 883-8594.

Our Epson prices are so low, we're not allowed to print them.

EPSON MX-80 .....$CALL

80 cps/9x9 matrix/Lower case with true descenders/Bi-directional & Logic seeking/Adjustable tractor/Expanded printing/Block graphics/Forms control/Compressed printing/Double-strike printing/Correspondence quality/Emphasized printing mode/Standard parallel interface

EPSON MX-80 F/T .....$CALL

Same features as the MX-80 plus Friction Feed. Adjustable removable tractor is standard for ease of handling forms and single sheets.

EPSON MX-100 F/T .....$CALL

Same features as the MX-80 & MX-80 F/T but on 15½ inch carriage for printing 132 columns with standard 10 cpi font or 232 columns in the compressed character font. The MX-100 is complete with Dot Resolution Graphics

EPSON INTERFACES & OPTIONS

TRS-80 MODEL I III CABLE	$ 30	SERIAL INTERFACE (2K BUFFER)	$ 149
TRS-80 MODEL I Keyboard Interface	$ 95	SERIAL CABLE Male to Male	$ 30
TRS-80 MODEL II CABLE	$ 30	DOT RESOLUTION GRAPHICS	$ 90
APPLE INTERFACE & CABLE	$ 100	REPLACEMENT RIBBON	$ 13
IEEE 488 INTERFACE	$ 60	REPLACEMENT PRINT HEAD (Quiet type)	$ 40
SERIAL INTERFACE	$ 70	EPSON SERVICE MANUAL	$ 40

Alpha Byte STORES

We built a reputation on our prices and your satisfaction.

We guarantee everything we sell for 30 days. If anything is wrong, just return the item and we'll make it right. And, of course, we'll pay the shipping charges.

We accept Visa and Master Card on all orders. COD accepted up to $300.00. We also accept school purchase orders.

Please add $2.00 for standard UPS shipping and handling on orders under 50 pounds, delivered in the continental U.S. Call us for shipping charges on items that weigh more than 50 pounds. Foreign, FPO and APO orders please add 15% for shipping. California residents add 6% sales tax.

31245 LA BAYA DRIVE, WESTLAKE VILLAGE, CALIFORNIA 91362

CIRCLE 170 ON READER SERVICE CARD

New Games for the Apple

David Lubar

Among the software to cross this desk recently are several new games for the Apple II. They are all worth covering, though each might appeal to a different section of the Apple community.

A Shoe in the Works

On-Line Systems has done it again with *Sabotage*, a highly captivating game that will put blisters on anyone's paddle finger. The player has a small cannon at the bottom of the screen. Aiming and firing can be controlled either through a paddle or the keyboard. The player attempts to defend his cannon against helicopters that drop parachutists, and against planes that drop bombs. If enough saboteurs reach the ground, they destroy the cannon in a very amusing manner. If a bomb lands, the cannon is blown to pieces. The player has the option of using steerable shells which curve as the cannon is rotated. With paddle control, a stream of shells can be fired by holding the button down.

If the game sounds too easy, add the fact that each shot costs a point. The player can hose the helicopters with a stream of shells, but that strategy won't contribute much to his score. Once saboteurs reach the ground, they can't be shot. But there is a way to get rid of them. If the parachute is shot away from an attacker in the air, he will fall to the ground with a splat. A saboteur unfortunate enough to be beneath the plummetting paratrooper will be eradicated. The game starts out at an easy pace with just one or two helicopters on the screen at any time. After a while, the planes appear. When the helicopters return, they drop more saboteurs. The shrapnel from struck helicopters can wipe out other helicopters or paratroopers, and it's possible, in this way, to get two or three helicopters with one shot.

The game keeps track of high score during individual runs, but doesn't store the high score on disk. *Sabotage* is a very good game with fine graphics and high replayability.

creative computing

SOFTWARE PROFILE

Name: Sabotage
Type: Arcade Game
System: 48K Apple, Disk Drive
Format: Disk
Language: Machine Language
Summary: Excellent game
Price: $24.95
Manufacturer:
On-Line Systems
36575 Mudge Ranch Rd.
Coarsegold, CA 93644

Sabotage.

On the Circuit

International Gran Prix Racing is everything an Apple game should be, and more. Written by Richard Orban, who created *Three Mile Island*, it is one of the few driving games that successfully solves the paddle problem. Namely, how can a player shift, accelerate, decelerate, and steer without getting hopelessly tangled in a jumble of paddles and keys? The solution in *Gran Prix* is absolutely elegant. The player uses only one paddle. The paddle controls steering. If the button is held, the car accelerates. If the button is quickly released and pressed, the car will shift to the next gear, assuming high enough engine revs have been reached. Releasing the button causes the car to decelerate. During deceleration, a press and release of the button is used for downshifting. If the player desires, he can switch to automatic transmission. There is even a cruise control.

creative computing

SOFTWARE PROFILE

Name: International Gran Prix
Type: Road race game
System: 48K Apple, Disk Drive, Paddles
Format: Disk
Language: Machine Language
Summary: Best road race on the market
Price: $30
Manufacturer:
Riverbank Software, Inc.
Smith's Landing Road
P.O. Box 128
Denton, MD 21629

All this merely scratches the surface of an excellent game. The program is basically a road race game, similar to the arcade game *280-ZAP*, where the screen displays roadposts flashing by the car. The icing on the cake comes in the form of five Gran Prix courses. At the start of the game, the player selects a course, then chooses the number of laps he wants to drive (from 1 to 10). Next, the amount of fuel is selected, followed by the skill level.

International Gran Prix.

There are eight levels. At the easiest, the car barely drifts; in middle levels, it skids; at the top level, the road turns to Teflon.

The dashboard display includes speedometer, tachometer, a timer for current lap and total time, and indicators showing the relation of the tires to the posts. Whenever the car moves dangerously close to the posts, a clicking warns the driver. Collisions are accompanied by a weird sound that seems to defy the limitations of the Apple speaker. The player's best lap time and total time for any course and skill level are stored and displayed by the game. All the curves have names, and these names are displayed on the screen when the car approaches.

Beyond great graphics and superb design, the game also simulates driving with nearly total realism. Whatever algorithms the author used, he did a good job. The car handles very accurately. It can accelerate through curves, go into controlled skids, and fishtale if the player oversteers. *Gran Prix* is a winner.

That Familiar Glow

Fighting its way through the plethora of Missile Command clones, *Norad*, from Western MicroData, emerges as a new twist on the theme. The player has a hi-res map of the good old USA, dotted with ten cities and ten missile bases. Each base has a number. Press that number on the keyboard and a missile leaves the base. The arrow keys control the horizontal motion of the missile. The space bar detonates the missile. If it is detonated close to an incoming warhead, all is well. If not, the warhead hits a city or a base. Cities hit twice are destroyed. Bases are wiped out with one hit. At intervals throughout the game, the cities are rebuilt, and any eradicated bases near a surviving city are replaced. The surviving cities also stock the silos with extra missiles. Silos start with ten missiles. The player receives bonus points for unused missiles.

Norad.

There are three skill levels. Higher levels start with faster attacks, and throw more waves of attack at the player. On each level, the player wins if he survives a specific number of waves. At a certain point, the player is also given an MX missile site which can be moved across the map. The lowest skill level is good for learning the game. The highest level is very tough.

Raiders of the Lost Star

Strongly resembling a certain Atari classic, *Space Raiders* is a search-and-destroy game. Using a joystick or keys, the player moves through galactic quadrants, blasting enemy ships. The strong point of the game is the motion of the stars. The field moves toward the player and shifts realistically when he turns. The question is whether to compare it to the Atari version, or to view it as a game in itself. By comparison, it just doesn't offer the same graphics or sound. What works for the Atari won't necessarily work on the Apple, and vice versa. As a game, it is interesting, but rather repetitive. Only one ship attacks at a time. Basically, the player goes into a sector, destroys all the enemy ships, goes into the next sector, and so on. The player can also dock at a starbase when he needs more energy. The target has to be in the center of the crosshairs to be hit, adding a bit of difficulty to the game. If Atari Star Raiders appeals to you, this is as good a version as is likely to be produced for the Apple.

creative computing
SOFTWARE PROFILE

Name: Norad
Type: Arcade Game
System: 48K Apple, Disk Drive
Format: Disk
Language: Machine Language
Summary: Defend the U.S.A. against missiles
Price: $27.50
Manufacturer:
Western MicroData
Enterprises, Ltd.
P.O. Box G33,
Postal Station G
Calgary, Alberta, Canada T3A 2G1

creative computing
SOFTWARE PROFILE

Name: Space Raiders
Type: Space Fight
System: 48K Apple, Disk Drive
Format: Disk
Language: Machine Language
Summary: Apple version of Star Raiders
Price: $29.95
Manufacturer:
United Software of America
750 3rd Ave.
New York, NY 10017

Treking On

Rainbow has made improvements to *A Stellar Trek* (reviewed Oct., 1980), producing *Super Stellar Trek*. The game offers a hi-res, real-time fight against Klingons and other baddies. The most obvious improvement is the elimination of constant disk access. In the original version, the program went to the disk after every command. Now, the routines remain in RAM, speeding up play and lowering disk wear. The first time a user plays the game he is asked to name all the officers. From then on, this information is used to add color to the game, with reports coming to the bridge from the officers.

creative computing
SOFTWARE PROFILE

Name: Super Stellar Trek
Type: Spacefight simulation
System: 48K Apple, Applesoft, Disk Drive
Format: Disk
Language: Basic
Summary: Good Trek game
Price: $39.95
Manufacturer:
Rainbow Computing, Inc.
19517 Business Center Dr.
Northridge, CA 91324

Overall play is in the basic StarTrek format; the player has a limited amount of time in which to find and destroy the Klingons, using photon torpedos and phasers. Extensive commands are available for such exotic actions as mining dilithium crystals. Those who enjoy Trek games will like this one.

Riverbank Software Inc.

PROUDLY INTRODUCES

INTERNATIONAL GRAN PRIX

an arcade-like race car simulation
by RICHARD ORBAN
author of THREE MILE ISLAND*

REQUIRES APPLE II ★ ★ OR APPLE II PLUS ★ ★ 48K, 13 & 16 SECTOR DISK, PADDLE CONTROL

VISA/MASTERCHARGE
MONEY ORDERS/COD
DEALER/DISTRIBUTOR
INQUIRIES INVITED

$30.00 PER DISK
MD. RESIDENTS ADD 5%
U.S. CURRENCY ONLY

See your local dealer
or call Toll-free
24 hours for
ORDERS ONLY:
1-800-327-9191 ex. 244
(Outside Florida)
INQUIRIES AND FLORIDA
ORDERS: 301-479-1312
SMITH'S LANDING ROAD
POST OFFICE BOX 128
DENTON, MD. 21629

● SPECIAL FEATURES ●

Five GRAND PRIX-style road circuits, including: Oulton Park, Warwick Farm, Karlskoga, and Monaco ● Five speed manual or automatic transmission (with or without cruise control) ● Eight levels of difficulty.

● ADDITIONAL FEATURES ●

Speeds to 198 MPH ● controlled skids ● spinouts ● spectacular crashes ● hair pin turns ● narrow corners ● obstacles ● identified circuit features ● number of laps selection ● flashing last lap indicator ● 'Christmas tree' controlled start ● switch for silent operation ● blue post marks 300' intervals ● best lap/best race times posted ● fully instrumented control panel: lap timer ● race timer ● indicator lights ● edge detectors ● position indicator ● steering indicator ● moving speed tape ● lap counter ● gear and RPM indicators ● operating fuel gauge

RIVERBANK WILL REPLACE DAMAGED DISKS WITHIN 1 YEAR OF PURCHASE. RETURN DISK WITH PROOF OF PURCHASE PLUS FIVE DOLLARS POSTAGE AND HANDLING FOR IMMEDIATE REPLACEMENT (TEN DOLLARS OVERSEAS)

*TRADEMARK MUSE CO., BALT. MD. ★ ★ APPLE COMPUTER, INC., CUPERTINO, CA

CIRCLE 303 ON READER SERVICE CARD

Apple Games, continued...

Ashes to Apples

An arcade game dealing with a certain mythical bird has found its way to the Apple in the form of *Falcons*. The game seems fairly easy for the first ten seconds or so. Several rows of ships move above the player, firing down at his base. This part is reminiscent of Invaders. Then a few ships break formation and swoop down. Now it seems a bit like Galaxian. The similarity vanishes as the attacking ships begin to fly in strange patterns, moving below the screen and attacking the player from below. A transformation suddenly occurs. The ship changes to a falcon and flies evasive patterns. It's worth more points now, but harder to hit. If the player clears the field, he gets another with a different formation. After this second field is cleared, the hard part begins. Small blue dots appear on the screen, weaving back and forth.

creative computing
SOFTWARE PROFILE

Name: Falcons
Type: Arcade Game
System: 48K Apple II or Apple III, Disk Drive
Format: Disk
Language: Machine Language
Summary: Superb and challenging game
Price: $29.95
Manufacturer:
Picadilly Software
89 Summit Ave.
Summit, NJ 07901

They start to grow, becoming large dots, then huge falcons. They swoop at the player, moving at high speed. If hit straight on, the falcon is destroyed. If only winged, it returns. If the player gets through this field without losing his allotment of three ships, he gets a second field of dots that grow into falcons. Survivors are given a chance to destroy the mother ship. Make that MOTHER SHIP. The thing is huge.

Attacking the mother ship in Falcons.

To destroy it, the player first has to blast a hole through the bottom. Next, a hole has to be made in a revolving rim. Once there is a clear path for a shot to the inside, the ship can be destroyed. But the mother ship shoots back. And groups of small ships hover above it, swooping down on the player. If the player destroys the mother ship, the game cycles back through the five levels again.

Beside firing, the player has the option of using shields. A shield lasts for about four seconds, then can't be used again for about five seconds. Shields are great for destroying swooping falcons since the birds are killed on contact with the force field. The game can be played with keys, paddles, or a joystick. There was one rough edge noticeable when fighting the mother ship. Occasionally, one of the attackers wouldn't be entirely erased from the screen when destroyed. But this barely detracts from the appeal of the game. *Falcons* is tough, fun and very well done.

Killer Robots, Drones, and Low-Life Storm Troopers

Mission Escape arrived here two days ago and has already taken control of the staff. They've been lining up to play this one. It is a cross between the arcade game, *Berzerk*, and some high-adrenalin contest that might be thought of as death chess. The player starts at one of four doors to a room containing robots, drones, and storm troopers. His object is to get to the specified exit, and thus, to the next level. The storm troopers fire lasers that do damage to the player's armor. The drones also fire lasers but, if shot, explode with enough force to destroy anything adjacent to them. The robots fire missiles that always kill with one shot. Against this arsenal, the player has three weapons. He can fire a laser, fire a burst of three laser shots, or fire a missile. The missiles and rapid-fire bursts are limited, single laser shots are unlimited.

creative computing
SOFTWARE PROFILE

Name: Mission Escape
Type: Strategy and Action Game
System: 48K Apple, Applesoft, Disk Drive
Format: Disk
Language: Machine Language
Summary: Highly replayable game
Price: $24.95
Manufacturer:
CE Software
801 73rd. St.
Des Moines, IA 50312



Mission Escape.

The player and the enemy alternate turns. The player has ten seconds to issue up to three orders. Movement and firing are controlled from the keyboard. While some keyboard-controlled games are unexciting, *Mission Escape* is definitely not dull. Despite the alternation of turns, there is a real-time feel to it. As an extra touch, the top five scores are kept on the disk. *Mission Escape* is highly recommended.

It Isn't Raining Rain

Finally, in an attempt to make up for not reviewing it sooner, one more game deserves mention in this roundup. *Alien Rain* pits the player against a swarm of hovering, swooping attackers. They start out placidly enough, just moving back and forth across the top of the screen, letting the player pick them off with his ship. Then one or more of the critters comes swooping down, flying a drunken path and raining missiles. Attackers that make it to the bottom wrap around to rejoin the formation at the top. There are two flagships that are worth bonus points if shot while swooping. If the player clears the board, he gets another screenful. If he scores 3000 points, he gets an extra ship.

creative computing
SOFTWARE PROFILE

Name: Alien Rain
Type: Arcade Game
System: 48K Apple, Disk Drive
Format: Disk
Language: Basic
Summary: Tough and fast moving
Price: $24.95
Manufacturer:
Broderbund Software
Box 3266
Eugene, OR 97403

The animation here is very smooth, and the game is tough enough for most players. For those who have it mastered, Broderbund also offers *Alien Typhoon* with more aliens and faster action. □

HI-RES MASTERPIECES

SNOGGLE

You are Snoggle, fleeing through a maze of ghosts who will eat you if they catch you. You have to be quick, you need to be bold, to master the eight levels of this fast-action puzzler. From the Japanese masters of hi-res animated graphics. Apple II Integer/Plus, 48K disk. $24.95

ALIEN TYPHOON

In brilliantly colored array, the Aliens swoop down from all sides in dazzling, swift attacks to do battle upon the lone defender. Keyboard or paddle controlled. Twice as many aliens, twice as fast, as Alien Rain. Apple II Integer/Plus, 48K disk — $24.95

NEW!

SPACE WARRIOR

You are the space warrior, attacked on all sides by multi-colored waves of drone ram ships. You must destroy them all before they pierce your shields and take you to pieces. Hi-res animation from the author of Planetoids! Apple II Integer/Plus, 32K disk — $24.95
16K cassette — $19.95

Brøderbund Software 2 Vista Wood Way San Rafael, CA 94901 . (415) 456-6424

CIRCLE 322 ON READER SERVICE CARD

A Tourist's Guide to the Cybernetic Tower of Babel

George Blank

The whole earth had one language and few words... Then (men) said. "Come, let us build ourselves a city, and a tower with its top in the heavens..." And the Lord came down to see the city and the tower, which the sons of men had built. And the Lord said, "They are one people, and they have all one language; and this is only the beginning of what they will do; and nothing that they propose to do will now be impossible for them. Come, let us go down and confuse their language, that they may not understand one another's speech." So the Lord scattered them abroad from there over the face of all the earth, and they left off building the city. Therefore its name was called Babel (confusion), because there the Lord confused the language of all the earth. (Genesis: Chapter 11.)

According to this Bible story, mankind was given different languages to prevent us from joining together and developing enough power to rival God. Perhaps we have developed the many computer languages to keep the computers from joining together and developing enough power to rival mankind? It is virtually certain that a single good computer language that could be used in any computer without modification would vastly extend the range of what we now do with computers.

There have been many attempts to construct a universal computer language, and I suspect that anyone who has developed a good language could be tempted to wish that it could be universally available. However, it is doubtful that there will ever be an ideal computer language.

Every language has its own design objectives, which usually means that the particular language is ideal for some purposes and inappropriate for others. As a result, most present languages have passionate advocates and equally vehement enemies. Basic, as the most widely used computer language today, probably has the largest and most passionate groups of defenders and detractors.

The reason there is no such thing as the best computer language is that there is no possible way to agree on what the best language should do. Some languages are ideal for the program developer. For example, APL allows rapid and easy development of an application program. Other languages are easy to maintain. The structure of Pascal makes it easy for a programmer to understand what is going on in any particular module, and to make changes as necessary. Basic is popular because it is widely available, can be used in a computer with limited memory, and is not difficult to learn. Therefore manufacturers build it into their computers and programmers write application programs in it. The very characteristics that make some languages ideal for certain applications make them unsuited for other uses.

One way to gain understanding of the strengths and weaknesses of different languages is to write the same program in several different languages. To a certain extent, this is unfair, as any conceivable problem would be well suited to some languages and poorly suited to others. No one problem is likely to demonstrate the real strengths of even two different languages.

We took the uncanny realism and the excitement of John Allen's famous PINBALL; added more features, more thrills, and more sound to come up with new ASTROBALL. Once you load ASTROBALL into your TRS-80* model I or III, the arrow keys become flipper buttons, the screen becomes the play board, and you become the "Pinball Wizard!"

A flying saucer bumper hovers at the top, lights flashing, while spaceship bumpers fly across the board beneath it. Your ball bounces off the moving spaceships in a most unpredictable fashion, so you must stay alert to keep it in play.

As your ball zings around the board scoring on the bumpers, knock out five of the meteor rollovers and you'll get an extra ball. There are double and triple bonus targets to increase your score, too, but be careful—below each is a black hole, waiting to swallow your ball!

ASTROBALL will have all your family and friends lining up for the action and challenge. Five selectable playing speeds make it suitable for all skill levels. Available on your choice of 16K tape or 32K disk for $19.95. Order its companion, PINBALL, for $14.95 on 16K tape, $20.95 on 32K disk.

ACORN PROGRAMS ARE AVAILABLE AT FINE COMPUTER STORES EVERYWHERE

By Steven Kearns

Huge antimatter rocks appear on the Tactical Display Screen of your spacecraft. You blast away but they just explode into smaller chunks for you to destroy.

To add to your woes, alien ships and time bombs appear periodically. If the ships hit you or the timers reach zero—BOOM! Maneuver, fire lasers, jump to hyperspace—anything to avoid the onslaught. For one or two players, with five skill levels.

For TRS-80* model I or III. Versions for 16K tape or 32K disk are $19.95 each.



TENPINS

By John Allen

A realtime action game with 3-D graphics and sound, TENPINS brings the thrill of championship bowling to your TRS-80*

From one to four players participate, and the program senses the skill of each player. Beginners can simply "roll" the ball while the more skilled players can vary the ball's force, direction, and spin.

TENPINS even has factors to simulate imperfections in the lanes, adding even more realism. Available for only $14.95 for 16K tape version, $20.95 for 32K disk.

SUPERSCRIPT

By Richard Wilkes

Using your SUPERSCRIPT modified SCRIPSIT Word Processor and a compatible printer, you can now underline, boldface, insert text during printout, slash zeros, set type pitch, subscript and, of course, superscript! You can even read your directory and kill files without ever leaving SCRIPSIT.

Includes drivers for popular printers and easy instructions. Just $50.00 for TRS-80* model I (requires 32K, 1 drive, SCRIPSIT/LC) or model III (requires 32K, 2-drives, SCRIPSIT/LC model I version).

*Trademark of Tandy Corp.

(202) 544-4259

Acorn
Software Products, Inc.
634 North Carolina Avenue, S.E., Washington, D.C. 20003

ALL ACORN ENTERTAINMENT SOFTWARE SUPPLIED FOR TRS-80* MODELS I & III

MAIL ORDERS: Include $2.00 shipping & handling (D.C. residents add 6% sales tax).
CHARGE CARD CUSTOMERS: Call (202) 544-4259 for fastest service.

CIRCLE 101 ON READER SERVICE CARD

Tower of Babel, continued...

I have prepared a series of programs to illustrate the differences among popular languages in three areas; console input, console output, and common arithmetic. No attempt has been made to polish the programs. In fact, in some of these cases, the program shown is only my second or third program in that language. Except for the Logo and Lisp examples, developed on an Apple II, and the Cobol program which was written by Eric Wolcott of Creative Computing Software, the programs were developed and tested on a Model I TRS-80 microcomputer.

The Problem

Prompt the user and accept two numbers. Display the numbers on the console, calculate the average of the two numbers, and display that as well.

Basic

A Basic language solution to the problem is shown as Listing 1. Basic actually has many advantages as a language for a microcomputer. It is relatively compact, so it does not require much memory. There is now a single computer chip, the Z-8, which has Basic built right in. Because Basic uses standard English words like "PRINT," it is not difficult to learn or to understand. Many special features are available for graphics and file handling. It is easy to connect Basic to machine language subroutines which do things for which Basic is not well suited. As an interpreted language, it is easy to develop programs and test modules while one is writing them. At the same time, compilers are available to increase the speed and security of programs written in Basic.

The most popular version of Basic for microcomputers is Microsoft Basic, which is now available for the Pet/CBM, Apple, TRS-80, Atari, and other popular computers. Microsoft Basic is actually a family of similar languages, ranging from a rather limited version for the Pet to a sophisticated version with many extra features for Atari and CP/M based computers. Applesoft and TRS-80 Level II and Disk Basic fall in between.

There are also several Basic compilers available. Some of them, such as the Basic Compiler from Microsoft, compile completely to machine code. However, most compiled languages require a set of copyrighted routines, called a run-time package, in order to work. While these are usually compiled right into the program, they do pose a problem for someone wishing to sell compiled programs. The company that owns the copyright on the run-time package usually wants a royalty on each copy sold.

I used Accel II, a partial compiler that does not require a license fee for the run-time package, to compile a text processing program I wrote to insert typesetting control codes into my articles. The original was too slow, taking 18 minutes and 20 seconds to process a sample file. After compiling the program with Accel II, it processed the same file in 1 minute and 58 seconds.

Pascal

Pascal is often touted as the language that will replace Basic. The major advantage of Pascal is its modular structure. It practically forces the programmer into good programming habits, which tend to pay off in programs that are easier to debug and modify. Pascal also allows recursive programming, allowing a subroutine to call itself. Another advantage is the ability to use local variables, eliminating conflicts between variables so familiar to Basic programmers. A Pascal solution to our programming problem is shown as Listing 2.

The only popular Pascal that really rivals its Basic competitor in features is Apple Pascal. It has excellent graphics features, text enhancements, and input/output routines. Unfortunately, it also adds at least $500 to the cost of an Apple II Plus. I have three different versions of Pascal for the TRS-80. The UCSD Pascal from FMG Corporation is a complete development system that requires three disk drives. It has been withdrawn from sale, but FMG does offer Pascal/MT, a version that compiles to machine code, for CP/M systems, including TRS-80 CP/M.

Radio Shack sells their Tiny Pascal, at the other end of the spectrum. Two versions are included, one each for 16K and 32K of memory. Both are cassette based. Tiny Pascal is more of a toy than anything else. I found difficulty in following several Pascal textbooks due to the limitations and non-standard functions of the language. However, it is a good way for the person with only a 16K TRS-80 to experiment with Pascal.

In between the other two TRS-80 Pascal versions is Pascal 80 from Ramware. It has a reasonably complete Pascal syntax with several useful extensions. Accuracy of 14 digits on real numbers makes it quite useful for serious applications. The editor is easy to use and the compiler is fast. While both of the other versions give very specific numerical error messages, I hate to look up the codes and prefer the more limited set of English messages (with an arrow pointing to the probable error) in Pascal 80. The manual is limited to 14 small pages, but the language is close enough to standard Pascal to use standard textbooks. After trying out all three versions, I found myself using Pascal 80 exclusively. It only requires a single disk system, and is very tightly coded to conserve memory, leaving about 24K in my 48K system.

APL

My favorite second language is APL 80, a version of APL by Phelps Gates, the author of Pascal 80. APL is a marvelously simple and compact language, as shown by the program in Listing 3. It is an interpreted language, not a compiled language like Pascal. The line numbers are generated by the language, so all the programmer has to do to write a message on the screen is enclose the text in single quotes. The functions are almost all single characters, although some may look strange. For example, the box in lines 2 and 4 is called a "Quad," and tells APL to get an input from the console. The back arrow tells APL to assign the number input to a variable, ONE in line 2 and

Listing 1. Basic program to average two numbers.

```
10 CLS
20 INPUT "Type a number and press ENTER"; A
30 INPUT "Give me another number"; B
40 PRINT
50 PRINT "Your numbers are "; A; " and "; B
60 PRINT
70 PRINT "The average is "; (A + B) / 2
80 PRINT
```

Listing 2. Pascal program to average two numbers.

```
PROGRAM AVERAGE (INPUT, OUTPUT);

VAR ONE, TWO : REAL;

BEGIN
    WRITELN('Type a number and press RETURN');
    READLN(ONE);
    WRITELN('Give me another number');
    READLN(TWO);
    WRITELN;
    WRITELN('Your numbers are ',ONE,' and ',TWO);
    WRITELN;
    WRITELN('The average is ',(ONE + TWO)/2.0);
END.
```

Out of the ashes of a civilization gone mad...
will rise the greatest Empire the galaxy has ever known.

Interactive Fantasies

Soon conquering your local computer store

Edu-Ware Services, Inc. 22222 Sherman Way Suite 102 Canoga Park, CA 91303 (213) 346-6783

CIRCLE 106 ON READER SERVICE CARD

Tower of Babel, continued...

Listing 3. APL program to average two numbers.

```
0:      AVERAGE ;A ;B
1:      'Type a number and press RETURN'
2:      ONE ← ⎕
3:      'Give me another number'
4:      TWO ← ⎕
5:      ' '
6:      'Your numbers are:'
7:      ONE ;TWO
8:      ' '
9:      'The average is ';(ONE +TWO ) % 2
```

Listing 4. Forth program to average two numbers.

```
: AVERAGE CR
." Type a number and press RETURN " #IN CR
." Give me another number " #IN CR
." Your numbers are " OVER OVER . . CR
." The average is " + 2 / . ;
```

Listing 5. Fortran program to average two numbers.

```
00100   C       AVERAGE TWO NUMBERS
00200           REAL ONE, TWO, AVG
00300           WRITE(5,5)
00400   5       FORMAT(' TYPE A NUMBER AND PRESS ENTER ')
00500           READ(4,10) ONE
00600   10      FORMAT(F7.0)
00700           WRITE(5,15)
00800   15      FORMAT(' GIVE ME ANOTHER NUMBER ')
00900           READ(4,10) TWO
01000           WRITE(5,20) ONE, TWO
01100   20      FORMAT(' YOUR NUMBERS ARE',F7.0,' AND ',F7.0)
01200           AVG=(ONE + TWO)/2
01300           WRITE(5,25) AVG
01400   25      FORMAT(' THE AVERAGE IS ',F9.1)
01500           END
```

Listing 6. Cobol program to average two numbers.

```
 ID DIVISION.
 PROGRAM-ID. AVERAGE.
 AUTHOR. Eric P. Wolcott.
 INSTALLATION. Creative Computing.
 DATE-WRITTEN. 8/9/81.
 DATE-COMPILED.
*
 REMARKS: This program will read in two numbers A & B, and
          determine their average. It will print out the
          two numbers and their average.
*
 ENVIRONMENT DIVISION.
 CONFIGURATION SECTION.
 SOURCE-COMPUTER.      TRS-80.
 OBJECT-COMPUTER.      TRS-80.
 INPUT-OUTPUT SECTION.
 FILE-CONTROL.
 DATA DIVISION.
 FILE SECTION.
*
 WORKING-STORAGE SECTION.
 01 A          PIC  S9(9)V9(5) COMP-3 VALUE  0.
 01 B          PIC  S9(9)V9(5) COMP-3 VALUE  0.
 01 AVERAGE    PIC  S9(9)V9(5) COMP-3 VALUE  0.
 01 DISPLAY-A        PIC ---,---,---.9(5) VALUE  0.
 01 DISPLAY-B        PIC ---,---,---.9(5) VALUE  0.
 01 DISPLAY-AVERAGE  PIC ---,---,---.9(5) VALUE  0.
*
 PROCEDURE DIVISION.
*
     DISPLAY "Type a number and press RETURN" UPON CONSOLE.
     ACCEPT A FROM CONSOLE.
     DISPLAY "Give me another number" UPON CONSOLE.
     ACCEPT B FROM CONSOLE.
     MOVE A TO DISPLAY-A.
     MOVE B TO DISPLAY-B.
     DISPLAY "Your numbers are " UPON CONSOLE.
     DISPLAY DISPLAY-A " and " DISPLAY-B UPON CONSOLE.
     COMPUTE AVERAGE = (A+B)/2.
     MOVE AVERAGE TO DISPLAY-AVERAGE.
     DISPLAY "The average is " DISPLAY-AVERAGE UPON CONSOLE.
     GOBACK.
```

TWO in line 4. APL does not restrict the length of variable names, and every character is significant.

If Pascal encourages good programming habits, APL encourages bad ones, especially the writing of incomprehensible code. I constantly find myself writing quick and dirty code in APL, partly because it is so easy and partly because every program statement must be complete on one screen line. APL is so easy to learn that APL 80 comes with a self teaching course in the language on the diskette. Since the TRS-80 does not allow the standard APL character set, APL 80 substitutes lower case characters, a compromise that purists find intolerable, and which can lead to confusion when following the textbooks.

Forth

Many computer languages turn their advocates into passionate missionaries for the cause, but few seem as fervent as the Forth fanatics. Ted Nelson, our former editor, is an enthusiastic user of Forth on his Atari. I do not have a version of the language, and have only experimented with it briefly under the tutelage of Dick Miller, who with his wife Jill is the author of MMS Forth for the TRS-80. I liked the language when I used it, and if the mandatory licensing fee didn't make it so impractical for program development, probably would be a convert myself. Jill Miller wrote the program in Listing 4.

Forth compiles itself as it goes along into commands which can in turn form the building blocks for subsequent commands. This makes it rather easy to develop powerful routines which are easily transportable from one program to another. Forth is not far removed from machine language, and is therefore very fast.

Fortran

Fortran is a very fast compiled language normally used for batch processing of large quantities of data. It is probably not suitable for the interactive use common with microcomputers. The extensive and cumbersome formatting that can be seen in Listing 5 does allow the Fortran compiler to create memory-efficient final code, but it creates a great deal of work for the programmer.

Fortran also suffers from age. A quarter of a century ago it was a major step forward in simplifying the solving of mathematical problems. However, the vast majority of research into languages has come since the development of Fortran, and many advances in language design cannot be added onto Fortran.

Cobol

Upon first glance at Listing 6, Cobol appears to be a complex joke. In a small computer, it probably is. The long keywords and complex introduction eat up too much memory for a microcomputer.

ATARI® SOFTWARE

PIRACY: THIS GAME IS OVER.

ATARI® has led the industry in the development of video games such as ASTEROIDS™ and MISSILE COMMAND.™ The outstanding popularity of these games has resulted from the considerable investment of time and resources which ATARI has made in their development. We appreciate the worldwide response from the videophiles who have made our games so popular.

Unfortunately, however, some companies and individuals have copied ATARI games in an attempt to reap undeserved profits from games that they did not develop. ATARI must protect its investment so that we can continue to invest in the development of new and better games. Accordingly, ATARI gives warning to both the intentional pirate and to the individuals simply unaware of the copyright laws that ATARI registers the audiovisual works associated with its games with the Library of Congress and considers its games proprietary. ATARI will protect its rights by vigorously enforcing these copyrights and by taking the appropriate action against unauthorized entities who reproduce or adapt substantial copies of ATARI games, regardless of what computer or other apparatus is used in their performance.

We ask that legitimate software developers cooperate with us to protect our property from any form of software piracy, imitation or infringement. ATARI is currently offering copyright licenses for a limited number of its games to selected software developers. If you happen to be selling a software product which performs a game similar to any ATARI game (such as a game created for a home computer), please contact us immediately. Write to the attention of: Patent Counsel, ATARI, Inc., 1265 Borregas Ave., Sunnyvale, Calif. 94086

ATARI®

A Warner Communications Company

© 1981, ATARI, INC

CIRCLE 287 ON READER SERVICE CARD

```
average {
    int one, two
    pl "Type a number and press RETURN "
    one = gn
    pl "Give me another number "
    two = gn
    pl " "
    pl "Your numbers are";
    pn "one;
    pl " and ";
    pn two
    pl " "
    pl "The average is ";
    pn ((one + two) /2)
}
```

Listing 7. Tiny C program to average two numbers.

and are usually unnecessary in most applications suitable for small computers. However, Cobol is a good language for a major business application. The thorough documentation and easy readability are an asset in a complex program. While we were promised a version of Radio Shack's new Cobol, it did not come in time to allow us to test this program, so the sample program has not been run in a microcomputer.

Tiny C

Our example in Listing 7 really does not capture the flavor of C, as all input and output in the language is done with functions, not native commands. C is a versatile general purpose programming language that was developed at Bell Telephone Laboratories. AT&T is one of the world's largest users of computers, and they even manufacture some of the computers they use. They have developed a microprocessor specifically for the C language. C is popular in both universities and industry, and the powerful computer operating system UNIX was written in C.

Logo

Logo is similar to C in its structure and environment. Both, build on understandings gained with Basic, are well structured, and use the same environment for both programming and execution. Logo is an interactive, procedural language like Forth and APL, which encourages the building of complex functions by combining simple

Languages Available for Some Popular Computers

Computer	Basic Interpreter	Basic Compiler	Pascal	APL	Fortran
Apple II (Softcard)	Included 48K 2D $195 (12)	48K D $395 (12)	48K D $495 (1)		
Atari	32K D $90 (2)				
PET CBM	Included				
TRS-80 Model I	Included	16K C $45 (7) 32K D $75 (7) 48K D $150 (16)	16K C $20 (16) 48K D $100 (15) 48K CPM 2D $250 (6)	32K D $40 (15)	48K 2D $100 (15) 48K 2D $100 (12)
Heath H8, H89	32K D $175 (8)	40K 2D $250 (8)			40K 2D $175 (8)
CP/M		48K D $395 (12)	56K 2D $475 (6) 56K D $225 (11)	48K D $500 (11)	48K 2D $500 (12)

Computer	Cobol	C, Tiny C	Forth	Lisp	Pilot
Apple II (Softcard)	48K 2D $750 (12)	32K D $150 (11)	48K D $50 (10) 24K D $50 (17)	48K D $125 (4) 32K D $100 (13)	48K 2D $150 (1) 48K D $100 (9)
Atari			40K D $80 (14)	48K D $150 (4)	16K (ROM) $90 (2)
PET CBM		32K C $100 (5)			
TRS-80 I	48K 2D $199 (16)	16K C $100 (18) 32K D $100 (18)	16K D $130 (20) 16K C $90 (20)		
Heath	48K 2D $395 (8)	32K D $100 (18)			
CP/M	48K D $750 (12) 56K D $850 (19)	56K D $75 (3) 32K D $100 (18)			

KEY:
16K = Requires 16K memory minimum
C = Cassette D = 1 Disk Drive 2D = 2 Disk Drives
(1) = Supplier Number 1
$99 = Price to nearest dollar

OSI

AARDVARK NOW MEANS BUSINESS!

OSI

WORD PROCESSING THE EASY WAY — WITH MAXI-PROS

This is a line-oriented word processor designed for the office that doesn't want to send every new girl out for training in how to type a letter.

It has automatic right and left margin justification and lets you vary the width and margins during printing. It has automatic pagination and automatic page numbering. It will print any text single, double or triple spaced and has text centering commands. It will make any number of multiple copies or chain files together to print an entire disk of data at one time.

MAXI-PROS has both global and line edit capability and the polled keyboard versions contain a corrected keyboard routine that make the OSI keyboard decode as a standard typewriter keyboard.

MAXI-PROS also has sophisticated file capabilities. It can access a file for names and addresses, stop for inputs, and print form letters. It has file merging capabilities so that it can store and combine paragraphs and pages in any order.

Best of all, it is in BASIC (OS65D 51/4" or 8" disk) so that it can be easily adapted to any printer or printing job and so that it can be sold for a measly price.

MAXI-PROS – $39.95

NEW NEW – NEW
TINY COMPILER

The easy way to speed in your programs. The tiny compiler lets you write and debug your program in Basic and then automatically compiles a Machine Code version that runs from 50-150 times faster. The tiny compilar generates relocatable, native, transportable machine code that can be run on any 6502 system.

It does have some limitations. It is memory hungry – 8K is the minimum sized system that can run the Compiler. It also handles only a limited subset of Basic – about 20 kaywords including FOR, NEXT, IF THEN, GOSUB, GOTO, RETURN, END, STOP, USR(X), PEEK, POKE, :=*'+'/(,),<,>,Variable names A-Z, and Integer Numbers ffom 0-64K.

TINY COMPILER is written in Besic. It can be modified and augmented by the user. It comes with a 20 page manual.

TINY COMPILER – $19.95 on tape or disk

THE AARDVARK JOURNAL

FOR OSI USERS – This is a bi-monthly tutorial journal running only articles about OSI systems. Every issue contains programs customized for OSI, tutorials on how to use and modify the system, and reviews of OSI related products. In the last two years we have run articles like these!

1) A tutorial on Mechina Code for BASIC programmers.
2) Complete listings of two word processors for BASIC IN ROM machines.
3) Moving the Directory off track 12.
4) Listings for 20 game programs for the OSI.
5) How to write high speed BASIC – and lots more –

Vol. 1 (1980) 6 back issues - $9.00
Vol. 2 (1981) 2 back issues and subscription for 4 additional issues - $9.00.

ACCOUNTS RECEIVABLE – This program will handle up to 420 open accounts. It will age accounts, print invoices (including payment reminders) and give account totals. It can add automatic interest charges and warnings on late accounts, and can automatically provide and calculate voluma discounts.

24K and OS65D required, dual disks recommended. Specify sytem.

Accounts Receivable. $99.95

*** * * SPECIAL DEAL – NO LESS! * * ***

A complete business package for OSI small systems – (C1, C2, C4 or C8). Includes MAXI-PROS, GENERAL LEDGER, INVENTORY, PAYROLL AND ACCOUNTS RECEIVABLE – ALL THE PROGRAMS THE SMALL BUSINESS MAN NEEDS. $299.95

P.S. We're so confident of the quality of these programs that the documentation contains the programmer's home phone number!

SUPERDISK II

This disk contains a naw BEXEC* that boots up with a numbered directory and which allows creation, delation and renaming of files without calling other programs. It also contains a slight modification to BASIC to allow 14 character file names.

The disk conteins a disk manager that contains a disk packer, a hex/dec calculator and several othar utilities.

It also has a full screen editor (in machine code on C2P/C4I) that makes corrections a snap. We'll also toss In renumbering and program search programs – and sell the whole thing for –

SUPERDISK II $29.95 (5 1/4") $34.95 (8").

AND FUN, TOO!

BOOKKEEPING THE EASY WAY — WITH BUSINESS I

Our business package 1 is a set of programs designed for the small businessman who does not have and does not need a full time accountant on his payroll.

This package Is built around a GENERAL LEDGER program which records all transactions and which provides monthly, quarterly, annual, and year-to-date PROFIT AND LOSS statements. GENERAL LEDGER also provides for cash account balancing, provides a BALANCE SHEET and has modules for DEPRECIATION and LOAN ACCOUNT computation.

GENERAL LEDGER (and MODULES) $129.95.

PAYROLL is designed to interface with the GENERAL LEDGER. It will handle annual records on 30 employees with as many as 6 deductions par employee.

PAYROLL - $49.95.

INVENTORY is also designed to interface with the general ledger. This one will provide instant information on suppliers, initial cost and currant value of your inventory. It also keeps track of the order points and date of lest shipment.

INVENTORY - $59.95.

GAMES FOR ALL SYSTEMS

GALAXIAN - 4K - One of the fastest end finest arcade games ever written for the OSI, this one features rows of hard-hitting evasive dogfighting aliens thirsty for your blood. For those who loved land tired of) Alien Invaders. Specify system – A bargain at $9.95

NEW – NEW – NEW

LABYRINTH - 8K - This has a display background similar to MINOS as the action takes place in a realistic maze seen from ground level. This is, however, a real time monstar hunt as you track down and shoot mobile monsters on foot. Checking out and testing this one was the most fun I've had in years! – $13.95.

NIGHT RIDER - You've seen similar games in the arcades. You see a winding twisting road ahead as you try to meke time and stey on the road. NIGHT RIDER uses machine code to generate excellent high speed graphics - by the sama author as MINOS.

NIGHT RIDER – $12.95 cassette only

THIEF - Another machine code goody for the C1P cassetta only. You must use mobile cannon to protact the valuable jewels in the middle of the screen from increasingly nasty and trigger happy thiefs. Fast action and fun for one or two players. THIEF $13.95 on C1 cassette only!

SUPPORT ROMS FOR BASIC IN ROM MACHINES – C1S/C2S. This ROM adds line edit functions, software selectable scroll windows, bell support, choice of OSI or standerd kayboard routines, two callable screen clears, and software support for 32-64 characters per line video. Has one character command to switch model 2 C1P from 24 to 48 character line. When installed In C2 or C4 (C2S) requires installation of additional chip. C1P requires only a jumper change. – $39.95

C1E/C2E similar to above but with extended machine code monitor. – $59.95

Please specify system on all orders

This is only a partial listing of what we have to offer. We now offer over 100 programs, data sheets, ROMS, and boards for OSI systems. Our $1.00 catalog lists it all and contains free program listings and programming hints to boot.

VISA

OSI

AARDVARK TECHNICAL SERVICES, LTD.
2352 S. Commerce, Walled Lake, MI 48088
(313) 669-3110

CIRCLE 102 ON READER SERVICE CARD

OSI

```
TO TYPEIN
 OUTPUT FIRST REQUEST
END

TO AVERAGE
 PRINT "
 PRINT [TYPE A NUMBER AND PRESS RETURN]
 MAKE "ONE TYPEIN
 PRINT [GIVE ME ANOTHER NUMBER]
 MAKE "TWO TYPEIN
 PRINT "
 PRINT [YOUR NUMBERS ARE]
 PRINT SENTENCE ( :ONE [AND] :TWO )
 PRINT "
 PRINT [THE AVERAGE IS]
 PRINT ( :ONE +:TWO ) / 2
 PRINT "
END
```

Listing 8. M.I.T. Apple II Logo program to average two numbers.

procedures into larger ones. Although Logo is a powerful and flexible general purpose language, it has been successfully used in teaching programming concepts to even young children. Logo is currently available for the TI 99/4, and will shortly be available for the Apple II.

Our example in Listing 8 is somewhat awkward and unrepresentative of Logo, as the use of holding variables is somewhat foreign to the language. A more typical Logo program to average two numbers is this one, taken from a forthcoming book by Hal Abelson of M.I.T.:

```
TO PAVERAGE :X :Y
 PRINT (:X :Y) / 2
END
```

In a normal Logo environment, the user would enter something like:

PAVERAGE 100 150

and the computer would reply:

125

This style of operation is also typical in APL, where the program:

```
0: PAVERAGE ;A ;B
1: (A + B) / 2
```

would function in exactly the same way.

Lisp

As Listing 9 shows, Lisp is not very well suited to handling numbers. The strength of the language lies in its ability to redefine itself dynamically, treating all present contents of memory including the "program," as data. Normally, self-modifying code is a programmer's nightmare, but this feature is probably ideally suited to creating a relational data base because Lisp can examine and relate the data it is working on to other data. Lisp is popular

Sources of Computer Languages for Popular Computers

(1) Apple Computer
10260 Bandley Drive
Cupertino, CA 95014
(408) 996-1010
Fortran, Pilot

(2) Atari, Inc.
1272 Borregas Ave.
Sunnyvale, CA 94086
(408) 745-2000
Microsoft Basic, Pilot ROM cartridge

(3) Codeworks
Box 550
Goleta, CA 93116
Codeworks C (CP/M)

(4) Datasoft
19519 Business Center Dr.
Northridge, CA 91343
(800) 423-5916
Lisp 1.7 (Apple II), InterLisp 2.0 (Atari)

(5) Eastern House Software
3239 Linda Dr.
Winston-Salem NC 27106
(919) 671-2296
Tiny C (Pet/CBM) Cassette $50, Manual $50

(6) FMG Corp.
P.O. Box 16020
Ft. Worth, TX 76133
Pascal/MT (CP/M), Pascal/Mt (TRS-80 CP/M)

(7) Allen Gelder Software
Box 11721 Main Post Office
San Francisco, CA 94101
Accel cassette, Accel II disk (TRS-80)

(8) Heath Company
Benton Harbor, MI 49022
(800) 253-0570
Microsoft Basic, Basic Compiler, Fortran, Cobol

(9) Muse
330 N. Charles Street
Baltimore, MD 21201
(301) 659-7212
Appilot II (Apple)

(10) Programma International
50 Essex St.
Rochelle Park, NJ 07662
(800) 631-0856
Forth (Apple)

(11) Lifeboat Associates
1651 Third Ave.
New York, NY 10028
(212) 860-0360
APL V80, JRT Pascal, BDS C (CPM)

(12) Microsoft
400 108th Ave. N.E. Suite 200
Bellevue, WA 98004
Fortran, Cobol, Basic Compiler (TRS-80, Apple Softcard, CP/M)
Softcard (Apple)

(13) Pegasys Systems
4005 Chestnut St.
Philadelphia, PA 19104
(800) 523-0725
P-Lisp (Apple)

(14) Quality Software
6660 Reseda Blvd. Suite 105
Reseda, CA 91335
(213) 344-6599
Forth (Atari)

(15) Ramware
6 South Street
Milford, NH 03055
(800) 258-1790
Pascal 80, APL 80 (TRS-80)

(16) Radio Shack
1 Tandy Center
Ft. Worth, TX 67102
Tiny Pascal, Fortran, Cobol, Basic Compiler

(17) Softape
10432 Burbank Blvd.
N. Hollywood, CA 91601
Forth II (Apple)

(18) Tiny C Associates
P.O. Box 269
Holmdel, NJ 07733
(201) 671-2296
Tiny C Manual $50, Media $50
(Apple II, TRS-80, Heath H8/89, Northstar, KIM)

(19) MicroFocus
58, Acacia Road
St John's Wood
London, UK
CIS Cobol (CP/M)

(20) MMS
61 Lake Shore Rd.
Natick, MA 01760
(617) 653-6136
MMS FORTH TRS-80

```
(DEFINEQ GETNUM
    (LAMBDA NIL
        (PROG (NUM)
              LOOP
                    (SETQ NUM( READ))
              (COND ((EQ (# NUM) NIL)
                    (PRINT 'NOT-A-NUMBER)
              (GO LOOP))
              (T (RETURN NUM)))))
(DEFINEQ AVG
    (LAMBDA NIL
        (PRINT '(ENTER TWO NUMBERS))
        (PRINT
              (/
                    (+ (GETNUM) (GETNUM))
              2))))
```

Listing 9. Lisp program to average two numbers.

```
T: TYPE A NUMBER AND PRESS RETURN
A: I
T: GIVE ME ANOTHER NUMBER
A: J
T: YOUR NUMBERS ARE #I AND #J
C: I+J
C: ZJ
C: J+2
C: ZK
*NUM
C: I-J
C: K+1
J(I>J):NUM
J(I=J):NUM
T: THE AVERAGE IS #K
E:
```

Listing 10. Pilot program to average two numbers.

in artificial intelligence research because the redefinition allows the program to be set up to learn from experience.

Pilot

Last, and in my personal bias, certainly the least among languages is Pilot. Pilot was designed for educational use, and seems to assume that a language for teachers must be extremely simple. As a former teacher, I do not like the implication that teachers are not capable of learning better languages. I am also predjudiced against the use of the computer for drill and practice, and Pilot is primarily useful for exactly that. The commands are single letters like T for type and M for match, followed by a colon and the operator. Instead of variables, Pilot has "counters." The version of Pilot I used for Listing 10, no longer available and mercifully forgotten, did not even have division, so I had to divide by repeated subtraction, using a counter to determine how many times 2 could be subtracted from my total. Apple Pilot, the best current microcomputer Pilot of which I am aware, is much more complete.

Conclusion

This trip through ten languages has been conducted for tourists. It is not an attempt to provide a detailed description of the different languages. The sample problem was chosen to illustrate three important functions in an interactive microcomputer environment; console input, console output, and simple calculations. There are many other considerations to choosing a programming language for a particular task. The reader is encouraged to choose the languages which stimulate interest and study them further. □

SAVE $$ **DISCOUNT PRICES** SAVE $$

apple computer

16K APPLE II	1049.00
32K APPLE II	1074.00
48K APPLE II	1099.00
DISK W/CONTROLLER	499.00
DISK ONLY	445.00
APPLESOFT CARD	139.00
INTEGER CARD	139.00
PASCAL SYSTEM	399.00
SILENTYPE PRINTER	349.00
HAYES MICROMODEM	295.00
Z-80 SOFTCARD	295.00
VIDEX 80 COL. BRD.	295.00
16K RAM BOARD	189.00

RAM MEMORY

FOR TRS-80, APPLE II	
16K SET 4118's (200 NS)	24.95

ATARI

400 18K	349.00
800 16K	759.00
410 Recorder	64.00
815 Disk	1199.00
810 Disk	489.00
822 Printer	359.00
825 Printer	779.00
830 Modem	159.00
850 Interface Module	179.00
CX853 RAM	85.00
CX70 Light Pen	64.00
CX30 Paddle	18.00
CX40 Joystick	18.00

VERBATIM DISKETTES

Box of 10 5¼"	29.50
Box of 10 8"	39.50

North Star Computers

HR2-2D-32K	2795.00
HR2-20-48K	2956.00
HR2-2D-64K	3145.00
HR2-2Q-32K	2975.00
HR2-2Q-48K	3165.00
HR2-2Q-64K	3360.00
HRAM 32K	469.00
HRAM 48K	662.00
HRAM 64K	849.00
HDS-18 HARD DISK	4025.00
MDS-DRV-D	495.00
MDS-DRV-Q	665.00
ADC-1-D	740.00
ADC-2-D	995.00
ADC-1-Q	795.00
ADC-2-Q	1285.00

PRINTERS

EPSON MX-70	399.00
EPSON MX-80	499.00
EPSON MX-80 FT	599.00
GRAFTRAX	90.00
INTERFACE (APPLE)	75.00
CABLE	22.50
CENTRONICS 737-1	795.00
CENTRONICS 737-3	855.00
IDS 445G	815.00
IDS 460G	1195.00
IDS 560G	1450.00
NEC 5510 W/TRACTORS	2650.00
NEC 5520 KSR W/TRAC.	2995.00
QUME 5/45 SPRINT	2675.00
FORMS TRACTOR	195.00
STARWRITER W/TRAC.	1695.00
STARWRITER W/O TRACTOR	1500.00

General Information:

We carry a large selection of hardware and software by other companies. Send for our catalog.

We are an authorized repair center for APPLE, ATARI, NORTH STAR, AND EPSON.

PRICES SUBJECT TO CHANGE WITHOUT NOTICE. MARYLAND RESIDENTS ADD 5% SALES TAX

FREDERICK COMPUTER PRODUCTS, INC.

5726 INDUSTRY LANE
FREDERICK, MD. 21701

Store Hours:
MON. THRU THURS. 9:30 AM—9:00 PM
FRI. AND SAT. 9:30 AM—5:00 PM

TO ORDER CALL: (301) 694-8884

The Choice

SUPERBRAIN
INTERTEC DATA SYSTEMS®

		SAVE
Superbrain 64K Double Density	$ 2549	28%
Superbrain 64K Quad Density	$ 2895	28%

ATARI® 800 16K **$739**
SAVE 32%

ATARI®

Atari 400 16K	$ 325
Atari 820 Printer	$ 249
Atari 810 Disk Drive	$ 449
Atari 410 Program Recorder	$ 59
Atari 16K RAM Module	$ 85
Atari 850 Interface	$ 159
Atari Star Raiders	$ 29

Note: Up to 4 weeks delivery on drives.

NO SALES TAX

★ SUPER BUYS

SOFTWARE for Apple II/II+

Apple:		SAVE
Language/Pascal System	$ 379	25%
DOS 3.3	$ 49	20%
Apple Writer	$ 59	21%
The Controller	$ 495	21%
Apple Pilot	$ 119	27%
DOS Tool Kit	$ 59	22%
Apple Fortran	$ 149	25%
Apple Plot	$ 49	30%
Tax Planner	$ 99	33%
Dow Jones News & Quotes	$ 69	28%
Dow Jones Portfolio Eval.	$ 45	10%
Personal Software:		
Visicalc 3.3	$ 159	25%
Visiplot	$ 139	28%
Visitrend/Visiplot	$ 199	31%
Visidex	$ 159	30%
Visiterm	$ 119	27%
Desktop Plan II	$ 159	21%
CCA Data Base Mgt.	$ 79	20%
Zork	$ 29	27%
Muse, Super Text II	$ 109	27%
Info. Unlim., Easywriter	$ 199	13%
Hayden, Sargon II (chess)	$ 29	22%
PFS, Filing/Data Base	$ 69	28%
Stoneware, DB Master (new version)	$ 179	22%
Softech, Stockfile (inventory)	$ 299	35%
Microsoft (on disks):		
Typing Tutor	$ 15	30%
Fortran 80	$ 149	25%
A.L.D.S.	$ 110	10%
BASIC Compiler	$ 299	25%
Olympic Decathalon	$ 19	24%
Cobol 80	$ 559	25%
Wordstar	$ 199	24%
Epson, MX 80 Graphics Dump	$ 7	30%
Insoft		
★ ALD System II	$ 110	10%
★ TransFORTH II	$ 110	10%
★ Accounting Software	$ 365	66%
A full professional quality integrated GL, A/R, A/P, Payroll package. Hot-line support available. Send for free sample printouts.		
Peachtree, Inventory	CALL	CALL
Broderbund, Payroll	CALL	CALL
★ Central Point Software: NEW!		
Copy II Plus *Will copy most copy protected software for your backup in 45 seconds!*	$39.95	

Technical Hotline (503) 772-3803
(CUSTOMERS ONLY-PLEASE HAVE INVOICE # OR PACKING SLIP #)
Oregon Order Desk (503) 773-3803
Repair Department (503) 772-4401

VISA

TOLL FREE (800)547-1289
NATIONAL ORDER DESK

Computer Exchange

National Sales Dept. of CUSTOM COMPUTER
259 Barnett Rd., Unit 3, Medford, OR. 97501

CIRCLE 141 ON READER SERVICE CARD

# of Professionals

HARDWARE for Apple II/II+

		SAVE
Disk II and 3.3 Controller	$ 499	23%
Disk II only	$ 429	18%
Micro-Sci 5" Drives for Apple II:		
* A70, 286K, 5" Drive	$ 499	20%
* A40, 160K, 5" Drive	$ 369	18%
Controller Card with utility diskette	$ 79	21%
Apple, Language/Pascal System	$ 379	25%
M&R, RF Modulator	$ 25	27%
MONITORS:		
* ATI: 9" B&W	$ 139	CALL
12" Color	CALL	CALL
SANYO: 9" B&W	$ 159	32%
12" B&W	$ 249	33%
12" Green	$ 299	25%
NEC 12" Color	$ 429	30%
12" Green	$ 225	21%
DISKETTES, 5", box of 10:		
Apple	$ 44	21%
Maxell	$ 39	33%
Memorex	$ 25	45%
Apple, Game Paddle	$ 30	20%
GSC Videostick, Joystick	$ 35	20%
Keyboard Company: Joystick II	$ 39	22%
Numeric Keypad	$ 119	21%
ABT, Keypad B, 10 key	$ 99	21%
SSM AIO, Serial/Para. Interface	$ 159	20%
CCS: Serial Interface Card	$ 129	35%
Parallel Interface Card	$ 99	37%
Apple, IEEE-488 Card	$ 339	25%
Apple, Clock/Calendar Card	$ 239	15%
80 Column Video Cards:		
Apple, Smarterm	$ 299	17%
* Videx, Videoterm	$ 249	18%
Ask about other Videx accessories		
PRINTERS:		
Apple, Silentype w/Interface	$ 329	17%
Centronics, 737	$ 759	26%
Apple, Centronics 737 Interface	$ 169	33%
* Epson:		
MX 80	CALL	CALL
MX 80 FT	CALL	CALL
MX 100 W/Graphics	CALL	CALL
MX 80/100 Interface	CALL	CALL
MX 80 friction feed adapter	CALL	CALL
MX 80 graphics chip	CALL	CALL
MISCELLANEOUS:		
Apple, Graphics Tablet	$ 695	13%
Microsoft:		
* Z80 Softcard	$ 249	28%
* 16K RAM Card	$ 159	20%
* Hayes: Micromodem II™	$ 299	26%
Smartmodem	$ 249	11%
* Apple, 1 Yr Extended Warranty	$ 175	20%
Mountain, CPS Multifunction Card	$ 179	13%
Corvus.		
5 Meg Hard Disk	CALL	CALL
10 Meg Hard Disk	CALL	CALL
20 Meg Hard Disk	CALL	CALL
Mirror	CALL	CALL

★ STAR INDICATES SPECIAL VALUE

apple computer Sales and Service

We are an authorized dealer and repair center and will repair all Apple equipment regardless of where you purchased it, in or out of warranty. Normally our turn-around time on repairs is 24 hours. Call before sending equipment.

Apple II+

		SAVE
16K	$ 1029	23%
48K	$ 1079	30%
64K	$ 1249	28%
Disk II W/3.3 DOS	$ 499	23%

All are 1981 models with Apple RAM. 64K unit is 48K unit with Microsoft 16K RAM board. 64K units include Applesoft and Integer BASIC's when used with DISK II. The Apple II no longer comes with game paddles. Paddles are extra - CALL.

APPLE ///

		SAVE
128K	$ 3299	
Disk	$ 479	13%
Info Analyst Pack	$ 399	20%

Above prices for mail orders only. Our store showroom is 259 Barnett Rd., Unit 2, Medford, OR. Store prices, which include software service, differ from mail order prices. No mail order sales at store. CALL ORDER DESK.

ORDERING INFORMATION:

Minimum order $100. Money Orders, Cashier Checks or Bank Wire welcomed. Visa and MC orders add 3%. Personal or company checks are accepted (allow 20 days to clear). Add 3% for shipping, handling and insurance. UPS ground is standard. Add 6% total for UPS Blue or 10% total for foreign orders or US Parcel Post. Include your telephone number. No COD's. Prices are subject to change without notice. Order desk hours are 9 to 6 PDT, 10 to 3 Saturdays.

REFERENCES:
We have been an Apple dealer since 1978. Our bank reference is First Interstate Bank (503) 776-5620. We belong to the Chamber of Commerce. (503) 772-6293.

Computer Exchange

National Sales Dept. of CUSTOM COMPUTER
259 Barnett Rd., Unit 3, Medford, OR. 97501

CIRCLE 141 ON READER SERVICE CARD



A Structured Spatial Language

George Arthur Miller

Languages are used to communicate ideas. Until the advent of computers most languages were "natural," such as English or French. Pre-computer examples of "artificial" languages are musical notation and mathemetical symbology.

Readers of *Creative Computing* are, no doubt, familiar with one or more popular computer languages such as Basic or Pascal which are used to communicate procedures or algorithms to a computer. Boxes is a simple language used to communicate how a particular space is to be segmented. Although Boxes can be extended to three dimensions or more, we shall describe only the two dimensional version.

The motivation for developing Boxes came from the need to build a general purpose output routine for a computer calendar. We have a machine which can print text and lines. We wanted the text and lines arranged on a page to look like a standard monthly calendar with Monday, Tuesday, etc. along the top and little boxes for each day. We also wanted a weekly calendar and a daily schedule of activities. Knowing we couldn't please everyone with just one format we designed Boxes to allow us to describe quickly any layout of lines and text on a page.



Figure 1.

There are other languages, such as Xerox's FDL, which accomplish the same goal. What makes Boxes unique is the relative nature of its descriptions. Instead of describing a line or box in page coordinates, each box is described in relation to another box.

Consider a page of blank paper. This page can be divided into two horizontal boxes. The bottom box can be divided into three vertical boxes, and so on. The entire page can be progressively segmented into smaller and smaller boxes until we arrive at an atomic box. An atomic box cannot be further segmented and has two characteristics, a border and text.

An atomic box can have any combination of its top, bottom or sides drawn. In addition, the box can contain written text. A non-atomic box can be segmented horizontally or vertically by any number of subboxes in any proportion of heights or widths. For example, how would we describe the figure in Figure 1?

The page is divided horizontally into two boxes. The top box is six times as high as the bottom box. The box is further segmented into three boxes of equal width, each containing a person's name. This is the English description of the page layout. The same description in the Boxes language is:

```
H 6,1
  [ ]F
  V 1,1,1
    [Sue]F
    [John]F
    [Harry]F
```

Notice there are two non-atomic boxes and four atomic boxes. The atomic boxes are easy to recognize since they have square brackets around the text and are followed by the letter "F." The non-atomic boxes start with either a horizontal or vertical segmentation. The numbers fol-

George Arthur Miller, 2426 Bush St., San Franciso, CA 94115.

Spelling Errors? Does your **TRS-80*** wordprocessor need help?

PROOFREADER™

CAN SPELL* rendezvous *AND* mnemonic *AND OVER 38,000 OTHER WORDS

Now let TRS-80 and Proofreader by Aspen Software Company check your Scripsit*, Electric Pencil, or other documents for spelling and typographical errors. It has all the features needed to meet your proofreading requirements.

- **Checks every single word of even your biggest document in under 5 minutes.**
- **The 38,000 word dictionary is one of the largest available.**
- **Dictionary can be easily extended to add more words such as technical terms or names.**
- **All unknown words are listed on the screen and can be saved on a file for printing.**
- **Works with almost any TRS-80 wordprocessor including Scripsit and Electric Pencil.**
- **Comes with complete and easy to understand User's Manual.**
- **Proof-Edit'™, optional interactive corrections feature for Model I/III**

GRAMMATIK™

BEYOND SPELLING CHECKING

A spelling checker may not be enough! This paragraph contains a number of common errors (indicated by underlining) that will be discovered by Grammatik that would seldom ever be caught by a spelling checker. FOr example, Grammatik checks for improper word usage as identified by a number of writing style manuals (such as "seldom ever). Grammatik will check for the presence of certain words such as jargon or sexist terms. It also checks for consistant punctuation, capitalizAtion, balanced quotation marks and parentheses, and and repeated words. In addition, it will produce a list of all unique words found in your document with the number of times each was used. Grammatik comes with a dictionary of commonly misused phrases and a dictionary of sexist terms. It also includes a complete set of utilities to build, sort, and merge phrase and jargon dictionaries of your own. Works with Scripsit, Electric Pencil, and other standard TRSDOS text files.

	Proofreader	Proof-Edit	Grammatik
MODEL I Requires 32K RAM, 1 disk drive, TRSDOS or NEWDOS	$54.00	$30.00	$49.00
MODEL II Requires 64K RAM, 1 disk drive, TRSDOS 2.0 (can check 1.2 files using XFERSYS)	$109.00	N/A	$99.00
MODEL III Requires 32K RAM, 1 disk drive, TRSDOS	$64.00	$30.00	$59.00
Manual only, specify model (refundable)	$3.00	$5.00	$5.00

Aspen Software programs are professional quality software tools developed for the TRS-80 by a Ph.D. in Computer Science. Other tools include:

— SOFT-SCREEN'™, a powerful, state of the art full screen text editor. Over a year in development, Soft-Screen is compatible with all TRS-80 programming languages, including BASIC, FORTRAN, MACRO, Ratfor, and COBOL. Easy to use, comes with tutorial and full documentation.

— RATFOR, a structured language preprocessor for Fortran developed at Bell Labs. Aspen Software Ratfor provides a number of extensions, including "case" and "string". Includes complete manual with all the information needed to learn and write Ratfor programs. Requires FORTRAN.

— PP-RATFOR, a pretty printer for use with Aspen Software Ratfor. Automatically formats and indents Ratfor source programs.

	Ratfor	PP-Ratfor	Both	Soft-Screen
MODEL I	$49.00	$30.00	$74.00	$49.00
MODEL II	$99.00	$49.00	$139.00	$99.00
MODEL III	$59.00	$34.00	$84.00	$75.00
Manual only(refundable)			$12.00	$15.00

MODEL I, III require 48K, 2 drives, TRSDOS
MODEL II requires 64K, 1 drive, TRSDOS 2.0
Please call or write for details about our wordprocessor

ASPEN SOFTWARE COMPANY™

Orders sent postpaid by first class mail.
Terms: Cash, check, money order, VISA, or Master Card. NM residents add 4% tax.
When ordering, specify model, memory size, number of drives, and operating system.

Formerly SOFT-TOOLS

Dealer inquiries invited

ASPEN SOFTWARE
P. O. Box 339
Dept. C
Tijeras, NM 87059
(505) 281-1634

* Trademark of Tandy Corporation Proofreader, Grammatik, and Soft-Screen are trademarks of Aspen Software.

CIRCLE 262 ON READER SERVICE CARD

lowing the H or V indicate not only into how many boxes the non-atomic box is to be segmented but also in what proportion. So, the "H 6,1" says "divide me horizontally into two boxes with the top box taking 6/7th of the available space and the bottom box taking 1/7th of the available space."

Spaces and indentation are ignored by the computer (except within the square brackets) and are included only to make it easier to read. The letter "F" at the end of each box indicates the full border is to be drawn around the atomic box. A zero means no border is to be drawn. Any

```
V 2,7
  H 5,1,2              []0 []D []0
  H 2,2,1,1,1,1
     V 3,1,3           []0 []8 []0
     V 3,1,3           []8 []0 []8
     V 2,1,1,1,2       []8 []F []4 []F []2
     V 2,5             []8 []E
     V 2,1,1,3         []8 []E []0 []8
     V 4,3             []E []0
```

Listing 1.



Figure 2.

Figure 3.



combination of sides around the box can be drawn by following the square brackets with some hexadecimal digit 0-F. Assume the following assignments of values:



To draw just the top and bottom of a box we would use the hexadecimal digit 5 (1 + 4). Using just this hexadecimal notation, any orthogonal design can be created. Consider the Boxes program in Listing 1.

The output from this program is shown in Figure 2.

This same program produces a similar, but fatter figure when printed on a wider page. The relative nature of Boxes is demonstrated in Figure 3.

At this point it might be helpful to go through the construction of a box diagram step by step. Prior to the execution of any Boxes instructions, there is a single, undivided rectangular box. No subdivisions, borders, or text have been specified:

The first instruction will be a vertical subdivision, with a 1:1 ratio of the size of the resulting subboxes:

V 1,1

The shaded box designates the next focus of attention. Next, we horizontally segment the shaded box with the top box twice as large as the bottom:

H 2,1

No longer wanting to subdivide the shaded box, we specify the border for the box (this is the first atomic box). The hexadecimal digit D (1+8+4) will produce the border consisting of the top, bottom and left walls as follows: ||D

apples apples apples apples

WE HAVE EVERYTHING YOU NEED FOR YOUR APPLE COMPUTER

LET AN ACP PROFESSIONAL PUT TOGETHER A SYSTEM TO MEET YOUR BUSINESS OR PERSONAL NEEDS.

apple computer Sales and Service

Apple II® 64K

- Z-80 Softcard
- 16K Ram Card
- Disk II w/controller
- Apple II w/48K

Maxi-System

Call for more pricing!

Total Value $2719.00 your price $2229.00

save! *For Pascal System add $425.00*

apple II hardware clearance up to 25% off

Vista TPS/APL/LIS			BC Hawes Microchipset II	249.95	New
Revolution Processor/Apple II P S	399.95	New	Apple Centauri	1295.00	
Revolution Processor/Z80	229.95	New	Apple Hi Speed Serial I/O	174.00	
Vision 80 16K/24 Card	325.95	New	Apple Hi Speed Parallel I/O	174.00	
Vision 80 Hot Job enhancement	125.00	New	Apple Hi Speed Serial I/O	174.00	
Vision 80 Hot Job 5.5" Controller	175.00	New	Apple Hi Speed Parallel I/O	174.00	
Microsoft Z-80 Softcard	349.00		Apple Hi Speed Parallel I/O	174.00	
Microsoft 16K Ram card	195.00		Apple Hi Speed Parallel I/O	174.00	
SSM AIO Serial/Parallel I/O	159.00		Apple Hi Speed Parallel I/O	174.00	
SSM Serial/Parallel/Clock Calendar	179.00		Apple Hi Speed Parallel I/O	174.00	
CCS Parallel Card 7728	150.00		Apple Hi Speed Parallel I/O	174.00	
Apple Joystick "BEST"	54.00		Apple Hi Speed Parallel I/O	174.00	
Microsoft Softcard			Apple Hi Speed Parallel I/O	174.00	
Remove 1	149.00		Apple Hi Speed Parallel I/O	174.00	
Ram Writer	150.00		Apple Hi Speed Parallel I/O	174.00	
Ram Writer II	150.00		Apple Hi Speed Parallel I/O	174.00	
Hippo/Hi Remote Cont. Sys.	249.95		Apple Hi Speed Parallel I/O	174.00	
Super Talker	275.00		Apple Hi Speed Parallel I/O	174.00	
Super Talker	275.00	New	Apple Hi Speed Parallel I/O	174.00	
CPS Multifunction	229.00	New	Corvus 10Mb Hard Disk	Call	
Supertron Chassis	699.95	New	Corvus 20Mb Hard Disk	Call	New
BC Hawes Microchipset	249.95	New	Corvus Omnidisk	Call	
Thunderclock	275.00		Corvus Omnilink	Call	
S-100 Option*	49.95	New	ACP 16K Upgrade Kit	34.95	
Pascal Fix 80/64*	29.95	New	Scott Micro Peripheral VST 2	895.00	New

apple /// Triple Play!

1. Apple III 128K RAM Dual Drives Amphenol Plug 12" Green Phosphor Monitor — 4200.00
2. Apple III 128K RAM Dual Drives Amphenol Plug Apple Green Phosphor Monitor Drive 0 Drive 1 Apple III Expansion Chassis — 5100.00
3. Apple III 128K RAM Dual Drives Amphenol Plug Apple Green Phosphor Monitor Drive 0 Drive 1 Apple III Expansion Chassis — 5500.00

Buy a System and Save

New apple software

We only offer Apple CPM software which has been evaluated by our software staff

Visicalc—Now Better Than Ever	169.00	WORDSTAR The Benchmark of Wordprocessing software requires Z-80	349.00
Visiplot—Graph your Visicalc Worksheets	149.00	VITA 80 CP/M Wordprocessor has no screen thetus uses new keycode (revolution) to display Key.	319.00 New
Visiplot—Graph your Visicalc w/Tand Analysis	239.00	MAIL-MERGE A Wordstar Enhancement Prog. allows form-letter generation & chained printing	199.00
Visidex—The Ultimate DBMS Visicalc Compatible	219.00	SPELLGUARD Will proofread Wordstar & VITA 80 Text files against an expandable 20,000 word dictionary	199.00
Visiterm—Communicate w/other Systems	209.00		
BPI General Ledger	299.00	SUPER SORT Will sort, merge, & perform record selection on your CP/M Data Files	199.00
BPI Accounts Receivable	299.00		
BPI Inventory	299.00	PORTRA 80 by Microsoft	195.00
Bookmite Inventory System	349.00		
Infosys Inventory System	499.00	COBOL 80 by Microsoft	749.00
Mailmite Mailing List	229.00		
Microsyn Microbiograph	229.00	ACB BASIC ACCOUNTING SYSTEM. Total accounting system includes G/L, A/R, A/P, PAYROLL	995.00 New
Accounting Plus I/BPI Prog.	1250.00		
Stoneware DB Master	199.00		
Stoneware Utility Prog (For above)	99.00		

NEW Breakthrough In Mass Storage!

Vista Dual 8" Subsystem

New Double Sided Double Density DMA Floppy Disk Subsystem For Your Apple II

Features:

- High speed DMA transfer of data (1 microsecond byte)
- Complete documentation provided — includes theory of operation, source code for DOS enhancement utilities, schematics and diskette
- Uses all standard Apple DOS commands (OPEN CATALOG, LOCK, DELETE, LOAD, etc) except for INIT which has been improved and enhanced in a Vista format routine
- Compatible with Apple DOS 3.2/3.3 Pascal 1.1 and CPM 2.2 (with the Z80 soft card by Microsoft)
- 2K x 8 PROM contains Autoboot functions and all eight-inch floppy driver code allowing complete compatibility with Apple DOS 3.2/3.3
- 120 days parts and labor warranty
- Immediate delivery

System includes:

- Vista V1000 subsystem w/case power supply & two QUME DATATRAK 8 Disk Drives
- Vista A800 Quad Density DMA Disk Controller with software
- 5-foot interconnecting cable (50 pin)

	List Price
V1000 —	2295.00
A800 —	595.00
Cable —	49.00
Ready To Run	$2939.00

Advanced Computer Products System Package Special

$2495.00

NEW

Wordstar from Micro-Pro

The "ultimate Word Processor" requires Z80 Softcard, Ramcard, and 80 col card

$349.00

Mail-Merge

Enhancement package for Wordstar available now

$169.00

Locksmith Ver. 3.1

Back-up your valuable software only

$79.95

ROMWRITER

Program your own EPROMs Create your own firmware Programs 2K, 2716 5V EPROMs Disk software package provides easy EPROM programming EPROMs are verified after BURN RUN your programs from on-board socket or install them on ROMPLUS

$175.00

ADVANCED COMPUTER PRODUCTS

RETAIL STORES OPEN MON - SAT

STORE #1: 1310 "B" E. Edinger, Santa Ana, CA 92705
STORE #2: 542 W. Trimble Road, San Jose, CA 95131 • (408) 946-7010

Showrooms, Retail, Warehouse Specializing in Systems

FOR INTERNATIONAL ORDERS: 1310 E. Edinger, Santa Ana, CA 92705 TWX 910-595-1565

P.O. Box 17329 Irvine, Calif. 92713
Direct Order Lines: (714) 558-8813
(800) 854-8230 or (800) 854-8241

Having completed the first atomic box, the focus of attention switches to the box immediately below. It may be further subdivided if so desired, but instead we choose to consider it an atomic box also, and draw the right wall only: |]2

Continuing in a similar fashion, the diagram is completed when the final atomic box is outlined:

H 1.2



|]C

|]6

Combining these steps, the Boxes program.

```
V 1,1
  H 2,1
    |]D
    |]2
  H 1,2
    |]C
    |]6
```

produces the following result:

The only thing left to describe is what can go inside the square brackets of an atomic box. Actually any sort of other language can be used here. For example: a graphics language describing pie charts and bar graphics might be used. For our purposes a simple word processing language was chosen.

Text placed in the square brackets is printed in the atomic box as written, it is left justified and word wrapped until the box is filled. There are three special characters which influence the way the text is written within the box: ";" and "*" and ">."

The semicolon is used to indicate a required carriage return. For example one;two| will come out in two lines within a box.

The asterisk, "*," is a special character which acts as padding of spaces. The asterisk will insert enough spaces to push



surrounding strings to the edge of the box. For example |one*two| will come out as one line in a box with "one" all the way to the left and "two" all the way to the right:



More than one asterisk can appear on any line. When this happens, an equal amount of space is allocated to each asterisk. In addition, when a line has only an asterisk and nothing more the padding will be vertical rather than horizontal. For example |*;*one*| will produce a box with "one" centered on the bottom:



The " > " is used for simple indentation with an atomic box. Any text following a " > " will word wrap back to the column in which the " > " appears. The " > " (as well as the semicolon and asterisk) will not be printed. For example:

|Step 1: > Sketch out a rough draft of
... your boxes on a piece of paper;;...

Step 2: > Identify all of the atomic boxes|

will print as:

```
Step 1: Sketch out a rough
        draft of your boxes
        on a piece of paper

Step 2: Identify all of the
        atomic boxes
```

Systems With Spice...
Everything's Nice with California Computer Systems

Spice up your S-100 or Apple II™ with system enhancements from ASAP. From motherboards and mainframe cabinets to I/O boards and RAMs, we have the California Computer System product that will give you the added capability you need.

FOR S-100 USERS

32K Static RAM Board — 200 nS RAMs, compatible with Alpha Micro, Cromemco and others. 32K memory divided into 8K blocks. Fully static 2114 RAMs. Assembled and tested.

Part Number 2032C ..... Price: $610.00

16K Static RAM Board — 200 nS RAMs, compatible with Alpha Micro, Cromemco and others. 16K memory divided into 4K blocks. Assembled and tested.

Part Number 2116C ..... Price: $290.00

64K Dynamic RAM Board — For 8080 and Z-80 based S-100 systems. Provides processor-transparent refresh. 200 nS, 4MHz. Supports IMSAI-type front panels. Expandable. Assembled and tested

Part Number 2065C ..... Price: $550.00

Z-80A CPU Board — 2 or 4MHz, switch selectable. 158 instructions, including 8080's 78 instructions for total 8080 software compatibility. 2K monitor ROM and RS-232-C port on-board. Assembled and tested.

Part Number 2810A ..... Price: $239.00

Floppy Disk Controller — Controls up to four 5¼" and 8" drives in any combination. Double-sided and side-select signals for double-sided drives. Compatible with IBM 3740 and System 34 standards.

Part Number 2422A ..... Price: $335.00

CP/M™ Version 2.2 Free With Purchase

S-100 Mainframe — 12-slot motherboard. Active termination on all bus lines. Built-in power supply, fan and circuit breaker. "Double path" trace pattern. Solder plated circuit area. Assembled and tested.

Part Number 2200A ..... Price: $350.00

2201A (220VAC) ... $375.00

S-100 Motherboard — 12-slot capacity using standard S-100 connectors. Capable of supporting CPU's at 4MHz and above. "Double path" trace pattern. On-board voltage regulator.

Part Number 2510A ..... Price: $105.00

4-Port Serial I/O Interface — 4 individually-controlled asynchronous ports. Fully buffered inputs and outputs. Includes RDM circuitry for 2716 2K EPROM (user supplied). Ports meet RS-232-C interface specs. 3 control and 3 status registers per port.

Part Number 2710A ..... Price: $265.00

2-Serial, 2-Parallel I/O Board — Fully buffered inputs and outputs. Includes RDM circuitry for 2716 2K EPROM (user supplied). Parallel ports have full four-line-per-port handshaking and 8-bit data transfer. Serial ports meet RS-232-C interface specs. Port A transmits and receives in asynchronous mode; Port B in either synchronous or asynchronous.

Part Number 2718A ..... Price: $275.00

4-Port Parallel I/O Board — 3 I/O ports and one output port. Seven bit status register. Fully buffered inputs and outputs. RDM circuitry for 2716 2K EPROM (user supplied). Ports provide 8-bit parallel data transfer; TTL-compatible.

Part Number 2720A ..... Price: $195.00

FOR APPLE II™ USERS

Synchronous Serial Interface — Compatible with RS-232-C (configurations A thru E, 1978). Supports full or half duplex. DTC type interface.

Part Number 7712A ..... Price: $149.00

Programmable Timer — Time events in continuous, single shot, frequency comparison and pulse width comparison modes. Interface patch area for custom interface applications.

Part Number 7440A ..... Price: $ 95.00

Asynchronous Serial Interface — RS-232-C compatible (configurations A thru E, 1978). DCE type interface; supports half or full duplex operation.

Part Number 7710A ..... Price: $139.00

Calendar/Clock Module — Accurate, real-time counting. Software programmable for 12- or 24-hour format. Each decimal digit of data is separately addressed for freedom of data format.

Part Number 7424 ..... Price: $ 99.00

3¾ Digit BCD A-to-D Converter — Converts DC voltages to BCD numbers for monitoring and anaylsis. 400 mSec per conversion. -3.999 to +3.999 VDC full scale. ±5% non-linearity.

Part Number 7470A ..... Price: $ 95.00

12K RDM/PROM Module — Capable of accepting operating systems, system patches or firmware in 2K increments of mixed ROM or PROM. Addressable 12K in any of 4 16K blocks. 2316E ROM and 2716 PROM compatible.

Part Number 7114A ..... Price: $ 65.00

Parallel Interface — Two bidirectional 8-bit buses for interface to peripherals. Two programmable control registers. Four individually controlled interrupt input lines, two usable as peripheral control outputs.

Part Number 7720A ..... Price: $ 99.00

Arithmetic Processor — Add, subtract, and divide; trig and inverse trig functions; square roots, logarithms and exponentiation. Fixed point 16 and 32-bit operation.

Part Number 7811A ..... Price: $349.00

Centronics Printer Interface — Interfaces high-speed Centronics-type parallel printers to Apple II™ computers. Features 8-bit parallel data output bus, 4-bit status input, Data Strobe and Acknowledge handshake signals and printer reset signal.

Part Number 7728A ..... Price: $ 95.00

asap computer products, inc.
1198 E. Willow St., Signal Hill, CA 90806

Toll free outside California:
(800) 421-7701
Inside California:
(213) 595-6431
(714) 891-2663

ASAP offers a 120-day buyer protection policy; full money-back guarantee if not totally satisfied.

Ordering information: name, address, phone, ship by UPS or Mail. Shipping charge: add $2.50 up to 1 lb (UPS blue); U.S. Mail add $1.50 (U.S. only) ($25.00 minimum order).

Terms: We accept cash, check, money orders, Visa and Master Charge (U.S. funds only). Tax 6% Calif. Res. COD's and terms available on approval (school PO's accepted).

CIRCLE 109 ON READER SERVICE CARD

July 1981

M	T	W	T	F	S	S
		1	2	3	4	5
6	7	8	9	10	11	12
13	14	15	16	17	18	19
20	21	22	23	24	25	26
27	28	29	30	31		

Monday		6 2:30 Meeting with Mr. Smith, Auditor	13 3:30 APR demo on COOLS - See Steve for place 1) reminder - call Vincent for tour of his office	20 9:00 Strategic Planning Workshop at the Holiday Inn	27
Tuesday		7 8:30 Labor Relations class	14 10:45 Tech Council Meeting - asked to attend by Frank	21 9:00 Strategic Planning Workshop at the Holiday Inn	28
Wednesday	1 1) Vacation - White water rafting on the Klamath river	8	15	22	29
Thursday	2 1) Personal Choice Day - Rafting	9 9:00 Monthly IOS Staff Meeting 2:00 Meet with Rick Pflaum	16 1) STAR Demonstration	23	30 1) Start Planning Process
Friday	3 1) 4th of July Holiday - Rafting	10 9:00 Tech Session 2:00 Meeting with Svend 7:30 Dinner at Keith and Brett's	17	24	31
Saturday	4	11 7:00 Dinner	18	25	
Sunday	5	12	19	26	

Figure 4. Sample Calendar Produced Using Boxes

Beat The Socks Off Your Computer's Quarterback—You Hope
Tuesday Morning Quarterback
COMPUTER GAMES THINKERS PLAY
EPYX
CIRCLE 110 ON READER SERVICE CARD

Small Business Systems User!

WHEN BUYING CHECKS, STATEMENTS AND INVOICES — LOOK FOR THIS MARK:

DFS Computer Forms

ON THE DOOR OF YOUR COMPUTER STORE

DFS Computer Forms are

- Sold by a Local Business
- Satisfaction Guaranteed
- Available in Small Quantities
- Compatible with Existing Software
- Very Economical

DFS Computer Forms

P.O. Box 643 • Townsend, MA. 01469

36460

CIRCLE 305 ON READER SERVICE CARD

Boxes, continued...

Notice the use of the ellipses, "...". They can be used to break up a long line of text in an atomic box description. The ellipsis and all following blanks will be ignored by the program. This is important since all other blanks in the text of an atomic box are otherwise accepted like any other character.

As mentioned at the beginning, the motivation for creating Boxes was to have an easy-to-use language to produce calendars. On page 112 is an example of such a calendar (Figure 4). You may be somewhat startled at the complexity of the Boxes program (Listing 2) in the following example. This program was written by the Calendar program using Boxes as an intermediate language for forms creation. □

```
h 1,7
  v 26,46,21
    [|0
  [⍕;⍕July, 1981⍕;⍕|0
  [⍕ M  T  W  T  F  S  S⍕;...
   ⍕    1  2  3  4  5⍕;...
   ⍕ 6  7  8  9 10 11 12⍕;...
   ⍕13 14 15 16 17 18 19⍕;...
   ⍕20 21 22 23 24 25 26⍕;...
   ⍕27 28 29 30 31      ⍕|0
v 5,8,8,8,8,8
  h 11,11,11,11,11,3,3
    [⍕;Monday;⍕|0
    [⍕;Tuesday;⍕|0
    [⍕;Wednesday;⍕|0
    [⍕;Thursday;⍕|0
    [⍕;Friday;⍕|0
    [⍕;Saturday;⍕|0
    [⍕;Sunday;⍕|0
  h 22,11,11,11,3,3
    [|0
    [⍕1;⍕;1) Vacation - White water rafting on the Klamath river|F
    [⍕2;⍕;1) Personal Choice Day - Rafting|F
    [⍕3;⍕;1) 4th of July Holiday - Rafting|F
    [⍕4;|F
    [⍕5;|F
  h 11,11,11,11,11,3,3
    [⍕6;2:>30 Meeting with Mr. Smith, Auditor|F
    [⍕7;8:>30 Labor Relations class|F
    [⍕8;|F
    [⍕9;9:>00 Monthly IOS Staff Meeting;2:>00 Meet with
    Rick Pflaum|F
    [⍕10;9:>00 Tech Session;2:>00 Meeting with Svend;...
          7:>30 Dinner at Keith and Brett's|F
    [⍕11;7:>00 Dinner at Stacy's|F
    [⍕12;|F
  h 11,11,11,11,11,3,3
    [⍕13;3:>30 APR demo on COOLS - See Steve for place;⍕;...
          1) reminder - call Vincent for tour of his office|F
    [⍕14;10:>45 Tech Council Meeting - asked to attend by Frank|F
    [⍕15;|F
    [⍕16;⍕;1) STAR Demonstration|F
    [⍕17;|F
    [⍕18;|F
    [⍕19;|F
  h 11,11,11,11,11,3,3
    [⍕20;9:>00 Strategic Planning Workshop at the Holiday Inn|F
    [⍕21;9:>00 Strategic Planning Workshop at the Holiday Inn|F
    [⍕22;|F
    [⍕23;|F
    [⍕24;|F
    [⍕25;|F
    [⍕26;|F
  h 11,11,11,11,11,6
    [⍕27;|F
    [⍕28;|F
    [⍕29;|F
    [⍕30;⍕;1) Start 1982 Planning Process|F
    [⍕31;|F
    [|0
```

Listing 2: A Program Written in Boxes to Produce a Calendar.

LOWEST SOFTWARE PRICES - UNBEATABLE DISCOUNTS

STOP

if you didn't buy from CPI you paid too much! We won't be undersold.

STOP

We'll meet any nationally advertised software prices even 45 days after your order. (Just send a copy of the ad.)

APPLE. APPLE APPLE APPLE

Adventure Time

ADVENTURE INTERNATIONAL

Adventure #1, 2, 3	d	32.00
Adventure #4, 5, 6	d	32.00
Adventure #7, 8, 9	d	32.00
Adventure #10, 11, 12	d	32.00
Stone of Sisyphus	d	24.00
Kid Adventure #1	c	12.00
Adv. Hint Book	d	6.50

AUTOMATED SIMULATIONS

Rescue at Rigel	c/d	24.00
Morlac's Tower	c/d	16.00
Datestones of Ryn	c/d	16.00
3 PAK (all 3 above)	d	40.00
Temple of Apshai	d	32.00
Invasion Orion	c/d	20.00

BRODERBUND SOFTWARE

Galactic Empire	d	20.00
Galactic Trader	d	20.00
Galactic Revolution	d	20.00
Tawala's Redoubt	d	24.00

EDU-WARE

The Prisoner	d	24.00
Terrorist	d	24.00

ON-LINE SYSTEMS

Hi-Res Adv. #0	d	16.00
Hi-Res Adv. #1	d	20.00
Hi-Res Adv. #2	d	26.50
Hi-Res Adv. #3	d	28.00
Softporn Adv. (Isolated)	d	24.00

SYNERGISTIC SOFTWARE

Wilderness Campaign	d	16.00
Dungeon Campaign	d	14.00
Wilderness Dungeon	d	26.00
Odyssey	d	24.00
Doom Cavern Sorcerer	d	16.00
Escape from Arcturus	d	24.00
Dungeon Campaign	c	12.00
Wilderness Campaign	c	14.00

AVON HILL GAME

Empire Overmind	d	28.00
Conflict 2500	c	12.00
Planet Miners	c	12.00
Computer Acquire	c	16.00
Lords of Karma	c	16.00
Empire Overmind	c	24.00

CONTINENTAL SOFTWARE

L.A. Land Monopoly	d	24.00
Torpedo Terror	d	20.00
The Guardian	d	20.00

HIGHLANDS COMPUTER

Oldorf's Revenge	d	16.00
Tarturian	d	20.00
Creature Venture	d	20.00

PERSONAL SOFTWARE

Zork	d	34.00
Gammon Gambler	d	21.00
Monty Monopoly	d	29.00
Monty Scrabble	d	29.00
Micro Chess	d	21.00
Bridge Partner	d	21.00
Checker King	c	17.00
Micro Chess	c	17.00

★ ★ ★ KEY ★ ★ ★
d = Disk
c = Cassette
★ ★ ★ b = book ★ ★ ★

Apples = BUSINESS

CONTINENTAL SOFTWARE

#1 General Ledger	d	200.00
#2 Accts. Rec.	d	200.00
#3 Accts. Pay.	d	200.00
#4 Payroll	d	200.00

DENVER SOFTWARE

Financial Partner	d	140.00

HOWARD SOFTWARE

Tax Preparer	d	80.00
Real Estate Analyzer	d	120.00
Creative Financing	d	120.00

PERSONAL SOFTWARE

Desk Top Plan II	d	166.00
Visicalc 3.3	d	166.00
Visiplot	d	151.00
Visiboard Visiplot	d	219.00
Visidex	d	166.00
Visiterm	d	127.00

SOFTWARE PUBLISHING

PFS (Filing Sys)	d	76.00
PFS: Report	d	76.00

MICRO PRO (CP/M)

Spell Sort I	d	195.00
Word Star	d	290.00
Data Star	d	290.00
Mail Merge	d	95.00
Super Sort I	d	155.00

Programmer Helpers

DENVER SOFTWARE

Pascal Programmer	d	100.00
Pascal Tutor	d	100.00

HAYDEN SOFTWARE

Assembly Dev. Sys.	d	32.00
Applesoft Compiler	d	160.00

IUS

FORTH Dev. Sys	d	112.00

MICROSOFT

Fortran 80	d	156.00
A.L.D.S.	d	100.00
Basic Compiler	d	316.00
Cobol 80	d	600.00
SOFT Card	d	335.00
RAM Card	d	165.00

SYNERGISTIC SOFTWARE

Prog. Line Editor	d	32.00
Higher Fonts	d	12.00
Higher Text II	d	32.00
Higher Graphics	d	28.00
Prog. Line Editor (ROM)		48.00

UNITED SOFTWARE

3-D Super Graphics	d	32.00
KRAM	d	80.00
Super KRAM	d	140.00
Request	d	180.00
Thinker	d	395.00

ARCADE in to Home

BRODERBUND SOFTWARE

Snoggle	d	20.00
Galaxy Wars	d	20.00
Alien Rain (Galaxian)	d	20.00
Alien Typhoon	d	20.00
Apple Panic	d	24.00
Space Maziac	d	20.00
Snoggle (Joystick)	d	26.50

BUDGECO

Raster Blaster	d	24.00

CAVALIER COMPUTER

Astroid Field	d	20.00
Star Thief	d	24.00

CONTINENTAL SOFTWARE

Hyperspace Wars	d	24.00
3-D Skiing	d	20.00

INNOVATIVE DESIGN

Pool 1.5	d	28.00
Shuffleboard	d	24.00

MUSE

3 Mile Island	d	32.00
A B M	d	20.00
Robot Wars	d	32.00

SENTIENT SOFTWARE

Oo-Topus	d	26.50

SIRIUS SOFTWARE

Star Cruiser	d	20.00
Cyber Strike	d	32.00
Phantoms Five	d	24.00
Space Eggs	d	24.00
Pulsar II	d	24.00
Oblivion	d	24.00
Autobahn	d	24.00
Gamma Goblins	d	24.00
Gorgon	d	32.00
Sneakers	d	24.00

SIR TECH SOFTWARE

Galactic Attack	d	24.00
Wizardry	d	32.00

SOFTAPE

Apple "21"	d	16.00
Craps	d	16.00
Gomoku	d	16.00
Microgammon II	d	16.00
Roulette	d	16.00
Crosswords	d	24.00
Draw Poker	d	24.00

STRATEGIC SIMULATIONS

Warp Factor	d	32.00
Torpedo Fire	d	48.00
President Elect.	d	32.00
Computer Bismarck	d	48.00
Computer Ambush	d	48.00
Computer Napoleonic	d	48.00
Computer Air Combat	d	48.00
Computer Conflict	d	32.00
Cartels & Cut Throats	d	32.00
Computer Baseball	d	32.00
Computer Quarterback	d	32.00
Oper. Apocalypse	d	48.00

*Requires 280 SOFTCARD.

Prices subject to change without notice. All products full guaranteed

★ ★ ★ ★ CPI SUPER SAVER ★ ★ ★ ★

Select one of the following for only $17.90 (normally $29.95) with each purchase of $75.00 or more and postmarked within 30 days of publication of this issue.

APPLE: Raster Blaster — **TRS-80: Sargon II (c)**
APPLE: Olympic Decathlon — **TRS-80: Olympic Decathlon**

★ ★ ★ TRS-80 ★ ★ ★ ★ ★ ★ ★ ★ TRS-80 ★ ★ ★

How about Tandy dandies?

ADVENTURE INTERNATIONAL

Escape from Traam	d	16.50
Adventure #1, 2, 3	d	32.00
Adventure #7, 8, 9	d	32.00
Adventure #10	d	16.50
Curse of Crowley Manor	d	16.50
Kid Adventure	c	12.00
Mean Checker Mach	c	16.00
Games by Lance (Color)	c	16.00

AUTOMATED SIMULATIONS

Temple of Apshai	d/c	32.00
Crush, Crumble & Chomp	d/c	24.00
Invasion Orion	d/c	20.00

BRODERBUND SOFTWARE

Galactic Empire	d	32.00
Galactic Trilogy	d	32.00
Tawala's Redoubt	d	16.00

EDU-WARE

Prisoner (Mod III)	d	24.00

AVON HILL GAMES

Empire of Overmind	d	28.00
Major League Baseball	d	24.00
Lords of Karma	c	16.00
Tankticks	c	23.50
Conflict 2500	d	12.00

Personal Pastimes

DATASOFT

Arcade - 80	c	16.00
SECS (Screen Editor)	c	24.00
Sigmon (Color)	c	24.00
Iago	d	20.00
Football Classics	d	24.95

MICROSOFT

Olympic Decathlon	d	24.00
FORTRAN 80	d	80.00
A.L.D.S.	d	80.00
BASIC Compiler	d	158.00
muMATH	d	60.00
Typing Tutor	c	16.00
Editor Assm.t	c	24.00
Level III BASIC	c	40.00
Adventure (Orig.)	d	24.00

PERSONAL SOFTWARE

Zork	d	34.00
Checker King	c	17.00
Time Trek	c	17.00
Microchess	c	17.00
Bridge Partner	c	17.00
Arcade Classics	c	21.00
CCA Data Mgt. 4.1	c	85.00
Monty Monopoly	d	29.50

Didn't find it? Send for a Catalog of over 800 items. (Incl. ATARI & PET)

ORDERING INFORMATION

VISA

To insure correct shipment, indicate computer make/model and it you desire disk or cassette. Personal checks accepted, please allow 14 days for processing. For faster service, make payment by: Money Order, Cashier Check, C.O.D., Master Charge or VISA Card. For charge card indicate card type and date, expiration date and phone number. California residents add 6% sales tax. Shipping charge: include $2.50 for domestic or $10.00 for international.

CPI

Computer Products International
Dept. C
P.O. Box 56
Arcadia, Calif. 91006

CIRCLE 222 ON READER SERVICE CARD

An eclectic interview with Art Luehrmann, writer, philosopher, and renaissance man of the computer age.

Pascal, Ada and Computer Literacy

David H. Ahl

In 1969, when I took over the Educational Products Group at Digital Equipment Corp. and first started to give serious thought to instructional uses of computers, Dr. Arthur Luehrmann at Dartmouth was one of the people to whom I turned. Art had developed a series of interactive graphics programs *for student use in physics at a time when most other people were still thinking punched cards and batch processing. Two years later when other people had graduated to Teletypes, Art had developed a graphics football game which depicted the playing field in perspective.*

In 1978, Art left Dartmouth to head up the computer program at Lawrence Hall of Science. In 1980, he and his wife Martha struck out on their own with a new venture, 'Computer Literacy."

Over the years, Art has written many provocative articles. Probably his most quoted piece is, "Should the Computer Teach the Student or Vice Versa?" done for the 1972 Spring Joint Computer Conference. It was reprinted in Creative Computing *and now appears in* The Best of Creative Computing-Volume 2.

I recently had a chance to talk with Art at his home in Berkeley. This is an edited transcript of the conversation which ranges from Pascal to Ada to future computers to artificial intelligence to computer literacy. Want a glimpse of the future? Read on.

D.A.: There is a growing interest in Pascal today. People are buying Pascal language cards, but perhaps some don't really understand the reason of another language. Why Pascal?

A.L.: That's a good question. Your remark about people having bought the language system and not knowing why is probably very accurate. My guess is that 40-50% of the people who bought the language system still don't know how to work Pascal because of the inadequate documentation that came out with the product the first time around.

However, my feeling about languages is not purist. I don't think there are good languages and bad languages; I don't think that's a good way to think about languages.

Computer languages came into being like natural languages. After all, they are human inventions. They have a culture that grows along with them of people who speak that language, do their writing in it and think in it. New languages come along and have a different kind of shape and thrust and there will be groups of people who think in that new language. Deep down, they are not all that different from one another. A linguist wouldn't waste ten minutes on a computer language. They have about 30, 40, 50, or 100 words at the most in their vocabulary and there are probably eight or nine sentences you can say that are legal. They are boring. A person who works around computers probably knows three or four languages. If he wants to learn a new one, it takes about a week. It's not like learning Russian. The differences between computer languages, I feel, are very much overrated.

Pascal and Basic are much more alike than they are different. LISP and Basic are certainly more different than Basic and Pascal. There's a place for all of them. I don't think it is right to say that some languages are good and some are bad; and that as soon as we get the perfect language everything will be wonderful. They each are great at some things and bad at other things.

The differences in computer languages, I feel, are very much overrated.

Basic is good, I think, not because of the language, but because of the way it is implemented. It is accessible. Anyone, within five minutes at most, can do something in Basic. One can write a program that generates output and maybe does some processing along the way. On the other hand, writing a Pascal program in the first five minutes is virtually impossible. It's not because Pascal is hard; the programs are equally easy or hard, but the implementation is such that when you are using Pascal you have to know you are entering the editor; you have to know that you have to leave the editor in a certain way to be sure that what you wrote gets saved;

PRICE BREAKTHROUGH

We've done it again! As a leader in small computer sales we must constantly find new ways to save customers money while offering quality products. Our most popular seller, the Apple II Plus, is now available with 64K of user RAM at the unbeatable price of only $1249. This is possible because we manufacture the 16K RAM Card that expands the factory Apple II 48K to it's maximum capacity of 64K. The Ram Card allows use of Integer and Applesoft Basic and other languages like Pascal. It's a must for large data bases, Visicalc, and the Z-80 cards. The card is made from high quality components and has a full one year warranty.

64K APPLE II PLUS*

*48 K Apple II Plus with 16K Ram Card

ONLY $1249

16K ONLY **$1025** **48K** ONLY **$1089**

DISK II DRIVE WITH CONTROLLER CARD **$499**

DISK II DRIVE ADD ON **$439**

FREE SHIPPING* on all pre-paid cash orders

Apple Cards and Hardware

16K Ram Card by CCI	130
Language System w/Pascal	379
Silentype Printer w/Interface Card	349
Hayes Micromodem II	299
Novation Apple-Cat II	339
Video Videoterm 80 Column w/Graphics	269
Z-80 Softcard by Microsoft	299
16K RamCard by Microsoft	159
ABT Numeric Keypad (sold as new hybrid)	110
ALF 3 Voice Music Card	239
ALF 9 Voice Music Card	169
Lazer Lower Case Plus +	55
Micro Sci Disk Drives (A 40 & A 70)	CALL
SSM AIO Serial, Parallel Card A&T	189
Sup'R Terminal 80 Column Card	329
SVA 2V/X4 Megabyte 8" Disk Controller	589
SVA 2+2 Single Den 8" Disk Controller	345
ThunderClock Plus	119
Syntec Hi-Res Light Pen	210
Integer or Applesoft Firmware Card	145
Graphics Tablet	619
Parallel Printer Interface Card	135
Hi-Speed Serial Interface Card	135
Smartarm 80 Column Card	299
Joystick by Keyboard Co	45
Music System (16 Voices)	679
A/D + D/A Interface	299
Expansion Chassis	599
Intrel X-10 Controller Card	169
Clock Calendar Card	225
CPS Multifunction Card	189
Supertalker SD-200	239
Romplus + Card	135
Romwriter Card	169
Clock/Calendar Module	99
GPIB IEEE-488 Card	269
Asynchronous Serial Interface Card	129
Centronics Parallel Interface Card	99
Arithmetic Processor Card	299

We carry all CCS cards, please call for best prices.

Software for the Apple

Visicalc 3.3	169
CCA Data Management	85
DB Master	169
WordStar (Apple 80 col. version)	299
Applewriter	65
Easywriter	225
Peachtree Business Software	CALL
Visiterm	129
Visitrend/Visiplot	219
Real Estate Analyzer	89
Tax Preparer	99
DOS Toolkit	65
Tax Planner	99
Dow Jones Portfolio Evaluator	45
Dow Jones News & Quotes Reporter	85
Apple Fortran	165
Controller Gen Bus System	499

Printers

Epson MX-80 CALL

Anadex 9500/9501 w/2K Buffer	1299
C Itoh Starwriter 25 CPS	1499
C Itoh Starwriter 45 CPS	1899
Epson MX-70	CALL
Epson MX-80 F/T	CALL
Paper Tiger IDS-445	699
Paper Tiger IDS-460	949
Paper Tiger IDS-560	1249
Silentype w/Apple II interface card	349
Qume Sprint 5/45	2495

TOLL FREE ORDER LINE
800-854-6654
California and outside Continental US
(714) 698-8088
TELEX 695000 BETA CCMO

Video Monitors

Amdek/Leeden Video 100 12" B&W	139
Amdek (Hitachi) 13" Color	359
NEC 12" Green Phosphor Screen	CALL
NEC 12" RGB Hi-Res Color	CALL
Panasonic 13" Color	449
Sanyo 9" B&W	185
Sanyo 9" Green Phosphor Screen	CALL
Sanyo 12" B&W	269
Sanyo 12" Green Phosphor Screen	285
Sanyo 12" Color w/excellent resolution	449

Atari Personal Computer

ATARI 800 16K $749

Atari 400 16K	349
410 Program Recorder	65
810 Disk Drive	449
815 Dual Disk Drive (Dbl Den.)	1295
822 Thermal Printer	349
850 Interface Module	159
16K Ram Memory Module	149
16K Ram Memory Module (by CosComp)	89

NEC Microcomputer



PC-8001A 32K Ram Computer	CALL
PC-8012A 1/O Unit w/32K Ram	CALL
PC-8031A Dual Mini-Disk Drive Unit	CALL

Please write for more information about the NEC computer.

Ordering: Please call or write. Terms: VISA, MASTERCARD, AMERICAN EXPRESS, DINER'S CLUB, CARTE BLANCHE, bank wire transfer (bulk orders only) cash (money order or certified check, normally order or purchase order must be received before product shipped with cash, please call for shipping, handling and insurance commission). Bid/Ask quotations and OEM solicited. We accept CCSL / ABM business and educational purchase orders. Prices, specifications, availability of product are subject to change without notice. All prices are in US dollars. All trademarks and trade names belong to their owners. We decline responsibility for typographical errors.

Send Orders to:

consumer computers Mail Order
8314 Parkway Drive
La Mesa, California 92041

CIRCLE 140 ON READER SERVICE CARD

Adwar APM* polishes up your Apple™ color graphics for video tape.

Adwar APM* polishes up your Apple TM color graphics for video tape

Want to videotape your Apple color graphics?

Just plug your new Adwar Apple Proc Mod* into slot number 7 It's that simple

Now the non-standard output of the Apple computer can be recorded as stable full-color images on video tape

You can show, edit, or duplicate polished, crisp color graphics

The new Apple Proc Mod: another exciting innovation from Adwar Video Corp., 100 Fifth Avenue, New York, NY 10011

Call today for complete details 212-691-0976

ADWAR VIDEO CORP

The Video Buyers Advantage

CIRCLE 103 ON READER SERVICE CARD

you have know to type RUN to run the program and when you get your error messages, you must know to go back to the editor.

In most implementations of Basic you are always in the editor except when you are running. The editor understands words like RUN and LIST and understands the syntax of Basic. It is a kind of peculiar editing. It's not really an editor, but a kind of mixture. In a Basic environment many things go on under the cover of which you are not aware as a beginner programmer. You are able to write a few things, get some answers and write some more and make your changes quickly.

Basic is particularly easy to get into and Pascal is hard. It has nothing to do with the language. The languages are really structurally very similar.

If you can write a program that fits on the screen of your computer, there is absolutely no reason to do it in Pascal.

D.A.: Why would someone want to use Pascal?

A.L.: For a short, quick and dirty program, they shouldn't use Pascal. If they are trying to get an answer and they can do it, my rule of thumb is: if you can write a program that fits on the screen of your computer, there is absolutely no reason to do it in Pascal. It doesn't make any sense. If, on the other hand, your program is going to grow into four or five or ten screen fulls, probably Pascal is a good choice among languages because you can read what you wrote. You can follow the logic more clearly. If you come back a month later and try to make a little change in a Basic program that is 100-200 lines long, you have to read it really carefully, and watch all the GOTOs and all the line number references. You can't just pick out a block of 10 lines and say "Gee, I know how that works. I can make a change because I know with confidence how that section works." In a structured language like Pascal, you can indeed read a block without looking at the context at all. You can say, "I know exactly how these ten lines work, and if I make this change, in high confidence I know that it won't have side effects." That's the big thing. I think that's the bottom line.

D.A.: You've been comparing Pascal with Basic but isn't it more closely related to Algol?

A.L.: It derives from Algol. You can see all kinds of Algol-like ideas in Pascal. That's its closest relative. Basic is derived from Algol too. When Kemeny and Kurtz put Basic together they were very much influenced by Algol 60. More so than Fortran. Fortran had some real problems that Basic was supposed to resolve; the formatting of outputting is the most obvious one. The Basic FOR loop is more like the Algol FOR than it is like the Fortran FOR. In Fortran, the FOR loop gets executed once no matter what. (Or it did until recently.) The Basic FOR loop was devised so that it didn't do that. Unfortunately the people at Microsoft never seemed to get that point. They made their Basic FOR loop into somethng that is like the old buggy Fortran FOR loop, the one that makes you go through it whether or not you are supposed to.

D.A.: What do you think the future of languages is going to be? Will there be many new ones?

A.L.: There probably will. I also think that languages are getting more complex as people realize the variety of different things that computers can do. I think it will probably take a different kind of a language to handle parallel processing. What we are seeing right now is languages that are really designed to do one thing after another. That's been reasonable because the processor has been an expensive part, but today you can buy a 6502 for about $7 or $8. Imagine a computer that has 100 or even 1000 of those. What kind of language does it take to define a task that might be carried out by any of 100 processors at the same time; or at a time you may not even know about or specify. What kind of language does it take to do that? It's very different from languages that are basically sequential.

D.A.: Do you think it will be more like some of the things that Carnegie-Mellon is doing in which, if a processor is unable to do a job, it calls on another and another, etc.? Or more like Smalltalk?

A.L.: I don't know. Smalltalk assumes that there is only one processor, but conceptually there are a bunch of different actors. The language is closer to the kind of computer system that is likely to be around for the next ten years than the computer system that the Smalltalk researchers are designing. There probably will be a more appropriate language development than sequential languages. My own notion is that as multiple processors become possible and feasible economically that one will have to start to think of internal computer management systems similarly to corporate managment

™

Don't make your computer old before its time

Now there's Palantir™ — Word Processing and Accounting Software for Today's Computers

You've just gotten a brand new computer. Don't tie it down with old software. Two-year-old software will make it run like a two-year-old computer.

The microcomputer industry is the fastest growing, most exciting industry in the world. Today's printers, terminals and disk drives can do things no one even dreamed of two years ago.

But a computer is just a dumb piece of metal until software gives it life, and, unfortunately, microcomputer software has not kept up with the hardware.

Until now.

There's a commonly held belief that you should not buy new software because it hasn't been tested. We say, *"Hogwash!"*

At one time those complaints might have been valid, but the software industry has come of age. We do our testing before we release a product, not afterwards.

More importantly, we've learned that quality cannot be *tested* into a product; it must be *built* in from the beginning by people who know what they are doing.

And we do.

We formed Designer Software because we believed that the quality hardware of today demanded software of equal quality. It took a lot of time, sweat, money, care, experience and talent to make that belief a reality.

We set high standards, but our team of CPA's, systems analysts, programmers, writers, artists and marketers that created *Palantir*™ Word Processing and Accounting have exceeded all of our expectations.

Palantir™ is the most professional packaged software ever to be offered to the CP/M® market.

We don't expect to convince you of that with just one ad, and we won't try. But if you're in the market for business software, we hope we've convinced you to find out more about *Palantir*™ — today's software for today's computers.

Designer Software™
HOUSTON

For more information and the name of a dealer near you, please write, call, telex or use The Source. Dealer, distributor and OEM inquiries invited.

3400 Montrose Blvd. • Suite 718 • Houston, Texas 77006
(713) 520-8221 • Telex 790510 • Source TCU671

CP/M is a registered trademark of Digital Research

CIRCLE 150 ON READER SERVICE CARD

Designer Software and Palantir are trademarks of Palantir Inc.

systems. You must allow a certain amount of autonomy and lack of information down below to get the job done. Then you look once in a while to see if the job got done and once in a while you fire a processor, because it's just not doing the job. That's a silly idea, but it's probably not that silly after all. If you tried to analyze what it would take to have truly centralized control of a computer system that had 1000 processors and just start counting the number of wires that would go from each processor to all the rest you realize that you couldn't build a computer like that. You are forced into autonomy, letting processors run by themselves, and checking up on them once in a while. You are also forced into the lack of being absolutely sure that the job ever gets done. What large company really knows if the job they are doing is really getting done? It drives the mathmetician crazy because he can't prove anything except in a statistical sense.

The complexity issue is a major one today. There are scores of problems that you just can't solve in any absolute sense because of the inherent complexity at hand. But on the other hand, you can get by pretty well with solutions about which you can establish proof. I think to make really smart computer systems, we are going to have to tolerate much more uncertainty in terms of proof than we have previously considered. That flies in the face of all tradition in the proof of a algorithm and proof of correctness that has given us such nice structured languages like Pascal.

D.A.: It flies in the face of all the computer scientists too, and the fundamental design of computers which aren't designed for the partial or imprecise solution.

A.L.: On the other hand, without computers we have had to get by with people and their decisions. We can't prove anything about how people arrive at decisions and by and large they have done pretty well. Our model of intelligence is the human being. Artificial intelligence is trying to make computers as good as people. It may be to get there the designs will have to relax a bit and permit error. That may be the only way to get to true intelligence. True intelligence sees things that aren't really there and that creates theories. Theory is always more than the fact. Any scientific theory claims things to be true that are far in excess of the number of experiments that have been carried out. Having that theory is already a leap of the imagination and if computers are going to be truly intelligent, we are going to have to permit them to go beyond that which is provable and let them do the kind of inductive thinking that people do. Seeing a pattern is inductive, the pattern isn't really there, it's an imposition on the data. It organizes it in a certain way.

D.A.: Do you think computers can see such patterns? You're saying, "Okay, we'll design computer programs that come up with unproved and uncertain results and therefore they will have the same inductive reasoning powers that humans do." That's quite a leap.

A.L.: Yes, and it's dangerous. We want to be able to pull the plug if we don't like what the computer comes up with. The inductive leap isn't all that different from seeing things that aren't there. It's true, nevertheless, that the way people make advances is by jumping way ahead of things that they can prove deductively. Suddenly seeing there's another way to organize the known facts. Saying, "Let's make that a law. Let's see how far we can go with this new theory." Then it goes for a while until another theory is proposed. The theory is always bigger than the facts. That is quite the opposite of what we do with computers. We want computers to be rigorous logicians, deductive, deductive, deductive. We want to be able to prove everything from the first principles. Computers do things very differently from the way people do. A truly intelligent, automatic system is going to have to be allowed a lot more freedom.

People should always worry about any systems that pretend to be more important than they are.

D.A.: Do you think people will allow it enough freedom to make a decision that really counts, or will we think of computers as dolphins, something that we try to understand, or more likely, will we think of them as slaves? After all, we've built them and they must do our bidding.

A.L.: It depends on the quality of the theories they – computers – come up with. If they are better than the ones people come up with, we might have a little more respect for the computer. That's still far down the road, and I can't imagine that actually coming into being for a long time. People should always worry about any systems (machine systems, government systems, etc.) that pretend to be more important than they are. You have to be ready to pull the plug on all of these and not trust them all the time because they may be wrong. When we permit computers to be wrong, we have to also be prepared to be very critical and pull the plug.

D.A.: Earlier today we were talking about the Ada language. I believe that this is a case where it may not be good to let the computer be wrong by choice; where being wrong because the program wasn't debugged or because the language itself wasn't totally correct is not at all desirable. Furthermore, DoD plans to use Ada to control all of our weapons systems, a herculean task. But no matter how huge the programming job, I also would rather not see a computer leaping to intuitive case of launching a missile, I would side with that point of view.

theories of how best to deploy these weapons.

A.L.: That's a very good example. If you launch a missile you want it to go and explode where it was programmed to go and not some other place. That's a supreme case that cries out for provability. In a case of launching a missle, I would side with that point of view.

On the other hand, much of what happens in life is not subject to those same laws of provability. We, in fact, live with systems that are not subject to that same criteria and we suffer for it. We have major wars every few decades and lots of people die because we don't have that same confidence and provability in the social systems we live with. On the other hand there are productive systems that plant food and harvest crops, etc.

D.A.: I would hardly say that those systems, mechanical or whatever, are responsible for wars.

A.L.: I agree. However, I maintain that the non-computer systems that we live with such as government, law, education and those many other complex systems work for the most part. With the number of people in the universe, it's hard to imagine how any centralized control system would work any better than these decentralized systems. Nevertheless, every so often they go crazy and awful things happen like war. It's that kind of tension that I see between systems that are semi-autonomous and once in a while go crazy and about which it is hard to establish

JUST LAUNCHED!
VOYAGE OF THE VALKYRIE
BY LEO CHRISTOPHERSON

ADVANCED OPERATING SYSTEMS

450 St. John Road
Michigan City,
Indiana 46360

The ancient Norse lords bravely sailed their ships across new waters in search of adventure. No obstacle was too great to overcome nor any force powerful enough to prevent their mighty advance. ■ Now you're in command. You are the pilot of the attack ship Valkyrie. Your mission: to wrestle the island Fugloy from the grasp of an army of laser-wielding war birds and secure the golden treasures hidden within the walls of the island castles. Success of the mission depends solely upon you. The castle Drage appears on the horizon when suddenly the air is alive with the flutter of giant wings. Your prize is in sight . . . do you dare accept the challenge and go on? ■ You can put yourself at the controls of the Valkyrie thanks to the genius of Leo Christopherson and the versatility of the *TRS-80 microcomputer. As absolutely flickerless birds sail smoothly across the screen, strains of Wagner's "Ride of the Valkyries" are heard. The game offers 10 levels of difficulty which provide a challenge for players of all ages and skills. The game also provides one of the finest examples of computer cartoon-graphics presently available. Accept the challenge of the Voyage of the Valkyrie . . available now at leading software retailers.

*Trademark of Tandy Corp.

CIRCLE 114 ON READER SERVICE CARD

proof versus systems that are top-down, totally logical, and terribly complex. The more tight the organization is the more complex the system is. It may just grind to a halt because we can never get all the information around all the actors in a coordinated way. I think complexity forces autonomy. The more complex things are the more it is necessary to divide the system up into autonomous units just to be able to cut the wires and let them run independently (sometimes in conflict). There has to be a way to resolve conflict as soon as you have autonomy.

D.A.: This sort of brings you full circle back to Pascal.

A.L.: Yes. Pascal is a kind of exercise in a purist notion of top-down—logical and with tremendous clarity. Yet you must wonder whether it can handle truly complex problems.

D.A.: Thinking of Ada again, I find it amazing that the Department of Defense would switch their gargantuan computer effort into an entirely new language.

Kids should have a good command of their native language and a command of one or more computer languages.

A.L.: Yes, but they did the same with Cobol. They defined it from the ground up. Classified it and suddenly it came into being. The thing is that people have very little experience with real-time programming environments. I think that is probably what worried Hoare.* People were attempting to specify a language without having had prior experience with it. To nail things down in a standards document that are not related to everyone's common experience is risky. The standards should come after you know what you are doing. You discover your errors and find standards are needed. But to use a standards document to invent a new thing is a chancey proposition.

D.A.: With your new venture in Computer Literacy, do you have some thoughts on what children should learn first? I don't necessarily mean a language. In the future, kids will be growing up and dealing with machines, computers, and technology in general. What should they do to learn to use it efficiently as well as to just cope?

A.L.: First of all, they should learn how to write and express their ideas in a form that a computer can carry out. That is the essential thing. Kids should have a good command of their native language, English or whatever, and a command of one or more computer languages. Which one or ones is not terribly important. To be able to express an idea in the form of an algorithm is the main ideal. It's a new idea and didn't really exist in the practical sense before the computer. To me the notion of computer literacy is a fairly simple one; it is modelled after literacy in your own language. It's the ability to be



able to express an idea and not just know some trivial words about computers. Computer literacy is the ability to read and write. Write for the computer and read what other people have written for the computer and criticize those ideas and prove them. In other words, to express a thought in the form of a computer program.

D.A.: When should kids start to get into this?

A.L.: As soon as they are ready. I think kids are clearly developmentally ready by the time they get into seventh or eighth grade. Some kids are ready before that. But surely by seventh or eighth grade kids can handle the levels of abstraction necessary to deal with a computer. To put that in perspective, the levels of abstraction are, when dealing with a computer, lower than the levels of abstraction needed to do algebra. If anything, computing ought to be a prerequisite to algebra. However, in many schools, algebra is a prerequisite to computing. I feel a kid develops the primitive ideas of algebra much better after working with a computer than the other way around.

D.A.: Do you think our *Computers for Kids* books (1st to 4th grade) are starting too early?

A.L.: No. I think it is a good idea for kids to know as much as possible as soon as possible. They're going to ask questions and want to know what computers are. They will see them everywhere. But I think that mastering a vocabulary about computers isn't terribly important. It's hearsay knowledge; it's not knowledge of the thing itself. Whenever I think about computers I think about learning how to ride a bicycle. It's different but there are some deep similarities in that a kid who is in the first grade can't ride a bicycle but he has bicycle knowledge because he sees other kids riding bicycles and he needs a vocabulary to describe that. "That is a

I think that English teachers would be much better teachers of computers than math teachers.

bicycle. See Johnny ride the bicycle. See Johnny fall off the bicycle." They know those words; that's important. But they can't ride the bicycle yet. They're not bicycle-literate. They have hearsay knowledge about bicycles. They become bicycle literate when they can get on the bicycle and ride around. That's what we want kids to do with computers. Get on the thing and ride it around. Make it do things for them.

D.A.: How do you see computers versus calculators?

A.L.: Totally different. Calculators are a math instrument for arithmetic. Computers do billions of other things. We make a big mistake if we use computers to teach math. Computers are really ways to express ideas. Computing is more like English or like a natural language than it is like math. I think English teachers would be much better teachers of computers than math teachers. They would ask the kids to rewrite; they'd say "Gee, Johnny that stinks. That computer may understand what you wrote, but I don't understand it. Rewrite it, make it clear." It's really not math. Math almost could be left out of computing. A good introduction course in computing probably wouldn't even

*Turing Award winner Prof. C.A.R. Hoare says, "For none of the evidence we have so far can inspire confidence that this language — Ada — has avoided any of the problems that have afflicted other complex language projects of the past."

deal with math problems until very late in the sequence.

D.A.: Should there be computers in the ideal classroom? Should kids have them available in their study periods or homes? When should kids use computers?

A.L.: I think there should be a computer course that should be part of schooling. At a certain time in a kids life, he would take computing. The same way he takes math, English, science, social studies, etc. He should certainly have an intensive exposure in a computing course. I see that as a preliminary experience to computer uses in a lot of other courses. Once the kids have that knowledge and once they know how to use the computer to solve problems, then the other courses in the curriculum should take advantage of this. Much as a history course takes advantage of a kid's ability to write. For the same reason a science teacher ought to give a programming problem to a kid to teach him to express an idea in science as another way to get that idea across. I see a structured use of computers in a computer course and a less formal use in other courses. The kids are going to have computers at home because they are cheap. The kids may be doing their homework at home on the computer for their classes at school.

D.A.: About school computers, some people have said, "Everybody should have their own." Other people have come out very strongly in favor of teams of two or three kids on a computer where they get problems to solve and can help each other solve them. What do you think?

A.L.: I've seen it work well both ways. The number sharing one machine can be limiting. You can get about three people at a machine; one at the keyboard, one on the left, one on the right. If there's a fourth, forget it. That person is out. Even with three, socially, there is usually an odd man out. Two seems to work reasonably well. I think that is an effective way of dealing with a limited amount of equipment. But when you get down to it, the kid who is moving ahead pretty well, moves ahead even faster, if it's one-on-one. But the kid who is not quite with it may drift behind. I think we need more experience in this area to be sure. Somewhere between one and two seems to be the right number, three is tolerable, and four is impossible.

D.A.: What are you going to do with *Computer Literacy* as a company or an organization?

A.L.: Specifically, we want to produce curriculum materials to teach computing as a regular school subject. That is our problem right now. The top item on our agenda is to create a course which introduces computing as a regular subject in the school—probably around the high-school or junior high-school level. The thing is that computers have come on the scene faster than the generations go and there are many older folks who are discovering they can do their jobs better if they know more about computers and their applications. We are also working with adults in their professional activities to teach them about computers and their aplications.

D.A.: Everyone at *Creative Computing* and I personally wish you the best! □

Renewing your subscription is the sincerest form of flattery!

WE'VE BEEN USING COMPUTERS IN BRITAIN FOR A LONG TIME . . .

. . . So you know you're getting a wealth of experience from the new range of software from LITTLE GENIUS. Programmed by some of Britain's brightest experts, there are teach-yourself BASIC programming packages for the Apple, ITT 2020, and Pet and packages for learning PASCAL, too. Each package has three modules: elementary, advanced, and disk operation to help you get the best from your micro. So don't go round in circles - you'll find a dealer stocking them not a stone's throw away!

Separate disk modules available for $69.95 or all three modules in a special '3-in-1' package for $179.95. Ask your dealer or write to:
LITTLE GENIUS, SUITE 504, ALBANY HOUSE,
324 REGENT STREET, LONDON W1R 5AA. ENGLAND.

Little Genius

CIRCLE 184 ON READER SERVICE CARD

Three Roads to Pascal

David Lubar

Like cleaning the leaves from the gutters, learning Pascal was something I kept planning to do and kept putting off. When the boss put three Pascal books on my desk, along with a request for a review, I knew the time had come. Two of the books were specifically for Apple Pascal while the third took a more general approach but leaned toward the Apple. The problem with covering three books is that while I could read the first as a rank beginner, there would be no way short of self-induced amnesia to view the next two in the same light. With this Heisenbergian dilemma in mind, I randomly selected *Apple Pascal—A Hands-On Approach* (Arthur Luehrmann and Herbert Packham, McGraw-Hill Book Company, New York, 430pp., $14.95) and began a journey through what some claim is the language of the future.

Getting Started

After a brief introduction, the authors guide the reader through the process of booting the language from disk. The book is aimed at users with a single drive, but contains an appendix covering any differences encountered in a dual-drive system. It soon became obvious that the authors are doing more than teaching a language; they are patiently showing the novice how to use the Apple Pascal *system*. It definitely is a hands-on approach. The reader is shown not only the correct procedures, but also various ways to crash the system. The authors suggest various steps to try, allowing the user to lose a file or hang the system. Once all is lost, they explain what happened and what steps are required to get back into the system. This better-now-than-later approach is good. Rather than just cautioning against something, they let you make the mistake. Pavlov would approve.

Within the first few chapters, the reader is entering programs into the system and learning to use the powerful editing features of Apple Pascal. The early programs are simple examples of how to put text on the screen. While later examples grow in complexity, none is so long as to discourage the slow typist. In many cases, the authors first present a short program and then give several modifications or additions that can be entered through the Pascal Editor. Each chapter ends with a summary of what was covered, followed by a short quiz, giving the reader a chance to make sure he hasn't been lost along the way.

Throughout the book, the authors make almost no mention of Basic, working on the assumption that Pascal is the reader's first language. This approach seems to work.

After introducing a few elementary Pascal commands, there is a chapter on generating music using routines from the Applestuff library. Applestuff contains procedures dealing with sound, paddles, and other Apple-specific features. More commands are introduced, appearing in logical order as they are needed to expand or improve the sample programs. Another highlight of the book is the illustrations, which show exactly what appears on the screen. In this way, the reader knows whether he has followed the example correctly.

After the music section, the book moves into one of the major features of Pascal—defining procedures. A procedure is a set of commands that can be called from other parts of the program (or even referenced recursively). While the concept is similar to Basic subroutines, there are differences. The next chapter introduces functions, which are the other main building blocks of Pascal programs. After that, the book goes strictly Apple again with a section on graphics.

At no time do the authors throw too much at the reader. Everything appears when it is needed, and everything is clearly explained. The above covers the first seven chapters. There are seven more, covering branching, string variables, while loops, data types and sets, arrays, records and files, and many other features of Pascal. The final chapter tackles the tough topic of recursion.

By choice, the authors did not cover the GOTO statement. In some circles, this statement is frowned upon. A few other portions of the language aren't touched, but nothing crucial is missing. I am impressed with the book, and feel it gives an excellent introduction to the Apple Pascal System. While it does not encompass every single aspect of the language, it contains eveything the beginner needs.

Next up was *Pascal Primer* (David Fox and Mitchell Waite, Howard W. Sams & Co., Inc., Indianapolis, IN, 206pp., $16.95). The book has much to offer in the way of eye appeal. It is sprinkled liberally with cartoons and all listings are highlighted in orange. The topic is mostly standard UCSD Pascal, with a few mentions of specific Apple features. Since standardization was the goal, nothing is said about the Apple Editor or Filer. Thus the book shouldn't be used as an Apple user's sole source of information. On the other hand, those who use this book will be able to write code that will run on any Pascal system. The authors mention that the book should be used in conjunction with the manuals accompanying any specific system. Throughout, they point out any non-standard features, warning the reader about commands that might defeat transportability.

The approach here is somewhat concentrated. In one chapter, for example, six variable types are covered. Each is explained, though some are not used until later chapters. This concentrated approach is good for reference or for a second source of learning, but a bit tough on the novice. It's a bit easier to learn one or two variable types at a time than to see them all at once. The book is rich in sample programs. Unfortunately, the sample program often appears on the page after the explanation, necessitating a lot of page turning during the learning process.

COBOL the language of business.
The language of Micro Focus

CIS COBOL

WITH FORMS-2

Our CIS COBOL product family brings you the most successful business programming tool ever devised, COBOL, in a form optimized for today's most cost effective hardware, the microcomputer. Standard COBOL as defined by ANSI X3.23-1974.

The reliability and performance of CIS COBOL are strongly emphasized by its continued qualification for U.S. government contracts. In January 1981 CIS COBOL entered its 2nd year of G.S.A. certification.

CIS COBOL is powerful but simple to use. Its screenhandling, dynamic module loading and fast ISAM let you take full benefit from micro computer facilities.

Our FORMS-2 utility is a COBOL source code generator to help you build interactive applications with ease. Using our unique demonstration "How to create a COBOL program in 20 minutes", you can quickly try out new application ideas.

And if you are developing software for resale, the variety of systems running CIS COBOL offers you a very large available market.

CIS COBOL and FORMS-2 are available through our dealers and distributors for many 8080, Z80 and LSI-11 systems including Apple II with Softcard and CP/M.

For OEM purchase on 8086, PDP-11, TI990 and other order codes approach us direct. Our system transfer technology has made CIS COBOL first on a number of processors and enabled us to interface to 30 different operating systems.

For more information about CIS COBOL write or call us at our USA or European sales offices.

Micro Focus, Inc.
1601 Civic Center Drive
Santa Clara, CA 95050
Telex: 278-704 MFCIS UR
Phone: (408) 496-0176

Micro Focus Ltd.
58 Acacia Road
London N.W.8.
England
Telex: 28536 MICROF G
Phone: (01) 722 8843/4/5/6/7

MICRO FOCUS

CIS COBOL and FORMS-2 are trademarks of Micro Focus. 8080 is a trademark of Intel Corp, Z80 of Zilog, LSI-11 and PDP-11 of Digital Equipment Corp, Apple II of Apple Computer, Softcard of Microsoft Consumer Products, CP/M of Digital Research and TI 990 of Texas Instruments

CIRCLE 209 ON READER SERVICE CARD

Three Roads, continued...

Though the book begins with short programs, some of the later examples are rather long. The long programs, however, do present useful examples. One is a loan-payment program that, in its final version, takes up seven pages. Another, for tic-tac-toe, is twelve pages long. The merit to these programs is that they are developed step by step, giving the reader an insight into not just the langauge, but also the logic behind the language.

Several useful appendices are included. One explains techniques for interfacing assembly language to Pascal. Sample programs show how to simulate the PEEK and POKE functions available in Basic.

In general *Pascal Primer* contains a lot of information and an admirable aim toward transportable code. While it might not be the ideal book for those who own the Apple Pascal System, it is good for those who are interested in an overall view of the language.

Third in the line came *Pascal Programming for the Apple* (T.G. Lewis, Reston Publishing Co., Inc., Reston VA, 234pp., $12.95 in paperback). Here the feeling was overenthusiasm. The author seemed so excited about Pascal that he threw everything at the reader at once. He always seemed three steps ahead of the reader, making it easy to become lost. Even with the advantage of having just read two other Pascal books, I had a hard time keeping up with this one. The book also lost touch with the user at times. When statements requiring the left bracket were first mentioned, for example, no explanation of how to get the symbol from the Apple keyboard was included.

This is not to say that the book is without merit. It contains a great deal of information, including handy summaries of intrinsic functions, compact examples of the results of various Boolean expressions, and good reference information on the graphics commands. Those who are familiar with Pascal will find much of value here. But the beginner should not make this book his first stop on the road.

Of the three, *Apple Pascal—A Hands-On Approach* is the best buy for the Apple owner. It could even be used by someone without a Pascal system at hand. The only problem is that there are times when the authors suggest things for the reader to try without explaining what the result will be. This works well when the reader has a system available, but might be a bit frustrating for those who don't. Still, this is a minor disadvantage when compared with the high quality of the book, and the book shouldn't be faulted for this since it is designed for hands-on learning.

The real test was whether I had learned enough to do a program on my own. For a test, I tried that old classic, the bouncing ball. Keeping in mind the procedure-oriented nature of Pascal, I wrote routines to draw a box, to determine new coordinates, and to change delta-x and delta-y whenever the user pressed a paddle button. A small driver at the bottom did the work of calling the procedures, and a While loop kept the whole thing running until a key was pressed. The program was short and didn't take long to enter. My initial pleasure with the ease of the editor faded slightly as I had to recompile the program for every syntax error. I had been spoiled by Basic and assembly language. In Basic, you can just fix a syntax error and get on with things. With machine language, the assembler catches syntax problems. Here, I was jumping from editor to compiler, running through the whole thing again for every forgotten semicolon. Luckily, besides the syntax errors, the program worked well enough for me to feel I had at least a grasp of what Pascal was all about. The books, especially *Apple Pascal—A Hands-On Approach*, had gotten me on the road. □

COLOR COMPUTER OWNERS!
CLOAD INC. ANNOUNCES

CHROMASETTE MAGAZINE!

A monthly magazine-on-cassette for your Extended BASIC Color TRS-80!

Goleta California — With **CHROMASSETTE Magazine,** Color Computer owners can now enjoy the variety, economy, and easy entry of programs that CLOAD subscribers have enjoyed for 3 years.

CHROMASETTE Magazine gets rid of the type-in-and-edit blues by putting a rainbow of ready-to-load programs on cassette, and sending them to you by First Class Mail each month. Educational, practical, utility, and game programs are delivered right to your mailbox.

CHROMASETTE Magazine in its Prime State

Put a rosy color in you and your computer's cheeks, stop reading these old cliches, and get a subscription to **CHROMASETTE Magazine.**

Please Write for Foreign Rates and other info.

$45.00 year, $25.00 6 months, $5.00 single issue, or Send a Blank Check and your account balance. Visa and MasterCard also accepted.

Chromasette Magazine
P.O. Box 1087, Santa Barbara, CA 93102
805 962-6271

CIRCLE 111 ON READER SERVICE CARD

- **Text-to-speech algorithm vocally reproduces any typed entry**
- **Unlimited vocabulary**
- **Standard RS-232C interface**

VOTRAX® brings your computer to life with Type-'N-Talk™. Now you can hear your computer tell you where you are in a program; taunt you during computer games; praise you; remind you; warn you. Thanks to the unique VOTRAX® text-to-speech algorithm, your typewritten words are automatically translated into electronic speech—all for just $375.00.

You type—your computer talks. It's that easy because Type-'N-Talk™ uses ASCII code from your computer. *You just send English text to hear synthesized speech through your audio loudspeaker*

The smallest personal computer can talk and execute programs simultaneously. Type-'N-Talk™ has a built-in microprocessor and a 750 character buffer so your host computer and memory isn't tied up with text translation.

If you can print it, you can hear it by placing Type-'N-Talk™ between your computer or modem and a terminal. All the data you're sent while online can be seen and heard. You can even "de-select" Type-'N-Talk™ with its data switching options. Data switching allows you to send speech and visual data independently on one data channel.

Look what you get for $375.00:

- RS-232C interface is compatible with most computers
- Text-to-speech algorithm
- Complete installation and programming instructions
- Baud (75-9600)
- One watt audio amplifier
- 750 character buffer
- SC-01 speech synthesizer chip (data rate: 70-100 bits per second)
- Data switching capability
- Selectable data modes for versatile interfacing
- Data echo of ASCII characters
- Phoneme access modes

The Type-'N-Talk™ unit's simplicity enables the beginning hobbyist to use and enjoy it immediately, yet its total capability can challenge even the most sophisticated user. VOTRAX® developed Type-'N-Talk™ to function with operator designed programs or with the new VOTRAX® talking software currently under development. Type-'N-Talk™ is so easy to use, it can also be used without software.

Order now. Toll-free.
1-800-521-1350
Dealer inquiries invited.

Call the toll-free number to order or request additional information. MasterCard or Visa accepted. Charge to your credit card or send a check for $375.00 plus $4.00 delivery. Add 4% sales tax in Michigan. California residents add appropriate sales tax.

Send check to:
Votrax® -Consumer Products Group
500 Stephenson Hwy., Troy, MI 48084

TYPE-'N-TALK™

SAYS IT ALL.

VOTRAX
NOW YOU'RE TALKING

Mail Chauvinism:

The Magicians, the Snark and the Camel

Ted Nelson

It may not look it, but much of the action in computers has already ended. In the next decade they'll simply stamp out machines like those we know already though with new interconnections, at lower and lower prices and with, we hope, better and better software.

But the real action now is in Networks, Protocols, Standards, Encryption and Databases; and at least one war of shadows in Washington may determine our freedoms as users and citizens. And you may already have won! But eternal vigilance is the price of freedom, so read carefully.

I. The Snark

In Lewis Carroll's epic poem, "The Hunting of the Snark," a party of very dissimilar Victorian gentlemen all go off to catch something called a Snark. The *real* catch, however, is that though all think they are after the same thing, each has an utterly different preconception of what a "Snark" must be, an image conjured up from each man's background and preconceptions.

This allegory will be found suggestive in many branches of the computer field. At the Electronic Mail and Message Conference, its relevance was particularly striking.

The Electronic Mail and Message (hereafter M&M) Conference was held in Washington on December 11 and 12, 1980—the waning days of the Carter administration. Sponsored by numerous federal agencies and committees of Congress, and by AFIPS, the computer society of all computer societies, it took place in a huge oak-panelled room in the Sam Rayburn Office Building. The room was called, by a sign on the door, "Committee on Interstate and Foreign Commerce."

TAKE A HARD LOOK AT OUR SOFTWARE.

Introducing CYBERSOFT™ custom ATARI® programs. The Grand Masters of programming at a mail order price.

Now that you own ATARI®, the finest, most versatile, most powerful home computer on the market, you should have the software to make your ATARI sit up and really function.

We have the "best of the best" programs from the Grand Masters of micro-computer software: Automated Simulations, Crystal, Swifty Software, Adventure International, Datasoft, Personal Software, and Dynacomp. All sold by mail. And, with the CYBERSOFT Ironclad guarantee*.

Space Chase *(Swifty Software) 16K* Nifty eye-hand coordination tests... If you clear one galaxy of "planets" and avoid destruction at the hands of an alien ship you are rewarded by an attack by two aliens and then three. Game keeps score and displays high score. Colorful graphics and good playing. Cassette $14.95

Fastgammon™ *(Quality Software) 8K* The best of the computer backgammon games. You can repeat games with the same dice rolls to try different strategies. You roll dice or let computer roll for you. This machine language program challenges experienced and beginners alike. Underutilizes ATARI® graphics but playing quality more than makes up. Cassette $19.95

Invasion Orion™ *(Automated Simulations) 32K* You are the fleet commander pitted against the Klaatu somewhere in space. You play the leading role in a number of carefully crafted scenarios. This game takes more skill than luck in order to be successful. The documentation is superb. Create your own senarios. Excellent graphics, good sound. Cassette $24.95

Rescue at Rigel *(Automated Simulations) 32K* Ten people from the Orion colony at Ultima Thule (including your favorite female) have been captured. Your mother ship must leave in 60 minutes. As "Sudden" Smith, you must find and release them, but it won't be easy in the maze of corridors, rooms and levels. Oh, by the way, the place is crawling with bad guys. Cassette $29.95

Sands of Mars *(Crystal) 40K* This is the one gamesters are all talking about. A two diskette game, with diskette one putting you in command of the "Starship Herman". You must stock her, select her crew, command the launch and negotiate your way through the hazards of the Universe. Diskette two holds your adventures on the Sands of Mars. The game is saveable. Two Diskettes $39.95

Star Trek 3.5 *(Adventure International) 24K* Lots of color, lots of action as you hyperwarp through the quadrants in your search for Klingons. This program will satisfy the "trekkie" in us all. Cassette $14.95

Text Wizard™ *(Datasoft) 32K* ATARI owners have waited a long time for a high quality, full blown word processor. Text Wizard was well worth the wait. This easy-to-use and comparatively inexpensive program has received raves from user groups across the country. This program fully utilizes the unique ATARI keyboard and ease of cursor movement. Justifies right, left and center. Pagination. Word search and substitute. Diskette and ATARI 825, Centronics 737 or Epson MX-80 printer. $99.95

Adventureland *(Adventure International) 24K* Designed for the novice at adventuring and a great way to get hooked on the world of adventure. As you make your way through an enchanted world you will encounter wild animals, spell-ridden critters and more. Your task is to avoid the perils as you try to collect the 13 lost treasures. Cassette $14.95

Mission Impossible *(Adventure International) 24K* Another adventure from the great Scott Adams. Beginning "Good morning, your mission is..., your task is to save a nuclear reactor from destruction. No magic help in this one. Addiction is possible. Cassette $14.95

Bridge 2.0 *(Dynacomp) 24K* Now you can practice your bridge at home before you have to embarrass yourself at the neighbors. Bridge 2.0 bids (Goren) and plays both contract and duplicate bridge. It even doubles if you get carried away with your bidding. No graphics, but clearly arranged format makes playing easy. Cassette $17.95

Visicalc™ *(Personal Software) 32K* If you use your ATARI for any business purpose or for your personal finances, you will want Visicalc. It probably sold more computers than any program other than Star Raiders. Visicalc creates a very large accountants ledger pad upon which you write with your ATARI. The fundamental difference is, if you change any figure(s) the balance of the figures are automatically adjusted. Extensive documentatigh outlices the full features of this fantastic business tool. Diskette $199.95

Nomlnoes Jigsaw *(Dynacomp) 24K* A 60 piece jigsaw puzzle you complete on your screen. Three levels of difficulty to confound you. Scoring is a function of how many tries and how difficult the puzzle. Cassette $17.95

***CYBERSOFT Ironclad Guarantee.**
We fully guarantee the software we sell. If for any reason, you are not satisfied with your purchase, return the program within 30 days in its original packaging. We'll refund your money, no questions asked.

Our order system is as accurate and fast as our software. Just dial

1-800-247-2000 EXT. 505

(In Iowa 1-800-362-2133, extension 505).
Or, you can write to CYBERSOFT at P.O. Box 505 Bellevue, Washington 98009. VISA and MasterCard gladly accepted.

Included $2.00 handling charge per order. Washington residents add 5.4% sales tax.

2803 102 N.E. Bellevue, WA 98005
© Copyright 1981 Cybersoft Inc.
*Atari is a registered trademark of ATARI Inc.

cybersoft

CIRCLE 135 ON READER SERVICE CARD

The conference began in an atmosphere of excitement and wound down from there. When it began, at 8:00 a.m. Thursday, the room was tense and crowded, packed with hundreds of people, and the rows of officials' chairs that stared down at us were mostly full. But the next morning only half as many came, and only a few were left at the close.

But the beginning started in a crackling atmosphere. Middle-aged executives looked quizzical, elegantly-dressed young lawyers grinned smugly, nervous reporters looked cowed. ("What do Electronic Mail and Message Systems have to do with *news*?" pleaded their eyes.) Almost everybody was well-dressed and had short hair. Many or most of the technical speakers were bearded, but few of the audience.

There were some exhibits downstairs of on-line systems (unfortunately not including Arpanent, which was often mentioned). Tasteless lunches were served by listless waiters, though a marvelous open-bar buffet miraculously appeared after the first day.

Mainly the conference was a rapid-fire succession of speakers, tightly paced from 8:00 a.m. to 5:00 p.m. for two days—a note-taker's nightmare. In the ensuing months I believe I have been able to figure out the major themes and issues, even though the speakers were randomly sequenced and spoke in different tongues.

Rather than tell about the speakers in the order they spoke, requiring you to untangle many separate threads, I will describe as coherent sequences various stories that actually came through to us piecemeal and in random order. In this article I will try to present the new things I learned and the principal issues, as expressed by some of the strong personalities present.

Several different schools of "electronic mail" were present at the M&M Conference, though not all were spoken for from the platform.

Two main views were heard, though there are several more. One was the idea that electronic mail is in some sense a simple replacement of paper mail, which the Post Office speakers seemed to think. The other view sees "electronic mail" as just one facet of the coming new world of transmissive computing in which a lucky few already live.

The speakers can be divided into several groups. Outstanding were the three I call "the magicians," whose presentations of a computer tomorrow went far beyond electronic messages, though electronic messages formed an integral part of their presentations. Another group, the "packeters," explained the various conceptual levels of packet communications and packet networks—the highways, and rules of the road, for this tomorrow. Another group spoke of dividing the electronic spectrum and when you should buy satellites; regretfully I must omit discussing them.

Then came representatives and spokesmen for the U.S. Postal Service, essentially explaining why they felt a need and a right to control electronic mail as they saw it.

And, finally, numerous "regulators"—government lawyers and administrators—told us about regulating the spectrum (which I must skip) and regulating private services and the post office (which must be covered).

Almost everybody was well-dressed and had short hair.

A surprising political issue surfaced at the conference: the role demanded by the U.S. Postal Service in a new world they claim to understand but may not. What the Postal Service wants to do might narrow and restrict what you can do in the future with your computer. At present there is a compromise, but these political issues may resurface at any time.

The lines appear to be tightly drawn. On the second afternoon a lady in the audience told me she was the only remaining attendee from the Postal Service—the other three had left.

Representative Rose

In a way the first luncheon speaker and his enthusiasms perfectly embodied the ideas and controversy of the conference. This was Representative Charles Rose (D., N.C.), who wore a striking plaid jacket. He heads the Policy Group on Information and Computers of the Committee on House Administration of the House of Representatives, and is chairman of the House Agriculture Subcommittee on Dairy and Poultry.

A computer enthusiast, Rep. Rose was introduced as having a "split screen bulletin board." Congress, he told us, has budgeted an "informational terminal" for every member of Congress. The two approved brands are Hazeltine and TI. A portable is given out only if the member signs a paper "agreeing to be trained in its use." Freshmen congresspersons have found this very appealing. Rep. Rose told us that at the next Congressional seating, the House would get a full view of electronic mail—now that "Old Stonehead," whose name I did not catch, was retiring from some post or other.

Many letters pass between congressmen, he told us, particularly "Dear Colleague" letters about their individual concerns, that go out to all fellow members. A representative reads the ones from certain people but not from others, he explained, and he would like to be able to automate this—including the screening out of the unwanted material. He is also interested in forms of teleconferencing for members: he would like to "create an electronic place where we can meet as friends in private."

But he was concerned for the use of these new media back in the districts. "I want Granny, at home, with her video text to be able to use this too...." And he would like to see public-access write-your-congressman terminals.

Unexpectedly, Rep. Rose spoke on what would be the political issue of the conference. "The U.S. Congressman has many friends," he intoned, "and one of these in the U.S. Postal Service." And so, he explained simply, he wants Electronic Mail to be beneficial to the Post Office. We will return to this point later.

The Wizards

During the opening remarks, Bob Taylor sat and listened like a college president: his gaze one of Olympian calm and warmth; musing, sympathetic but impassive. He looks still in his thirties, but can't be, since he was head of Arpa/Ipt over a decade ago.

Taylor is manager of the Computer Science Laboratory at Xerox PARC. The people there do the most powerful and exciting things in the whole computer

CONTINUED ON PG. 134

THEY SAY THE JAPANESE ARE COMING AND WILL DOMINATE MICROCOMPUTING. THE INNOVATORS SAY WELCOME!

In 1978 Exidy introduced the Sorcerer® Microcomputer to the personal computer marketplace.

It was clearly ahead of its time and the competition in price and performance. The graphics were superior, upper/lower case characters were standard and numeric keyboard was included. Printer, communication and dual cassette electronics were built-in, not options. Twice as much information was displayed on the screen. **The competition created their next generation to catch up.**

In 1980 Exidy introduced their integrated desktop Computer System 80 for the very small business. It was an extension of the Sorcerer® computer . . . not obsoleting it but expanding its capacity from the home to the office. Its price/performance outstripped the competition in desktop computers. Dual disk drives with 1.2 million words of information, letter quality printer and office automation software . . . **a complete business computer breaking a new price barrier.**

In 1981 Exidy Systems introduced Multi-Net 80, the first

multi-processor, multi-user, multi-tasking computer system with MP/M™, CP/NET™ and CP/NOS™ for the serious small business. Once again the Multi-Net is an extension of the same Sorcerer® Computer purchased in 1978 or 1980. Your 'getting started' computer becomes your 'getting serious' computer in a multi-user, multi-task environment. **Networking becomes a reality with Exidy Systems, with our competition it's a twinkle in their eye.**

By adding Multi-Net 80 capacity to your stand alone computer system you add a minimum of 35 megabytes of Winchester storage and true 16 user capability because each user has their very own CP/M compatible Z80 microcomputer. That's true upward compatibility in both hardware and software from the company that delivers Innovation in Microcomputing™

EXIDY SYSTEMS

MP/M, CP/NET, Multi-User DOS are trademarks of Digital Research, Inc.

1234 Elko Drive
Sunnyvale, California 94086
(408) 734-9831

What do we say about competition? We welcome it!!!

INNOVATION IN MICROCOMPUTING™

CIRCLE 177 ON READER SERVICE CARD

Regulation: Not What You'd Expect

The Regulators

The Postal Service representatives showed us, in the flesh, a government bureaucracy in its struggle for power. You don't often meet bureaucracy as *them*, in person. But surprises also came from other government bureaucrats at the M&M Conference.

You've heard about too much regulation out of Washington? Well, so have they, these bureaucrats who spoke at the M&M Conference, and it is astonishing to see and hear half-a-dozen administrators and regulators presenting different aspects of how they hope to *avoid* regulating private industry, in the electronic network business, but how they *hope* to regulate the Post Office, to keep it from getting out of hand.

The Post Office wants to take over point-to-point electronic mail, or at the very least compete with private enterprise message services, which are already offering total point-to-point packet services and more. And new "value-added" services, such as data banks, storage and retrieval services, are competing with the very packet networks that carry their services.

So we have a complex picture, one obviously ripe for government regulation. But who will be regulated, why, and in what way?

While the impact of the new Reagan administration may be hard to assess, it would seem to favor private enterprise and less incursion by the Post Office. However, it might also favor less regulation, and it is regulation that holds the Postal Service in check.

It's a complex picture, and nobody really knows what's going to happen, but in the following I'll cover what came up during the Mail and Message conference.

What Holds the Post Office In Check?

The Postal Service is held in check by the Postal Rate Commission, which oversees it. And the PRC, in turn, has a consumer interest office which noticed the problems with the original ECOM proposal.

The FCC, too, has oversight over the Postal Service, simply because it has control over interstate electronic carrier services and radio licensing. ("They're going to have to get their licenses somewhere," observed an FCC commissioner archly.)

Congress, of course, has the power to pass laws that reduce or expand the Postal Service role. (But once laws are passed, of course, it is generally up to executive agencies to interpret them, including those watchdogs already mentioned.)

Theory of Common Carriers

Both private services and the Post Office, if they offer point-to-point electronic communication, fall under the heading of "common carriers," and thus fall subject to the Federal Communications Commission. Thus, some common-carrier theory is in order.

A common carrier is somebody who offers to provide some kind of transportation to anyone. (You are probably wondering when the term "common carrier" originated in written law. 1930? No. 1890? No. 1348? Yes.) Modern regulation of common carriers began in the nineteenth century, under the Interstate Commerce Commission, principally because the railroads were being blatantly unfair in their rate structure.

The common carrier must provide service to all customers who request it, with no undue discrimination in pricing or other conditions of service. In order to recognize improper pricing, however, regulators must investigate the relation between the cost of providing a service, and the price of that service based on that cost. (Otherwise a carrier could gouge on one service and provide another at a low cost. Note that in ordinary business this is called a "loss leader," and perfectly acceptable, but in a regulated industry, it is called *cross-subsidized*, meaning that it is actually being paid for out of profits from something else. And it is illegal, because it distorts the cost of transportation, a fundamental necessity for all.



Thus, published "tariffs," or tables of rates, state the precise conditions of service, and the carrier must keep up these services for these rates indefinitely until he is given permission not to do so. (Note that with published tariffs, not only is what you see what you get, but what you see is pretty much *all* you get, since any enhancements or additional service would fall outside the permitted tariffs.)

A gloomy business, this, utterly insulating suppliers from the market forces which make our economy otherwise so dynamic. But generally regarded as very necessary.

In this century, especially through the Communications Act of 1934, common carrier doctrine has given the Federal Communications Commission regulatory power over such services as telephone, telegraph and radio station, much as other agencies oversee railroads and freight haulers.

The foregoing theory of common carriers was presented at the conference in a fascinating talk given by Philip Verveer, a lawyer at the FCC. Verveer, silverhaired, seems generally depressed and talks rapidly in a low voice, but with such directness and cogency as to get very full attention. There had been no applause at the conference till after his speech.

In his summary, Verveer expressed his personal opinions of the upcoming problems. What then must the FCC be concerned with in the new services? Three things.

1. *Possible cross-subsidy*. If a common carrier, such as the telephone company, or even the Post Office, proposes a new electronic service, they must prove the service can stand on its feet without being subsidized out of other profits.

2. *"Pipeline infrastructure."* The new basic transportation services, such as Telenet, must be regulated in the standard fashion.

3. *Enhanced services*. The question is whether enhancements to that pipeline service—new features, new software on top, connections to other programs and Licklider's showers of sparks—need to be regulated. The FCC, answers Verveer, proposes a double standard for these new services, depending on whether they're offered by old companies or new. He proposes only light regulatory oversight over enhanced services by *recognized* common carriers (read: Ma Bell, P.O.), in particular to make sure there is no cross-subsidization.

But the question, then, is will the *new* enhancers be common carriers?

Verveer saw this as "metaphysics." If a common carrier is an "entity found in nature," then you ought to know it when you see it, but if the notion is an arbitrary one to be applied by the FCC, then the FCC in its wisdom can leave most of them alone.

And that is his position: A common carrier in electronic hyperspace is whatever we say it is, and we don't intend to see any, regulating neither resale nor enhancement.

Verveer stressed that these were only his opinions. Nevertheless the arguments gained stature from both his keen presentation and his position as Chief of the Common Carrier Bureau of the FCC.

Is It Under The Tent?

Henry Geller, of the National Telecommunications and Information Authority, Department of Commerce, somehow reminded me of Henry Morgan. I think it was a two-level mischievous smile and a gallus-snapping manner.

Our policy, said Geller, is "to promote competition whenever possible," so as to foster a true market place and so businesses don't have to keep asking federal agencies what is legal. The issue, however, is what

IF YOU'RE WAITING FOR THE PRICE OF WORD PROCESSORS TO FALL WITHIN REASON,

Everyone expected it would happen sooner or later... with WordPro PLUS™ it already has! Now all the marvelous benefits of expensive and advanced word processing systems are available on Commodore computers, America's largest selling computer line. WordPro PLUS, when combined with the new 80 column CBM 8032, creates a word processing system comparable to virtually any other top quality word processor available—but at savings of thousands of dollars!

New, low cost computer technology is now available at a fraction of what you would expect to pay. This technology allowed Commodore to introduce the new and revolutionary CBM 8032 Computer.

WordPro PLUS turns this new CBM 8032 Computer into a sophisticated, time saving word processing tool. With WordPro PLUS, documents are displayed on the computer's screen. Editing and last minute revisions are simple and easy. No more lengthy re-typing sessions. Letters and documents are easily re-called from memory storage for editing or printing with final drafts printed perfectly at over five hundred words per minute!

Our nationwide team of professional dealers will show you how your office will benefit by using WordPro PLUS. At a price far less than you realize.

Invest in your office's future...
Invest in WordPro PLUS...
Call us today for the name of the WordPro PLUS dealer nearest you.

Professional Software Inc.
166 Crescent Road
Needham, MA 02194
(617) 444-5224
TELEX: 95 1579

CIRCLE 251 ON READER SERVICE CARD

Regulation, continued...

should the Postal Service do in Electronic Mail.

The current "uneasy truce"—ECOM—has the Post Office doing only paper output and end delivery, not electronic output; but Geller considers that "inefficient." The possibility remains that this compromise will fall apart: "The Camel's nose is under the tent," says Geller. Geller further predicts that Congress will let the matter slide, and the problem will end up in the courts.

Geller's argument is an administrative one. If the Post Office makes an end-to-end system, it's a "hybrid" situation where government is competing with private industry. It is neither free enterprise nor the governmental "Postal Telephone and Telegraph" system of Europe.

But if that happens, end-to-end service head-to-head with private carriers, how can you have simplification and deregulation? If the government is operating a business, how can the real businesses get a fair shake? Industry and government agencies have different motivations and "different ways of borrowing money."

His position is that the Post Office ought to do physical delivery when people want it, and be hooked up for input from all nets, and that's it. But mainly for the sake of an uncomplicated regulatory picture.

Geller was joined in his presentation by Richard Neustadt from the White House, a smoothie young lawyer type in a striped suit.

On the camel issue, Neustadt was an optimist. The Post Office will *never* get into end-to-end transmission; the "camel's nose" model is wrong; the industry will never allow it.

Interestingly, none of the regulators approached the problem of the Post Office from the point of view of the dangers of oversimplification and inflexibility. The Post Office's greatest threat may be in reducing the imagination and power of evolving services. (See "Humph.") □

Mail Chauvinism, continued...

community, and he is their shepherd. It is rather like a shepherd fondly inspecting a bleating flock that he addresses us.

Taylor takes a poll of the group. Half the audience had used "electronic nets" (whatever they think they mean by that); but only a third had written a program. (This suggests that half scarcely knew what a computer was.)

Onward nevertheless. Taylor explains that one of the special features of electronic messages is that they are read at the *receiver's convenience*, waiting somewhere till he is ready. And that since they are really brought to us by and through computers, message systems are "software-intensive," requiring programming development on a grand scale.

He rolls the videotape. On screen we see Taylor at his Alto, the famous PARC hot minicomputer with the finely detailed screen. We see the screen divided into many fields, which part like the Red Sea as Taylor on the screen points first at one thing, then another. A prompt tells him that messages are waiting; he reads them, replies, acts, discards, causing various rearrangements of the screen with offhand magical passes of his hand.

"If you think about these as systems for moving strings of characters, you miss the point of their power."

One note we see him read on the screen causes him to change a schedule; another he tells, effectively, "Go file yourself." One note he sends electronically to several other people, selecting them by flicking their names from a list that appears.

Taylor explains as he goes. "My message system is much more than a message system," he understates.

Fields of text rearrange themselves on the screen, compress, expand. Sometimes the moving cursor is a box, sometimes an hourglass, sometimes something else. So quickly and effortlessly do the messages come and go on Taylor's Alto screen, you hardly realize that the work you see him doing would be a storm of activity if he were shuffling actual paper.

(The audience is studious but impassive. I get the feeling that only a few understand what they see—those who already know about it—but that the rest of the audience doesn't know what it's about and can't tell.)

These messages we see the videotaped Taylor working with are not mere telegrams that go from one person to another and stop. Rather, he may search and scan through them, alter them, pass them on, or reply, with a flick of the wrist; they roll and fly before his face like the cards of a riverboat gambler. Some of them involve graphics and color and audio. "If you think about these as systems for moving strings of characters, you miss the point of their power," he says.

The phrase "Office of the Future" has been bruited about a great deal in Xerox publicity, as in, "we're developing the Office of the Future at Xerox PARC," but of course who can agree on what that means? Yet here it is in front of us: the paper trivia-flows of the office are calmly controlled on the Flatland of the screen. I

don't know what the paperwallopers at Xerox Corporate think the Office of the Future may be, but I'll gladly settle for this one.*

What we see Taylor working with is still, in fact, a world of documents, separate, potentially printable on paper. But here is the kicker. Less than 1% of the electronic messages at PARC, he tells us, ever get printed out.

Wizard Two is Michael Dertouzous of MIT. He heads what used to be called Project MAC, where time-sharing began; now it has 300 employees and a more boring name, the Laboratory for Computer Science. He is tall, dashing, accented, ought to wear a cape.

As computer prices go down 30% a year, he says, hidden computers will proliferate everywhere, just like the "hidden motors" that we know as hair dryers and such.

He shows us screen-views of his own personal files: a schedule (which becomes a history file as it slides through the present), his list of associates and acquaintances (cross-filed by name and city, so he can fill his travels with companionship); his checkbook (which automatically categorizes everything).

And he shows us how message systems of the future might let us go shopping. Suppose he wants a certain kind of wallet. His computer now makes inquiries at various shopping data banks, looking for wallets of the right size and color, and makes notes on which ones come closest to the desired configuration.

Wizard Three gives us a conceptual framework for thinking about this world. He is J.C.R. Licklider, called Lick by everybody. Warm and cheery, Lick is a founder of time-sharing, past director of Project MAC, and Arpa pioneer. (Starting up the computer work at Arpa, he financed Ivan Sutherland's Sketchpad.) One of the greats.

Licklider foresees a world where "all intellectual functions are well supported by computers." (Right now we have "access to gigabits through punybaud," but that will change.)

Licklider's messages and examples on the screen involve fill-ins and subroutines and modelling. He shows how he can program his computer to make dinner arrangements when he goes to a certain city: if the first person invited can't have dinner, his computer scans the list of his other friends in the same city and issues dinner invitations to *them*. All this in a simple conditional language.

"I want Granny, at home, with her video text, to be able to use this too...."

But rather than talk about "computers," whose actual whereabouts and boundaries become indeterminate in this sort of a coming world, Lick prefers to talk about "agents" or "assistants," things you set up to do things for you. (Lick also likes to call them Olivers, after Oliver Selfridge, who came up with the idea around 1966.) Agents will handle "augmented telephone calls," stacking the calls and pushing them through automatically. Agents will pay your bill, checking them against the appropriate invoices in standard electronic forms. They will sniff out information a friend may have set out: his birthday, gift preferences and sizes, party invitations, information he would like from whoever knows it.

Agents will not merely receive messages; they will react to them, sending out new feelers and requests to other computers and agents. Messages, forking and thrusting through a forest of computers and agents, will inquire, update and reply, often waiting for interactive responses. Messages will independently link to animated diagrams and status displays, keeping them current.

* Note: this system effectively became available at the 1981 National Computer Conference, where Xerox demonstrated the Star personal computer. Stars are individual $20,000 machines to be connected together throughout a company by the Ethernet cable.

Zeitgeist™

...The Spirit of the Times

Zeitgeist

...an organization of educators serving education...provides creative microcomputer course materials for secondary/elementary schools and higher education.

Zeitgeist

...programs reviewed by content and learning theory specialists...pretested in school settings... instructor/student guides provided.

Zeitgeist *presents*

Secondary School Mathematics Competency Series

in Apple Soft, for the Apple II (48K)

Programs prepare students to meet secondary school proficiency standards...serve as remedial preparation for college students...combine color, sound and animation in a space/time simulation.

Zeitgeist

...searches for creative program designers worldwide.

For further information, contact:

Zeitgeist ... 5150 N. 6th St., Suite 179, Fresno, Ca. 93710

CIRCLE 284 ON READER SERVICE CARD

If you can beat these prices, you must have a brother-in-law in the business.

16 K RAM KITS

NEC 4116 200 ns	17.95

DISKETTES

MO 525-01,10,16	26.50
MO 550-01,10,16	44.50
MO 577-01,10,16	34.80
MO 557-01,10,16	45.60
FO 32 OR 34 -9000	36.00
FO 32 OR 34 -8000	45.60
FD 34-4001	48.80

DISKETTE STORAGE

5¼" PLASTIC LIBRARY CASE	2.50
8" PLASTIC LIBRARY CASE	3.50
PLASTIC STORAGE BINDER WITH INSERTS	9.95
PROTECTOR 5¼"	24.95
PROTECTOR 8"	29.95

INTEGRATED COMPUTER SYSTEMS

ITHACA INTERSYSTEMS	CALL
ALTOS	CALL
ZENITH Z89	CALL
CALIF COMPUTER SYSTEMS	CALL
MORROW DESIGNS	CALL

PRINTERS

ANADEX DP 9500	1295.00
ANADEX DP 9501	1295.00
CENTRONICS 739	765.00
C-ITOH 25 CPS PARALLEL	1440.00
C-ITOH 25 CPS SERIAL	1495.00
C-ITOH 45 CPS PARALLEL	1770.00
C-ITOH 40 CPS SERIAL	1870.00
C-ITOH TRACTOR OPTION	195.00
EPSON MX-80	$CALL
EPSON MX-80 F/T	$CALL
EPSON MX-100 GRAPHIC	$CALL
EPSON GRAPHICS ROM	90.00
IDS-445G PAPER TIGER	779.00
IDS-460G PAPER TIGER	945.00
IDS-560G PAPER TIGER	1195.00
INFOSCRIBE 500 9X9, 150 CPS	1495.00
MALIBU 200 DUAL MODE	2995.00
NEC SPINWRITER 3510 SERIAL RO	2099.00
NEC SPINWRITER 3530 PARALLEL RO	2099.00
NEC SPINWRITER 7710 SERIAL RO	2595.00
NEC SPINWRITER 7730 PARALLEL RO	2595.00
NEC SPINWRITER 7700 O SELLUM OPTION	2795.00
NEC SPINWRITER 3500 SELLUM OPTION	2295.00
OKIDATA MICROLINE 80	399.00
OKIDATA MICROLINE 82A	599.00
OKIDATA MICROLINE 83A	899.00
OKIDATA MICROLINE 84	1199.00

MODEMS

NOVATION CAT ACOUSTIC MODEM	145.00
NOVATION D-CAT DIRECT CONNECT MODEM	155.00
NOVATION AUTO-CAT AUTO ANSWER MODEM	219.00
NOVATION APPLE-CAT	349.00
UDS 103 LP DIRECT CONNECT MODEM	175.00
UDS 103 JLP DIRECT CONNECT/AUTO ANSWER	209.00
D.C. HAYES MICROMODEM II (Apple)	299.00
D.C. HAYES 100 MODEM (S-100)	325.00
D.C. HAYES STACK Smart Modem (RS 232)	249.00
LEXICON LX-11 MODEM	115.00

APPLE HARDWARE

VERSA WRITER DIGITIZER	219.00
ABT APPLE KEYPAD	119.00
MICROSOFT Z-80 SOFTCARD	299.00
MICROSOFT RAMCARD	170.00
ANDROMEDA 16K CARD	170.00
VIDEX 80 X 24 VIDEO CARD	299.00
VIDEX KEYBOARD ENHANCER	99.00
M & R SUPERTERM 80 X 24 VIDEO BOARD	315.00
NEC 12" GREEN MONITOR	235.00
SANYO 12" MONITOR (B & W)	249.00
SANYO 12" MONITOR (Green)	279.00
SANYO 13" COLOR MONITOR	469.00
TEECO 12" HIGH RES GREEN MONITOR	169.00
SSM A/D BOARD (INTERFACE) A&T	165.00
SSM A/D BOARD (INTERFACE) KIT	135.00
SSM IEEE 488 INTERFACE	369.00

MOUNTAIN HARDWARE

CPS MULTIFUNCTION BOARD	209.00
SUPERTALKER SO200	259.00
ROMPLUS WITH KEYBOARD FILTER	179.00
ROMPLUS W/O KEYBOARD FILTER	130.00
KEYBOARD FILTER RDM	49.00
COPYROM	49.00
MUSIC SYSTEM	459.00
RDMWRITER	149.00
APPLE CLOCK	252.00
A/D + D/A	299.00
EXPANSION CHASSIS	575.00

VISTA COMPUTER CO.

APPLE 40 Track Drive A40 (163 K Bytes)	389.00
APPLE 80 Track Drive A80 (326 K Bytes)	549.00
APPLE 160 Track Drive A160 (652 K Bytes)	799.00
APPLE 80 Column Card	329.00
APPLE 8 Inch Disk Drive Controller	549.00

CALIF. COMPUTER SYSTEMS

S-100 BOARDS

2200A MAINFRAME	349.00
2032A 32K STATIC RAM	599.00
2065C 64K DYNAMIC RAM	499.00
2422 FLOPPY DISK CONTROLLER & CP/M	339.00
2710 FOUR SERIAL I/O	249.00
2718 2 SERIAL/2 PARALLEL I/O	269.00
2720 FOUR PARALLEL I/O	199.00
2810 Z-80 CPU	249.00

APPLE BOARDS

7710A/O ASYNCHRONOUS SERIAL INTERFACE	139.00
7712A SYNCHRONOUS SERIAL INTERFACE	149.00
7424A CALENDAR/CLOCK	99.00
7728A CENTRONICS PRINTER INTERFACE	99.00

APPLE SOFTWARE

MAGIC WINDOW WORDPROCESSOR	89.00
MAGIC WAND	275.00
WORDSTAR—APPLE	259.00
MAILMERGE—APPLE (REQUIRES WORDSTAR)	90.00
SPELLSTAR—APPLE (REQUIRES WORDSTAR)	169.00
DATASTAR	199.00
EXPEDITER II APPLESOFT COMPILER	89.00
PFS: PERSONAL FILING SYSTEM	79.00
PFS: REPORT GENERATOR	79.00
ASCII EXPRESS TERMINAL PROGRAM	59.95
Z—TERM COMMUNICATIONS SOFTWARE	89.95
MICROSOFT FORTRAN	165.00
MICROSOFT COBOL	550.00
DB MASTER 2.4	179.00
VISICALC 3.3	169.00
VISIPLOT	149.00
VISIDEX	169.00
CCA DATA BASE MANAGER	99.00
A-STAT COMPREHENSIVE STATISTICS PKG	119.00

APPLE GAME SOFTWARE

SPACE EGGS	24.95
POOL 1.5	29.95
RASTER BLASTER	24.95
GORGON	32.95
APPLE PANIC	24.95

CP/M SOFTWARE

MICROSOFT BASIC-80	299.00
MICROSOFT BASIC COMPILER	319.00
MICROSOFT FORTRAN-80	399.00
PEACHTREE SYSTEMS	CALL
MAGIC WAND (REQUIRES CP/M)	275.00
WORDSTAR (REQUIRES CP/M)	325.00
MAILMERGE (REQUIRES WORDSTAR)	110.00
SPELLSTAR (REQUIRES WORDSTAR)	199.00
DATASTAR	249.00
SPELLGUARD	239.00
CP/M PICKLES & TROUT FOR TRS-80 II	175.00

MORROW DESIGNS

FLOPPY DISK SYSTEMS

Controller, P.S., Cables, Microsoft Basic, CP/M, A&T

DISCUS I (Single Drive—250 K)	799.00
DISCUS I (Dual Drive—500 K)	1429.00
DISCUS 2D (Single Drive—500 K)	869.00
DISCUS 2D (Dual Drive—1 MEG)	1499.00
DISCUS 2+2 (Single Drive—1 MEG)	1099.00
DISCUS 2+2 (Dual Drive—2 MEG)	1999.00

HARD DISK SYSTEMS

Controller, P.S., Microsoft Basic, CP/M, A&T

DISCUS M10 (10 Megabytes)	2949.00
DISCUS M20 (20 Megabytes)	3829.00
DISCUS M26 (26 Megabytes)	3949.00

DECISION 1 COMPUTER

Z-80A, CP/M, NIX (UNIX Identical), 32 to 1 MEG of memory

Floppy and/or Hard Disk	CALL

SD SYSTEMS

S-100 BOARDS

VERSAFLOPPY II A&T	389.00
VERSAFLOPPY II KIT	329.00
SBC 200 (Z-80 CPU) A&T	369.00
SBC 200 (Z-80 CPU) KIT	299.00
Z-80 STARTER KIT	289.00
EXPANDORAM II KIT (0K)	220.00

TRS-80 MOD I HARDWARE

PERCOM DATA SEPARATOR	27.00
PERCOM DOUBLER II	159.00
DOUBLE ZAP II/80	45.95
TANDON 80 TRACK DISK DRIVE	429.00
TANDON 40 TRACK DISK DRIVE	299.00
LNW DOUBLER WITH DOSPLUS 3.3D	169.00

TRS-80 SOFTWARE

NEWDOS/80 2.D MOD I	139.00
LAZY WRITER MOD I	125.00
PROSOFT NEWSCRIPT MOD I,III	99.00
SPECIAL DELIVERY MOD I,III	119.00
X-TRA SPECIAL DELIVERY MOD I,III	199.00
TRACKCESS MOD I	24.95
OMNITERM SMART TERMINAL MOD I,III	89.95
MICROSOFT BASIC COMPILER FOR MOD I	165.00

CORVUS

FOR S-100, APPLE OR TRS-80 MOD I,II

Controller, Case/P.S., Operating System, A&T

5 Megabytes	3095.00
10 Megabytes	4495.00
20 Megabytes	5395.00
MIRROR BACK-UP	700.00

SUPPLIES

AVERY TABULABLES

1,000 3½ X 15/16	8.49
3,000 3½ X 15/16	14.95
5,000 3½ X 15/16	19.95

UARCO PAPER (Prices F.O.B. S.P.)

9½ X 11 18 lb white	29.00
14¾ X 11 18 lb white	39.00

We stock a complete line of computer covers, printer ribbons, print wheels & NEC thimbles—CALL US FOR YOUR NEEDS.

We built a reputation on our prices and your satisfaction.

Alpha Byte STORES

(213) 883-8594

We guarantee everything we sell for 30 days. If anything is wrong, just return the item and we'll make it right. And, of course, we'll pay the shipping charges.

We accept Visa and Master Card on all orders. COD orders accepted up to $300.00. We also accept school purchase orders.

Please add $2.00 for standard UPS shipping and handling on orders under 50 pounds, delivered in the continental U.S. Call us for shipping charges on items that weigh more than 50 pounds. Foreign, FPO and APO orders please add 15% for shipping. California residents add 6% sales tax.

The prices quoted are only valid for stock on hand and all prices are subject to change without notice.

31245 LA BAYA DRIVE, WESTLAKE VILLAGE, CALIFORNIA 91362

CIRCLE 159 ON READER SERVICE CARD

Subprograms call each other *internally* all the time, says Lick; soon they'll be doing it *externally*, sometimes in parallel, sometimes queuing. So the interchange of "messages" becomes something larger, a cross fire of interacting events.

But now you see this messaging is something else. It is not postcards or telegrams, it is not document handling. In its back-and-forthing it is more like the telephone than telegraph. It is a new form of closely coupled responsive session, a chain-reaction system of intercommunications, among—what? Agents. Places. Data bases. Programs, texts, indications, semaphores. It is a pool-table model, like a gunbattle, like atomic nuclei near critical mass: the event-shower-interchange session. A shower of sparks.

CONTINUED ON PG. 140

Agents will pay your bills, checking them against the appropriate invoices in standard electronic forms.

The World of Packets, Protocol-and-Dagger

Packet nets range from Ethernet—a packet system for going between computers and terminals in an individual office—on up to Telenet, a world-wide packet service to which you can subscribe that will hook you to most other nets and time-sharing systems.

The basic idea of packet service is to get information—text, pictures, even voice—to and from the places you want. And it has to move in the timely manner that today's computer user expects—within fractions of a second. This is particularly true for highly interactive sessions involving two or more computers or agents in united interaction.

The internal mechanisms of packet communication are not hard to understand if you already understand about computers and disks. Essentially a packet network is a set of interconnected computers and disk drives, which finally connect to users of one sort or another.

All messages, however long or short, are divided into "packets," sequences of bytes of a uniform size (such as 128 bytes) and padded out to fill the last packet.

In a full-scale packet network, the actual data is sandwiched between the many additional bytes required to carry it along. The packet of data is surrounded by an "envelope" of bytes specifying parity checks, packet numbers (for the identification, retransmission and reassembly of damaged ones), addressee routing information, billing information. The envelopes may be changed by various computers along the way; only the contents are meant for the recipient.

A packet is not unlike a disk block. Though a disk block may be surrounded by various bits (parity, clock, guard), in the final analysis these are not the contents, but only helper information that goes away when the contents arrive successfully.

Packet transmissions go from one computer to another—sometimes through a long chain of computers—before reaching the final user. The first computer gets its packets ready—either dividing up and padding out the original message, or straightening out the packets it has received from elsewhere.

These it then sends sequentially over some channel to the next computer. The next computer signals to the sending computer when to send and when to pause.

Pause requests occur when the buffer area of the receiving computer is full, or part of the transmission has been damaged. If the buffer area is full, the receiving computer may in turn re-transmit the packets down the line, or put them in longer-term storage (such as disk). Such buffering may occur, for instance, if there has been faulty transmission, while the computer awaits the broken packets again.

Because so many operations can be performed quickly by the packet computers, they are able to make numerous and repeated checks on the integrity of the data, and effectively create a flawless transmission chain depite unreliable channels. And the transmission lines can be used very efficiently, even with all the extra bytes, because the packets may be densely packed over time.

(Commercial packet nets may also vary their transmission capacity dynamically, renting additional lines at higher cost during moments of peak demand. Thus, successive packets in a given message may arrive over different channels and different routes, arriving at intermediate points quite out of order. It's the integrity of the material at its final destination that counts.)

Protocols

The back-and-forth interchange associated with data communication is called a "protocol." We saw this above with respect to packet transmission: the receiving unit says when it's ready, and tells the sending unit when to stop. But that's just the beginning.

The packet protocols are not seen by the user; they are "transparent." But other levels of protocol may be part of the interchange that the user (or his program) actually sees. The construction and combining of protocols is one of the frontier problems of today.

There are simple protocols and complex ones, such as the protocol needed to drive a Calcomp pen-plotter. The computer must repeatedly wait for signals saying the plotting unit is ready, and send out the next commands only at such times. This is an "application" protocol.

Or consider the protocol of the automatic bank-teller machines.

The automatic teller has four basic functions: account status, deposit, withdrawal, and guarantee-a-check-at-the-supermarket. All but deposit require "authentication," making sure that the card in the slot and the password permit what has been requested.

The teller box sends a transaction ID, password, command and parameters. The bank's computer replies with the transaction number again, followed by either GO or NO GO (or the strong form of NO GO, GRAB, which causes the card to be eaten).

In today's complex packet networks, protocols are stacked and nested, relating to a hierarchy of computers, programs and agents along the way, with different messages addressed to "subnets," "gateway processors," "host processors" and the "user application" itself. The logic is along the lines of "Give this first note to the bartender and he'll let you in the back. Then give this note to the guy in back and he'll fix you up."

Several of the researchers at the M&M Conference—John McQuillan of BBN, Ian Cunningham of Bell Northern, Carl Sunshine of USC Information Sciences Institute, Vinton Cerf of Darpa—are working on systems of higher-level protocols that can be customized for a variety of purposes at the user level while providing reliable transport and confirmation at the packet and other levels. Higher-level protocols are like higher-level languages: they seem to be inefficient at first blush, but the supposed inefficiencies are far outweighed by their improved maintainability and evolutionary potential. They can evolve and be upgraded indefinitely.

Ian Cunningham's OSI protocol, for example, is intended to work on a variety of networks and a variety of computers, providing a framework of standard protocols within and upon which can be built a variety of applications. There are seven layers (that we needn't get into here), but they go up to "session" layers, communicating between processes, and "presentation," dealing with data representation. Only a couple of these are within user reach.

Security: Privacy, Encryption, Authestication

Packet transmission of plain text is all very well in a world of trust and good

CREATURE VENTURE

You have just inherited your Uncle Stashbuck's mansion but first you must rid it of the horrible creatures that have taken it over and find your uncle's buried treasure.

Directing the computer with two word commands such as 'Go North', 'Get Key', 'Look Room', 'Punchout Boogeyman' etc. you will need to explore deep into the mansion to finally find the Stashbuck Fortune.

There are tons of High Resolution graphics plus some clever animation just for fun.

Requires 48K Ram, Applesoft Rom and disk.

All High Resolution characters generated with Higher Graphics II by Robert Clardy.

CREATURE VENTURE on disk

$24.95

GOBLINS

Escape to GOBLIN Country, an adventure to challenge your wits and cunning where you will need skill and sorcery to survive Dragons, Ogres and Goblins.

Myths and Magic, Treasure and Danger.

Fantastic High Resolution Graphics and animation help you on your journey.

Requires 48K, Applesoft ROM and disk

A world apart – enter if you dare!

GOBLINS on disk

$27.50

TARTURIAN

THE TARTURIAN requires 48K RAM, APPLESOFT ROM, and disk. As you explore the 160 rooms (each done in HI-RES), gathering weapons and treasure that will prepare you for the final battle against the TARTURIAN, you will encounter deadly KROLLS, battle the MINOTAUR, try and get by COUNT SNOOTTWEEKER, decipher the YUMMY YAKKY'S secret, make friends with the TULIESWEEP, avoid GHOULS, explore the PILLAR tombs, discover secret passages and more, 5 interlocking programs.

TARTURIAN on disk

$24.95

OLDORF'S REVENGE

OLDORF is a well done and exciting HI-RES game using over 100 HI-RES pictures. OLDORF requires 48K, Applesoft Rom, and Disk. As you explore the caverns and castles (each locale is done in HI-RES) looking for treasure, you must battle the one-eyed, two-thumbed torkie; find the grezzerlips' sword; visit the snotgurgle's palace and get through the domain of the three-nosed ickyup – Plus MORE!

OLDORF on disk

$19.95

CRAE

The finest Global Applesoft program editor on the market today and here's why:

Written entirely in Machine Language. Global Find (Search) for anything in your program; Global Change (Replace) that can substitute anything in your program, anything!; List 40 columns across on screen with no added spaces; The fastest renumber in the business; Quote (Copy command for moving program lines anywhere in your program; Automatic Line Numbering; HEX/ASCII Memory Dump. Plus 5 more powerful commands. CRAE co-resides in memory with your Applesoft program so that all editing of your program is done right in RAM. If you are familiar with TSO then you are familiar with CRAE. Compatible with Neil Konzen's P.L.E. Requires 48K RAM, Applesoft ROM and disk.

CRAE on disk with manual

$24.95

MCAT 2.0

MCAT 2.0 is a fast binary utility which creates a sorted master catalog which is saved on disk as a binary file (Fast). The master catalog can be easily updated a whole diskette at a time (Add, Delete, Replace), List/Print have global search capability and one or two columns. Provisions for duplicate volume numbers. Approximately 1200 file names. 48K or 32K, 13 or 16 sectors DOS supported.

MCAT on disk with 10 page manual

$19.95

SPECIALS

EROM 1, 2, 3

$99.95

CRAE and MCAT on one disk

$39.95 with manuals

EROM #1

Requires Applesoft ROM & ROM-PLUS. CRAE'S powerful Global change/find, optimizes List Command, Hex to Decimal and Decimal to Hex conversion now available on a 2716 EPROM.

EROM #1 with manual

$49.95

EROM #2

Requires Applesoft Rom and Romplus

CRAE's Autoline numbering, formatted memory Dump, Append, Number Conversion (Hex/Dec) on one 2716 EPROM.

EROM #2 with manual

$34.95

EROM #3

CRAE's powerful Renumber and Quote function now on two 2716 EPROMS.

EROM #3 with manual

$34.95

apple

SEE YOUR LOCAL DEALER OR SEND CHECKS TO

HIGHLANDS COMPUTER SERVICES

14422 S.E. 132nd
Renton, Washington 98056
(206) 228-6691

Washington residents add 5.4% sales tax. Applesoft and Apple are registered trademarks of Apple Computers, Inc.

Romplus is a registered trademark of Mountain Computers, Inc.

apple

VISA

master charge

CIRCLE 259 ON READER SERVICE CARD

Dagger, continued...

will. Unfortunately, there will also be a need for privacy—for personal reasons, business reasons, and reasons of state—and to protect us *from* the state. And we need to think about these matters now.

The first and most obvious problem of privacy is encryption—keeping other people (and their computers) from reading your messages. This is not easy, and strange political problems are surfacing.

The "official" encryption standard—a code system generally available—is the DES. You can get a chip that performs this encoding and decoding, using a secret key you've chosen. But public accusations have been levelled at this method, specifically that the U.S. government may be promoting it because they know how to break it.

The much more powerful, tough-nut encryption system is the remarkable RSA code out of MIT, a "trapdoor" code with two keys. Either may decode what has been encoded by the other—but you *cannot derive one from the other*, at least in less than a million years of computation. This means *you can safely make one of them public*, so that anybody can send you a secret message (encoding it with your public key; only you can decode it) or you can "authenticate" a message, encoding it with your private key so that anyone can decode it only by using your public key, thus proving its origin. Though the government has apparently been trying to suppress the RSA code, so far it is a uniquely powerful solution to the encryption problem. Though a thousand times slower than the DES, it, too, may soon be available on a chip.

Unfortunately secret contents and authentication aren't the whole ballgame. Disguising whom a message is *to*, and how long it is, may also be important; yet these must be incorporated in the enveloping techniques of the packet system itself—a level of service which hasn't been offered yet.

Certain other desirable features also should be built in at the network level. These include "time-stamping" of transmitted material, and ways of proving a thing was sent—effectively, "registered mail."

Because of the ferment, complication and newness of all these areas, the packet-and-protocol men at the M&M Conference appeared to be unanimously against standardization at the present time. And would-be suppliers of service, such as the Post Office, must demonstrate that they give a hang about such matters.

1984sville

As already mentioned, several commentators have expressed alarm at the government's curious treatment of the DES and RSA codes. But other sinister forebodings can be found if you look.

Dertouzos of MIT warned us that networking can become a new totalitarian instrument, with surreptitious and unauthorized "explorations" an important new area of government imposition. Neustadt of the White House put it more simply: "Can the FBI intercept your messages?" And if someone snoops in the records of a message-repeating station where your messages may have been kept on tape, is it wiretapping?

Vezza of MIT also feels very strongly about this. In the testimony that led to the new ECOM design, he fought the Post Office's plan of keeping tapes for message verification: there was no reason, he thought, that the sender's original record would not be sufficient in case of doubt. But that has been overruled, and tapes of the billions of ECOM messages *will* be kept by the Post Office—for, we are told, a limited period of time. This is not unlike having the Post Office Xerox every letter that goes through the mail.

Those who believe conspiratorial tales of government intelligence agencies, covering the deaths of John Kennedy through John Lennon, see these matters as additional indication that our Secret Masters are preparing our further future enslavement. A more moderate perspective, however, would indicate simply that many people and agencies are behaving with authority in areas where not much is known yet. Perhaps the time is ripe for neither alarm nor smugness. □

Mail Chauvinism, continued...

The Camel

Across this landscape of cheery electronic possibilities there came, not so very long ago, an interesting intruder: the United States Postal Service.

You have heard of camels. You have undoubtedly also heard the expression, "When the camel gets its nose inside the tent, the rest will follow," or some exotic equivalent, intended to convey the idea that the rest of a camel cannot be far behind its intruding tip, and all of the camel will soon be within any environment it penetrates.

Now before this parable can be fully explained, and we can get back to the conference, it is necessary to fill in some facts and history.

By law, the Post Office has monopoly power over delivered things. You cannot, for instance, open a delivery service between cities except under certain between cities except under certain specific, narrow conditions. (And symbolically, you must have U.S. stamps on the parcels your service brings.)

This is the infamous "delivery monopoly." At least one M&M speaker, Lloyd Johnson, spoke as though there were a danger that the post office might *attempt to extend this monopoly to all electronic messages*. This also seemed to be the position presented by Jaquish of the Postal Service, who spoke as if the Postal Service had a natural right that extended into this new realm.

In 1978 the Post Office proposed to open a new service, called E-COM (Electronic Computer Originated Mail; the hyphen is something of a mystery).

Now, the Post Office cannot just do anything it wants. It must get permission from the Postal Rate Commission, making formal proposals for new services.

sending thousands of pieces a year—to a centralized computer system. (This would be Western Union's facility in Middletown, VA.)

In this original proposal, a large variety of inputs would bring messages to the Western Union computer. Bills and form letters would be repetitively copied, electronically, with appropriate names, amounts and other fill-ins; then these finished telegraphic communiques would be sent electronically to 25 major "serving post offices," where their contents would be printed out, stuffed in envelopes, and delivered with the regular mail.

Original E-Com Proposal.

The Post Office proposed in 1978 to connect very large mail-senders—those

This proposal had several problems. One was technical ghastliness: tapes being

This Months Special

Okidata Microline 80

At a New Low, Low, Price!

Microline 80

A great buy

– List Price is $545. The **Microline 80** is a quiet, small printer with field proven reliability.

Features:

- Friction & pin paper feed, roll or fan fold
- Prints expanded characters and block graphics
- Print speed 80 characters per second
- Printhead rated at 200 million characters continuous cycle
- 132-column compressed print
- Available RS-232C Serial Interfaces: LIST

ORS-256 (256 Character Memory) . . $109.00
MSP-100 (Unbuffered, Switch Select Data Rates) $120.00
MSP-200X (200 Character Memory) $215.00
MSP-2000X (2000 Character Memory) $300.00

Other available options:
Adjustable Tractor Feed - Model 54100201 . . . . . $ 50.00
TRS-80 Parallel Output, cable to printer . . . . . $ 35.00
Ribbons . . . . . $ 3.00

TRANSFORM YOUR COMPUTER

into a Word Processing or Data Processing System by adding one of the NEW Okidata Printers



Microline 83A

Microline 82A

If you require a system printer, the new Okidata Microline 82A, 83A, 84 should be your choice.

These printers feature:

- 9 x 9 Dot Matrix heads rated at 200 million characters continuous duty - true lower descenders
- Full forms control – vertical tab, top of form
- Block Graphics
- Bidirectional, Short Line Seeking
- Dual Interface – Parallel & RS-232C Serial

Microline 82A – 80-column, LIST
120 characters per second . . . . . $ 879.
Tractor Optional . . . . . $ 50.
Microline 83A – 136-column,
120 cps, built-in tractor . . . . . $1195.
Microline 84 – 136-column,
200 cps, built-in tractor . . . . . $1495.
Optional Serial Interfaces – RS-232C:
HS-RSZ32 – 256 Character Buffer . . . . . $ 180.
HS-RSZ32 – 2K Character Buffer . . . . . $ 270.

THE STOCKING SOURCE

ASK FOR OUR INSTANT DISCOUNT
From Roy Hawthorne
Talk To Bill Toker On Applications

CALL TOLL FREE
U.S.A.
1-800-521-2764
MICHIGAN
1-800-482-8393

Remember:
We are open
8:30 AM to
6:00 PM EST
Monday – Friday

MasterCharge VISA
No Credit Card Penalty

"The Stocking Source"
24069 Research Drive
Farmington Hills, MI
48024
313-474-6708

CIRCLE 233 ON READER SERVICE CARD

Mail Chauvinism, continued...

carried among separate computers, for instance. Another was high cost (30 to 60¢ a letter). Then came some deeper problems: in selling electronic transmission services, the Post Office would be competing with several common carriers. This further threatened a monopoly fight related to the Post Office's monopoly prerogative of delivery, threatening (at worst) that whatever electronic mail *might* become would only be what the Post Office *allowed* it to become. And finally and darkly, archival copies of tapes were to be kept.

This proposal was brought before Albert Vezza, MIT professor and one of the architects of the Arpanet. He proposed a rather straightforward alternative: no centralized facility, and the use of common carriers—available electronic nets—between the serving post offices, where the printing and stuffing and delivery would occur.

This was simpler. It did not compete with common carriers, but used them. And it cost about ten times less per piece.

The two alternatives—the original one and Vezza's—were brought before the Postal Rate Commision, which decides these things. There was a bitter fight. The PRC's decision: "implement the Vezza alternative." The Post Office fought this decision in the courts, but had to give in. Finally it was accepted by the Post Office board of governors, but they then turned around and filed a lawsuit against the Postal Rate Commission to make the new arrangement *permanent* before it had even been tried—that very arrangement they had just been fighting.



ECOM as modified by Vezza and PRC, to be implemented in 1982 by RCA.

The Post Office proposed in 1978 to connect very large mail-senders—those sending thousands of pieces a year—to a centralized computer system.

The new system will supposedly be implemented in 1982. (As of this writing, the Post Office has accepted a proposal from RCA, but its contents have not yet become available.)

One leading and mischievous feature was added to the Vezza alternative in the ECOM system that was finally approved. This was an input link direct to the serving post offices. However, since the Postal Service was explicitly forbidden to provide end-to-end service ("generation three"), information received in this fashion is to be *put on magnetic tape and sent by express mail to receiving post offices*. (It is as though this step were undertaken explicitly to be inefficient, and cry out for the electronic completion that is not now allowed. A cynic might say the feature was put there as a festering inconvenience, crying out for proper electronic consummation and thus challenging the present compromise.)

This was essentially the view of Henry Geller (see "The Regulators")—that the Post Office will be continually maneuvering to add electronic services until it has "the whole thing," a monopoly of delivery to your own terminal. With ECOM, "*The camel's nose is under the tent*," says Geller.

What is anticipated in these early stages, since only high-volume mailers may play the game, are corporate mass mailings such as dunning letters, product recalls, bills and special advertising. A special advantage of ECOM is its ability to put special Text Insert Messages (TIMs) into COmmon Text (COT), adding all the John Smiths to supposedly personal messages. It seems this would save considerable in-house effort along the same lines for major mailers.

The Conference Again

Now here we are at the conference again, and we will hear some spokesmen from the Post Office.

First comes the head of R&D for the Post Office, Paul Jaquish. He is slow-spoken, balding, somewhat angry-seeming; his title is Senior Assistant Postmaster General, Research and Technology Group of the U.S. Postal Service.

He comes on as the heavy with a belligerent and defiant manner. Here is what I got down:

"We *must control service*."

"We cannot allow our resources to be spirited away." And finally:

"We have a legislative mandate and a financial requirement."

Well, at least it's up front. But what did it mean? Was he talking only about delivery on foot? Or is he telling us *their* electronics must eventually be the only ones that make messages available to our personal computers? It certainly sounded to *me* as though Jaquish said, essentially: "Whatever this is, it belongs to us."

When it came time for questions, I tried to ask the question that was burning on my mind, but it took too long. I said something like: "The format of this conference suggests a premature delineation of 'mail and message' systems, arbitrarily cutting them away from teleconferencing, data bases, highly interactive environments, electronic publishing and archiving. Could you comment?"

Jaquish's one-syllable answer got a big laugh, and we broke for the first lunch.

The next day we heard Vincent Sombrotto, president of the National Association of Letter Carriers and its 233,000 members. That's right, a quarter of a million.

Jaquish's one-syllable answer got a big laugh, and we broke for the first lunch.

The next day we heard Vincent Sombrotto, president of the National Association of Letter Carriers and its 233,000 members. That's right, a quarter of a million.

Sombrotto was fiftyish, with white hair and a ruddy complexion. The former president of the New York branch of the union, he had a Jimmy Durante Brooklyn accent and just about as much charm. Everyone seemed to find him unexpectedly likable.

Sombrotto addressed himself, naturally, to the question of what should be the role of postal personnel in electronic mail. I got down just three quotes.

"It's da most effecient postal soivice in da woild."

"If da wave of da future is electronic transmission of mail, den it only makes sense to use da most efficient awganization in da woild."

"If dis seems self-soiving" (cheery grin), "dat's exactly what it's meant to do."

Creative Computing-- Albert Einstein in black on a red denim-look shirt with red neckband and cuffs.

Creative's own outrageous **Bionic Toad** in dark blue on a light blue shirt for kids and adults.

Plotter display of **Pi to 625 Places** in dark brown on a tan shirt.

I'd rather be playing spacewar-- black with white spaceships and lettering.

Give your tie a rest!

All T-shirts are available in adult sizes S,M,L,XL. Bionic Toad, Program Bug and Spacewar also available in children's sizes S(6-8),M(10-12)and L(14-16). Made in USA. $6.00 each plus 75¢ shipping.

Specify design and size and send payment to Creative Computing, 39 E. Hanover Ave., Morris Plains, NJ 07950. Orders for two or more shirts may be charged to Visa, MasterCard or American Express. Save time and call toll-free **800-631-8112** (in NJ 201-540-0445).

Crash Cursor and Sync from the comic strip in SYNC magazine emblazoned in white on this black shirt.

Computer Bum-- black design by cartoonist Monte Wolverton on gray denim-look shirt with black neckband and cuffs.

The **Program Bug** that terrorized Cybernia in Katie and the Computer is back on this beige t-shirt with purple design. You can share the little monster with your favorite kid.

Roll down the block with this little black **Robot Rabbit** (on a bright orange t-shirt) on your back and you can intimidate every carrot, radish or cuke in your way.

CIRCLE 350 ON READER SERVICE CARD

Key Quotations

I. The New World

Bob Taylor of PARC: "If you think about these as systems for moving strings of characters, you miss the point of their power."

Sirbu: "Many people find that the filing and retrieval capabilities are the most useful."

Licklider of MIT: "[It's currently a problem of] access to gigabits through punybaud."

Neustadt of the White House: "Spectrum management will be the central issue of the 1980's," and "Can the FBI intercept messages?"

Kent of BBN: People say RSA code solves the key distribution problem. "But they lie."

Cunningham of Bell-Northern: "Once your letter is pushed through a mail slot, and a dog chews it, it's your problem."

McQuillan of BBN: "The great thing about standards is that there are so many of them."

Showalter of congressional staff: "We may not be able to teach congressmen C or Basic, but we may be able to fake 'em into thinking computers speak English."

Rose of congress: "I want Granny, at home with her video text, to be able to use this too."

II. The Post Office And, or In, the New World

Congressman Rose: "The U.S. congressman has many friends, and one of these is the U.S. Postal Service."

Sombrotto of the National Association of Letter Carriers: "It's da most effecient postal soivice in da wold," and "If da wave of da future is electronic transmission of mail, den it only makes sense to use da most efficient awganization in da wold," and "If dis seems self-soiving, dat's exactly what it's meant to do."

Joyce, consultant to the Post Office: "You're not going to see books and newspapers transmitted in the next twenty years," and "[In our estimates] We did not include the stimulation factor."

Jaquish of the Postal Service: "We *must control service*," and "We cannot allow our resources to be spirited away," and "We have a legislative mandate and a financial requirement."

Jackson of the FCC: "If they [the Postal Service] want to be involved in over-the-air bit streams, they have to get their radio licenses somewhere," and "I suspect this is something we'll have a lot of trouble with in our political system."

Anonymous professor with Arpanet connections, interviewed: "They [the Post Office] just don't understand this stuff and they don't know what they're doing."

Fritschler of the Postal Rate Commission: "The regulatory process can work, at least in this instance."

Zimmerman of the National Telecommunication and Information Authority: "You ought to be grateful that you don't get as much government as you pay for."

Anonymous consultant, interviewed: "I'm not interested in a Footnet." □

Mail Chauvinism, continued...

A Remarkable View

The most astonishing presentation was certainly that of Charles Joyce, formerly Director of Information Technology and Policy at the Mitre Corporation, and now consulting to the Post Office. He is a mumbler with a somewhat smug air and rather remarkable views.

Mr. Joyce had made a study of the "existing mailstream," that is, the things the Post Office delivers now. The question they tried to answer was what kinds of mail would be directly replaced electronically, or "diverted," according to this way of thinking.

The projections appear to hold approximately constant the number of messages per capita. The figures we saw foresee a slow drop in conventional mail as "generation two" and "generation three" get off the ground. And Joyce announces confidently: "You're not going to see books and newspapers transmitted in the next twenty years."

What makes him think the number of messages will stay the same? "We did not include the stimulation factor," he said.

Now this is most interesting: it assumes that each electronic message replaces a sheet of paper folded in an envelope, or some other enclosed packet of markings on cellulose. And it assumes a very constant universe. (Projections are often presented for varying sets of assumptions, none yet known to be true. No such fiddle-faddle here.)

Mr. Joyce's remarks were later commented on by Einar Stefferud, a consultant attending the conference:

"He wasn't considering the nature of the change of behavior. We aren't going to mail catalogs any more, there'll be query traffic."

"You're not going to see books and newspapers transmitted in the next twenty years."

Stefferud continued, "this rests on the assumption that electronic mail would be analogs or marginal equivalents of record traffic, but did not take into consideration the network transactions of Licklider's model—if you believe in networks."

Only time will tell, of course, but any observer would be reminded here of the projection made around 1947 that half-a-dozen of that day's computers (each with about the power of an Apple) would satisfy the United States for the foreseeable feature.

Or consider the market research of the Haloid Corporation, whose investigators repeatedly reported that the copying-machine Haloid was working on would only sell a few dozen before exhausting all the demand in the United States. (When the copier was finally introduced, Haloid changed its name to Xerox.)

The Friday lunch speaker was Lloyd Johnson, a poised and impressive individual, and staff director of the House of Representatives' Subcommittee on Postal Operations and Services. He sounded a less enthusiastic note for the Post Office than had Rep. Rose.

One of Johnson's first remarks was that everyone was proceeding from different assumptions, perhaps the best point made at the conference. He then went on to outline the history of the Post Office's maneuverings to institute electronic mail service, based on the notion that growing use of electronic messaging constituted "first-class mail diversion," as though someone were taking away what rightfully belonged to the Post Office, like the ball-point pens on chains.

Hair-raising estimates from various sources project staggering amounts of electronic communication. One commentator estimated that 220 million people would be sent ten items a day each averaging 30K bits per item. (Have you a better guess?) Vezza's earlier Congressional testimony had foreseen between 230 million and five billion electronic messages in *1983*, which would already be as much as *ten percent of the mail*!

CONTINUED ON PG. 150

#1 in Software and Applications

Sure, we could tell you we're the premier magazine of computer applications and software for both beginners and experts, but our readers say it even better.

Alvin Toffler, author of *Future Shock* and the *Third Wave* says, "I read **Creative Computing** not only for information about how to make the most of my own equipment but to keep an eye on how the whole field is emerging."

David Gerrold of Star Trek fame says, "**Creative Computing** with its unpretentious down-to-earth lucidity encourages the computer user to have fun. **Creative Computing** makes it possible for me to learn basic programming skills and use the computer better than any other source."

Order today at no risk. We'll give you a complete refund if you're not satisfied. But we're sure you'll want to join over 95,000 subscribers like Ann Lewin, Director of the Capital Children's Museum who says, "**Creative Computing** helps demystify the computer. It's articles are helpful, humorous and humane. The world needs **Creative Computing**."

Creative Computing, Morris Plains, NJ 07950
Toll-free **800-631-8112** (in NJ 201-540-0445)

Yes, enter my one-year (12 issues) trial subscription at no risk. Expires Dec '81

☐ $20 USA
☐ $29 Canada and Foreign Surface mail
☐ $50 Foreign Airmail
☐ Payment Enclosed ☐ Bill me
☐ American Express ☐ Visa ☐ MasterCard

Card No. Expires

Signature

Please print

Name

Address

City State/Province/Country Code

CCKH

creative computing

SAVE 33% off the cover price!

YES; I want to be assured of getting every issue of Creative Computing. Please enter my subscription for one year (12 issues), at the subscription price of $20. I save $10 off the regular newsstand price. (Canada and foreign surface $29, foreign air $50).

Name

Address

City

State Zip

☐ Bill me ☐ Payment enclosed
☐ Visa ☐ MasterCard ☐ American Express

Card number Expiration date

Signature

CCKH

FIRST CLASS

Permit No 738
Morristown NJ

BUSINESS REPLY MAIL

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

Postage will be paid by —

creative computing

P.O. Box 789-M
Morristown, New Jersey 07960

FIRST CLASS

Permit No 738
Morristown NJ

BUSINESS REPLY MAIL

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

Postage will be paid by —

creative computing

P.O. Box 789-M
Morristown, New Jersey 07960

Get 12 issues of Creative Computing for the price of 8.

Some things are still cheaper by the dozen.

When you subscribe to *Creative Computing*, you get 12 issues for just $20. The same 12 issues would cost you $30 at the newsstand.

Why not enjoy *Creative Computing* all year long and save $10 at the same time.

To subscribe, call toll-free from 9 AM to 6 PM 800-631-8112. In New Jersey, call 201-540-0445. Or write to Creative Computing, Morris Plains, NJ 07950. We accept Visa, MasterCard and American Express.

Creative Computing is the leading magazine of small computer applications and software. It has in-depth reviews of new systems, peripherals and software. Also articles for both beginners and experts; columns about popular computers, programming techniques and new products; and complete program listings for your computer.

Alvin Toffler says, "I read *Creative Computing* not only for information about how to make the most of my own equipment but to keep an eye on how the whole field is emerging."

Why not join over 90,000 subscribers and save money at the same time? If you're clever enough to order a dozen.



What's Who In All This

AFIPS American Federation of Information Processing Societies.
ARPA (now called DARPA) Advanced Research Projects Agency of the Department of Defense.
ARPA/IPT Information Processing Technology division of ARPA—original backers of computer graphics, time-sharing and packet nets.
Arpanet The defense-and-research packet net connecting numerous universities and defense locals.
BBN Bolt, Beranek and Newman, a frontier hotshot computer consulting and system design firm in Boston.
DARPA (New name of ARPA.) Defense Advanced Research Projects Agency.
DES Data Encryption Standard, supported by NBS and NSA.
ECOM or E-COM Electronic Computer-Originated Mail. Post Office trademark for their original proposal and that now under implementation. The migration of the rogue hyphen is inexplicable.
EMM Electronic Mail and Message System(s).
FAX Facsimile: pushing a picture through a wire with a converted analog signal.
FCC Federal Communications Commission.
IFIP International Federation for Information Processing. (A society of societies, like the U.S. AFIPS.)
ISO International Standards Organization.
MAC Project MAC (Man And Computer), pioneering time-sharing department at MIT (now become the Laboratory for Computer Science).
M&M (Electronic) Mail and Message: doesn't melt in your hand or disintegrate en route.
MIT Massachusetts Institute of Technology: a principal contributor to computer revolutions.
NBS National Bureau of Standards.
NSA National Security Agency, a huge government agency occupied with coding and decoding things. Their opposition to the RSA code has raised serious questions.
OSI Open Systems Interconnect, a proposed universal protocol framework.
PARC Xerox Palo Alto Research Center, a key hotshot location.
PO Post Office: the United States Postal Service.
PRC Postal Rate Commission, watchdog agency over the PO.
PS The United States Postal Service.
RSA Rivest-Shamir-Adelman code, supposedly unbreakable "trapdoor" code or "public-key cryptosystem." Two very long numbers mutually code and decode each other's results; if one is published, the other cannot be deduced in feasible time, and therefore remains secret. NSA opposition to RSA has been interpreted as sinister by some observers.
TELEX Brand name of a prevailing form of push-through digital printout message system.
TWX (TeletypeWriter eXchange.) Push-through digital printout message system operated by the phone company.
USC University of Southern California.
VAN Value-Added Network: digital service which somehow does more than time-share or transmit messages.
X.21 The circuit-switched data communication standard (where wires are reconnected for each transmission, as in the present-day phone system).
X.25 The packet data communication standard. □

Two Models of Mail





Classic Model of "Mail".

Sender (A) consigns letter to official postal receptacle (B) whence it is moved and processed by vehicles and sortings (C,D,E). Final delivery by letter carrier (F) goes all the way to addressee (J)'s receptacle (H). Post Office cares tenderly and bravely for letter all the way from B to H, symbolized by such perils as dog G. Any threats beyond H, such as interior dog I, are the problem of addressee J. Note the irony if DOG1=DOG2: up to the door he will be bested; beyond he may do what he will.



Naive Electronic Parallel, (omitting interactions, acknowledgements, queries, etc.)

Sender (A), sitting at screen (B), dispatches message from his computer (C). It enters electronic service (D), some collection of disks and gadgets and long wires and who knows what. The message is stored. Instantaneously or by and by it reaches the destined computer and screen (E,F) of addressee (G). But to whom does he complain if all he gets on screen F is garbage?

Is the thing still in D? What recourse has G if purveyors of service B contend that his computer E is a dog that has eaten his message? (Can G reply that the relationship of D to E is a virtual external DOG1 rather than a domestic internal DOG2?) □

EXCITING DISCOUNTS

DISK with CONTROLLER
NEW DOS 3.3 $529
without . . . $445
Nearly Everything
for Apple

$1045

apple II
16K computer

WE WILL
MEET OR BEAT
ANY ADVERTISED PRICES
ON MOST ITEMS IF MERCHANDISE
IN STOCK

APPLE II 48K
$1095

APPLE SOFTWARE

Alien Rain by Broderbund	22
Appleplot by Apple	59
Applewriter	65
Asteroid Field by Cavalier	19
CCA Data Mgmt	84
Cyber Strike by Nasir	29
Data Factory by Microlab	129
Desktop Plan II	169
DB Master II by Stoneware	199
DOS BOS by Beagle Bros	21
DOS Tool Kit	65
DOS 3.3 Upgrade Kit	49
Gorgon by Nasir	25
Fortran for Language System	159
PASCAL Language System	425
Peachtree Bus. Pkgs	CALL
Personal Filing System	84
Pool 1.5	29
Pulsar II by Nasir	24
Raster Blaster by Budgeco	24
Sargon II Chess	32
Space Eggs by Nasir	25
Space Invader/Cosmos Mission	19
Sub-Logic FS-1 Flight Sim	34
SuperText II by Muse	129
Ultima by Lord British	29
Visicalc II	159
Visitrend/Visiplot	219

LARGE SELECTION OF SOFTWARE IN STOCK!
CALL FOR FREE BROCHURE

ACCESSORIES FOR YOUR APPLE

Amdek 12" Color Monitor	349
Amdek 12" Green Screen	169
Amdek/Leedex 12" B/W	129
NEC 12" Green Screen	239
Sanyo 9" B/W	169
Dysan Disks (pkg 10)	50
Memorex Disks (pkg 10)	40
Verbatim Datalife Disks	35
A/D D/A by Mtn. Comp	319
Andromeda 16K RAMcard	179
Apple Game Paddles	25
Applesoft Firmware Card	149
CCS Interface Cards	CALL
Centronics Interface Card	179
CPS Multifunction by Mtn. Comp	239
Expansion Chassis by Mtn. Comp	555
Graphics Input Tablet by Apple	649
Hayes Micromodem II	299
Hayes Smartmodem	239
HiSpeed Serial Card by Apple	155
Integer Basic Firmware Card	149
Joystick for Apple	47
ROMPLUS by Mtn. Comp	135
SSM AIO Serial/Parallel Card	149
SuperTalker Speech Synthesizer	239
Versa-Writer Digitizer Drawing Sys	239
Videx Keyboard Enhancer	115
Videx Videoterm	319
Z-80 SOFTCARD CP/M by Microsoft	319
EPSON Printers	CALL
Paper Tiger 560 w/graphics	1495
Silentype w/interface	349
Starwriter Daisywheel by C. Itoh	1750

CALL 1-800-854-2833
PHONE ORDERS MON.-SAT. 8 TO 6 P.S.T.

master charge

TO ORDER Phone orders invited using Visa, Mastercard or bank wire transfers Visa and MC service charge of 2% Mail orders may send charge card number (include expiration date), cashiers check, money order, or personal check (allow 10 business days for personal or company checks to clear) Please add 3% ($5 00 minimum) for UPS shipping, handling, and insurance APO and FPO include 5% ($7 00 minimum) for postage Calif residents add 6% sales tax Please include phone number on all orders. FOREIGN ORDERS include 1% handling — shipped air FREIGHT COLLECT only Credit cards not accepted on foreign orders All equipment is in factory cartons with manufacturer warranty Opened products not returnable Restocking fee for returned merchandise Equipment subject to price change and availability Retail prices differ from mail order prices WE SHIP THE SAME DAY ON MOST ORDERS!

VISA

(714) 579-0330 • MAIL TO: 1251 BROADWAY, EL CAJON, CA 92021

AUTHORIZED APPLE SALES & SERVICE

COMPUTER SPECIALTIES

DIV. OF COMPUTER METRICS INC.

CIRCLE 145 ON READER SERVICE CARD

Why The Post Office Thinks "Electronic Mail" Is Like Paper Mail

When any person meets the computer, he sees it in terms of his life up to that point, as a simpleminded genie to take over the drudgery of what he already does.

Mathematicians and engineers saw in it a fast numerical device, generals saw a bombardier, businessmen saw a billing machine, I personally saw a writing and movie machine. Now the Post Office looks, and Lo! they think it is a letter-transmission device.

Nobody is wrong in these perceptions. But to flesh out any of these visions well and rightly, you have to know a great deal more about the computer's other possibilities than was obvious at first.

Misled By the Word

The phrase "Electronic Mail" is just as leading—and misleading—as so many other phrases and paradigms that have generated compiling computer visions and narrow-minded systems.

It is easy to see why the Post Office might get the idea that "electronic mail" is related to what they do already. Let us consider some of the superficial resemblances that might lead to this idea.

The word, to begin with. "Mail" sounds so familiar. But in some way this is falling prey to the sound of words, like wanting to put milk and sugar on a daytime serial.

"Packet" also sounds familiar. (Packets ordinarily go first class, right?) The terminology of the electronic packeters, too, sounds awfully like mail. A digital packet has private contents, an "envelope" of bytes, which includes the "address" and transport billing information, which is rather like a "stamp." But that's obviously just a superficial resemblance of the transport quantum.

(Amusing, too, and tying in with this simplified view, was IBM's presentation of the Math Conference of "output devices for electronic mail" as being *printers*, not screens; the *paper* is somehow thought to be fundamental. This despite the fact that Taylor or PARC says only 1% of messages on their system ever get printed.)

STORAGE, SPARKS AND "MAIL"

But essentially the "mail" concept of old is like only certain kinds of electronic messages: those which are not interacting with "agents," or part of highly interactive sessions; whose storage is deemed to be temporary; and which wait for their recipients, who are human beings, to read them, reply at leisure, and file them *elsewhere*.

It is impossible at this time to guess even vaguely what proportion of digital traffic will represent this old-fashioned kind of "mail." □

A Misleading Model

In the model repeatedly referred to by the Post Office representatives at the M&M conference, there are three "generations" of electronic mail. To their way of thinking, there is a natural progression from paper mail to a destined, but similar, electronic future. Let's look at this.

The idea of the telegram—more recently the "mailgram"—is indeed a form of electronic mail, well known to everyone: paper arrives at your office or front door. People who have seen conventional letters sent electronically may think that's it, that "electronic mail" means simply some shortening of the path.

Now it is certainly the case that the forthcoming ECOM system, discussed in this article, is mail in the ordinary sense; it has to be. It comes out on paper and is walked to your door. It does not come out on a terminal, it does not trigger electronic events. But what is misleading is the *extension* of that idea, the notion of Paper Destiny, that that's all there is. And that misleading extension is their model of electronic mail "generations."

The Generations

Generation One is called "paper in, paper out." This involves somehow getting a message into a computer, transmitting it electronically, printing it out, and delivering it on foot.

Hypothetical Generation I: "PAPER IN, PAPER OUT"

this is wholly impractical, since digital scanning and conversion does not work well in general. This brings us directly to Generation Two. "Electronic in, paper out," as in forthcoming ECOM.



Hypothetical Generation II: "ELECTRONIC IN, PAPER OUT"

WE WILL NOT BE UNDERSOLD

DISK DRIVES

FOR TRS-80® Model I

CCI-100	5¼", 40 Track (102K)	$299

ADD-ON DRIVES FOR ZENITH Z-89

CCI-189	5¼", 40 Track (102K)	$394
Z-87	Dual 5¼" system	$995

External card edge and power supply included. 90 day warranty/one year on power supply.

RAW DRIVES

5¼" TEAC or TANDON	$ CALL
8" SHUGART 801R	$ CALL

DISKETTES — Box of 10

5¼"	Maxell	$40	BASF/Verbatim	$26.95
8"	Maxell	$45	BASF/Verbatim	$36.00

PLASTIC FILE BOX–Holds 50 5¼" diskettes		$19.00
PLASTIC LIBRARY CASE	5¼" $3.00 8"	$ 4.00
HEAD CLEANING DISKETTE		$25.00
FLOPPY SAVER	$10.95 RINGS	$ 6.95

16K RAM KITS

2 for $37 **$19**

200ns for TRS-80®Apple II, (specify): Jumpers $2.50

SYSTEM SPECIAL

Apple II Plus 48K w/drive and controller. Epson MX-80 printer and interface. SUP-R Mod RF Modulator: List $2965 You Pay $2299

COMPUTERS/TERMINALS

ARCHIVES	64K, 2-Drives, 77 Track				$CALL
ALTOS	ACS8000 Series				$ CALL
ZENITH	48K, all-in-one computer				$2200
ZENITH	Z-19				$ 725
TELEVIDEO	910 $559	920C	$ 729	950	$1039
IBM	3101 Display Terminal				$1189
ATARI	400 $ 359			800	$ 795
MATTEL	INTELLIVISION				$ 259
APPLE PERIPHERALS					$ CALL

S-100 CALIFORNIA COMPUTER SYSTEMS

MAINFRAME	Model 2200A	$349
Z80 CPU	Model 2810	$259
MOTHER BOARD	Model 2501	$106
16K STATIC RAM, 200ns	Model 2116C	$309
32K STATIC RAM, 200ns	Model 2032C	$619
64K DYNAMIC RAM	Model 2065C	$580
FLOPPY DISC CONTROLLER	Model 2422A	$345
EXTENDER BOARD	Model 2520K	$ 52
2P + 2S I/O	Model 2718A	$309

PRINTERS

NEC SPINWRITER
Letter Quality High Speed Printer

R.O.	$2395
R.O. with tractor feed	$2555
KSR with tractor feed	$2795

NEC SPINWRITER	3500 Series				$CALL
EPSON	MX-70	MX-80	MX-80FT	MX100	$CALL
PAPER TIGER					
IDS 445	Graphics & 2K buffer				$ 695
IDS 460	Graphics & 2k buffer				$ 799
IDS 560	Graphics				$ 999
ANADEX	DP-8000 $849			DP-9500/01	$1295
OKIDATA					
Microline 80	Friction & pin feed				$CALL
Microline 80	Friction, and pin & tractor feed				$CALL
Microline 82	Friction & pin feed				$CALL
Microline 83	120 cps, uses up to 15" paper				$CALL
CENTRONICS	739, new model with graphics				$ 739
C. ITOH					
Starwriter I	25 cps, parallel interface				$1449
Starwriter I	25 cps, serial interface				$1529
Starwriter II	45 cps, parallel interface				$1829
Starwriter II	45 cps, serial interface				$1949

PRINTER SPECIAL

SEIKOSHA GP-80M List $399 You Pay $319

MONITORS

BELL & HOWELL	9" B & W BHD911			$175
LEEDEX	12" B & W	$129	12" Green Screen	$159
	13" Color	$329		
SANYO	9" B & W	$149	12" Green Screen	$238
	12" B & W	$219	13" Color	$406
ZENITH	13" Color	$349	12" Green Screen	$129

TELECOMMUNICATIONS

LIVERMORE STAR MODEM 2-year guarantee	$125
UNIVERSAL DATA SYSTEMS UDS-103	$179
D-CAT HARD WIRED DIRECT MODEM	$189
AUTO-CAT Auto Answer, Direct Connect Modem	$249
APPLE-CAT II	$349
D.C. HAYES MICRO-MODEM	$295
D.C. HAYES SMART-MODEM	$235
CCI Telnet Communications Package	$135

APPLE ACCESSORIES AND SOFTWARE

VISICALC $155.00		DB MASTER	$159.00
CPS MULTIFUNCTION CARD			$189.00
Z-80 SOFTCARD			$259.00
VIDEX BOARD			$255.00
KEYBOARD ENHANCER			$110.00
16K CARD			$159.00
APPLE JOYSTICK			$ 49.00
SUP-R MOD			$ 25.00
CCS CARDS			$ CALL
GALAXIAN			$ 22.95
SPACE ALBUM			$ 35.00
ASTEROIDS			$ 17.95
FLIGHT SIMULATOR			$ 29.00
WIZARD & PRINCESS			$ 28.00
SARGON 2			$ 29.00
MYSTERY HOUSE $ 24.00		HI-RES FOOTBALL	$ 35.00

For fast delivery, send certified checks, money orders or call to arrange direct bank wire transfers. Personal or company checks require two to three weeks to clear. All prices are **mail order only** and are subject to change without notice. **Call for shipping charges.**

DEALER (NATIONAL/INTERNATIONAL) INQUIRIES INVITED **Send for FREE Catalogue**

The CPU SHOP

TO ORDER CALL TOLL FREE 1-800-343-6522

TWX: 710-348-1796 Massachusetts Residents call 617/242-3361

5 Dexter Row, Dept. CC11M
Charlestown, Massachusetts 02129
Hours 10AM-6PM (EST) Mon.-Fri. (Sat. till 5)

Technical Information call 617/242-3361
Massachusetts Residents add 5% Sales Tax
Tandy Corporation Trademark® Digital Research

master charge THE INTERBANK CARD

VISA

CIRCLE 171 ON READER SERVICE CARD

Misleading Model, continued...

By seeming logical progression, the supposed next step, "Generation Three," drops the paper and is "electronic in, electronic out."



Hypothetical Generation III:
"ELECTRONIC IN, ELECTRONIC OUT"

It is this supposed "stage" to which Postal Service spokesmen have claimed the right, that the Postal Rate Commission has defeated, and that the Carter administration forbade by explicit executive order.

But is it the next stage at all? Just because the preceding stages involved, of necessity, things that could be printed on paper, this next "generation" allows things that can't be usefully printed—such as animations—and can at once go beyond the transmission of letter-like alphabetical chunks to the shower-of-sparks model presented by the magicians. As Bob Taylor said, "If you think about these as systems for moving strings of characters, you miss the point of their power."

"Third Generation" Really Means Storage

Here is a real irony: the Post Office's "Generations" are based on the push-through idea, but actually what they call the Third Generation *must involve external storage*. A postman can always get to a mail slot in your door, even if it means fighting rain, sleet or gloom of night, or even if it means saying "Excuse me" to a crowd of people in the way. If the lines to your computer are busy, however, there is no way that message can be pushed through. Thus there must be provisions to store or buffer it externally until ready.

Moreover, in the event of a garbled message reaching your computer, there must be provision for re-verification. It is all very well to say, "Once the letter is pushed through your mail slot, and a dog chews it, it's your problem," but a letter that has been chewed by your dog, or accidentally trampled, spilled on, or perhaps inhaled by your vacuum cleaner, is nevertheless usually identifiable and readable, even if too icky to file. But bit-hash is another problem. If supposed messages are sitting in your computer when you get home and they are wholly meaningless and unidentifiable, there must be some way to ask your carrier for a replay.

But if you call in to that carrier's computer, how does it know you are not an imposter spying on you? What procedures give you a retry?

Well, these problems are essentially worked out on such systems as Arpanet and Tyme-Share. You call with your password and "open your mailbox," meaning that the disk storage of your message is unveiled to you; material is discarded when you give permission.

Well and good in a private-enterprise or research situation. But if a government supplier takes over the entire act, all these arrangements become more portentous and perhaps more sinister. You become not just a customer, but a *captive* customer. When dissatisfied under private enterprise, you have the option of going to another vendor; if it's the government you have the option of filing complaints and briefs, or not sending messages at all.

But, of course, most sinister is the notion that *your communications are being stored by a government agency*, even if it is the Good Ol' Post Office.

The Second Generation maintains a tie to the first. The "Third Generation," in its full realization, does not. (We might just as well call an automobile a Second Generation Horse-and-Buggy, and the comparison is pretty clear point by point. But when we get to calling an airplane a third generation Horse-and Buggy, we're in trouble. And I think it's the same for this model of generations.

The very term "mail diversion," used in some of the estimates of future electronic messaging, confirms this: if letters go down in quantity and digital transmissions go up, they call that "mail diversion." But is a phone call a "diverted letter?" No, it's *something else*.

The problem is in the frame of mind. The Post Office people seem to believe that fulltext transmission is the only model. To go beyond that, and recognize the panorama of remarkable interactive possibilities, requires a broad-scale knowledge of computers and all the things that they can do.

The remark of consultant Joyce, that "You're not going to see books and newspapers transmitted in the next twenty years," epitomizes this narrow focus. Of course, a book or newspaper is not sent electronically in full all at once. What happens is an interchange session with the *stored* document. And that is something very different.

Paradigm Shift

The original conceptual model was perhaps best stated by Herbert Simon in *The Shape of Automation*. In a nutshell Simon says that automation changes the shape of an activity so much as to make it a complete surprise. For example: if we talk about automating garbage *disposal*, visions might come to mind of prowling robot garbage trucks emptying the cans—but not of in-sink Disposalls, which involve changes all across the paradigm.

Whether a thing *can* be printed on paper may be the best dividing line between what usefully constitutes "mail" and what doesn't anymore. Text or bit-map pictures could be paper mail—but it is senseless to print executable programs or digitally explorable data bases and graphic structures. Fishlines to databases and text repositories, cascading interactive events, have nothing to do with mail as we know it. And these will be our next generation of library and communication. □

Mail Chauvinism, continued...

Other consultants foresaw twelve and a half billion pieces "diverted" in 1990, twenty-six billion in 2000.

So whatever it is, it's important. And it is not surprising that the postal workers are agitating for a piece of this action, which Johnson called "turfmanship," even though the General Accounting Office has estimated that "any loss" to the P.O. could be covered by attrition.

HUMPH: A Concluding Editorial Opinion

Some of the finest minds of our time are trying to build a new world of interactive communication and instantaneous availability of information, pictures, ideas, models, worlds.

Meanwhile the Post Office has come to assume, in some innocence, that electronic message services are directly related to, and in competition with, what they already do—the "same thing" as letters on paper.

Postal workers are agitating for a piece of the action.

This "turfmanship," as Lloyd Johnson called it, is strongly reminiscent of the typesetting-union problems faced by newspapers in the sixties, when the typesetters imagined that "new jobs" would be created in electronic typesetting to which they had a natural right—even though the *actual* new jobs involved computer programming, and were being carried out by vendors elsewhere. What is going to happen is *something different*.

There still exists the faint possibility that the Post Office might actually force a monopoly of its services in these new areas, based by some miraculous extension of law on its existing delivery monopoly. This possibility is slight, because compe-

CONTINUED ON PG. 156

DISCOUNT DATA PRODUCTS

presents

APPLE SOFTWARE

***** GAMES *** UTILITIES *** BUSINESS *****

Software at Affordable Prices for the budget minded individual

30% OFF

SPECIAL ITEMS DISCOUNT

APPLE	LIST PRICE	OUR PRICE
ADVENTURE INTERNATIONAL		
Adventure Hint Book	7.95	6.35
Adventures #1, #2, #3	D 39.95	27.95 ‡
Adventures #4 #5, #6	D 39.95	27.95 ‡
Adventures #7, #8, #9	D 39.95	27.95 ‡
Adventure #10 Savage Island	D 20.95	18.75
Planetoids	D 19.95	15.95
Poker Tournament	D 19.95	15.95
Tank Command	D 14.95	11.95
Adventures 0 - 10 each	T 19.95	15.95
Asteroids/Planetoids	T 14.95	11.95
ARISCI		
Magic Window	D 99.95	79.95
Magic Master	D 69.96	55.95
AUTOMATED SIMULATIONS		
Introductory 3 Pack (Rescue, Morloc's, and Datestones)	D 49.95	39.95
Temple of Apshai	D 39.95	31.95
Halllins Warrior	D 39.95	27.95‡
Star Warrior	D 39.95	31.95
Crush, Crumble & Crunch	D 29.95	23.95
Dragon's Eye	D 24.95	19.95
Rescue at Rigel	D 29.95	20.95‡
Morloc's Tower	D 19.95	15.95
Datestones of Ryn	D 19.95	15.95
Tuss Morn Orrtback	D 29.95	23.95
AVALON HILL GAME COMPANY		
Empire Overmind	D 35.00	27.95
Myr Leag Baseball	D 30.00	23.95
Tanktics	D 29.00	22.95
Myr Leag Baseball	T 25.00	19.95
B-1 Nuclear Bomber	T 15.00	11.95
Midway Campaign	T 15.00	11.95
Nukewar	T 15.00	11.95
Conflict 2500	T 15.00	11.95
Planet Miners	T 15.00	11.95
Computer Acquire	T 20.00	15.95
Lords of Karma	T 20.00	15.95
Empire Overmind	T 30.00	23.95
Tanktics	T 24.00	19.95
BRODERBUND SOFTWARE		
Galactic Empire	D 24.95	19.95
Galactic Trader	D 24.95	19.95
Galactic Revolution	D 24.95	19.95
Snoggle	D 24.95	19.95
Alien Typhoon	D 24.95	19.95
Tawala's Last Redoubt	D 29.95	23.95
Alien Rain	D 24.95	19.95
Demon Derby	D 24.95	19.95
Golden Mountain	D 19.95	15.95
Payroll	D395.00	319.95
Space Warrior	D 24.95	19.95
General Ledger	D395.00	319.95
Apple Panic	D 29.95	23.95
BUDGECO		
Raster Blaster	D 29.95	23.95
CONTINENTAL SOFTWARE ★ CAVALIER		
Hyperspace Wars	D 29.95	23.95
L.A. Land Monopoly	D 29.95	23.95
Home Money Minder	D 34.95	27.95
3-D Skiing	D 24.95	19.95
Torpedo Terror	D 24.95	19.95
The Home Accountant	D 74.95	59.95
The Guardian	D 29.95	23.95
CPA General Ledger	D250.00	199.95
CPA Acc Rec	D250.00	199.95
CPA Acc Pay	D250.00	199.95
CPA Payroll	D250.00	199.95
CPA Prop Mgt	D175.00	139.95

	LIST PRICE	OUR PRICE
DAKIN 5		
3.3 Programming Aids	D 90.00	71.95
DATA SOFT		
Micro Painter	D 34.95	24.50 ‡
Mychess W/Z 80	D 34.95	27.95
Micro Painter alb 1	D 19.95	15.95
Micro Painter alb 2	D 19.95	15.95
Chart Wizard	D 99.95	79.95
Lisp inter	D124.95	99.95
★ DELTA SOFTWARE ★ DENVER SOFTWARE		
HAYDEN SOFTWARE		
Sargon II	D 34.95	24.50 ‡
Reversal	D 34.95	27.95
Data-Graph	D 49.95	39.95
Histo-Graph	D 29.95	23.95
Assembly Lang Dev	D 39.95	31.95
Applesoft Compilar	D200.00	159.95
HIGHLANDS COMPUTING		
Crae 2.0	D 24.95	19.95
Mcat 2.0	D 19.95	15.95
Oldars Revenge Wiz	D 19.95	15.95
Tarturan Wizard II	D 24.95	19.95
Creature Venture	D 24.95	19.95
INNOVATIVE DESIGN SOFTWARE		
Pool 1.5	D 34.95	27.95
MICROSOFT		
Typing Tutor	D 19.95	15.95
Olympic Decathlon	D 29.95	23.95
Adventure	D 29.95	23.95
FORTRAN-80	D195.00	154.95
A.L.D.S.	D125.00	99.95
WordStar	D315.00	249.95
★ MICRO SOFT ★ MICRO PRODUCTS		
★ MUSE		
ON-LINE SYSTEMS		
Mission Asteroid	D 19.95	15.95
Mystery House	D 24.95	19.95
Wiz & Princess	D 32.95	25.95
Cranston Manor	D 34.95	27.95
Football	D 39.95	27.95 ‡
Trilogy of Games	D 24.95	19.95
Cribbage	D 24.95	19.95
Missile Defense	D 29.95	20.95 ‡
Soccer	D 29.95	23.95
Paddle Graphics	D 39.95	31.95
Sabotage	D 24.95	19.95
Superscribe Word Pr	D 89.95	71.95
Gobbler	D 24.95	19.95
Expediter II		
AppleSft Compiler	D 99.95	79.95
Dev. Sys	D 79.95	64.95
Speed-asm	D 39.95	31.95
PERSONAL SOFTWARE		
Checker King	D 24.95	20.95
Gammon Gambler	D 24.95	20.95
Monty Plays Monopoly	D 34.95	28.95
Zork	D 39.95	32.95
Microchess	D 24.95	20.95
Desktop Plan II	D199.95	159.95
Bridge Partner	D 24.95	20.95
Visiplot	D179.95	148.00
Visicalc 3.3	D199.95	159.95
Visitrend	D259.95	207.95
Visidex	D199.95	159.95
Visiterm	D149.95	119.95
CCA Data Mgmt Sys	D 99.95	85.95

	LIST PRICE	OUR PRICE
SENSIBLE SOFTWARE		
Applesoft-Plus Str Basic	D 25.00	19.95
Applesoft Optimizer	D 20.00	15.95
DOS Plus	D 25.00	19.95
Disk Organizer	D 25.00	19.95
Disk Recovery	D 20.00	23.95
MultiDisk Ctlog III	D 25.00	19.95
Super Disk Copy III	D 30.00	23.95
SENTIENT SOFTWARE		
00-Topos	D 32.95	25.95
SIERRA SOFTWARE		
Alien Lander	D 24.95	19.95
Retro-Ball	D 29.95	19.95
Space Adventure	D 29.95	19.95
SIRIUS SOFTWARE		
E-Z Draw 3.0	D 49.95	34.95‡
Phantoms 5	D 29.95	23.95
Space Eggs	D 29.95	23.95
Pulsar II	D 29.95	20.95 ‡
Autobahn	D 29.95	23.95
Orbitron	D 29.95	23.95
Gamma Goblins	D 29.95	23.95
Gorgon	D 39.95	31.95
Snaakars	D 29.95	23.95
Epoch	D 34.95	27.95
★ SIR-TECH SOFTWARE		**★ SOFTAPE**
SOFTWARE PUBLISHING CO.		
PFS Per Filing Sys	D 95.00	75.95
PFS Report	D 95.00	75.95
SOUTHWESTERN DATA SYSTEMS		
Apple Doc 3.3	D 44.95	35.96
The Correspondent	D 59.95	47.95
Ace 3.3	D 29.95	23.95
Ascii Express 3.3	D 64.95	51.95
Z-Term	D 99.95	79.95
Online	D 89.95	71.95
Speed Star	D135.00	108.95
STONEWARE		
DB Master	D225.00	179.95
STRATEGIC SIMULATIONS		
Computer Bismark	D 59.95	47.95
Computer Quarterback	D 39.95	31.95
Computer Conflict	D 39.95	31.95
Topedo Fire	D 59.95	41.95‡
Cartels & Cutthroats	D 39.95	31.95
Computer Baseball	D 39.95	31.95
The Warp Factor	D 39.95	31.95
Shattered Alliance	D 59.95	41.95‡
SYNERGISTIC SOFTWARE		
DoomCavern/Sorcerers	D 20.00	15.95
Higher Graphics II	D 35.00	24.50 ‡
Higher Text	D 40.00	31.95
Odyssey	D 30.00	23.95
Wilderness/Dungeon	D 32.50	27.95
Modifiable Data Base	D 79.50	54.95
Modifiable D B II	D150.00	119.95
UNITED SOFTWARE OF AMERICA		
Appleworld	D 59.95	47.95
Super Kram	D175.00	139.95
3-D Supergraphics	D 39.95	31.95
Request	D225.00	179.95
Thinker	D495.00	395.95
Space Raiders	D 29.95	23.95
VERSA COMPUTING		
Versawriter	289.00	239.95
Versawriter Expansion Pak I	D 39.95	31.95

★ SEND FOR OUR PRICE SHEET FOR SPECIFIC PROGRAMS AND PRICES

PLEASE CHECK FOR SYSTEM REQUIREMENTS BEFORE ORDERING
INCLUDE PUBLISHER AND PRODUCT NAME
FOREIGN INQUIRIES INVITED — ADD 10% SHIPPING

All Orders Prepaid by Personal Check Money Order Cashier Check
For Faster Delivery Service COD Cash Only/Master Charge Visa
Mastercharge — Visa add 3% and include expiration date on card
Please Allow Sufficient Time for Checks to Clear
Please Add $2.50 for Shipping

California Residents Add 6% Sales Tax
Prices Valid Through This Month's Issue
Prices Subject to Change Without Notice
Please Specify Tape or Disk

★TRS-80 ★ATARI ★COMMODORE

DIRECT ORDER INQUIRIES TO:
DISCOUNT DATA PRODUCTS
P.O. BOX 19674-K
SAN DIEGO, CA 92119
PHONE 714-287-0190

CIRCLE 158 ON READER SERVICE CARD

Five Snark Paradigms

At least five models of "electronic mail" can be discerned. I believe these constitute a more comprehensive view than those elsewhere called "Generation 1, 2 and 3." The real and overriding question is, what is the conceptual structure of this thing? And what are its boundaries?

1. *Push-through*. (Also called "forced delivery.") Some people seem to think electronic mail is a sort of telephonic scribe: from some kind of a sending unit, you dial up your addressee's receiving unit. If it is functioning and not busy, you push through a series of signals which the receiving unit records, usually on paper.

Several such systems already exist. One of these is facsimile (or Fax), the sending of pictures down a wire from one unit to another. To send a letter, you transmit *a picture of the letter*, an incredibly inefficient method which may take a minute or more.

Push-through alphanumeric systems are also popular: the TWX and Telex networks, widely used by businesses, effectively permit you, the sender, to type on an addressee's teletypewriter. As with Fax, the sender effectively seizes the recipient's machine during the time of transmission.

The question arises, however, as to whether such systems are "mail." They only permit as much material to be transmitted as there is time in the day, and they effectively force entry into a continuing scroll of material. One attendee, Einar Stefferud, puts it this way: "They aren't mail, they are forced-delivery systems. True mail requires a *mailbox*, a place the addressee can open at his leisure."

2. *Point-to-point*. These systems assume a sender and a receiver, and have a general resemblance to "mail" in its usual form. The transmission occurs in just one direction. A reply, if any, is expected in the *other* direction, but not as part of the same event or session.

According to this view, electronic mail is really just a simple transmutation of ordinary paper mail, going from one "drop" (where the sender puts it) to the addressee's mail drop (where a postman—or something—puts it).

Because much electronic mail seems to take this form, some people, including the Post Office, have been led to think that that's what electronic mail "is." Storage, buffering, acknowledgements, complex sessions and chain reactions are not taken into account.

3. *Repository Systems*. Rather than sending a message directly from A to B, it may be better to leave it on some other system, C, where it may be left until needed—or archived indefinitely.

The third-party system, C, may be a small file-server machine in an office, or such a large-scale service as Telemail, which stores mail on request as well as transmitting it. (This is analogous to both secretarial services and telephone-answering services.) Actually *most* "electronic mail" uses storage outside the recipient's own machine.

One of the most obvious reasons for doing this is safety. As Cunningham said, "Once your letter is pushed through a mail slot, and a dog chews it, it's your problem." Rather than having to worry about, or pay for, super-reliable equipment that won't lose your communications, it makes sense to pay a third party who's got the reliable equipment—possibly even the carrier—just to hold onto the message for you.

But there are other kinds of externalized messages. Links or mentions citing external files for optional pullout (as on the proposed Xanadu network) may also prove to be of great practicality: a letter no longer says "According to your communication of the 27th," but actually hooks to that communication so the reader may see at once what is being mentioned. "With reference to your letter on the 27th" becomes an actual link to the letter of the 27th. "With respect to our order number 3794" becomes, "with respect to" and then a link to the actual order itself, stored. These links cannot be usefully printed out; a fishline is for pulling, it is not a line on paper.

Expanding this in a slightly different way, a message may be built out of citations. It may cite and summon materials out of some data bank, the assemblage of these materials being the *real* messsage.

4. *Interactive sessions*. In this approach, the sending and receiving units remain coupled during an interaction, and indeed other units may join in the activity, in a "shower of sparks" responseplex. (See "The Magicians," described elsewhere.)

But here tradition is lost and we are in a new universe. In such a multifunction interchange of queries, requests, notifications, acknowledgements, links, contributions and invocations, among agents, data bases, personal files, programs, graphical displays, executable programs and subprograms, cascades of information chunks caroming in chain reaction, dancing demons and sprites, *there is no boundary between "mail" and active programs.*

"Shower of Sparks"—Sophisticated Multi-Agent Session (Licklider, Dertouzos)



5. *High-Interchange with External Storage*. Combining types 3 and 4 gives us our final type, that which uses external files plus multi-agent interchanges on the Licklider model.

This paradigm is perhaps the most exciting to computer freaks, the most powerful for a variety of business functions, and the most unimaginably remote from anything like conventional message services. But it is toward this that we are going, I believe. Data bases and external archiving will become inextricable; and they will grow together into a generalized form involving multi-computer, multi-agent interchange. Welcome to the funhouse. □

Actual Mechanism of "Electronic Mail"



THE GREAT SIMPLIFIER!



The only book that simplifies the BASIC language by explaining its many dialects is now even better! We've added 240 BASIC words from the world's latest computers, for a new total of nearly 500 words detailed in a concise easy-to-read manner.

The 480-page **2nd Edition BASIC Handbook** tells you everything you need to know about today's BASIC language. It explains *all* significant Statements, Functions, Operators and Commands, so you can put them to work instantly!

If there's an alternate way to write a program using other BASIC words, the **Handbook** shows you how. If a program needs a Function your computer doesn't have, the **Handbook** generally has a subroutine which does the same thing. And it's all alphabetized and indexed for fast access!

The big *new* **2nd Edition** helps you convert those "strange" programs found in magazines and professional journals to RUN on your computer. Extra sections describe many specialty BASICs, including Atari, Sinclair, Tektronix, TRS/Color, plus Disk BASIC.

For students, businessmen, hobbyists, and pros — anyone who works with BASIC, the updated **Handbook** is indispensable. Order your **Second Edition** today! It's the missing link between you and more computer power!

Yes! Give Me More BASIC Power!

Please send _____ copies of **THE BASIC HANDBOOK 2nd Edition.**

☐ My check for $19.95 each and $1.65 P&H is enclosed. (Californians add 6% tax.)

☐ Charge it to my MasterCard or Visa (circle one).
Acct. No. _____ Exp. Date _____

Name _____

Address _____

City _____ State _____ Zip _____

Signature _____

Mail to: **CompuSoft® Publishing**, 1050-E Pioneer Way, Dept. B
El Cajon, CA 92020

Or Call: **(714) 588-0996** to order now!

CIRCLE 286 ON READER SERVICE CARD

THE ORIGINAL MAGAZINE FOR OWNERS OF THE TRS-80™* MICROCOMPUTER

* TRS-80™ IS A TRADEMARK OF TANDY CORP

SOFTWARE FOR TRS-80™ OWNERS

H & E COMPUTRONICS INC.

MONTHLY NEWSMAGAZINE FOR TRS-80™ OWNERS

MONTHLY NEWSMAGAZINE
Practical Support For Model I, II & III

- PRACTICAL APPLICATIONS
- BUSINESS
- GAMBLING • GAMES
- EDUCATION
- PERSONAL FINANCE
- BEGINNER'S CORNER
- NEW PRODUCTS
- SOFTWARE EXCHANGE
- MARKET PLACE
- QUESTIONS AND ANSWERS
- PROGRAM PRINTOUTS

. . . . AND MORE

ALL PRICES AND SPECIFICATIONS SUBJECT TO CHANGE

NOW IN OUR 4th YEAR

PROGRAMS AND ARTICLES PUBLISHED IN RECENT ISSUES INCLUDE THE FOLLOWING:

- FINCALC - A COMPLETE FINANCIAL APPLICATIONS PACKAGE
- INFORMATION SYSTEM REVIEW
- STATISTICAL COMBINATIONS
- PASCAL'S TRIANGLE
- ASSEMBLY LANGUAGE FOR BEGINNERS
- DISK FILES
- MOD III REVIEW
- KEYBOARD THUNDER AND LIGHTING EXPLAINED
- DOS COMMANDS IN LEVEL II
- PROBABILITY CURVE GENERATOR
- CALCULATOR SIMULATIONS
- THE MEGABYTE GAP*
- STOCKS AND BONDS
- BUDGET ANALYSIS (FOR BUSINESS AND HOME)
- NEWDOS 80 REVIEW
- DUTCHING - THE HORSE SYSTEM THAT CAN'T LOSE
- A SIMULATED GOLF GAME
- CONTINUOUS FORM SOURCES
- TAX SAVER REVIEW

AND MORE

FREE* WITH YOUR SUBSCRIPTION OR RENEWAL

FINCALC

A Complete Financial Analysis Package Used To Calculate Markup, Margin, Annuities, Compound Interest, Nominal And Effective Rates, Sinking Funds, Mortgage Calculations, Future Value, Savings and Insurance, Percentage Difference Between Two Numbers, Amortization Schedule and More . . . . . .

SEND FOR OUR NEW 64 PAGE SOFTWARE CATALOG (INCLUDING LISTINGS OF HUNDREDS OF TRS-80™ PROGRAMS AVAILABLE ON CASSETTE AND DISKETTE) $2.00 OR **FREE** WITH EACH SUBSCRIPTIONS OR SAMPLE ISSUE

* All programs are supplied on cassette (add $3 for Diskette Version - add $5 for modified Mod-II Version).

COMPUTRONICS
MATHEMATICAL APPLICATIONS SERVICE

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

ONE YEAR SUBSCRIPTION $24 . . . .
TWO YEAR SUBSCRIPTION $48 . . . . . .
SAMPLE OF LATEST ISSUE $ 1 . . . . . .
START MY SUBSCRIPTION WITH ISSUE . . . . . .
(#1 July 1978 • #12 June 1979 • #24 July 1980 • #30 January 1981)
NEW SUBSCRIPTION . . . . . RENEWAL . . . . . .

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

NEW!!!
MOD-II NEWSLETTER
$18/year (or 12 issues)

VISA

24 HOUR ORDER LINE
(914) 425-1535

CREDIT CARD NUMBER _____ EXP. DATE _____
SIGNATURE _____ NAME _____
ADDRESS _____ CITY _____ STATE _____ ZIP _____

*** ADD $12 YEAR (CANADA, MEXICO) - ADD $24 YEAR AIR MAIL - OUTSIDE OF U.S.A., CANADA & MEXICO ***

CIRCLE 138 ON READER SERVICE CARD

THE COMPUTRONICS INC.

• EVERYTHING FOR YOUR TRS-80* • ATARI* • APPLE* • PET* •

*TRS-80 is a trademark of the Radio Shack Division of Tandy Corp. - *ATARI is a trademark of Atari Inc. - *Apple is a trademark of Apple Corp. - *Pet is a trademark of Commodore

NEW

BUSINESS PAC 100

100 Ready-To-Run Business Programs

★ All orders processed within 24-Hours
★ 30-Day money back guarantee on all Software (less a $3 penalty for handling)

(ON CASSETTE OR DISKETTE).....Includes 110 Page Users Manual.....5 Cassettes (Or Diskettes)
Inventory Control.....Payroll.....Bookkeeping System.....Stock Calculations.....
Checkbook Maintenance.....Accounts Receivable.....Accounts Payable.....

BUSINESS 100 PROGRAM LIST

1	RULE78	Interest Apportionment by Rule of the 78's
2	ANNUI	Annuity computation program
3	DATE	Time between dates
4	DAYYEAR	Day of year a particular date falls on
5	LEASEINT	Interest rate on lease
6	BREAKEVN	Breakeven analysis
7	DEPRSL	Straighttime depreciation
8	DEPRSY	Sum of the digits depreciation
9	DEPRDB	Declining balance depreciation
10	DEPRDDB	Double declining balance depreciation
11	TAXDEP	Cash flow vs. depreciation tables
12	CHECK2	Prints NEBS checks along with daily register
13	CHECKBK1	Checkbook maintenance program
14	MORTGAGE/A	Mortgage amortization table
15	MULTMON	Computes time needed for money to double, triple, etc.
16	SALVAGE	Determines salvage value of an investment
17	RRVARIN	Rate of return on investment with variable inflows
18	RRCONST	Rate of return on investment with constant inflows
19	EFFECT	Effective interest rate of a loan
20	FVAL	Future value of an investment (compound interest)
21	PVAL	Present value of a future amount
22	LOANPAY	Amount of payment on a loan
23	REQWTH	Equal withdrawals from investment to leave 0 over
24	SIMPDISK	Simple discount analysis
25	DATEVAL	Equivalent & nonequivalent dated values for oblig.
26	ANNUDEF	Present value of deferred annuities
27	MARKUP	% Markup analysis for items
28	SINKFUND	Sinking fund amortization program
29	BONDVAL	Value of a bond
30	DEPLETE	Depletion analysis
31	BLACKSH	Black Scholes options analysis
32	STOCVAL1	Expected return on stock via discounts dividends
33	WARVAL	Value of a warrant
34	BONDVAL2	Value of a bond
35	EPSEST	Estimate of future earnings per share for company
36	BETAALPH	Computes alpha and beta variables for stock
37	SHARPE1	Portfolio selection model-i.e. what stocks to hold
38	OPTWRITE	Option writing computations
39	RTVAL	Value of a right
40	EXPVAL	Expected value analysis
41	BAYES	Bayesian decisions
42	VALPRINF	Value of perfect information
43	VALADINF	Value of additional information
44	UTILITY	Derives utility function
45	SIMPLEX	Linear programming solution by simplex method
46	TRANS	Transportation method for linear programming
47	EOQ	Economic order quantity inventory model
48	QUEUE1	Single server queueing (waiting line) model
49	CVP	Cost-volume-profit analysis
50	CONDPROF	Conditional profit tables
51	OPTLOSS	Opportunity loss tables
52	FQUOQ	Fixed quantity economic order quantity model

NAME	DESCRIPTION
53	FQEOWSH	As above but with shortages permitted
54	FQEOQPB	As above but with quantity price breaks
55	QUEUECB	Cost-benefit waiting line analysis
56	NCFANAL	Net cash-flow analysis for simple investment
57	PROFINDI	Profitability index of a project
58	CAP1	Cap. Asset Pr. Model analysis of project
59	WACC	Weighted average cost of capital
60	COMPBAL	True rate on loan with compensating bal. required
61	DISCBAL	True rate on discounted loan
62	MERGANAL	Merger analysis computations
63	FINRAT	Financial ratios for a firm
64	NPV	Net present value of project
65	PRINDLAS	Laspeyres price index
66	PRINDPA	Paasche price index
67	SEASIND	Constructs seasonal quantity indices for company
68	TIMETR	Time series analysis linear trend
69	TIMEMOV	Time series analysis moving average trend
70	FUPRINF	Future price estimation with inflation
71	MAILPAC	Mailing list system
72	LETWRT	Letter writing system-links with MAILPAC
73	SORT3	Sorts list of names
74	LABEL1	Shipping label maker
75	LABEL2	Name label maker
76	BUSBUD	DOME business bookkeeping system
77	TIMECLOCK	Computes weeks total hours from timeclock info.
78	ACCTPAY	In memory accounts payable system-storage permitted
79	INVOICE	Generate invoice on screen and print on printer
80	INVENT2	In memory inventory control system
81	TELDIR	Computerized telephone directory
82	TIMUSAN	Time use analysis
83	ASSIGN	Use of assignment algorithm for optimal job assign.
84	ACCTREC	In memory accounts receivable system-storage ok
85	TERMSPAY	Compares 3 methods of repayment of loans
86	PAYNET	Computes gross pay required for given net
87	SELLPR	Computes selling price for given after tax amount
88	ARBCOMP	Arbitrage computations
89	DEPRSF	Sinking fund depreciation
90	UPSZONE	Finds UPS zones from zip code
91	ENVELOPE	Types envelope including return address
92	AUTOEXP	Automobile expense analysis
93	INSFILE	Insurance policy file
94	PAYROLL2	In memory payroll system
95	DILANAL	Dilution analysis
96	LOANAFFD	Loan amount a borrower can afford
97	RENTPRCH	Purchase price for rental property
98	SALELEAS	Sale-leaseback analysis
99	RRCONVBD	Investor's rate of return on convertable bond
100	PORTVAL9	Stock market portfolio storage-valuation program

☐ **CASSETTE VERSION** $99.95
☐ **DISKETTE VERSION** $99.95
☐ **TRS-80* MODEL II VERSION** $149.95

ADD $2.00 FOR SHIPPING IN UPS AREAS
ADD $3.00 FOR C.O.D. OR NON-UPS AREAS
ADD $4.00 OUTSIDE U.S.A, CANADA & MEXICO

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

VISA

24 HOUR ORDER LINE
(914) 425-1535

THE COMPUTRONICS INC.
MATHEMATICAL APPLICATIONS SERVICE

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

CIRCLE 137 ON READER SERVICE CARD

Nets, Messages and Arpanet

Computer networks, fondly called nets, are generally thought of as many computers connected by communication lines. And a user at a terminal, or personal computer, effectively connects to the whole net by hooking up to any one.*

Nets may hold data, which is sometimes "distributed"—spread out among the computers—and they may run programs for you. They also carry "electronic mail," which are really messages left on the disk drives somewhere in the network. A user of the net, when told he has "mail waiting" uses his password to cause the computer to show what's been left there for him.

Already vast numbers of such "electronic" messages—actually they are usually magnetic, but never mind—travel among individuals every day. The Old Guard who developed time-sharing really had no inkling that one of the principal uses of time-shared computing would be simply this forwarding of stored messages.

There are many network mail systems; almost all time-sharing systems offer something like a mail system. One of the most powerful is "Augment," offered by Tym-Share—the commercial version of Douglas Engelbart's two decades of pioneering designs at Stanford Research Institute.

The most influential computer net is the mighty Arpanet, a curious system of over a hundred computers across the country—at universities, research establishments and military installations. Financed by the Defense Department, it was originally conceived as a means by which defense-linked researchers could use the special facilities of each other's computers. This it is. However, to everyone's surprise, it has come about that the principal use of the Arpanet is as a message highway, carrying millions of transmissions and replies every day. (Many of these messages are programs and dataplexes which cannot be usefully printed. Indeed, many of these "messages" are simply individual bursts in high-density interactive sessions in which two or more devices are participating.)

* A "net" can sometimes be just one computer. Indeed, in a way it could be argued that "net" is just a new word for time-sharing, the simultaneous use of big computers by many people.

The elite who use Arpanet think of it as their connection to an extraordinary universe of brilliant individuals—each other. Membership in this community is a vital part of the sense of identity of many people in it; and the idea of losing this connection is dreaded as a fearsome expulsion, like losing credit card privileges.

Nevertheless, there is talk that the Defense Department suspects it is paying for some usage which is not directly related to defense. (This is obviously true, but Arpanet is also an expanded experiment in high-tech informational community.)

In any case, the rug may one day be pulled out from many of these users, and as yet no service broad or powerful enough to replace it is on the horizon. □

Can the At-Sign Save Us?

There is already a convention for passing messages among nets, which is in use between certain of them. A user of one net may address a user at, say, Arpanet, as follows:

SNERD@ARPANET

"Snerd" being the registered password of an Arpanet regular, the nets will pass this message on through to Arpanet, which will in turn see to it that "Snerd" is informed of its being stored there.

It was argued in private by certain attendees of the M&M Conference that dangers posed by the Post Office to the hopes of sophisticated users could in some ways be mollified by this convention.

Suppose the PO obtained that most feared prerogative, a monopoly of "electronic mail." Nonetheless, if you are a member of a known net and addressed through that net—like SNERD@ARPANET—then that message would be diverted to your home net before it ever got into the PO net.

But this is cold comfort for those concerned with creating an exciting information society, not merely for the network elite, but for everybody. And unless the freakiest ideas can be tried on a competitive basis, we may never know what we would have really wanted. □

Mail Chauvinism, continued...

titors would not stand for it and customers would not stand for it—besides which, of course, there is the Reagan administration's stand against government services in general.

But most important, the Postal Rate Commission has in its wisdom given the Post Office that fraction of electronic communication which can be stuffed in an envelope.

However, that does not necessarily end the threat. The warnings of Henry Geller, for instance, centered on the difficulty of a mixed economy where the Post Office offered electronic services in competition with private vendors.

I see a different sort of threat: that the Postal Service might make electronic mail become what they think it is. And this could cripple us all for the indefinite future. At a point so early in the development of such services, it is astonishing that the Postal Service is already petitioning to make ECOM *permanent*. What if permanence had been legislated for the Ford Trimotor, the Eniac computer and the SOAP language?

The Postal Service might make electronic mail become what they think it is.

But it is in the further services the Post Office might offer—currently forbidden—that the danger lies. Even if they get no monopoly, by offering new services they have the power to structure an industry.

If the Post Office can, with flexibility, participate in this with as much foresight as those whose vision is driving it, then their participation will do no harm. But if Post Office participation means low-grade visions are to be foisted on the public, simplified and degraded forms of transmission that cripple the kind of interaction we are trying to create, these maneuverings are to be viewed with the greatest alarm by those who care about the world of tomorrow. Oversimplification and inflexibility could greatly reduce the imagination and power of tomorrow's evolving services. Let us hope the Post Office can find the wisdom to expand its understandings, and make an orderly contribution to the structure of our new life of the future, rather than a narrow, monopolistic impediment to the world some of us are trying to create.

Epilog

In "The Hunting of the Snark," the quarry all were seeking turned out to be that most horrible of beasts, the Boojum. If the finest visions are not shared as widely and clearly as possible, what Boojum may we not find? □

H&E COMPUTRONICS INC.

●●● EVERYTHING For Your TRS-80* Model I or Model III ●●●

* TRS-80™ is a trademark of Tandy Corp.

- All orders processed within 24 Hours
- 30-Day money back guarantee
- Add $3.00 for shipping in UPS Areas
- Add $4.00 for C.O.D. or NON-UPS Areas
- Add $5.00 to Canada or Mexico
- Add exact postage to all other countries

REMsoft, Inc.

Let Your TRS-80™ Teach You ASSEMBLY LANGUAGE

REMASSEM-1

Tired of buying book after book on assembly language programming and still not knowing your **POP** from your **PUSH**?

REMSOFT proudly announces a more efficient way, using your own TRS-80™ to learn the fundamentals of assembly language programming at YOUR pace and at YOUR convenience.

Our unique package, "**INTRODUCTION TO TRS-80™ ASSEMBLY PROGRAMMING**", will provide you with the following:

- Ten 45-minute lessons on audio cassettes
- A driver program to make your TRS-80™ video monitor serve as a blackboard for the instructor
- A display program for each lesson to provide illustration and reinforcement for what you are hearing
- A textbook on TRS-80™ Assembly Language Programming
- Step-by-step dissection of complete and useful routines to test memory and to gain direct control over the keyboard, video monitor, and printer
- How to access and use powerful routines in your Level II ROM

This course was developed and recorded by Joseph E. Willis and is based on the successful series of courses he has taught at Meta Technologies Corporation, the Radio Shack Computer Center, and other locations in Northern Ohio. The minimum system required is a Level II, 16K RAM.

LEARN TRS-80™ ASSEMBLY LANGUAGE DISK I/O

REMDISK-1

Your disk system and you can really step out with **REM**SOFT's Educational Module, **REMDISK-1**, a "short course" revealing the details of DISK I/O PROGRAMMING using assembly language.

Using the same format as our extremely popular introduction to assembly language programming, this "**ASSEMBLY LANGUAGE DISK I/O PROGRAMMING**" course includes:

- Two 45-minute lessons on audio cassette
- A driver program to make your TRS-80™ video monitor serve as a blackboard for the instructor
- A display program for each lesson to provide illustration and reinforcement for what you are hearing
- A booklet of comprehensive, fully-commented program listings illustrating sequential file I/O, random-access file I/O, and track and sector I/O
- A diskette with machine-readable source codes for all programs discussed, in both Radio Shack EDTASM and Macro formats
- Routines to convert from one assembler format to the other

This course was developed and recorded by Joseph E. Willis, for the student with experience in assembly language programming. It is an intermediate-to-advanced-level course. Minimum hardware required is a Model I Level II, 16K RAM one disk drive system.

COMPUTRONICS
CORPORATE OFFICES

50 N. PASCACK ROAD
SPRING VALLEY, NEW YORK 10977

CASHIER'S CONVENIENCE

24 HOUR ORDER LINE
(914) 425-1535

VISA

NEW TOLL-FREE ORDER LINE
(OUTSIDE OF N.Y. STATE)
(800) 431-2818

PLEASE SEND ME:

- ☐ REMASSEM-1 (TRS-80 MODEL I CASSETTE) $69.95
- ☐ REMASSEM-1 (TRS-80 MODEL I DISKETTE) $74.95
- ☐ REMASSEM-1 (TRS-80 MODEL III CASSETTE) $74.95
- ☐ REMASSEM-1 (TRS-80 MODEL III DISKETTE) $79.95
- ☐ REMDISK-1 (TRS-80 MODEL I DISKETTE) $29.95
- ☐ REMDISK-1 (TRS-80 MODEL III DISKETTE) $34.95

CREDIT CARD NUMBER ..... EXP. DATE .....

SIGNATURE ..... NAME .....

ADDRESS ..... CITY ..... STATE ..... ZIP .....

*** ALL PRICES AND SPECIFICATIONS SUBJECT TO CHANGE ***

CIRCLE 139 ON READER SERVICE CARD

C $49 for Sorcerer

C/80 gives you the power and efficiency of structured programming. Programs written in C/80 run up to 10 times faster than BASIC and require less debugging.

C/80 Supports:
Character and integer types
Pointers and arrays
String constants
All C math and logic
Full function recursion
All C control statements
I/O redirection
Standard C I/O library
Dynamic storage allocation
C preprocessor statements

C/80 includes:
C/80: compiler and library
CASM: absolute assembler
Sample C/80 programs:
file compression utility
file comparison utility
WP Pac file conversion

Based on Ron Cain's small-C, C/80 was written by Walt Bilofsky of the Software Toolworks. Triangle Systems distributes C/80 for the Sorcerer with an enhanced tutorial introduction to C/80. C/80 needs at least 40K of RAM and either Exidy or Micropolis C/PM.

Sorcerer and C/PM are trademarks of Exidy Systems and Digital Research.

Ask your Exidy dealer for Triangle System products or order direct specify hardware configuration and software format (1200 baud cassette, Exidy CPM, or Micropolis CPM) add $3.00 domestic $8.00 overseas shipping and handling. 5 % sales tax in Ohio and send check or money order in US funds to

TRIANGLE SYSTEMS

P.O. Box 44026, Columbus, Ohio 43204
614 272-8201

CIRCLE 237 ON READER SERVICE CARD

Side by Side: Pascal and Basic

Al Evans

It may seem a bit heretical to describe a Pascal program in terms of a Basic program, but that's precisely what I'm going to do in this article. Most of us are used to Basic and fairly friendly with it. Pascal puts us in a new environment full of editors, filers, compilers, linkers, system libraries, segmented programs and external units.

It's important to realize that all these possibilities are provided for one reason: to increase the number of ways we can approach a problem. Pascal provides a rich and coherent field for programming: a structured system. On the level of the functional units of any given program, the differences between Pascal and Basic are less striking than the similarities.

Most of us are used to Basic and fairly friendly with it. Pascal puts us in a new environment.

Program Makemenu was orginally written in Apple Pascal as a general-purpose menu utility. The Pascal version should run on any UCSD Pascal system with minor reformatting (a 40-column screen is presently assumed). The procedure "Select" can be inserted directly into any UCSD Pascal program. The only entity which *must* be available to both the procedure "Select" and the calling routine is the Type "TextPage."

This menu uses the convention of moving a "pointer" with the right- and left-arrow keys. A carriage return (in Pascal, a carriage return or space) selects the item currently pointed to.

Most people find this type of menu faster and easier to use than the "pick a number" kind. It can be completely controlled with only 3 keys. Functions most often used can be placed near the top and bottom for rapid selection. A "wrap-around" display is used—the top item is one step below the bottom item and vice versa. Illegal entries are impossible, short of pushing RESET.

For purposes of demonstration and experimentation, Makemenu also includes a procedure to format input into an array of strings centered to print in the middle of a 40-column line. The main program allows you to format and select from a menu.

The Basic version of Makemenu is, as nearly as practical, a statement-for-statement translation of the Pascal program. I stopped short of using "non-standard" Basic programming practices which would be expensive in terms of memory and execution time. And I did not "strain" the Basic language to precisely duplicate the process of a statement when the same effect could be achieved more economically in Basic by altering the process.

Al Evans, 1206 Karen Ave., Austin, TX 78757.

Double your disk storage capacity...

simply by switching to Omni's new reversible disk.

If you have an Apple, TRS-80, Zenith, North Star or any other single-sided 5¼" disk drive, you can double disk capacity by simply switching to the Flip/Floppy disk from Omni. It works just like your present disks, except you can flip it over and record on the reverse side. So you can consolidate programs and files that used to require two disks. You can halve your disk requirements. And save money.

Each disk comes with some impressive specifications: They're certified error-free at more than twice the error-threshold of your system. Rated for more than 12 million passes without disk-related errors or significant wear. And precision fabricated with such standard features as reinforced hub rings.

Call Omni toll-free today. Get premium disks. Twice the capacity. A full money-back guarantee. Unbeatable price. And if you order a ten pack now, a free $5.00 storage case as well.

OMNI

Omni Resources
4 Oak Pond Avenue, Millbury, MA 01527
(800) 343-7620 In Mass. (617) 799-0197

Dealer inquiries invited.
Software Houses: We also offer duplicating and formatting services.

$21.00-Five pack
(Equivalent to 10 single-sided disks)

$40.00-Ten pack
(Equivalent to 20 single-sided disks)

Free
Protective plastic storage case with each 10 pack ordered by 12/25/81

Order toll-free (800) 343-7620. In Mass. (617) 799-0197.

Send the following Flip/Floppy disks.
I understand they have a full 90 day money-back guarantee if I'm not completely satisfied.

System & model # _____

____ Five packs @ $21.00 $_____
____ Ten packs @ $40.00 * $_____
* includes plastic case
Shipping and handling $ 1.50
5% sales tax (Mass. only) $_____
Total $_____

____ Check (to Omni Resources) ____ C.O.D.
____ Master Card ____ Visa
Card # _____ Exp. _____
Name _____
Address _____
_____
Tel _____

CIRCLE 243 ON READER SERVICE CARD

In either language, Program Makemenu starts with a brief initialization section (lines 10-40 in the Basic program). This is followed by a jump to a main controlling routine (lines 10000-10700 in Basic, Main Program in Pascal). The main program lets you format a control menu with the routine Format (lines 1000-1900 in Basic, Procedure Format in Pascal), then displays the menu and accepts selections from it using the routine Select (lines 2000-2950 in Basic, Procedure Select in Pascal). Being a demonstration program, it then simply displays your selection and waits for you to continue or quit.

Let's follow the program step by step, beginning with initialization.

Initialization

Pascal programs start with declarations of global constants, types, and variables. "Global" means "defined everywhere within a program or procedure." The opposite of global is "local." Hold that thought for a few paragraphs—we'll come back to it.

Constants in Pascal are indeed constant. They remain the same throughout the program and from one run to the next. The only way to change them is to alter the source text and recompile the program.

In Basic, on the other hand (lines 10-15), their constancy is a function of the programmer's state of mind. For example, if you add

10025 MAXCHAR = 85

to the Basic program, you will be free to enter long lines when formatting your menu. This is guaranteed to produce incomprehensible effects.

Basic has nothing directly comparable to a type declaration. The variable types used in Basic are integer, real, and string, plus arrays of these types. In Pascal, a type might be defined as: Type Hicard=(J,Q,K,A); or Type Weekday=(MON,TUE,WED,THUR,FRI).

Later in the program, a variable of the type Weekday could only be assigned one of its defined values, just as an integer in the Apple can only be assigned a value between -32767 and 32767. Furthermore, these types are ordered. Just as the integer 1 is less than 2, the Weekday MON is "less than" TUE. Obviously, the possibilities are endless.

But in the present program, I have simply used the Type TextPage as a convenient word to stand for an array of 20 strings.

"Variable declarations" in Basic are optional (but considered good form). The Type of a variable is defined by its suffix (none for real, % for integer, $ for string). The Basic "DIM" statement on line 35 is approximately equivalent to the Pascal variable declaration MENU:TextPage. But there is one important difference, with the advantage going to Basic in this case.

As I mentioned before, PAGESIZE is actually a variable, rather than a constant, in the Basic program. We could add the line

20 INPUT "PAGESIZE: ";PAGESIZE

and change this constant on every run. Or we could CLEAR all variables later in the program, change PAGESIZE, and dimension the array again. This type of dynamic storage allocation is comparatively difficult in UCSD Pascal. In fact, it can't be done at all with arrays.

Controlling the Main Program

With initialization complete, we'll skip over the working routines to the controlling Main Program. Line 50 takes care of this in Basic; in Pascal it is automatic.

In Pascal, one major objective is to write Main Programs which are concise and easy to understand. Names of variables and procedures are selected carefully. If they are clear and meaningful, the Main Program can approach an English-language description of the process used to perform the task at hand. Ideally, a person not familiar with the program can read the Main Program section and gain a quick understanding of what is going on.

Of course, there is a good reason to do this in Basic, too. We are free to select appropriate names and use REM's to make the process obvious. Nor is it difficult to be obtuse in Pascal, but the dividing line is sharper. In Basic, we can at least always tell what actions the computer itself is performing. Unclear Pascal code borders on the completely incomprehensible.

Procedure Format

The first statement in the Pascal Main Program is Format(MENU). This statement does two things. First, it calls Procedure Format, serving exactly the same purpose as the GOSUB 1000 in the Basic program (line 10050). Second, it assigns MENU as the "parameter" passed to Format. The top line of Format reads:

Procedure Format(Var TEXT:Text Page);

This declaration means that I item is to be

```
1  REM  MAKEMENU BASIC:
2  REM  TRANSLATION OF PASCAL
3  REM  PROGRAM MAKEMENU
5 :
10  REM  CONSTANTS
15 PAGESIZE = 20:MAXCHAR = 36
20 :
25  REM  VARIABLES
30 MENUITEMS = 0:INDEX = 0
35  DIM MENU$(PAGESIZE)
40 CH$ = ""
45 :
50  GOTO 10000: REM  JUMP TO MAIN PROGRAM
55 :
60 :
1000  GOTO 1100: REM  PROCEDURE (ROUTINE) FORMAT
1005 :
1010  REM  PROCEDURE (SUBROUTINE) CENTER
1020 SPACE$ = " "
1030  FOR J = 0 TO  INT ((38 - LEN (S$)) / 2)
1040 S$ = SPACE$ + S$
1050  NEXT J
1060  RETURN : REM  END OF 'CENTER'
1065 :
1100  REM  BEGIN MAIN BODY OF FORMAT
1150  HOME
1200  PRINT "**FORMAT A MENU**"
1250  PRINT
1300  PRINT "YOU MAY USE UP TO ";PAGESIZE;" LINES"
1350  PRINT "OF UP TO ";MAXCHAR;" CHARACTERS EACH"
1400  PRINT
1450  INPUT "ENTER NO. OF MENU LINES: ";MENUITEMS
1500  IF MENUITEMS < 1 OR MENUITEMS > PAGESIZE THEN  PRINT "BETWEEN 1 AND
     ";PAGESIZE;", PLEASE": GOTO 1450
1550  PRINT
1600  PRINT "ENTER EACH LINE OF MENU:"
1650  FOR I = 1 TO MENUITEMS
1700  PRINT I;", ";: INPUT "";MENU$(I)
1750  IF  LEN (MENU$(I)) > MAXCHAR THEN  PRINT "MAXIMUM ";MAXCHAR;" CHARAC
     TERS, PLEASE": GOTO 1700
1800 S$ = MENU$(I): GOSUB 1010:MENU$(I) = S$
1850  NEXT I
1900  RETURN : REM   END OF 'FORMAT'
1905 :
1910 :
```

passed to Format, that the item may be changed by the procedure ("Var"), that the item will be referred to as TEXT within the procedure, and that the item TEXT is in fact a TextPage (as compared to an Integer or String).

This makes it possible, within a single program, to Format(MENU), then Format(WINELIST) or Format(PROCEDURETABLE), presuming that these are all defined as TextPages.

Parameter-passing is more difficult in Basic; it must be explicitly defined by the programmer. I'll return to this subject. At this point, just note that the main body of the Basic Format routine (lines 1100-1900) refers directly to the MENU$ array, while the same portion of the Pascal program [BEGIN (*Format*)... END; (*Format*)] refers to it indirectly as TEXT.

Actual processing in Format begins at the Pascal line which reads "BEGIN (*Format*)" (Basic line 1200). The program prints out the parameters to be used in making up the menu (Basic lines 1150-1400) and asks for the number of lines of text to be placed on the menu [Basic lines 1450-1500. Pascal lines REPEAT... UNTIL (MENUITEMS>=1) and (MENUITEMS<=PAGESIZE)].

Note the different approaches to range-checking. Pascal, as we all know, frowns on GOTO statements. Loosely, the Basic program says "Get it and check it; if it's wrong, go back and get it again." The Pascal program says "Just keep getting it until it's right." The results are the same.

The rest of the procedure is an indexed loop to fill each line in the menu with an entry from the keyboard. The loop is contained between FOR and NEXT in Basic, between BEGIN and END in Pascal. Again, note the different approaches to range-checking.

Subroutine Center

Just before the end of the loop is a call to a subroutine used to center each line of text [Center(TEXT[I]) in Pascal, line 1800 in Basic]. In Pascal, TEXT[I] is passed as a variable parameter to Center. Center refers to this string as "S." Line 1800 of the Basic program shows how such parameters can be passed explicitly in Basic. This is fairly simple for a string or numeric variable. Obviously, it would be more complicated to pass an entire array in this manner, although it is completely possible.

As I mentioned above, Pascal refers indirectly to the menu array as TEXT by the use of parameter-passing. To do the same in Basic, we would have to add the statements

```
FOR I = 1 TO PAGESIZE
TEST$(I) = MENU$(I)
NEXT I
```

The inverse operation would be required after formatting was complete.

This would often lead to a disproportionate increase in time and memory required for a Basic program. I therefore considered it against the "rules" of this program translation.

In any case, the procedure/subroutine Center simply adds spaces to each string entered in the menu to center it on the screen. In doing so, it brings us back to the distinction between global and local variables.

Note that the Pascal Procedure Center uses "I" as a loop control variable, even though "I" is the variable controlling the loop from which the procedure is called. "I" is declared as a variable in both the heading for Format and the heading for Center. The variable "I" declared in the Format heading is "local" to the procedure Format. It does not exist anywhere else in the program. The "I" declared as a variable in Center is local to Center. It does not exist anywhere else in Format or, of course, anywhere in the main program. (You Pascal programmers know that Format's "I" would exist in Center if it were not superceded by a local declaration, but that's beyond the scope of this article.)

This distinction between global and local variables makes it possible to add procedures to a Pascal program and know that they will not change variables which might later be used somewhere else with unexpected results. There is no such distinction in Basic. Another variable ("J" is this case) must be used to control the subroutine in lines 1010-1060.

The Pascal operator "DIV" is simply an integer version of "/." Line 1030 of the Basic program has the same effect.

The Format routine checks each line for length as it is entered and centers it. When MENUITEMS strings have been entered, Format has completed its operation and passes control back to the main program.

The main program now enters a loop which will be repeated until something other than a "C" is entered at its end.

```
      PROGRAM MAKEMENU;

  Const PAGESIZE=20;
        MAXCHAR=36;

  Type TextPage=Array[1..PAGESIZE] of String;

  Var MENUITEMS,INDEX:Integer;
      MENU:TextPage;
      CH:Char;


      Procedure Format(Var TEXT:TextPage);
      Var I:Integer;


        Procedure Center(Var S:String);
        Const SPACE=' ';
        Var I:Integer;

         BEGIN
          For I:=0 to (38-Length(S)) DIV 2 do
              S:=Concat(SPACE,S)
         END; (*Center*)


       BEGIN (*Format*)
        Page(OUTPUT);
        Writeln('**Format a Menu**');
        Writeln;
        Writeln('You may use up to ',PAGESIZE,' lines');
        Writeln('of up to ',MAXCHAR,' characters each.');
        Writeln;
        REPEAT
         Write('Enter No. of Menu Lines: '); Readln(MENUITEMS);
         If (MENUITEMS<1) or (MENUITEMS>PAGESIZE)
          Then Writeln('Between 1 and ',PAGESIZE, ', please')
       UNTIL (MENUITEMS>=1) and (MENUITEMS<=PAGESIZE);
        Writeln;
        Writeln('Enter each line of menu');
        For I:=1 to MENUITEMS do
          BEGIN
            REPEAT
             Write(I,'. ');Readln(TEXT[I]);
             If Length(TEXT[I])>MAXCHAR
              Then Writeln('Maximum ',MAXCHAR,' characters, please.')
            UNTIL Length(TEXT[I])<=MAXCHAR;
            Center(TEXT[I])
          END;
       END; (*Format*)
```

Side by Side, continued...

Procedure Select

This loop sets INDEX to point to the first item on the menu and calls the Procedure Select (Basic lines 2000-2950). Once again, note the technique used to pass parameters in Basic (line 10150). The array itself is not passed for the same reason as before.

Procedure Select sets TOP to center the menu vertically on the screen, calls a subroutine to display it (Pascal Procedure Display, Basic lines 2010-2070), and uses arrows to point to the top item on the menu (Pascal Procedure Markitem, Basic lines 2110-2170). Note that the variable names used in the two languages are slightly different.

In Basic, I could not use POINTER or TOP as variable names. They contain the reserved words INT and TO. Furthermore, in Applesoft and many other versions of Basic, OLDINDEX and OLDPOINTER would refer to the same variable, as the first two letters are the same. In UCSD Pascal, the first eight letters of a variable name are significant.

The same programming problem can be solved very similarly in two reputedly-dissimilar programming languages.

Otherwise, the operation of Display and Markitem is the same in either language.

Procedure Select now reads a character from the keyboard [Read(KEYBOARD.CH) in Pascal, line 2400 in Basic]. We are interested in only three characters: left arrow, right arrow, and carriage return. (For reasons beyond the scope of this article, Pascal considers a carriage return to be the same as a space when only a single character is being read.)

A carriage return sends us back to the Main Program, with INDEX set to the menu position of the item selected. A right arrow moves the pointers one step down the display (increasing the present value of INDEX by 1). A left arrow moves them one step up. No other entry has any effect on the program, the arrows, or the value of INDEX. In any case, the display is updated by Markitem according to the character read.

Slightly different loops are used to perform these functions in Basic and Pascal

```
2000  GOTO 2200: REM  PROCEDURE (ROUTINE) SELECT
2005 :
2010  REM  PROCEDURE (SUBROUTINE) DISPLAY
2020  HOME
2030  HTAB (1): VTAB (TP)
2040  FOR I = 1 TO ITEMS
2050  PRINT MENU$(I)
2060  NEXT I
2070  RETURN : REM  END OF 'DISPLAY'
2075 :
2110  REM  PROCEDURE (SUBROUTINE) MARKITEM
2120 LEFT = 1:RIGHT = 39
2130  HTAB (LEFT): VTAB (TP - I + OINDEX): PRINT "  "
2140  HTAB (RIGHT): VTAB (TP - I + OINDEX): PRINT "  "
2150  HTAB (LEFT): VTAB (TP - I + INDEX): PRINT ">"
2160  HTAB (RIGHT): VTAB (TP - I + INDEX): PRINT "<="
2170  RETURN : REM  END OF 'MARKITEM'
2175 :
2200  REM  BEGIN MAIN BODY OF SELECT
2250 TP =  INT ((24 - ITEMS) / 2)
2300  GOSUB 2010: REM  DISPLAY
2350 INDEX = PTR:OINDEX = PTR: GOSUB 2110: REM    MARKITEM
2400  GET CH$
2450  IF CH$ =  CHR$ (13) THEN  GOTO 2950: REM   JUMP OUT ON C/R
2500 OPTR = PTR
2550  IF CH$ <  >  CHR$ (21) THEN  GOTO 2700: REM   RIGHT ARROW
2600 PTR = PTR + 1
2650  IF PTR > ITEMS THEN PTR = PTR - ITEMS
2700  IF CH$ <  >  CHR$ (8) THEN  GOTO 2850: REM   LEFT ARROW
2750 PTR = PTR - 1
2800  IF PTR < 1 THEN PTR = PTR + ITEMS
2850 OINDEX = OPTR:INDEX = PTR: GOSUB 2110: REM  MARKITEM
2900  GOTO 2400
2950  RETURN : REM  END OF 'SELECT'
2955 :
2960 :
2965 :
10000  REM  MAIN PROGRAM
10050  GOSUB 1000: REM   FORMAT
10100 INDEX = 1
10150 ITEMS = MENUITEMS:PTR = INDEX: GOSUB 2000: REM   SELECT
10200  HOME
10250  HTAB (1): VTAB (8)
10300  PRINT "ITEM SELECTED WAS:"
10350  PRINT
10400  PRINT MENU$(INDEX)
10450  PRINT
10500  PRINT "PRESS 'C' TO CONTINUE"
10550  PRINT "ANYTHING ELSE TO QUIT"
10600  GET CH$
10650  IF CH$ = "C" THEN 10100
10700  END
```

[Basic lines 2400-2950, Pascal "Then REPEAT...UNTIL CH=CHR(32)].

The main difference is that Pascal makes it possible to execute conditionally any number of actions based on the results of a comparison (If...Then BEGIN...END). In Basic, I achieved the same result by reversing the comparison and using GOTO to skip over the actions NOT to be taken (for example, line 2550).

The other difference is the fact that the statement Read(KEYBOARD.CH) is repeated twice in the Pascal program. This is usually necessary in Pascal, and is a side-effect of not using the command GOTO. The first read (outside the loop) is used to determine whether to enter the loop at all. The second (at the bottom of the loop) is used to determine whether to exit the loop. This is perfectly reasonable, but seems peculiar at first.

When you make a choice and press <RETURN>, Select passes control back to the Main Program, along with the new value of INDEX [line 2950 in Basic, END; (*Select*) in Pascal]. Subsequent operation is exactly the same in Pascal and Basic: the program clears the screen, prints out the menu line you selected to prove it is operating correctly, and asks whether you want to choose again.

In a real Basic program, the action taken at the point of return would be determined by a statement such as

ON INDEX GOSUB 3000,4000,...

The same selection process is accomplished in Pascal by

```
Case INDEX of
  1: Procedure1
  2: Procedure2
  3: etc.
END; (*Cases*)
```

```
Procedure Select(TEXT:TextPage;ITEMS:Integer;Var POINTER:Integer);

Var  OLDPOINTER, TOP:Integer;
     CH:Char;


  Procedure Display;
  Var I:Integer;

    BEGIN
     Page(OUTPUT);
     Gotoxy(0,TOP);
     For I:=1 to ITEMS do Writeln(TEXT[I]);
    END; (*Display*)


  Procedure Markitem(INDEX,OLDINDEX:Integer);
  Const LEFT=0;
        RIGHT=38;

   BEGIN
    Gotoxy(LEFT,TOP-1+OLDINDEX); Write('  ');
    Gotoxy(RIGHT,TOP-1+OLDINDEX); Write('  ');
    Gotoxy(LEFT,TOP-1+INDEX); Write('=>');
    Gotoxy(RIGHT,TOP-1+INDEX); Write('<=')
   END; (*Markitem*)


BEGIN (*Select*)
 TOP:=(24-ITEMS) DIV 2;
 Display;
 Markitem(POINTER,POINTER);
 Read(KEYBOARD,CH);
 If CH<>CHR(32)       (*<RETURN> or <SPACE>*)
 Then REPEAT
        OLDPOINTER:=POINTER;
        If CH=CHR(21) (*Right arrow*)
        Then BEGIN
               POINTER:=POINTER+1;
               If POINTER>ITEMS
               Then POINTER:=POINTER-ITEMS
             END;
        If CH=CHR(8)  (*Left arrow*)
        Then BEGIN
               POINTER:=POINTER-1;
               If POINTER<1
               Then POINTER:=POINTER+ITEMS
             END;
        Markitem(POINTER,OLDPOINTER);
        Read(KEYBOARD,CH);
       UNTIL CH=CHR(32)  (*<RETURN> or <SPACE>*)
END; (*Select*)


BEGIN (*MAIN PROGRAM*)
 Format(MENU);
 REPEAT
  INDEX:=1;
  Select(MENU,MENUITEMS,INDEX);
  Page(OUTPUT);
  Gotoxy(0,8);
  Writeln('Item selected was:');
  Writeln;
  Writeln(MENUI[INDEX]);
  Writeln;
  Writeln('Press "C" to continue');
  Writeln('Anything else to quit');
  Read(CH);
 UNTIL (CH<>'C') and (CH<>'c')
END.
```

Conclusion

And so I have shown that the same programming problem can be solved very similarly in two reputedly-dissimilar programming languages. In this particular case, neither seems to have any particular advantage over the other. This apparent equivalence is somewhat misleading.

While I have used a fair percentage of the "power" of Basic (defined in terms of the constructs and actions possible), I have hardly scratched the surface of UCSD Pascal. The brief discussions of type definitions and parameter-passing give only hints of the capabilities of this language.

There are several additional types of loops—all the string functions of Basic and a few extras, completely recursive multiline functions. There are "file" and "record" type variables. Long programs can be broken down into "segments" which are loaded from disk only when they're needed.

But the point of this article is that I was not required to use any of the unfamiliar structures of Pascal to write a useful program. They are simply available. And they will still be available when I am writing a program which cannot be so easily translated into Basic. □

Adwar ARS 170A puts Apple™ color graphics on the air.

Standby for broadcastable color graphics generated by your Apple computer.

With the Adwar ARS 170A your Apple computer can now be used to generate high resolution color graphics suitable for broadcasting within NTSC standards.

What a great idea!

And the nicest part about it is the price. You get state-of-the-art capabilities at a fraction of the cost of larger computer/video graphics systems.

So if you want to put your crisp color graphics on the air and keep your costs on the ground, look into the Adwar ARS 170A.

For detailed information on the ARS 170A and the many other video innovations from Adwar, mail in the coupon below or call today at (212)691-0976.

Adwar Video Corp
100 Fifth Ave
NYC NY 10011

ADWAR VIDEO CORP

Name _____

Address _____

City/State/Zip _____

Phone# _____

Please send more information on
☐ Adwar ARS 170A
☐ Other Adwar video products

The Video Buyers Edge.

CIRCLE 104 ON READER SERVICE CARD

COMPUTER SYSTEMS INC.
15620 South Inglewood Avenue
Lawndale, California 90260
(213) 978-0952



SYSTEM+ (8")

MINI-SYSTEM+ (5¼")

QT SYSTEM +

The QT System+ is designed for both businessmen and engineers in accordance with the latest IEEE standards. Among other functions, it can be used for accounting and word processing, as well as a variety of scientific applications. The system will soon be available with MP/M® to allow multiuser, multi-tasking operations. This means, for example, that an engineer could be working on scientific applications in the lab while an accountant is writing payroll checks in the office. QT also offers a full line of business and applications software, ranging from a business package to word processing.

Technical specifications: 4MHz Z-80A CPU • Dbl-sided, dbl-den. 5¼" & 8" floppy disk controller (handles both drives simultaneously) • Two 8" dbl-den., sgl. or dual sided disk drives, expandable to 4 floppy drives • CP/M® 2.2 included • 64K RAM • Comes complete in single mainframe • EPROM/ROM in any combination to 8K • Two RS232C serial I/O ports • Two parallel I/O parts • Hard disk compatible • Real time clock • Std. 2K monitor program & disk routines included on ROM • Power-on/Reset jump to monitor program • 2716 (5V) EPROM programmer (software incl. on monitor ROM) (ext. 25.5V @ 50ma req.) • Uses Z-80A CPU vectored interrupts • Assembled, tested & burned •Documentation included.

With Terminal 920C Add $900.00

SYSTEM + I (1MB+)

SYS•SS Computer System with 8" Single Sided Drives (801R) without Terminal

A&T (6 slot) **$3595.00**
A&T (8 slot) **$3695.00**
A&T (12 slot) **$3795.00**

SYSTEM + II (2MB+)

SYS•DS Computer System with 8" Dual-Sided Drives (Qume DT-8) without Terminal

A&T (6 slot) **$4495.00**
A&T (8 slot) **$4595.00**
A&T (12 slot) **$4695.00**

MINI-SYSTEM + I (½MB+)

Computer System with 5¼" Single Sided Drives (uses B-51 Disk Drives) No Terminal

A&T (6 slot) **$2495.00**
A&T (8 slot) **$2595.00**
A&T (12 slot) **$2695.00**

MINI-SYSTEM + II (1MB+)

Computer System with 5¼" Double Sided Drives (uses B-52 Disk Drives) No Terminal

A&T (6 slot) **$2795.00**
A&T (8 slot) **$2895.00**
A&T (12 slot) **$2995.00**

DISK DRIVE PRODUCTS



QT DISK PACKAGES

DDC-86-1 Dbl Den Controller, A&T, two 8" dbl den drives (801R) CP/M® 2.2 cabinet, power supply & cables ..... **SPECIAL $1495.00**

DDC-86-2 Two 801R disk drives with cabinet, power supply, fan & cables **$1200.00**

DDC-86-22 Two DT-8 Qume drives with cabinet, power supply, fan & cables **$1600.00**

DDC-86-3 Cabinet with power supply, fans & cables ..... **$ 275.00**

DDC-86-4 Cabinet only ..... **$ 75.00**

DISK DRIVES

8"

Shugart 801R Sgl/Sided Dbl/Den ..... **$ 450.00**
Qume Datatrak 8" Dbl/Den OME-8DS (851R)compatible ..... **$ 850.00**
Pkg of two **$1250.00**

5¼"

MPI-B51 MPI B-51 ..... **$ 235.00**
Sgl Sided Sgl/Dbl Den

MPI-B52 MPI B-52 ..... **$350.00**
Sgl Sided, Dbl Den

MPI-B81
MPI B-91 ..... **$ 375.00**
Sgl Sided, Dbl Den, 77 tracks

Shugart SA400 SHU-SA400 ..... **$ 250.00**
Sgl Sided, Dbl/Den

S-100 PRODUCTS

Double Density - Cal Comp Sys
5¼" or 8" disk controller with free CP/M 2.2
CCB-2422A A&T **$374.95**

Expando RAM II - SD Systems
4 MHz RAM board expandable from 16K to 256K
SDS-RAM216K 16K kit **$289.95**
SDS-RAM216AT 16K A&T **$339.95**
SDS-RAM232K 32K kit **$329.95**
SDS-RAM232AT 32K A&T **$379.95**
SDS-RAM248K 48K kit **$369.95**
SDS-RAM248AT 48K A&T **$418.95**
SDS-RAM264K 64K kit **$409.95**
SDS-RAM264K 64K A&T **$458.95**

PROM-100 - SD Systems
2708, 2716, 2732, 2758 & 2758 EPROM programmer
SDS-PROM-100K kit **$220.00**
SDS-PROM-100AT A&T **$275.00**

ITHACA AUDIO REV 2.0 Z-80 BD

Bare Board ..... **$35.00 each**
10 for $300.00

SEALS ELECTRONICS 32K STATIC BD

Uses TMS-4044 or 5257L ..... **$35.00 each**

QT MEMORY EXPANSION KITS

TRS-80 • APPLE • EXIDY

4116 200 ns ..... 8 for $32.00
2716 (5V-450 ns) ..... $ 9.00
2716 (5 & 12V-450 ns) .... $ 9.00
2732 (5V) $40.00
2114L 300 ns ..... 8 for $36.00
100 - $3.50 ea.

PARTS

MICROPROCESSORS

Z80 (2MHz)	$10.95
Z80A (4MHz)	$12.95
8502	$11.25
6800	$12.50
6802	$18.00
6035	$20.00
8080A	$ 3.50
8085A	$20.00
8086-4	$60.00
8088	$60.00
8748	$60.00
TMS 9900 JL	$29.95

8080A SUPPORT

8212	$ 3.50
8214	$ 4.50
8216	$ 2.95
8224	$ 4.00
8238	$ 8.00
8238	$ 6.00
8243	$ 5.00
8251	$ 7.00
8253	$18.00
8253-5	$20.25
8255	$ 8.25
8257	$17.95
8257-5	$18.00
8258	$18.95
8275	$49.95
8278	$17.50
8279-5	$18.00
8295	$18.50

KEYBOARD CHIPS

AY5-2378	$13.75
AY5-3600	$13.75

BAUD RATE GENERATORS

MC14411	$11.00
1.8432 XTAL	$ 4.95

DISK CONTROLLER

1771B01	$24.95
1791B01(CER)	$37.85

EPROMS

1702A	$ 4.95
2708	$ 8.25
2518 (5V)	$ 8.00
2718 (5V)	$ 8.00
2718 (5 & 12V)	$ 8.00
2758	$18.95
2532	$40.00
2732	$40.00

USRT

S2350	$ 7.95

MISCELLANEOUS OTHER COMPONENTS

N6T20	$ 3.25
N6T26	$ 2.50
N6T47	$ 2.00
N6T68	$ 2.00
1488	$ 1.25
1489	$ 1.25
D3205	$ 3.00
D3242	$14.00
P3404	$ 8.75
TM55501	$18.00
DM8131	$ 3.00

UARTs

TR1602B	$ 4.50
AY5-1013A	$ 4.50

CHARACTER GENERATORS

2513 UP CASE (5&12V)	$10.95
2513 LWR CASE (5&12V)	$10.95
2513 UP CASE (5V)	$ 8.75
2513 LWR CASE (5V)	$10.95

6800 PRODUCTS

6800P	$18.00
6821P	$ 5.25
6840P	$18.25
6845P	$22.00
6850P	$ 4.80
6860P	$11.55
6875P	$ 7.40

CIRCLE 298 ON READER SERVICE CARD

QT PRODUCTS

SBC+2/4 SINGLE BOARD COMPUTER

Features: 1K RAM (which can be located at any 1K boundary) plus one each Parallel and Serial I/O parts on board • Power on jump to on-board EPROM (2708 or 2716) • EPROM addressable on any 1K or 2K boundary • Full 64K use of RAM allowed in shadow mode • Programmable Baud rate selection, 110-9600 • 2 or 4MHz switch selectable • DMA capability allows MWRT signal generation on CPU board or elsewhere in system under DMA logic or front panel control • Two programmable timers available for use by programs run with the SBC+2/4 (timer output and controls available at parallel I/O connector; parallel input and output ports available for use on CPU board).

Bare Board ..... $ 80.00
Kit $190.00
A&T $295.00

Z+80 CPU

Features: Power on jump to on-board EPROM (2708, 2716 or 2732) • EPROM addressed on any 1K or 2K boundary, also shadow mode allows full 64K use of RAM • On-board USART for Synchronous or Asynchronous RS-232 Operation (Serial I/O port) • Programmable Baud rate selection, 110-9600 • Switch selectable 2 or 4 MHz • MWRITE signal generated if used without front panel • Front panel compatible

Bare Board ..... $ 50.00
Kit $150.00
A&T $210.00

RAM+16

Features: S-100, 16K x 8 bit static RAM • 2 or 4 MHz • Uses 2114 1K x 4 static RAM chip • 4K step addressable • 1K increment memory protection, from bottom board address up or top down • Deactivates up to six 1K board segments to create "holes" for other devices • DIP switch selectable wait states • Phantom line DIP switch • Eight bank select lines expandable to ½ million byte system • Data, address and control lines all input buffered • Ignores I/O commands at board address.

Bare Board ..... $ 35.00
4Mhz Kit $190.00
4Mhz A&T $225.00

RAM+ 65

•S-100, 16K x 8 bit static RAM •2 or 4MHz •Uses 2114L (300NS) CHIP •Addressable in 4K steps •Memory protection in 1K increments, from bottom board address up or top down • May deactivate up to six 1K segments of board to create "holes" for other devices • DIP switch selectable wait states • Phantom line DIP switch •Features bank selection by I/O instruction using any one of 256 DIP switch-selectable codes—allows up to 256 software-controlled memory banks.

Bare Board ..... $ 35.00
4MHz Kit $210.00
4MHz A&T $250.00

NEW EXPANDABLE+ REV II DYNAMIC MEMORY BOARD

Features: Runs at 4MHz • 3242 refresh controller with delay line • Four layer PC board insures quiet operation • Supports 16K, 32K, 48K or 64K of memory • 24 IEEE-specified address lines • Optional M1 wait state allows error free operation with faster processors • Optional Phantom disable • Uses Z-80 or on-board refresh signal • Bank on/off signal selected by industry standard I/O port 40 (Hex) • Convenient DIP switch selection of data bus bits determines bank in use • 3 watts low power consumption • Convenient LED indication of bank in use

Definitely works with Cromemco and North Star

Bare Board ..... $ 75.00

KIT		A&T	
No RAM	$230.00	16K	$350.00
16K	$280.00	32K	$450.00
32K	$360.00	48K	$575.00
48K	$480.00	64K	$675.00
64K	$525.00		

CLOCK/CALENDAR+ FOR APPLE II, S-100 OR TRS-80

Features: Date/Month/Year • Day of week • 24 hour time or 12 hour (a.m./p.m.) selectable • Leap year (perpetual calendar) • 4 interval interrupt timer, 1024Hz (approx. 1 millisec), 1 sec., 1 min., 1 hr. • On-board battery backup • Simple time and date setting • Simple software interface • Time advance protection while reading

Battery Included

S-100 or Apple		TRS-80	
A&T	$150.00	A&T Only	$150.00
Kit	$100.00		
Bare Bd.	$ 60.00		

WATCH FOR THE FOLLOWING NEW BDS:

- 4 Port Serial Bd (APR)
- E-PROM Programmer (MAY)
- Floppy Disk Controller (JUN)
- Hard Disk Controller (JUN)
- Color Video Bd (AUG)

I/O+ INDUSTRIAL GRADE I/O BD

Has two serial Sync/Async ports (RS-232, current loop or TTL) with individual Xtal controlled programmable baudrate generators • Four 8-bit Parallel ports; one latched input port and other three can be programmed in combinations of input, output or bidirectional • Also, has three 16-bit Programmable Timers and an 8-level Programmable Interrupt Controller w/Auto restart (8080 / Z80) • Other features include: on-board clock divisor for timers, completely socketed, wire wrap posts for easy port configuration plus more.

Bare Board ..... $ 70.00
Kit $200.00
A&T $375.00

SILENCE+ MOTHERBOARDS

These motherboards are among the quietest on the market. A unique grounding matrix — with each line completely surrounded by ground shielding — eliminates need for termination and gives high crosstalk rejection • They're customer-proven, without crosstalk sometimes operating at 14MHz • A LED power indicator helps eliminate zapped circuits • IEEE S-100 std. compatible, available with 6, 8, 12, 18 or 22 slots • (The 22 slot board fits Imsai chassis and has slot for front panel.)

8 Slot		12 Slot	
Bare Board	$ 25.00	Bare Board	$ 30.00
Kit	$ 40.00	Kit	$ 70.00
A&T	$ 50.00	A&T	$ 90.00
8 Slot		**18 Slot**	
Bare Board	$ 27.00	Bare Board	$ 50.00
Kit	$ 55.00	Kit	$100.00
A&T	$ 70.00	A&T	$140.00

QT MAINFRAMES

MF+MD

MF+

5¼" Disk Mainframe with 25A Pwr Sup

MF+MD12 (12 slot M/B) $500.00
MF+MD8 (8 slot M/B) $475.00
MF+MD6 (6 slot M/B) $450.00
MF+MD w/o M/B $400.00

Q.T. Mainframe

MF+12 (12 slot M/B) $450.00
MF+18 (18 slot M/B) $500.00
MF+22 (22 slot M/B) $600.00

MAINFRAME+ DISK DRIVE



Includes cabinet, 25 amp power supply, IEEE S-100 compatible 6, 8 or 12 slot motherboard and dual 8" disk drive with disk drive power supply.

MF+DD8 ..... $625.00
MF+DD8 ..... $650.00
MF+DD12 ..... $675.00

DDC-8 SINGLE 8" DISK CABINET

Accepts one 8" disk drive (Shugart, Remex, PerSci, Siemens, etc.) • Fan cooled, with data cable and AC line filter to eliminate EMI • Operates from 100-125VAC/200-250VAC at 50-60Hz • Disk drive NOT included.

DDC+8 ..... $195.00

QT COMPUTER SYSTEMS INC.
15620 South Inglewood Avenue
Lawndale, California 90260
(213) 970-0952

PLACE ORDERS TOLL FREE
1-800-421-5150
(CONTINENTAL U.S. ONLY)
(EXCEPT CALIFORNIA)

Apple is a trademark of Apple Computer, Inc
CP/M and MP/M are trademarks of Digital Research
TRS-80 is a trademark of Radio Shack

TERMS OF SALE Cash, checks, money orders, credit cards accepted Also C.O.D. orders under $100.00 Minimum order $10.00 California residents add 6% sales tax Minimum shipping and handling charge $3.00 Prices subject to change without notice International sales in American dollars only

VISA

CIRCLE 298 ON READER SERVICE CARD

BASIC BEATS PASCAL

Jacob Ever

We hear a lot about the virtues of Pascal and structured programming, and the impending obsolescence of Basic. This article presents another view.—EBS

Most personal computers are programmed in Basic. In many cases the language is built into the read only memory of the machine. As a result most users of small computers learn Basic as their first, and sometimes their only, language. In the October 1980 survey of *Byte* magazine almost 50% of the readers indicated that they use Basic frequently, and close to 90% indicated occasional or intended use.

Yet computer language experts argue that Basic is a bad language. I have even heard it called a "spaghetti" language. This does not indicate that Basic has the elegance and style of the Italian language. No, quite the contrary might be true. The term actually refers to the control structure of the language. If one traces with a pencil the lines being executed in a Basic program, in sequence of execution, one ends up with lines crisscrossing one another. Not unlike a bowl of pasta. This is due to the many GOTOs, or branches, that one typically encounters in a Basic program.

Jacob Ever, 175 Ivy Hill Cr., Rye Town, NY 10573.

The spaghetti syndrome, it is argued, makes the program difficult to read and, therefore, difficult to maintain. This is contrasted with the smooth flow of a "structured" language such as Pascal. One can usually write a program in Pascal without any jumping around, i.e. without GOTOs. Some versions of Pascal have branching only as a discouraged option.

Will the superior qualities of Pascal win out over the popularity but poor structure of Basic?

Furthermore, most Basics do not allow explicit naming of objects. For example, a variable in Basic usually has a two character name, the first being alphabetic. This makes reading a Basic program a feat of memorization. It is a well known fact that short term human memory can hold only six or seven items. Therefore a program that contains more than a few non-mnemonic names is indigestible, again reminding one of the aforementioned bowl of noodles.

Finally, almost all Basics are interpretive. That means that the lines of the program are translated into machine instructions as they are encountered during the running of the program. In a loop that is executed many times, the interpreter figures out each time separately the action to be taken based on the stated instructions. This is slow!

Before getting my personal computer, a Northstar Horizon, I read many articles on this subject in the pages of this and other computer publications. It was stated repeatedly that now that Pascal is widely available, the days of Basic are numbered. Therefore, I resolved that Pascal would be the language that I would use for programming my applications. Unfortunately it was several months before I could lay my hands on a UCSD Pascal compiler so I fell back to programming in Northstar Basic. Later I had a chance to program in Microsoft Basic. By the time I learned Pascal, I became interested in comparing the various languages in a given application.

The application I chose for comparison is a word processor which I called Simpleword. Simpleword is a full screen editor which is simple to learn, yet has a full range of editing features. I programmed it in Northstar Basic (NBasic), in Microsoft Basic (MBasic) and Pascal. The article is the result of my experiences in writing Simpleword.

Innovative Design Software, Inc.
ANNOUNCES
SHUFFLEBOARD
for your APPLE II.™
only $29.95

NEW

- *Real time HIRES Color Graphics*
- *Play Against your APPLE or another opponent*
- *An accurate and challenging game following in the tradition of Pool 1.5*

— Another first from IDSI

POOL 1.5 features

- Realistic, life-like motion
- HIRES Color Graphics
- Choice of 4 popular pool Games
- You've Got to see it to believe it!
- Only $34.95



"IT (Pool 1.5) is so realistic, you begin filling in the details of the pool hall yourself"
— Softalk Magazine

Both of these excellent games require a 48K APPLE II/Plus and a DISK II. Pool 1.5 requires a set of game paddles or Joystick. Order directly from IDSI or see your nearest APPLE dealer.

IDSI
P.O. BOX 1658
Las Cruces N.M. 88004
(505) 522-7373
CIRCLE 147 ON READER SERVICE CARD

We accept
Visa, MasterCard,
Check or Money Order.

• Apple II/Plus is a Trademark of Apple Computer Inc. Pool 1.5 is a trademark of IDSI

Pascal

```
Program Test;
const nol=300
var  i:integer;
     ar:array[1..nol] of string[26];

Procedure create;
begin
  ar[1]:='abcdefghijklmnopqrstuvwxyz';
  for i:=2 to nol do
     a[i]:=ar[i-1]
end;

Procedure replace;
begin
  for i:=1 to nol do
     ar[i,pos('z',ar[i])]:=chr(13)
end;

Procedure print;
begin
  for i:=1 to nol do
     write(ar[i])
end;

begin (* main *)
  create;
  write(chr(7)); (* ring bell *)
  replace;
  write(chr(7));
  print;
  write(chr(7));
end.
```

Nbasic

```
100 DIM P$(7800)
110 REM Create
120 PRINT CHR$(7)
130 FOR I=1 TO 7774 STEP 26
140 P$(I,I+26)="abcdefghijklmnopqrstuvwxyz"
150 NEXT I
160 REM Replace
170 PRINT CHR$(7)
180 FOR I=1 TO 7800
190 IF P$(I,I)="z" THEN P$(I,I)=CHR$(13)
200 NEXT I
210 REM Print
220 PRINT CHR$(7)
230 PRINT P$
240 PRINT CHR$(7)
250 END
```

Mbasic

```
100 clear 10000
110 nol=300
120 dim P$(nol)
130 ' Create
140 print chr$(7);
150 P$(1)="abcdefghijklmnopqrstuvwxyz"
160 for I=2 to nol
170 P$(I)=P$(I-1)
180 next I
190 ' Replace
200 print chr$(7);
210 for I=1 to nol
220 mid$(P$(I),instr(P$(I),"z"),1)=chr$(13)
230 next I
240 ' Print
250 print chr$(7);
260 for I=1 to nol
270 print P$(I)
280 next I
290 print chr$(7);
300 end
```

Figure 1.

Performance

Why should one be concerned about the performance of a language? Well the only time one should pay any attention to this area is when the system response time is bothersome (i.e. when it affects productivity). In Simpleword one first enters text. In my experience, one almost simultaneously starts changing it. Let me address the performance aspects of each one of these operations separately.

When it comes to entering text, all languages are fast enough to pick up the input as fast as it is typed in. Even a touch typist is satisfied with the capability of the languages to accept input. This is very important since a slowdown in this area can have a major impact on the usefulness of a text editor.

When it comes to editing, the picture is mixed. Northstar Basic turns out to be slow when editing requires searching a string of text. It is interesting to note that in a recent performance test done by the Association of Computer Users and published in *Computer World*, Northstar Basic outperformed several machines costing many times more.

However, when it comes to word processing, NBasic has two disadvantages: 1) lack of built in string searching function; 2) primitive string storage facilities. So I devised a series of benchmark tests that compare the three languages in their ability to handle a typical word processing application.

Before describing the benchmarks and the results, let me spend a moment on text storage. If asked to identify a basic unit of text, most people will say a word or, possibly, a sentence. Yet most word processing systems use a character or a line as a basic unit. Simpleword is a character-oriented word processor, yet it has to be aware of lines, since lines are the unit printed or displayed at any given time.

In NBasic the working text is stored as one long string. The program has to have the intelligence to break up the long string into individual lines. An empty line is simply stored as a line full of blanks. This takes a lot of space and is cumbersome to handle. Pascal as well as MBasic allows storing the text as an array of lines.

MBasic is particularly adept at storing individual lines in a very economical manner. It reserves space only for the characters that are actually contained in the lines. Pascal on the other hand stores every line as if it contained a full complement of characters. Thus, an empty line occupies a full line of space in Pascal, but not in MBasic.

The text handling benchmark creates a text with 300 lines, each one containing the complete alphabet. The next module searches each line, replacing the last character in the line with a carriage return. Finally the complete text is displayed. So the text consists of three modules: create,

	Nbasic	Mbasic	Pascal
Create	4	2	2
Replace	55	2	2
Print	8	9	8
Total	67	13	12

Figure 2. Run time in seconds.

HUNTINGTON COMPUTING

PROGRAMS LISTED BELOW ARE ON DISK:

EDUCATION

Compu Math Arithmetic	$49 95	now	$44.99
The Linguist	$40 00	now	$22.99
Serendipity Grade Book	$169 00	now	$143.59
Dynacomp s Teacher Pet	$14 95	now	$12.09
Spanish Hangman	$29 95	now	$20.99
French Hangman	$29 95	now	$20.99
Clock (Hartley)	$29 95	now	$26.99
Dr Daley s Software Library	$79 95	now	$69.99
Physics I	$24 00	now	$21.49
J&S Chemistry	$150 00	now	$139.99
J&S Chemistry/Biology Demo			$5.00
Cook s Touch Typing	$14 95	now	$13.49
Mastertype	$34 95	now	$29.09
Compak Math Grade by Concept	$495	now	$445.49
Statistics (Edu Ware)	$29 95	now	$25.29
Algebra I (Edu Ware)	$39 95	now	$33.99
Microsoft Typing	$19 95	now	$16.99
Basic Tutor 1-8 (each)	$32 00	now	$28.79
Milliken Math Sequences	$450 00	now	$405.00
Compupoem			$15.95
The Learning System	$150 00	now	$127.49
Snake Eggs II	$24 95	now	$21.19
Android Nim	$24 95	now	$31.19
Hartley Cass Control Device	$79 95	now	$71.95
Alicia Bilingual Reader	$29 95	now	$25.29
EAI Critical Reading	$39 95	now	$35.99
EAI Reading Comprehension	$39 95	now	$35.99
Chemistry (Ed Courseware)	$32 00	now	$20.79
American History	$32 00	now	$28.79
Spelling (Ed Courseware)	$32 00	now	$28.79
Astronomy	$32 00	now	$28.79
Biology	$32 00	now	$20.79
Statistics 3 0	$29 95	now	$25.29
Compu Read 3 0	$29 95	now	$25.39
ESP			$12.09
Compu Math Decimals	$39 95	now	$33.89
Compu Math Fractions	$39 95	now	$33.89
Prescriptive Math (Hartley)	$79 95	now	$71.99
Word Search (Hartley)	$14 95	now	$13.49
Letter Recognition	$19 95	now	$17.99
Spelling Bee (Edu-Ware)	$29 95	now	$35.39
Dracula (Pendulum Press)	$34 95	now	$29.69
Moby Dick (Pendulum Press)	$34 95	now	$29.69
Time Machine (Pendulum Press)	$34 95	now	$29.09
Black Beauty (Pendulum Press)	$34 95	now	$20.09
PDI Analogies	$23 95	now	$20.29

UTILITIES

Visicalc Utility #3	$129 95	now	$99.99
Program Line Editor	$40 00	now	$34.99
Super Kram	$175 00	now	$142.5e
Super Disk Copy III	$30 00	now	$25.39
Hayden AS Compiler	$200 00	now	$159.00
Expediter II	$99 95	now	$84.99
Pascal Programmer	$125 00	now	$106.19
S-C Assembler II (V 4 0)	$55 00	now	$46.69
Verscalc	$100 00	now	$84.99
Quicktrace	$35 00	now	$29.09
Tiny Pascal (Programma)	$49 95	now	$42.89
Tiny Pascal Plus + (Abacus)	$50 00	now	$42.49
Apple Cillin	$29 95	now	$25.39
Micro Apple 1 (incl Book)	$24 95	now	$22.99
Pascal Graphics Editor	$114 95	now	$97.09
P L E in ROM	$60 00	now	$58.99
Disk Fixer	$28 95	now	$24.29
Super Sound	$16 95	now	$14.39
Memory Management System	$39 95	now	$33.89
Super Disk Copy (Sensible)	$29 95	now	$25.39
Disk Recovery	$29 95	now	$25.39
Multi Disk Catalog	$24 95	now	$21.19
Double Dos Plus	$24 95	now	$21.19
Aplus	$24 95	now	$21.19
Disk Organizer	$24 95	now	$21.19
Quickloader	$24 95	now	$21.19
Apple Doc	$34 95	now	$29.59
Z Term	$99 95	now	$84.99
Ace	$29 95	now	$25.39
Co op Complete Graphics Sys	$59 95	now	$50.09
P Lisp Interpreter (Pegasys)	$99 95	now	$89.89
Lisa	$49 95	now	$43.39
Apple Forth (Programma)	$49 95	now	$42.39

WORD PROCESSORS

Apple Writer			$65.99
Magic Window	$100 00	now	$84.99
Easy Writer Professional	$250 00	now	$219.00
Letter Perfect	$150 00	now	$137.ae
Super Text	$150 00	now	$127.49
Superscribe	$129 95	now	$110.2e
Apple Pie (All Versions)	$129 95	now	$99.99
Executive Secretary	$250 00	now	$212.49
Apple Wordstar	$375 00	now	$284.00
Hebrew II	$60 00	now	$50.99
Apple Writer Extended	$29 95	now	$25.29

GAMES

Hi Res Soccer	$29 95	now	$25.39
Apple Oids	$29 95	now	$25.39
Wurst of Huntington Computing			$19.99
Gobbler	$24 95	now	$31.19
Ultima	$39 95	now	$33.89
Autobahn	$29 95	now	$25.39
Battle Cruiser Action	$44 95	now	$38.19
Gorgon	$39 95	now	$33.09
Super Stellar Trek	$39 95	now	$33.89
Hellfire Warrior	$39 95	now	$33.99
Gamma Goblins	$29 95	now	$25.39
Mission Asteroid	$19 95	now	$17.99
Wizardry	$49 95	now	$42.49
Star Mines	$29 95	now	$35.39
Warp Factor	$39 95	now	$33.99
Microsoft Adventure	$29 95	now	$35.39
Wizard and the Princess	$32 95	now	$28.99
Flight Simulator	$34 95	now	$29.49
Odyssey	$29 95	now	$25.39
Sargon II	$34 95	now	$29.69
Space Eggs	$29 95	now	$25.39
Hi-Res Cribbage	$24 95	now	$21.19
Lords of Karma (cass)	$20 00	now	$16.99
Oh Shoot		now	$19.99
ABM	$24 95	now	$21.19
Computer Conflict	$39 95	now	$35.99
Computer Air Combat	$59 95	now	$52.99
Temple of Apshai	$39 95	now	$33.89
Zork	$39 95	now	$33.99
All Nibble Software			15% off list
Robot Wars	$39 95	now	$33.99
Cranston Manor	$34 95	now	$29.69
Dragon s Eye	$24 95	now	$31.19
Computer Acquire	$20 00	now	$16.99
Twala s Last Redoubt	$29 95	now	$25.39
Snoggle	$24 95	now	$31.19
Alien Rain	$24 95	now	$21.19
Alien Typhoon	$24 95	now	$31.19
Raster Blaster	$29 95	now	$25.39
3-D Skiing	$24 95	now	$21.19
Creature Venture	$24 95	now	$31.19
Galaxy Space War I	$39 95	now	$33.99
Hodge Podge	$23 95	now	$21.39
Meteoroids in Space	$19 95	now	$16.99
Dragon Fire	$49 95	now	$42.49
Pool 1 5	$34 95	now	$29.09
Orbitron	$29 95	now	$25.39
Galactic Attack	$29 95	now	$25.39
Swordthrust I	$29 95	now	$25.39
Swordthrust II	$24 95	now	$21.19
Swordthrust III	$24 95	now	$21.19
Enchanted Island/Atlantis	$21 95	now	$18.59
Original Adventure	$24 95	now	$21.19
Mad Venture	$24 95	now	$21.19
Crown of Arthane	$35 00	now	$29.69
Orbitron	$29 95	now	$25.39
Pulsar II	$29 95	now	$25.39
Sneakers	$29 95	now	$35.39
Invasion Force	$23 95	now	$30.39
Wizard s Mountain	$16 95	now	$14.39
Kaves of Karkhan	$49 95	now	$43.39
I F Six Micro Stories	$14 95	now	$12.69
Milestones	$19 95	now	$16.89
Inferno	$29 95	now	$25.39
A2-3D A Saturn Navigator	$24 95	now	$31.19
Black Hole	$18 95	now	$16.09
The Shattered Alliance	$59 95	now	$58.99
Space Warrior (Broderbund)	$24 95	now	$21.19
OO Topos	$32 95	now	$27.99
Monty Plays Scrabble	$39 95	now	$33.89
Poker Tournament	$20 95	now	$17.79
Star Thief	$29 95	now	$25.39
Apple Panic	$29 95	now	$25.39

VISIDEX
List $200.00
now $139.00
(Offer expires 12-30-81)

STOCK PROGRAMS

Portfolio Master	$75 00	now	$63.69
Market Charter	$129 95	now	$118.39
Dowlog for Market Charter	$99 95	now	$89.99
Investment Decisions	$99 95	now	$84.99
Stock Tracker	$190 00	now	$161.49
Stock Tracker (Auto Ver)	$300 00	now	$254.99

BUSINESS APPLICATIONS

Invoice Factory (Special)	$200 00	now	$149.00
Regression Trend Analysis	$26 95	now	$23.89
Multiple Regression	$29 95	now	$25.39
Microsoft Fortran	$200 00	now	$165.69
Microsoft Cobol 80	$750 00	now	$637.49
Business Pac 100	$99 95	now	$84.99
Desktop Plan II	$200 00	now	$169.99
Visicalc 3 3 Special	$200 00	now	$149.00
Visiplot	$179 95	now	$152.89
Visitrend/Visiplot	$259 95	now	$228.89
Visiterm	$149 95	now	$127.39
Complete Mailing (Avant-Garde)	$59 95	now	$50.89
DB Master	$229 95	now	$194.59
PFS	$95 00	now	$80.69
PFS Report	$95 00	now	$80.69
Data Factory	$150 00	now	$124.00
Thinker	$495 00	now	$420.09
Request	$225 00	now	$191.19
Super Kram	$175 00	now	$148.69
ASCII Express	$99 95	now	$84.99
BPI Accounts Receivable	$395 00	now	$335.69
BPI General Ledger	$395 00	now	$335.69
The Mail Room	$29 95	now	$35.39
Continental General Ledger	$250 00	now	$313.49
Cont Accounts Receivable	$250 00	now	$212.49
Cont Accounts Payable	$250 00	now	$313.49
Continental Payroll	$250 00	now	$313.49
Broderbund Payroll	$395 00	now	$335.69
Informer II	$49 95	now	$42.49
Creative Financing	$150 00	now	$137.49
Real Estate Analyzer	$150 00	now	$127.49
Accounting Assistant (cass)	$7 95	now	$6.89
Spell Star	$250 00	now	$212.49
Muse Form Letter	$100 00	now	$84.99
Property Management System	$225 00	now	$191.19

PERSONAL/HOME

Interlude (disk)	$19 95	now	$16.99
Handwriting Analysis	$19 95	now	$10.89
Decision Master	$29 95	now	$25.39
The Correspondent	$44 95	now	$38.19
Diet Planning	$24 95	now	$21.19
Win at the Races	$39 95	now	$33.89
Pro Football (SDL)	$26 95	now	$22.89
College Football (SDL)	$26 95	now	$22.89
Grocery List	$19 95	now	$16.89
Financial Management System II	$39 95	now	$33.09
Creativity Tool Box	$44 95	now	$38.19
Home Money Minder	$34 95	now	$29.69

MISCELLANEOUS

Memorex Disks			10 for $24.99
Verbatim Datalife-plain w/hubs			10 for $27.99
Dysans			10 for $49.99
Flipsort Box			$29.00
Scotch Disk Cleaner	$29 95	now	$26.99
E Z Port	$24 94	now	$21.19
Atari TRS-80 Pet			Write for information

HARDWARE

D C Hayes Micromodem	$375 00	now	$299.00
D C Hayes Smart Modem	$279 00	now	$249.00
MX 80 Printer Cable/Card	$755 00	now	$575.00
MX 80 Replacement Head	$39 00	now	$34.99
MX 100FT with Graftrax	$995 00	now	$799.00
MX 80FT with Graftrax	$795 00	now	$669.00
460G Paper Tiger	$1094 00	now	$961.99
560G Paper Tiger	$1394 00	now	1225.00
Tiger Trax	$16 95	now	$15.25
Mark IV DOS Boot Switch	$24 95	now	$21.19
Z 80 Softcard	$395 00	now	$299.00
Expansion Chassis	$795 00	now	$675.00
Mt Comp Music System	$545 00	now	$479.00
Versawriter	$249 00	now	$219.00
NFC 12 Green on Black	$260 00	now	$22e.00
Videx 80 col	$350 00	now	$299.00
Videx Switchplate	$19 95	now	$17.99
Andromeda 16K Ram Expansion	$199	now	$179.00
Microsoft 16K Ram Expansion	$195 00	now	$169.00
Centronics 739			Call for Price
Lazer (Rev 6 or 7)	$69 95	now	$58.99
Keyboard Plus	$119 00	now	$99.99
TG Joystick	$59 95	now	$58.89
TG Game Paddles	$39 95	now	$33.89
Mim Joystick	$59 95	now	$54.99
Paymar LCA Rev 7			$29.0e

Call Toll-Free 800-344-4111 (Outside California)

HUNTINGTON COMPUTING
Post Office Box 787
Corcoran California 93212

Order by Phone 800-344-4111
In California (209) 992-5411

SUPER DISCOUNTS
apple® SOFTWARE

VISA
master charge

We take MasterCard or VISA (Include card # and expiration date) California residents add 6% tax Include $2 00 for postage Foreign and hardware extra Send for free catalog Prices subject to change

CIRCLE 260 ON READER SERVICE CARD

replace and print. Figure 1 shows the program as implemented in Pascal, NBasic and MBasic. There are obvious differences in program readability, but this will be explored in a subsequent section. Figure 2 shows the results of executing the three programs on a Northstar Computer. NBasic running native on the machine while MBasic running under CP/M.

It is interesting to note that there is almost no difference in execution time between MBasic and Pascal. The fact that MBasic is fully interpretive while Pascal is partially compiled is dwarfed by the availability of a built-in string searching function. On the other hand, NBasic suffers for not having such a capability.

My conclusion from the performance test and practical experience in running all three word processors is that any one is satisfactory as an input device. NBasic is lacking in editing performance, but this could be overcome by augmenting it with an appropriate machine language routine. However, NBasic also takes a lot of memory for text storage.

MBasic and Pascal were about equal in performance, with an edge for MBasic in storage economy. The more important question, however, is the simplicity, readability and ease of maintenance of programs written in the two languages. More on this in the next section.

Language Structure

Here is the crux of the matter: Will the superior qualities of Pascal win out over the popularity but poor structure of Basic? Trying to answer this question, one runs immediately into a "basic" difficulty (pardon the pun—it just slipped out). The problem is that there is no one Basic. Even in this limited sample there are two Basics from which to choose: MBasic from Microsoft and NBasic from Northstar. The following is a comparison of the three languages in terms of ease of writing and ease of changing a program.

The system aspects of Basic were the determining factors in choosing it over Pascal.

Scanning the programs in Figure 1, it is obvious that Pascal has the best readability index. Unfortunately, there is no such index, but the point is still valid. The Basic programs require comments to make them readable; Pascal with its explicit names is usually self-explanatory.

In the benchmark program there is no need for any GOTOs, but in the actual implementation of Simpleword in NBasic there are quite a few of them. Interestingly, in the MBasic version there are none. This is because MBasic implements the IF...THEN statement differently from NBasic.

Specifically, in MBasic THEN can be followed by multiple statements. This capability can be used to approximate a limited block structuring. To illustrate, let's take a very ordinary situation of a program where the value of an input determines a set of actions. Figure 3 is an implementation of such a program in the three languages.

Now NBasic requires two branches to implement the logic of this program. Maybe one could reduce it to one with some performance penalty; but it is remarkable that MBasic does not require any branches for the same program. However, the program is still difficult to read due to the unrevealing nature of the GOSUB statement. GOSUB 1000 is as obscure as a moonless night. To overcome this handicap, one is forced to add comments to the text. Even more are needed in the NBasic program because of the potentially confusing GOTOs.

Interestingly, one can achieve the same readability in the Pascal version of the program without any comments whatsoever. One reason, no doubt, is the superior structure of Pascal, but equally important is the ability to use explicit names. Most Basics allow any name as long as it fits into two alphanumeric characters, the first always being alphabetic. There are limitations on how much intelligence can be crammed into two characters.

After a lot of thought I decided to write the final version of Simpleword in MBasic. From the foregoing it was clear that I could write in a straightforward, "structured" manner. And indeed the MBasic version of Simpleword, with 150 lines of code, does not need the crutches of any branching statement. To overcome the readability problem, I added a comment next to every GOSUB call—all 25 of them—and I documented, in a dictionary at the beginning of the program, all the important variables. Then I wrote a small program that eliminated all remarks from the final, production version of the program. This is a space-saving feature since in Basic, unlike Pascal, remarks do occupy valuable storage space during execution.

Of course, the obvious question is: why bother? Write the program in Pascal to start with! Yes, indeed. But there is a catch. This relates not to the language features of Pascal, which are indeed superb, but to the systems aspects of Pascal as compared to MBasic. Let me explain.

Figure 3.

```
        Mbasic

100 for J=1 to 100
200 input I
300 if I=1 then gosub 1000: next J: ' Read a line
400 if J>1 then gosub 2000: ' Write a line
500 if J=9 then print "end": end
600 next J

        Nbasic

100 FOR J=1 TO 100
200 INPUT I
300 IF I=1 THEN GOTO 700 \ REM Read a line
400 IF I>1 THEN GOSUB 2000 \ REM Write a line
500 IF I=9 THEN EXIT 900 \ REM End
600 NEXT J
700 GOSUB 1000 \ REM Read a line
800 NEXT J
900 PRINT "end" \ END

        Pascal

Program readwrite;
var i:integer;
begin
  repeat
    read(i);
    case i of
      1:readline;
      2:writeline;
    end
  until (i=9);
  writeline
end.
```

INCREDIBLE

PRINTING MACHINE

Typriter 221

IMAGINE a computer printer/electronic typewriter with a 100 character daisy wheel, controlled by 6 microprocessors (including 2 Z-80's) with an all-electronic keyboard...all in one machine!
THAT'S INCREDIBLE!
THAT'S THE TYPRINTER 221!

AUTOMATICALLY, IT WILL:

Center copy.
Line up decimal points.
Print vertical lines (to separate columns).
Layout columns.
Center titles (over a column).
Print flush right.
Return carriage (at end of line).
Paper feed to pre-set starting point.
Indicate end of page.
Set tabs from one to many.
Clear tabs from one to all.
Set temporary margins (wherever you like) as often as needed.
Repeat all typing keys as needed.
Underline copy.
Print bold face and underline.
Do reverse print (white on black), sort of "reverse Video".
Allow alphabetic and decimal tabulation.
Indent paragraphs.
Store in non-volatile resident memory:
- Often used line formats (margins & tab stops).
- Often used phrases (up to 835 characters) in 10 "bins".
- Up to 10 complete forms (tax, medical, insurance, etc.).
- Up to 14,000 characters in an additional 26 "bins"*.

Print perfectly spaced proportional letters.
Return to typing position after correction with relocation key.
Allow one character to overlap another (Ø).
Right margin justification.
Print two columns with both right and left margins justified and the center ragged.
Lift off errors (from single character to entire line).

IT WILL EVEN:

Allow a carriage return without a linefeed or a linefeed without a carriage return.
Allow you to pre-set an impression control for high-quality carbon copies.
Allow both vertical and horizontal half-spacing.
Allow cancellation of copy before printing.
Allow express and normal backspacing.
Print in four different sizes: 10 pitch pica, 12 pitch elite, 15 pitch micron.
Allow insertion of a missing character in an already printed line.
Accept paper up to 17" wide.

Backspace 1/10, 1/12, 1/15 or even 1/60 of an inch.
Buffer and print out one word at a time, or one line or as many as 10 pages*.
Print up to 198 columns.
Do 1/2 line spacing for footnotes and scientific notation.
Accepts carbon film or reusable nylon ribbons.

IT HAS:

A lighted key to inform you that it's set to temporary margin.
A factory installed noise reduction shield.
A 16K buffer/automatic spooler*.
A lighted key to indicate upper case only.
A Centronics standard parallel interface and can be ordered with:

RS-232 Serial interface* or
IEEE (PET) interface*.

A print speed of 20 cps and (because of logic seeking circuitry) a through-put of approx. 32 cps.
A built-in anti-glare shield.

IT EVEN HAS:

Carbon film ribbons in various colors.
20 character plasma readout that informs you as to:
- Number of characters to end of line.
- Number of lines left to end of page.
- The existence of an error condition.
- The contents of a memory "bin".
- Number of characters left in buffer.

An automatic "feature in use" indicator (centering, storage, etc.)
With scrolling, both FORWARD and BACKWARDS.

INCREDIBLE?

THE 221 OFFERS EVEN MORE!

It's totally compatible with all computers and software.
It will print in English, French, Spanish, Italian and German. It will automatically switch between English and foreign keyboards*. (Under computer control).
Scientific, mathematic, financial and legal daisy wheels available*.
Tractor feed available*.
Can be used as a stand-alone terminal*.
Can be used to access both TWX and TELEX networks*.

TRY WHAT YOU'VE BEEN MISSING.
TRY THE INCREDIBLE MACHINE.
TRY THE TYPRINTER 221.

Suggested price $2850.00
Dealer inquiries invited.
(Call for store nearest you).
Service available through the world-wide facilities of the Olivetti Corporation.

HOWARD INDUSTRIES
2051 E. CERRITOS AVE., 8-C
ANAHEIM, CA 92806
714/778-3443

CIRCLE 190 ON READER SERVICE CARD

SPECTACULAR OFFERS

BASF "FLEXYDISK"
Superior Quality data storage medium. Certified and guaranteed 100% error free.

SINGLE SIDED-SINGLE DENSITY

5¼" or 8" Diskettes ..... 10/$24
5¼" or 8" Vinyl Storage Pages ..... 10/$5

MAXELL-DISKETTES
The best quality diskette money can buy. Approved by Shugart and IBM.

Sold only in boxes of 10

5", 1 side $3.30
8", 1-side $3.90
5", 2-side $4.25
8", 2-side $5.60

ALL MAXELL DISKETTES ARE DOUBLE DENSITY

LIBRARY CASE...
3-ring binder album. Protects your valuable programs on disks. Fully enclosed and protected on all sides. Similar to Kas-sette storage box.

Library 3-Ring Binder $6.50
5¼" Mini Kas-sette/10 ..... $2.49
8" Kas-sette/10 ..... $2.99

DISKETTE DRIVE HEAD CLEANING KITS
Prevent head crashes and insure efficient, error-free operation.

5¼" or 8" $19.50

SFD CASSETTES
C-10 Cassettes ..... 10/$7
(All cassettes include box & labels)
Get 8 cassettes, C-10 sonic and Cassette/8 library album for only $8.00
(As illustrated)

HARDHOLE
Reinforcing ring of tough mylar protects disk from damage

5¼" Applicator $3 5¼" Hardholes $6
8" Applicator $4 50/8" Hardholes $8

VISA • MASTERCHARGE • MONEY ORDERS
CERTIFIED CHECK • FOR PERSONAL CHECKS ALLOW TWO WEEKS • C.O.D. REQUIRES A 10% DEPOSIT • CAL. RES. ADD 6% SALES TAX
MIN $2 SHIPPING & HANDLING • MINIMUM ORDER $10 • SATISFACTION GUARANTEED OR FULL REFUND
Write for our free catalog

ABM PRODUCTS
8868 Clairemont Mesa Blvd.
San Diego, CA 92123
Toll Free
1-800-854-1555
For Orders Only
For information or California orders
(714) 268-3537

CIRCLE 105 ON READER SERVICE CARD

Basic Beats Pascal, continued...

The System

When one writes a program, one actually interacts with two environments—sometimes more. One is the environment of the language one uses, in this case Basic or Pascal, and the other one is the system environment which includes everything else besides the language itself. The latter is usually ignored when discussing alternatives, with all attention focused on the attributes of the language. Yet it is an important aspect of writing, debugging and then running a program.

As I indicated, the system aspects of Basic were the determining factors in choosing it over Pascal. To explain what I mean let's examine the process of writing and debugging a program. One writes the source statements using a text editor of some sort. In Basic one can use the integrated text editor that is a part of the package. The very next step can be the start of a test run. In Pascal on the other hand one first explicitly invokes the text editor. Then the source code is stored. Next the compiler is run. Then finally the test run can start.

This is a time-consuming process during the debugging phase when, at least in my case, many errors are found and require corrections; but then even finding a bug can be very tiresome in Pascal. The compiler gives one very good pointer for syntax errors, but if an execution error is encountered watch out! You are on your own. My version of Pascal gives a cryptic message like P#5 S#12 E#28. And don't try to find an explanation in the manual (PAS-DOC Revision 1). I tried, but did not find any. I presume that the good people in San Diego thought it best to keep a few secrets to themselves.

Basic also allows one a fair degree of freedom for controlling the system resources. This is very important if one wants to make the program easy to use. For example MBasic allows error trapping. In Simpleword, the user is asked for the name of the file where the text to be edited is stored. If the file name is not found in the directory, one gets an error message and the program aborts. This can happen in Pascal or in MBasic. But in the latter, the error can be trapped by the program, which can then ask the user to please re-enter the name as it cannot be found in the directory.

Another example is the FRE function in MBasic. It gives the amount of space remaining for storage of text strings. Using this function the program can be aware when space is running short and gives the user a chance to store his text before the inevitable program termination due to lack of space. There are other statements and functions that give an MBasic programmer a tighter control over his environment than that accorded to the Pascal programmer.

Conclusion

Of the three languages compared, Northstar Basic, Microsoft Basic and UCSD Pascal, Northstar Basic was rejected first due to performance and language deficiencies for text processing application. Pascal was found, not unexpectedly, to have the best language features. However, to my surprise, I found the better system capabilities of Microsoft Basic outweighed the language advantage. So MBasic was chosen as the vehicle for implementing my text editor Simpleword.

My conclusion is that rumors of the imminent demise of Basic are premature. The latest version of Microsoft Basic (version 5) has, I understand, explicit naming capabilities and better control structures. So I expect that many personal computer users will continue to use it as happily as they have in the past. Basic has a simplicity that is still very attractive—this not only at the language level, but from the system point of view as well. Its interpretive nature allows for very easy debugging. Its performance, at least for my application, compared very well with that of Pascal, and Basic allows the programmer to manipulate the system resources as well.

Many of my friends, casual personal computer users rather than professional programmers, use Basic to write programs for fun and sometimes even for profit. The language is perfectly adequate for their needs, but yet they have a grawing doubt. Should they use a 'better' language—say Pascal? What heights of programming virtuosity could they reach using a structured language? My advice to them is that unless they want to take up programming as a more or less full-time occupation they should not bother. Basic is true and tested and will be with us as long as they own their computers and a lot longer. □



"P-ssst—buddy!! Want a see some quick and dirty programs?"



High Roller

Three binary dice add up to fast fun and easy winnings

Binary dice? That sounds strange. What's the point?

Each binary die has six sides but instead of one to six spots, three sides have the numeral one and three have a zero. When rolled, the three dice, red, blue and green, produce a 3-bit binary number.

The binary number can be easily converted to a decimal numbr. A binary 101 equals a decimal 5. After using these dice a few times, these conversions are quickly done even by 7 year olds.

Designed for Understanding

Binary dice are just one of many unique elements of the *Computer Rage* board game. The whole game is designed to help players easily understand the complexities of a large multiprocessing computer system while having great fun playing.

Imagine you're using a large computer along with many other users. It's Thursday and payroll checks have to be run. They have priority over your job. When this happens in the game you lose a turn. But then a vice president wants the results from the program you're working on—take another turn. Oh, oh, in your hurry you make a program mistake. Too bad—return to the last checkpoint.

Meanwhile one of your opponents, a fellow user of the computer, has heard from the president that one of his three programs has top priority; it advances to the output queue. But wait, on your next move you land on an "interrupt" and find that a brownout has just occurred, the computer has crashed, and all the programs of all players must return to the last checkpoint.

The binary dice return to your opponent. He rolls 011, a four, and lands on a decision point. Rolling one die he gets a 1 which means he takes an 8-step flow intead of a 16-step one.

One it goes until one of the two to four players gets all of his programs to the output printer and wins.



Sets of three binary dice used in Computer Rage are available separately.

Sturdy Components

The game comes with a colorful, big 19" x 19" playing board, 38 interrupt cards, 12 miniature disk pack playing pieces (3 for each player) and 3 binary dice. A supplement to the rules describes the way in which *Computer Rage* parallels a multiprocessing system.

Computer Rage is designed for players from 7 to 14 years old but obviously can be played by adults as well. It is for two to four players. Many schools use the game along with a book such as *Be A Computer Literate* in computer literacy units for Grades 3 to 8. It's also an excellent game to have available in open or alternative classrooms.

Discounts Available

In fact we feel so strongly that *Computer Rage* should be in every school that we're offering a special discount to schools and to people who buy a game for a school.

The price of one game is $8.95 postpaid. Buy one game for your family and another for a school and the total price is just $14.00 postpaid (and $8.95 is tax deductible). Individuals or schools buying five or more games may take a whopping 50% discount—just $4.50 each. Customers outside of the U.S. must add $2.00 additional postage per game.

If you'd like an extra set of three binary dice for home or classroom, they are available for just $1.25 per set or five sets for $5.00.

Order today at no risk. If you're not completely satisfied, return the game or dice for a full refund. To order, send your check or charge card number to the address below. Visa, MasterCard, and American Express orders may be called in toll-free to **800-631-8112** (in NJ 201-540-0445). School purchase orders should add an additional $1.00 billing fee.

Don't put it off. Order this entertaining and educational game today.

creative computing

Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)

CIRCLE 350 ON READER SERVICE CARD

Trilingual Tutorial

Ray C. Horn Jr.

Below are definitions of several terms that appear in this article.

Source Code—Computer programs as written by most humans. Source code contains conveniences and shortcuts that the machine can't directly use. For example, rather than using the instruction JP $1000 (jump to location 1000 hex), the programmer can enter the line JP SUB1, and then label the line he wants to jump to with the label SUB1. An assembler or compiler program takes this code and turns it into straight machine language.

Object Code—The actual machine language that the computer uses. This is in the form of numbers which refer to instructions, memory locations, and just plain numbers.

Interpreted Language—Some computer languages are translated into machine code during execution. Each line is interpreted every time it occurs. Consider the Basic lines

```
10 FOR X = 1 TO 10
20 PRINT X
30 NEXT X
```

lines 20 and 30 would be translated into machine code ten times. The interpreter doesn't remember that it has interpreted a line before. This repetition is the major reason why interpreted languages execute slowly.

Compiled Language—Computer languages can be translated, as whole programs, into machine language. The compiled language performs the desired functions of the original program without any need to translate while running. This type of language runs considerably faster than an interpreted language. A program is written in source code, then compiled into object code.—D.L. □

Microcomputer programming is more than just Basic, Pascal or Fortran, or who's got what CPU, or how much RAM we own, or even how many megabytes of on-line disk storage we command. It is much more than this. It is, and necessarily should be, fun and enjoyable.

How many times have you heard someone say that Assembly Language or any other language is difficult to program? Sure, assembly is difficult because of the nature of what you are trying to accomplish, but should that preclude you from learning how to program assembly effectively? More importantly, should you be fearful or apprehensive about taking the plunge into Assembly Language just because you'll need to learn a couple of other numbering systems or just because you'll have to lower yourself to the level of the machine in order to tell the little beast what you want it to do without all the elegant Basic niceties you've come to know and rely on?

My answer is an absolute NO! Assembly Language programming should not cause anybody to be fearful or apprehensive. Fearful of what? The computer isn't going to byte anybody (pardon the pun), or get mad and walk away if you make a few mistakes. So what if the first couple of programs don't quite run properly? So what if you have to go back and rewrite a program to get rid of an elusive bug? It's all part of the total programming experience.

My objective in this article is to expose you to three different programming languages: Basic, Basex (a little known but very useful language) and Z-80 Assembly Language.

To illustrate the relative strengths and weaknesses of the three languages I will use a single problem and present its solution in each language. The problem at hand is "What to Name the Baby?," the inspiration for which came to me after reading Paul Raymer's article in the August 1980 issue of *Creative Computing*.

Ray C. Horn Jr., PSC Box 3303, Edwards AFB, CA 93523.

Accounting Plus II
It Figures



It figures that the same people who brought you Accounting Plus* on the larger computer systems wouldn't forget the Apple:** Accounting Plus II brings to the Apple Computer a completely integrated, easy to use accounting system. Accounting Plus II doesn't require any special hardware, only 48K of RAM and two floppy drives or hard disk, and you don't have to be a CPA to use it. Accounting Plus II organizes and streamlines your paper flow and generates checks, invoices, statements and purchase orders on pre-printed forms. The system supports a solid audit trail which your business requires and your accountant demands.

Modules now available:
- General Ledger
- Accounts Receivable
- Accounts Payable
- Inventory with purchasing

For additional information call or write Systems Plus Inc., 3975 East Bayshore, Palo Alto, CA 94303 Phone 415/969/7047

Seeing is believing.

Systems Plus

*TM of Software Dimensions, San Jose, CA
**TM of Apple Computers, Cupertuno, CA

CIRCLE 277 ON READER SERVICE CARD

Listing 1. (Basic Listing.)

```
100   CLEAR:DEFINT W-Z
110
120   * * * * * * * * * * * * * * * * * * * * * * * * * * *
130   *                                                   *
140   *          FOUR LETTER WORDS . . . REVISTED         *
150   *                                                   *
160   *                 BY:  RAY C. HONNACKER.            *
170   *            COPYRIGHT (C). 19 AUGUST 1980          *
180   *                                                   *
190   * * * * * * * * * * * * * * * * * * * * * * * * * * *
200
210   FOR Z=1 TO 26:FOR Y=1 TO 26:FOR X=1 TO 26:FOR W=1 TO 26
      :T=T+1
      :PRINT"  "CHR$(64+W)CHR$(64+X)CHR$(64+Y)CHR$(64+Z)"  ";
      :NEXT:NEXT:NEXT:NEXT:PRINT
220   PRINT"TOTAL WORDS = "T
      :END
```

Listing 2. (Basex Listing.)

```
33000  REM I WHAT TO NAME THE BABY - BASEX I
33006  DIM CR$ 1
33014  STR CR$ 1 1=13
33026  SET T=0
33044  *** START
33060  FOR Z=65
33068  FOR Y=65
33056  FOR X=65
33064  FOR W=65
33072  INC T
33078  CHR 32
33086  CHR 32
33090  CHR Z
33096  CHR Y
33102  CHR X
33108  CHR W
33114  CHR 32
33120  CHR 32
33126  TIL W+1 90
33138  TIL X+1 90
33150  TIL Y+1 90
33162  TIL Z+1 90
33174  PRT CR$ 1
33182  PRT "TOTAL WORDS= T CR$ 1
33194  END
```

Simply stated, the problem is to generate and display all possible four-letter words using the entire alphabet from A-Z. Such as AAAA, AAAB, AAAC, etc. There are exactly 456,976 four-letter words possible. Not exactly a trivial problem after all.

The Basic Listing

The Level II Basic listing (Listing 1) is quite straightforward. Lines 210-220 do all the work necessary to produce a listing of all possible four-letter words. Unfortunately, interpretive Basic is quite slow. Listing 1 prints out approximately 22.4 four-letter words per second, and takes over five hours to complete the list. But then Basic isn't used because it's fast. Basic is easy to program and debug, and most of us get lazy every now and then and go back to Basic for recreational programming.

The Basex Listing

Basex stands for Basic and Executable machine code, which is exactly what it is: part Basic and part machine code mnemonics. Basex is a compiled, interactive, high level language, and what it lacks in structure it gains in processing speed. For this application Basex is about five times faster than Level II Basic. Basex (see Listing 2) runs to completion in about 1 hour, 7 minutes, 24.38 seconds, or about 113 four-letter words per second.

For those of you not really familiar with Basex syntax or structuring, I'll walk through Listing 2 and explain.

With Basex we don't use line numbers as with Basic, instead we use a memory address where the call to the runtime routine is located. Also we don't use multi-function lines as in Basic, instead we get one Basex statement for each statement address or program line.

Line 33000 is a regular REMark statement. Line 33006 is a regular DIMension statement familiar to most of us in conjunction with data arrays, except here we are setting aside string storage space at the string variable CR$. Line 33014 is a string storage statement which directs Basex to assign the ASCII code 13 to the first location of string CR$.

Basex is a compiled, interactive, high level language, and what it lacks in structure it gains in processing speed.

Line 33026 is similar to a Basic LET statement; in Basex SET does the same job as LET. Line 33034 is a program label; Basex will assign the value 33034 to the symbolic label START. Lines 33040-33064 do the same job as the first logical line of line 210 in Basic listing: setting up nested FOR...TIL loops. ASCII code 65 is the letter "A."

In line 33072 (since Basex is an integer subset language we can count only from 0 to 65535) variable T was supposed to count the total words printed. A small goof on my part—variable T does not actually reflect the total words printed.

Lines 33078-33120 will print two spaces, a four-letter word, and two more spaces continuously throughout the running of the program. This will cause eight words to be printed to a line on the video display, and this will also allow normal scrolling. Variables Z, Y, X and W are used to keep track of the four different letters we are using at any given time. The CHR statement in Basex causes an ASCII code to be printed to the video display, much like CHR$(x) statement in Basic.

Lines 33126-33162 close each of the open FOR...TIL loops established in lines 33040-33064. ASCII code 90 is the letter "Z."

Lines 33174-33194 print a carriage return to the screen and then tell us the value of T, not the actual number of words printed. The END statement in Basex is similar to END in Basic; it tells Basex where and when to stop and turn control back over to the Basex monitor program.

If you study listings 1 and 2 you should see quite a few similarities in both syntax and structure. This is because Basex and Basic are so very much alike that one could readily convert Basic syntax to Basex syntax. But that's where the similarities end, because Basex is compiled language, not an interpretive language like Basic; hence Basex will run about five times faster than interpretive Basic.

The Sinclair ZX80 is innovative and powerful. Now there's a magazine to help you get the most out of it.

Get in sync

SYNC magazine is different from other personal computing magazines. Not just different because it is about a unique computer, the Sinclair ZX80 (and kit version, the MicroAce). But different because of the creative and innovative philosophy of the editors.

A Fascinating Computer

The ZX80 doesn't have memory mapped video. Thus the screen goes blank when a key is pressed. To some reviewers this is a disadvantage. To our editors this is a challenge. One suggested that games could be written to take advantage of the screen blanking. For example, how about a game where characters and graphic symbols move around the screen while it is blanked? The object would be to crack the secret code governing the movements. Voila! A new game like Mastermind or Black Box uniquely for the ZX80.

We made some interesting discoveries soon after setting up the machine. For instance, the CHR$ function is not limited to a value between 0 and 255, but cycles repeatedly through the code. CHR$ (9) and CHR$ (265) will produce identical values. In other words, CHR$ operates in a MOD 256 fashion. We found that the "=" sign can be used several times on a single line, allowing the logical evaluation of variables. In the Sinclair, LET X=Y=Z=W is a valid expression.

Or consider the TL$ function which strips a string of its initial character. At first, we wondered what practical value it had. Then someone suggested it would be perfect for removing the dollar sign from numerical inputs.

Breakthroughs? Hardly. But indicative of the hints and kinds you'll find in every issue of **SYNC**. We intend to take the Sinclair to its limits and then push beyond, finding new tricks and tips, new applications, new ways to do what couldn't be done before. **SYNC** functions on many levels, with tutorials for the beginner and concepts that will keep the pros coming back for more. We'll show you how to duplicate commands available in other Basics. And, perhaps, how to do things that can't be done on other machines.

Many computer applications require that data be sorted. But did you realize there are over ten fundamentally different sorting algorithms? Many people settle for a simple bubble sort perhaps because it's described in so many programming manuals or because they've seen it in another program. However, sort routines such as heapsort or Shell-Metzner are over 100 times as fast as a bubble sort and may actually use less memory. Sure, 1K of memory isn't a lot to work with, but it can be stretched much further by using innovative, clever coding. You'll find this type of help in **SYNC**.

Lots of Games and Applications

Applications and software are the meat of **SYNC**. We recognize that along with useful, pragmatic applications, like financial analysis and graphing, you'll want games that are fun and challenging. In the charter issue of **SYNC** you'll find several games. Acey Ducey is a card game in which the dealer (the computer) deals two cards face up. You then have an option to bet depending upon whether you feel the next card dealt will have a value between the first two.

In Hurkle, another game in the charter issue, you have to find a happy little Hurkle who is hiding on a 10 X 10 grid. In response to your guesses, the Hurkle sends our a clue telling you in which direction to look next.

One of the most ancient forms of arithmetical puzzle is called a "boomerang." The oldest recorded example is that set down by Nicomachus in his *Arithmetica* around 100 A.D. You'll find a computer version of this puzzle in **SYNC**.

Hard-Hitting, Objective Evaluations

By selecting the ZX80 or MicroAce as your personal computer you've shown that you are an astute buyer looking for good performance, an innovative design and economical price. However, selecting software will not be easy. That's where **SYNC** comes in. **SYNC** evaluates software packages and other peripherals and doesn't just publish manufacturer descriptions. We put each package through its paces and give you an in-depth, objective report of its strengths and weaknesses.

SYNC is a Creative Computing publication. **Creative Computing** is the number 1 magazine of software and applications with nearly 100,000 circulation. The two most popular computer games books in the world, *Basic Computer Games* and *More Basic Computer Games* (combined sales over 500,000) are published by Creative Computing. Creative Computing Software manufactures over 150 software packages for six different personal computers.

Creative Computing, founded in 1974 by David Ahl, is a well-established firm committed to the future of personal computing. We expect the Sinclair ZX80 to be a highly successful computer and correspondingly, **SYNC** to be a respected and successful magazine.

Order SYNC Today

To order your subscription to SYNC, in the USA send $10 for one year (6 issues), $18 for two years (12 issues) or $24 for three years (18 issues). Send order and payment to the address below or call MasterCard, Visa or American Express orders to our toll-free number.

Subscriptions in the UK are mailed by air and cost £10 for one year, £18 for two years or £25 for three years. Send order and payment to the UK address below.

Canadian and other foreign surface subscriptions cost $15 per year or $27 for two years and should be sent to the USA address.

We guarantee your satisfaction or we will refund your entire subscription price.

Needless to say, we can't fill up all the pages without your help. So send in your programs, articles, hints and tips. Remember, illustrations and screen photos make a piece much more interesting. Send in your reviews of peripherals and software too—but be warned: reviews must be in-depth and objective. We want you to respect what you read on the pages of **SYNC** so be honest and forthright in the material you send us. Of course we pay for contributions—just don't expect to retire on it.

The exploration has begun. Join us.

The magazine for Sinclair ZX80 users

sync

39 East Hanover Avenue
Morris Plains, NJ 07950, USA
Toll free **800-631-8112**
(In NJ 201-540-0445)

27 Andrew Close, Stoke Golding
Nuneaton CV13 6EL, England

CIRCLE 215 ON READER SERVICE CARD

Tutorial, continued...

Assembly Listing

Listing 3 represents a quantum leap in data throughput for this particular problem. It will run to completion in just about 32 minutes 42 seconds, or about 232.8 four-letter words per second on the video. For this particular example, Assembly Language will run just about 10 times faster than Basic and about 2.5 times faster than Basex. Obviously if you were going to run a program such as I have presented in this article, you would not want to wait five hours for the program to finish; even one hour is a long time when you just want to see the program run to completion. With the aid of Assembly Language, it is possible to attain fantastic output rates with only minimal effort.

Contrary to popular belief, Assembly Language is not difficult to program. In fact, once you see just how easy it is to get successful results you'll probably never go back to Basic except for light recreational programming.

With the aid of Assembly Language, it is possible to attain fantastic output rates with only minimal effort.

For those who are not familiar with Assembly Language I'll go through the source code line by line:

Line 200 may be changed to suit your individual needs; I'm running 48K RAM so I always put the object code well above the source code for my assembler.

Line 210, CALL 01C9H, calls a subroutine from the Basic ROMs to clear the screen and put the cursor in the upper left corner. Lines 220-240 initialize the four counters we will be using to contain 0's. Lines 250-280 initialize the six-digit BCD (binary coded decimal) total words printed counter that we'll be using later.

Lines 290-430 form a function similar to 'T=T+1' using single precision variables in Basic. Here we are using a six digit BCD counter.

Line 440-460 get two spaces (ASCII code 20 hex or 32 decimal) and puts them at the beginning and the end of the output string buffer, similar to the two CHR 13's at the front and back of the four letter output segment in the Basex program (see lines 33078-33120).

Lines 470-530 do the same job as. CHR$ (64+W)CHR$(64+X)CHR$(64+Y) CHR$(64+Z) in Basic.

Listing 3. (Assembly Listing.)

```
                100   ; WHAT TO NAME THE BABY? REVISITED.
                110   ;  ADAPTED FROM APPLESOFT LISTING.
                120   ;  CREATIVE COMPUTING, AUGUST 1980, PG. 98
                130   ;
                140   ; ASSEMBLY PROGRAM : WORD4 VERSION 2.3
                150   ;  BY:  RAY C. HORN JR.
                160   ; COPYRIGHT (C). 1980 AUGUST 1980
                170   ;
                180   ;
                190   ;
A000            200          ORG 0A000H    ; MID 32K
A000  CD C9 01  210   START  CALL 01C9H    ; CLEAR SCREEN
A003  21 01 01  220          LD HL,0101H   ; GET 1 G
A006  22 D1 A0  230          LD (W),HL     ; INIT  X  W
A009  22 D3 A0  240          LD (Y),HL     ; INIT. Z  Y
A00C  21 00 00  250          LD HL,0000H   ; GET 0 G
A00F  22 D5 A0  260          LD (T),HL     ; INIT. BCD COUNTER
A012  AF        270          XOR A         ; ZAP ACC.
A013  32 D7 A0  280          LD (T+2),A    ; INIT. ALL OF BCD CNTR.
A016  21 D7 A0  290  MNLOOP  LD HL,T+2     ; PNT TO BYTE #0
A019  7E        300          LD A,(HL)     ; GET BYTE #0 OF BCD CNTR
A01A  C6 01     310          ADD A,1       ; BUMP BYTE 0
A01C  27        320          DAA           ; DECIMAL ADJUST BYTE 0
A01D  77        330          LD (HL),A     ; PUT BYTE 0 BACK
A01E  2B        340          DEC HL        ; PNT TO BYTE 1
A01F  7E        350          LD A,(HL)     ; GET BYTE 1
A020  CE 00     360          ADC A,0       ; BUMP BYTE 1 (ADD CY)
A022  27        370          DAA           ; DECIMAL ADJUST BYTE 1
A023  77        380          LD (HL),A     ; PUT BYTE 1 BACK
A024  2B        390          DEC HL        ; PNT TO BYTE 2
A025  7E        400          LD A,(HL)     ; GET BYTE 2
A026  CE 00     410          ADC A,0       ; BUMP BYTE 2 (ADD CY)
A028  27        420          DAA           ; DECIMAL ADJUST BYTE 2
A029  77        430          LD (HL),A     ; PUT BYTE 2 BACK
                432   ; LINES 290 - 430 ARE SAME AS
                434   ;  BASIC  T=T+1      (SINGLE PRECISION)
                436   ; ONLY MUCH FASTER.
                438   ;
A02A  21 20 20  440          LD HL,2020H   ; GET SPACES
A02D  22 DB A0  450          LD (WORD),HL  ; PAD 2 SPACES IN FRONT
A030  22 DE A0  460          LD (WORD+6),HL ; PAD 2 SPACES IN REAR
                462   ;
A033  01 40 40  470          LD BC,4040H   ; GET ( A -1)
A036  2A D1 A0  480          LD HL,(W)     ; GET W  X CNTRS.
A039  09        490          ADD HL,BC     ; COMPUTE (W+40H),(X+40H)
A03A  22 DA A0  500          LD (WORD+2),HL ; STORE 1ST TWO LETTERS
A03D  2A D3 A0  510          LD HL,(Y)     ; GET Y  Z1 CNTRS.
A040  09        520          ADD HL,BC     ; COMPUTE (Y+40H),(Z1+40H
A041  22 DC A0  530          LD (WORD+4),HL ; STORE LAST TWO LETTERS
A044  21 DB A0  540          LD HL,WORD    ; PNT TO WORD
A047  06 08     550          LD B,8        ; 8 CHARS TO SEND
A049  7E        560  PLOOP   LD A,(HL)     ; GET CHAR
A04A  CD 33 00  570          CALL 0033H    ; SEND IT TO VIDEO
A04D  23        580          INC HL        ; BUMP PNTR
A04E  10 F9     590          DJNZ PLOOP    ; DO 8 TIMES
                592   ;
A050  3A B0 38  600  BREAK   LD A,(3B30H)  ; CHECK SHIFT?
A053  CB 47     610          BIT 0,A       ; SHIFT?
A055  28 09     620          JR Z,NEXTZ    ; IF NOT SHIFT, DO NEXT
A057  3A 40 38  630          LD A,(3840H)  ; BREAK CHECK
A05A  CB 57     640          BIT 2,A       ; BREAK?
A05C  28 02     650          JR Z,NEXTZ    ; IF NOT BREAK, DO NEXT
A05E  18 48     660          JR TOTALW     ; ELSE IF SHIFT-BREAK, EN
                662   ;
A060  3A D4 A0  670  NEXTZ   LD A,(Z1)     ; GET Z1 CNTR
A063  3C        680          INC A         ; BUMP Z1
A064  32 D4 A0  690          LD (Z1),A     ; PUT BUMPED Z1 BACK
A067  FE 18     700          CP 27         ; Z1 + 1 <= Z1 <= 26 ?
A069  FA 78 A0  710          JP M,NEXTY    ; IF Z1 < 27
A06C  3A D3 A0  720          LD A,(Y)      ; ELSE GET Y CNTR
A06F  3C        730          INC A         ; BUMP Y
A070  32 D3 A0  740          LD (Y),A      ; PUT BUMPED Y BACK
A073  3E 01     750          LD A,1        ; GET 1
A075  32 D4 A0  760          LD (Z1),A     ; INIT Z1 COUNTER
A078  3A D3 A0  770  NEXTY   LD A,(Y)      ; GET Y CNTR
A07B  FE 18     780          CP 27         ; Y + 1 <= Y <= 26 ?
A07D  FA BC A0  790          JP M,NEXTX    ; IF Y < 27
A080  3A D2 A0  800          LD A,(X)      ; ELSE, GET X CNTR
A083  3C        810          INC A         ; BUMP X
A084  32 D2 A0  820          LD (X),A      ; PUT BUMPED X BACK
A087  3E 01     830          LD A,1        ; GET 1
A089  32 D3 A0  840          LD (Y),A      ; INIT Y CNTR
A08C  3A D2 A0  850  NEXTX   LD A,(X)      ; GET X CNTR
A08F  FE 18     860          CP 27         ; X + 1 <= X <= 26 ?
A091  FA A0 A0  870          JP M,NEXTW    ; IF X  27
A094  3A D1 A0  880          LD A,(W)      ; GET W CNTR
```

THE PROGRAM STORE

CALL TOLL FREE
800 424-2738

By John Harris from On Line
If you like the PAC MAN arcade game, you'll love JAW BREAKER! Guide your chompers through a candystore maze, eating "wife savers" as you go. You are pursued by varicusly colored "smilies," determined to knock your teeth out. If you eat a jawbreaker, the "smilies" turn to blue "frownies," and you try to eat them! Sound familiar? It's one of the best uses of Atari graphics and sound we've seen yet you'll love it!

16K disk...$29.95



DODGE RACER

From Synapse Software
You guide your racecar through six lanes of speedway with your joystick, scoring points as you pass over the white dots in each lane. Chasing you in the opposite direction is the phantom jam car with one purpose to meet you head on in a fiery crash!

Full of sound, color, and excitement, DODGE RACER can be played with one to four competitors and has 12 play options.

16K tape...$22.50 24K disk...$22.50



CONFLICT 2500

From Avalon Hill
While checking your orbiting minefields, one of your Hyperfighters detects the presence of enemy Planet Pulverizers. Get set for a star battle in the 26th century. This new space game contains all the elements to hold your fascination: graphics, strategy, and challenge. Using the unique "Variable Scenario System" you set the size of your fleet and the level of complexity. Play one-on-one with the computer or with up to 10 players.

Tape for 16K Apple, 32K Atari,
TRS 80 (16K/I, 32K/III)...$14.95

LUNAR LANDER

By Wall, Moncrief & Jesses from A.I.
Grab your joystick and sweat out the touchdown of your LEM. This fascinating and challenging game makes good use of Atari's player/missile graphics, color, and four voice sound.

Choose from four lunar landscapes, with many choices for landing sites. Select a more difficult site and get more points. If you can land successfully. You have complete control of your LEM via main engines and small side thrusters, and five successful landings are heralded with a flag raising ceremony. Great fun!

24K tape (disk compatible)...$14.95

POKER SOLITAIRE

By Jerry White from Artsci
You are dealt 25 cards which are then turned up one at a time. As each card is faced, you must decide where to place it on a 5 X 5 grid. The final results are scored from each of the 10 poker hands formed. From one to four players can compete and for added fun, a time penalty can be invoked. It's fun!

16K tape...$14.95

3-D SUPERGRAPHICS

By P. Lutus from United Software
A program development system that allows you to project 3-dimensional images of color, high resolution images and manipulate them at will.

Images are drawn at a speed that makes animation not only possible but almost easy! Routines developed with this system can be incorporated into your BASIC programs. Includes manual and demonstration programs.

40K disk...$39.95

TYPING TUTOR

By Ainsworth & Baker from Microsoft
Speed up your programming and word processing with this excellent touch typing instructional program. First proper finger positioning is taught, the program adding new characters as you progress. Then practice paragraphs are evaluated for accuracy and speed. Continuously adjusting to your increasing skill, TYPING TUTOR senses any keys you're not sure of and points them out.

16K tape...$19.95

TOUCH TYPING

From Atari
Three program modes plus separate data tape guide you from "hunt n peck" beginner through expert typing skills. On screen graphics aide finger placement and drills progress from character patterns to sentences to full paragraphs. Start at your own level; learn at your own pace.

16K 2 tape package...$24.95

ASSEMBLER BOOK

By Don & Kurt Inman
While the ATARI ASSEMBLER CARTRIDGE comes with an operating manual, it assumes that you already know assembly language. If you're new to the Atari or its 6502 processor, this book is a must.

The Inmans guide you through the rudiments of this fascinating type of programing in clear, easy steps. Includes full listing and description of 6502 mnemonics and addressing modes.

$12.95

ASSEMBLER EDITOR

From Atari
Write your own 6502 assembly language programs. The editor and assembler options operate alone or with tape or disk storage, and a comprehensive debugger/disassembler is included.

ROM cartridge & manual...$54.95

Visit Our Baltimore, MD Store: W. Bell Plaza - 6600 Security Blvd

TO ORDER CALL TOLL FREE 800 424-2738 For information Call (202) 363-9797

MAIL ORDERS: Send check or M.O. for total purchase price, plus $1.00 postage & handling. D.C. residents, add 6% tax. Charge card customers: include all embossed information on card.

THE PROGRAM STORE
4200 Wisconsin Avenue NW, Dept. CT 11 Box 9609
Washington, D.C. 20016

Prices Subject To Change

CIRCLE 175 ON READER SERVICE CARD

Tutorial, continued...

Lines 540-590 do the same job as 'PRINT" "CHR$(64+W)CHR$(64+X) CHR$(64+Y)CHR$(64+Z)" ";" in Basic. In other words it prints eight characters, with the four inner characters being the four letter word we generated in lines 470-530.

Lines 600-660 strobes the keyboard for the Shift and Break keys to be pressed. If Shift-Break keys are pressed simultaneously, the program will print the total words printed up until that point and then it stops at the SYSTEM entry commend prompt. We have to have some way of stopping the program in an orderly manner outside of pressing the RESET button.

Lines 670-960 do the same job as 'NEXT Z:NEXT Y:NEXT X:NEXT W:' in Basic only much faster.

Lines 970-1090 are where our program ends up after 32 minutes of strenuous activity. It will print a CR/LF (carriage return and line feed), then it will print a message for the operator, and then it will convert and print the total number of words generated from the six digit BCD counter. Then the program will wait for a few seconds for the operator to take his finger off the Break key, otherwise you'd fall back into Basic 'READY' without getting a change to restart the program from the SYSTEM entry prompt ('*?_').

Lines 1096-1180 define variable names, store our messages and create a word buffer.

Lines 1190-1310 are a very simple BCD to ASCII conversion routine taken from a Z-80 handbook I had laying around at home. We need some way of converting BCD to ASCII to be easily understood.

Line 1320 is a standard assembler END statement; it causes START to be considered as the auto-start address upon assembly.

```
A097  3C          890            INC A          ; BUMP W
A098  32 D1 A0    900            LD (W),A       ; PUT BUMPED W BACK
A09B  3E 01       910            LD A,1         ; GET 1
A09D  32 D2 A0    920            LD (X),A       ; INIT X TO 1

A0A0  3A D1 A0    930   NEXTW    LD A,(W)       ; GET W CNTR
A0A3  FE 1B       940            CP 27          ; W = 1 -> W <= 26?
A0A5  F2 AB A0    950            JP P,TOTALW    ; IF W > 26
A0A8  C3 16 A0    960            JP MNLOOP      ; IF W >= 27
                  962   ;
A0AB  3E 0D       970   TOTALW   LD A,13        ; GET CR/LF
A0AD  CD 33 00    980            CALL 0033H     ; SEND IT TO VIDEO
A0B0  21 E1 A0    990            LD HL,TOTWRD   ; PNT TO MESSAGE
A0B3  CD A7 28    1000           CALL 28A7H     ; TELL OPERATOR
A0B6  3A D5 A0    1010           LD A,(T+0)     ; GET BYTE #2 BCD CNTR.
A0B9  CD F1 A0    1020           CALL BXBCD     ; CONVERT PRINT ASCII
A0BC  3A D6 A0    1030           LD A,(T+1)     ; GET BYTE #1 BCD CNTR.
A0BF  CD F1 A0    1040           CALL BXBCD     ; CONVERT PRINT ASCII
A0C2  3A D7 A0    1050           LD A,(T+2)     ; GET BYTE #0 BCD CNTR
A0C5  CD F1 A0    1060           CALL BXBCD     ; CONVERT PRINT ASCII
A0C8  01 FF FF    1070           LD BC,0FFFFH   ; GET DELAY COUNT
A0CB  CD 60 00    1080           CALL 0060H     ; DELAY HERE FOR A WHILE
A0CE  C3 B2 02    1090           JP 02B2H       ; BACK TO BASIC(SYSTEM *?
                  1092  ;
                  1094  ;
                  1096  ; SYSTEM VARIABLES:
A0D1  01          1100  W        DEFB 1         ;
A0D2  01          1110  X        DEFB 1         ;
A0D3  01          1120  Y        DEFB 1         ; N = 1 <= N <= 26
A0D4  01          1130  Z1       DEFB 1         ;
A0D5              1140  T        DEFS 3         ; REAL 6 DIGIT BCD CNTR.
A0D8              1150  WORD     DEFS 8         ; WORD BUFFER
A0E0  00          1160           DEFB 00H       ; DELIMITER
A0E1  20 54 4F    1170  TOTWRD   DEFM "TOTAL WORDS : "
A0E4  54 41 4C
A0E7  57 4F 52
A0EB  53 20 3A
A0EF  20 00
                  1180           DEFB 00H       ; DELIMITER
                  1182  ;
                  1184  ; END SYSTEM VARIABLES.
A0F1  4F          1190  BXBCD    LD C,A         ; SAVE BCD BYTE IN C
A0F2  E6 F0       1200           AND 0F0H       ; MASK OFF LOW DIGIT
A0F4  0F          1210           RRCA           ;
A0F5  0F          1220           RRCA           ;
A0F6  0F          1230           RRCA           ; ALIGN HI-DIGIT TO LOW
A0F7  0F          1240           RRCA           ;
A0F8  C6 30       1250           ADD A,30H      ; MAKE ASCII (30H-39H)
A0FA  CD 33 00    1260           CALL 0033H     ; PRINT DIGIT ON SCREEN
A0FD  79          1270           LD A,C         ; GET BCD BYTE BACK FROM C
A0FE  E6 0F       1280           AND 0FH        ; MASK OFF HI DIGIT
A100  C6 30       1290           ADD A,30H      ; MAKE ASCII (30H-39H)
A102  CD 33 00    1300           CALL 0033H     ; PRINT DIGIT ON SCREEN
A105  C9          1310           RET            ; RETURN TO CALLER
                  1312  ;
A000              1320           END START      ; AUTO-START HERE
```



"This computer set us back a pretty yen!"

Conclusion

That's really all there is to programming Basic, Basex and Assembly Language for a fairly simple problem.

In general, once you've determined how to go about solving a given problem in Basic, it's really a very easy task to rewrite the program for almost any other language whether it be Basex, Pascal, Fortran, Forth, or Assembler. The logic of the thing stays the same no matter which language you choose to express the problem. With this general concept in mind, programming can become quite enjoyable and even fun. I thoroughly enjoy programming Assembly Language because of the challenge it presents and also because of the raw programming power that Assembly allows me to use. In Assembly Language you have total control over what the CPU does and how it does it. Not many languages afford you that much control. □

NEED A PRINTER?

UP TO 25% DISCOUNTS! — SAME DAY SHIPMENT!

NEW CENTRONICS 739 (RADIO SHACK LINE PRINTER IV)

With Graphics and Word Processing Print Quality

• 18 x 9 dot matrix; suitable for word processing • Underlining • proportional spacing • right margin justification • serif typeface • 80/100 CPS • 9½" Pin Feed/Friction feed • Reverse Platen • 80/132 columns • Top of form

CENTRONICS 739-1 (Parallel)	(List $995)	$785
CENTRONICS 739-3 (Serial)	(List $1045)	815
GRAPPLER™ Apple graphics interface		$165

ANADEX

Dot Graphics, Wide Carriage



• 11 x 9 dot matrix; lower case descenders • Dot resolution graphics • Bi-directional, logic seeking • Up to 200 CPS • RS 232 Serial & Parallel • Forms control • X-ON/X-OFF • Up to 6 part copy.

ANADEX 9501	(List $1650)	$ Call
GRAPPLER™ Apple graphics interface		$165

VISTA — C. ITOH STARWRITER

Daisy Wheel Letter Quality

• 25 CPS (Optional 45 CPS) • Typewriter quality • Centronics parallel • RS 232 Serial (Optional) • Proportional spacing • Bidirectional • Programmable VFU • Self test • Diablo compatible • Friction feed (Optional tractors) • 136 printable columns • Manufactured by C. ITOH.

VISTA V300 (C. ITOH) STARWRITER	(List $1895)	$1575

IDS PAPER TIGERS

Dot Resolution Graphics, quality print, speed

9 wire printhead (460) with lower case descenders • Over 150 CPS • bi-directional, logic seeking • 8 character sizes: 80-132 columns • Adjustable tractors • High-resolution dot graphics • Proportional spacing & text justification

IDS 460G 9 wire printhead, graphics	(List $1094)	$Call
IDS 560G wide carriage, graphics	(List $1394)	$Call
GRAPPLER™ Apple graphics interface		$165

EPSON MX80/MX70/MX100

Low-Priced Professional Print Quality

• 9 x 9 dot matrix • Lower case descenders • 80 CPS • Bidirectional, Logic seeking • 40, 66, 80, 132 columns per line • 64 special graphic characters: TRS-80 Compatible • Forms handling • Multi-pass printing • Adjustable tractors

We also carry a full line of Epson Accessories.

EPSON MX80 (& MX80FT)	(List $645)	$Call
EPSON MX70 Dot graphics, 5 x 7 matrix	(List $450)	$Call
EPSON MX100 wide carriage, graphics	(List $945)	$Call
GRAPPLER™ Apple Graphics Interface		$165
GRAFTRAX 80 - MX80 Dot Graphics		$ 95

MX80/70 FRICTION FEED KIT

User installable kit for single sheets.

Easy 30 minute installation	$ 75

ANACOM

Low Cost, High Speed, Wide Carriage

• 9 x 9 dot matrix • Lower case descenders • Wide carriage • Adjustable tractors to 16" • 150 CPS, Bidirectional, Logic Seeking

ANACOM 150	(List $1350)	$995

NEC SPINWRITER

High Speed Letter Quality

• 55 CPS • Typewriter quality • Bidirectional • Plotting • proportional spacing.

5510 RO, Serial	(List $3055)	$2575
5530 RO, Parallel	(List $3055)	$2575

TELEVIDEO CRT'S

AT DISCOUNT PRICES!

QUANTITY PRICING AVAILABLE

TVI 910
TVI 912C
TVI 920C
TVI 950

Please Call Toll Free Prices are too low to advertise

CRT'S

ADDS VIEWPOINT	(List $698)	$600

PRINTERS

MALIBU 165 wide carriage, graphics, letter quality	(List $1975)	$1325
QUME 5/45 typewriter quality	(List $2905)	$2559
DIABLO 630		$Call

INTERFACE EQUIPMENT

EPSON ACCESSORIES	$ Call
ORANGE INTERFACE for Apple II parallel interface board & cable	$ 110
MICROTRONICS Atari parallel interface	$ 69
TRS-80 CABLES to keyboard or Exp interface	$ Call
NOVATION D-CAT direct connect modem	$ 180

CALL FOR INFORMATION & CATALOG

(800) 854-8275

CA, AK, HI (714) 630-3322

RETAIL PRINTER STORES:

Store #1 3150 E. La Palma, #I Anaheim, CA (714) 630-3622
Store #2 13604 Ventura Bl., Sherman Oaks, CA (213) 501-3486

Store Hours: M-F 10-6 Sat. 10-4

Orange Micro inc.

3150 E. LaPalma, Suite G, Anaheim, CA 92806

Phone order WELCOME; same day shipment. Free use of VISA & MASTER-CARD. COD's accepted. Manufacturer's warranty included on all equipment. Prices subject to revision.

CIRCLE 250 ON READER SERVICE CARD

Model I and III ROM Look Alikes

Model I and III ROM Look Alikes

Model I and III ROM Look Alikes

Joseph Cesaitis

Now that the Model III TRS-80 computer has made its way into the marketplace, it appears to have successfully replaced the Model I and left over 200,000 owners out in the cold with a software compatibility problem. Or has it?

Many Basic programs will run on both machines with few or no changes. Machine language programs which do not use any ROM code should function properly assuming no critical timing loops are used.

The Model III Z-80A CPU runs slightly (14%) faster than its predecessor. Machine language programs which utilize ROM routines may or may not have problems depending on the routine used.

Table 1 lists the addresses (from-to) which are identical in both machines. As you can see much of the code is identical (thank you, Tandy). In those cases where the from and to addresses are the same only a single byte matched. This table should aid those who wish to write machine language software for both machines, but only have access to one machine. □

Joseph Cesaitis, 10380 Launcelot Lane, Columbia, MD 21044.

0000-0002	0005-000D	0010-0046	0049-004F	0063-0065
0071-0081	0083-00A9	00AB-00AD	00AF-00B1	00B5-00C5
00C7-00E9	00EB-00FE	0102-0105	010B-010C	0110-0111
0116-0117	011C-011C	0122-0124	012D-01D9	01F0-01F0
01F2-01F2	01F5-01F7	0210-0211	0232-0234	0246-0246
025F-0263	0283-0283	02A8-02E1	02E5-03C1	03EA-03EA
0469-046A	0495-0495	049F-049F	04B8-04B8	050D-050D
0533-0533	05D0-05D0	05D4-0673	0708-124B	124E-1917
1919-191B	191D-1B5C	1B60-206C	206E-2072	2074-2074
2076-2076	20B9-20BB	20BD-20F6	20F8-213A	213C-2166
2168-2269	226F-2B84	2B89-2B8B	2B8F-2B90	2B94-2C1E
2C43-2C79	2C80-2C80	2C83-2C89	2C8D-2FFB	—

Table 1. Model I and Model III ROM comparison (start address-end address).

C L O A D M O N T H L Y

"all the fit that's news to load"

TRS-80 PROGRAMS ON CASSETTE

CLOAD Magazine for your Model I or III!

by Clyde Cload, star reporter

Goleta, Calif. You can get 7 or 8 programs on cassette, each month, that **CLOAD** directly into your **TRS-80** Model I or III!

A subscriber, too engrossed in trying to save the world from invading aliens (March, 1981 issue) to give his name, stated, "I receive a 30 minute cassette by First Class Mail each month containing some of the best games and educational programs I have ever played. Some are even in machine language!" Another **CLOAD** subscriber, Claudine Cload, could now "fit the computer into her schedule" thanks to the utilities and occasional disk programs she received from **CLOAD.** She was writing about it to all of the people on her mailing list (November, 1979 issue).

Get the news firsthand. Get a subscription to **CLOAD** Magazine.



The Fine Print:

Overseas rates slightly higher—please write for them.
Back issues available—ask for our list *
TRS-80 is a trademark of Tandy Corporation
California residents add 6% to single copies and anthologies. Programs are for Level II 16K, Model III 16K, and occasionally for disks.

*24 Level I back issues also available.

PRICES

1 year subscription	$42.00
6 month subscription	$23.00
Single copies	$4.50
Anthology volume 1	$10.00
Anthology volume 2	$15.00

Mastercard/Visa Welcome

CLOAD MAGAZINE INC.
P.O. Box 1448, Santa Barbara, CA 93102 805 962-6271 ©1981

CIRCLE 113 ON READER SERVICE CARD

TRS-80 sensational software

creative computing software

Board Games

Cassette CS-3001 $11.95 — 6 Programs — Requires 8K



Quibic A 3-dimensional tic-tac-toe type of game played in a 4x4x4 cube A real challenge

Backgammon (by Scott Adams) Excellent graphics and challenging play in this popular game.

Mugwump. Four friendly Mugwumps are hiding on a 10x10 grid. Can you find them all in ten moves?

Wumpus Try to find the Wumpus in a dodecahedron network of caves complete with bottomless pits and giant bats

Wumpus 2 Five different types of caves or create your own. More hazards too.

Flip Disc. Our version of Othello with three skill levels from good to expert.

Z-Chess III

Disk CS-3513 (32K) $24 95 — Cassette CS-3017 (16K) $19 95



This is one of the most sophisticated computer chess playing programs available today Seven different skill levels provide practice for the beginner as well as challenge the more experienced players. The speed of Z-Chess will also surprise you. Even at the highest skill level it is one of the fastest chess programs available.

Battle Games

Cassette CS-3012 $11.95 — 4 Programs — Requires 16K

GUNNER. Destroy enemy aircraft with your anti-aircraft gun.

SUB HUNT. Pursue and destroy a computer-controlled submarine.



TANK BATTLE. Two players battle it out in this real-time graphic game.



GETACROSS Evade the enemy in this real-time, sound game.

Stock & Options Analysis

Cassette CS-3306 (16K), $99 95
Disk CS-3801 (32K), $99 95

Should you hedge, buy, or sell out? **Stock and Options Analysis** puts a securities advisor in your computer, providing you with four powerful investment tools **Option** gives important indices for opening and closing call option transactions **Opgraph** presents a graph or table of profit for any combination of long or short calls, puts, and stocks This allows the detailed evaluation of three types of hedges. **Newprem** helps predict the future premiums of an option at any desired time and future stock price **Portval** lets the computer do the paper work, providing full portfolio services, including value per share, current value, and capital gain. The program includes the effects of commissions, margin interest and dividends Beyond helping to organize and evaluate your present portfolio, **Stock and Options Analysis** is an excellent aid for planning and testing future strategies The comprehensive 24-page manual with this package not only shows how the programs work, but is also a primer on the strategy of hedging listed options against common stocks This strategy has been repeatedly shown to actually be more conservative and more consistently profitable than straight buying and selling of stocks

Original Adventure

Disk CS-3518 (48K) $19 95

This is the original adventure game complete with a colossal cave populated with nasty little dwarves, a giant clam, trools and much, much more Includes the SAM76 language in which the game runs

Games Pack on Disk

Disks CS-3503 (32K) $39 95

This set of menu-driven disk contains all 20 games from cassettes CS-3001, CS-3002 CS-3004 and CS-3005

Order Today

To order any of these software packages send payment plus $2.00 postage and handling per order to Creative Computing Morris Plains, NJ 07950 Visa MasterCard and American Express orders may be called in toll-free

Order today at no risk It you are not completely satisfied your money will be promptly and courteously refunded

Creative Computing Software
Morris Plains NJ 07950
Toll-free 800-631-8112
In NJ 201-540-0445

creative computing software

TRS-80 is the registered trademark of Tandy Corp

PERIODIC TABLE



Dean Schmidt

Periodic Table is a program which produces a Periodic Table on the screen with each element symbol in its correct place. Three options are given. The first allows the user to select a group of elements, for example, the transition elements, which are shown in inverse on the periodic table. There are eleven different groups that can be selected.

Another option starts with the temperature in the upper left hand starting at absolute zero. As the temperature rises, each element changes to inverse on the screen as it reaches its melting point. When an element reaches its vaporization point its symbol is removed from the periodic table.

The third option is a variation of the second. The user may select a specific temperature and have the conditions shown for that temperature. For example, if 0° Celcius were chosen, each element that is a solid at that temperature is shown on the screen in normal characters. Each element that is a liquid is shown in inverse, and each element that is a gas is eliminated from the table.

The program is written in Pascal for the Apple II Plus with language card.

Sample runs of Periodic Table are shown here. If you would like a listing of the program, please send $1.00 with an SASE to: Magic City Campus, Minot H.S., Minot, ND 58701, Attn: Computer Club. For a disk containing the program, send $10 or $5 and a blank disk to the same address. □

Dean Schmidt, #1 Southwest 22nd St., Minot, ND 58701.







4 New Games From Hayden In the SARGON Tradition!

New! KLONDIKE 2000

(Trackman) A Space Age Treasure Hunt! An exciting new game of fabulous treasures, hidden caves and dangerous robots! The object: to become the richest player. Finding the gold is only half the battle . . . the other half is keeping it. You'll need robots to guard your fortune. How do you make a robot your ally? Simple - feed it more power chips than its previous owner did, or you can overcome the enemy with robots you have already won. For one to four players.

#10209, Apple II Disk, $24.95

New! TRS-80 GALAXY OF GAMES

(Savolaine, Dilley and Wilkerson) 4 For the Fun Of It! Choose from four challenging games and enjoy hours of fun!
HANGMAN - a word game enthusiasts will love this computerized classic that features excellent graphics! ONE ARM BANDIT - brings slot machine excitement into your own home. SKUNK - a unique dice game with special sound effects. JACKS - a card game to play with the computer or your friends; trade high cards for low cards and compete for the lowest point total

#09903, TRS-80 Models I and III, $14.95

ORDER TODAY!

Hayden Book Co., Inc
50 Essex St., Rochelle Park, NJ 07662

Please send me the software checked. Residents of NJ and CA must add sales tax. Name of individual ordering must be filled in. Offer good in US only. Payment must accompany orders from P.O. Box numbers.

☐ Enclosed is my check or money order.
☐ Please bill to my Master Card or VISA account #_____
Interbank #_____ Expiration Date #_____

☐ 01209	☐ 03440
☐ 03404	☐ 03444
☐ 03408	☐ 03484
☐ 03409	☐ 07403
☐ 03410	☐ 09809
☐ 03414	☐ 09903
☐ 03418	

Name _____
Address _____
City/State/Zip _____

CC 11/81-012

SARGON II

(Spracklens) The first great computer Chess program! "We are impressed with the program's speed, its opening book, and its much improved end game . . . Save your money and buy SARGON II . . ." *'80 Software Critique*. 7 levels of play, and levels 0-3 in tournament time. It has randomized opening book for all levels through three moves. Special hint mode included at all levels except 0 will suggest a good (but not necessarily the best!) move you can next make.

#03404, Apple II;
#03410, OSI C1P;
#03418, TRS-80 Models I and III;
#03440, OSI C4P;
each tape $29.95

#03408, TRS-80 Level II Disk;
#03409, Apple II Disk;
#03414, OSI C1P Disk;
#03444, OSI C4P Disk;
#03484, OSI C8P Disk;
each disk, $34.95

Available at your local computer store!

New! TETRAD

(Hess) Now try a 3-dimensional Tic Tac Toe and enjoy beautiful color, surprising sound and a choice of 3 levels of difficulty! A real challenge that allows 76 winning combinations. Tetrad adds a new dimension to a familiar game, as you battle the computer to get 4 in a row in any direction.

#09809, Apple II Disk, $19.95

New! MIND THRUST

(Sackson and Wazaney) Match wits with the computer! Be the first to complete a chain across the board. Switch sides at any time and control your opponent's pieces as he controls yours

#07403, TRS-80 Tape, $16.95

Other Hayden Gameware . . .

REVERSAL (Apple II)
BLACKJACK MASTER (TRS-80 Level II; Apple Version Soon to be Available)
BATTER UP!! A Microbaseball Game (TRS-80 Level II)
GRIDIRON: A Microfootball Game (TRS-80 Level II)

Soon to be available . . .

CHAMPIONSHIP GOLF
ALIBI
STAR TRADERS
ASTEROID BLASTER
QUICK SILVER/CRAZY COURSE
WORD SOLITAIRE

For Orders, Inquiries and Technical Support Call Toll Free

HAYDEN HOTLINE
800-631-0856

Hayden

50 Essex Street, Rochelle Park, NJ 07662 **Book Company, Inc.**

CIRCLE 205 ON READER SERVICE CARD

A Basic Generative Grammar Program

Kimball M. Rudeen

The article "Grammar as a Programming Language" (Jan/Feb 1978) contained examples of how to use the REPLACE command in Logo to generate sentences from syntactical rules. The following article shows how a similar approach can be done in Basic on the TRS-80.

This program was inspired by the article "Grammar as a Programming Language" in the Jan/Feb 1978 issue of *Creative Computing*. Since I had studied formal grammars in college, the idea of a program able to generate statements according to a given grammar was familiar and fascinating. I decided to write my own as soon as I had my own computer. The program described in this article is, I think, a decent attempt. It has all the necessary basic capabilities, plus a few frills which I found convenient.

The program, written in Basic for the TRS-80, is separated into five modes—Grammar, Generate, Edit, Read and Write. The capacities and operation of these modes are described in the following sections.

Figure 1.

```
MODE - GRAMMAR, GENERATE, EDIT, READ, WRITE, TERMINATE:
GRAMMAR
INPUT RULE - USE END TO HALT:
SEN=SUB VER OBJ
SUB=ARTICLE NOUN/NAME
VER=LIKES/HATES/SEES/RUNS AFTER
OBJ=ARTICLE NOUN
NAME=BILL/TOM/HARRY/JOE
END
```

Figure 2.

```
MODE - GRAMMAR, GENERATE, EDIT, READ, WRITE, TERMINATE:
GENERATE
INPUT START SYMBOL LIST - USE PERIOD TO END LIST AND END TO EXIT
GENERATE MODE.
1 SEN AND SEN
2 SEN
.
1 SUB VER OBJ AND SUB VER OBJ
1 NAME VER OBJ AND NAME VER OBJ
1 NAME SEES OBJ AND NAME RUNS AFTER OBJ
1 NAME SEES ARTICLE NOUN AND NAME RUNS AFTER ARTICLE NOUN
1 JOE SEES ARTICLE NOUN AND HARRY RUNS AFTER ARTICLE NOUN
2 SUB VER OBJ
2 ARTICLE NOUN VER OBJ
2 ARTICLE NOUN HATES OBJ
2 ARTICLE NOUN HATES ARTICLE NOUN
1 JOE SEES ARTICLE NOUN AND HARRY RUNS AFTER ARTICLE NOUN
2 ARTICLE NOUN HATES ARTICLE NOUN
FINISH
INPUT START SYMBOL LIST - USE PERIOD TO END LIST AND END TO EXIT
GENERATE MODE.
END
```

Grammar Mode

Grammar mode is used to input the rules of the chosen grammar. Rules are of the form

STRING = SUB1/SUB2/SUB3.../SUBN

where STRING is the string of characters to be replaced, and SUB1...SUBN are the possible replacement strings, separated in the rule by the "/" character. Recursion is allowed, and replacement strings may of course, be the initial strings of other rules. "Null" replacement strings, which replace an initial string with zero characters, are indicated by a double slash "//." Every time the Grammar or Read modes are entered, all previously defined rules are lost. An existing grammar may be modified by the edit commands (see Edit mode). Rules may be input by the user or read from tape, rules may be saved on tape (see Read/Write Mode). Figure 1 illustrates grammar input.

Generate Mode

Generate mode is used to input the list of strings to which the program will apply the grammar defined in the grammar mode. Each entry string may contain substrings not defined as an initial string in any grammar rule. Such substrings will not be changed by the program.

Each entry string will be treated separately. The program will continue to try the rules of the defined grammar against a given string, printing out intermediate results, until no more replacements can be made. If no grammar rule applies to a list entry, it will be left unchanged.

At the end of the process, the final result for each list entry will be printed out. The output subroutine is designed to avoid ending a line in the middle of a substring when possible. When this occurs, the subroutine will backtrack to a blank in the current string and end the line there. If no blank exists, the string will be printed as is. Note: a recursive grammar rule can generate an infinite loop. Figure 2 illustrates the operation of the Generate mode.

Kimball Rudeen, 57 Taft Ave., Lexington, MA 02173.

PUT YOUR COMPUTER IN ITS PLACE.

Don't be afraid of your computer. Tell it exactly what's on your mind and don't take no for an answer.

But first you'll have to understand it.

Without Me You're Nothing is the title and the spirit behind the new book by Frank Herbert, the author of *Dune*. You probably read excerpts in *Omni*. His straight talk about home computers straightens the record on just who's running the show.

Herbert rips through the fear by demystifying "computerese." He lays out the simple facts about how computers work. How to choose the system you need. And how to use it to defend yourself against the other guy's computer.

In plain English, you can learn to program your computer to do most anything. From balancing your checkbook to maintaining your car.

Once you understand your machine, you can get down to business. Demand results. And rest a little easier, knowing that the microchips aren't plotting against you.

On sale in time for Christmas, in oversize format. $5.95. Illustrated, and including a guide to computer magazines, microcomputer accessories and manufacturers, and a glossary of computer terms.

POCKET BOOKS, Department WMY
1230 Avenue of the Americas, New York NY 10020
Please send me_____copies of WITHOUT ME YOU'RE NOTHING.
I am enclosing $_____ (Please add 50¢ to cover postage and handling. NYS and NYC residents please add appropriate sales tax.) Send check or money order — no cash, stamps or CODs please. Allow six weeks for delivery.

NAME_____

ADDRESS_____

CITY_____STATE_____ZIP_____

At your bookseller now. Or use this coupon to order by mail.

POCKET BOOKS

```
MODE - GRAMMAR, GENERATE, EDIT, READ, WRITE, TERMINATE:
EDIT
EDIT - LIST, ADD, DELETE, MODIFY, QUIT:
EDIT:LIST
  1                 3/SEN/ 1/SUB VER OBJ/
  2                 3/SUB/ 2/ARTICLE NOUN/NAME/
  3                 3/VER/ 4/LIKES/HATES/SEES/RUNS AFTER/
  4                 3/OBJ/ 1/ARTICLE NOUN/
  5                 4/NAME/ 4/BILL/TOM/HARRY/JOE/
EDIT:DELETE
NAME
EDIT:MODIFY
SUB=ARTICLE ADJECTIVE NOUN
EDIT:ADD
ARTICLE=A/THE
EDIT:ADD
NOUN=CAT/DOG/BIRD/HORSE
EDIT:LIST
  1                 3/SEN/ 1/SUB VER OBJ/
  2                 3/SUB/ 1/ARTICLE ADJECTIVE NOUN/
  3                 3/VER/ 4/LIKES/HATES/SEES/RUNS AFTER/
  4                 3/OBJ/ 1/ARTICLE NOUN/
  5                 7/ARTICLE/ 2/A/THE/
  6                 4/NOUN/ 4/CAT/DOG/BIRD/HORSE/
EDIT:QUIT
```

Figure 3.

Edit Mode

Edit mode is used to modify an existing grammar. There are four commands: List, Add, Delete, and Modify. The List command will list the current grammar rules in their storage format. This consists of the original Grammar mode input format, plus two count values giving the length in characters of the initial string and the number of possible replacement strings.

The Add and Modify commands allow new rules to be changed. The Modify command requires the modified rule to be specified completely. The Delete string needs to be given. Figures 3 and 4 illustrate the operation of the Edit mode.

Read/Write Modes

Read/write modes are used to input or store in a grammar. I/O facilities may have to be provided by the user. The subroutines shown are designed for my machine, a TRS-80. These modes will save the trouble of redefining a complex grammar.

Applications

Applications of this program are many and varied. The examples given suggest demonstrating the rules of English grammar. The same rules defined "in reverse" would analyze a given sentence into its component parts. This program can be used to generate or analyze bars of music, statements in languages such as Pascal, graphic commands, or speech synthesizer commands—almost anything defined by a grammar.

Extensions

There is, of course, plenty of room for improvement. In the current program, the length of a generated string is limited to the length of a single string variable. It should be possible to generate into a string array rather than a single variable. Another possibility is special command characters to control output, such as a "#" character causing a skip to a new line. Additional features will suggest themselves with experience. □

Figure 4.

```
MODE - GRAMMAR, GENERATE, EDIT, READ, WRITE, TERMINATE:
GENERATE
INPUT START SYMBOL LIST - USE PERIOD TO END LIST AND END TO EXIT
GENERATE MODE.
SEN
.
SUB VER OBJ
ARTICLE ADJECTIVE NOUN VER OBJ
ARTICLE ADJECTIVE NOUN HATES OBJ
ARTICLE ADJECTIVE NOUN HATES ARTICLE NOUN
A ADJECTIVE NOUN HATES A NOUN
A ADJECTIVE BIRD HATES A BIRD
A ADJECTIVE BIRD HATES A BIRD
FINISH
INPUT START SYMBOL LIST - USE PERIOD TO END LIST AND END TO EXIT
GENERATE MODE.
END
MODE - GRAMMAR, GENERATE, EDIT, READ, WRITE, TERMINATE:
TERMINATE
```


apple computer
Sales and Service

Apple II Plus 48K-$Call Toll Free

ATARI ATARI

Epson MX-80 F/T

Z80 Softcard	$319.00
16K RAM Card	$159.00
Videx 80 Col	$289.00
NEC 12" Green Monitor	$ CALL
Zenith 12" Green Monitor	$ CALL

APPLE OWNERS! Intercept Worldwide Press & Gov't Agencies—Call Us For Our Short-Wave Package Price!

THE COMM CENTER
Open Tuesday thru Saturday
Laurel Plaza-198, Laurel, MD 20810
MD: 301-792-0600
CALL TOLL FREE
1-800-638-4486

CIRCLE 134 ON READER SERVICE CARD

NEW FOR THE APPLE III

DATA MANAGER III

This data base management system is especially designed for the Apple III. It can be used with a floppy disk or up to 50 M.G., hard disk drive. Easy to use. Easy to understand. Data Manager III has the power, speed, and flexibility that delivers the results you expect from your Apple III. Coming to your Apple dealer soon.

NEW FOR THE APPLE II

MERGER

COMPATIBLE

THE DATA FACTORY

THE INVOICE FACTORY

Merge information from the fields of any Data Factory or Invoice Factory file to any other Data Factory or Invoice Factory file.

We saved at least five hundred dollars the first week we used this program. We wanted to change the account numbers of our customers. There were invoices in a Data Factory file going back a year and a half, and our customer file contained 750 dealers around the world. Quite a job to change all those records. Using The Data Factory and the Merger we completed the job in a morning!

The Merger is easy to use. Just specify a field common to both data base files. Then list which fields to merge from one data base to the other. Press RETURN and the Merger does the rest. The Data Factory, The Invoice Factory and The Merger are partners to get your work done quickly.

© 1981, Micro Lab, Inc
Apple is a trademark of Apple Computers, Inc

micro lab

systems that work

2310 Skokie Valley Road
Highland Park, IL 60035 • 312-433-7550

CIRCLE 155 ON READER SERVICE CARD

Generate Program Listing

```
10 REM    GENERATE! A GENERATIVE GRAMMAR PROGRAM
20 REM              BY KIMBALL M. RUDEEN
30 CLS
40 CLEAR 3000
50 RANDOM
60 DEFINT A-Z
70 DIM COM$(50), ND$(25)
75 REM  SELECT OPERATING MODE
80 PRINT "MODE - GRAMMAR, GENERATE, EDIT, READ,
   WRITE, TERMINATE    :"
90 INPUT M$:IF LEFT$(M$,3)="TER" END
100 IF LEFT$(M$,3)="GRA" GOTO 160
110 IF LEFT$(M$,3)="EDI" GOTO 2000
120 IF LEFT$(M$,3)="GEN" GOTO 220
130 IF LEFT$(M$,3)="REA" GOTO 4000
140 IF LEFT$(M$,3)="WRI" GOTO 5000
150 GOTO 80
155 REM  GRAMMAR RULE INPUT
160 CC=0
170 PRINT "INPUT RULE - USE END TO HALT:"
180 INPUT CC$
190 IF CC$="END" GOTO 80
200 GOSUB 1000
210 GOTO 180
215 REM  STRING GENERATION: INPUT START SYMBOLS
220 PRINT "INPUT START SYMBOL LIST - USE PERIOD
    TO END LIST AND END TO EXITGENERATE MODE."
230 CSD=0
240 INPUT ISD$
250 IF ISD$="." GOTO 280
260 IF ISD$="END" GOTO 80
265 REM  STRING GENERATION: SCAN STRINGS
270 CSD=CSD+1:ND$(CSD)=ISD$:GOTO 240
280 CD=0
290 CD=CD+1:IF CD)CSD GOTO 820
300 SD$=ND$(CD):CF=0:CL=0
310 CF=CF+1:CN=0
320 IF CF)CC GOTO 810
330 LN=VAL(COM$(CF))
340 M=4
350 IF LN)9 M=M+1
360 SUB$=MID$(COM$(CF),M,LN)
370 PS=0
380 LSD=LEN(SD$)
390 PS=PS+1
400 IF PS)LSD-LN+1 GOSUB 690:GOTO 310
410 NN=LN+PS-1
420 IF SUB$=MID$(SD$,PS,LN) OOTO 440
430 GOTO 390
435 REM  REPLACE STRINGS
440 LC=LEN(COM$(CF)):CL=1
450 M=LC-LN-4:IF LN)9 M=M-1
460 CN=VAL(RIGHT$(COM$(CF),M))
470 CM=INT(CN*RND(0))+1
480 PSD$=LEFT$(SD$,PS-1)
490 L1=LN+7
500 IF LN)9 L1=L1+1
510 IF CN)9 L1=L1+1
520 SN=0
530 FOR I=L1 TO LC
540 IF MID$(COM$(CF),I,1)="/" SN=SN+1
550 IF SN<>CM GOTO 500
560 NEXT I
570 PRINT "ERROR":CM,SN:GOTO 820
580 FI=I+1:GM=0
590 FOR I=FI TO LC
600 CH$=MID$(COM$(CF),I,1)
610 IF CH$="/" OOTO 650
620 PSD$=PSD$+CH$
630 GM=GM+1
640 NEXT I
650 IF GM=0 NN=NN+1
660 I=LSD-NN
670 IF I)0 PSD$=PSD$+RIGHT$(SD$,I)
680 SD$=PSD$:ND$(CD)=SD$:PS=PS+GM-1:GOTO 380
685 REM  OUTPUT GENERATED STRINGS
690 IF CN=0 GOTO 800
700 LSD=LEN(SD$):M=1
710 LD=63
720 IF LSD-M+1)63 GOTO 750
730 PRINT MID$(SD$,M,LSD-M+1)
740 OOTO 800
750 FOR I=1 TO 63
760 IF MID$(SD$,M+LD,1)()" " LD=LD-1:NEXT I
770 IF LD(>0 PRINT MID$(SD$,M,LD) ELSE PRINT
    MID$(SD$,M,63)
780 IF LD(>0 M=M+LD+1 ELSE M=M+63
790 GOTO 710
800 RETURN
805 REM  CONTINUE GENERATION OR TERMINATE
810 IF CL(>0 OOTO 300 ELSE GOTO 290
820 PRINT:CN=1
830 FOR CD=1 TO CSD
840 SD$=ND$(CD):GOSUB 690
850 NEXT CD
860 PRINT "FINIBH":GOTO 220
870 END
895 REM  REPLACE RULE CF IN LIST
900 SC=CC
910 CC=CF-1
920 GOSUB 1000
930 CC=SC
940 RETURN
995 REM  ADD GRAMMAR RULE TO LIST
1000 CC=CC+1:CE=1:CA=0
1010 FOR I=1 TO LEN(CC$)
1020 IF MID$(CC$,I,1)="/" CE=CE+1
1030 IF MID$(CC$,I,1)="=" CA=I
1040 NEXT I
1050 COM$(CC)=STR$(CA-1)+"/"+LEFT$(CC$,CA-1)
1060 COM$(CC)=COM$(CC)+"/"+STR$(CE)+"/"
1070 COM$(CC)=COM$(CC)+RIGHT$(CC$,LEN(CC$)-CA)+"/"
1080 RETURN
2000 PRINT "EDIT - LIST, ADD, DELETE, MODIFY, QUIT:"
2005 REM  EDIT GRAMMAR RULES
2010 INPUT "EDIT:"!E$
2020 IF E$="LIST" GOTO 2080
2030 IF E$="ADD" OOTO 2100
2040 IF LEFT$(E$,3)="DEL" GOTO 2130
2050 IF LEFT$(E$,3)="MOD" GOTO 2220
2060 IF E$="QUIT" OOTO 80
2070 OOTO 2010
2080 FOR I=1 TO CC:PRINT I,COM$(I):NEXT I
2090 GOTO 2010
2100 INPUT CC$
2110 GOSUB 1000
2120 OOTO 2010
2130 INPUT SUB$
2140 LNN=LEN(SUB$)
2150 OOSUB 3000
2160 IF CF=0 PRINT "NOT FOUND":OOTO 2010
2170 FOR I=CF+1 TO CC
2180 COM$(I-1)=COM$(I)
2190 NEXT I
2200 CC=CC-1
2210 OOTO 2010
2220 INPUT CC$
2230 LN=0
2240 FOR I=1 TO LEN(CC$)
2250 IF MID$(CC$,I,1)()"=" LN=LN+1:NEXT I
2260 SUB$=LEFT$(CC$,LN)
2270 GOSUB 3000
2280 IF CF=0 PRINT "NOT FOUND":OOTO 2010
2290 GOSUB 900
2300 OOTO 2010
2995 REM  LOCATE GRAMMAR RULE
3000 FOR CF=1 TO CC
3010 IF LN()VAL(COM$(CF)) OOTO 3040
3020 M=4:IF LN)9 M=M+1
3030 IF SUB$=MID$(COM$(CF),M,LN) OOTO 3060
3040 NEXT CF
3050 CF=0
3060 RETURN
3995 REM  INPUT GRAMMAR RULES
4000 CC=0
4010 INPUT#-1,CC$
4020 IF CC$="END" GOTO 80
4030 CC=CC+1:COM$(CC)=" "+CC$:OOTO 4010
4995 REM  WRITE GRAMMAR RULES
5000 FOR CF=1 TO CC:PRINT#-1,COM$(CF):NEXT
5010 PRINT#-1,"END":GOTO 80
```

ECHO SERIES™ SPEECH SYNTHESIZERS

COMPUTERS ARE SPEAKING OUT!

Now you can add intelligible speech to your computer without using vast amounts of memory! The ECHO][™ speech synthesizer for the Apple* is the first of a series of synthesizers based on the same technology that made the Speak & Spell** a success.

The initial operating system allows the creation of your own vocabulary with phonemes (word sounds) while using very little RAM memory (approx. 800 bytes + 20 bytes/word). Enhanced operating systems and vocabulary ROMs will be offered as they become available.

The ECHO][™ comes complete with speaker, instruction manual, and a disk containing a speech editor, sample programs, and a sample vocabulary. Suggested list price is $225.

See your dealer or contact:

SEC STREET ELECTRONICS CORPORATION
3152 E. La Palma Ave., Suite C
Anaheim, CA 92806 (714) 632-9950

*Trademark of Apple Computer
**Trademark of Texas Instruments

CIRCLE 258 ON READER SERVICE CARD

NEW APPROACH TO LEARNING

SAT
English 1
By Eileen Shapiro

Did you ever choose an answer on an exam and

A) think it was wrong, but got it right.
B) were sure it was right — it wasn't!
C) made a lucky guess and wondered how.
D) think you were right, but not sure why.
E) all of the above

With these unique tutorial programs, you will be shown why your answer was right or wrong. Learning becomes fun when you understand the reasoning behind a choice.

The ENGLISH SAT I (which provides aid in the verbal section — Antonyms, Analogies, Sentence Completions, and Reading Comprehension), of the Scholastic Aptitude Tests, and the U.S. CONSTITUTION TUTOR (to help prepare for any level exam in U.S. Government) are currently available for an Apple II computer with 48K and a disk drive at $30 each.

★★ U.S. ★★
Constitution
TUTOR
By Myrna Helfand

© 1981 Micro Lab, Inc
Apple is a trademark of Apple Computers, Inc

micro lab learning center
systems that work

2310 Skokie Valley Road • Highland Park, IL 60035 • 312-433-7560

CIRCLE 156 ON READER SERVICE CARD

Henri Picciotto

PET Screen Line Length

Notes on Overcoming Some Strange Problems on the PET

The fact that on the PET screen a line has 40 characters, while a logical line can have up to 80 (actually 79), leads to some tricky situations.

When you press the RETURN key, the PET enters your input into memory. This applies to entering direct mode commands, Basic program lines, or inputs during a program RUN. Your input is picked up off the screen, not directly from the keyboard as on many other computers. (Actually the screen buffer in memory—Ed.) This has many advantages: for instance, it allows you to enter a modifed version of a Basic program line without having to retype the whole line. However, to do this properly, The PET must know whether it is expected to pick up input off a 39- or a 79- character line. The length of the current line (39 or 79) is stored at memory location 213 (242 in the old ROMs). The program entitled Experiment 1 will allow you to check this out for yourself, by entering various values for M. The PET also needs to know where the line in questions begins. This information is kept at memory locations 196-197 (224-225 on the old ROMs).

When the cursor is on a given line on the screen, the PET generally assumes that it is a 39-character line. However, if a character has been printed in the 40th position of the same screen line, the PET will assume that the cursor is in the first half of a 79-character line. If a character has been printed in the 40th position of the preceding screen line, the PET assumes that the cursor is in the second half of a 79-character line. (There is one exception. "Printing" a cursor movement through the 40th position of a screen line does not affect the length of the logical line. To verify this, put a "cursor right" instead of a graphic character on line 120 of Experiment 1.) This feature usually works to the user's advantage by allowing him to enter Basic program lines or INPUTs of up to 79 characters automatically. However, there are situations where this arrangement causes problems.

One such situation is when a program prints a carriage return while the cursor is in the first half of a 79-character line. What happens then is that the cursor is sent to the beginning of the next logical line, which is one screen line below the location expected by the user. For example, try writing a program that will draw a box, 40 characters wide and 12 characters high, and then number the 10 lines in the box, producing the result shown in Figure 5. Of course, there are several ways to do this. (Feel free to find your own before reading on.) Program 1 shows one way to draw the box using PRINT statements. However the program runs into trouble when trying to number the lines (see Figure 1). The 1 is in the second half of a 79-character line, so the carriage return, generated by the lack of a semi-colon after the "Z" in line 180, works normally. But the numbers 2 through 6 are in the first halves of 79-character lines, and the carriage return skips a screen line

```
100 REM     EXPERIMENT  1
110 INPUT M
120 FOR Z=1 TO M : PRINT "■".   NEXT
130 PRINT PEEK(213)
140 RUN
```

Experiment 1.

```
1
2
3
4
5
6
7
8
9
10
READY
■
```

Figure 5. Program 1B, 1C or 1D output.

```
100 REM   PROGRAM  1
110 PRINT "□";
120 FOR Z=1 TO 40 : PRINT "■"; : NEXT
130 FOR Z=1 TO 10
140 : PRINT "■■■■■";
150 NEXT
160 FOR Z=1 TO 40 : PRINT "■"; : NEXT
170 PRINT "■■";
180 FOR Z=1 TO 10 : PRINT "■" Z : NEXT
```

Program 1.

Henri Picciotto, 1805 Monterey Avenue, Berkeley, CA 94707.

Yes! I want to make the most of my computer. Send me:

Quan.	Item	Price	Total
____	Basic Computer Games	$7.95	____
____	More Basic Computer Games	7.95	____
____	Computers For Kids—Apple	3.95	____
____	Computers For Kids—TRS-80	3.95	____
____	Computers For Kids—Atari	3.95	____
____	Computers in Mathematics	15.95	____
____	Blister Ball (48K) Apple Disk	29.95	____
____	Air Traffic Controller:		
____	Apple Disk (16K)	19.95	____
____	Apple Cassette (16K)	11.95	____
____	Atari Disk (24K)	19.95	____
____	Atari Cassette (16K)	14.95	____
____	TRS-80 Disk (32K)	19.95	____
____	TRS-80 Cassette (16K)	11.95	____
____	Computer Music Record	6.00	____
____	48-page catalog	FREE	____
		SUBTOTAL	____

Order Toll Free in continental U.S.
800-631-8112
In NJ call 201-540-0445

creative computing

Magazine and Term	USA	Canada and Foreign Surface	Foreign Air
Creative Computing			
1-year (12 issues)	☐ $20	☐ $29	☐ $50
Small Business Computers			
1-year (6 issues)	☐ $12	☐ $18	☐ $28
Microsystems			
1-year (6 issues)	☐ $10	☐ $15	☐ $25

Books, Records, Games ____
$3 USA, $6 Foreign Shipping Charge ____
NJ residents add 5% sales tax ____
Magazine subscriptions ____
TOTAL ____

☐ Check or Money order enclosed (U.S. funds only)
☐ VISA ☐ MasterCard ☐ American Express

Card number

Expiration Date Signature

Name ____
Address ____
City ____ State ____ Zip ____

Yes! I want to make the most of my computer. Send me:

Quan.	Item	Price	Total
____	Basic Computer Games	$7.95	____
____	More Basic Computer Games	7.95	____
____	Computers For Kids—Apple	3.95	____
____	Computers For Kids—TRS-80	3.95	____
____	Computers For Kids—Atari	3.95	____
____	Computers in Mathematics	15.95	____
____	Blister Ball (48K) Apple Disk	29.95	____
____	Air Traffic Controller:		
____	Apple Disk (16K)	19.95	____
____	Apple Cassette (16K)	11.95	____
____	Atari Disk (24K)	19.95	____
____	Atari Cassette (16K)	14.95	____
____	TRS-80 Disk (32K)	19.95	____
____	TRS-80 Cassette (16K)	11.95	____
____	Computer Music Record	6.00	____
____	48-page catalog	FREE	____
		SUBTOTAL	____

Order Toll Free in continental U.S.
800-631-8112
In NJ call 201-540-0445

creative computing

Magazine and Term	USA	Canada and Foreign Surface	Foreign Air
Creative Computing			
1-year (12 issues)	☐ $20	☐ $29	☐ $50
Small Business Computers			
1-year (6 issues)	☐ $12	☐ $18	☐ $28
Microsystems			
1-year (6 issues)	☐ $10	☐ $15	☐ $25

Books, Records, Games ____
$3 USA, $6 Foreign Shipping Charge ____
NJ residents add 5% sales tax ____
Magazine subscriptions ____
TOTAL ____

☐ Check or Money order enclosed (U.S. funds only)
☐ VISA ☐ MasterCard ☐ American Express

Card number

Expiration Date Signature

Name ____
Address ____
City ____ State ____ Zip ____

987654321

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 738 MORRISTOWN, NJ

POSTAGE WILL BE PAID BY ADDRESSEE

creative computing

P.O. Box 789-M
Morristown, New Jersey 07960

987654321

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 738 MORRISTOWN, NJ

POSTAGE WILL BE PAID BY ADDRESSEE

creative computing

P.O. Box 789-M
Morristown, New Jersey 07960

Get The Most From Your Small Computer

Magazines

Creative Computing:
The magazine for everyone

Creative Computing has four things that set it apart from other magazines. (1) Hard-hitting, in-depth, honest evaluations of computers, peripherals and software. (2) An incredible diversity of applications and software that readers can run directly. (3) Award-winning articles by top thinkers and doers in the field. (4) A unique style combining clarity, integrity and flair.

As the premier magazine for beginners, it is our solemn responsibility to make computers comprehensible to the newcomer. However, beginners become experts remarkably quickly so we publish applications and programmming techniques for all levels of expertise. It is our goal to publish the new and important ideas of the field in such a way that a 14-year old student, a business manager or a relaxing professional can understand and use them.

Along with tutorial articles and new applications, we present the hardest-hitting evaluations in the field. New systems, peripherals and software are reviewed in depth and without bias. We feel that our first obligation is to our readers and that editorial excellence and integrity are our highest goals. $20 per year.

Small Business Computers:
The magazine for the businessperson

Small Business Compters provides timely product information, tutorials, reviews, and applications for mini, micro and pocket computers. Contributors are experts in their fields and adept at providing pragmatic information to businessmen who realize the benefit of making the mos efficient use of their computer systems. $12 per year.

Microsystems:
For the CP/M and S/100 user

Each bi-monthly issue of *Microsystems* has articles, applications with complete program listings, tutorials, and new product news especially for users of CP/M and S-100 systems. Emphasis is on Pascal, C, and other development languages. $10 per year.

Books

Basic Computer Games:
More Basic Computer Games

Why have half a million people purchased these books? Obviously, one reason is to play the great selection of 185 games and simulations, ranging from classics such as *Hurkle* and *Star Trek* to historically important programs such as *Eliza*, the therapist program. Another reason is to learn Basic. There is, perhaps, no better way to gain an understanding of the language than through program listings. You can learn while you evade a man-eating rabbit, crack a safe, tame a wild horse, become a millionaire, race your Ferrari, trek across the desert on your camel and much more. Both books are in standard Microsoft Basic. $7.95 each.

Computers for Kids:
Starting Out Early

This popular book provides children with a complete, easy-to-understand, step-by-step guide to programming in Basic. No need to know algebra; suitable for ages 8 and up. The book gets quickly into graphics for each computer, and includes many sample programs.

A section for parents and teachers offers teaching ideas for each chapter. *Computers for Kids* comes in three editions: TRS-80, Apple and Atari. $3.95 each.

Computers In Mathematics:
A Sourcebook of Ideas

This huge 224-page sourcebook contains sections on computer literacy, problem solving techniques, art and graphics, simulations, computer assisted instruction, probability, functions, magic squares, and programming style. One section includes over 250 problems, puzzles, and programming ideas.

Pragmatic, ready-to-use classroom ideas are presented for everything from binary numbers to advanced techniques such as multiple regression analysis and differential equations. Includes program listings and sample runs. $15.95

Software

Air Traffic Controller:
You're in the hot seat

Try this game and you'll understand the recent threatened strike. This simulation gives the player real-time control over 27 craft that enter his air space. Give the right orders and there's no problem. But send two planes to the same runway and watch out! Written by an actual air traffic controller, it has variable skill levels and realistic detail that will keep you challenged for months. Land one of your own on the TRS-80, Apple or Atari.

Blisterball:
Fast-paced Apple Game

A frantic, fast-paced romp that can be played for hours, *Blisterball* is the first truly original arcade-type game for a home computer. As the bouncing balls drop from above, the player moves his laser base and tries to shoot them. It's easy at first—with just one ball. Then come two, then three. It's getting harder. Four balls come, and finally five. Surviving them, the player gets to shoot at inelastic bonus balls. If he makes it this far, the second round starts. The balls bounce lower, the walls close in. Shades of Poe and Newton! Making superb use of Apple graphics and sound, *Blisterball* can be played by one or two people. $29.95.

Computer Music Festival Record
Bach to Beatles in Binary

This 12" LP of the Philadelphia Computer Music Festival features 8 different computer music synthesizers programmed to play the music of J.S. Bach, J. Pachelbel, Rimsky Korsakov, Scott Joplin, Neil Diamond, Lennon and McCartney, and seven others. The music ranges from Baroque to Rock. Traditional to Rag, and even includes an historic 1963 computerized singing demonstration by Bell Labs. $6.00.

The Catalog
250 Other Great Products

Free 48-page catalog describes 20 books on programming, games, and educational applications; 160 software packages for six popular computers; five peripherals; and many other products for personal computer users.

Morris Plains, NJ 07950

creative computing

```
1
2
3
4
5
6
7
8
9
10

READY
■
```

Figure 1. Program 1 output.

every time. Outside the box, the lines are 39-character lines, so that the carriage return functions as expected.

Another problem arises in the use of the TAB function, which counts the columns starting at the beginning of the logical line. This can be quite confusing if the cursor is in the second half of a 79-character line and the program prints a TAB(5), for example. Much to the user's surprise, nothing happens! The reason is that the cursor is already beyond the 40th column, and one cannot TAB backwards.

```
     1
     2
     3
     4
     5
     6
     7
     8
     9
    10

READY
■
```

Figure 6. Program 2B, 2C or 2D output.

```
1
    2
3
    4
5
    6
7
    8
9
    10

READY
■
```

Figure 2. program 2 output.

```
100 REM   PROGRAM 1A
110 PRINT "J";
120 FOR Z=1 TO 39 : PRINT "■";   NEXT
130 PRINT
140 FOR Z=1 TO 10
150 : PRINT "■" SPC(37) "■"
160 NEXT
170 FOR Z=1 TO 39 : PRINT "■";   NEXT
180 PRINT "■M";
190 FOR Z=1 TO 10 : PRINT "■" Z : NEXT
```

Program 1A.

```
100 REM  PROGRAM 2
110 PRINT "J";
120 FOR Z=1 TO 40 : PRINT "■";   NEXT
130 FOR Z=1 TO 10
140 : PRINT "■■■■■";
150 NEXT
160 FOR Z=1 TO 40 : PRINT "■"; : NEXT
170 D$="■"
180 FOR Z=1 TO 10
190   D$=D$+"N"
200   PRINT D$ TAB(5) Z
210 NEXT
```

Program 2.

```
100 REM   PROGRAM 2A
110 PRINT "J";
120 FOR Z=1 TO 39 : PRINT "■";   NEXT
130 PRINT
140 FOR Z=1 TO 10
150 : PRINT "■" SPC(37) "■"
160 NEXT
170 FOR Z=1 TO 39 : PRINT "■":   NEXT
180 PRINT "■M";
190 FOR Z=1 TO 10
200 : PRINT TAB(5) Z
210 NEXT
```

Program 2A.

Try running Program 2, which is intended to yield the display shown in Figure 6. Variable D$ is there to help avoid the problem of line skipping we encountered in Program 1. However, the result, shown in Figure 2, is not quite what we intended: the odd numbers were not TABbed. This is because they were in the second half of a 79-character line, and the TAB argument should have been 45, not 5.

There are various ways to get around these difficulties. The simplest is to avoid printing in the last column. This will guarantee that the line length is consistently 39 throughout the program, thereby solving the problems. (This suggestion refers to printing under program control, not to the keying in of the program, which of course should take advantage of the 79-character line possibility.) Programs 1A and 2A use this

LEARN

Having trouble learning to use your computer?

Reference manuals don't teach. Most BASIC texts don't cover specific personal computers.

TIS solves these problems with step-by-step books tailored for your machine.

For PET/CBM

Understanding Your PET/CBM $16.95
Vol 1: Basic Programming
PET Graphics ..... $ 6.95

For OSI CIP/C4P

Understanding Your C1P/C4P ..... $ 9.95
A Workbook of BASIC Exercises

For VIC

Understanding Your VIC $13.95
Vol. 1: Basic Programming

Money Back Guarantee VISA/MC accepted
All prices include UPS or 1st Class postage

TIS INC

Total Information Services, Inc.
Box 921, Dept. CC
Los Alamos, NM 87544

CIRCLE 193 ON READER SERVICE CARD

A.N.A.L.O.G. 400/800 MAGAZINE

SUPPORTING THE ATARI 400* AND 800* COMPUTERS*

- Practical Applications • Personal Finance
- Games • Video Computer Update
- Business • Hardware Reviews
- Education • Program Printouts
- New Product Reviews • Contests
- Questions and Answers • Music
- Software Reviews • Classifieds
- Readers Comments • Tutorials

Subscribe Today!

$12.00 USA 1 year (6 issues bi-monthly) — $20.00 Foreign (surface mail) — Sample issue $2.00

A.N.A.L.O.G. 400•800 Magazine®
P.O. BOX 23, WORCESTER, MA 01611
(617) 892-3488

VISA — MasterCard

® Trademarks of Atari Inc.

CIRCLE 255 ON READER SERVICE CARD

the learning system.™ BY SCOT KAMINS, Ph.D.

Your Computer Costs You Nothing

New Training Device

Training is one of your most expensive costs in conducting business. When an employee leaves or is promoted, and a new person must take over, how long will the supervisor or manager be taken away from his job? How much time will be lost, money wasted, and other important work delayed until the new person is trained and the instructor freed to catch up with the projects interrupted by that training? By using The Learning System with an Apple computer to train just one or two employees, you can reduce your training costs and pay for the entire computer system.

Anyone Can Use It

There is no programing skill or special instruction needed to set-up or operate the program. The Learning System operates like a word processor. Simply type in the job description or training program; then make up the test questions (fill-in, multiple choice, or column match) to correspond to specific sections of the information. Using the tutorial mode, the employee gets hints, encouragement, and repeated exposure to the information, progressing at his own rate until he feels confident enough to use the exam mode (which does not offer additional help) to truly test the knowledge required for the job. Those results can then be scored, analyzed, or averaged with others.

Many Office Applications

Place job descriptions in your computer disk library. Employees will enjoy learning new jobs or additional skills on the computer. Your personnel manager can present a general survey of the company to a waiting applicant and observe his learning comprehension before the interview.

With The Learning System, learning is a positive experience that will reinforce the desire to learn more. When people enjoy learning they will catch-on quicker and more effectively. Your time and money are saved — and an individual's motivation to learn increases.

This description of The Learning System is meant to stimulate your thoughts about its applications in your office. The system has so much potential that only a brief summary of its features can be described here. See a demo at your local Apple dealer. The Learning System is priced at an introductory offer of $150.

© 1981, Micro Lab, Inc
Apple is a trademark of Apple Computers, Inc

micro lab learning center
systems that work

2310 Skokie Valley Road • Highland Park IL 60035 • 312 433-7550

CIRCLE 153 ON READER SERVICE CARD

```
 1
 2
 3
 4
 5
 6
 7
 8
 9
 10

READY
■
```

Figure 3. Program 1A output.

```
     1
     2
     3
     4
     5
     6
     7
     8
     9
     10

READY
■
```

Figure 4. Program 2A output.

```
100 REM     EXPERIMENT  2
110 S=32768
120 INPUT M
130 PRINT "□";
140 FOR Z=S TO S+M : POKE Z,102 : NEXT
150 PRINT "M" PEEK(213)
160 RUN
```

Experiment 2.

```
100 REM   PROGRAM  1B
110 PRINT "□";
120 FOR Z=1 TO 39 : PRINT "*",   NEXT
130 GOSUB 240  : PRINT
140 FOR Z=1 TO 10
150 : GOSUB 240
160 : PRINT "*"
170 NEXT
180 FOR Z=1 TO 39 : PRINT "*"; : NEXT
190 GOSUB 240
200 PRINT "M";
210 FOR Z=1 TO 10   PRINT "M" Z   NEXT
220 END
230
240 EL=256*PEEK(197)+PEEK(196)+39
250 POKE EL,102
260 RETURN
```

Program 1B.

```
100 REM  PROGRAM  2B
110 PRINT "□";
120 FOR Z=1 TO 39 : PRINT "*"; : NEXT
130 GOSUB 260 : PRINT
140 FOR Z=1 TO 10
150 : GOSUB 260
160 : PRINT "*"
170 NEXT
180 FOR Z=1 TO 39 : PRINT "*"; : NEXT
190 GOSUB 260
200 PRINT "M";
210 FOR Z=1 TO 10
220 : PRINT TAB(5) Z
230 NEXT
240 END
250 :
260 EL=256*PEEK(197)+PEEK(196)+39
270 POKE EL,102
280 RETURN
```

Program 2B.

approach, and yield the displays shown in Figures 3 and 4, which closely resemble our original goal.

Another solution, if you must put a character in the last column, is to POKE it there. This is easy to do if you know the address you need to POKE. (If you don't, use the routine at the end of Program 1B and 2B to figure it out. The routine PEEKs into the memory locations mentioned above and adds 39 to get to the end of the screen line. Note that the routine assumes that the cursor is placed on the line whose last column you want POKEd.) While printing a character in the 40th position affects the length of the logical line, poking a character there does not. Use Experiment 2 to check this. Programs 1B and 2B use this fact to yield the desired display. Of course the entire box could have been POKEd onto the screen.

```
100 REM     PROGRAM  1C
110 PRINT "□";
120 FOR Z=1 TO 40   PRINT "*".   NEXT
130 FOR Z= 1 TO 10
140   PRINT "M[illegible]";
150 NEXT
160 FOR Z=1 TO 40 : PRINT "*",   NEXT
170 PRINT "M";
180 FOR Z= 1 TO 10
190 : PRINT "M" Z;
200   P=POS(0) : LL=PEEK(213)
210   IF P<40 AND LL=79 THEN UP$="□"
220 : PRINT   PRINT UP$:   UP$=""
230 NEXT
```

Program 1C.

APPLE DISK & MEMORY UTILITY

- Repairs Blown Disks
- Reads Nibbles
- Maps Disk Space
- Searches Disks
- Searches Memory
- Edits Disk Sectors
- Outputs Screen to Printer
- Displays Memory In HEX/ASCII

THE INSPECTOR

These utilities enable the user to examine data both in the Apple's memory and on disks. Simple commands allow scanning through RAM and ROM memory as well as reading, displaying and changing data on disk

Read and rewrite sections of Random Access files Reconstruct a blown VTOC Weed out unwanted control characters in CATALOG listings UnDELETE deleted files or programs Repair files that have erroneous data All without being under program control and more

You may transfer sectors between disks This allows you to transfer DOS from one disk to another thereby saving a blown disk when all that's blown is DOS itself, or to restore a portion of a blown disk from its backup disk

Its unique NIBBLE read routine provides a Hi Res graphical representation of the data on any track allowing you to immediately ascertain whether your disk is 13 sector or 16 sector Get an I O error is it because you have the wrong DOS up? is it because of a bad address field? or a bad data field? or because a track was erased? This will allow you to tell in an instant without blowing away any program in memory

The **INSPECTOR** even lets you search through an entire disk or through on board memory for the appearance of a string Now you can easily add lower case to your programs (with LCA)

Do you want to add so called illegal line numbers into your program? or have several of the same line numbers in a program (like the professional programmers do)? or input unavailable commands (like HIMEM to Integer Basic)? or put quotation marks into PRINT statements? Here's the easy way to do them all!

AND MORE

The **INSPECTOR** provides a USER exit that will interface your own subroutines with those of the **INSPECTOR** itself For example, just put a screen dump routine (sample included in documentation) at HEX 0300 and press CTRL Z The contents of the screen page will print to your printer

ROM RESIDENT ROUTINES

The **INSPECTOR** utilities come on an easily installed EPROM This makes them always available for instant use No need to load a disk and run a program

FULLY DOCUMENTED

Unlike other software of its kind, The **INSPECTOR** comes with an EASY to understand manual and reference card Examples and graphics help even the uninitiated use the power of these utilities And furthermore, we offer the kind of personal service which you have never experienced from a software vendor before

CIRCLE 200 ON READER SERVICE CARD

See your LOCAL DEALER OR Mastercard or Visa users call TOLL FREE 1-800-835-2246. Kansas residents call 1-800-362-2421. Or send $49.95. Illinois residents add $3 sales tax

SYSTEM REQUIREMENTS

All Apple II configurations that have access to Integer Basic (either in ROM or RAM) will support The **INSPECTOR** Just plug the chip in empty socket U8 either on the mother board or in an Integer firmware card Apple II+ systems with RAM expansion boards or language systems will receive the **INSPECTOR** on disk to merge and load with INTBASIC

And if you have an Apple II+ without either RAM or ROM access to Integer Basic you will still be able to use The **INSPECTOR** because we are making available 16k RAM expansion boards at a very affordable price Not only will you be able to use The **INSPECTOR**, but you will also have access to Integer Basic and other languages. Our price for BOTH the **INSPECTOR and our 16k RAM board is $169.95**, less than most RAM boards alone Call our office for details.

Another Quality Product from
Omega Software Products, Inc.
222 S. Riverside Plaza, Chicago, IL 60606
Phone (312) 648-1944

1981 Omega Software Products, Inc
Apple is a registered trademark of Apple Computer, Inc

D

NEW ART FORM.

micro lab presents

PAINTER POWER

BY ERIC PODIETZ

Be an Artist

No longer do you need art skills to create bold abstracts or impressionistic landscapes. Using "Painter Power," you are able to achieve new effects that cannot be duplicated on canvas. Eric Podietz has produced a fascinating new art form which can be mastered by anyone. Using his skills as an artist and programmer, he has been developing this extraordinary graphics program for over a year, showing it to both children and adults in an artmobile and a museum. The technique is now perfected. Take control of the power and speed of the computer and free your artistic imagination and creativity. Micro Lab is offering you the opportunity to create works of art in a new and exciting medium.

Endless Possibilities

Using the keyboard, paddle, or joystick to control the shape and movement of your own design, begin painting, alternating the six hi-resolution colors of Painter's palette to produce various effects. Choose different speeds for precise design placement at slower speeds or switch to the faster speeds for a more flamboyant, free-flowing effect. Expand into new design dimensions using repetition of various geometric shapes, (circles, ellipses, lines) computed at your command by Painter. You will be absorbed for hours manipulating shapes and colors into a new visual expression. Save it anytime. Re-work it if you choose. Each creation is a unique, original work of computer art. There are two modes — one for the beginner and another for the more advanced user. The beginner version, with a simpler operation, is especially suited for children.

A Slide Program Too!

You may arrange a special screening of your slide creations. Whether they were made with Painter Power or any other program makes no difference. Give a professional presentation of any saved screen. Slides created with Painter Power can also be incorporated into programs you produce.

Enter our Art Fair

Micro Lab is sponsoring a computer art fair of your creations. The winning entry will be featured in a leading computer magazine. All entries received by March 31st will be considered for this showing. Proof of purchase of the program is required to enter.

"Painter Power" will create a gallery of computer art on an Apple with 48K and a disk drive. You will also need Applesoft in ROM or a language card. The program sells for only $39.95. See a demo at your dealer.

1981 Micro Lab Inc Apple is a trademark of Apple Computers, Inc

micro lab
systems that work

2310 Skokie Valley Road
Highland Park, IL 60035 • 312-433-7550
CIRCLE 143 ON READER SERVICE CARD

```
100 REM   PROGRAM 1D
110 PRINT "□";
120 FOR Z=1 TO 40 : PRINT "■";   NEXT
130 FOR Z= 1 TO 10
140 : PRINT "■■■■■■",
150 NEXT
160 FOR Z=1 TO 40 : PRINT "■";   NEXT
170 PRINT "■■",
180 FOR Z= 1 TO 10
190 : PRINT "■" 2;
200 : P=POS(0): IF P>40 THEN P=P-40
210 : PRINT SPC(40-P)
220 NEXT
```

Program 1D.

```
100 REM    PROGRAM 2D
110 PRINT "□";
120 FOR Z=1 TO 40 : PRINT "■";   NEXT
130 FOR Z=1 TO 10
140 : PRINT "■■■■■■";
150 NEXT
160 FOR Z=1 TO 40 : PRINT "■"; : NEXT
170 D$="■■"
180 FOR Z=1 TO 10
190 : D$=D$+"■"
200 : PRINT D$ TAB(5-40*(POS(0)>39)) Z
210 NEXT
```

Program 2D.

Yet another solution is to compensate for the problems caused by the 39/79 alternative. If printing the carriage return sent the cursor one line below your goal, print a "cursor up" followed by a semicolon to get it where you want it (Program 1C), or else simulate the carriage return with judicious use of the SPC function (Program 1D). If your TAB appears not to be working properly, use SPC (Program 2C), or attempt to add 40 to the argument (Program 2D). These piecemeal solutions are adequate for most purposes.

Study these programs, modify them, RUN them, and soon you will known all there is to know about this small PET problem. If you don't have the energy to do all this, buy yourself a new 80-column screen PET! □

```
100 REM   PROGRAM 2C
110 PRINT "□",
120 FOR Z=1 TO 40 : PRINT "■";   NEXT
130 FOR Z=1 TO 10
140 : PRINT "■■■■■■";
150 NEXT
160 FOR Z=1 TO 40 : PRINT "■"; : NEXT
170 D$="■■"
180 FOR Z=1 TO 10
190 : D$=D$+"■"
200 : PRINT D$ SPC(5) Z
210 NEXT
```

Program 2C.

```
100 REM          REMARKS
110
120 REM   ALL PROGRAM LISTINGS ASSUME NEW ROMS.
130 REM   FOR OLD ROMS, REPLACE PEEK(213) WITH PEEK(242),
140 REM                         PEEK(196) WITH PEEK(224),
150 REM                         PEEK(197) WITH PEEK(225).
160
170 REM   "□"=CLR (CLEAR THE SCREEN)
180 REM   "■"=HOME (CURSOR TO TOP LEFT OF SCREEN)
190 REM   "□"=CURSOR UP
200 REM   "■"=CURSOR DOWN
210 REM   "■"=CURSOR LEFT
220 REM   "■"=CURSOR RIGHT
230
READY.
```

Remarks and an explanation of special characters used in the programs.

"I put one too many loops in this exercise program."

The Text Solution for APPLE II®

Now APPLE II® Owners Can Solve Text Problems With VIDEOTERM 80 Column by 24 Line Video Display Utilizing 7 X 9 Dot Character Matrix

Perhaps the most annoying shortcoming of the Apple II® is its limitation of displaying only 40 columns by 24 lines of text, all in uppercase. At last, Apple II® owners have a reliable, trouble-free answer to their text display problem. VIDEOTERM generates a full 80 columns by 24 lines of text, in upper and lower case. Twice the number of characters as the standard Apple II® display. And by utilizing a 7 by 9 character matrix, lower case letters have true descenders. But this is only the start.

VIDEOTERM, MANUAL, SWITCHPLATE

VIDEOTERM

BASICs VIDEOTERM lists BASIC programs, both Integer and Applesoft, using the entire 80 columns. Without splitting keywords. Full editing capabilities are offered using the ESCape key sequences for cursor movement. With provision for stop/start text scrolling utilizing the standard Control-S entry. And simultaneous on-screen display of text being printed.

Pascal Installation of VIDEOTERM in slot 3 provides Pascal immediate control of the display since Pascal recognizes the board as a standard video display terminal and treats it as such. No changes are needed to Pascal's MISC.INFO or GOTOXY files, although customization directions are provided. All cursor control characters are identical to standard Pascal defaults.

Other Boards The new Microsoft Softcard™ is supported. So is the popular D. C. Hayes Micromodem II™, utilizing customized PROM firmware available from VIDEX. The powerful EasyWriter™ Professional Word Processing System and other word processors are now compatible with VIDEOTERM. Or use the Mountain Hardware ROMWriter™ (or other PROM programmer) to generate your own custom character sets. Naturally, VIDEOTERM conforms to all Apple OEM guidelines, assurance that you will have no conflicts with current or future Apple II™ expansion boards.

Advanced Hardware Design VIDEOTERM is on-board asynchronous crystal clock ensures flicker-free character display. Only the size of the Pascal Language card, VIDEOTERM utilizes CMOS and low power consumption ICs, ensuring cool, reliable operation. All ICs are fully socketed for easy maintenance. Add to that 2K of on-board RAM, 50 or 60 Hz operation, and provision of power and input connectors for a light pen. Problems are designed out, not in.

Available Options The entire display may be altered to inverse video, displaying black characters on a white field. PROMs containing alternate character sets and graphic symbols are available from Videx. A switchplate option allows you to use the same video monitor for either the VIDEOTERM or the standard Apple II™ display, instantly changing displays by flipping a single toggle switch. The switchplate assembly inserts into one of the rear cut-outs in the Apple II™ case so that the toggle switch is readily accessible. And the Videx KEYBOARD ENHANCER can be installed, allowing upper and lower case character entry directly from your Apple II™ keyboard.

Firmware 1K of on-board ROM firmware controls all operation of the VIDEOTERM. No machine language patches are needed for normal VIDEOTERM use.

Firmware Version 2.0

Characters	7 x 9 matrix	Display	24 x 80 (full descenders)
Options	7 x 12 matrix option. Alternate user definable character set option. Inverse video option		18 x 80 (7 x 12 matrix with full descenders)

Want to know more? Contact your local Apple dealer today for a demonstration. VIDEOTERM is available through your local dealer or direct from Videx in Corvallis, Oregon. Or send for the VIDEOTERM Owners Reference Manual and deduct the amount if you decide to purchase. Upgrade your Apple II™ to full terminal capabilities for half the cost of a terminal. VIDEOTERM. At last.

7X12 MATRIX 18X80 OPTIONAL

7X9 MATRIX 24X80 STANDARD

Apple II™ is a trademark of Apple Computer Inc.
ROMWriter™ is a trademark of Mountain Hardware Inc.
Micromodem II™ is a trademark of D. C. Hayes Associates Inc.
Softcard™ is a trademark of Microsoft.
EasyWriter™ is a trademark of Information Unlimited Software Inc.

PRICE:
- VIDEOTERM includes manual — $345
- + SWITCHPLATE — $ 19
- + MANUAL refund with purchase — $ 19
- + 7 x 12 CHARACTER SET — $ 39
- + MICROMODEM FIRMWARE — $ 25

APPLE II® OWNERS!

Introducing the KEYBOARD & DISPLAY ENHANCER

- ***PUT THE SHIFT AND SHIFT LOCK BACK WHERE IT BELONGS***
- ***SEE REAL UPPER AND lower CASE ON THE SCREEN***
- ***ACCESS ALL YOUR KEYBOARD ASCII CHARACTERS***

Videx has the perfect companion for your word processor software: the **KEYBOARD AND DISPLAY ENHANCER**. Install the enhancer in your APPLE II and be typing in lower case just like a typewriter. If you want an upper case character, use the SHIFT key or the CTRL key for shift lock. Not only that, but you see upper and lower case on the screen as you type. Perfectly compatible with Apple Writer and other word processors like, for example Sugar Text.

If you want to program in BASIC, just put it back into the alpha lock mode, and you have the original keyboard back with a few improvements. Now you can enter those elusive 9 characters directly from the keyboard, or re quire the Control key to be pressed with the RESET to prevent accidental resets.

KEYBOARD AND DISPLAY ENHANCER is recommended for use with all revisions of the APPLE II. It includes 6 ICs, and EPROM and dip-switches mounted on a PC board, and a jumper cable. Easy installation, involving no soldering or cutting traces. Alternate default modes are dip switch selectable. You can even remap the keyboard, selecting an alternate character set, for custom applications.

PRICE
- **KDE-700 (REV. 7 or greater)** ..... $129.
- **KDE-000 (REV. 6 or less)** ..... $129.

Apple II® is a trademark of Apple Computer, Inc.

Videx INC.
VIDEX
897 N.W. Grant Avenue
Corvallis, Oregon 97330
Phone (503) 758-0521

CIRCLE 240 ON READER SERVICE CARD

SAM: A New Type of Mortgage

Is It Best for You?

E. Lynn Crawford

With spiraling inflation and extremely high interest rates, lending institutions are developing new types of home mortgages to insure higher yields. The fixed rate, fixed term, instrument most of us know as a home mortgage is dead!

Throughout the United States, new mortgages known as "variable rate" or "roll over" mortgages are being used. This type of mortgage allows the lending institution to increase (or decrease) the interest rate, typically every three years, in step with the economy. This, of course, means increasing monthly mortgage payments through the years.

Now a new type of mortgage is being proposed by lending institutions. This mortgage is a "shared appreciation mortgage" or SAM. Basically it provides for the lending institution to participate in the appreciation of the home, the lending institution reduces the interest rate by two or three points (percent).

It works like this. In return for a one-third share of the appreciation, a bank will reduce the mortgage rate by three percent. Or in return for 25% of the appreciation, lending institutions will reduce the interest rate by two percent. If the home is sold within the allotted time, then the lending institution receives its share of the appreciation of the property.

If the home is not sold within the allotted time, the home is appraised and the lending institution's share is due and payable by the home owner. The mortgage may provide for this lump sum payment of interest income or shared appreciation to be added to the mortgage.

A reduction of three percent in the interest rate can mean a substantial reduction in monthly payments, allowing the buyer to purchase a larger home or spend less per month on a smaller home. But computing the possibility of gain or loss overall (interest cost plus loss of shared appreciation) is almost impossible without the aid of a computer.

Question, is this type of mortgage in the best interest of the home owner? The following program for the TRS-80 can provide the answer. □

Lynn Crawford, 8045 Oaklandon Rd., Indianapolis, IN 46236.

SAM MORTGAGE COMPARISONS

THE COMPARISONS BELOW ARE BASED ON THE FOLLOWING INFORMATION:

	STANDARD MORTGAGE	SAM MORTGAGE
SALES PRICE	$ 40,000.00	$ 40,000.00
INITIAL MORTGAGE	$ 30,000.00	$ 30,000.00
INTEREST RATE	14.0000%	11.0000%
MONTHLY PAYMENT	$ 473.95	$ 380.93
SHARED PERCENTAGE	-0-	33.300%
APPRECIATION RATE	12.0000%	12.0000%

THE COMPARISONS WILL BE RUN FOR 5 YEARS.

** ALL FIGURES ARE BELIEVED ACCURATE BUT ARE NOT GUARANTEED. **

AMORIZATION DETAILS

YEAR	TYPE	TOTAL INTEREST	PRINCIPAL REDUCTION	PRINCIPAL BALANCE	CURRENT APPRECIATION	PROPERTY VALUE
1	STD	$ 4,100.75	$ 1,586.65	$ 28,413.30	$ 4,800.00	$ 44,800.00
	SAM	$ 3,233.91	$ 1,337.25	$ 28,662.80	$ 4,800.00	$ 44,800.00
		TOTAL EQUITY	SHARE EQUITY	LENDERS EQUITY	NET EQUITY	LENDERS INCOME
	STD	$ 16,386.70	-0-	-0-	$ 16,386.70	$ 4,100.75
	SAM	$ 16,137.20	$ 4,800.00	$ 1,598.40	$ 14,538.80	$ 4,832.31
YEAR	TYPE	TOTAL INTEREST	PRINCIPAL REDUCTION	PRINCIPAL BALANCE	CURRENT APPRECIATION	PROPERTY VALUE
2	STD	$ 7,964.54	$ 3,410.26	$ 26,589.70	$ 5,376.00	$ 50,176.00
	SAM	$ 6,313.08	$ 2,829.24	$ 27,170.80	$ 5,376.00	$ 50,176.00
		TOTAL EQUITY	SHARE EQUITY	LENDERS EQUITY	NET EQUITY	LENDERS INCOME
	STD	$ 23,586.30	-0-	-0-	$ 23,586.30	$ 12,065.30
	SAM	$ 23,005.20	$ 10,176.00	$ 3,388.61	$ 19,616.60	$ 12,935.60
YEAR	TYPE	TOTAL INTEREST	PRINCIPAL REDUCTION	PRINCIPAL BALANCE	CURRENT APPRECIATION	PROPERTY VALUE
3	STD	$ 11,556.00	$ 5,506.21	$ 24,493.80	$ 6,021.12	$ 56,197.10
	SAM	$ 9,219.60	$ 4,493.88	$ 25,506.10	$ 6,021.12	$ 56,197.10
		TOTAL EQUITY	SHARE EQUITY	LENDERS EQUITY	NET EQUITY	LENDERS INCOME
	STD	$ 31,703.30	-0-	-0-	$ 31,703.30	$ 23,621.30
	SAM	$ 30,691.00	$ 16,197.10	$ 5,393.64	$ 25,297.40	$ 24,160.20
YEAR	TYPE	TOTAL INTEREST	PRINCIPAL REDUCTION	PRINCIPAL BALANCE	CURRENT APPRECIATION	PROPERTY VALUE
4	STD	$ 14,834.40	$ 7,915.17	$ 22,084.80	$ 6,743.66	$ 62,940.80
	SAM	$ 11,933.50	$ 6,351.16	$ 23,648.80	$ 6,743.66	$ 62,940.80
		TOTAL EQUITY	SHARE EQUITY	LENDERS EQUITY	NET EQUITY	LENDERS INCOME
	STD	$ 40,855.90	-0-	-0-	$ 40,855.90	$ 38,455.70
	SAM	$ 39,291.90	$ 22,940.80	$ 7,639.28	$ 31,652.70	$ 38,339.40
YEAR	TYPE	TOTAL INTEREST	PRINCIPAL REDUCTION	PRINCIPAL BALANCE	CURRENT APPRECIATION	PROPERTY VALUE
5	STD	$ 17,753.10	$ 10,683.90	$ 19,316.10	$ 7,552.89	$ 70,493.70
	SAM	$ 14,432.50	$ 8,423.35	$ 21,576.70	$ 7,552.89	$ 70,493.70
		TOTAL EQUITY	SHARE EQUITY	LENDERS EQUITY	NET EQUITY	LENDERS INCOME
	STD	$ 51,177.60	-0-	-0-	$ 51,177.60	$ 56,208.80
	SAM	$ 48,917.00	$ 30,493.70	$ 10,154.40	$ 38,762.60	$ 55,286.90

Educational Excellence

Excellent educational software is the exception rather than the rule.

Excellence in educational software. It's not easily achieved

Many large publishers have entered the computer software business. Many have flopped. Why? Because producing good software is not the same as producing a textbook.

Tough Criteria

Good educational software must meet specific objects in the teaching/learning process. If must motivate and hold the attention of the students. It must not bore the gifted students nor be over the heads of slower students. It must be "user friendly" to both the teacher and student. And it must be accompanied by clear support material, worksheets and all the material necessary to use it effectively

A tall order

But one which MECC has met

The Minnesota Educational Computer Consortium (MECC) was founded in 1973 with the goal of extending the benefits of computers to every school in the state. Over the years, MECC has developed procedures for finding and perfecting programs from contributors throughout the state

Few Programs Quality

Before a program is accepted for the MECC library it is judged on specific criteria. For example

1) Accuracy . Is all spelling and grammer correct? Does each question provide for a correct and appropriate response?

2) Audience . Is the intended audience (grade level and subject) served by the degree of difficulty and scope of the program? Is the reading level of the text material suitable?

3) Clarity . Are explanations and instructions sufficient, clear and straight forward? Is the presentation well-formatted?

4) Graphics . Are the graphics appropriate and sufficient in quantity?

Other criteria include documentation, function, programming, and the like. Similar criteria are applied to the documentation. This ensures that the reading level is appropriate, that objectives are well-stated and that associated materials are available.

What that means is that the educational software packages from MECC are among the best available anywhere. They are pedagogically sound, thoroughly tested and well documented.

Now the MECC software library is available to both schools and individuals through Creative Computing Software

MECC software is currently available only on disk for the Apple II. All disks run under DOS 3.2 and require a minimum of 32K memory and Applesoft in ROM or an Apple II Plus

Software using a printer uses the Apple serial, parallel or communications card

Order Today

Order In confidence at no risk. All MECC software is covered by an unconditional 30-day money-back guarantee from Creative Computing Software.

To order any MECC software package, send payment plus $2.00 postage and handling to the address below. To charge an order to Visa, MasterCard or American Express include card number and expiration date. Charge orders may also be called in to our toll-free number. School purchase orders should add an additional $2.00 billing fee

Order MECC software today for the highest quality and best value in educational software available anywhere.

Apple Demonstration Diskette
MECC-701, $19.95

A sample of the different kinds of applications available on the MECC diskettes is shown. The software demonstrates applications in drill and practice, tutorial, simulation, problem solving, and worksheet generation. Samples from music, science, social studies, industrial arts, reading and mathematics are provided.

Elementary—Volume 1 (Mathematics)
MECC-702, $24.95

The first elementary diskette contains programs to be used in the elementary mathematics classroom. Games of logic such as BAGELS, TAXMAN, and NUMBER, drill and practice programs, such as SPEED DRILL, ROUND, and CHANGE, and programs about the metric system such as METRIC ESTIMATE, METRIC LENGTH, and METRIC 21 are included on the diskette.

Elementary—Volume 2 (Language Arts)
MECC-703, $24.95 (Available 7/81)

The teacher can enter lists of spelling words in the computer and have them used by the program SPELL, which drills students on the spelling, MIXUP which presents the word in mixed up order, or WORD FIND, which will create a word find puzzle for the teacher to duplicate. If words and definitions are entered, a CROSS WORD puzzle can be generated or a WORD GAME can be played. Two other programs included on this diskette are TALK, a program designed to introduce students to the computer or AMAZING which prints out worksheet mazes. Several programs on the diskette use a printer.

Elementary—Volume 3 (Social Studies)
MECC-704, $24.95 (Available 7/81)

The self series, SELL APPLES, SELL PLANTS, SELL LEMONADE, and SELL BICYCLES which appears on the ELEMENTARY VOLUME 3 diskette can be used to teach elementary economics to students in grades 3-6. CIVIL will reinact battles of the CIVIL war while STATES and STATES2 provide drill and practice on the location of states in the U.S. and their capitals.

Elementary—Volume 4 (Mathematics And Science)
MECC-705, $24.95

Two mathematics programs ESTIMATE and MATHGAME provide reinforcement on estimating and basic facts. Food chains in fish can be studied through ODELL LAKE while ODELL WOODS deals with food chains in animals. SOLAR DISTANCE teaches the concepts of distances in space and URSA provides a tutorial on constellations

Elementary—Volume 5 (Language Arts)
MECC-710, $24.94 (Available 7/81)

ELEMENTARY—VOLUME 5 deals with the reading concept of prefixes. The diskette contains five lessons which both teach the prefixes of UN, RE, DIS, PRE, and IN. Two review drills, DRAGON FIRE and PRE-APP II, are also contained on the diskette.

Elementary—Volume 6
MECC-725, $24.95 (Available 7/81)

Historical simulations, OREGON, VOYAGEUR and FURS are included in the ELEMENTARY—VOLUME 6 diskette. Along with these programs are NOMAD which teaches map reading and SUMER

Special Needs—Volume 1 (Spelling)
MECC-727, $24.95 (Available 7/81)

The diskette is designed to drill handicapped students on frequently misspelled primary and intermediate words. Students answer problems by either using the game buttons, the game paddles or any key on the keyboard.

Science—Volume 2 (Senior High)
MECC-709, $24.95 (Available 7/81)

Many of the programs on this diskette were developed by Minnesota teachers. PEST, which deals with the use of pesticides, and CELL MEMBRANE which the user takes the part of a cell membrane, can be used in biology classes. SNELL plots light refraction demonstrating SNELL's law while COLLIDE simulates the collision between two bodies. DIFFUSION deals with the diffusion rates of various gases, NUCLEAR SIMULATION shows radioactive decay of nine different radioisotopes, ICBM and RADAR teach angles and projections on a coordinate system.

Science—Volume 3 (Middle School)
MECC-707, $24.95 (Available 7/81)

The FISH program through the use of low resolution graphics show the circulatory system of a fish. Simulations like ODELL LAKE which is used to explore food chains, URSA which teaches about constellations, and QUAKES which simulates earthquakes are on the diskette. MINERALS can be used in the area of earth science to identify 29 minerals by having students perform simple tests.

Mathematics—Volume 1 (Senior High)
MECC-706, $24.95 (Available 7/81)

BAGELS, SNARK, ICBM, and RADAR will teach students logic while reinforcing the concepts of plotting prints or angle measurements. ALGEBRA provides a drill and practice in solving equations. Three programs on the diskette can be used in plotting equations on a grid: SLOPE which is designed for use in ninth grade with linear functions, POLYGRAPH which will plot any equation on a rectangular coordinate system, and POLAR which graphs functions on polar coordinates.

Aestheometry teaches the topic of curves by viewing curves from two perspectives. The first method demonstrates the "space concepts" of elliptical, parabolic, and hyperbolic curves. Curve sketching designs are developed to provide an aesthetic view of geometric shapes. The second method uses a mathematical approach and defines a curve as the intersection of planes with a cone. The support booklet provides worksheets and classroom ideas

Teacher Utilities—Volume 1
MECC-715, $24.95 (Available 7/81)

The TEACHER UTILITIES diskette is designed to aid the teacher and would not be used by the student unless the teacher creates questions using the REVIEW program. This program allows the teacher to set up a list of questions which can be used either by the REVIEW program or the TEST GENERATOR program. The teacher can also make CROSS WORD puzzles, WORD FIND puzzles, BLOCK LETTER banners and POSTERS using the program FREQUENCY and PERCENT can be used to calculate grades and to do statistical analysis. A printer is needed for some of the programs on this diskette

Programmer's Aid—Volume 1
MECC-720, $32.95 (Available 7/81)

The PROGRAMMER's AID diskette provides help for the programmer. Programs to be able to UPLOAD and DOWNLOAD to the MECC system, programs that work with text files including ZIP TO TEXT, RANDOM EDITOR, SEQUENTIAL EDITOR and TEXT LIST along with programs to work with binary files, BINARY FILE INFO, BINARY FILE TO PRint included. Two programs TABLES and MERGAR allow the user to create, change and merge graphic shapes for use in a program. FREE SPACE will tell the amount of space on the diskette while HIDDEN CHARACTERS will locate control character. STARTER will put standard routines such as space bar, music, graphic characters or input into a user's program which is just being created or already created

MICAS—Volume 1
MECC-721, $32.95 (Available 7/81)

Microcomputer Integrated Computerized Accounting System requires dual disks and 132 characters width printer. The MICAS computerized accounting system provides a realistic experience with automated accounting systems. The package consists of four integrated systems: (1) general ledger, (2) accounts payable, (3) accounts receivable, and (4) inventory control

Shape Tables—Volume 1
MECC-724, $24.95 (Available 7/81)

The SHAPE TABLES diskette includes 12 files of 187 shapes that can be incorporated in a user's program. Also included are aids needed to work with shape tables

creative computing software

Morris Plains, NJ 07950
Toll-free 800-631-8112
(In NJ 201-540-0445)

Buy by Mail and SAVE!

COMPUTERS

Intertec Superbrain SPECIALS

64K Ram, List $3495	$2595
64K Quad, List $3995	$2995

NorthStar

Horizon I 32K DD List $2695	CALL
Horizon I QD List $2995	CALL
Horizon 2 32DD List $3095	CALL
IntersystemDPS-1 List $1749	CALL

Cromemco Z-2H, List $8895	$7945
System 2, 64K List $4695	$3749
System 3, 64K, List $7995	$6395

Disk Systems

Thinker Toys Discus 2D	$939
Dual Discus 2D	$1559
Discus 2 + 2, List $1549	$1259
M26 Hard Disk, List $4995	$3949
Discus M-10, List $3695	$2995

Printers & Terminals

Paper Tiger IDS 445	$649
with graphic option	$719
Centronics 730-1, List $795	$549
739-1, List $995	$789
704-9 RS232	$1495
704-11	$1569
TI 810, List $1895	$1489
NEC SPINWRITER 5530	$2395
NEC SPINWRITER 5515, 5510	$2395
Diablo 630 List $2711	$2399
Intertube III List $899	$729
Zenith Z-19	$719
Televideo 912C	$679
920C	$799
950	$999
Hazeltine 1420	$789
1500	$845
Soroc 120 List $895	$689
IQ135	$719
140	$994

Computers Wholesale

P.O. Box 144 Camillus, NY 13031

VISA (315) 472-2582

Most items in stock for immediate delivery. Factory sealed cartons w/ full factory warranty. NYS residents add appropriate sales tax. Prices do not include shipping. VISA and Master Charge add 3% C.O.D. orders require 25% deposit. Prices subject to change without notice.

CIRCLE 130 ON READER SERVICE CARD

Program Listing

```
10  '* * * * * * * * * * * * * * * * * * * * * * * * * * * * * *
20  '*                                                         *
30  '*                  SAM MORTGAGE COMPARISONS               *
40  '*                                                         *
50  '*    A PROGRAM TO COMPARE INTEREST EXPENSE OF FIXED TERM *
60  '* FIXED RATE MORTGAGES WITH THE EXPENSE OF SAM (SHARED   *
70  '* APPRECIATION MORTGAGES) TYPE MORTGAGES.                 *
80  '*                                                         *
90  '*                          BY E. LYNN CRAWFORD            *
100 '*                                 3/5/81                  *
110 '* ALL RIGHTS RESERVED                                     *
120 '* * * * * * * * * * * * * * * * * * * * * * * * * * * * * *
130 '
140 '
150 '                        * VARIABLE LIST *
160 '
170 'EQUITY VARIABLES
180 '     NE = NET EQUITY
190 '     SR = SHARE PERCENTAGE RATE
200 '     SE = SHARE EQUITY
210 '     TE = TOTAL EQUITY
220 '     LE = LENDERS EQUITY
230 'APPRECIATION VARIABLES
240 '     AR = APPRECIATION RATE AVERAGE OVER N YEARS
250 '     TA = TOTAL APPRECIATION
260 '     YA = YEARLY APPRECIATION
270 'INTEREST VARIABLES
280 '     AI = ACCUMULATED INTEREST
290 '      I = INTEREST
300 '     IR = INTEREST RATE
310 '     MI = MONTHLY INTEREST
320 '     TI = TOTAL YEARLY INTERST
330 '     PR = PERCENTAGE RATE
340 'PRINCIPAL VARIABLES
350 '     PV = PROPERTY VALUE
360 '     SP = SALES PRICE
370 '      P = PAYMENT
380 '     PB = PRINCIPAL BALANCE
390 '     PR = PRINCIPAL REDUCTION
400 '     TP = TOTAL PRINCIPAL REDUCTION
410 'MISCELLANEOUS
420 '      L = LOOP
430 '      N = NUMBER OF YEARS
440 '      M = MONTHS
450 '    HC$ = HARD COPY
460 '    Q$ = QUESTION
470 '      X = SWITCH FROM STANDARD TO SAM AND BACK
480 '     TL = TIMING LOOP
490 '      C = CORRECTION
500 '    U$ = PRINT USING STRINGS (UA$ THRU UI$)
510 '     LI = LENDER'S INCOME
520 '    X$ = TYPE STRING
530 '     PL = PAGE LENGTH
540 '      Z = FOR NEXT LOOP
550 GOSUB 2660 '                > FOR NAME BLOCK
560 '
570 '
580 '                        * TO INITIALIZE *
590 '
600 UA$ = "     $###,###.##"                        $###,###.##"
610 UB$ = "                -0-                        ##.###%"
620 UC$ = "        ##.####%                           ##.####%"
630 UD$ = "$###,##.##"
640 UE$ = " ##"
650 UF$ = "    %  %   $###,###.##  $###,###.##  $###,###.##
  $###,###.##  $###,###.##"
660 UG$ = "    %  %   $###,###.##          -0-          -0-
  $###,###.##  $###,###.##"
670 UH$ = "$###,###.##     $###,###.##"
680 UI$ = "        -0-     $###,##.##"
690 '
700 '
710 '                        * TO ENTER DATA *
720 '
730 CLS
740 PRINT "TO ENTER DATA, SIMPLY RESPOND TO THE QUESTIONS ASKED
  BY THE        COMPUTER."
750 PRINT "PLEASE ENTER THE DATA IN DECIMAL FORM, WITHOUT THE
USE OF COMMASOR $ SIGNS."
```

Ω WEST COAST / EAST COAST Ω

Special of the Month!

EPSON MX-80

INTERFACES:
IEEE $55, TRS-80 $35,
APPLE INTERFACE & CABLE $90,
RS-232 $70

ATARI 800 16K
$ 769



We Accept C.O.D.'s • Stock Shipments Same Day or Next
No Surcharge for Credit Cards • All Equipment Factory Fresh with MFT Warranty

NEC
INTERTEC
OKIDATA
APPLE
TELEVIDEO
COMMODOR
RADIO SHAC
AMDEK
QUME
ATARI

INTERTEC SUPERBRAIN 64K RAM	$2799
QD SUPERBRAIN	$2999
NEC 5510 SPINWRITER (7710)	$2345
NEC 5520 SPINWRITER (7720)	$2695
NEC 5530 SPINWRITER (7730)	$3345
NEC 12" MONITOR	$ 229
OKIDATA MICROLINE 80	$ 399
OKIDATA MICROLINE 82	$ 529
OKIDATA MICROLINE 83	$ 769
DIABLO 630	$1995
APPLE II PLUS 48K	$1139
APPLE DISK w/3.3 DOS Controller	$ 525
APPLE DISK w/o Controller	$ 449
HAZELTINE 1420	$ 799
NORTHSTAR HORIZON II 32K QD	$2925
ANADEX DP-9500/9501	$1249
TELEVIDEO 912C	$ 669
TELEVIDEO 920C	$ 729
TELEVIDEO 950	$ 929
CBM 8032 COMPUTER	$1149
CBM 8050 DISK DRIVE	$1349
CBM 4032 COMPUTER	$1029
CBM 4040 DISK DRIVE	$1029
CBM 4022	$ 649
CBM VIC-20	$ 269
RADIO SHACK II 64K	$3245
RADIO SHACK III 16K	$ 849
LEEDEX/AMDEK 100	$ 139
LEEDEX/AMDEK 100G	$ 169
LEEDEX/AMDEK COLOR-1 13" Color Monitor	$ 329
MICROTEK 16K RAMBOARD for Atari	$ 79
MICROTEK 32K	$ 149
QUME SPRINT 9/45 (Full Panel)	$2295
ATARI 400 16K	$ 349
ATARI 825 PRINTER	$ 650
ATARI 850 INTERFACE	$ 139
ATARI 810 DISK DRIVE	$ 449
ATARI 800	$ 749

Call for price list of ATARI software

PRICES ARE SUBJECT TO CHANGE WITHOUT NOTICE

We carry the complete line of Personal Software

WEST COAST
1-800-235-3581

OMEGA SALES CO.
3533 Old Conejo Rd. #102
Newbury Park, CA 91320
1-805-499-3678
CA. TOLL FREE 1-800-322-1873

ΩMEGA SALES CO.

EAST COAST
1-800-556-7586

OMEGA SALES CO.
12 Meeting St.
Cumberland, RI 02864
1-401-722-1027

VISA

ΩMEGA SALES COMPANY

CIRCLE 213 ON READER SERVICE CARD

meet a REAL PLUS

Color Computer 4K $310
w/Ext. Basic 16K $459

Model II 64K
$3300

Atari 800 32K $789

Model III 16K
$839
2 DR + RS232C
$2100

These are just a few of our many fine offers — computers, peripherals, modems, printers, disc drives and an unusual selection of package values. Call TOLL FREE today and check us out for price and warranty.

Factory warrantees on Apple and Atari equipment. Other equipment carries manufacturer's warranty or Computer Plus 180 day extended warranty. Combined warrantees carry Computer Plus 180 day warranty or original manufacturer's warranty

DEALER INQUIRIES ARE INVITED
Prices subject to change without notice
TRS-80 is a registered trademark of Tandy Corp

call TOLL FREE
1-800-343-8124

computer plus

Write for your free catalog

245A Great Road
Littleton, MA 01460
(617) 486-3193 Dept F

CIRCLE 160 ON READER SERVICE CARD

SAM, continued...

```
760 PRINT "FOR EXAMPLE, 12 3/4% INTEREST WOULD BE ENTERED AS
 .1275 AND      $3,650.45 WOULD BE ENTERED AS 3650.45."
770 GOSUB 2400
780 GOSUB 2410
790 GOSUB 2420
800 GOSUB 2430
810 GOSUB 2440
820 GOSUB 2450
830 GOSUB 2460
840 GOSUB 2470
850 GOSUB 2480
860 GOSUB 2490
870 PV = SP
880 GOSUB 2500
890 PB(1) = PB
900 PB(2) = PB
910 '
920 '
930 '                    * DATA ENTRY CORRECTION & RECAP *
940 '
950 CLS
960 PRINT TAB(18) "SAM MORTGAGE COMPARISONS"
970 PRINT "(1) HARD COPY PRINTOUT? - ";HC$
980 PRINT "(2) SALES PRICE OR INITIAL VALUE = ";
990 PRINT USING US$; SP
1000 PRINT "(3) INITIAL MORTGAGE BALANCE = ";
1010 PRINT USING US$; PB
1020 PRINT "(4) ANTICIPATED AVERAGE APPRECIATION RATE PER YEAR ";PR(4);"%"
1030 PRINT "(5) COMPARISONS TO BE MADE OVER ";N;" YEARS."
1040 PRINT TAB(10) "STANDARD MORTGAGE DATA:"
1050 PRINT "(6) INTEREST RATE = ";PR(1);"%"
1060 PRINT "(7) MONTHLY PAYMENT = ";
1070 PRINT USING US$;P(1)
1080 PRINT TAB(10) "SAM MORTGAGE DATA:"
1090 PRINT "(8) INTEREST RATE = ";PR(2);"%"
1100 PRINT "(9) MONTHLY PAYMENT = ";
1110 PRINT USING US$;P(2)
1120 PRINT "(10) MORTGAGE COMPANY SHARES ";PR(3);"%"
1130 INPUT "DO YOU WANT TO CORRECT ANY OF THE DATA SHOWN";Q$
1140 IF LEFT$(Q$,1) = "Y" GOTO 1160
1150 GOTO 1190
1160 INPUT "ENTER ITEM NUMBER YOU WANT TO CORRECT";C
1170 ON C GOSUB 2490 ,2400 ,2410 ,2480 ,2470 ,2420 ,2430 ,2440 ,2450 ,2460
1180 GOTO 870
1190 CLS
1200 PRINT CHR$(23)
1210 PRINT @ 462, "ONE MOMENT PLEASE"
1220 IF LEFT$(HC$,1) = "Y" GOSUB 2090
1230 '
1240 '
1250 '                    * MATH COMPUTATIONS *
1260 '
1270 FOR L = 1 TO N
1280 FOR X = 1 TO 2
1290 FOR M = 1 TO 12
1300 I(X) = IR(X) * PB(X)
1310 MI(X) = I(X)/12
1320 PR(X) = P(X) - MI(X)
1330 TI(X) = TI(X) + MI(X)
1340 TP(X) = TP(X) + PR(X)
1350 PB(X) = PB(X) - PR(X)
1360 IF PB(X) < P(X) GOTO 2760
1370 NEXT M
1380 NEXT X
1390 Y = Y + 1
1400 YA = AR * PV
1410 PV = PV + YA
1420 TE(1) = PV - PB(1)
1430 TE(2) = PV - PB(2)
1440 SE = PV - SP
1450 LE = SE * SR
1460 NE(1) = TE(1)
1470 NE(2) = PV - PB(2) - LE
1480 AI(1) = AI(1) + TI(1)
1490 AI(2) = AI(2) + TI(2)
1500 LI = LE + AI(2)
1510 IF LEFT$(HC$,1) = "Y" GOTO 1860
1520 INPUT "PRESS ENTER TO CONTINUE";Q$
1530 '
1540 '
1550 '                    * SCREEN PRINTOUT *
1560 '
1570 CLS
1580 PRINT "COMPARISONS FOR YEAR NUMBER ";Y
1590 PRINT "                                        STD MTG          SAM MTG"
1600 PRINT "TOTAL INTEREST";
1610 PRINT TAB(30) USING UH$;TI(1);TI(2)
1620 PRINT "PRINCIPAL REDUCTION";
1630 PRINT TAB(30) USING UH$;TP(1);TP(2)
```

WHY BUY FROM THE BEST?

NEECO

Service... Support...
Software...

commodore

16K B (16K RAM-40 Column) - Lim. Qty	$ 995
32K B (32K RAM-40 Clm.) - Lim. Qty	$1295
4016 (16K RAM 4.0 Basic-40 Clm.)	$ 995
4032 (32K RAM 4.0 Basic-40 Clm.)	$1295
8032 (32K RAM 4.0 Basic-80 Clm.)	$1495
8050 Dual Disk (1 Meg. Storage)	$1795
4040 Dual Disk (343K Storage)	$1295
8010 IEEE Modem	$ 280
C2N Cassette Drive	$ 95
CBM - IEEE Interface Cable	$ 40
IEEE - IEEE Interface Cable	$ 50
VIC 20 Home/Personal Computer	$ 295

ALTOS

ACS 8000-2 64K 1M	$ 4500
ACS 8000-15 64K 1M	$ 5990
ACS 8000-6 208K 14.5M	$10490
ACS 8000-7 208K 29.0M	$11690
ACS 8000-10 208K 10M	$ 8500
ACS 8000-10/MTU	$10990

EPSON PRINTERS

MX-80 PRINTER	$ 645
MX-80 FT	$ 745
MX-100	$ 945
MX-70	$ 459
INTERFACE CARDS	
8141 (RS-232)	$ 75
8150 (2K Buffered RS-232)	$ 150
8161 (IEEE 488)	$ 55
8131 (Apple Card)	$ 85
8230 (Apple Card)	$ 25
8220 (TRS-80 Cable)	$ 35

NEC SPINWRITER PRINTERS

5530 (Parallel)	$3055
5510 (Serial)	$3055
5520 (KSR-Serial)	$3415
Tractor Option	$ 225

DIABLO 630 PRINTER

DIABLO 630 - Serial - RS-232	$2710
Tractor Option	$ 250

APPLE

16K APPLE II+	$1330
32K APPLE II+	$1430
48K APPLE II+	$1530
APPLE DISK w/3.3 DOS	$ 650
APPLE DRIVE Only	$ 490
APPLE III 128K - In Stock! w/Monitor + Info Analystpak	$4740

AMDEK MONITORS

Video 100 12" B+W	$ 179
Video 300 12" Green	$ 249
Color I 13" Low Res	$ 449
Color II 13" High Res	$ 999

INTERTEC COMPUTERS

64K Superbrain (360 Disk Storage), CP/M™	$3495
64K QD Superbrain (700K Disk Storage), CP/M™	$3995

*CP/M is a registered trademark of Digital Research.

ATARI COMPUTERS

Atari 400 (16K RAM)	$ 399
Atari 800 (32K RAM) - good thru 8/31	$1080
Atari 410 RECORDER	$ 89.95
Atari 810 DISK DRIVE	$ 599.95

NEECO carries all available ATARI Software and Peripherals.

PROFESSIONAL SOFTWARE

WordPro 1 8K	$ 29.95
WordPro 3 (40 Clm.)16K	$ 199.95
WordPro 3+	$ 295
WordPro 4 (80 Clm.) 32K	$ 375
WordPro 4+	$ 450

JUST A SAMPLE OF THE MANY PRODUCTS WE CARRY. CALL US FOR OUR NEW 60-PAGE CATALOG.
WE WILL MATCH ANY ADVERTISED PRICE ON PRODUCTS LISTED UNDER SIMILAR "IN STOCK" CONDITIONS.

NEECO

679 HIGHLAND AVE.
NEEDHAM, MA 02194

(617) 449-1760
Telex: 951021

MON-FRI 9:00 - 5:00

MasterCharge and VISA Accepted

CIRCLE 285 ON READER SERVICE CARD



TRS-80
MODEL I
DISK
INTERFACING
$5.95
$7.95 Foreign Airmail (US Funds)
Postpaid mailed to you
FIRST CLASS
United States Only
Send To:
80-U.S. Journal
3838 South Warner St.
Tacoma, Washington 98409
(206) 475-2219
A DIVISION OF 80 NORTHWEST PUBLISHING
Dealer Inquiries Invited

Send _____ Copies of the Guide
Check Enclosed _____
Visa or MasterCharge
_____
Exp. Date _____
Signature _____
Name _____
Address _____
City _____ State _____
Zip _____

TRS 80 is a registered trademark of TANDY CORP.

80-U.S.

SAM, continued...

```
1640 PRINT "PRINCIPAL BALANCE";
1650 PRINT TAB(30) USING UH$;PB(1);PB(2)
1660 PRINT "CURRENT APPRECIATION";
1670 PRINT TAB(30) USING UH$;YA;YA
1680 PRINT "PROPERTY VALUE";
1690 PRINT TAB(30) USING UH$;PV;PV
1700 PRINT "TOTAL EQUITY";
1710 PRINT TAB(30) USING UH$;TE(1);TE(2)
1720 PRINT "SHARE EQUITY";
1730 PRINT TAB(30) USING UI$;SE
1740 PRINT "LENDERS' EQUITY";
1750 PRINT TAB(30) USING UI$;LE
1760 PRINT "NET EQUITY";
1770 PRINT TAB(30) USING UH$;NE(1);NE(2)
1780 PRINT "LENDERS INCOME";
1790 PRINT TAB(30) USING UH$;AI(1);LI
1800 PRINT
1810 NEXT L
1820 INPUT "PRESS ENTER TO CONTINUE";Q$
1830 GOTO 2890
1840 '
1850 '
1860 '                    * PRINTING SUBROUTINE *
1870 '
1880 CLS
1890 PRINT @ 470,"PRINTING YEAR NUMBER ";Y
1900 LPRINT "                          TOTAL     PRINCIPAL     PRINCIPAL
     CURRENT          PROPERTY"
1910 LPRINT "YEAR  TYPE        INTEREST     REDUCTION     BALANCE
  APPRECIATION        VALUE"
1920 X$ = "STD"
1930 LPRINT USING UE$;Y;
1940 LPRINT USING UF$;X$;TI(1);TP(1);PB(1);YA;PV
1950 X$ = "SAM"
1960 LPRINT TAB(3) USING UF$;X$;TI(2);TP(2);PB(2);YA;PV
1970 LPRINT TAB(17) " TOTAL          SHARE       LENDERS
 NET          LENDERS"
1980 LPRINT TAB(17) "EQUITY          EQUITY        EQUITY
   EQUITY        INCOME"
1990 X$ = "STD"
2000 LPRINT TAB(3) USING UG$;X$;TE(1);NE(1);AI(1)
2010 X$ = "SAM"
2020 LPRINT TAB(3) USING UF$;X$;TE(2);SE;LE;NE(2);LI
2030 LPRINT CHR$(138):LPRINT CHR$(138)
2040 GOSUB 2570
2050 NEXT L
2060 GOTO 2890
2070 '
2080 '
2090 '                    * HARD COPY RECAP *
2100 '
2110 LPRINT TAB(28) "SAM MORTGAGE COMPARISONS"
2120 LPRINT CHR$(138)
2130 LPRINT TAB(5) "THE COMPARISONS BELOW ARE BASED ON THE
FOLLOWING INFORMATION:"
2140 LPRINT CHR$(138)
2150 LPRINT TAB(31) "STANDARD MORTGAGE                    SAM MORTGAGE"
2160 LPRINT "SALES PRICE";
2170 LPRINT TAB(30) USING UA$;SP;SP
2180 LPRINT "INITIAL MORTGAGE";
2190 LPRINT TAB(30) USING UA$;PB;PB
2200 LPRINT "INTEREST RATE";
2210 LPRINT TAB(30) USING UC$;PR(1);PR(2)
2220 LPRINT "MONTHLY PAYMENT";
2230 LPRINT TAB(30) USING UA$;P(1);P(2)
2240 LPRINT "SHARED PERCENTAGE";
2250 LPRINT TAB(30) USING UB$; PR(3)
2260 LPRINT "APPRECIATION RATE";
2270 LPRINT TAB(30) USING UC$;PR(4);PR(4)
2280 LPRINT CHR$(138)
2290 LPRINT "THE COMPARISONS WILL BE RUN FOR ";N;" YEARS."
2300 LPRINT CHR$(138)
2310 LPRINT " ** ALL FIGURES ARE BELIEVED ACCURATE BUT ARE NOT GUARANTEED.**
2320 FOR Z = 1 TO 3: LPRINT CHR$(138): NEXT Z
2330 LPRINT TAB(30) "AMORIZATION DETAILS"
2340 LPRINT CHR$(138)
2350 RETURN
2360 '
2370 '
2380 '                    * DATA ENTRY SUBROUTINE *
2390 '
2400 INPUT "ENTER SALE PRICE OR INITIAL VALUE ";SP: RETURN
2410 INPUT "ENTER AMOUNT OF INITIAL MORTGAGE ";PB: RETURN
2420 INPUT "STANDARD MORTGAGE INTEREST RATE ";IR(1): RETURN
2430 INPUT "STANDARD MORTGAGE MONTHLY PAYMENT ";P(1): RETURN
2440 INPUT "          SAM MORTGAGE INTEREST RATE ";IR(2): RETURN
2450 INPUT "          SAM MORTGAGE MONTHLY PAYMENT ";P(2): RETURN
2460 INPUT "          SAM MORTGAGE SHARED PERCENTAGE ";SR: RETURN
2470 INPUT "NUMBER OF YEARS FOR WHICH YOU WANT TO MAKE COMPARISONS ";
     N: RETURN
```

80 COLUMN GRAPHICS

The Integrated Visible Memory for the PET has now been redesigned for the new 12" screen 80 column and forthcoming 40 column PET computers from Commodore. Like earlier MTU units, the new K-1008-43 package mounts inside the PET case for total protection. To make the power and flexibility of the 320 by 200 bit mapped pixel graphics display easily accessible, we have designed the Keyword Graphic Program. This adds 45 graphics commands to Commodore BASIC. If you have been waiting for easy to use, high resolution graphics for your PET, Isn't it time you called MTU?

The image on the screen was created by the program below.

```
 10 VISMEM: CLEAR
 20 P=160: Q=100
 30 XP=144: XR=1.5*3.1415927
 40 YP=56: YR=1: ZP=64
 50 XF=XR/XP: YF=YP/YR: ZF=XR/ZP
 60 FOR ZI=-Q TO Q-1
 70 IF ZI<-ZP OR ZI>ZP GOTO 150
 80 ZT=ZI*XP/ZP: ZZ=ZI
 90 XL=INT(.5+SQR(XP*XP-ZT*ZT))
100 FOR XI=-XL TO XL
110 XT=SQR(XI*XI+ZT*ZT)*XF: XX=XI
120 YY=(SIN(XT)+.4*SIN(3*XT))*YF
130 GOSUB 170
140 NEXT XI
150 NEXT ZI
160 STOP
170 X1=XX+ZZ+P
180 Y1=YY-ZZ+Q
190 GMODE 1: MOVE X1,Y1: WRPIX
200 IF Y1=0 GOTO 220
210 GMODE 2: LINE X1,Y1-1,X1,0
220 RETURN
```

K-1008-43M Manual only $10 (credited toward purchase)
k-1008-43 Complete ready to install package $495

Mastercharge and Visa accepted

Write or call today for our full line catalog describing all MTU 6502 products, including our high speed 8" Floppy Disk Controller for up to 4 megabytes of PET storage.

Micro Technology Unlimited
2806 Hillsborough Street
P.O. Box 12166
Raleigh, NC 27605, U.S.A.
(919) 833-1458

NOW 80 COLUMN PETS CAN HAVE MTU HIGH RESOLUTION GRAPHICS

CIRCLE 224 ON READER SERVICE CARD

THE UNIVERSE AT YOUR FINGERTIPS

TellStar™ for the Apple II

Choose a date, time, and place on Earth and let **TellStar** display the Stars, Planets, Sun, Moon and fascinating Stellar Objects in High Resolution Graphics.

With interactive commands, **TellStar** enables you to easily locate and identify stellar objects. Right Ascension, Declination, Azimuth, Elevation, Rise and Set Times are presented adjusted for precession. Planetary data is calculated using Kepler's equations. Constellations are drawn before your eyes. Print High Resolution Graphics displays on a Silentype. Scientific data can be printed on any printer.

A Calculation Utility is provided for equatorial, ecliptic, horizontal, and precession conversions.

TellStar Level I on disk **$39.95**
Northern Hemisphere Star Tables
TellStar Level II on disk **$79.95**
Comprehensive 47 page manual
Northern Hemisphere Star Tables
Southern Hemisphere Star Tables
Messier Object Star Tables

Visit your local computer store for demonstration or write for more information

Name _____
Address _____
City _____ Zip _____

Information Unlimited Software, Inc.
281 Arlington Avenue
Berkeley, CA 94707
(415) 525-9452

TellStar is a trademark of Scharf Software Services.
Apple is a trademark of Apple Computers Inc.

CIRCLE 273 ON READER SERVICE CARD

SAM, continued...

```
2480 INPUT "AVERAGE YEARLY APPRECIATION DURING PERIOD ";AR: RETURN
2490 INPUT "DO YOU WANT A HARD COPY PRINTOUT ";HC$: RETURN
2500 PR(1) = IR(1)*100
2510 PR(2) = IR(2)*100
2520 PR(3) = SR*100
2530 PR(4) = AR*100
2540 RETURN
2550 '
2560 '
2570 '                          * PAGE LENGTH *
2580 '
2590 IF PEEK (16425) < 56 THEN RETURN
2600 PL = 66 - (PEEK(16425))
2610 FOR Z = 1 TO PL: LPRINT CHR$(138): NEXT Z
2620 POKE 16425,0
2630 RETURN
2640 '
2650 '
2660 '                          * TITLE BLOCK *
2670 '
2680 CLS
2690 PRINT CHR$(23)
2700 PRINT @ 452, "SAM MORTGAGE COMPARISONS"
2710 PRINT @ 584, "BY E. LYNN CRAWFORD"
2720 FOR TL = 1 TO 1500: NEXT TL
2730 RETURN
2740 '
2750 '
2760 '                          * END OF MORTGAGE TERM *
2770 '
2780 M = 12
2790 X = 2
2800 L = N
2810 PRINT "THE NEXT FIGURES WILL BE FOR THE FINAL MORTGAGE
 YEAR.  MORTGAGE FIGURES MAY NOT BE ACCURATE DUE TO ROUNDING.      ";
2820 IF LEFT$(HC$,1) = "Y" GOTO 2840
2830 GOTO 1390
2840 LPRINT "FINAL MORTGAGE YEAR.  MORTGAGE FIGURES MAY NOT
 BE ACCURATE DUE TO ROUNDING."
2850 LPRINT CHR$(138)
2860 GOTO 1390
2870 '
2880 '
2890 '                          * ANOTHER PRINTOUT? *
2900 '
2910 CLS
2920 PRINT:PRINT:PRINT:PRINT
2930 GOSUB 2600
2940 INPUT "DO YOU WISH TO RUN ANOTHER COMPARISON";Q$
2950 IF LEFT$(Q$,1) = "Y" GOTO 3020
2960 CLS
2970 PRINT CHR$(23)
2980 PRINT @ 466, "THANK YOU!"
2990 PRINT @ 590, "HAVE A NICE DAY."
3000 GOSUB 2720
3010 END
3020 CLEAR
3030 GOTO 580
```


Engineering Software Library
Apple II 48K DOS 3.3 Or Listing Only

I. Truss And Linkage Analysis
   2D & 3D, Up To 70 Beams
II. Beam Analysis
   Section Properties & Diagrams
III. Linear Natural Frequencies
IV. Torsional Natural Frequencies
   Holzer Method With Branching
V. Rubber Element Design
   Compression And Shear Pad
VI. Bolted Joint Design

Write For Complete Program List
Written In Basic, Easily Converted

User Oriented. Complete Prompting
Disc Or Listing $40 Ea.

Engineering Software, Suite 2,
104 Queenwood Rd., Morton, IL 61550
(309) 263-2602

CIRCLE 267 ON READER SERVICE CARD

PERSONAL COMPUTER SOFTWARE

Is your software a game, a business system, or a mathematical solution?
Do you desire national distribution while protecting your authorship?
To have your software earn money for you contact:

SYSTEMS PLUS Inc. of Maryland
9380 Annapolis Road
Lanham, MD 20706
(301) 459-1330
(301) 358-2993

CIRCLE 276 ON READER SERVICE CARD

DISCOUNT TRS-80® BUY DIRECT

COMPUTER SPECIALISTS

CALL US. . . SAVE MONEY

MODEL II

26-4002
64K 1 Drive
$3297.00

26-4160 1 Drive Exp... ....$1034.00
26-4161 2 Drive Exp.....1574.00
26-4162 3 Drive Exp.....2114.00
26-4150 Hard Drive -1. .....3994.00+
26-4151 Hard Drive -2. .....3144.00+
26-4530 Scripsit II.....265.00
26-4512 Profile II.....162.00
26-4511 Visicalc II.....265.00
26-4501 Gen Ledger.....180.00
26-4506 Mail List.....72.00

MODEL III

26-1061 4K I.....**$609.00**
26-1062 16K III.....**849.00**
26-1066 48K III
W/2 Drives, RS232.....**2077.00**

We carry the full line of TRS-80 Computers. All other software, furniture, and accessories at discount from catalog price. We stock most items to assure you fast delivery and save you money.

26-1140 Expansion Interface.....$249.00
26-1141 16K Exp. Interface.....339.00
26-1142 32K Exp. Interface.....429.00
26-1145 RS232C Board.....84.00
26-1160/1 Mini Disk Drive.....419.00
26-1563 Scripsit-Disk.....79.00
26-1566 Visicalc.....83.00

• • • • • •PRINTERS• • • • • •

26-1165 Line Printer V.....1710.00
26-1167 Line Printer VII.....360.00
26-1166 Line Printer VI.....1080.00
26-1158 Daisy Wheel II.....1799.00
26-1168 Line Printer VIII.....720.00

COLOR

26-3001 4K.....**$318.00**
26-3002 16K Ext. Basic.....**488.00**
26-3003 32K Ext. Basic.....**628.00**
26-3010 Color Video.....**353.00**
26-1206 Recorder.....**54.00**

PRINTERS



CENTRONICS

BEST PRICES

Text Quality Centronics
739-1 Printer.....**$729.00**

Pocket Computer

26-3501 1.9K P.C.....$188.00
26-3503 Cassette IF.....45.00
14-812 Recorder.....72.00
26-3505 Mini Printer.....134.00

WRITE US FOR A
FREE CATALOG

REALISTIC®
VIDEO DISK
Player
$448.00

ALL POCKET AND COLOR COMPUTER SOFTWARE SOLD AT DISCOUNT

THOUSANDS OF SATISFIED CUSTOMERS

1-800-841-0860 Toll Free Order Entry

MICRO MANAGEMENT SYSTEMS, INC.

No Taxes on Out Of State Shipments

Immediate Shipment From Stock on Most Items

DOWNTOWN PLAZA SHOPPING CENTER
DEPT. # 3
115 C. SECOND AVE. S.W.
CAIRO, GEORGIA 31728
(912) 377-7120 Ga. Phone No. & Export
TRS-80 is a registered trademark of the Tandy Corp.
CIRCLE 163 ON READER SERVICE CARD

A copy of the manufacturer's warranty can be obtained free upon specific written request to the Electronic's Department of our Cairo, Georgia Retail Store.

Traveller in your Computer

Chris Marvel



As in life, players have adventures together and learn to rely on one another.

"Put a Dungeon in Your Computer" in the July issue of *Creative Computing*, inspired me to adapt Glen Charnock's system to Traveller. In case you're not familiar with it, Traveller is one of a series of popular sci-fi "role playing" games not unlike Dungeons & Dragons. The big difference is that it deals with the future and possibly some predicted reality rather than fantasy, magic, and myth. Not that I am knocking D&D players—I play D&D myself on occasion. It's just that Traveller is easier to identify with, and for sci-fi nuts like me, it has adventure that can be savored.

What Is Traveller

Traveller, published by Game Designer's Workshop, 203 North St., Normal, IL 61761, is a "role-playing" game about future societies. It deals with their struggles and the technology that has enabled them to reach the stars. It postulates the probable problems societies will have with communication and transportation over the vastness of space.

The game is refereed in much the same manner as D&D. A referee generates characters and a universe for them to explore, and determines the course of play. He writes down each different planet, and for those which are habitable, he records continents, topography, oceans, cities and even, on occasion, different countries on the same planet.

Play begins with a referee creating a character for the player. Characters are created in a different environment from those in D&D. The characters' attributes are strength, dexterity, endurance, intelligence, education, and social standing. Since the society that the character has grown up in requires compulsory military service, each character must either enlist or be drafted. Most people choose the latter because by doing so they increase their chances of obtaining officer status on the first hitch.

Christopher Marvel, 1313 Beaufort, Laramie, WY 82070.

Some of the Brightest Apple Software Available...

aurora systems inc.

VERSACALC™

Sort Visicalc.
Batch updata
Conditional testing
Menu-driven modules
Auto-catalog
Pretn the list of commands
13 or 16 sectora

$100

PERFORMANCE MANAGER™

Thia Versacalc driven Visicalc modula allowa you to compara currant month and year-to-data performancia against budget or goat, pranviua year, and 12 month moving average figurea. Use it to manage your budget, salea, productiion, and other situations whera you want to monitor individual categorea aa weha aa an entira department or firm
Requira Vaicalc 3.3

$75

FIXED ASSET MANAGER™

Thia menu-driven Vsicalc modula uaea Varacalc techniquea to give
Management ol 65 assata per ahaet
No limit to the number ol sheata
All General Ledger antriea
Straight line, DDB, SOYD depreciation
Monthly reporta
Investmtan tax creditа
Taxable gainon salaa
Automatic batch updating
Requires Vsicalc 3.3

$75

QUICKTRACE™

Machina languaba debugger
Traca, angle-atep, and background
Displaya registara, flaga, stack, and aa locationa of choica
Relocatabla
Allowa changes to displayed valuea
Compatibla with DOS, BASICs, and graphica
Output to screen or printer
Can traca BASIC programa

$35

The RENTAL MANAGER™

General Ledger
Accounta Racaivabla
Accounta Payabla
Currant & Futura Tenant Records
Automatic Posting
Automatic Tracking

$695

EDUCATION PROGRAMS

Teacher's Gradebook	$60
Marching Band Database	$40
Quantum Atom & Sina Waves	$40
Density Lab	$40
Elementa and Symbols	$40
Balancing Molecules	$40

The FLIPPER™

is a small circuit board that fits on the game bus (but leaves it free) and switches two inputs (or outputs) into one output (or input). Usually used for 40 80 column video switching. The Executive Secratary supporta it automatically

$50

OMNISCAN™

is an interfaca between the Apple II and the Pioneer Laser Video Disk It allowa full control ol the LaserDisk from tha kayboard or program and includea the board and software

$250

The EXECUTIVE SECRETARY™

All the usual word procaasor functions
40 or 80 columna - salectabla
Real shift kay without soldering
Full lormal control
Full forma handling
Kayboard input at print time
Supports any printer
Built in Card File w/Report Generator
Accesa to aternal databases, such as Data Factory and others
Built-in Electronic Mail

$250

HEBREW II™

Firat loraign language word procaasor in Amanca It prints from right to lalt on the screen, can label graphs and pictures, and can print on the Sitantype or other graphics printers

$60

Ask about package deals on the Versacalc line of modules

Yes, we said, "SORT VISICALC!"

aurora systems, inc.
2040 E. Washington Ave.
Madison, WI 53704
608 - 249 - 5875

Versacalc is a trademark of Versacalc Systems

The Executive Secretary is a trademark of Personal Business Systems, Inc
Performance Manager, Fixed Asset Manager, QuickTrace, Omniscan, the Flipper, are trademarks of Aurora Systems, Inc.
The Rental Manager is a trademark of Money Tree Systems, Inc

CIRCLE 107 ON READER SERVICE CARD

MONEY BACK GUARANTEE

YORK 10 BASF-DPS
WORLD STANDARD TAPE

- PROFESSIONAL 5-SCREW SHELL
- UNIVERSAL INDUSTRY ACCEPTANCE

DATA TRAC — C-1D, C-2D
MUSI TRAC — C-45, C-90

HERE'S WHAT USERS SAY ABOUT YORK 10 CASSETTES:

"Excellent tape — I haven't had a bad CSAVE and volume level for CLOAD's is consistent for all cassettes. Your tape is good enough for me to order more, enclosed is a money order for two dozen more cassettes." Robert W. Bruggemeyer, Long Beach, CA

"The quality to price ratio is very high on these cassettes — had very good luck loading programs back to the computer." Douglas Ekuan, Millinocket, ME

"High quality tape in the proper lengths and at the right price. Keep it up." William E. Brown, Jr., Reisterstown, MD

"YOU'VE TRIED THE REST, NOW BUY THE BEST"

Call: 213/710-1430 for IMMEDIATE SHIPMENT on Credit Card Orders.

ORDER NOW...Mail to: **YORK 10 Computerware**
24573 Kittridge St., #C1, Canoga Park, CA 91307

Please send cassettes checked below:

LENGTH	1 ORDER	2 ORDERS	TOTAL
C-10	☐ 8.00	☐ 14.40	
C-20	☐ 10.00	☐ 18.00	
C-45	☐ 13.00	☐ 23.00	
C-90	☐ 21.75	☐ 39.00	
		SUB TOTAL	
Calif. residents, add 6% sales tax			
Shipping: 1 doz. $2. 2 doz. $3. 10 add'l doz. $1			
		TOTAL	

WRITE FOR QUANTITY DISCOUNTS
Shipped both each by UPS to street address in Cont U.S.A. only. We cannot ship to P. O. Boxes

☐ Check or M.O. enclosed ☐ Charge to my Credit Card
☐ VISA ☐ MASTER CARD Expires date

account no
name
address
city state zip
sig/nature

CIRCLE 283 ON READER SERVICE CARD

MICROSTAT NOW AVAILABLE FOR CP/M*

MICROSTAT, the most powerful statistics package available for microcomputers, is completely file-oriented with a powerful Data Management Subsystem (DMS) that allows you to edit, delete, augment, sort, rank-order, lag and transform (11 transformations, including linear, exponential and log) existing data into new data. After a file is created with DMS, Microstat provides statistical analysis in the following general areas: Descriptive Statistics (mean, sample, and population S.D., variance, etc.), Frequency Distributions (grouped or individual), Hypothesis Testing (mean or proportion), Correlation and Regression Analysis (with support statistics), Non-parametric Tests (Kolmogorov-Smirnov, Wilcoxon, etc.), Probability Distributions (8 of them), Crosstabs and Chi-square, ANOVA (one and two way), Factorials, Combinations and Permutations, plus other unique and useful features.

MICROSTAT requires 48K, Microsoft MBasic with CP/M and is sent on a single-density 8" Disk. It is also available on 5" diskettes for North Star DOS and Basic (32K and two drives recommended), specify which when ordering. The price for Microstat is $250.00. The user's manual is $15.00 and includes sample data and printouts. We have other business and educational software, call or write:

master charge THE INTERBANK CARD

ECOSOFT
P.O. Box 68602
Indianapolis, IN 46268
(317) 283-8883

CP/M is a registered trade mark of Digital Research

CIRCLE 154 ON READER SERVICE CARD

If the player survives the first tour of service, he may reenlist. Benefits are bestowed on the player for rank, length of service, and branch of service (some branches are more hazardous than others). Prizes at the player's final discharge can include tickets for star travel, a yearly pension, all sorts of experience, a membership in the highly prized Traveller's Aid Society, and even, on a rare occasion, ownership of a star ship—Scout Class. Various attributes of one player may make him valuable to another. As in life, players have adventures together and learn to rely on one another.

The sooner the character is created, the sooner the player can start exploring the universe. A typical opening exchange may go something like this:

Referee (Playing the part of a customs official on Regina): "What is your destination?"

Player 1: "Dragonia."

Player 2: "Moonglow."

Referee: "Your tickets and passports please."

Player 1: "Here. One mid-passage."

Player 2: "Low passage."

Player 2, after being discharged as Third Officer in the Merchants, is on his way to pick up a newly-constructed Serpent Class Scout Ship on Moonglow. Heavily in debt to the tune of 21,630,000 credits. Player 2 has allied himself with Player 1. They have combined their funds to hire a band of mercenaries led by Player 3 to hijack the passenger starship. They will then be able to ransom the lives of all first class passengers and raise the funds to buy their dream. Player 4 has accepted a commission in the Imperial Navy and is sworn to uphold the loosely defined laws of the Imperial Confederation.

Referee: "Your weapons must be checked before entering the boarding area."

Player 3 emerges from hiding with nine mercenaries in battle dress equipped with laser carbines. Four Port Guard androids with laser rifles, alerted by startled passersby are thrown into action. They open fire hitting two mercenaries before being eliminated.

And so goes the play. The referee describes the action through the use of his tables and charts. Possibilities are infinite. Charts are endless. And too much of both tend, as in most role-playing games, to lessen the players' enjoyment.

Computerizing Traveller

I am totally convinced that computers can be employed successfully as tools to increase enjoyment and make life easier for the referee. For Pete's sake, if you don't have one it's a great excuse to buy a computer!

The following program modules take some of the drudgery out of refereeing while enabling the player to establish the basic worlds of the universe. To use this program all you need is a hex paper map sold in most hobby stores, colored pencils or press on numbers, and of course, your computer (in this case, I have used a TRS-80). Each record number as recorded on disk becomes a separate world occurrence and is marked on the hex map. As soon as the worlds have been created and marked, consult the jump generator to determine the routes for star lanes. Each world may then be neatly tucked away on disk or can be printed out using the NEWDOS JKL screen print command and stored in a notebook for future reference. If you decide to store on disk, the second program will read the file by record number and describe the world. Just record the record number on the hex map and presto, your map is linked to the computer. Oh, by the way, the program is written using NEWDOS80 DISK FILES and must be changed if you intend to run with TRSDOS. I have marked those lines for readers who wish to do this.

The following program modules take some of the drudgery out of refereeing while maintaining the referee concept.

The second module is a character generator which generates a Traveller character. This is interactive with each player making early decisions about his or her characters. The referee may advise the player about the best course of action besides helping to whet the player's appetite for adventure. In the end this will provide a neatly described character for both referee and player.

These are only a referee's aids and are not intended to limit his imagination. Most referees have very fertile imaginations.

For those readers who don't like typing code into your computer, I would be glad to send a copy. You provide a clean disk and $5. and I will provide you with a copy of the three programs listed. □

World Generator

```
10 'WORLD GENERATOR FOR TRAVELER(TM) - GAME DESIGNER WORKSHOP
20 'BY CHRISTOPHER C. MARVEL / MARVEL SOFTWARE  COPYRIGHT 1980
30 '1313 BEAUFORT, LARAMIE, WYOMING 82070
40 RANDOM
50 CLEAR1000:DEFSTR A:DIMP1$(15),P2$(15),P3$(15)
60 DEF FNB=RND(6)+RND(6)
70 DEF FNC=B2+B1
80 C1=0:B=0:B1=0:B2=0:RN=0
90 CLS:PRINTCHR$(23):PRINT:PRINT"+ + + + + w o r l d  + + + + +"
100 PRINT"+ + + + g e n e r a t o r + + + +"
110 PRINT:PRINT"*****************************************************
*******  ":PRINT:PRINT              BY"
120 PRINT:PRINT"CHRISTOPHER C. MARVEL"
140 PRINT:PRINT"                  COPYRIGHT 1980"
150 FORJ=1TO3000:NEXT
160 CLS:PRINT@320,"GENERATE 1 - WORLDS OR 2 - JUMPS FOR PLANETS":INPUT""1X$
170 ONX$GOTO 180,2050
180 OPEN"O",1,"WORLD/DAT","MF",150       'NEWDOS80 FILE
190 INPUT"DO YOU WISH TO GENERATE AN ENTIRELY NEW GALAXY "1A$:IFLEF1$(A$,
1)="N" THEN210
200 INPUT"LAST RECORD IN WORLD DATA FILE"1RN ' UPDATE @LAXY FILE
210 B=0:B1=0:B2=0:S1=0:S2=0:I=0:J=0:A0="0":P1$="":P2$="":P3$="":N$="" 'NEW
 @LAXY
220 CLS:PRINT@320,"****************** W O R L D   G E N E R A T O R *****
******* ***"
230 B=RND(2)
240 IFB=2THEN270
250 PRINT"ND WORLD IN HEX":INPUT"ENTER TO CONTINUE"1X$    'DOES WORLD
EXIST IN HEX
260 GOTO220
270 INPUT"NAME PLANET":N$
280 CLS:PRINT"======PLANET=====================":N$1"========="
 '@ENERATE @LANET
290 GOSUB3070:GOSUB2120:GOSUB1830
:."1A1
300 PRINT"STARPORT.....................................
310 IFA1="A"PRINT"EXCELLENT. REFINED FUEL. ANNUAL MAINTENANCE. SHIPYARD
CAPABLE OFHANDLING STARSHIPS AND NO-STARSHIPS."
320 IFA1="B"PRINT"GOOD. REFINED FUEL. ANNUAL MAINTENANCE. SHIPYARD CAPABLE
OF CONSTRUCTING NON STARSHIPS."
330 IFA1="C"PRINT"ROUTINE. ONLY UNREFINED FUEL AVAILAIBLE. REASONABLE
REPAIR FACILITY PRESENT."
340 IFA1="D"PRINT"POOR. ONLY UNREFINED FUEL AVAILABLE. NO REPAIR.)
350 IFA1="E"PRINT"FRONTIER.  NO FUEL OR BASES."
```

TRS-80 ADVENTURES FOR 16K COLOR 80

Extended color or Level II BASIC

ESCAPE FROM MARS — You are stranded on Mars and somewhere in the Martian city are the parts you need to repair your ship. Our best adventure for naw adventurers.

TREK ADVENTURE — You will recognize the spaceship this takes place on. The crew has left—for good rasson—but they forgot you—and the "Orbit is Decaying." Almost as good as being there.

PYRAMID — Our most advanced and challenging adventura, this takes place in our own special ancient pyramid. The builders were as nasty as pyramid builders usually are, and ransacking this one is a dangerous job.

ADVENTURES are all written in BASIC, all come with listings, and each sells for $14.95.

ARCADE AND THINKING GAMES

16K and extended or level II BASIC

TIME TREK, REAL TIME REAL GRAPHICS TREK. See the torpedoes fly and the Klinsons explode. No more scolling displays, no more turn taking. — This one has real time and real displays. In BASIC — for 16K level II or extanded color BASIC. $14.95.

STARFIGHTER — This one man space war game pits you against spacecruisers, battlewagons, and one man fighters. You have tha view from your cockpit window, a working instrument panel, and your wits. Another real time goody.

BATTLEFLEET — This grown-up version of Battleship is the toughest thinking game availabla on 80 computers. There is no luck involved as you seak out the 80's hidden fleet. This is a topographical toughie. $9.95.

SLASHBALL — A two player game of strategy and skill, this is like nothing you have evar seen before. This takes fast fingers, quick wits and concentration. Playable from age 6 to 65, it is a good family gama. $9.95.

FREE CATALOG

AARDVARK-80
2352 S. Commerce, Walled Lake, MI 48088
(313) 669-3110

CIRCLE 112 ON READER SERVICE CARD

TERMINALS FROM TRANSNET

PURCHASE PLAN • 12-24 MONTH FULL OWNERSHIP PLAN • 36 MONTH LEASE PLAN

	DESCRIPTION	PURCHASE PRICE	PER MONTH 12 MOS	24 MOS	36 MOS
DEC	LA36 DECwriter II	$1,095	$105	$ 58	$ 40
	LA34 DECwriter IV	995	95	53	36
	LA34 DECwriter IV Forms Ctrl	1,095	105	58	40
	LA120 DECwriter III KSR	2,295	220	122	83
	LA120 DECwriter III RO	2,095	200	112	75
	VT100 CRT DECscope	1,595	153	85	58
	VT132 CRT DECscope	1,995	190	106	72
TEXAS INSTRUMENTS	TI745 Portable Terminal	1,595	153	85	58
	TI765 Bubble Memory Terminal	2,595	249	138	93
	TI Insight 10 Terminal	945	90	53	34
	TI785 Portable KSR, 120 CPS	2,395	230	128	86
	TI787 Portable KSR, 120 CPS	2,845	273	152	102
	TI810 RO Printer	1,895	182	102	69
	TI820 KSR Printer	2,195	211	117	80
DATAMEDIA	DT80 1 CRT Terminal	1,895	162	90	61
	DT80 3 CRT Terminal	1,295	125	70	48
	DT80 SL APL 15 CRT	2,295	220	122	83
LEAR SIEGLER	ADM3A CRT Terminal	875	84	47	32
	ADM31CRT Terminal	1,450	139	78	53
	ADM42 CRT Terminal	2,195	211	117	79
HAZELTINE	1420 CRT Terminal	945	91	51	34
	1500 CRT Terminal	1,095	105	58	40
	1552 CRT Terminal	1,295	125	70	48
TELEVIDEO	920 CRT Terminal	895	86	48	32
	950 CRT Terminal	1,075	103	57	39
NEC SPINWRITER	Letter Quality, 55 15 RO	2,895	278	154	104
	Letter Quality, 55 25 KSR	3,295	316	175	119
QUME	Letter Quality KSR, 55 CPS	3,395	326	181	123
	Letter Quality RO, 55 CPS	2,895	278	154	104
CENTRONICS	730 Desk Top Printer	715	69	39	26
	737 W P Desk Top Printer	895	86	48	32

FULL OWNERSHIP AFTER 12 OR 24 MONTHS • 10% PURCHASE OPTION AFTER 36 MONTHS

MICROCOMPUTERS
APPLE • COMMODORE • HP85 • DEC LSI 11

ACCESSORIES AND PERIPHERAL EQUIPMENT
ACOUSTIC COUPLERS • MODEMS • THERMAL PAPER • RIBBONS • INTERFACE MODULES • FLOPPY DISK UNITS

TRANSNET CORPORATION
1945 ROUTE 22 • UNION, N.J. 07083 • (201) 688-7800
TWX 710-985-5485

CIRCLE 181 ON READER SERVICE CARD

SHADOWHAWK

A LONE SPACE PIRATE ATTACKS THE GALACTIC EMPIRE

You are the sole surviving Naval Commander of the Free Space Confederation. The Galactic Empire has overrun the entire solar system . . **except** for your remote outpost on a moon at the outer limits. Exploiting the unmatched ship **SHADOW HAWK I**, you prey on the Empire's merchant fleet to capture enemy material, which can be bartered for better weaponry, shielding, missiles, etc., for **SHADOW HAWK I**. But the Empire's interceptors, corvettes, lancers, destroyers, and cruisers are probing the galaxy for you. You must evade them and the deadly battle stations throughout. Your skill is measured by nine rankings, up to **STAR LORD**. Warning: You must be very, very good to reach **STAR LORD** rank! Very good indeed!

SHADOW HAWK I uses **THREE-AXIS** rotation high resolution 3-D graphics! On **Apple II**, **DOS 3.3**, or **Atari 800**, 48K with disk drive. Joysticks required. Specify **Apple** or **Atari** on your order. Games are on **Dysan** diskettes. Game time: 15-30 min. **$49.95** ppd. VISA & MasterCard accepted. DEALER INQUIRIES ARE WELCOME

107 E. Main #2, Medford, OR 97501
(503) 779-0078

"**Apple II**, **DOS 3.3**" and **Atari 800** are registered trademarks, respectively, of Apple Computer, Inc. and Warner Communications, Inc.

HORIZON SIMULATIONS

The games of tomorrow for the minds of today.

CIRCLE 183 ON READER SERVICE CARD

```
360 IFA1="X"PRINT"NO STARPORT "
370 IFS1=1PRINT"NAVAL BASE PRESENT"
380 IFS2=1PRINT"SCOUT BASE PRESENT"
390 IFA0="1"PRINT"RDSETTE WORLDS (3)"
400 IFA0="2"PRINT"RINGWORLDS"
410 IFA0="3"PRINT"SHPEREWORLDS - ARTIFICIAL ATMDSPHERE";A5="0"
420 PRINT"PLANETARY SIZE (MILES DIAMETER) ........."
430 IFA4="0"PRINT"ASTERDID/PLANETOID COMPLEX'
440 IFA4="1"PRINT"1000 "
450 IFA4="2"PRINT"2000 "
460 IFA4="3"PRINT"3000 "
470 IFA4="4"PRINT"4000 "
480 IFA4="5"PRINT"5000 "
490 IFA4="6"PRINT"6000 "
500 IFA4="7"PRINT"7000 "
510 IFA4="8"PRINT"8000 "
520 IFA4="9"PRINT"9000 "
530 IFA4="A"PRINT"10000 "
540 IFA4="B"PRINT"11000 "
550 IFA4="C"PRINT"12000 "
560 PRINT"PLANETARY ATMDSPHERE................";
570 IFA5="0"PRINT"NDNE"
580 IFA5="1"PRINT"TRACE"
590 IFA5="2"PRINT"VERY THIN,TAINTED"
600 IFA5="3"PRINT"VERY THIN"
610 IFA5="4"PRINT"THIN,TAINTED"
620 IFA5="5"PRINT"THIN"
630 IFA5="6"PRINT"STANDARD"
640 IFA5="7"PRINT"STANDARD,TAINTED"
650 IFA5="8"PRINT"DENSE"
660 IFA5="9"PRINT"DENSE,TAINTED"
670 IFA5="A"PRINT"EXDTIC"
680 IFA5="B"PRINT"CORRDSIVE
690 IFA5="C"PRINT"INSIDIDUS"
700 PRINT"HYDRDGRAPHIC % ........................";
710 IFA6="0"PRINT"NO FREE STANDING WATER"
720 IFA6="1"PRINT"10%"
730 IFA6="2"PRINT"20%"
740 IFA6="3"PRINT"30%"
750 IFA6="4"PRINT"40%"
760 IFA6="5"PRINT"50%"
770 IFA6="6"PRINT"60%"
780 IFA6="7"PRINT"70%"
790 IFA6="8"PRINT"80%"
800 IFA6="9"PRINT"90%"
810 IFA6="A"PRINT"ALL WATER. NO LAND MASSES"
820 PRINT"POPULATION.......................";
830 IFA7="0"PRINT"NDNE"
840 IFA7="1"PRINT"10"
850 IFA7="2"PRINT"100"
860 IFA7="3"PRINT"1000"
870 IFA7="4"PRINT"10.000"
880 IFA7="5"PRINT"100.000"
890 IFA7="6"PRINT"1.000.000"
900 IFA7="7"PRINT"10.000.000"
910 IFA7="8"PRINT"100.000.000"
920 IFA7="9"PRINT"1.000.000.000"
930 IFA7="A"PRINT"10.000.000.000"
940 PRINT"GDVERNMENT TYPE.............................................."
950 IFA8="0"PRINT"ND GDVERNMENT STRUCTURE. IN MANY CASES, FAMILY BDNDS WILL
  PREDDMINATE.
960 IFA8="1"PRINT"COMPANY/CDRPDRATIDN. RULING FUNCTIDNS ARE ASSUMED BY A
CDMPANY MANAGERIAL ELITE, AND MDST CITZENRY ARE CDMPANY EMPLDYEES DR
DEPENDENTS."
970 IFA8="2"PRINT"PARTICIPATING DEMDCRACY. RULING FUNCTIDN DECISIDNS ARE
REACHED BY ADVICE DF THE CITIZENRY DIRECTLY."
980 IFA8="3"PRINT"SELF PERPETUATING OLIGARCHY. RULING FUNCTIDNS ARE
PERFDRMED BY  ARESTRICTED MINDRITY, WITH LITTLE DR NO INPUT FRDM THE MASS
DF  CITIZENRY."
990 IFA8="4"PRINT"REPRESENTATIVE DEMDCRACY. RULING FUNCTIDNS ARE PERFDRMED
 BY  ELECTED REPRESENTATIVES."
1000 IFA8="5"PRINT"FEUDAL TECHNDCRACY. RULING FUNCTIDNS ARE PERFDRMED BY
SPECIFIC  INDIVIDUALS FDR PERSDNS WHD AGREE TD BE RULED BY THEM. RELATIDN
SHIPS'ARE BASED DN THE PERFDRMANCE DF TECHNICAL ACTIVITIES WHICH ARE
MUTUALLY  BENEFICIAL."
1010 IFA8="6"PRINT"CAPTIVE GDVERNMENT. RULING FUNCTIDNS ARE PERFDRMED BY AN
IMPDSED GDVERNMENT FRDM AN DUTSIDE GRDUP. A CDLDNY DR CDNQUERED AREA."
1020 IFA8="7"PRINT"BALKANIZATIDN. ND CENTRAL RULING AUTHDRITY EXISTS! RIVAL
  GDVERNMENTS CDMPETE FDR CDNTRDL. LAW LEVEL REFERS TD THE  GDVERNMENT NE
AREST THE STARPDRT."
1030 IFA8="8"PRINT"CIVIL SERVICE BUREAUCRACY. RULING FUNCTIDNS ARE PERFDRMED
BY GDVERNMENT AGENCIES EMPLDYING INDIVIDUALS WITH A SELECTED  EXPERTISE."
1040 IFA8="9"PRINT"IMPERSDNAL BUREAUCRACY. RULING FUNCTIDNS ARE PERFDRMED BY
  AGENCIES WHICH HAVE BECDME INSULATED FRDM THE GDVERNED CITIZENRY
1050 IFA8="A"PRINT"CHARISMATIC DICTATDRSHIP. RULING FUNCTIDNS ARE PERFDRMED
 BY AGENCIES DIRECTED BY A SINDLE LEADER WHD ENJDYS THE DVERWHELMING
CDNFIDENCE DF  THE CITIZENRY."
1060 IFA8="B"PRINT"NDN-CHARISMATIC LEADER. APREVIDUS CHARISMATIC DICTATDR
HAS BE EN REPLACED BY A LEADER THRDUGH NDRMAL CHANNELS."
1070 IFA8="C"PRINT"CHARISMATIC DLIGARCHY. RULING FUNCTIDNS ARE PERFDRMED
 BY A  SELECT GRDUP DF MEMBERS DF AN DRGANIZATIDN DR CLASS WHICH ENJDYSTHE
DVERWHELMING CDNFIDENCE DF THE CITIZENRY."
1080 IFA8="D"PRINT"RELIGIDUS DICTATDRSHIP.RULING FUNCTIDNS ARE PERFDRMED BY
A RELIGIDUS DRGANIZATIDN WITHDUT REGARD TD THE SPECIFIC NEEDS DF
THE CITIZENRY."
1090 B=VAL(A$):INPUT"ENTER TD CDNTINUE";X$:CLS:PRINT"LAW LEVEL..........
........................................................."
1100 IFB=0PRINT"ND LAWS AFFECTING WEAPDN PDSSESSIDN DR WEAPDN DWNERSHIP."
1110 IFB=1PRINT"CERTAIN WEAPDNS ARE PRDHIBITED.INCLUDING SPECIFICALLY
1)BDDY PISTDLS WHICH ARE UNDETECTABLE BY STANDARD DETECTDRS 2)EXPLDSIVE
WEAPDNS SUCH AS  BDMBS DR GRENADES, AND 3) PDISDN GAS."
1120 IFB=2PRINT"PDRTABLE ENERGY WEAPDNS, SUCH AS LASER RIFLES DR
CARBINES ARE  PRDHIBITED, SHIP'S GUNNERY IS NDT AFFECTED"
1130 IFB=3PRINT"WEAPDNS DF A STRICT MILITARY NATURE (SUCH AS MACHINE
GUNS DR) AUTDMATIC RIFLES. THDUGH NDT SUBMACHINEGUNS) ARE PRDHIBITED."
1140 INPUT"PRESS ENTER TD CDNTINUE";X$
1150 IFB=4PRINT"LIGHT ASSAULT WEAPDNS (SUCH AS SUBMACHINE GUNS) ARE
PRDHIBITED. "
1160 IFB=5PRINT"PERSDNAL CDNCEALABLE FIREARMS (SUCH AS PISTDLS AND
REVDLVERS)  ARE PRDHIBITED."
1170 IFB=6PRINT"MDST FIREARMS  ARE PRDHIBITED. THE CARRYINGDF ANY TYPE
DF WEAPDN IS DISCDURAGED."
1180 IFB=7PRINT"SHDTGUNS ARE PRDHIBITED."
1190 IFB=8PRINT"LDNG BLADED WEAPDNS (AL BLADE WEAPDNS EXCEPT DAGGERS)
ARE  STRICTLY CDNTRDLLED. DPEN PDSSESSIDN IN PUBLIC IS PRDHIBITED.
DWNERSHIP IS.HDWEVER, NDT RESTRICTED. "
1200 IFB=9PRINT"PDSSESIDN DF ANY WEAPDN DUTSIDE DNE'S HDME IS PRDHIBITED."
1210 INPUT"ENTER TD CDNTINUE";X$
1220 CLS:PRINT"TECNDLDGICAL INDEX.....................................
 ......."
1230 PRINT"========= WEAPDNS =========
1240 PRINTTAB(8)"PERSDNAL";TAB(28);"ARMDR";TAB(38);"SPECIAL";TAB(48);
 "COMPUTERS"  ;TAB(58);"CDMMUNICATIDN"
1250 IFT=0PRINTTAB(8)"CLUB, CUDGEL, SPEAR";TAB(58)"RUNNERS"
1260 IFT=1PRINTTAB(8)"DAGGER,PIKE,SWDRD";TAB(28);"JACK";TAB(38);
"CATAPULT";TAB(48);"ABACUS";TAB(58);"HELIDGRAPH"
1270 IFT=2PRINTTAB(8)"HALBRED, BRDADSWDRD";TAB(38);"CANNDN"
1280 IFT=3PRINTTAB(8)"FDIL,CUTLASS,BLADE"
1290 IFT=3PRINT"BAYDNET"
1300 IFT=4PRINTTAB(8)"REVDLVER,SHDTGUN";TAB(28);"CLDTH";TAB(38);"ARTIL
 LERY";TAB( 48);"ADDING";TAB(58);"TELEPHDNES"
1310 IFT=4PRINTTAB(48)"MACHINES"
```

The story behind the two best selling computer games books in the world.

Computer Games

by David H. Ahl

Everybody likes games. Children like tic tac toe. Gamblers like blackjack. Trekkies like Star Trek. Almost everyone has a favorite game or two.

It Started In 1971

Ten years ago when I was at Digital Equipment Corp. (DEC), we wanted a painless way to show reluctant educators that computers weren't scary or difficult to use. Games and simulations seemed like a good method.

So I put out a call to all our customers to send us their best computer games. The response was overwhelming. I got 21 versions of blackjack, 15 of nim and 12 of battleship.

From this enormous outpouring I selected the 90 best games and added 11 that I had written myself for a total of 101. I edited these into a book called 101 Basic Computer Games which was published by DEC. It still is.

When I left DEC in 1974 I asked for the rights to print the book independently. They agreed as long as the name was changed.

Contents of *Basic Computer Games* (right) and *More Basic Computer Games* (below).

Artillery-3
Baccarat
Bible Quiz
Big 6
Binary
Blackbox
Bobstones
Bocce
Boga II
Bumbrun
Bridge-It
Camel
Chase
Chuck-A-Luck
Close Encounters
Column
Concentration
Condot
Convoy
Corral
Countdown
Cup
Dealer's Choice
Deepspace
Deluse
Dodgem
Doors
Drag
Dr. Z
Eliza
Father
Flip
Four In A Row
Geowar
Grand Prix
Guess-It
ICBM
Inkblot
Joust
Jumping Balls
Keno
L Game
Life Expectancy
Lissajous
Magic Square
Man-Eating Rabbit
Maneuvers
Mastermind
Masterbagels
Matpuzzle
Maze
Millionaire
Minotaur
Motorcycle Jump
Nomad
Not One
Obstacle
Octrix
Pasart
Pasart 2
Pinball
Rabbit Chase
Roadrace
Rotate
Safe
Scales
Schmoo
Seabattle
Seawar
Shoot
Smash
Strike 9
Tennis
Tickertape
TV Plot
Twonky
Two-to-Ten
UFO
Under & Over
Van Gam
Warfish
Word Search Puzzle
Wumpus 1
Wumpus 2
Introduction
The Basic Language
Conversion to Other Basics
Acey Ducey
Amazing
Animal
Awari
Bagels
Banner
Basketball
Batnum
Battle
Blackjack
Bombardment
Bombs Away
Bounce
Bowling
Boxing
Bug
Bullfight
Bullseye
Bunny
Buzzword
Calendar
Change
Checkers
Chemist
Chief
Chomp
Civil War
Combat
Craps
Cube
Depth Charge
Diamond
Dice
Digits
Even Wins
Flip Flop
Football
Fur Trader
Golf
Gomoko
Guess
Gunner
Hammurabi
Hangman
Hello
Hexapawn
Hi-Lo
High I-O
Hockey
Horserace
Hurkle
Kinema
King
Letter
Life
Life For Two
Literature Quiz
Love
Lunar LEM Rocket
Master Mind
Math Dice
Mugwump
Name
Nicomachus
Nim
Number
One Check
Orbit
Pizza
Poetry
Poker
Queen
Reverse
Rock, Scissors, Paper
Roulette
Russian Roulette
Salvo
Sine Wave
Slalom
Slots
Splat
Stars
Stock Market
Super Star Trek
Synonym
Target
3-D Plot
3-D Tic-Tac-Toe
Tic Tac toe
Tower
Train
Trap
23 Matches
War
Weekday
Word

Converted to Microsoft Basic

The games in the original book were in many different dialects of Basic. So Steve North and I converted all the games to standard Microsoft Basic, expanded the descriptions and published the book under the new name Basic Computer Games.

Over the next three years, people sent in improved versions of many of the games along with scores of new ones. So in 1979, we totally revised and corrected Basic Computer Games and published a completely new companion volume of 84 additional games called More Basic Computer Games. This edition is available in both Microsoft Basic and TRS-80 Basic for owners of the TRS-80 computer.

Today Basic Computer Games is in its fifth printing and More Basic Computer Games is in its second. Combined sales are over one half million copies making them the best selling pair of books in recreational computing by a wide margin. There are many imitators, but all offer a fraction of the number of games and cost far more.

The games in these books include classic board games like checkers. They include challenging simulation games like Camel (get across the desert on your camel) and Super Star Trek. There are number games like Guess My Number, Stars and Battle of Numbers. You'll find gambling games like blackjack, keno, and poker. All told there are 185 different games in these two books.

Whether you're just getting started with computers or a proficient programmer, you'll find something of interest. You'll find 15-line games and 400-line games and everything in between.

The value offered by these books is outstanding. Every other publisher has raised the price of their books yet these sell for the same price as they did in 1974.

Moneyback Guarantee

Examine one or both of these books and key some games into your computer. If you're not completely satisfied we'll refund the full purchase price plus your return postage.

Basic Computer Games costs only $7.50 and More Basic Computer Games just $7.95 for either the Microsoft or TRS-80 edition (please specify your choice on your order). Both books together are $15. Send payment plus $2.00 shipping and handling to Creative Computing Press, Morris Plains, NJ 07950. Visa, MasterCard and American Express orders should include card number and expiration date. Charge card orders may also be called in toll-free to 800-631-8112 (In NJ 201-540-0445).

Order today to turn your computer into the best game player on the block.

creative computing

Morris Plains, NJ 07950
Toll-free 800-631-8112
(In NJ 201-540-0445)

CIRCLE 350 ON READER SERVICE CARD

```
1320 IFT=5PRINTTAB(0)"CARBINE,RIFLE,SMG"!TAB(30);"SANDCASTER";TAB(40);
"MODEL/1"; TAB(50);"RADIO"
1330 IFT=5PRINTTAB(0)"PISTOL";TAB(30);"MORTARS"
1340 IFT=6PRINTTAB(0)"AUTO RIFLE";TAB(20);"MISSILES";TAB(40);"MODEL/1BIS
 ";TAB(50 );"TELEVISION"
1350 IFT=7PRINTTAB(0)"BODY PISTOL";TAB(20);"MESH";TAB(30);"PULSE LASER"
;TAB(40); "  MODEL/2"
1360 IFT=8PRINTTAB(0)"LASER CARBINE";TAB(28);"AUTO-CANNON";TAB(40);
"MODEL/2BIS"
1370 IFT=9PRINTTAB(0)"LASER RIFLE";TAB(20);"ABLAT";TAB(30);"BM LASER";
TAB(40);"MODEL/3"
1380 IFT=10PRINTTAB(20)"REFLEC";TAB(40);"MODEL/4"
1390 IFT=11PRINTTAB(40)"MODEL/5"
1400 IFT=12PRINTTAB(40)"MODEL/6"
1410 IFT=13PRINTTAB(20)"BATTLE DRESS";TAB(40);"MODEL/7"
1420 IFT=17PRINTTAB(40)"ARTIFICIAL"
1430 IFT=17PRINTTAB(40)"INTELLIGENCE"
1440 PRINT"==============TRANSPORTATION================"
1450 PRINTTAB(0)"WATER";TAB(20);"LAND";TAB(30);"AIR";TAB(40);"SPACE";TAB
(50);"FUELS"
1460 IFT=20PRINTTAB(0)"CANOES";TAB(20);"CARTS";TAB(30);"WHEELS"
1470 IFT=1PRINTTAB(0)"GALLEY";TAB(20);"WAGON"
1480 IFT=2PRINTTAB(50)"WIND"
1490 IFT=3PRINTTAB(0)"SAILING SHIPS";TAB(30);"HOT AIR BALLOON";TAB(50);
"WATER WHEEL"
1500 IFT=4PRINTTAB(0)"STEAMSHIPS";TAB(20);"TRAINS";TAB(30);"DIRIGIBLES";
TAB(50); "COAL"
1510 IFT=5PRINTTAB(20)"GROUND ";TAB(30);"FIXED ";TAB(50);"OIL"
1520 IFT=5PRINTTAB(20)"CAR";TAB(30);"WING"
1530 IFT=6PRINTTAB(0)"SUBMERSIBLES";TAB(20);"ATV,AFV";TAB(30);"ROTARY
WING";TAB(50);"FISSION"
1540 IFT=SORT=6PRINTTAB(30)"AIRCRAFT"
1550 IFT=7PRINTTAB(0)"HOVERCRAFT";TAB(20);"HOVERCRAFT";TAB(40);
"NON-STARSHIP";TAB(55);"SOLAR"
1560 IFT=8PRINTTAB(30)"AIR/RAFT";TAB(50);"FUSION"
1570 IFT=9ANDT=(1SPRINTTAB(40)"STARSHIPS"
1580 IFT=10PRINTTAB(40)"DRIVE H"
1590 IFT=11PRINTTAB(40)"DRIVE K"
1600 IFT=12PRINTTAB(30)"GRAV BELTS";TAB(40);"DRIVE N"
1610 IFT=13PRINTTAB(40)"DRIVE O"
1620 IFT=14PRINTTAB(40)"DRIVE U"
1630 IFT=)10ANDT=(14PRINTTAB(40)"OR LESS"
1640 IFT=15PRINTTAB(40)"ALL DRIVES"
1650 IFT=16PRINT"********** MATTER TRANSPORT **********"
1660 IFT=17PRINTTAB(50)"ANTI MATTER"
1670 PRINT:PRINT:PRINT"REFEREE MAY ADD TO ANY BLANK LINES"
1680 INPUT"DO YOU WISH TO ADD";A$:IFLEFT$(A$,1)="N"THEN1730
1690 INPUT"ADDITION TO TECHNOLOGICAL LEVEL - HOW MANY (MAX 3)";B
1700 INPUT"NAME OF ADDITION";P1$:IFB=1THEN1730
1710 INPUT"NAME OF ADDITION";P2$:IFB=2THEN1730
1720 INPUT"NAME OF ADDITION";P3$
1730 CLS:PRINT"PLANET=================================";IN$:PRINT
1740 D$=A1+A4+A5+A6+A7+A8+A9+TF$:PRINT"UNIVERSAL PLANET PROFILE.........
...";ID$
1750 PRINT"TECH INDEX";T
1760 PRINT"SPECIAL ADDITIONS"
1770 PRINTP1$:PRINTP2$:PRINTP3$
1780 INPUT"DO YOU WISH TO STORE DATA";A$:IFLEFT$(A$,1)()"Y"THEN1800
1790 RN=RN+1:GOSUB 3230:PRINT"WORLD ";IN$;" IS RECORD #";RN;" ON WORLD
DATA FILE"
1800 INPUT"DO YOU WISH TO CONTINUE";A$
1810 IF LEFT$(A$,1)()"N"THEN210
1820 CLOSE:END
1830 'TECH INDEX
1840 IFA1="A"B2=6:B2=FNC
1850 IFA1="B"B2=4:B2=FNC
1860 IFA1="C"B2=2:B2=FNC
1870 IFA1="X"B2=-4:B2=FNC
1880 IFA4="0"ORA4="1"B2=2:B2=FNC
1890 IFA4="2"ORA4="3"ORA4="4"B2=1:B2=FNC
1900 IFA5="0"ORA5="1"ORA5="2"ORA5="3"ORA5="A"ORA5="B"ORA5="C"ORA5="D"ORA5
="E"B2= 1:B2=FNC
1910 IFA6="9"B2=2:B2=FNC
1920 IFA6="A"B2=1:B2=FNC
1930 IFA7="1"ORA7="2"ORA7="3"ORA7="4"ORA7="5"B2=1:B2=FNC
1940 IFA7="9"B2=2:B2=FNC
1950 IFA7="A"B2=4:B2=FNC
1960 IFA8="0"ORA8="5":B2=FNC
1970 IFA8="D"B2=FNC
1980 T=ABS(RND(6)+B2)
1990 B=T
2000 IFB)9THEN2020
2010 TF$=RIGHT$(STR$(B),1)
2020 IFB=1TF$="X"
2030 IFB=10TF$="A"
2040 IFB=11TF$="B"
2050 IFB=12TF$="C"
2060 IFB=13TF$="D"
2070 IFB=14TF$="E"
2080 IFB=15TF$="F"
2090 IFB=16TF$="G"
2100 IFB=17TF$="H"
2110 RETURN
2120 B=RND(14)-1
2130 GOSUB2330:A4=A2
2140 B1=B
2150 IFB1=0B=0:GOTO2170
2160 B=ABS(FNB-7+B1)
2170 GOSUB2330:A5=A2
2180 IFB1=1ORB1=0B=0:GOTO2210
2190 IFB1)9B=FNB-11:GOTO2210
2200 B=ABS(FNB-7+B1)
2210 GOSUB2330:A6=A2
2220 B=ABS(FNB-2)
2230 GOSUB2330:A7=A2
2240 B1=B1+B=ABS(FNB-7+B1)
2250 GOSUB2330:A8=A2
2260 B1=B1+B=ABS(FNB-7+B1)
2270 GOSUB2330:A9=A2
2280 B=RND(100)
2290 IFB=1A0="1"
2300 IFB=2A0="2"
2310 IFB=3A0="3"
2320 RETURN
2330 'WORLD RANDOMIZER
2340 IFB(0B=0
2350 IFB)9THEN2380
2360 A2=RIGHT$(STR$(B),1)
2370 RETURN
2380 IFB=10A2="A"
2390 IFB=11A2="B"
2400 IFB=12A2="C"
2410 IFB=13A2="D"
2420 RETURN

2430 DS=0:C1=0:CLS:PRINT"=================== JUMP GENERATOR =========
======= ========":PRINT:PRINT    'DETERMINE JUMP ROUTES BETWEEN PLANETS
2440 INPUT"STARPORT 1 =";A2
2450 INPUT"STARPORT 2 =";A3
2460 INPUT"DISTANCE IN HEXES BETWEEN STAR PORTS";DS
2470 B=RND(6)
2480 IFA2="A"THENGOSUB2580:GOTO2540
2490 IFA2="B"THENGOSUB2740:GOTO2540
2500 IFA2="C"ANDDS=(2THENGOSUB2920:GOTO2540
2510 IFA2="D"ANDDS=1THENGOSUB3000:GOTO2540
2520 IFA2="E"ANDDS=1THENGOSUB3040:GOTO2540
2530 IFA2="X"PRINT"NO SPACE LANE":GOTO2560
2540 IFC1=0PRINT"JUMP.........NO JUMP ROUTE"
2550 IFC1=1PRINT"JUMP..........";C1
2560 INPUT"GENERATE ANOTHER JUMP";A$:IFLEFT$(A$,1)()
"N"THEN2430
2570 END
2580 IFDS=)2THEN2620
2590 IFA3="A"ORA3="B"ORA3="C"ORA3="D"ANDB=)1C1=1
2600 IFA3="E"ANDB=)2C1=1
2610 RETURN
2620 IFDS=)3THEN2680
2630 IFA3="A"ANDB=)2C1=2
2640 IFA3="B"ANDB=)3C1=2
2650 IFA3="C"ANDB=)4C1=2
2660 IFA3="D"ANDB=)5C1=2
2670 RETURN
2680 IFDS=)4THEN2710
2690 IFA3="A"ORA3="B"ANDB=)4C1=3
```



IF YOU ENJOY MUSIC, WHY JUST LISTEN?

You and your Apple could be making beautiful music together!

Join the thousands of Apple owners who are making music — without the years of practice needed for conventional instruments. You can quickly and easily enter a song from sheet music. Just follow the detailed examples and instructions provided.

THE PRODUCT. ALF's economical 9-voice Music Card MC1 is just $195, the gourmet 3-voice Music Card MC16 is $245 (use 2 for 6 voices or 1 for 9). Both come with detailed manual, complete software, and cable for connection to your stereo system.

THE SOFTWARE. We're convinced our product is by far the easiest to use and most versatile system for the Apple. You get many features not available in other systems, plus a very large note capacity. And no customer has ever reported a "bug" or error.

THE HARDWARE. ALF strives for the best quality possible. No MC1 card has ever been returned with a manufacturing defect.

THE COMPANY. ALF has been making computer controlled synthesizers since 1975. We made the first music peripheral for the Apple — and it's still one of the most popular.

Available through Apple dealers, or write for more information.

WANT TO DUPLICATE DISKS QUICKLY?

ALF's disk duplication service has been a major source of quality reproduction for Apple-compatible software houses since 1980. Now you can use the same techniques for fast and accurate reproduction yourself, with ALF's Copy System. Why spend over $10,000 for a duplication system when for just $595 you can connect the ALF Copy System to your own Apple? Copying time is about 17 to 17.5 seconds, depending on number of drives used. That's over 1,600 disks in 8 hours from a single system. Are you completely confident of your present copying methods? At ALF, accurate reproduction is more important than speed. The ALF Copy System is designed to produce perfect copies every time.

Special hardware and software copies any standard 13 or 16 sector Apple format disk. Hardware plugs easily into computer — no permanent changes required. If you wish to do your own drive maintenance, the manual tells how to use standard Shugart procedures and accessories, and all necessary software is included.

Too busy to get into disk copying? You can still count on ALF's convenient copying service. Ask about our copy-resistant and "double boot" services too!

Write for complete details.

NEED CONVENIENT FLOPPY DISK PROTECTION?

ALF's Floppy Boxes are specially designed to offer great protection with more convenient use than other methods. They're designed with two layers of corrugated cardboard with a special "cross grain" construction for extra strength. The standard square size holds 3 5 minifloppies for mailing or packing in products. The larger rectangular size holds minifloppies plus a standard 5¼ x 8½ booklet (8½ x 11 folded in half). Available with an adhesive closure tab for use as a mailer (just seal with tab, address other side, and mail). Software houses: write for details on attractive, protective packaging for your products.

Small quantity price is 75¢ for standard box.

Available singly at computer dealers, in large quantities from ALF. (New dealer inquiries invited.)

Aug. 81

ALF PRODUCTS INC. 1448 ESTES DENVER, CO 80215

NOW AVAILABLE

BPILOT

Why pay for Educational Programs that don't quite work the way you want? Write your own! Tailor lessons to your class or child's specific needs. You can with **BPILOT**, the easy to use CAI language.

BPILOT gives you the power and ease of both PILOT and BASIC. You can intermix PILOT and BASIC instructions in **BPILOT** programs. In addition, you get extra long labels to mark instructions and the capability of Indirect Matching. Release 3.0 **BPILOT** now provides Turtle Graphics capabilities for drawing pictures, Link capabilities for larger than memory programs, and expanded eXecute Indirect capabilities.

BPILOT 3.0 is a Z80 assembly language program for the Model I TRS-80®, Level II (16K+) or disk (32K+). Send $39.95 + $2.00 S&H (Calif resd add 6% sales tax). Reference manual alone $7.95 (credited toward future purchase).

Apple II Plus® owners write direct for availability of 6502 version.

CAMI Computer Aided & Managed Instruction
Your Computer Friend P.O. Box 2030 Goleta, CA 93118

CIRCLE 258 ON READER SERVICE CARD

ATARI 800/400 Users and Dealers

Our software is available now for your computer including:

Sing along with your ATARI and the Music Composer Cartridge this Christmas with the help of our CHRISTMAS MUSIC files.
Words Included — 24K Disk $24.95
Specially Selected Set — 16K Tape $19.95

MATHFAKS helps reinforce basic math skills with the help of the Votrax Type-N-Talk™ and ATARI 850 interface (both optional) — 24K Disk $19.95, 16K Tape $19.95

Votrax Type-N-Talk™ for above with RS-232 cable $129

Please add 72 postage and handling for each item. Michigan residents add 4% sales tax.

Computer's Voice
2370 ELLA DR. - DEPT. CC-11
FLINT, MI. 48504
(313) 238-5585

CIRCLE 127 ON READER SERVICE CARD

Continental Adventures Presents Three Adventures And Two Games For The Atari Computer Owners

The Talisman Of Power—A Search For The Four Keys Of Gremlock-16K-$18.95.
The Ghost Tower-Combat With Diabolical Demons-16K-$16.95.
Town Of Derange—Avenging The Death Of A Father-8K-$16.95.
Super Shape Builder—A Graphics Game, Creating Your Own Pictures-8K-$14.95. Joy Sticks Required.
Splat—Bouncing Fred And His Trampoline-8K-$9.95. One Joy Stick Required.

Continental Adventures
4975 Brookdale
Bloomfield Hills, Mich. 48013
(313) 645-2140

CIRCLE 231 ON READER SERVICE CARD

```
2700 IFA3="C"ANDB=6C1=3
2710 IFD$)4THEN2730
2720 IFA3="A"DRA$="B"ANDB=\"5C'=6
2730 RETURN
2740 IFDS=)2THEN2800
2750 IFA3="B"ANDB=)1C1=1
2760 IFA3="C"ANDB=)2C1=1
2770 IFA3="D"ANDB=)3C1=1
2780 IFA3="E"ANDB=)4C1=1
2790 RETURN
2800 IFDS=)3THEN2850
2810 IFA3="B"ANDB=)3C1=2
2820 IFA3="C"ANDB=)4C1=2
2830 IFA3="D"ANDB=6C1=2
2840 RETURN
2850 IFD$=)4THEN2890
2860 IFA3="B"ANDB=)4C1=3
2870 IFA3="C"ANDB=6C1=3
2880 RETURN
2890 IFDS()4THEN2910
2900 IFA3="B"ANDB=6C1=4
2910 RETURN
2920 IFDS=)2THEN2970
2930 IFA3="C"ANDB=)3C1=1
2940 IFA3="D"ANDB=)4C1=1
2950 IFA3="E"ANDB=)4C1=1
2960 RETURN
2970 IFDS=)3THEN2990
2980 IFA3="C"ANDB=6C1=2
2990 RETURN
3000 IFDS=)2RETURN
3010 IFA3="D"ANDB=)4C1=1
3020 IFA3="E"ANDB=)5C1=1
3030 RETURN
3040 IFDS=)2RETURN
3050 IFA3="E"ANDB=6C1=1
3060 RETURN
3070 'STARPORT
3080 B=FNB
3090 IFB=(6A1="A"!GOTO3150
3100 IFB=5ORB=6A1="B"!GOTO3150
3110 IFB=7ORB=8A1="C"!GOTO3170
3120 IFB=9A1="D"!GOTO3170
3130 IFB=10ORB=11A1="E"!GOTO3220
3140 IFB=12A1="X"!GOTD3220
3150 B=FNB
3160 IFB=)BS1=1
3170 B=FNB
3180 IFA1="A"ANDB=)1BS2=1
3190 IFA1="B"ANDB=)9S2=1
3200 IFA1="C"ANDB=)8S2=1
3210 IFA1="D"ANDB=)7S2=1
3220 RETURN
3230 'DISK SAVE
3240 A$=A1+A4+A5+A6+A7+A8+A9+TF$+A0
3250 PUT 1,RN,.N$,A$,P1$,P2$,P3$,S1%,S2%:
3260 RETURN
```

```
10 'WORLD GENERATOR FDR TRAVELER(TM) - GAME DESIGNER
WORKSHOP
20 'BY CHRISTOPHER C. MARVEL  CDPYRIGHT 1980
30 '1313 BEAUFORT, LARAMIE, WYOMING 82070
40 RANDOM
50 CLEAR1000:DEFSTRA
60 C1=01:B=01:B1=01:B2=01:RN=0
```

World Reader

```
70 CLS:PRINTCHR$(23);PRINT:PRINT"* * * * * w o r l d  * * * * *"
80 PRINT"* * * * * R E A D E R * * * *"
90 PRINT:PRINT"*****************************************************
******* !PRINT:PRINT"              BY"
100 PRINT:PRINT"CHRISTDPHER C. MARVEL"
120 PRINT:PRINT"              CDPYRIGHT 1980"
130 FDRJ=1TD3000:NEXT
140 DPEN"I",1,"WORLD/DAT","MF",150   'NEWDDS80 DISK FILE
150 B=01:B1=01:B2=01:S1=01:S2=01:T=01:I=01:A0="0":P1$=""!P2$=""!P3$=""!N$=""
160 CLS:PRINTØ512,"WHAT IS THE RECDRD # DF THE WDRLD YDU WISH TO RETRIEVE"
:INPUT"";RN
170 GOSUB1660
180 CLS:PRINTØ320,"****************** W O R L D   G E N E R A T O R *****
***:**** ***"
190 CLS:PRINT"======PLANET:======================="!N$!"========="
200 PRINT"STARPDRT......................................"!A1
210 IFA1="A"PRINT"ELLIDT. DEFINED FUEL. ANNUAL MAINTENANCE. SHIPYARD
CAPABLE DFHANDLING STARSHIPS AND NO-STARSHIPS."
230 IFA1="B"PRINT"GDDD. REFINED FUEL. ANNUAL MAINTENANCE. SHIPYARD CAPABLE
OF CDNSTRUCTING NDN STARSHIPS."
230 IFA1="C"PRINT"RDUTINE. DNLY UNREFINED FUEL AVAILABLE. REASDNABLE
REPAIR  FACILITY PRESENT."
240 IFA1="D"PRINT"PDDR. DNLY UNREFINED FUEL AVAILABLE. ND REPAIR.)
250 IFA1="E"PRINT"FRDNTIER.   ND FUEL DR BASES."
260 IFA1="X"PRINT"ND STARPDRT "
270 IFS1=1PRINT"NAVAL BASE PRESENT"
280 IFS2=1PRINT"SCDUT BASE PRESENT"
290 IFA0="1"PRINT"RDSETTE WDRLDS (3)"
300 IFA0="2"PRINT"RINGWDRLDS"
310 IFA0="3"PRINT"SHPEREWDRLDS - ARTIFICIAL ATMDSPHERE";A5="0"
320 PRINT"PLANETARY SIZE (MILES DIAMETER) ......."!
330 IFA4="0"PRINT"ASTERDID/PLANETDID COMPLEX"
340 IFA4="1"PRINT"1000 "
350 IFA4="2"PRINT"2000 "
360 IFA4="3"PRINT"3000 "
370 IFA4="4"PRINT"4000 "
380 IFA4="5"PRINT"5000 "
390 IFA4="6"PRINT"6000 "
400 IFA4= 7"PRINT"7000 "
410 IFA4='8"PRINT"8000 "
420 IFA4="9'PRINT"9000 "
430 IFA4="A"PRINT"10000 "
440 IFA4="B"PRINT"11000 "
450 IFA4="C"PRINT"12000 "
460 PRINT"PLANETARY ATMDSPHERE....................";
470 IFA5="0"PRINT"NDNE"
480 IFA5="1"PRINT"TRACE"
490 IFA5="2"PRINT"VERY THIN,TDINTED"
500 IFA5="3"PRINT"VERY THIN"
510 IFA5="4"PRINT"THIN,TAINTED"
520 IFA5="5"PRINT"THIN"
530 IFA5="6"PRINT"STANDARD"
540 IFA5= 7"PRINT"STANDARD,TAINTED"
550 IFA5="8"PRINT"DENSE"
560  FA5='9"PRINT"DENSE,TDINTED"
570 IFA5="A"PRINT"EXDTIC"
580 IFA5="B"PRINT"CDRRDSIVE
590 IFA5="C"PRINT"INSIDIDUS"
600 PRINT"HYDRDGRAPHIC % ......................."!
610 IFA6="0"PRINT"ND FREE STANDING WATER"
620 IFA6="1"PRINT"10%"
630 IFA6="2"PRINT"20%"
640 IFA6="3"PRINT"30%"
650 IFA6="4"PRINT"40%"
660 IFA6="5"PRINT"50%"
670 IFA6="6"PRINT"60%"
680 IFA6="7"PRINT"70%"
690 IFA6="8"PRINT"80%"
700 IFA6="9"PRINT"90%"
710 IFA6="A"PRINT"ALL WATER, ND LAND MASSES"
720 PRINT"PDPULATIDN......................."!
730 IFA7="0"PRINT"NDNE"
740 IFA7="1"PRINT"10"
750 IFA7="2"PRINT"100"
760 IFA7="3"PRINT"1000"
770 IFA7="4"PRINT"10.000"
780 IFA7="5"PRINT"100.000"
790 IFA7="6"PRINT"1.000.000"
800 IFA7="7"PRINT"10.000.000"
810 IFA7="8"PRINT"100.000.000"
820 IFA7="9"PRINT"1.000.000.000"
830 IFA7="A"PRINT"10.000.000.000"
840 PRINT"GDVERNMENT TYPE.....................................
850 IFA8="0"PRINT"ND GDVERNMENT STRUCTURE. IN MANY CASES, FAMILY BDNDS WILL
  PREDDMINATE."
860 IFA8="1"PRINT"COMPANY/CDRPDRATIDN. RULING FUNCTIDNS ARE ASSUMED BY A
COMPANY MANAGERIAL ELITE, AND MDST CITZENRY ARE CDMPANY EMPLDYEES DR
DEPENDENTS."
870 IFA8="2"PRINT"PARTICIPATING DEMDCRACY. RULING FUNCTIDN DECISIDNS ARE
REACHED  BY ADVICE OF THE CITIZENRY DIRECTLY."
880 IFA8="3"PRINT"SELF  PERPETUATING OLIGARCHY. RULING FUNCTIDNS ARE
PERFDRMED BY ARESTRICTED MINDRITY, WITH LITTLE DR ND INPUT FRDM THE MASS
DF CITIZENRY"
890 IFA8="4"PRINT"REPRESENTATIVE DEMDCRACY. RULING FUNCTIDNS ARE
PERFDRMED BY  ELECTED REPRESENTATIVES."
```

November Software Specials

Robotwar
from Muse

In the year 2002, wars are fought with robots instead of people. This fascinating game helps you learn creative programming techniques while you plan your battle strategies. 75 page manual included.
Cat No. 3206 Apple II/II +, 48K, Applsft ROM, disk $39.95

Survival Adventure
USA Software

Here's a unique twist. Try to survive in this real world adventure simulation.
Cat. No. 3218 Atari 800, 32K, cassette $24.95
Cat. No. 3219 Atari 800, 40K, disk $24.95

Meteor Mission II
Big Five Software

Six stranded astronauts are crying out for your help on the planet below. Can you maneuver your rescue shuttle thru the asteroids and save them?
Cat. No. 3214 TRS-80, Modl & III, 16K, cass. $15.95
Cat. No. 3215 TRS-80, Modl & III, 16K, disk $19.95

How To Order

Write or phone. Mention this ad and WE PAY UPS GROUND shipping & handling (USA only). Pay by check, M/C, Visa or COD (add $1.40 for COD). Offer expires Dec. 1, 1981.

Send for our FREE catalogue.

HW ELECTRONICS

(Formerly Hobbyworld Electronics)
19511 Business Center Dr., Dept. C11
Northridge, CA 91324
(800) 423-5387 (Outside Calif.)
(213) 886-9200 (In Calif.)

Apple, Atari and TRS-80 are registered trademarks.

DISK DRIVE WOES?
PRINTER INTERACTION?
MEMORY LOSS?
ERRATIC OPERATION?

Don't Blame The Software!

Power Line Spikes, Surges & Hash could be the culprit! Pat. #4,259,705
Floppies, printers, memory & processor often interact! Our patented ISOLATORS eliminate equipment interaction AND curb damaging Power Line Spikes, Surges and Hash.

- ISOLATOR (ISO-1) 3 filter isolated 3-prong sockets; integral Surge/Spike Suppression; 1675 W Maximum load, 1 KW load any socket $62.95
- ISOLATOR (ISO-2) 2 filter isolated 3-prong socket banks; (6 sockets total); integral Spike/Surge Suppressior; 1675 W Max load, 1 KW either bank $62.95
- SUPER ISOLATOR (ISO-3), similar to ISO-1 except double filtering & Suppression $94.95
- ISOLATOR (ISO-4), similar to ISO-1 except unit has 6 individually filtered sockets $106.95
- SUPER ISOLATOR (ISO-11) similar to ISO-2 except double filtering & Suppression $94.95
- CIRCUIT BREAKER, any model (add-CB) ..... Add $ 6.00
- CKT BRKR/SWITCH/PILOT (-CBS) ..... Add $16.00

AT YOUR DEALERS

Master-Card, Visa, American Express
Order Toll Free 1-800-225-4876
(except AK, HI, PR & Canada)

Electronic Specialists, Inc.
171 South Main Street, Natick, Mass. 01760
Technical & Non-800: 1-617-655-1532

CIRCLE 142 ON READER SERVICE CARD

ASSESS YOUR ASSETS.

Get a better insight into your expenditure decisions with an Apple personal computer.

Evaluate your financial position with Tax Planner. Chart your progress with Apple Plot. And take stock of your portfolio with The Dow Jones News & Quotes Reporter.

To discover how an Apple can be your greatest asset, drop by our store today.

apple computer
Authorized Dealer

Featuring Now . . . . .
- Apple II Plus w/48K
- Disk Drive w/3.3
System Price $1795
(List Price *2175)

SALES SERVICE INSTRUCTION
—LARGE SHOWROOM—

FARNSWORTH COMPUTER CENTER
1891 N. Farnsworth Ave. (at the E-W Tollway)
Aurora, Il. 60505 Ph. (312) 851-3888
Weekdays 10-8, Sat. 10-5

CIRCLE 179 ON READER SERVICE CARD

```
900 IFA8="5"PRINT"FEUDAL TECHNOCRACY. RULING FUNCTIONS ARE PERFORMED BY
SPECIFIC INDIVIDUALS FOR PERSONS WHO AGREE TO BE RULED BY THEM.
RELATIONSHIPS ARE BASED ON THE PERFORMANCE OF TECHNICAL ACTIVITIES WHICH
ARE MUTUALLY BENEFICIAL."
910 IFA8="6"PRINT"CAPTIVE GOVERNMENT. RULING FUNCTIONS ARE PERFORMED BY
AN IMPOSED LEADERSHIP FROM OUTSIDE GROUP. A COLONY OR CONQUERED AREA."
920 IFA8="7"PRINT"BALKANIZATION.NO CENTRAL RULING AUTHORITY EXISTS! RIVAL
 GOVERNMENTS COMPETE FOR CONTROL. LAW LEVEL REFERS TO THE GOVERNMENT NEA
REST THE STARPORT."
930 IFA8="8"PRINT"CIVIL SERVICE  BUREAUCRACY. RULING FUNCTIONS ARE
PERFORMED BY GOVERNMENT AGENCIES EMPLOYING INDIVIDUALS WITH A SELECTED
EXPERTISE."
940 IFA8="9"PRINT"IMPERSONAL BUREAUCRACY. RULING FUNCTIONS ARE PERFORMED
BY AGENCIES WHICH HAVE BECOME INSULATED FROM THE GOVERNED CITIZENRY
950 IFA8="A"PRINT"CHARISMATIC DICTATORSHIP. RULING FUNCTIONS ARE
PERFORMED BY AGENCIES DIRECTED BY A SINGLE LEADER WHO ENJOYS THE
OVERWHELMINGCONFIDENCE OF THE CITIZENRY."
960 IFA8="B"PRINT"NON-CHARISMATIC LEADER. APREVIOUS CHARISMATIC DICTATOR
HAS BEEN REPLACED BY A LEADER THROUGH NORMAL CHANNELS."
970 IFA8="C"PRINT"CHARISMATIC OLIGARCHY. RULING FUNCTIONS ARE PERFORMED
BY A SELECT GROUP OF MEMBERS OF AN ORGANIZATION OR CLASS WHICH ENJOYSTHE
OVERWHELMING CONFIDENCE OF THE CITIZENRY."
980 IFA8="D"PRINT"RELIGIOUS DICTATORSHIP. RULING FUNCTIONS ARE PERFORMED
BY A RELIGIOUS ORGANIZATION WITHOUT REGARD TO THE SPECIFIC NEEDS OF  THE
CITIZENRY."
990 B=VAL(A9):INPUT"ENTER TO CONTINUE";XX:CLS:PRINT"LAW LEVEL.........
........................"
1000 IFB=0PRINT"NO LAWS AFFECTING WEAPON POSSESSION OR WEAPON OWNERSHIP."
1010 IFB=1PRINT"CERTAIN WEAPONS ARE PROHIBITED,INCLUDING SPECIFICALLY
1)BODY PISTOLS WHICH ARE UNDETECTABLE BY STANDARD DETECTORS 2)EXPLOSIVE
WEAPONS SUCH AS  BOMBS OR GRENADES. AND 3) POISON GAS."
1020 IFB=2PRINT"PORTABLE ENERGY WEAPONS. SUCH AS LASER RIFLES OR
CARBINES ARE PROHIBITED. SHIP'S GUNNERY IS NOT AFFECTED"
1030 IFB=3PRINT"WEAPONS OF A STRICT MILITARY NATURE (SUCH AS MACHINE
GUNS OR  AUTOMATIC RIFLES. THOUGH NOT SUBMACHINEGUNS) ARE PROHIBITED."
1040 INPUT"PRESS ENTER TO CONTINUE";XX
1050 IFB=4PRINT"LIGHT ASSAULT WEAPONS (SUCH AS SUBMACHINE GUNS) ARE
PROHIBITED."
1060 IFB=5PRINT"PERSONAL CONCEALABLE FIREARMS (SUCH AS PISTOLS AND
REVOLVERS) ARE PROHIBITED."
1070 IFB=6PRINT"MOST FIREARMS  ARE PROHIBITED. THE CARRYINGOF ANY TYPE
OF WEAPON IS DISCOURAGED."
1080 IFB=7PRINT"SHOTGUNS ARE PROHIBITED."
1090 IFB=8PRINT"LONG BLADED WEAPONS (ALL BLADE WEAPONS EXCEPT DAGGERS)
ARE STRICTLY CONTROLLED. OPEN POSSESSION IN PUBLIC IS PROHIBITED.
OWNERSHIP IS,HOWEVER. NOT RESTRICTED."
1100 IFB=9PRINT"POSSESION OF ANY WEAPON OUTSIDE ONE'S HOME IS
PROHIBITED."
1110 INPUT"ENTER TO CONTINUE";XX
1120 CLS:PRINT"TECNOLOGICAL INDEX.......................................
......."
1130 PRINT"========= WEAPONS =========="
1140 PRINTTAB(0)"PERSONAL";TAB(20);"ARMOR";TAB(30);"SPECIAL";TAB(40)!
"COMPUTERS"  ;TAB(50)!"COMMUNICATION"
1150 IFT=0PRINTTAB(0)"CLUB. CUDGEL. SPEAR";TAB(50)"RUNNERS"
1160 IFT=1PRINTTAB(0)"DAGGER.PIKE.SWORD";TAB(20)!"JACK";TAB(30);"CATAPULT
";TAB(4 0)!"ABACUS";TAB(50);"HELIOGRAPH"
1170 IFT=2PRINTTAB(0)"HALBRED. BROADSWORD";TAB(30);"CANNON"
1180 IFT=3PRINTTAB(0)"FOIL.CUTLASS.BLADE"
1190 IFT=3PRINT"BAYONET"
1200 IFT=4PRINTTAB(0)"REVOLVER.SHOTGUN";TAB(20);"CLOTH";TAB(30);"ARTIL
LERY";TAB( 40)!"ADDING";TAB(50);"TELEPHONES"
1210 IFT=4PRINTTAB(40)"MACHINES"
1220 IFT=5PRINTTAB(0)"CARBINE.RIFLE.SMG";TAB(30);"SANDCASTER";TAB(40)!
"MODEL/1"! TAB(50)!"RADIO"
1230 IFT=5PRINTTAB(0)"PISTOL";TAB(30);"MORTARS"
1240 IFT=6PRINTTAB(0)"AUTO RIFLE";TAB(30);"MISSILES";TAB(40);"MODEL/1BIS"
;TAB(50 );"TELEVISION"
1250 IFT=7PRINTTAB(0)"BODY PISTOL";TAB(20);"MESH";TAB(30);"PULSE LASER";
TAB(40)! " MODEL/2"
1260 IFT=8PRINTTAB(0)"LASER CARBINE";TAB(20);"AUTO-CANNON";TAB(40);"MODEL
/2BIS"
1270 IFT=9PRINTTAB(0)"LASER RIFLE";TAB(20);"ABLAT";TAB(30);"BM LASER";TAB
(40);"MODEL/3"
1280 IFT=10PRINTTAB(20)"REFLEC";TAB(40);"MODEL/4"
1290 IFT=12PRINTTAB(40)"MODEL/5"
1300 IFT=13PRINTTAB(40)"MODEL/6"
1310 IFT=14PRINTTAB(0)"BATTLE DRESS";TAB(40);"MODEL/7"
1320 IFT=17PRINTTAB(40)"ARTIFICIAL"
1330 IFT=17PRINTTAB(40)"INTELLIGIENCE"
1340 PRINT"==============TRANSPORTATION================"
1350 PRINTTAB(0)"WATER";TAB(20);"LAND";TAB(30);"AIR";TAB(40);"SPACE";TAB
(50);"FUELS"
1360 IFT=0PRINTTAB(0)"CANOES";TAB(20);"CARTS";TAB(50);"MUSCLE"
1370 IFT=1PRINTTAB(0)"GALLEY";TAB(20);"WAGON"
1380 IFT=2PRINTTAB(50)"WIND"
1390 IFT=3PRINTTAB(0)"SAILING SHIPS";TAB(30);"HOT AIR BALLOON";TAB(50);
"WATER WHEEL"
1400 IFT=4PRINTTAB(0)"STEAMSHIPS";TAB(20);"TRAINS";TAB(30);"DIRIGIBLES";
TAB(50); "COAL"
1410 IFT=5PRINTTAB(20)"GROUND ";TAB(30);"FIXED ";TAB(50);"OIL"
1420 IFT=5PRINTTAB(20)"CAR";TAB(30);"WING"
1430 IFT=6PRINTTAB(0)"SUBMERSIBLES";TAB(20);"ATV,AFV";TAB(30);"ROTARY WING"
;TAB( 50);"FISSION"
1440 IFT=5DRTPRINTTAB(30)"AIRCRAFT"
1450 IFT=7PRINTTAB(0)"HOVERCRAFT";TAB(20);"HOVERCRAFT";TAB(40);"NON-STAR
SHIP";TAB(53);"SOLAR"
1460 IFT=8PRINT"TAB;30;"OIB/AFF";TAB(50);"FUSION"
1470 IFT=9ANDT<(15PRINTTAB(40)"STARSHIPS"
1480 IFT=10PRINTTAB(40)"DRIVE H"
1490 IFT=11PRINTTAB(40)"DRIVE K"
1500 IFT=12PRINTTAB(30)"GRAV BELTS";TAB(40);"DRIVE N"
1510 IFT=13PRINTTAB(40)"DRIVE O"
1520 IFT=14PRINTTAB(40)"DRIVE U"
1530 IFT>10ANDT<(14PRINTTAB(40)"OR LESS"
1540 IFT=15PRINTTAB(40)"ALL DRIVES"
1550 IFT=16PRINT"========= MATTER TRANSPORT =========="
1560 IFT=17PRINTTAB(50)"ANTI MATTER"
1570 PRINT:INPUT"ENTER TO CONTINUE";XX
1580 CLS:PRINT"PLANET==================================:N$:PRINT
1590 PRINT"UNIVERSAL PLANET PROFILE....................."IA$
1600 PRINT"TECH INDEX";T
1610 PRINT"SPECIAL ADDITIONS"
1620 PRINTP1$:PRINTP2$:PRINTP3$
1630 INPUT"DO YOU WISH TO CONTINUE";A2$
1640 IF LEFT$(A2$,1)()"N"THEN150
1650 CLOSE:END
1660 'DISK SAVE
1670 GET 1,N$,A$,P1$,P2$,P3$,S1$,S2$:
1680 A1=LEFT$(A$,1):A4=MID$(A$,2,1):A5=MID$(A$,3,1):A6=MID$(A$,4,1):A7=MID
$(A$,5 ,1):A8=MID$(A$,6,1)
1690 A9=MID$(A$,7,1):TF$=MID$(A$,8,1):A0=RIGHT$(A$,1)
1700 A$=LEFT$(A$,8)
1710 IFTF$="0"T=0                    1810 IFTF$="A"T=10
1720 IFTF$="1"T=1                    1820 IFTF$="B"T=11
1730 IFTF$="2"T=2                    1830 IFTF$="C"T=12
1740 IFTF$="3"T=3                    1840 IFTF$="D"T=13
1750 IFTF$="4"T=4                    1850 IFTF$="E"T=14
1760 IFTF$="5"T=5                    1860 IFTF$="F"T=15
1770 IFTF$="6"T=6                    1870 IFTF$="G"T=16
1780 IFTF$="7"T=7                    1880 IFTF$="H"T=17
1790 IFTF$="8"T=8                    1890 IFTF$="X"T=18
1800 IFTF$="9"T=9                    1900 RETURN
```

OMNISCAN™

The interface that provides the most revolutionary means of information retrieval since the printing press by combining these important technologies:

1) *the Apple II computer,*
2) *the Pioneer VP-1000 Laser Video Disc,*
3) *and the Color Television.*

The **OMNISCAN** *interface is used to control the Pioneer LaserDisc player in an interactive way, with software running on the Apple II computer. The system can display information with color, motion, and stereo or bilingual sound under program control. It can teach, review, test, and grade material while allowing for individual learning rates. The branching capability of the computer gives unlimited flexibility in programing a learning sequence.*

Documentation on the hardware and a tutorial on the software is provided.

Price: $ 250 *Dealer inquiries invited*

aurora systems, inc.
2040 E. Washington Ave.
Madison, WI 53704
608 - 249 - 5875

OMNISCAN is a trademark of Aurora Systems, Inc
Apple II is a trademark of Apple Computers, Inc. VP-1000 is a trademark of Pioneer USA, Inc

CIRCLE 124 ON READER SERVICE CARD

YOU'RE OUR PATIENT...

MEDICAL & DENTAL SYSTEMS

- Appointments
- Master Records
- Private Billing
- ADA or AMA Claim Preparation
- Diagnostic and Treatment Records
- Recall and more

• Apple II • TRS-80 • Apple ///

CHARLES MANN & ASSOCIATES
Micro Software Division
55722 Santa Fe Trail
Yucca Valley, CA. 92284
(714) 365-9718

CIRCLE 133 ON READER SERVICE CARD

NEW FROM jem

for science experiments in the school laboratory

TEMPERATURE PROBE KIT

DESCRIPTION

The kit, at a cost of $125, consists of a temperature sensitive transducer, mounted in a glass tube, and an analog/digital interface card which plugs into slot #7 in the Apple.

If desired, the tiny transducer may be ordered without the glass tube, and can thus be used as an implant for various animal physiology experiments. Another probe will be available in the near future which will plug into the existing circuit board, allowing the user to plot voltage.

FEATURES

Digitized temperature readings, at user selected intervals so that readings can automatically be plotted using a high resolution graphics display. These graphs can be stored on diskette and printed on a high resolution printer at a later date.

Enables a student to see at leisure those temperature plateaus which are easily missed when manually recording and plotting thermometer readings.

SUGGESTED ACTIVITIES

- plot melting and freezing temperature plateaus for paradichlorobenzene!
- examine temperature regulating mechanisms of axotherms and endotherms!
- plot heat of solution and heat of neutralization graphs!
- determine boiling point of water at various atmospheric pressures!
- analyze temperature gradients in snow drifts!



Management Director

Discovery Park, P.O. Box 1700, Victoria, B.C. V8W 2Y2, Canada. Phone: (604) 477-7246

IT'S AS EASY AS.....ONE.....TWO.....THREE

Manager

Discovery Park,
P.O. Box 1700,
University of Victoria,
Victoria, B.C.
Canada, V8W 2Y2.
Phone: (604)-477-7246

THE ADMINISTRATORS' APPLE PACKAGE

The ADMINISTRATORS' APPLE PACKAGE contains the following:

1) The ATTENDANCE PROGRAM which keeps up to date student records on up to 1,200 students with printouts of absentee lists, bi-monthly attendance totals, personalized letters to parents and reports to students,

2) The DEMOGRAPHIC PROGRAM which can accomodate up to 1,200 student records and produce printouts of division lists, roster lists, grade lists, locker lists, and lists of files and label (both students' labels and address labels), and

3) The TEXTBOOK PROGRAM which stores up to 990 textbook records and produces two printouts

a) a list of texts alphabetically sorted by department, and

b) a form to be used in a debit-credit system of keeping track of texts.

The package requires a 48K, DOS 3.3 Apple II Plus with an 80 card reader, a printer (please specify), and a dual disk system if enrollment exceeds 500 students.

This package has been carefully field tested and is being used extensively in schools throughout the province of British Columbia.

Price $500.00 Documentation (alone) $25.00

CIRCLE 198 ON READER SERVICE CARD

Character Generator

```
10 'CHARACTER GENERATOR FOR TRAVELLER(TM) - GAME DESIGNER WORKSHOP
20 'BY CHRISTOPHER C. MARVEL COPYRIGHT 1980
30 '1313 BEAUFORT, LARAMIE, WYOMING 82070
40 DEFINT A-X
50 RANDOM
60 CLS:PRINTCHR$(23):PRINT:PRINT"+ + + C H A R A C T E R + + +"
70 PRINT"+ + + O E N E R A T O R + + +"
80 PRINT:PRINT"*****************************************************
******* ":PRINT:PRINT"                                    BY"
90 PRINT:PRINT"CHRISTOPHER C. MARVEL"
100 PRINT:PRINT"                    COPYRIGHT 1980"
110 FORJ=1TO3000:NEXT
120 'MAIN PROGRAM GENERTATION
130 DEF FNAX=RND(6)+RND(6)
140 S1=0:S2=0:S3=0:S4=0:S5=0:S6=0:S7=0:S8=0:S9=0:S0=0:W1=0:W2=0:W3=0:W4=0
:W5=0:W 6=0:K1=0:K2=0:K3=0:K4=0:K5=0:K6=0:K7=0:K8=0:K9=0:K0=0:L1=0:L2=0:
L3=0:L4=0:L5=0:L 6=0:L7=0:L8=0:L9=0:L0=0
150 BS=0:F=0:N$=""1P=0:C=0:E=0:B1=0:C1=0:C2'=0:C3'=0:C=0:B=0:D0=0:B2=0:
B3=0:B4=0
160 CLS:PRINTCHR$(23):INPUT" NAME YOUR CHARACTER":N$
170 B=FNA:A1=B 'GET BASIC ATTRIBUTES
180 B=FNA:A2=B
190 B=FNA:A3=B
200 B=FNA:A4=B
210 B=FNA:A5=B
220 B=FNA:A6=B
230 GOSUB3140
240 PRINT:INPUT"DO YOU WISH TO ENLIST"!A$ 'ENLIST OR GET DRAFTED''''
250 IFLEFT$(A$,1)()"N"THEN270
260 CLS:PRINT@512,"YOU HAVE BEEN DRAFTED":FORJ=1TO500:NEXT:B1=0:GOTO300
270 CLS:PRINT"*************** NAVY ****************":PRINT:PRINT"1
- NAVY", "3 - ARMY","5 - MERCHANTS":PRINT"2 - MARINES","4 - SCOUTS","6 -
OTHER"
280 B1=1
290 INPUT"WHAT BRANCH OF SERVICE DO YOU WISH TO APPLY TO"!BS:ONBSGOTO320,
750,115 0,1540,1830,2240
300 B1=0:FORJ=1TO30:CLS:FORI=1TO3:PRINT@530,".....DRAFTED.....":NEXTI:
NEXTJ:BS=R ND(6) 'DRAFT RANDOM GENERATION
310 IFBS=1THEN360ELSEIFBS=2THEN760ELSEIFBS=3THEN1180ELSEIFBS=4THEN1570.
ELSEIFBS=5 THEN1860ELSEIFBS=6THEN2240
320 B=FNA 'NAVY CHARACTER
330 IFA5=)9B=B+2
340 IFA4=)8B=B+1
350 IFB(@PRINT"YOU ARE REJECTED":FORJ=1TO1000:NEXT:GOTO300
360 CLS:PRINT,"*****************  NAVY  ****************":PRINT
370 PRINT"YOU HAVE BEEN ACCEPTED.....":B=FNA:IFA4=)7B=B+2
380 E=E+1
390 IFB)4THEN430
400 PRINT"YOU HAVE BEEN KILLED IN STAR BATTLE"
410 INPUT"DO YOU WISH A NEW CHARACTER"!A$:IFLEFT$(A$,1)()"N"THEN120
420 END
430 PRINT"YOU SURVIVE TOUR #"!E".....",
440 IFB1=0THEN520
450 IFC=)1THEN490
460 B=FNA:IFA6=)9B=B+1
470 IFB(10PRINT"YOU ARE NOT ACCEPTED FOR COMMISSINDINO":GOTO520
480 C1=1:PRINT"YOU'VE BEEN COMMISSIONED ENSIGN":C=1:GOTO520
490 B=FNA:IFA5=)8B=B+1
500 IFB(8PRINT"YOU'VE BEEN DENIED PROMOTION":GOTO520
510 PRINT"YOU'VE BEEN PROMOTED":P=)1C=C+1
520 B1=1:I=1
530 IFC=)1=2
540 IFP=1I=I+1
550 IFC=1I=I+1
560 IFC=5A6=A6+1
570 IFC=6A6=A6+1
580 PRINT"YOU HAVE ACQUIRED "!I!" SKILLS":PRINT"1 - PERSONAL DELEVOPMENT"
,"2 - SERVICE SKILLS":PRINT"3 - ADVANCED EDUCATION
590 FORJ=1TOI:B=RND(5)+1:GOSUB640:NEXT
600 GOSUB3140
610 INPUT"DO YOU WISH TO REENLIST"!A$:IFLEFT$(A$,1)="N"THEN630
620 B=FNA:IFB=)6THEN360
630 GOTO2500
640 INPUT"WHICH SKILL DO YOU WISH TO DEVELOP":XX:ONXXGOTO650,680,700
650 IFB=1A1=A1+1ELSEIFB=2A2=A2+1ELSEIFB=3A3=A3+1ELSEIFB=4A6=A6+1ELSEIFB=
5A4=A4+1 ELSEIFB=6A5=A5+1
660 IFB(4PRINT"+STRENGTH+"ELSEIFB=2PRINT"+DEXTERITY"ELSEIFB=3PRINT"+ENDUR
ANCE"ELSEIFB=4PRINT"+SOCIAL"ELSEIFB=5PRINT"+INTELLIGENCE"ELSEIFB=6PRINT"
+EDUCATION"
670 RETURN
680 IFB=1S1=S1+1ELSEIFB=2S2=S2+1ELSEIFB=3S3=S3+1ELSEIFB=4S4=S4+1ELSEIFB=5
S5=S5+1 ELSEIFB=6S6=S6+1
690 RETURN
700 IFA5=)8THEN730
710 IFB=1S2=S2+1ELSEIFB=2S0=S0+1ELSEIFB=3K1=K1+1ELSEIFB=4K9=K9+1ELSEIFB=
5S6=S6+1 ELSEIFB=6K2=K2+1
720 RETURN
730 IFB=1K8=K8+1ELSEIFB=2S9=S9+1ELSEIFB=3K9=K9+1ELSEIFB=4L2=L2+1ELSEIFB=
5K0=K0+1 ELSEIFB=6L1=L1+1
740 RETURN
750 B=FNA:IFA4=)8B=B+1 'MARINES CHARACTER
760 IFA1=)8B=B+2
770 IFB(8PRINT"YOU HAVE BEEN REJECTED":FORI=1TO300:NEXT:GOTO300
780 CLS:PRINT,"*****************  MARINES  *****************":PRINT
790 PRINT"YOU HAVE BEEN ACCEPTED.....":B=FNA:IFA3=)8B=B+2
800 E=E+1:W4=1
810 IFB)5THEN850
820 PRINT"YOU HAVE BEEN KILLED IN STAR BATTLE"
830 INPUT"DO YOU WISH A NEW CHARACTER"!A$:IFLEFT$(A$,1)()"N"THEN120
840 END
850 PRINT"YOU SURVIVE TOUR #"!E".....",
860 IFB1=0THEN940
870 IFC=)1THEN910
880 B=FNA:IFA5=)7B=B+1
890 IFB(9PRINT"YOU ARE NOT ACCEPTED FOR COMMISSINDING":GOTO940
900 C1=1:PRINT"YOU'VE BEEN COMMISSIONED LIEUTENANT":C=1:W3=1:GOTO940
910 B=FNA:IFA6=)8B=B+1
920 IFB(9PRINT"YOU'VE BEEN DENIED PROMOTION":GOTO940
930 PRINT"YOU'VE BEEN PROMOTED":P=1:C=C+1
940 B1=1:I=1
950 IFE=1I=2
960 IFP=1I=I+1
970 IFC=1I=I+1
980 PRINT"YOU HAVE ACQUIRED "!I!" SKILLS":PRINT"1 - PERSONAL DELEVOPMENT",
"2 - SERVICE SKILLS":PRINT"3 - ADVANCED EDUCATION
990 FORJ=1TOI:B=RND(5)+1:GOSUB1040:NEXT
1000 GOSUB3140
1010 INPUT"DO YOU WISH TO REENLIST"!A$:IFLEFT$(A$,1)="N"THEN1030
1020 B=FNA:IFB=)6THEN730
1030 GOTO2500
1040 INPUT"WHICH SKILL DO YOU WISH TO DEVELOP":XX:ONXXGOTO1050,1080,1100
1050 IFB=1A1=A1+1ELSEIFB=2A2=A2+1ELSEIFB=3A3=A3+1ELSEIFB=4K5=K5+1ELSEIFB=5
K6=K6+ 1ELSEIFB=6S4=S4+1
1060 IFB=1PRINT"+STRENGTH"ELSEIFB=2PRINT"+DEXTERITY"ELSEIFB=3PRINT"+ENDURANCE"
1070 RETURN
1080 IFB=1S7=S7+1ELSEIFB=2S2=S2+1ELSEIFB=3S4=S4+1ELSEIFB=4S4=S4+1ELSEIFB=5
S5=S5+ 1ELSEIFB=6S5=S5+1
1090 RETURN
1100 IFA5=)8THEN1130
1110 IFB=1S7=S7+1ELSEIFB=2S0=S0+1ELSEIFB=3K1=K1+1ELSEIFB=4L3=L3+1ELSEIFB=
5S4=S4+ 1ELSEIFB=6S5=S5+1
1120 RETURN
```

DON'T WRECK YOUR SYSTEM



FOR THE FIRST TIME A BOOK THAT TELLS ALL THE DO'S AND DON'TS FOR COMPUTER USERS... SIMPLE, EASY-TO-READ, FULLY ILLUSTRATED

DID YOU KNOW THAT...

- Most computers require *two* ground lines—a neutral one and a safety ground?
- A telephone ringing on your disk drive may wipe out your diskettes?
- Disks and diskettes must equalize temperature prior to use?
- Most computer breakdowns are due to faulty diskette handling?
- A radio transmitter will disrupt computer operation?

That computer you're using represents a lot of money, a lot of time—both that spent in purchasing just the right one and the time it will save doing the tasks it was made for—and a big investment in your future.

DON'T (Or How to Care For Your Computer), by Rodnay Zaks, is the first book exclusively dedicated to the care, preservation and correct operation of a small computer system: the computer itself, the CRT terminal, the printer, the magnetic disks and tapes—even the computer room.

PLEASE SEND ME ☐ DON'T, (Or How to Care For Your Computer) by Rodnay Zaks 200 pp., 100 Illustr., 6" × 9" Ref. C400, 11.95

MAIL TO: SYBEX DEPT. CC11
2344 SIXTH STREET
BERKELEY, CA 94710
PHONE ORDERS: INSIDE CA 415/848-8233 OUTSIDE CA TOLL FREE 800-227-2346

SYBEX

NAME _____ ☐ SEND ME YOUR FREE CATALOG
ADDRESS _____
CITY _____ STATE _____ ZIP _____
ADD ☐ $1.50/book UPS or ☐ 75¢/book 4th class mail or ☐ $8/book overseas airmail (CA add tax)
Total Amt. Enclosed _____ OR CHARGE MY ☐ VISA ☐ MC ☐ AM EX. CARD NO. _____
EXP. DATE _____ SIGNATURE _____

```
1130 IFB=1KB=KB+1ELSEIFB=2L3=L3+1ELSEIFB=3L3=L3+1ELSEIFB=4L2=L2+1ELSEIFB=
5L4=L4+ 1ELSEIFB=6L1=L1+1
1140 RETURN
1150 B=FNA!IFA2=)6B=B+1 'ARMY CHARACTER
1160 IFA3=)5B=B+2
1170 IFB(5PRINT"YOU HAVE BEEN REJECTED":FORI=1TO300:NEXT:GOTO700
1180 CLS:PRINT."******************* ARMY ******************":PRINT
1190 PRINT"YOU HAVE BEEN ACCEPTED......"!W5=1:B=FNA!IFA5=)6B=B+2:E=E+1
1200 IFB)4THEN1240
1210 PRINT"YOU HAVE BEEN KILLED IN STAR BATTLE"
1220 INPUT"DO YOU WISH A NEW CHARACTER":A$:IFLEFT$(A$,1)()"N"THEN120
1230 END
1240 PRINT"YOU SURVIVE TOUR #":E".....
1250 IFB1=0THEN1330
1260 IFC=)1THEN1300
1270 B=FNA!IFA3=)7B=B+1
1280 IFB(5PRINT"YOU ARE NOT ACCEPTED FOR COMMISSIONING":GOTO1330
1290 C1=1:PRINT"YOU'VE BEEN COMMISSIONED LIEUTENANT":W6=1:C=1:GOTO1330
1300 B=FNA!IFA5=)7B=B+1
1310 IFB(9PRINT"YOU'VE BEEN DENIED PROMOTION":GOTO1330
1320 PRINT"YOU'VE BEEN PROMOTED":P=1:C=C+1
1330 B1=1:I=1
1340 IFE=11=2
1350 IFP=1I=I+1
1360 IFC1=1I=I+I
1370 PRINT"YOU HAVE ACQUIRED "!I!" SKILLS":PRINT"1 - PERSONAL DELEVOPMENT"
,"2 - SERVICE SKILLS":PRINT"3 - ADVANCED EDUCATION
1380 FORJ=1TO!:B=RND(5)+1:GOSUB1430:NEXT
1390 GOSUB3140
1400 INPUT"DO YOU WISH TO REENLIST":A$:IFLEFT$(A$,1)="N"THEN1420
1410 B=FNA!IFB=)7THEN1180
1420 GOTO2500
1430 INPUT"WHICH SKILL DO YOU WISH TO DEVELOP":XX:ONXXGOTO1440,1470,1490
1440 IFB=1A1=A1+1ELSEIFB=2A2=A2+1ELSEIFB=3A3=A3+1ELSEIFB=4K5=K5+1ELSEIFB=
5K6=K6+ 1ELSEIFB=6A5=A5+1
1450 IFB=1PRINT"+STRENGTH"ELSEIFB=2PRINT"+DEXTERITY"ELSEIFB=3PRINT"+ENDURA
NCE"ELSEIFB=6PRINT"+EDUCATION"
1460 RETURN
1470 IFB=1S7=S7+1ELSEIFB=2S8=S8+1ELSEIFB=3S3=S3+1ELSEIFB=4S4=S4+1ELSEIFB
=5S5=S5+ 1ELSEIFB=6S5=S5+1
1480 RETURN
1490 IFA5=)8THEN1520
1500 IFB=1S7=S7+1ELSEIFB=2S0=S0+1ELSEIFB=3K1=K1+1ELSEIFB=4L3=L3+1ELSEIFB=5
S4=S4+ 1ELSEIFB=6S5=S5+1
1510 RETURN
1520 IFB=1KB=KB+1ELSEIFB=2L3=L3+1ELSEIFB=3L3=L3+1ELSEIFB=4L2=L2+1ELSEIFB=
5L4=L4+ 1ELSEIFB=6L1=L1+1
1530 RETURN
1540 B=FNA!IFA4=)6B=B+1 'SCOUTS CHARACTER
1550 IFA1=)8B=B+2
1560 IFB(7PRINT"YOU HAVE BEEN REJECTED":FORI=1TO300:NEXT:GOTO300
1570 CLS:PRINT."******************* SCOUTS ******************":PRINT
1580 PRINT"YOU HAVE BEEN ACCEPTED......"!K0=1!B=FNA!IFA3=)9B=B+2
1590 E=E+1
1600 IFB)6THEN1640
1610 PRINT"YOU HAVE BEEN KILLED IN STAR BATTLE"
1620 INPUT"DO YOU WISH A NEW CHARACTER":A$:IFLEFT$(A$,1)()"N"THEN120
1630 END
1640 PRINT"YOU SURVIVE TOUR #":E".....
1650 I=1:IFE=1I=2
1660 PRINT"YOU HAVE ACQUIRED "!I!" SKILLS":PRINT"1 - PERSONAL DELEVOPMEN
T","2 - SERVICE SKILLS":PRINT"3 - ADVANCED EDUCATION
1670 FORJ=1TO!:B=RND(5)+1:GOSUB1720:NEXT
1680 GOSUB3140
1690 INPUT"DO YOU WISH TO REENLIST":A$:IFLEFT$(A$,1)="N"THEN1710
1700 B=FNA!IFB=)3THEN1570
1710 GOTO2500
1720 INPUT"WHICH SKILL DO YOU WISH TO DEVELOP"!XX:ONXXGOTO1730,1760,1780
1730 IFB=1A1=A1+1ELSEIFB=2A2=A2+1ELSEIFB=3A3=A3+1ELSEIFB=4S5=S5+1ELIFB=5A
4=A4+1ELSEIFB=6A5=A5+1
1740 IFB=1PRINT"+STRENGTH"ELSEIFB=2PRINT"+DEXTERITY"ELSEIFB=3PRINT"+ENDU
RANCE"ELSEIFB=5PRINT"+INTELLIGENCE"ELSEIFB=6PRINT"+EDUCATION"
1750 RETURN
1760 IFB=1S8=S8+1ELSEIFB=2S2=S2+1ELSEIFB=3S9=S9+1ELSEIFB=4S0=S0+1ELSEIFB
=5K1=K1+ 1ELSEIFB=6K2=K2+1
1770 RETURN
1780 IFA5=)8THEN1810
1790 IFB=1S8=S8+1ELSEIFB=2S0=S0+1ELSEIFB=3K1=K1+1ELSEIFB=4K2=K2+1ELSEIFB
=5S6=S6+ 1ELSEIFB=6K8=K8+1
1800 RETURN
1810 IFB=1K8=K8+1ELSEIFB=2S9=S9+1ELSEIFB=3K9=K9+1ELSEIFB=4L2=L2+1ELSEIFB
=5K0=K0+ 1ELSEIFB=6K2=K2+1
1820 RETURN
1830 B=FNA!IFA1=)7B=B+1 'MERCHANTS CHARACTER
1840 IFA4=)6B=B+2
1850 IFB(7PRINT"YOU HAVE BEEN REJECTED":FORI=1TO300:NEXT:GOTO300
1860 CLS:PRINT."******************* MERCHANTS ******************":PRINT
1870 PRINT"YOU HAVE BEEN ACCEPTED......"!B=FNA!IFA4=)7B=B+2
1880 E=E+1
1890 IFB)4THEN1930
1900 PRINT"YOU HAVE BEEN KILLED IN STAR BATTLE"
1910 INPUT"DO YOU WISH A NEW CHARACTER":A$:IFLEFT$(A$,1)()"N"THEN120
1920 END
1930 PRINT"YOU SURVIVE TOUR #":E".....
1940 IFB1=0THEN2020
1950 IFC=)1THEN1990
1960 B=FNA!IFA4=)6B=B+1
1970 IFB(6PRINT"YOU ARE NOT ACCEPTED FOR COMMISSIONING":GOTO2020
1980 C1=1:PRINT"YOU'VE BEEN COMMISSIONED 4TH OFFICER":C=1:GOTO2020
1990 B=FNA!IFA4=)9B=B+1
2000 IFB(10PRINT"YOU'VE BEEN DENIED PROMOTION":GOTO2020
2010 PRINT"YOU'VE BEEN PROMOTED":P=1:C=C+1
2020 B1=1:I=1
2030 IFE=1I=2
2040 IFP=1I=I+1
2050 IFC1=1I=I+1
2060 IFC1=4K0=K0+1
2070 PRINT"YOU HAVE ACQUIRED "!I!" SKILLS":PRINT"1 - PERSONAL DELEVOPMENT
","2 - SERVICE SKILLS":PRINT"3 - ADVANCED EDUCATION
2080 FORJ=1TO!:B=RND(5)+1:GOSUB2130:NEXT
2090 GOSUB3140
2100 INPUT"DO YOU WISH TO REENLIST":A$:IFLEFT$(A$,1)="N"THEN2120
2110 B=FNA!IFB=)4THEN1860
2120 GOTO2500
2130 INPUT"WHICH SKILL DO YOU WISH TO DEVELOP"!XX:ONXXGOTO2140,2170,2190
2140 IFB=1A1=A1+1ELSEIFB=2A2=A2+1ELSEIFB=3A3=A3+1ELSEIFB=4A1=A1+1ELSEIF
B=5S4=S4+ 1ELSEIFB=6K7=K7+1
2150 IFB=1ORB=4PRINT"+STRENGTH"ELSEIFB=2PRINT"+DEXTERITY"ELSEIFB=3PRINT"
+ENDURANCE"
2160 RETURN
2170 IFB=1K3=K3+1ELSEIFB=2S2=S2+1ELSEIFB=3A1=A1+1ELSEIFB=4S5=S5+1ELSEIFB
=5K1=K1+ 1ELSEIFB=6K2=K2+1
2180 RETURN
2190 IFA5=)8THEN2220
2200 IFB=1L5=L5+1ELSEIFB=2S0=S0+1ELSEIFB=3K1=K1+1ELSEIFB=4S9=S9+1ELSEIFB
=5S6=S6+1ELSEIFB=6K8=K8+1
2210 RETURN
2220 IFB=1KB=KB+1ELSEIFB=2S9=S9+1ELSEIFB=3K9=K9+1ELSEIFB=4L2=L2+1ELSEIF
B=5K0=K0+ 1ELSEIFB=6L1=L1+1
2230 RETURN
2240 CLS:PRINT."******************* OTHER ******************":PRINT'OTHER
CHARACTER
2250 PRINT"YOU HAVE BEEN ACCEPTED......"!B=FNA!IFA4=)9B=B+2
```

Traveller, continued...

MALA

Educational
Computer
Subscription
Program

32 programs

$48

PET COMMODORE VIC

COMPUTER GAMES

FREE
Educational Catalog
Summary Available

COMM*DATA SYSTEMS, INC.
P.O. BOX 325
MILFORD, MICHIGAN 48042
[313] 685-0113

CIRCLE 126 ON READER SERVICE CARD

computer case company

comp case

• AP103

• AP101	Apple II with Single Disk Drive	$109
• AP102	Apple II with Double Disk Drives	119
• AP103	Apple II, 9 inch Monitor & Double Drives	129
• AP104	Apple ///, two additional Drives & Silentype	139
• AP105	12 inch monitor plus accessories	99
• RS201	TRS-80 Model I, Expansion Unit & Drives	109
• RS202	TRS-80 Monitor or TV set	84
• RS204	TRS-80 Model III	129
• RS205	Radio Shack Color Computer	89
• P401	Paper Tiger 440/445/460	99
• P402	Centronics 730/737 - Line Printer II/IV	89
• P403	Epson MX70 or MX80	89
• CC90	Matching Attaché Case	75

computer case company
5650 INDIAN MOUND CT. COLUMBUS, OHIO 43213 (614) 868-9464

CIRCLE 261 ON READER SERVICE CARD

ComputerVille

SHOP BY PHONE
IMMEDIATE DELIVERY
Toll Free 800-258-1551
IN NEW HAMPSHIRE CALL COLLECT 889-1980

NAME BRANDS
FEATURING
MEMOREX

Diskettes
TESTED - CERTIFIED - GUARANTEED
$2.29 each from BOX OF TEN

FULLY COMPATIBLE
• APPLE
• TRS80
• PET
• ALL OTHER 5¼ AND 8" DRIVES

©1981 Computer Products Unlimited, Inc.

VOLUME DISCOUNTS

Ribbons
BRAND NEW TOP QUALITY FABRIC/MYLAR
COMPATIBLE WITH HUNDREDS OF PRINTERS
CALL FOR PRICES

TEST OUR UNCONDITIONAL GUARANTEE

LIMITED TIME OFFER
1 DISKETTE FREE!
WITH INITIAL 2-BOX MINIMUM ORDER
CALL FOR DETAILS

FREE DISKETTE IS YOURS TO KEEP EVEN IF YOU RETURN THE 2 BOXES!

NO SALES TAX

5¼" 8"

C.O.D.
WE SHIP ANYWHERE

Paper
ALL SIZES, COLORS, WEIGHTS
MULTI-PART
CARBON OR CARBONLESS
SHIPPED DIRECT FROM OUR NATIONWIDE WAREHOUSES

CIRCLE 132 ON READER SERVICE CARD

```
2260 E=E+1
2270 IF@THEN2310
2280 PRINT"YOU HAVE BEEN KILLED IN STAR BATTLE"
2290 INPUT"DO YOU WISH A NEW CHARACTER"!A$:IFLEFT$(A$,1)()"N"THEN120
2300 END
2310 PRINT"YOU SURVIVE TOUR #";E"....."
2320 I=1:IFE=1I=2
2330 PRINT"YOU HAVE ACQUIRED "!I!" SKILLS":PRINT"1 - PERSONAL DELEVOPMENT
","2 -  SERVICE SKILLS":PRINT"3 - ADVANCED EDUCATION
2340 FORJ=1TOI:B=RND(5)+1:GOSUB2390:NEXT
2350 GOSUB3140
2360 INPUT"DO YOU WISH TO REENLIST":A$:IFLEFT$(A$,1)="N"THEN2380
2370 B=FNAI!F*)5THEN2240
2380 GOTO2500
2390 INPUT"WHICH SKILL DO YOU WISH TO DEVELOP";!XX:ONXXGOTO2400,2430,2450
 2400 IFB=1A!=A1+1ELSEIFB=2A2=A2+1ELSEIFB=3A3=A3+1ELSEIFB=4S4=S4+1ELSEIFB=
5K6=K6+ 1ELSEIFB=6A6=A6+1
2410 IFB=1PRINT"+STRENGTH"ELSEIFB=2PRINT"+DEXTERITY"ELSEIFB=3PRINT"+ENDUR
ANCE"EL SEIFB=6PRINT"-SOCIAL"
2420 RETURN
2430 IFB=1K4=K4+1ELSEIFB=2K5=K5+1ELSEIFB=3K6=K6+1ELSEIFB=4S4=S4+1ELSEIFB=
5S5=S5+ 1ELSEIFB=6K7=K7+1
2440 RETURN
2450 IFA5=)BTHEN2480
2460 IFB=1L5=L5+1ELSEIFB=2S0=S0+1ELSEIFB=3K1=K1+1ELSEIFB=4K5=K5+1ELSEIFB=
5K6=K6+ 1ELSEIFB=6K4=K4+1
2470 RETURN
2480 IFB=1K8=K8+1ELSEIFB=2K4=K4+1ELSEIFB=3K1=K1+1ELSEIFB=4L2=L2+1ELSEIFB=
5L5=L5+ 1ELSEIFB=6K2=K2+1
2490 RETURN
2500 CLS:PRINT"YOU ARE MUSTERED OUT........"
2510 T=1+E:IFC=1 OR C=2 T=T+1
2520 IFC)2T=T+2
2530 IFBS=1THEN2540ELSEIFBS=2THEN2630ELSEIFBS=3THEN2720ELSEIFBS=4THEN2810
ELSEIFB S=5THEN2900ELSEIFBS=6THEN2990 'MUSTER OUT BENEFITS FOR EACH BRANCH
OF SERVICE
2540 FORJ=1TOT:GOSUB2550:C3'=C3'+C2':NEXT:GOSUB3000:GOSUB3140:FORI=1TO1500
!NEXT: OOTO4030 'ARMY
2550 INPUT"WHICH BENEFIT (1 - MATERIALS, 2 - CASH ALLOWANCE)";!XX
2560 ONXXGOTO 2570,2600
2570 B=RND(6):IFC)A$=B+1
2580 IFB=1L6=L6+1ELSEIFB=2A4=A4+1ELSEIFB=3A5=A5+2ELSEIFB=4W1=W1+1ELSEIFB=
5LB=1ELSEIFB=6L7=L7+1ELSEIFB=7A6=A6+2
2590 RETURN
2600 B=RND(6):IFC)A$=B+1
2610 IFB=1C2'=.00!ELSEIFB=2ORB=3C2'=.005ELSEIFB=4C2'=.01ELSEIFB=5C2'=
.02ELSEIFB=[)6C2'=.05
2620 RETURN
2630 FORJ=1TOT:GOSUB2640:C3'=C3'+C2':NEXT:GOSUB3000:GOSUB3140:FORI=1TO1500
!NEXT: OOTO4030 'MARINES
2640 INPUT"WHICH BENEFIT (1 - MATERIALS, 2 - CASH ALLOWANCE)";!XX
2650 ONXXGOTO 2660,2690
2660 B=RND(6):IFC)A$=B+1
2670 IFB=1L6=L6+1ELSEIFB=2A4=A4+2ELSEIFB=3A5=A5+1ELSEIFB=4W1=W1+1ELSEIFB=
5LB=LBE LSEIFB=6L7=L7+1ELSEIFB=7A6=A6+2
2680 RETURN
2690 B=RND(6):IFC)A$=B+1
2700 IFB=1C2'=.002ELSEIFB=2ORB=3C2'=.005ELSEIFB=4C2'=.01ELSEIFB=5C2'=
.02ELSEIFB= 6C2'=.03ELSEIFB=7C2'=.04
2710 RETURN
2720 FORJ=1TOT:GOSUB2730:C3'=C3'+C2':NEXT:GOSUB3000:GOSUB3140:FORI=1T01500:
NEXT: GOTO4030 'NAVY
2730 INPUT"WHICH BENEFIT (1 - MATERIALS, 2 - CASH ALLOWANCE)";!XX
2740 ONXXGOTO 2750,2780
2750 B=RND(6):IFC)A$=B+1
2760 IFB=1L6=L6+1ELSEIFB=2A4=A4+1ELSEIFB=3A5=A5+2ELSEIFB=4W2=W2+1ELSEIFB=
5L7=L7+ 1ELSEIFB=6LB=LB+1ELSEIFB=7A6=A6+1
2770 RETURN
2780 B=RND(6):IFC)A$=B+1
2790 IFB=1C2'=.002ELSEIFB=2C2'=.005ELSEIFB=3ORB=4ORB=5C2'=.005ELSEIFB=6C2'
=.02EL SEIFB=7C2'=.03
2800 RETURN
2810 FORJ=1TOT:GOSUB2820:C3'=C3'+C2':NEXT:GOSUB3000:GOSUB3140:FORI=1TO1500:
NEXT: GOTO4030 'SCOUTS
2820 INPUT"WHICH BENEFIT (1 - MATERIALS, 2 - CASH ALLOWANCE)";!XX
2830 ONXXGOTO 2840,2870
2840 B=RND(6):IFC)A$=B+1
2850 IFB=1L6=L6+1ELSEIFB=2A4=A4+2ELSEIFB=3A5=A5+2ELSEIFB=4W1=W1+1ELSEIFB
=5W2=W2+ 1ELSEIFB=6C0=C0+1
2860 RETURN
2870 B=RND(6):IFC)A$=B+1
2880 IFB=(2C2'=.02ELSEIFB=3ORB=4C2'=.03ELSEIFB=)5C2'=.05
2890 RETURN
2900 FORJ=1TOT:GOSUB2910:C3'=C3'+C2':NEXT:GOSUB3000:GOSUB3140:FORI=1TO1500:
NEXT: GOTO4030 'MERCHANTS
2910 INPUT"WHICH BENEFIT (1 - MATERIALS, 2 - CASH ALLOWANCE)";!XX
2920 ONXXGOTO 2930,2960
2930 B=RND(6):IFC)A$=B+1
2940 IFB=1L6=L6+1ELSEIFB=2A4=A4+1ELSEIFB=3A5=A5+1ELSEIFB=4W2=W2+1ELSEIFB
=5W1=W1+ 1ELSEIFB=6L6=L6+1ELSEIFB=7L9=L9+1
2950 RETURN
2960 B=RND(6):IFC)A$=B+1
2970 IFB=1C2'=.001ELSEIFB=2C2'=.005ELSEIFB=3C2'=.01ELSEIFB=4ORB=5C2'=.
02ELSEIFB= )6C2'=.04
2980 RETURN
2990 FORJ=1TOT:GOSUB3000:C3'=C3'+C2':NEXT:GOSUB3000:GOSUB3140:FORI=1TO1500
!NEXT: OOTO4030 'OTHER SERVICE
3000 INPUT"WHICH BENEFIT (1 - MATERIALS, 2 - CASH ALLOWANCE)";!XX
3010 ONXXGOTO 3020,3050
3020 B=RND(6):IFC)A$=B+1
3030 IFB=1L6=L6+1ELSEIFB=2A4=A4+1ELSEIFB=3A5=A5+1ELSEIFB=4W2=W2+1ELSEIFB
=5L7=L7+ 1
3040 RETURN
3050 B=RND(6):IFC)A$=B+1
3060 IFB=1C2'=.001ELSEIFB=2C2'=.005ELSEIFB=)3ANDB=(5C2'=.01ELSEIFB=5C2'
=.05ELSEI FB=7C2'=.1
3070 RETURN
3080 IFE=)5PRINT"RETIREMENT PAY........" 'RETIREMENT PAY
3090 IFE=5PRINT"4000 CR/ANNUM"
3100 IFE=6PRINT"6000 CR/ANNUM"
3110 IFE=7PRINT"8000 CR/ANNUM"
3120 IFE=8 PRINT"10000 CR/ANNUM"
3130 RETURN
3140 CLS:PRINTTAB(4)"********* TRAVELER CHARACTER *********":PRINT
'DISPLAY CURRENT STATUS OF CHARACTER
3150 NZ$="":IFA6=(10NZ$=N$
3160 IFA6=11NZ$="SIR "+N$
3170 IFA6=12NZ$="BARON "+N$
3180 IFA6=13NZ$="MARQUIS "+N$
3190 IFA6=14NZ$="COUNT "+N$
3200 IFA6=15NZ$="DUKE "+N$
3210 PRINTTAB(0)"NAME.........";NZ$;TAB(25)"RANK..........";C
3220 IFBS)0PRINT"BRANCH OF SERVICE"
3230 IFBS=1PRINT,"NAVY"
3240 IFBS=2PRINT,"MARINES"
3250 IFBS=3PRINT,"ARMY"
3260 IFBS=4PRINT,"SCOUTS"
3270 IFBS=5PRINT,"MERCHANT"
3280 IFBS=6PRINT,"OTHER"
3290 PRINT
3300 P=01C1=0!A7=1B+4+E
3310 IFA1=)15A1=15
3320 IFA2=)15A2=15
```

```
3330 IFA3=)15A3=15
3340 IFA4=)15A4=15
3350 IFA5=)15A5=15
3360 IFA6=)15A6=15
3370 IFA7(34THEN3590
3380 IFA7=)66THEN3470
3390 IFA7=)46THEN3520
3400 B=FNA
3410 IFB(7A1=A1-1
3420 IFB(7A2=A2-1
3430 IFB(7A3=A3-1:GOTO3590
3440 IFB(8A1=A1-1
3450 IFB(9A3=A3-1
3460 GOTO3590
3470 B=FNA
3480 IFB(9A1=A1-2
3490 IFB(9A2=A2-2
3500 IFB(9A3=A3-2
3510 IFB(9A4=A4-4
3520 GOTO3590
3530 B=FNA
3540 IFB(8A1=A1-1
3550 IFB(8A2=A2-1
3560 IFB(8A3=A3-1:GOTO3590
3570 IFB(9A1=A1-1
3580 IFB(9A3=A3-1

3590 PRINTTAB(0)"STRENGTH  - "1A1:TAB(25)"INTELLIGENCE    - "1A4
3600 PRINTTAB(0)"DEXTERITY - "1A2:TAB(25)"EDUCATION       - "1A5
3610 PRINTTAB(0)"ENDURANCE - "1A3:TAB(25)"SOCIAL STANDING - "1A6
3620 PRINT"CURRENT AGE......"1A7
3630 PRINT"SPECIAL SKILLS.........","LEVEL"
3640 IFS1=)1PRINT."SHIP'S BOAT",,S1
3650 IFS2=)1PRINT."VAC SUIT",,S2
3660 IFS3=)1PRINT."FWD OBS",,S3
3670 IFS4=)1PRINT."BLADE CBT",,S4
3680 IFS5=)1PRINT."GUN CBT",,S5
3690 IFS6=)1PRINT."GUNNERY",,S6
3700 IFS7=)1PRINT."ATV",,S7
3710 IFS8=)1PRINT."AIR RAFT",,S8
3720 IFS9=)1PRINT."NAVIGATION",,S9
3730 IFS0=)1PRINT."MECHANICAL",,S0
3740 IFK1=)1PRINT."ELECTRONIC",,K1
3750 IFK2=)1PRINT."JACK/ALL TRADES",,K2
3760 IFK3=)1PRINT."STEWARD",,K3
3770 IFK4=)1PRINT."FORGERY",,K4
3780 IFK5=)1PRINT."GAMBLING",,K5
3790 IFK6=)1PRINT."BRAWLING",,K6
3800 IFK7=)1PRINT."BRIBERY",,K7
3810 IFK8=)1PRINT."MEDICAL",,K8
3820 IFK9=)1PRINT."ENGINEERING",,K9
3830 IFK0=)1PRINT."PILOT",,K0
3840 IFL1=)1PRINT."ADMINISTRATION",,L1
3850 IFL2=)1PRINT."COMPUTER",,L2
3860 IFL3=)1PRINT."TACTICS",,L3
3870 IFL4=)1PRINT."LEADER",,L4
3880 IFL5=)1PRINT."STREETWISE",,L5
3890 IFL6=)1PRINT."LOW PASSAGE",,L6
3900 IFL7=)1PRINT."HIGH PASSAGE",,L7
3910 IFL8=)1PRINT."TRAVELER'S AID SOCIETY"
3920 IFL9=)1PRINT."MERCHANT SHIP",,L9
3930 IFL0=)1PRINT."MID PASSAGE",,L0
3940 IFW1=)1PRINT."BLADE",,W1
3950 IFW2=)1PRINT."GUN",,W2
3960 IFW3=)1PRINT."REVOLVER",,W3
3970 IFW4=)1PRINT."CUTLASS",,W4
3980 IFW5=)1PRINT."RIFLE",,W5
3990 IFW6=)1PRINT."SMG",,W6
4000 IFQ0=)1PRINT."SCOUT SHIP",,D0
4010 IFC3')@PRINT"TOTAL CASH DISBURSEMENTS ...."!C3'1" MIL. CR
4020 RETURN
4030 CLS:PRINT@512," "!INPUT"WOULD YOU LIKE A HARD COPY OF YOUR CHARACTER"!Y$:IF
LEFT$(Y$,1)()"Y"THEN4630 'PRINT CHARACTER SUMMARY
4040 CLS:LPRINT"*****************************************************************
"!LPRINT" "!LPRINTTAB(20)"T R A V E L E R   C H A R A C T E R"!LPRINT" "!LPRINT
"*****************************************************************"
4050 N$="":IFA6=(1ON2$=N$
4060 IFA6=11N$="SIR "+N$
4070 IFA6=12N$="BARON "+N$
4080 IFA6=13N$="MARQUIS "+N$
4090 IFA6=14N$="COUNT "+N$
4100 IFA6=15N$="DUKE "+N$
4110 LPRINT" "!LPRINTTAB(4)"NAME.........."!N$:TAB(35)"RANK........"!C1
LPRINT" "!LPRINT"*****************************************************
***********"
4120 IFBS)@LPRINT"BRANCH OF SERVICE"
4130 IFBS=1LPRINT."NAVY"
4140 IFBS=2LPRINT."MARINES"
4150 IFBS=3LPRINT."ARMY"
4160 IFBS=4LPRINT."SCOUTS"
4170 IFBS=5LPRINT."MERCHANT"
4180 IFBS=6LPRINT."OTHER"
4190 LPRINT" "
4200 LPRINTTAB(0)"STRENGTH  - "1A1:TAB(35)"INTELLIGENCE    - "1A4
4210 LPRINTTAB(0)"DEXTERITY - "1A2:TAB(35)"EDUCATION       - "1A5
4220 LPRINTTAB(0)"ENDURANCE - "1A3:TAB(35)"SOCIAL STANDING - "1A6
4230 LPRINT"CURRENT AGE......"1A7:LPRINT" "
4240 LPRINT"SPECIAL SKILLS.........","LEVEL"
4250 IFS1=)1LPRINT."SHIP'S BOAT",,S1
4260 IFS2=)1LPRINT."VAC SUIT",,S2
4270 IFS3=)1LPRINT."FWD OBS",,S3
4280 IFS4=)1LPRINT."BLADE CBT",,S4
4290 IFS5=)1LPRINT."GUN CBT",,S5
4300 IFS6=)1LPRINT."GUNNERY",,S6
4310 IFS7=)1LPRINT."ATV",,S7
4320 IFS8=)1LPRINT."AIR RAFT",,S8
4330 IFS9=)1LPRINT."NAVIGATION",,S9
4340 IFS0=)1LPRINT."MECHANICAL",,S0
4350 IFK1=)1LPRINT."ELECTRONIC",,K1
4360 IFK2=)1LPRINT."JACK/ALL TRADES",,K2
4370 IFK3=)1LPRINT."STEWARD",,K3
4380 IFK4=)1LPRINT."FORGERY",,K4
4390 IFK5=)1LPRINT."GAMBLING",,K5
4400 IFK6=)1LPRINT."BRAWLING",,K6
4410 IFK7=)1LPRINT."BRIBERY",,K7
4420 IFK8=)1LPRINT."MEDICAL",,K8
4430 IFK9=)1LPRINT."ENGINEERING",,K9
4440 IFK0=)1LPRINT."PILOT",,K0
4450 IFL1=)1LPRINT."ADMINISTRATION",,L1
4460 IFL2=)1LPRINT."COMPUTER",,L2
4470 IFL3=)1LPRINT."TACTICS",,L3
4480 IFL4=)1LPRINT."LEADER",,L4
4490 IFL5=)1LPRINT."STREETWISE",,L5
4500 IFL6=)1LPRINT."LOW PASSAGE",,L6
4510 IFL7=)1LPRINT."HIGH PASSAGE",,L7
4520 IFL8=)1LPRINT."TRAVELER'S AID SOCIETY"
4530 IFL9=)1LPRINT."MERCHANT SHIP",,L9
4540 IFL0=)1LPRINT."MID PASSAGE",,L0
4550 IFW1=)1LPRINT."BLADE",,W1
4560 IFW2=)1LPRINT."GUN",,W2
4570 IFW3=)1LPRINT."REVOLVER",,W3
4580 IFW4=)1LPRINT."CUTLASS",,W4
4590 IFW5=)1LPRINT."RIFLE",,W5
4600 IFW6=)1LPRINT."SMG",,W6
4610 IFQ0=)1LPRINT."SCOUT SHIP",,D0
4620 LPRINT" "!IFC3')@LPRINT"TOTAL CASH DISBURSEMENTS ...."!C3'1" MILLION
CREDITS"
4630 CLS: PRINT@512," "!INPUT"DO YOU WISH ANOTHER CHARACTER"!Y$:IFLEFT$
(Y$,1)="Y "THEN1_0ELSEEND
```

```
-------------------- SAMPLE RUN - WORLD/BAS

*  *  *  *  *  W  O  R  L  D   *  *  *  *  *
*  *  *  G  E  N  E  R  A  T  O  R  *  *  *

* * * * * * * * * * * * * * * * * * * * * * * * * * * * * *
* * * * * * * * * * * * * * * * * * * * * * * * * * * * * *

GENERATE 1 - WORLDS OR 2 - JUMPS FOR PLANETS
? 1
DO YOU WISH TO GENERATE AN ENTIRELY NEW GALAXY ? Y_

****************** W O R L D   G E N E R A T O R ****************

NAME PLANET? OMUCRON 4_

======PLANET======================OMUCRON 4========
STARPORT.......................................................B
GOOD, REFINED FUEL. ANNUAL MAINTENANCE. SHIPYARD CAPABLE OF
CONSTRUCTING NON STARSHIPS.
NAVAL BASE PRESENT
PLANETARY SIZE (MILES DIAMETER) (........6000
PLANETARY ATMOSPHERE.................VERY THIN.TAINTED
HYDROGRAPHIC % ......................50%
POPULATION.....................1.000.000
GOVERNMENT TYPE.....................................
CAPTIVE GOVERNMENT. RULING FUNCTIONS ARE PERFORMED BY AN IMPOSED
 LEADERSHIP FROM AN OUTSIDE GROUP. A COLONY OR CONQUERED AREA.
ENTER TO CONTINUE? _


LAW LEVEL.....................................................
CERTAIN WEAPONS ARE PROHIBITED.INCLUDING SPECIFICALLY 1)BODY
PISTOLS WHICH ARE UNDETECTABLE BY STANDARD DETECTORS 2)EXPLOSIVE
WEAPONS SUCH AS BOMBS OR GRENADES, AND 3) POISON GAS.
PORTABLE ENERGY WEAPONS. SUCH AS LASER RIFLES OR CARBINES ARE
PROHIBITED. SHIP'S GUNNERY IS NOT AFFECTED
WEAPONS OF A STRICT MILITARY NATURE (SUCH AS MACHINE GUNS OR
AUTOMATIC RIFLES. THOUGH NOT SUBMACHINEGUNS) ARE PROHIBITED.
PRESS ENTER TO CONTINUE? _


TECNOLOGICAL INDEX.............................................
========== WEAPONS ==========
PERSONAL            ARMOR     SPECIAL   COMPUTERS COMMUNICATION
LASER RIFLE         ABLAT     BM LASER  MODEL/3
==============TRANSPORTATION================
WATER               LAND      AIR       SPACE     FUELS
                                        STARSHIPS


REFEREE MAY ADD TO ANY BLANK LINES
DO YOU WISH TO ADD? _


PLANET==================================OMUCRON 4

UNIVERSAL PLANET PROFILE.............B6256659
TECH INDEX 9
SPECIAL ADDITIONS


DO YOU WISH TO STORE DATA? _
```

```
-------------------- SAMPLE RUN - WDREAD/BAS

*  *  *  *  *  W  O  R  L  D   *  *  *  *  *
*  *  *  *  *  R  E  A  D  E  R  *  *  *  *

* * * * * * * * * * * * * * * * * * * * * * * * * * * * * *
* * * * * * * * * * * * * * * * * * * * * * * * * * * * * *


WHAT IS THE RECORD # OF THE WORLD YOU WISH TO RETRIEVE? 2_


======PLANET======================DICRON 7=========
STARPORT.......................................................C
ROUTINE, ONLY UNREFINED FUEL AVAILAIBLE. REASONABLE REPAIR
FACILITY PRESENT.
PLANETARY SIZE (MILES DIAMETER) .........12000
PLANETARY ATMOSPHERE.................DENSE
HYDROGRAPHIC % ......................NO FREE STANDING WATER
POPULATION.....................1000
GOVERNMENT TYPE.....................................
PARTICIPATING DEMOCRACY. RULING FUNCTION DECISIONS ARE REACHED
BY ADVICE OF THE CITIZENRY DIRECTLY.
ENTER TO CONTINUE? _


LAW LEVEL.....................................................
CERTAIN WEAPONS ARE PROHIBITED.INCLUDING SPECIFICALLY 1)BODY
PISTOLS WHICH ARE UNDETECTABLE BY STANDARD DETECTORS 2)EXPLOSIVE
WEAPONS SUCH AS BOMBS OR GRENADES, AND 3) POISON GAS.
PORTABLE ENERGY WEAPONS. SUCH AS LASER RIFLES OR CARBINES ARE
PROHIBITED. SHIP'S GUNNERY IS NOT AFFECTED
WEAPONS OF A STRICT MILITARY NATURE (SUCH AS MACHINE GUNS OR
AUTOMATIC RIFLES. THOUGH NOT SUBMACHINEGUNS) ARE PROHIBITED.
PRESS ENTER TO CONTINUE?
LIGHT ASSAULT WEAPONS (SUCH AS SUBMACHINE GUNS) ARE PROHIBITED.
PERSONAL CONCEALABLE FIREARMS (SUCH AS PISTOLS AND REVOLVERS)
ARE PROHIBITED.
ENTER TO CONTINUE? _


TECNOLOGICAL INDEX.............................................
========== WEAPONS ==========
PERSONAL            ARMOR     SPECIAL   COMPUTERS COMMUNICATION
BODY PISTOL         MESH      PULSE LASER MODEL/2
==============TRANSPORTATION================
WATER               LAND      AIR       SPACE     FUELS
HOVERCRAFT          HOVERCRAFT          NON-STARSHIP SOLAR

ENTER TO CONTINUE? _


PLANET==================================DICRON 7

UNIVERSAL PLANET PROFILE.............CC803257
TECH INDEX 7
SPECIAL ADDITIONS


DO YOU WISH TO CONTINUE? NO_
```

Buy with Confidence from the best

GREAT PRICES, GREAT SERVICE, GUARANTEED

COMPUTERS, PRINTERS, TERMINALS

Apple IEEE-488 card now available

CALL TOLL FREE: 1 800 421-1520
In Calif. 213 320-4772

COMPUTERS

apple computer

Apple Computers
Disk drives, accessories software, graphics tablets. CALL FOR BEST PRICES

HEWLETT PACKARD

Whether you want their great computer or a wide selection of computer calculators-we have them
HP-85 - Retail $3250
Only $2475

Call us for great prices: **Altos, Atari, NEC, Zenith and other computers**

PRINTERS - MONITORS

NEW MX 100 & MX 80 F/T

The new 136 column Epson printer with graphics and the Friction/tractor MX 80 are in stock. WE HAVE THE GRAPHIC PACKAGE FOR MX 80. call.

SILENTYPE PRINTER ONLY $284.00

MONITORS
BMC & NEC Green Screen
NOW IN STOCK

We have the CORVUS systems to hook up several Apple computers at once!

NEC & DIABLO PRINTERS
Anadex, Paper Tiger. CALL for latest prices

Computer furniture too

ACCESSORIES - SOFTWARE

Amazing Mountain Hardware
CPS Multi-function card
ALL IN ONE:
Parallel/Serial/Clock/Calen

SOFTWARE

Visicalc 3.3	$175/Reg.	$199
BPI GL/INV/AR/etc	299/Reg.	399
Tax Preparer by Howardsoft	79/Reg.	99
Real Estate Analyzer,Howardsoft	125/Reg.	150
Creative Financing, Howardsoft	125/Reg.	150
ASCII Express II by SDS	55/Reg.	65
Z-TERM (CPM) (16 sector)	85/Reg.	100

TRS 80 & ATARI SOFTWARE TOO

PLOTTERS
Bausch&Lomb plotters for your computer by Houston Instruments. CALL!

MICROSOFT 16K
Ramcard $155

CALL TOLL FREE

1(800)421-1520
In Cal (213)320-4772

Dysan
104/1
5¼" Disks only 3.95

Visit our retail store:
Net Profit Computers
521 W. Chapman Ave
Anaheim, Cal. 92802
714 750-7318

Mail orders ONLY:
NET PROFIT COMPUTERS
2908 Oregon Court, Bld G1
Torrance, Ca 90503
1(800)421-1520
in Cal: 213 320-4772

VISA

Cal residents add 6% sales tax. Minimum shipping and handling charges are $3.00. Mstch, Visa, Amex prices slightly higher on sale items. Store prices differ

CIRCLE 196 ON READER SERVICE CARD

The search for quality hardcopy stops

HERE

microCOMPOSER

THE ULTIMATE IN HARD COPY!

You can use the TRS-80® I or III to set publication grade photo type. Not "letter quality" impact type, but true publication level photo TYPE—with all the variety of style, size and format that is only possible with genuine typesetting. (Like this ad, for example.)

The microCOMPOSER system makes it possible for a TRS-80 I or III to drive a Compuwriter I or II (Juniors also) with complete control and access of the Compuwriter's capabilities. Enjoy all the power of a computerized word processor for keyboarding and store files on floppy disks.

The Compuwriter is not modified in any way. microCOMPOSER's interface is independently packaged and uses an already existing plug connector in the Compuwriter. Four simple wires to solder and a switch to mount in an existing hole. That's all! The computer and the Compuwriter may be used independently at any time.

The microCOMPOSER revolution has begun.

We have a free brochure with details:

COVE VIEW PRESS • Box 637 • Garberville, CA 95440 • (707) 923-3476
Dealer inquiries invited

CIRCLE 164 ON READER SERVICE CARD

MARKET ANALYSIS.

Easy. And Fast.

Programs for your personal computer.

STOCK TRACKER uses our technical volume analysis to give buy and sell signals on individual stocks, options and commodities. Telecommunications package optional.

MARKET TRACKER is a composite of six technical indicators which tell when the Dow turns bullish and bearish. Its four-year track record is available.

H & H
TRADING COMPANY
Post Office Box 549
Clayton, CA 94517
415/672-3233

CIRCLE 257 ON READER SERVICE CARD

TURN YOUR TYPEWRITER INTO A PRINTER

Dealer Inquiries Invited

New KGS-80 Keyboard Actuator.

- Because of its hardware interface, the KGS-80 is the only actuator that is delivered ready to set up and run with no alteration of your existing software.
- Rests on keyboard of IBM Selectric, SCM or other typewriters. May be installed or removed in seconds.
- New third generation unit engineered and manufactured for reliability and long life by Kogyosha Co., Ltd., Japan's largest manufacturer of DC solenoids
- Price $599 FOB New York, NY.
- "Y" cable switch option allows alternative operation with high speed matrix printer.

For further information, call (201) 569-8769

Authorized Importer

NIK International Trading Inc.
114 Liberty St. Suite 204, New York, NY 10006

CIRCLE 176 ON READER SERVICE CARD

Traveller, continued...

```
-------------------- SAMPLE RUN - TRAVEL/BAS

*   *   *   C   H   A   R   A   C   T   E   R   *   *
*   *   *   G   E   N   E   R   A   T   O   R   *   *

* * * * * * * * * * * * * * * * * * * * * * * * * * *
* * * * * * * * * * * * * * * * * * * * * * * * * * *

  N A M E   Y O U R   C H A R A C T E R ?   T H O R _


    ********* TRAVELER CHARACTER *********

 NAME........THOR          RANK........... 0

 STRENGTH  -  3            INTELLIGENCE    -  12
 DEXTERITY -  10           EDUCATION       -  4
 ENDURANCE -  11           SOCIAL STANDING -  8
 CURRENT AGE...... 18
 SPECIAL SKILLS...........                       LEVEL

 DO YOU WISH TO ENLIST? YES_


****************** MERCHANTS ******************

 YOU HAVE BEEN ACCEPTED......
 YOU SURVIVE TOUR # 1 .......
 YOU'VE BEEN COMMISSIONED &TH OFFICER
 YOU HAVE ACQUIRED  3  SKILLS
 1 - PERSONAL DEVELOPMENT          2 - SERVICE SKILLS
 3 - ADVANCED EDUCATION
 WHICH SKILL DO YOU WISH TO DEVELOP? 1
 +STRENGTH
 WHICH SKILL DO YOU WISH TO DEVELOP? 2
 WHICH SKILL DO YOU WISH TO DEVELOP? 3_
```


LOCK SMITH

INTRODUCING LOCKSMITH 4.0

Six utility routines designed to make using your **APPLE** easier.

Not just a copy program, the new **Locksmith** also has these utilities added:

1. **Surface Analysis** - Tests for questionable media - don't trust valuable data to untested diskettes.

2 **Disk Speed** - To assist in fine tuning your drives - includes diagrams to help you do it yourself.

3. **Bulk Erase** - Degausses your diskettes before reusing so no stray data is leftover.

4. **Quick Scan** - Check for unreliable data - find used and unused tracks.

5. **Nibble Editor** - To fix and edit raw disk data useful when a disk crashes.

And **Locksmith 4.0** is the most reliable copy program available for the **APPLE** computer at any price.

See your local dealer or . . . Mastercard or VISA users call **TOLL FREE 1- 800-835-2246**. Or send **$99.95.** Illinois residents add $6.00 sales tax. (current owners should have received a letter regarding our simple update procedure)

Another Quality Product from
Omega MicroWare, Inc.
(formerly Omega Software Products, Inc.)
222 So. Riverside Plaza
Chicago, IL 60606
Phone 312-648-1944

©1981 Omega MicroWare, Inc.
Apple is a registered trademark of Apple Computer, Inc

CIRCLE 201 ON READER SERVICE CARD

NorthStar™

HORIZON II COMPUTERS

Shop around find your best price then call us **COLLECT***we'll match the price plus ship it direct to you by **A I R**

*ABSOLUTELY FREE!**

WORRY FREE WARRANTY - This is our third year with North Star with a reputation of only the finest service (call North Star for a reference) all repairs are handled through our store service center.

**CONTINENTAL U.S. ONLY*

LONG ISLAND COMPUTER GENERAL STORE

1011 ATLANTIC AVE LYNBROOK NEW YORK 11563

(516) 887-1500

CIRCLE 206 ON READER SERVICE CARD

SHOP 'n SAVE at MANNFRED *EVERYBODY ELSE DOES!*

IC MACHINE & TOOL

- Digital Logic Probe #PRO-1 $33.95
- Dip IC Insertion Tools With Pin Straightener #IC-2120 $5.95
- 14-16 Pin Dip IC Inserter #IMS-1416 $3.95
- Wire Dispenser - Blue, Yellow, White or Red #WD-30 $4.95
- Tri-Color Dispenser #WD-30-TRI $7.95
- Tri-Color Dispenser Replacement Reels #R-30-TRI $.95
- Wire Dispenser Replacement Reels - Blue, Yellow, White, or Red #R-30-WDSR $.95

HOBBY-BLOX

- Basic Integrated Circuit Starter Pack #400 $5.95
- Basic Discrete Component Starter Pack #400 $5.95
- Blank Panel Pack #550 $1.95
- Control Panel Pack #546 $1.95
- Distribution Strips #510 $1.95
- Discrete Component Strip #515 $2.00
- Tray Extender Clips #570 $1.95
- Bus Strip #520 $2.00
- 3x16 Terminal Strip #525 $2.00
- Binding Post Strip #540 $2.95
- Terminal Strip Pack #585 $2.00

CAR AUTOSOUND PRODUCTS

- Cassette Stereo Tape Player & Pushbutton AM/FM Stereo Radio #C-220 $58.95
- Cassette Stereo Tape Player & AM/FM Stereo Radio #C-230 $42.95
- Auto-Reverse Cassette Stereo Tape Player & AM/FM Stereo Radio #C-325 $63.95
- 8-Track Stereo Tape Player & AM/FM Stereo Radio #C-250 $43.95
- Totalchip Wireless Remote Control #6361 $19.95

VIDEO TAPES

@ AMPEX & SONY @ STANTON (HC)

L250	2 for	$18.00
L500	2 for	21.00
L750	2 for	27.00
L830	2 for	28.00
T-120	2 for	28.00

NIGHT SENTRY

SOLID STATE **TIMER**

$19.95 2 for $15.00

TEL/ANSWER/MACHINES

RECORD-A-CALL

#60 $114.95 Remote #60 214.95

BECKMAN DIGITAL MULTI-METERS

0.5% Accuracy	#300	$182.00
0.25% Accuracy	#310	123.00
0.1% Accuracy	#330	186.00

Ademco Burglar & Fire Alarm Supplies... Now at Rock-Bottom Prices!

Warner Communications Pre-Recorded First Line Movies *WRITE FOR OUR CATALOG — THE PRICE IS RIGHT!*

CALL FOR SPECIAL DAY-TO-DAY QUOTES ON ENTIRE LINE OF COMMODORE & ATARI COMPUTERS
WE SHIP BY U.P.S. - C.O.D. CASH OR CERTIFIED CHECK

MANNFRED ELECTRONICS CORP.
60-10 KISSENA BLVD., FLUSHING, N.Y. 11355
TOLL FREE (800) 221-0466 HOURS 9AM - 4PM E.S.T.

CIRCLE 207 ON READER SERVICE CARD

LET YOUR APPLE SEE THE WORLD!

The DS-65 Digisector® opens up a whole new world for your Apple II. Your computer can now be a part of the action, taking pictures to amuse your friends, watching your house while you're away, taking computer portraits . . . the applications abound! The DS-65 is a random access video digitizer. It converts a TV camera's output into digital information your computer can process. The DS-65 features:

- **High Resolution** — a 256 × 256 picture element scan
- **Precision** — 64 levels of grey scale
- **Versatility** — Accepts either NTSC or industrial video input
- **Economy** — A professional tool priced for the hobbyist

The DS-65 is an intelligent peripheral card with on-board software in 2708 EPROM. Check these software features:

- Full screen scans directly to Apple Hi-Res screen
- Easy random access digitizing by Basic programs
- Line-scan digitizing for reading charts or tracking objects
- Utility functions for clearing and copying the Hi-Res screen

HI-RES PICTURE USING THE DS-65 AND PICTURE SCANNER SOFTWARE

Use the DS-65 for precision security systems; computer portraiture; robotics; fast to slow scan conversion; moving target indicators; reading UPC codes, musical scores and paper tape and more! **GIVE YOUR APPLE THE GIFT OF SIGHT!** DS-65 Price: $349.95 / FSII Camera Price: $299.00 / Combination Price: $599.00

ADDITIONAL SOFTWARE FOR THE DS-65

—Picture Scanner: Provides a variety of different dithering algorithms for compressing the digitized image into the Hi-Res screen. Available on 13-sector disk. Price: $39.95

—Superscan: Enables you to enhance the DS-65's Hi-Res pictures with colors! Choose from 21 different colors and assign them to grey scale values, modify pictures, zoom, enhance contrast, etc. Print routines for the Anadex and Paper Tiger* are provided. Comes on a 13-sector disk. Written for The Micro Works by Magna Soft. Price: $79.95

—Portrait System Software: This program includes captions and a credit line, reverse printing for T-shirt application and the option to save portraits on disk. Specifically for use with a Malibu 165 printer. Call or write for more information.

*Paper Tiger is a trademark of Integral Data Systems, Inc.

MasterCharge/Visa Accepted

THE MICRO WORKS

P.O. BOX 1110 DEL MAR, CA 92014 714-942-2400

CIRCLE 212 ON READER SERVICE CARD

Building a Better INPUT

Jonathan D. Ashwell

We sometimes receive letters from readers criticizing our use of articles and programs for specific computers. We feel, however, that there is often value in reading articles—and even programs—about computers other than one's own. Here is an example of what an Apple owner did with information found in an article about the Sorcerer. —EBS

One of the advantages of a high level language like Basic is the ease with which one can write interactive programs. The INPUT command is particularly useful, because it provides two functions: the ability to display questions and the means of accepting the response. However, the price one pays for this convenience is in the restrictions imposed upon the format the material to be input must take. This is especially true with strings.

This problem was stated nicely by David Persuitte in the February, 1981 issue of *Creative Computing*. When entering a string, the punctuation marks, comma and colon, are interpreted as "end-of-string" indicators, and any data following them will be ignored. You will be notified of this misunderstanding with the terse ?EXTRA IGNORED. This problem can be avoided by placing the material to be input in quotes, but this is a nuisance.

Moreover, if you are writing a program to be used by others, this sort of restriction is unacceptable. There is also a restriction in that the quote mark cannot be part of a string, since the computer will interpret it as a direction. These restrictions make it impossible to enter true prose into the computer with the INPUT command, for without adequate punctuation, sentences are difficult, if not impossible, to read.

In his article, Mr. Persuitte gives a simple and effective solution to this problem. He uses a short machine language routine written for the Exidy Sorcerer to enter characters (ASCII encoded) from the keyboard to a location in memory, from which they can be reassembled into a string by a series of PEEKs from a Basic language program. Although this works well, it has one major drawback. That is, one loses all of the editing features the computer provides.

As anyone who spends a lot of time in front of a monitor (or TV) knows, this can be quite a sacrifice. I use an Apple II Plus, which provides a backspace (shift rub), retype key (forward arrow) and a variety of pure cursor moves in the ESCAPE mode. Editing input is much more difficult without them.

Although it is possible to build screen editing features back into a routine such as the one described by Mr. Persuitte, it requires a thorough knowledge of the computer monitor routines and adds a lot of dead weight to the program.

I became interested in finding an alternative method of entering data because I wanted to write a program which called for the user to supply information as prose. All punctuation has to be allowed. Editing had to be easy to allow correction of typos and rearrangement of words without retyping a paragraph. There had to be another way to input, without the restrictions so far discussed—and, of course, there is.

The input routine that I devised is a simple adaptation of the GETLN routine that resides in the Apple monitor (see Apple II Reference Manual, pp. 33-34 and 62-63). This subroutine, located at $FD6A (decimal -662), displays a prompt on the screen and waits for input from the keyboard. The subroutine is terminated when a carriage return is encountered, and returns with the input line in the input buffer (beginning at location $200, decimal 512). The X register holds the length of the input line. The monitor's GETLN supports all the editing features of the Apple. It also allows the entry of punctuation marks. The maximum length of the input line is 255 characters (bytes).

Now that we have an alternate way of entering data into the keyboard buffer, it seems a simple matter to PEEK from a Basic program and retrieve the string entered, one byte at a time. There is, however, one catch. Data entered into the keyboard buffer is, of course, in ASCII code. It is entered with the "high bit on," which means that 128 (or hex $80) has been added to it. Data entered from Basic is entered with the "high bit off."

The difference is more easily seen with an example. CHR$ (65) and CHR$ (193) both represent the letter "A." However, the computer will see them as different characters, because their ASCII code is

Jonathan D. Ashwell, Box 19-B, 60 Haven Ave., New York, NY 10032.

CREATIVE SOFTWARE

is your source for

VIC® PROGRAMS

VIC Games **$24.95**
- VIC Trap
- Seawolf
- Bounce Out

Household Finance **$34.95**
- Part I — Entering & Updating
- Part II — Summing & Displaying
- Part III — Budgeting & Graphing
- Part IV — Deductibles Analysis

Home Inventory **$14.95**
- Part I — Entering Inventory
- Part II — Evaluating Inventory

Logic Games **$14.95**
- Code Maker
- Code Breaker

Recreational/Educational I **$14.95**
- Hangman
- Hangmath

Recreational/Educational II **$14.95**
- Math Hurdler
- Monster Maze

Ordering Information: *VISA/Mastercard, check or money order accepted. If charge, please include expiration date of card. Add $1.50 for shipping and handling. Calif. residents add sales tax.*

CREATIVE SOFTWARE

201 San Antonio Circle, #270
Mountain View, CA 94040
(415) 948-9595

CIRCLE 241 ON READER SERVICE CARD

MICROMAIL

CRT'S • PRINTERS • TELEPRINTERS

TELEVIDEO		DIABLO		ANADEX
910		630		DP-9500/9501
$599.00		$1950.00		$1299.00
912	CALL	1640	CALL	9000/9001 &
920	CALL	1650	CALL	8000 CALL
950	CALL			

CALL FOR OUR LOW PRICES ON

QUME, NEC, T.I., DEC
TELETYPE, SOROC, C.ITOH

TOLL FREE (800) 854-6028

To Order: Send check to MICROMAIL, P.O. Box 3297, Santa Ana, CA 92703. Personal or company checks require two weeks to clear. Visa/MasterCard accepted. C.O.D. requires a 15% deposit.
Handling: Add 3% to orders less than $750, 2% to order $751–$2,000, 1% to orders over $2,000. NOTE: Handling charges are waived on orders pre-paid in advance by check.
Shipping: We ship FREIGHT COLLECT via UPS or Motor Freight. Air and Express delivery is available. Prices subject to change without notice.

INTERNATIONAL ORDERS WELCOME
TWX, WRITE or CALL

MICROMAIL
P.O. Box 3297
Santa Ana, CA 92703
Phone: 714/731-4338
TWX: 910 595 1146

CIRCLE 210 ON READER SERVICE CARD



The Voice gives your Apple the power of speech! Use the standard Voice vocabulary to speak an endless combination of phrases, or easily record your own vocabulary and make your Apple say anything you like. Each data disk stores up to 80 words or phrases which can be sorted for quick reference. What's more, the Voice allows you to speak from any Basic program by using Print Commands. Guaranteed the best and easiest to use speech software available. For the Apple II or Apple II Plus with 48K. ($39.95)

from the leader in quality software

MUSE SOFTWARE

330 N. CHARLES STREET
BALTIMORE, MD 21201
(301) 659-7212

Apple is a trademark of Apple Computer Corp.

CIRCLE 225 ON READER SERVICE CARD

300	20 6A FD	JSR	$FD6A	JSR monitor's GETLN
303	86 FD	STX	$FD	Save X register
305	A0 00	LDY	#$00	Initialize Y register
307	38	SEC		
308	B9 00 02	LDA	$0200,Y	Get input, one byte at a time,
30B	E9 80	SBC	#$80	and subtract $80 (decimal 128)
30D	99 00 02	STA	$0200,Y	Replace with new value
310	C8	INY		
311	C4 FD	CPY	$FD	End of input line?
313	F0 02	BEQ	$0317	Yes, return to Basic program
315	D0 F0	BNE	$0307	No, get another byte
317	60	RTS		

Listing 1.

different. Therefore, if one was screening input and checking for a match, the wait would be a long one. For example, let's say that you have constructed a loop which asks for a series of strings to input. Further, after each entry the program checks to see if the string was the word "END," which you have chosen to be the signal that no more is to be entered. The program will check for the following ASCII values: 69 (E), 78 (N), 68 (D). The values retrieved from the keyboard buffer, however, when using the GETLN subroutine are: 197 (E), 206 (N), and 196 (D). Therefore, even when you have entered the string "END," the computer will fail to recognize this as the command to terminate the loop. The solution to this problem is to subtract $80 from each byte in the keyboard buffer before incorporating it into your string. That is what the routine in Listing 1 does.

This routine can also be POKEd into memory early in any program in which it is to be CALLed. The short routine in Listing 2 will accomplish this.

I use this subroutine in location $300 (decimal 768), but it has been written so that it is relocatable. If it is entered at $300, simply CALL 768 from a Basic program to use it.

```
 5 FOR Z = 768 to 791
10 READ A
15 POKE Z,A
20 NEXT Z
25 DATA 32,106,253,134,253,160,0,56,
   185,0,2,233,128,153,0,2,200,196,253,
   240,2,208,240,96
```

Listing 2.

I have included a sample program in Listing 3 which will recover a string (A$) entered with this routine.

Using a string array will allow for more input. Also, using a variable to represent 512, the base address of the input buffer, will speed up the retrieving loop.

One final twist that you can add to your programs with this routine is the use of your own prompt symbols. The Apple GETLN subroutine outputs the prompt character held in location $33 (decimal 51) when asking for input. This is the familiar close bracket in Applesoft, or the asterisk when in the monitor. You may supply your own prompt character if you wish. POKEing the ASCII value of the character into $33. I have included a short routine in Listing 4 which, when appended to the Basic routine, will ask for 26 inputs, each prompted by succeeding letters of the alphabet.

Although this was written for the Apple II Plus, the concept behind it is simple, and should be adaptable to any microcomputer. The only special information required is a knowledge of where the GETLN routine, or its equivalent, resides in the monitor. □

```
10 CALL 768
20 E = PEEK (253)  E = length of input line
30 FOR Z = 0 to E-1
40 Y$ = CHR$ (PEEK (512 + Z)) PEEK input buffer, one byte at a time
50 A$ = A$ + Y$
60 NEXT Z
70 PRINT A$
```

Listing 3.

```
 3 DIM A$(26)
 5 FOR C = 1 TO 26
 8 T = T + 1
 9 POKE 51,192 + T
10 CALL 768
20 E = PEEK (253)
30 FOR Z = 0 TO E-1
40 Y$ = CHR$ (PEEK (512 + Z))
50 A$(C) = A$(C) + Y$
60 NEXT Z
70 PRINT A$(C): PRINT
80 NEXT C
90 END
```

Listing 4.

GREAT GAMES

For TRS-80 I/III and Atari

Manhattan Software puts a shrewd, sophisticated card player behind the screen of your computer, to match wits with you at Gin Rummy and Cribbage. At the Blackjack table there's a tireless dealer and expert card counter to teach you how to beat the casino. These aren't programs that 'sort of' play, but real card playing opponents, who play full regulation games, keep score, and challenge you to beat them.

Gin Rummy 3.0

Card graphics and fast, expert play. Real Gin, knocking at ten points or less. Keeps score to game level. The disk version keeps score from game to game, so you can start another session where you left off. TRS-80 Mod I/III Cass. $16.95, Mod I Disk $21.95. Atari Cass. (24K) $19.95, Disk $24.95.

Cribbage Master

Excellent screen graphics, and plays hard for every point. Makes no counting mistakes, and will Muggins you if you do. User engineered for easy play, with order of cards shown for in-play scoring. Cassette version will not run in Disk Basic. TRS-80 Mod I/III Cass. $14.95, Mod I Disk $19.95. Atari version available soon.

Casino Blackjack/Counter

Learn card counting and beat the house at its own game! You play one of five hands (the computer plays the others) — and practice card counting as the cards are dealt, or just follow the recommended bets. Choose up to 6 decks to play against, and set the dealing speed to slow, medium, or fast. TRS-80 Mod I/III Cass. $14.95, Mod I Disk $19.95. Atari Cass. (24K) $19.95, Disk $24.95.

TRS-80 3-Game Pack

The three great card games above, on a single disk, and at a substantial savings. Mod I Disk $39.95.

Atari Game Pack

Gin Rummy, Casino Blackjack and the fascinating Concentration game on a single disk $49.95.

AT YOUR DEALER OR DIRECT FROM

MANHATTAN SOFTWARE

P.O. BOX 1063
WOODLAND HILLS, CA 91365
California residents add 6% tax
24-Hour Visa/MasterCard Order Line:
(213) 704-8495
Write for Software Catalog

CIRCLE 320 ON READER SERVICE CARD

AUTHORIZED TRS 80® DEALER #R491

$670.00 NOT AVAILABLE

MODEL I

16K Level II with Keypad
26 – 1056

$3500.00

MODEL II

MODEL II, 64K
26 – 4002

$825.00

MODEL III

MODEL III 16K RAM,
MODEL III BASIC
26 – 1062

WE ACCEPT CHECK, MONEY ORDER, OR PHONE ORDERS WITH VISA OR MASTER CHARGE. SHIPPING COSTS WILL BE ADDED TO CHARGE ORDERS. DISK DRIVES, PRINTERS, PERIPHERALS, AND SOFTWARE - YOU NAME, WE'VE GOT IT. WRITE OR CALL FOR OUR COMPLETE PRICE LIST.

FULL FACTORY WARRANTY ON ALL ITEMS SOLD.

C & S ELECTRONICS, LTD. 32 EAST MAIN ST. MILAN, MICH. 48160
(313) 439-1508 (313) 439-1400

C & S ELECTRONICS MART IS AN AUTHORIZED TRS 80® SALES CENTER STORE #R491

CIRCLE 119 ON READER SERVICE CARD

APPLE PASCAL™

A HANDS-ON APPROACH

Gives you everything you need to use the most powerful language your computer can have.

User-tested, step-by-step A-to-Z approach features hands-on experiences in creating, running, and debugging programs. Volume is spiral-bound to lie flat by the keyboard while it takes you from basics to advanced programming and graphics applications. No math background is required. Only $14.95. Order today — put the power of Pascal to work for you.

Also available
BASIC: A Hands-On Method
Second Edition
Herbert D. Peckham,
Spiral-bound, 306 pp., $12.95

Mail the coupon today

Mail to
D. LaFrenier
McGraw-Hill Book Company
1221 Avenue of the Americas
New York, N.Y. 10020

SAVE MONEY:
Remit with order and we pay all shipping and handling costs. Full return privileges still apply.

Please send me the books checked for 15 days free examination. At the end of that time I will pay for the books I keep, plus local tax, postage and handling, and return any unwanted books postpaid.

☐ APPLE PASCAL (49171-2), $14.95
☐ BASIC: A HANDS-ON METHOD (49160-7), $12.95

Name _____
Address _____
City/State/Zip _____

62-U444-1181-1

CIRCLE 208 ON READER SERVICE CARD

Atari is a reg ™ of Atari, Inc

UPGRADE YOUR ATARI®



THE ONLY LOGICAL UPGRADE FOR ATARI BASIC!

GRADUATE TO BASIC A+
FROM THE AUTHORS OF ATARI BASIC!

BASIC A+

BASIC A+ will rate an A+ from any Atari user! Upward compatible with Atari Basic, It adds statements and features that enhance the Atari 800's real power, flexibility, and ease of use: Superior I/O features for business and other applications. Additional file manipulation commands. Significant help in program development and debug. Structured programming aids. And MORE! A partial list of the enhancements of BASIC A+ includes:

RPUT/RGET (record I/O) **BPUT/BGET** (binary I/O) **ERASE PRINT USING SET TAB INPUT"..." OIR PROTECT RENAME TRACE WHILE...ENOWHILE IF...ELSE...ENOIF SUPERB PLAYER/MISSILE GRAPHICS**

BASIC A+ requires a disk and 32K bytes of RAM. Since no cartridge is used, BASIC A+ will take advantage of all the RAM (48K bytes) in a maximum Atari 800 system (recommended) $80

OS/A+

Completely compatible with Atari's DOS (version 2), but with an advanced, command-driven console processor. Simple. Flexible. Powerful. With an easy-to-use **BATCH** capability, OS/A+ **INCLUDES** all the following utilities (and more):

EASMD (Editor/ASseMbler/Debug) is our upgraded all-in-one assembly language development package for the 6502 microprocessor. The editor — with such features as FIND and REPLACE — can even edit BASIC A+ programs. The assembler can include multiple source files in a single assembly.

DUPDSK and FORMAT create master or slave disks. Make sector by sector copies of any OS/A+ disk

COPY a simple, single file copy utility.

All of this power is included in our OS/A+ package $80

For the utmost in capability and flexibility, our combination system — **BASIC A+** and **OS/A+** — is available $150

SOFTWARE IN A CLASS BY ITSELF
AVAILABLE NOW THROUGH LOCAL DEALERS

Optimized Systems Software, Inc.
10379-C Lansdale Ave., Cupertino, CA 95014.
(408) 446-3099

CIRCLE 232 ON READER SERVICE CARD

TRS-80 Model I Keyboard Repeat

Thomas Shapiro

```
10 Rem Automatic keyboard repeat by Tom Shapiro.

20 Rem Memory size=32654

30 POKE 16526,143:POKE 16527,127

40 FOR X=32655 TO 32767:READ A:POKE X,A:NEXT

50 X=USR(0)

60 DATA 33,152,127,34,22,64,195,25,26,33,54,64,1,1,56,22,0

70 DATA 10,95,163,32,26,119,20,44,203,1,121,214,128,32,241,126

80 DATA 6,7,45,134,16,252,254,0,62,0,192,50,26,64,201,166

90 DATA 40,16,58,26,64,60,50,26,64,254,255,32,217,61,50,26

100 DATA 64,123,115,197,1,0,2,205,96,0,193,10,163,200,197,229

110 DATA 245,6,64,58,61,64,230,253,103,246,2,111,125,211,255,124

120 DATA 211,255,197,6,64,16,254,193,16,242,241,225,193,195,251,3
```

The TRS-80 Model I computer comes with only one form of built in repeat function; its notorious and unpredictable keybounce. While an unwanted keyboard repeat is a nuisance, there are many occasions, especially in games, when a deliberately controlled repeat function is useful. This program will modify the keyboard scan routine to allow keyboard input to repeat as long as you hold a key down.

This works properly only in a 16K Model I TRS-80 with the memory size set to 32654. It takes a machine language program in DATA statements and POKEs it into protected memory. □

Thomas Shapiro, 1010 Fifth Ave., New York, NY 10028.

Quick Disk Catalog

Buck Buchanan

This handy program first takes the Control Character Finder program from page 151 of the Apple DOS 3.2 Manual and adds an EXEC program to catalog disks then print them.

The control characters will be visible on-screen only, of course.

Using this program it took five minutes to catalog and print my library of sixty disks. □

```
10  DATA  201,141,240,21,201,136
20  DATA  240,17,201,128,144,13
30  DATA  201,160,176,9,72,132
40  DATA  63,96,233,64,76,249
50  DATA  253,76,240,253
60  FOR I = 768 TO 768 + 27
70  READ V: POKE I,V: NEXT I
80  POKE 54,0: POKE 55,3
90  CALL 1002
100 D$ = ""
110  PRINT : PRINT : INPUT "WHAT
     IS THE NEXT DISK NUMBER? ";Z
     $
120  PRINT D$;"PR#1"
125  PRINT : PRINT : PRINT
127  PRINT "DISK NUMBER ";Z$
130  PRINT D$;"CATALOG"
140  PRINT D$;"PR#0"
150  GOTO 110
```

Buck Buchanan, P.O. Box 1263, Miri, Sarawak, East Malaysia.

Bit Pit

Chas Andres



The BEST games are from Creative Computing Software

1978: Adventure
1979: Air Traffic Controller
1980: Super Invader
1981: Blister Ball and Mad Bomber

Blister Ball

Blister Ball is the first completely original arcade-type game for a computer. Not a copy, not an adaptation, not a spinoff. **Blister Ball** is new—it's a new idea—better than Invaders, better than Circus, better than Asteroids, better than Galaxian. If you've played other games for hours, you'll play **Blister Ball** for days.

How does it work? Well, some mean but fun-loving aliens have produced some bouncing bombs. First they drop one and you've got to position yourself under it and zap it with your laser. If you miss, that's OK. It will bounce around, although each bounce is lower, and you have several chances to zap it. Got the hang of it? OK, here come two bouncing bombs. You zap them. Then you're faced with three, then four and five.

As they bounce longer and longer the walls begin to close in so you're faced with either zapping the bombs or being hit. Each hit knocks you a little further toward the gutter. But you can survive two hits which is usually enough to zap all the bombs.

Feeling confident? Don't. Because after 5 bombs the murderous little devils drop 5 bonus bombs, worth ten times as much. These don't bounce, so you get only one shot. You need nerves of steel and the reflexes of a tail gunner.

After you complete one round, the game starts again with bombs that bounce faster and lower (and are worth more) than the previous ones.

Blister Ball is a fantastic solo game. But there are two-player options as well in which players can play as a team or as opponents. Each player can move the entire width of the screen and zap any of the bombs. Here, you're not only trying to survive, but trying to outscore your opponent. The game has two skill levels.

Mad Bomber

In **Mad Bomber** you are faced with aliens in a huge ship hovering overhead. They have bomb racks which they constantly fill with bombs. Your object is to move from side to side on the ground and zap the bombs in the bomb racks or as they fall.



As the game progresses, the aliens fill up their bomb racks more quickly and the bombs fall faster. You lose after ten bombs have hit the area which you are defending.

Mad Bomber can be played by one player solo or by two players as a team or as opponents. Two skill levels.

Order Today

Blister Ball and **Mad Bomber** are available together for $24.95 on disk (DOS 3.2) only and require a 48K Apple with paddle controls. (We recommend using the Super Paddles from Peripherals Plus).

To order send $24.95 plus $2.00 shipping and handling to the address below. Credit card customers should include card number and expiration date of Visa, MasterCard or American Express card. Credit card orders may also be called in to our toll-free number in the continental U.S.

If you also wish to order a set of Super Paddles from our Peripherals Plus subsidiary, the cost is just $39.95. The paddles are backed by a 90-day limited warranty from the manufacturer as well as Peripherals Plus' moneyback guarantee of satisfaction.

Blister Ball and **Mad Bomber** are colorful, challenging, fast and noisy. They are the games of the year from Sensational Software.

creative computing

39 E. Hanover Avenue
Morris Plains, NJ 07950
Toll-free **800-631-8112**
In NJ 201-540-0445

CIRCLE 350 ON READER SERVICE CARD

DIGITAL DIDACTICS

Donald T. Piele

It is not easy to find a good format for teaching problem solving with the computer. On the one hand if you simply supply a set of problems and provide no assistance, many students have trouble getting started and learn very little from their feeble attempts. And many of those who do manage to produce a running program write very poor programs and do not learn the new skills and techniques that you hoped the problem would develop.

At the other extreme, if you provide too much help, the exploratory activity, which is so vital for the development of problem solving skills, is lost. What is needed is a compromise strategy. Here is one such strategy that I am currently using in a class I teach each summer on computer problem solving skills held at the University of Wisconsin-Parkside.

The Strategy

All of the students in the class have at least an elementary knowledge of Basic. However, there are wide differences in their programming experience and sophistication. Consequently, I let the students progress through the lessons at their own rate. Each lesson consists of two parts:

Part I consists of a series of short programs that asks the question: "What does this program do?" It is the student's job to figure out an answer to this question. This should be tried first by reading through the statements of the program and following the algorithm manually using paper and pencil if necessary. If this proves too difficult, the program may be typed in and run. This is also the way that the students can confirm their answers. Part I provides the opportunity to see specific programming techniques and algorithms in action. For many students this may be the first time they have encountered these ideas.

Part II consists of a set of problems that can be solved efficiently using the concepts from Part I. This provides the all-important challenge of writing a complete solution to a given problem. Advanced students may go directly to Part II.

Donald T. Piele, Department of Mathematics, University of Wisconsin-Parkside, Kenosha, WI 53141.

The Format

It is a shame to go to all the effort to write a logically correct program and then discover that no one else can read it, and in a week or so, neither can the creator of the program. Thus, I begin each class by insisting that the work handed in conform to a minimum format. Students will be writing and reading programs on a regular basis and the class will run more smoothly if some standards are established early. Again, there are extremes that must be avoided if you want a set of rules to work. Here is what works for me.

1. Begin all programs as follows.

```
10 PRINT  " (Program Name and/or Number) "
20 PRINT  " (Your Name, Date Completed) "
30 PRINT
```

2. Use REMARK statements liberally. Keep them on the same line if you have the room.

```
10 C=C+1                    :REM C is the loop counter.
```

(PET and TRS-80 get by with one colon)

```
15 IF A=B THEN 200::::::::REM Branch on equalit/
```

(The Apple II requires multiple colons)

```
20 D=R*T                    'Distance = Rate X Time
```

(Microsoft Basic's alternative to REM)

3. Use indentation.

```
10 FOR I=1 TO 10
20:    FOR J=1 TO I
30:       PRINT I*J
40:    NEXT J
50 NEXT I
```

(PET and TRS-80)

```
10 FOR I=1 TO 10
20:::FOR J=1 TO I
30::::::PRINT I*J
40:::NEXT J
50 NEXT I
```

(Apple II)

Some Basics, including Microsoft Basic, indent without the use of colons.

4. Separate parts of the program for easy reading.

apple computer inc. ATARI

CALL US!
We will meet or beat any mail order prices, but they won't match our service!!

NEW NEC COMPUTERS NOW IN STOCK!

TEC

Daisy Wheel Printer $1,495

TAMPICO LABS, INC.

P.O. BOX 1000
Across from Ramada Inn
Destin, FL. 32541
CALL 904-243-8565

CIRCLE 218 ON READER SERVICE CARD

BYTES & PIECES

10644 Garden Grove Blvd., Suite 120, Garden Grove, CA 92643 (714) 963-0087

ALL ITEMS IN STOCK

HARDWARE	
APPLE	
Apple II 48K+	1,259.00
Disk Drive 3.3	283.00
Disk Drive w/Cards	307.00
ADVANCED EUR. TECH	
110 Key Pad Nexo	93.48
AMDEK	
Amdek 100 12 B & W	138.80
Low-Res 12" Color Mon.	283.30
12" Green Monitor	165.30
AMADEE 5801	1,398.15
CALIF COMP. SYS	
64K Ram Card	480.20
Mainframe Ram	341.85
Integrated System	1,755.00
Disk w/Cont CPM	291.85
Motherboard	51.00
Z-80 CPU	229.75
Asynchronous Ser. Interface	111.15
Synchronous Ser. Interface	111.15
Parallel Interface	86.85
Centronics Parallel	86.85
COMPUTER STATION	
CPU with per w/Camera	524.40
Dual Disk Drive Pkg Fam	1,179.00
EPSON Mx 80	539.00
Apple Parallel Interface w/Cable	62.86
DC HAYES	
Smartmodem 1	280.45
Smartmodem S-100	280.45
Hayseeds	218.90
HIGH TEC 1 Hr Juice	222.50
LAZER	
Lower Case Adapter	50.20
Hi Res Plus	86.00
M & R	
RF Modulator	20.55
RGB Color Video Card	298.50
MICRO SCI	
40 Disk Dr. w/o/Contr	370.60
40 Disk Dr. w/Contr	450.00
80 Disk Dr. w/o/Contr	570.00
80 Disk Dr. w/Contr	570.00
MICRO SOFT	
Z-80 Soft Card	298.00
16K Ram Card	144.50
MOUNTAIN COMP	
CPS Multi-Func. Card	185.00
Music System	431.50
Supertalker	240.00
NEC	
Green Screens	224.00
Green/Color	351.00
DAN PAYMAR	
Lower Case Adapter New	30.80
SANYO	
9" & 9" Cart for price Color 13"	427.50
SOLID STATE MUSIC	
SSM A10 Card	147.00
IOTT 488 Controller	405.00
STREET ELECT.	
Votrax Speech Synthesizer	180.00
GAME PADDLES	27.36

HARDWARE	
JOY STICK	
TRENDCOM	42.00
Parallel Interface	439.00
Standard Interface	80.00
Graphics Interface	80.00
VIDEX	
80 - Col Card	267.00
Keyboard	14.00
Keyboard Enhancer/New & Old	85.50
SOFTWARE	
CONTINENTAL	
Home Money Minder	24.00
CPA Gen. Ledger	171.00
CPA A/R	171.00
CPA A/P	171.00
CPA Pay	171.00
INNOVATIVE DESIGN	
Pool 1.5	24.00
MESA RES Invest Decisions	68.50
MICRO PRO	
Word Star	213.00
Mail Merge	114.00
Mail Merger	71.00
MICRO SOFT	
Typing Tutor	13.70
Adventure	20.60
Computer Decathlon	20.60
Typinger	130.40
PERSONAL SOFTWARE	
Zork	29.70
Visicalc 2.3	148.00
Visiplot	117.00
Visiterm	148.00
Visiplot	148.00
Visicomp	180.00
Desktop Plan II	148.00
DOS Tools Mgr	74.00
PROGRAMMA Word Processors	
Vitalc	103.00
Supertext	103.00
Vide	103.00
Smartgen	119.00
Double Vision	103.00
SOFTWARE SORCERY	
P.T.S.	38.00
P.T.S.	38.00
P.U.M.P.	25.00
SOUTHEASTERN Data Capture 4.0	42.00
SOUTHWESTERN	
Ask-U Express	52.00
Ask-U	52.00
STONEWARE D B Master	165.00
SUB LOGIC	
Flight Simulator	29.00
3D Graphics Pak	44.50
Graphics Pak	16.50
SYNERGISTIC	
Linguist	27.40
Mail List Database	34.00
Modifiable Database	54.00
Mail Merger	102.60
Modifiable Database II	102.60

Money Orders & Cert. Cks/immediate De Pas. Cks/allow 2 weeks. No C.O.D.'s Add 3% Frt & Hdl. Calif. add 6% Tax. All Mfg. warranties apply. All orders must include NAME, ADDRESS & PHONE. Prices subject to change

CIRCLE 125 ON READER SERVICE CARD

SOFTWARE STREET
PRESENTS

ATARI

SOFTWARE

ADVENTURE INTERNATIONAL	
All Scott Adams' Adventures (each)	15.95
ATARI	
Music Composer	48.96
Kingdom	12.71
Hangman	12.71
Energy Czar	12.71
Blackjack	12.71
Space Invaders	16.96
Basketball	33.96
Video Easel	33.96
Super Breakout	33.96
Computer Chess	33.96
3D Tic Tac Toe	33.96
Star Raiders	48.96
Scram	16.96
Asteroids	33.96
Missile Command	33.96
Mailing List	16.95
Mortgage & Loan Analysis	12.71
Bond Analysis	21.21
Stock Analysis	21.21
Stock Charting	21.21
Calculator	25.46
Financial Management System	60.00
Dow Jones Invest Eval.	79.95
Accounts Receivable System	399.00
General Accounting System	399.00
Inventory Control	399.00
Word Processor	129.95
All Talk & Teach Cassettes	25.95
Invitation To Prog 1,2,3 (each)	16.96
Touch Typing	21.21
Conv Span, Fren, German (each)	50.96
Statistics I	16.96
Educ. Sys. Master Cartridge	49.95
States & Capitols	12.71
European Countries & Caps	12.71
Graph It	16.96
Assembler/Editor	48.96
Telelink I	21.21
Microsoft BASIC	74.95
Pilot	74.95
CRYSTALWARE	
Pontasyland	49.95
House Of Usher	19.95
Galactic Quest	24.95
Sumer	16.95
World War II	25.95
Laser Wars	25.95
Sands Of Mars	35.95
Beneath The Pyramids	25.95
Little Crystal	35.95
Waterloo II	44.95
DYNACOMP	
Poker Party	15.95
Valdez	13.95
Flight Simulator	15.95
Monarch	10.95
Intruder Alert	14.95
Giant Slalom	12.95
Mail List 2 2	29.95
The Communicator	42.95
LJK Letter Perfect Word Processor	129.95
PDI	
Minicrossword	14.95
Code Breaker	14.95
Memory Builder	14.95
Bowling	14.95
Vocabulary I & II (each)	14.95
Number Series	14.95
Reading Comprehension	14.95
PreSchool IQ Builder I & II (ea)	14.95
Addition With Carrying	14.95
Quantitative Comparisons	15.95
PERSONAL SOFTWARE	
Microchess	17.95
Checker King	17.95
VisiCalc	169.95
QUALITY SOFTWARE	
Fast Gammon	16.96
Tari-Trek	10.16
Tank Trap	10.16
Disassembler	10.16
Assembler	21.21
3D Supergraphics	33.96
QS Forth	67.96

AND MUCH MORE!!

HARDWARE

ATARI 800 16K	747.00
ATARI 400 16K	338.00
ATARI 410 Recorder	65.00
ATARI 810 Disk Drive	429.00
ATARI 815 Dual Disk	1049.00
ATARI 820 Printer	360.00
ATARI 822 Printer	360.00
ATARI 825 Printer	599.00
ATARI 830 Modem	175.00
ATARI 850 Intf Mod	149.00
8K Ram	49.00
16K Ram	89.00
Paddles (pr)	17.00
Joystick (each)	9.00
Blank Diskettes (5)	22.50

CALL FOR CHRISTMAS SPECIALS !!!

FREE CATALOG AVAILABLE

SOFTWARE STREET
3392 Clipper Dr.
Chino, CA 91710
(714) 597-6959

ATARI IS A REGISTERED TRADEMARK

$2.00 minimum shipping
prices subject to change

CIRCLE 234 ON READER SERVICE CARD

```
10 PRINT "ADD THEN UP"
20  FOR I=1 TO 10
30    C=C+I
40  NEXT I
50:
60 PRINT "THE TOTAL IS ";C
70 END
```

5. Keep a neat record of all of your work. List your programs on 8 1/2" x 11" paper or cut them up and tape them to paper of this size. Hand in a listing and the desired sample runs. Of course, you are free to add your own ideas to make the programs more readable. This is only a minimum readability format.

The programs found in this series this month and hereafter will follow this format. Here is a sample lesson.

Digit Extraction

It is often necessary to be able to dissect a number digit-by-digit with the computer. For example, if you want to add up the digits of a number or compute how many digits are repeated in a given number, then you must be able to isolate each one.

Part I

Consider the following programs. Try to read through each program and understand what it does. Refer to a Basic reference manual if necessary. Then type in each program, run it, and confirm your answer.

```
 10 PRINT "DIGIT 1"
 20 PRINT "WHAT DOES THIS PROGRAM DO?"
 30 PRINT
 40    INPUT "ENTER A THREE DIGIT NUMBER ";X
 50        H=INT(X/100)
 60        Y=X-100*H
 70        T=INT(Y/10)
 80        U=Y-10*T
 90    PRINT H;"-";T;"-";U
100 END
```

Now that you know what Digit 1 does, try your hand with Digit 2.

```
 10 PRINT "DIGIT 2"
 20 PRINT "WHAT DOES THIS PROGRAM DO?"
 30 PRINT
 40   INPUT "ENTER A WHOLE NUMBER ";X
 50         D=D+1
 60         IF INT(X/10^D)>0 THEN 50
 70:
 80         FOR I=D-1 TO 0 STEP -1
 90              N=INT(X/10^D)
100              PRINT X;N
110              X=X-N*10^I
120          NEXT I
130 END
```

Try a variety of sizes of whole numbers, 123, 12345, etc. Can you explain why Digit 2 doesn't do what you expected?

```
 10 PRINT "DIGIT 3"
 20 PRINT "WHAT DOES THIS PROGRAM DO?"
 30 PRINT
 40   INPUT "ENTER A WHOLE NUMBER ";X
 50         D=D+1
 60         IF INT(X/10^D)>0 THEN 50
 70:
 80   DEF FNF(X)=X-INT(X)
 90         FOR I=D TO 1 STEP -1
100              N=INT(10*FNF(X/10^I))
110              PRINT N;" ";
120          NEXT I
130 END
```

Does Digit 3 do what you expected? Be sure to try large whole numbers. How can the program be modified to work correctly?

```
 10 PRINT "DIGIT 4"
 20 PRINT "WHAT DOES THIS PROGRAM DO?"
 30 PRINT
 40    INPUT "ENTER A WHOLE NUMBER ";X$
 50          N=LEN(X$)
 60          FOR I=1 TO N-1
 70              PRINT MID$(X$,I,1);"/   ";
 80          NEXT I
 90    PRINT RIGHT$(X$,1)
100 END
```

Would Digit 4 work with a 70 digit number or do you need to modify it?

There are two functions that come in very handy when working with digits that have been extracted from whole numbers. They are STR$( ) and its inverse VAL( ). STR$( ) takes a number, like 123, and transforms it into the word or string "123". VAR( ) goes in reverse and transforms the string "123" into the number 123:

STR$(123) = "123"

VAL("123")= 123

Thus, VAL(STR$(X)) = X and STR$(VAL(X$))=X$, where X is a number and X$ is a number string. Also STR$(1)+STR$(2)="12," STR$(1+2)="3", VAL("1"+"2")=12, and VAL("1")+VAL("2")=3.

Part II

The following programs can be solved by using the ideas presented in Part I. They vary in difficulty from easy to medium hard. The solutions will appear next month.

1. *Sum of Digits Squared*

Write a program that will accurately sum the squares of each digit in a given whole number. For example, the answer for 123 should be 14.

2. *The Digital Sum*

If the digits of a whole number larger than 9 are added together the result is a smaller whole number. If the sum is still larger than 9, then, when its digits are added together, the next number is also smaller. This process will continue to generate smaller and smaller sums until the number is less than or equal to 9. The final single digit number is called the Digital Sum.

Write a program that will accept a whole number up to 40 digits long and find its Digital Sum. The program should show all the intermediate steps. For example, the output for the number 123456789 should be:

```
123456789
45
9   THE DIGITAL SUM
```

3. *Armstrong Numbers*

An N-digit number is called an Armstrong Number if the sum of the Nth power of each digit is equal to the number itself. Note that 153 is a 3-digit Armstrong Number because

$1^3 + 5^3 + 3^3 = 153$.

Write a program that will find all N-digit Armstrong Numbers where N is supplied by the user. Test your program for n=2, 3, 4.

4. *Balanced Numbers*

We will define a number as Balanced if the maximum digit in the number is equal to half the sum of all the digits. For example, 123 is balanced because (1+2+3)/2=3.

Write a program that will find all of the Balanced Numbers from 1 to N where N is supplied by the user. Test your program for N= 200, and 1000.

5. *Palindromes*

A number is called a Palindrome if it reads the same backwards as forwards. For example, 121, 14641, and 234432 are all Palindromes. If a number is not a Palindrome, it can usually be made into one by a simple reversal and addition

process as follows. Reverse the digits of the number and add it to itself. If the result is not Palindromic then repeat the process again. For example, beginning with 75 we have:

```
    75
+   57
   132 which is not a Palindrome,
+  231
   363 which is a Palindrome.
```

The number 75 requires two reversals before it becomes a Palindrome. Write a program that will examine all three digit numbers and print out the numbers that require 0, 1, 2, 3, 4, 5-10, 11-25, and over 25 reversals before they become Palindromes—if ever.

Contest Solutions

Listed below are the solutions to the First International Computer Problems Solving Contest sponsored by the University of Wisconsin-Parkside. The solutions are written in Microsoft Basic and will run on a PET, TRS-80, Apple II, or other systems that use a version of Microsoft Basic. Occasional minor modifications will be needed. The problems appeared in this series last month. □

Junior Division

```
10 PRINT "JR PROBLEM #1 "
20 PRINT "PARKSIDE'S TRIANGLE"

30  INPUT "WHAT IS THE SIZE (1<= N <=20) "1N
40  IF INT(N)<>N THEN PRINT "INTEGER PLEASE " : GOTO 30
50  IF N<1 OR N>20 THEN PRINT "OUT OF BOUNDS ": GOTO 30

60  INPUT "WHAT IS THE SEED (1<= S <=9) "1S
70  IF INT(S)<>S THEN PRINT "INTEGER PLEASE ": GOTO 60
80  IF S<1 OR S>9 THEN PRINT "OUT OF BOUNDS ": GOTO 60

90      PRINT:PRINT "SIZE"1N1", SEED"1S

100     FOR R=1 TO N            'R=ROW NUMBER
110        FOR C=1 TO R         'C=COLUMN NUMBER
120           PRINT S1          'S=NUMBER TO BE PRINTED
130           S = S +1          'INCREMENT S
140            IF S>9 THEN S=1  'WRAP S AROUND
150        NEXT C
160        PRINT                        'END OF ROW
170     NEXT R

180     PRINT
190 END
```

```
JR PROBLEM #1
PARKSIDE'S TRIANGLE

SIZE 6 , SEED 1

 1
 2 3
 4 5 6
 7 8 9 1
 2 3 4 5 6
 7 8 9 1 2 3

JR PROBLEM #1
PARKSIDE'S TRIANGLE

SIZE 7 , SEED 9

 9
 1 2
 3 4 5
 6 7 8 9
 1 2 3 4 5
 6 7 8 9 1 2
 3 4 5 6 7 8 9
```


LISP

for

TRS-80 Models I & III

SuperSoft LISP allows the TRS-80 to become a complete Artificial Intelligence laboratory! It is the tool that takes you to the frontier of Computer Science.

The SuperSoft LISP is a *complete and full* implementation. (It is NOT a subset!) It contains an efficient garbage collector which optimizes the usage of user RAM, and supports the TRS-80 graphics. Below are some features:

- Runs in 16k level II (with only 6K overhead)
- Fully implements atom property list structure.
- PROG is supported.
- FUNARG device is implemented.
- Efficient garbage collection.
- Complete with LISP editor and trace.
- Allows complete range of single precision numeric data.
- Works with old as well as new ROMs.
- Contains 97 functions.
- Sample Programs.

The LISP package is supplied on tape or discette and with a complete user manual.

cassette version: $75.00
(requires 16K level II)

Disk version: $100.00
(requires 16K disk)

(manual only: $15.00)

All Orders and General Information:
SUPERSOFT ASSOCIATES
P.O. BOX 1628
CHAMPAIGN, IL 61820
(217) 359-2112
Technical Hot Line: (217) 359-2691
(answered only when technician is available)

CIRCLE 266 ON READER SERVICE CARD

SuperSoft
First in Software Technology

TRS-80 TRADEMARK TANDY CORP

CIRCLE 272 ON READER SERVICE CARD

New Software for

NorthStar

Users

EXPENSE PROFILE

- Find out where your money goes! Summarize expenses by use and user.
- Simplify tax preparation. Calculates tax deductibles for each family member separately. Easy JOINT vs SEPARATE RETURN comparisons.
- Mono Drives. Interactive input. Add new spending categories and spenders any time. Find records by searching for any part of line, eg: 'car'.
- Correct mistakes anytime. Change wrong date only, not the whole line.
- Records stored on disc. Limited only by disc capacity. Output to TV or printer. $29.95 ppd

DYNAMIC BUDGET

- Wonder if you can afford that new printer or boat or ?? Find out with DYNAMIC BUDGET!
- Easy input. Periodic items like salary and rent are entered only once, even if periods are in weeks, quarters, etc.
- Includes INFLATION and CALENDAR.
- Output to printer or TV. Monthly listings of expenses and income. Calculates running balance.
- Interactive. Change data anytime and get new results immediately.
- Data stored on disc. Makes keeping budget up to date easy. $29.95 ppd

The Software Connection
DEPT CC 10703 Meadowhill Rd.
Silver Spring, MD 20901

CIRCLE 266 ON READER SERVICE CARD

Happy Hands

Offers Discounts on All

TRS-80 (TM)

COMPUTERS

We Have What You Are Looking For

- ☐ PROMPT SHIPPING
- ☐ AVAILABLE SERVICE CONTRACTS
- ☐ DISCOUNTED PRICES COMPARABLE TO ANY OTHERS
- ☐ NO TAX ON OUT OF STATE SHIPMENTS

Call Collect For Prices
And Shipping Schedules

505-257-7865

or write

HAPPY HANDS
P.O. DRAWER I
RUIDOSO, NEW MEXICO
88345

CIRCLE 160 ON READER SERVICE CARD

How to Solve It, continued...

```
10 PRINT "JR PROBLEM #2"
20 PRINT "ROUND NUMBERS"

30      INPUT "ENTER A POSITIVE INTEGER "!N
40      IF N<>INT(N) OR N<1 THEN PRINT "TRY AGAIN" !:GOTO 30

50      FOR I=1 TO N
60         X=I                          'X = The present integer.
70         L=0                          'L = The length of the binary rep. of X.
80         R=0                          'R = The number of 1's in binary rep.

90         R=X-2*INT(X/2)+R             'Accumulate remainders after division by 2
100        L=L+1                        'Keep track of the binary length of X.
110        X=INT(X/2)                   'Divide the integer in half.
120      IF X>1 THEN 90                 'Continue dividing until all remainders
121                                     'have been found.

130      IF R < L/2 THEN C=C+1          'Test for roundness of X. C=counter
131                                      for round numbers.
140     NEXT I

150     PRINT "THERE ARE"!C! " ROUND NUMBER LESS THAN OR EQUAL TO"!N

160 END
```

```
JR PROBLEM #2
ROUND NUMBERS

THERE ARE 5  ROUND NUMBER LESS THAN OR EQUAL TO 10

JR PROBLEM #2
ROUND NUMBERS

THERE ARE 47  ROUND NUMBER LESS THAN OR EQUAL TO 100
```

```
10 PRINT "JR PROBLEM #3"
20 PRINT " NFL Helmets"

25   PRINT
30   DIM H(28)                          'Room for 28 helmets
40   H=0                                'H= Total number of unique helmets.
50   S=0                                'S= Money spent.

60   S=S+.25                            'Deposit a quarter.
70   R= INT(28*RND(1))+1                'Get Random Helmet.
80   IF H(R)=0 THEN H=H+1 : H(R)=1      'If it's new count it and remember it.

90   IF H<28 THEN 60                    'Continue until you have then all.

100     PRINT "TOTAL SPENT TO GET ALL 28 HELMETS = $"!S
105 PRINT
110 END
```

```
JR PROBLEM #3
 NFL Helmets

TOTAL SPENT TO GET ALL 28 HELMETS = $ 33

JR PROBLEM #3
 NFL Helmets

TOTAL SPENT TO GET ALL 28 HELMETS = $ 24.5

JR PROBLEM #3
 NFL Helmets

TOTAL SPENT TO GET ALL 28 HELMETS = $ 19
```

```
10 PRINT "JR PROBLEM #4"
20 PRINT "Letter Count"

30      DIM T$(80)                      'Leave room for each line of text.
35      DIM T(26)                       'Leaver room for counting letters.

40      READ T$                         'T$= one line of text.
50      IF T$="/END/" THEN 200          'If done reading then begin ordering.
```

```
60      FOR I=1 TO LEN(T$)
70         C$=MID$(T$,I,1)                    'C$=The I'th character in T$
80         IF C$<"A" OR C$>"Z" THEN 120       'Skip over non alpha characters.
90         C=ASC(C$)-64                       'Translate so that 1<=C<=26
100        T(C)=T(C)+1                        'T(C)= individual character total.
110        T=T+1                              'T= total number of characters.
120     NEXT I

130 GOTO 40                                   'Continue reading lines of text.

200 '            PRINT OUT THE CHARACTERS IN FREQUENCY ORDER

205 PRINT
210 PRINT "LETTER              FREQUENCY              PERCENTAGE"
215   MAX=0
220     FOR I=1 TO 26
230        IF T(I)>MAX THEN MAX =T(I) : C=I
240     NEXT I
250        IF MAX=0 THEN 300
260        PRINT CHR$(C+64);TAB(17);MAX;TAB(38);INT(10000*MAX/T)/100
270        T(C)=0
280     GOTO 215

300 PRINT "TOTAL";TAB(17);T
310 END

500 DATA "CONSIDER A PARAGRAPH CONTAINING SEVERAL LINES OF TEXT"
510 DATA "INFORMATION. YOU ARE TO WRITE A PROGRAM TO PRINT A LETTER"
520 DATA "FREQUENCY TABLE WHICH WILL LIST THE FREQUENCY AND PERCENTAGE"
530 DATA "OF OCCURRENCES OF EACH LETTER (A THROUGH Z) OF THE TEXT IN "
540 DATA "ORDER OF HIGHEST FREQUENCY FIRST."
550 DATA "/END/"
```

JR PROBLEM #4
Letter Count

LETTER	FREQUENCY	PERCENTAGE
E	29	13.3
R	22	10.09
T	22	10.09
A	16	7.33
O	16	7.33
N	15	6.88
I	14	6.42
C	11	5.04
F	10	4.58
H	10	4.58
L	9	4.12
S	7	3.21
G	6	2.75
U	6	2.75
P	5	2.29
Y	4	1.83
D	3	1.37
G	3	1.37
W	3	1.37
M	2	.91
X	2	.91
B	1	.45
V	1	.45
Z	1	.45
TOTAL	218	

```
10 PRINT "JR PROBLEM #5"
20 PRINT "Missionaries and Cannibals"

30      PRINT "      ISLAND","MAINLAND","STATUS"
32         M$="MMM" : C$="CCC"
35      PRINT
40      FOR MC=0 TO 3          'MC=Mainland cannibals.
50         IC = 3-MC           'IC=Island cannibals.
60           FOR MM=0 TO 3     'MM=Mainland missionaries.
70              IM=3-MM        'IM=Island missionaries.
80                N=N+1        'N = number of arrangements

90      PRINTING ROUTINE
100        PRINT STR$(N);":";TAB(5)!
110          PRINT RIGHT$(M$,IM);RIGHT$(C$,IC),
120          PRINT RIGHT$(M$,MM);RIGHT$(C$,MC),
150             IF IM<IC AND IM>0 THEN 180
160             IF MM<MC AND MM>0 THEN 180
170        PRINT "SAFE"!
180        PRINT

190     NEXT MM
200 NEXT MC
210 END
```


POLY PAKS

FREE!
1981 DISCOUNT ELECTRONICS CATALOG

JOIN THE PAK!

Send for our Free catalog and become a member of our exclusive Pak. Our members receive Poly Paks' exciting catalog several times a year. We offer: Penny Sales, Free Premiums and Low, Low Prices on a wide variety of Electronic Products such as Computer Peripherals, Integrated Circuits, Speakers, Audio Equipment, Rechargeable Batteries, Solar Products, Semiconductors, and much, much more! Take advantage of our 25 years as America's foremost Supplier of discount electronics.

Over 4.5 Million Satisfied Customers

RUSH ME YOUR FREE DISCOUNT CATALOG!
NAME: _____
ADDRESS: _____
CITY: _____
STATE: _____ ZIP: _____

CLIP AND MAIL COUPON TODAY TO:
POLY PAKS, INC.
P.O. BOX 942, CC11
S. LYNNFIELD, MA. 01940 (617) 245-3828

CIRCLE 296 ON READER SERVICE CARD

DISCOUNT

TRS-80™

TRS-80 MODEL III
48-K $2100 16-K $850
2 DISK RS-232 (ALL RADIO SHACK EQUIPMENT)

TRS-80 MODEL II
64-K $3350
TRS-80 8 4 MEGABYTE HARD DISKS (PRIMARY UNIT) $4040

TRS-80 COLOR 4-K $315 16-K $495 32-K $635

WE HAVE COLOR DISK DRIVES 0 — $509 1-2-3 — $339

FREE OUT-OF-STATE TAXES AND SHIPPING COSTS
WE ALSO CARRY A FULL LINE OF PRINTERS, COMPUTERS AND ACCESSORIES
WARRANTIES HONORED BY ALL COMPANY OWNED RADIO SHACK STORES OR COMPUTER CENTERS. T.M. TANDY CORP.

PERRY OIL & GAS INC.
DEALERSHIP R162 #137 NORTH MAIN ST., PERRY, MICHIGAN 48872

WE ACCEPT CERTIFIED CHECKS CASHIERS CHECKS AND MONEY ORDERS

PHONE (517) 625-4161, MICH.
FOR OUR PRICES, PLEASE CALL TOLL FREE
1-800-248-3823

CIRCLE 235 ON READER SERVICE CARD

LISP for the Apple II

Pegasys Systems' new P-LISP interpreter is a full implementation of the well-known Artificial Intelligence language. Written in machine code, this powerful interpreter includes the following features:

- Over 55 functions implemented
- Extensive 45-page User Manual
- Full function trace
- Floating point math and Hires graphics
- Function editor and pretty-printer
- Break mode for function debugging
- PROG construct, EXPRs, and FEXPRs
- ELIZA and other sample programs included

P-LISP is supplied on disk with User Manual for $99.95. The manual is available separately for $10.00. Please specify DOS 3.2 or 3.3.

PEGASYS SYSTEMS, INC.
4005 Chestnut Street
Philadelphia, PA 19104

PEGASYS

Orders only: 800-523-0725
PA residents and inquiries: (215) 387-1500

Pennsylvania residents add 6% sales tax
Apple is a trademark of Apple Computer Inc

Good software is no longer a myth.

CIRCLE 292 ON READER SERVICE CARD

Low-Cost Built-In Modem Card for Model 43 Teletype®



Only $195*.
*Single-Unit End User Price
OEM Quantity discounts available

Omnitec's Model 9143AD Modem Card installs simply and quickly to most Model 43 Teletype Terminals, converting them to a Full Communications terminal. This new Direct Connect, Auto-Answer Modem has all of the most desired features —

- **300 Baud Rate.**
- **Automatic Voice to Data Transfer.**
- **FCC Registered Connection to Switched Telephone Network.**
- **Automatic Disconnect in both Originate and Auto-Answer Modes.**
- **Bell 100 Series and 212A Low-Speed Compatibility.**

$195 TO ORDER CALL 800-528-8423
STAND ALONE UNIT AVAILABLE SOON!

OMNITEC DATA
New Dimensions in Modems
2405 South 20th Street • Phoenix, Arizona 85034

CIRCLE 265 ON READER SERVICE CARD

How to Solve It, continued...

```
JR PROBLEM #5
Missionaries and Cannibals

      ISLAND    MAINLAND        STATUS

 1.   MMMCCC                    SAFE
 2.   MMCCC     M
 3.   MCCC      MM
 4.   CCC       MMM             SAFE
 5.   MMMCC     C               SAFE
 6.   MMCC      MC              SAFE
 7.   MCC       MMC
 8.   CC        MMMC            SAFE
 9.   MMMC      CC              SAFE
10.   MMC       MCC
11.   MC        MMCC            SAFE
12.   C         MMMCC           SAFE
13.   MMM       CCC             SAFE
14.   MM        MCCC
15.   M         MMCCC
16.             MMMCCC          SAFE
```

Senior Division

```
10 PRINT "SR PROBLEM #1"
20 PRINT "PARKSIDE'S OTHER TRIANGLE"

30      INPUT " ENTER SIZE,SEED";N,S
40      IF N<1 OR N>20 OR S>9 OR S<>INT(S) THEN 30
50      PRINT:PRINT "SIZE ";N;",SEED ";S
60      PRINT

70      FOR R=1 TO N                    'R=ROW NUMBER
80        X=S+R-1                       'X=NUMBER TO BE PRINTED
90          FOR C=1 TO N                'C=COLUMN NUMBER
100       IF C<R THEN PRINT "   ";:GOTO 120
110           PRINT X;
120             X=X+C
130             IF X>9 THEN X=X-9
140           NEXT C
150         PRINT
160     NEXT R
170     PRINT
180 END
```

"First batch system I've seen with baled read out..."

```
SR PROBLEM #1
PARKSIDE'S OTHER TRIANGLE

SIZE  6 ,SEED  1

 1  2  4  7  2  7
    3  5  8  3  8
       6  9  4  9
          1  5  1
             6  2
                3


SR PROBLEM #1
PARKSIDE'S OTHER TRIANGLE

SIZE  7 ,SEED  9

 9  1  3  6  1  6  3
    2  4  7  2  7  4
       5  8  3  8  5
          9  4  9  6
             5  1  7
                2  8
                   9
```

```
10 PRINT "SR PROBLEM #2"
20 PRINT "DIGITAL PRODUCT"

30      PRINT
40      DIM A$(70),B$(70),C$(70)
50      INPUT "ENTER THE NUMBER ";C$
60      PRINT C$

70      A$="1"                          'SET A$ TO IDENTITY ELEMENT
80      FOR Y=1 TO LEN(C$)              'SCAN INPUT NUMBER
90         T=VAL(MID$(C$,Y,1))          'EVALUATE A DIGIT OF THIS NUMBER
100        IF T>0 THEN A=T:GOSUB 170    'IF NOT 0, MULTIPLY BY DIGIT
110         A$=B$                       'SWAP NUMBERS
120     NEXT Y                          'NEXT DIGIT
130     PRINT B$                        'PRINT NEXT DIGIT PRODUCT
140     IF LEN(B$)>1 THEN C$=B$:GOTO 70 'REPEAT UNTIL ROOT IS FOUND

150     PRINT:PRINT "THE DIGITAL PRODUCT ROOT IS ";B$
160 END

170 ' SUBROUTINE
180     B$="" : C=0                     'C=CARRY ,B$=DIGIT PRODUCT
190     FOR X=LEN(A$)TO 1 STEP -1       'STANDARD STRING MULT.
200        P=A+VAL(MID$(A$,X,1))
210        P=P+C : C=0
220          IF P>9 THEN P=P-10:C=C+1:GOTO 220
230           X$=RIGHT$(STR$(P),1)      'NOT NECESSARY ON APPLE II
240           B$=X$+B$
250     NEXT X
260           Y$=RIGHT$(STR$(C),1)      'NOT NECESSARY ON APPLE II
270           IF C>0 THEN B$=Y$+B$
280   RETURN
```

```
SR PROBLEM #2
DIGITAL PRODUCT

7
7

THE DIGITAL PRODUCT ROOT IS 7

SR PROBLEM #2
DIGITAL PRODUCT

100
1

THE DIGITAL PRODUCT ROOT IS 1
```

```
SR PROBLEM #2
DIGITAL PRODUCT

12345678
362880
2304
24
8

THE DIGITAL PRODUCT ROOT IS 8

SR PROBLEM #2
DIGITAL PRODUCT

999999999
3486784401
516096
1620
12
2

THE DIGITAL PRODUCT ROOT IS 2
```




Solve your disc problems, buy 100% surface tested Dysan diskettes. All orders shipped from stock, within 24 hours. Call toll FREE (800) 235-4137 for prices and information. Visa and Master Card accepted. All orders sent postage paid.

PACIFIC EXCHANGES
100 Foothill Blvd
San Luis Obispo, CA
93401 (In Cal. call
(805) 543-1037)

CIRCLE 169 ON READER SERVICE CARD

CONVENIENCE WHEN YOU WANT IT
SECURITY WHEN YOU NEED IT
AT A PRICE YOU CAN AFFORD

TRS-80 MODEL I & III

$59.95

90 Day Warranty

Assembled & Tested.

COMPUTER CONTROLLED REMOTE CONTROL
Now an inexpensive and direct carrier current interface between the TSR 80 and the BSR X 10 remote control modules. The **MICRO COMMANDER** X 10 modules and your computer can control your lights, appliances, motors, TV, stereo, heaters, alarms, fans, pumps, etc.

COMPUTER CONTROLLED SECURITY
Add a new dimension to your security system. Place your home under control of your computer real time clock while you are on vacation. Add an input port to your computer and eavesdrop losers. With switches on doors or windows your computer can welcome guests or frighten intruders.

EASY TO USE NO WIRES TO RUN
Total control of all X 10 modules. Utilize all 256 house and unit code combinations. Direct interface to AC power line. No command console to purchase. No sonic link. Plugs directly into TRS 80 cassette jack.

NEW PDRT C SOFTWARE INCLUDED ON TAPE
Real time C.O.N.T.R.O.L. software for all TRS 80 (Model I and III, Minimum Level II or III - 16K Tape, 32K Disk). Control your **MICRO COMMANDER** or output ports with respect to real time and/or input port triggers. Save schedules on tape or disk.

MICRO COMMANDER with **PDRT C** on cassette	$59.95
PDRT C on disk	10.00
BSR SYSTEM X 10 LAMP MODULE	14.49
APPLIANCE OR NEW WALL SWITCH MODULE	15.49
IL Res add 6% TAX ... COD O.K. — S. and H.	3.00

INTERFACE TECHNOLOGY
P.O.Box 383, Des Plaines, IL 60017
Phone (312) 297-2265

CIRCLE 192 ON READER SERVICE CARD

FREE

business software directory

- Radio Shack's Model-I, II, III.
- Heath's MBASIC and HDOS.
- CPM

Data base manager, integrated accounting package, inventory, word processing, and advanced mailing list.

Micro Architect Inc.
96 Dothan St.
Arlington, MA 02174

CIRCLE 197 ON READER SERVICE CARD

NEW! for the '89 from

MAGNOLIA MICROSYSTEMS

DOUBLE DENSITY DISK CONTROLLER

for both 5¼" & 8" drives only $595 complete including CP/M™2.2

MAGNOLIA MICROSYSTEMS, INC.
2812 Thorndyke W., Seattle 98199
(206) 285-7266 (800) 426-2841

CP/M is a trademark of Digital Research

CIRCLE 182 ON READER SERVICE CARD

TRS-80® 16K COLOR GAME LIMITED OFFER!

FREE WE'LL SEND YOU OUR BONUS GAME OF THE MONTH WHEN YOU SEND US A SELF ADDRESSED STAMPED ENVELOPE FOR OUR FREE COLOR PROGRAM LIST

16K COLOR HI-RESOLUTION GAMES**

STARBASE ATTACK $12.95

METEOR STORM $12.95

STAR SIEGE $12.95

HIGH SPEED ARCADE GAME

KOSMIC KAMIKAZE $18.95

JOYSTICKS REQ'D

*TRS-80 is a TM of Tandy Corp.

CERTIFIED CHECKS OR MONEY ORDERS ONLY

illustrated memory banks
P.O.BOX 289
WILLIAMSTOWN, MA. 01267-0289

EXPIRES 12-15-81 **CASSETTE

CIRCLE 166 ON READER SERVICE CARD

How to Solve It, continued...

```
10 PRINT "SR PROBLEM #3"
20 PRINT "BUG WALK"

30      INPUT "ENTER N,P ";N,P                  'N=SIZE, P=PROBABILITY
40      IF P<=0 OR P>=1 THEN 30
50       DIM A(2*N)                             'ARRAY TO SAVE VISITS
60         R=RND(1)                             'RANDOM NUMBER
70         IF R < P THEN X=X+1                  'MOVE TO THE RIGHT
80         IF R >=P THEN X=X-1                  'MOVE TO THE LEFT
90           A(X+N)=A(X+N)+1                    'SAVE THE VISIT
100        IF A(N)=10 THEN 1000                 'HOME HAS BEEN VISITED 10 TIMES
110        IF X=N THEN X=X-1 : GOTO 90          'BOUNCE OFF THE ENDS
120        IF X=-N THEN X=X+1: GOTO 90
130       GOTO 60

1000 ' PRINT OUT OF POSITIONS VISITED
1002  PRINT
1004  PRINT "N=";N; " P=";P
1005  PRINT "SQUARE","OCCURRENCES"
1007  PRINT
1010    MAX = 0
1020     FOR I=0 TO 2*N                         'SEARCH FOR LARGEST FREQ.
1030       IF A(I)>MAX THEN MAX = A(I) : C=I
1040     NEXT I

1050     IF MAX=0 THEN 2000
1060     PRINT C-N,A(C)                    'C IS THE POSITION OF LARGEST FREQ.
1070     A(C)=0
1080     GOTO 1010
2000 END
```

```
SR PROBLEM #3                          SR PROBLEM #3
BUG WALK                               BUG WALK

N= 5  P= .5                            N= 6  P= .666667
SQUARE        OCCURRENCES              SQUARE        OCCURRENCES

 4              18                       5              331
-1              14                       6              224
 3              13                       4              163
-2              12                       3               83
 5              12                       2               42
 2              11                       1               23
-4              10                       0               10
-3              10                      -1                2
 0              10
 1               8
-5               4
```

```
10 PRINT "SR PROBLEM #4"
20 PRINT "WORD COUNT"
25 PRINT

30      DIM B(12)                       'B( ) HOLD THE FREQUENCY
40      READ A$                         'READ A LINE
50      IF A$="/END/" THEN 130          'END OF TEXT
60      C=0                             'C=WORD LENGTH COUNTER
70         FOR Y=1 TO LEN(A$)           'COUNT THE LENGTH OF THE WORDS
80            A=ASC(MID$(A$,Y,1))
90            IF A<65 OR A>90 THEN B(C)=B(C)+1 :C=0 :GOTO 110
100           C=C+1
110        NEXT Y
120        GOTO 40                      'NEXT LINE

130 '   PRINT OUT THE FREQUENCY AND PERCENTAGE TABLE
140       PRINT "LENGTH","FREQUENCY","PERCENTAGE"
150         FOR I=1 TO 12 : T=T+B(I) : NEXT I   'T=TOTAL FREQ.
155         MAX=0
160            FOR I=1 TO 12
170              IF B(I)>MAX THEN MAX = B(I) : C=I
180            NEXT I
190             IF MAX=0 THEN 230
200                PRINT C,B(C),100*B(C)/T
210             B(C)=0
220         GOTO 155
230   PRINT "TOTAL",T
240 END

1000 ' ***  DATA ***
1010 DATA "CONSIDER A PARAGRAPH CONTAINING SEVERAL LINES OF TEXT "
1020 DATA "INFORMATION. YOU ARE TO WRITE A PROGRAM TO PRINT A WORD "
1030 DATA "LENOTH FREQUENCY TABLE. THIS TABLE SHOULD LIST THE WORD "
1040 DATA "LENGTH. FREQUENCY OF OCCURRENCES. AND PERCENTAGE. IN THREE "
1050 DATA "COLUMNS. IN ORDER OF HIGHEST FREQUENCY FIRST. "
1060 DATA "/END/"
```

```
SR PROBLEM #4
WORD COUNT

LENGTH          FREQUENCY       PERCENTAGE
 5                 8              18.6047
 2                 7              16.2791
 4                 5              11.6279
 3                 4               9.30233
 7                 4               9.30233
 9                 4               9.30233
 1                 3               6.97674
 6                 3               6.97674
 10                2               4.65116
 11                2               4.65116
 8                 1               2.32558
 TOTAL            43
```

```
10 PRINT "SR PROBLEM #5"
20 PRINT "SHUTTLE PUZZLE"

30      INPUT "ENTER N "1N
40      DIM A$(2*N+1),B$(2*N+1)                 'A$=GIVEN, B$=GOAL
50      A$="" : B$=""
50      FOR I=1 TO N
60          A$=A$+"O" : B$=B$+"1"
70      NEXT I
80          A$=A$+"X"+B$ : B$=B$+"X"+M1D$(A$,1,N)
90      PRINT: PRINT "N="1N

100     PRINT A$                                'A$=CURRENT STATE
110     GOSUB 1000                              'LOCATE THE X SPACE

120 '*** MOVE X TO LEFT ***
130     IF J=1 THEN 200                         'J=POSITION OF X
140     IF J=2 THEN 180
150   IF M1D$(A$,J-2,3)="01X" THEN M1D$(A$,J-2,3)="X10":PRINT A$:GOTO 110
155   IF M1D$(A$,J-2,3)="10X" THEN M1D$(A$,J-2,3)="1X0":PRINT A$:GOTO 110
180   IF M1D$(A$,J-1,3)="0X1" THEN M1D$(A$,J-1,3)="X01" :PRINT A$:GOTO 110

190     GOSUB 1000                              J=POSITION OF X

200 '*** MOVE X TO RIGHT ***
210     IF J=2*N+1 THEN 300                     'J AT RIGHT ALREADY
220     IF J=2*N    THEN 280
230   IF M1D$(A$,J,3)="X01" THEN M1D$(A$,J,3)="10X" : PRINT A$:GOTO 190
240   IF M1D$(A$,J,3)="X10" THEN M1D$(A$,J,3)="1X0" :PRINT A$:GOTO 190
280   IF M1D$(A$,J-1,3)="0X1" THEN M1D$(A$,J-1,3)="01X":PRINT A$:GOTO 190

290     IF A$=B$ THEN END                       'GOAL IS REACHED
300     GOTO 110

1000    SUBROUTINE TO FIND POSITION OF X
1010     FOR J=1 TO 2*N+1
1020       IF M1D$(A$,J,1)="X" THEN RETURN
1030     NEXT J
```

```
                                        SR PROBLEM #5
                                        SHUTTLE PUZZLE

                                        N= 4
                                        0000X1111
                                        000X01111
                                        00010X111
                                        0001001X11
                                        0001X1011
                                        00X101011
                                        0X0101011
                                        010X01011
                                        01010X011
                                        0101010X1
                                        01010101X
                                        010101X10
                                        0101X1010
                                        01X101010
                                        X10101010
                                        1X0101010
                                        11X010010
                                        111X01010
                                        1110X0010
                                        11110X000
                                        11110X0000
```

```
SR PROBLEM #5
SHUTTLE PUZZLE

N= 3
000X111
00X0111
0010X11
00101X1
001X101
0X10101
X010101
10X0101
1010X01
10101X0
101010X
1X10100
11X0100
1110X00
111X000
```


THE LEAST EXPENSIVE PROGRAMS YOU CAN BUY.

Up to 77 high-quality programs for TRS-80, only $10.95

NewDOS-80—New Low Price!
Successor to NewDOS+, same package for which you pay $149 elsewhere, at CIE just... **$111**

SuperPIMS—People's Database
PIMS has been greatly speeded up and simplified, with machine-language sorts, key debounce, optional automatic lowercase (no keying, no hardware mod) on labels or reports. Up to 20 fields, limited by 240-character maximum per record. Easy to revise, add records, split or merge files, sum or average any fields. Customized for tape, tape & disk, Zoom, TCE Poor Man's Floppy, BIT, Stringy Floppy—all on one tape! As mailing labels program, easily manages 20,000 list. CIE does' Advanced labels module to come, $24.95, making system most powerful mailer available! on disk, $25.95
program (CIE) **$19.95** ($21.15 CA)
book, details uses (CIE) $11.95 ($12.67 CA)

PASPATCH
PasPatch, Tape 6P, makes Tandy tiny Pascal a powerful disk system!
Modular Software Assoc **$19.95**

Level II Tapes
'Tiny' Pascal runs on any 16K Level II system, includes the programming structuring capabilities of full Pascal, but not data structuring

Able to compile 2.5 machine code, programs run about 5X faster than Level II Basic—graphics run eight times faster! Requires use of T-Bug (or Tape 7) and ETASM.
Tape 3, People's Pascal $19.95

Tape 1, 34 buis, edu, game progs	$10.95
Tape 2, 77 programs from Osborne book Common Basic Programs	Same $10.95
Tape 5, 24 buis, edu, game progs	$10.95
Tape 7, 31 buis, edu, game progs	$10.95
Tape 9, 40, inc 4X tape speedup	$10.95
Tape 9, 25 buis, edu, game progs	$10.95
Tape 10, income tax, checkg act	$10.95
People's Tasman, fills-out all forms	$39.95

Send for free monthly bulletin and price list.

NewDOS-80 (Model I or 3?)	$111
DOS-plus (Model I or 3?)	$100
Percom Doubler	$165
LNW dbl. density, DOS-plus	$175
DoubleZAP-II/80 patch	$47.45
PMC-80 16k computer	$610
PMC-80 expansion (S-100)	$380
32k S-100 RAM card	$270
Percom 40-track drive	$375
Epson MX-80 printer	$525
Centronics 737 printer	$850
Starwriter 25cps daisywheel	$1,610
Anadex DP9500 200cps	$1,525
EPROM programmer	$610
ROM extender	$57
ANALOG input module	$61
Fastload hi-speed cassette	$147
CTR-41M cassette deck	$90
5" Memorex sing den bx 10	$27.50
5" Memorex dd bx 10	$29.50
5" FD or 3M cleaning kit	$25.50

Add $1 shipping per order, plus 50 cents per media box or kit. Major items shipped freight collect. Small items & books, software shipped postpaid.

NEW: Send for free monthly catalog
10% DISCOUNT
when ordering 3 items totaling $50 or more

All orders charge card, check or m.o.
Calif residents add 6 pct tax. Dealer inq. invited
Overseas, add $1.50 per tape postage

COMPUTER INFORMATION EXCHANGE
Box 159
San Luis Rey CA 92068

CIRCLE 122 ON READER SERVICE CARD

Endangered Species

Thirty-six different issues and not one has yet learned to breed in captivity. Their days in our warehouse are limited. Could you provide a good home for a magazine? In exchange, you're assured hours of reading pleasure. And, before they disappear, find the missing link in your own collection.

The applications, programming techniques, simulations, problems, commentary, articles and fiction are practically timeless. Not only that, but the earlier issues are actually increasing in value.

Prices are $2.50 each for all issues after March 1980, $2.00 each for all other issues, $5.00 for three, $15 for ten. Postage is $1.00 for up to 3 issues, $2.00 for 4 or more. Best bet is the **Super Special**: One of everything we have—36 magazines in all—for only $50 post paid.

creative computing

Vol. 3, No. 4—July/Aug 1977

Four Dynamic Games: Eliza (in Basic!), Bocce, Backgammon and UFO. First Part of Dwyer's "8-Hour Course in Basic." Writing Your Own CAI: "Structuring the Lesson to the student." Interview with Lee Felsenstein, Designer of the SOL (and several machines since!). Computers in Medicine and Health Care. Evaluations: Spacewar and TREK 80, "Sherlock Holmes and Charles Babbage."

Vol. 4, No. 4—Jul/Aug 1978

Features on Business Computing and Word Processing: Special Section on Interfacing Your Computer to the Outside World: Three Perspectives on Video Games: ROM Section: High Resolution Graphics for Apple II: GAMMON and EVILK Motor Cycle Jump Game Programs. Evaluations: Pet: Apple II: Atari Video Pinball: Atari Video Computer.

Vol. 3, No. 5—Sept/Oct 1977

Dynamic Debugging System for 8080 Assembly Language: Bibliography of "Limits to Growth" Models: Dwyer: 8 Hour Course in Basic—Part 2: Programming Approaches to Solving Complex Equations: Computerized Conferencing. Symmetric Art on your Computer. Games: Nomad, Rotate, Lissajous. Evaluations: 5 Microcomputer Basics: Software Technology Music System.

Vol. 4, No. 5—Sept/Oct 1978

Educational Features: 4 Simulation Articles: Accounts Receivable Systems: Real World Games: A Real-Time Clock You Can Build: All about PASCAL: Intelligent Videodiscs: 40 Programming Ideas: ROM Section: Hex and Star War Games. Evaluations: Exidy Sorcerer: Radio Shack TRS-80: Bally Arcade: Speak & spell and Spelling B: Computalker Speech Synthesizer: Peninsula Pet Cassettes. Merlin Video Interface.

Vol. 3, No. 6—Nov/Dec 1977

Programming Techniques: File Structures: CAI: Multiple Problem Types: Computer History. Quiz: Final Exams by Computer: Dwyer: 8 Hour Course in Basic—Part 3: Mastermind II, Othello, and Inorganic Chemistry Programs. Evaluations: Nine Microcomputer-based Toys. Comp IV: S-100 Compatible Kits. IDL Xitan, and three 8080 8K Basics.

Vol. 4, No. 6—Nov/Dec 1978

Consumer Computers Buying Guide: Critical Path Analysis: Experiment in Teaching Strategic Thinking: ROM Section. Subject Index and File Index in Basic. Programs for Mail Lists, Patterns, Plotting, Corral, Joust, Puzzle, and a Christmas Letter. Evaluations: CP/M Disk Operating System: North Star Horizon: Backgammon Computers: Smart Electronic Games and Video Games.

Vol. 4, No. 1—Jan/Feb 1978

Fast Sorting Algorithm: How to Write a Computer Simulation: More File Structures: LOGO: Murphy's Laws: Dwyer: 8 Hour Course in Basic—Part 4. Programs for World Population Model, Biorhythms in Basic and APL, Yahtzee, Van Gam, Kirkof, and Network. Evaluations: 3 Electronic Games: Radio Shack TRS-80: Heath H8 System.

Vol. 5, No. 1/January 1979

Computers and Robots in Fiction: Guidance Counselor System: Surveys of Educator's Attitudes: How to Hide Your Basic Program. A Program to Calculate Depreciation for Taxes, and the Space Maze Game. Counterfeit Cursor and Speed Reading for the Pet. Evaluations: Microsoft Fortran 80: Structured Programming with Tiny c: Smoke Signal's Text Editor: Exidy Sorcerer: Ohio Scientific Superboard II.

Vol. 5, No. 2—February 1979

Multiple Regression Analysis Simplified: Budget Management: Sports Predictions: PEEKing and POKEing for Video Displays: Interview with Michael Shrayer: Computers and Education—Questions of Value: Game Programs for Gold Mine and Atom 20. Evaluations: Heathkit H-8: Thinker Toys Floppy Disk: Electric Pencil: Western Digital Pascal Chip Set: Four Computer Music Records.

Vol. 5, No. 3—March 1979

Six Articles on Data Base Management: Sports Judging on a Microcomputer: Shopping for a Payroll System: Programming the Game of Go: Business Computing with the Sorcerer: Social Science Survey Program. Evaluations: Terrapin Turtle: Videobrain: Pet Monitor: TRS-80. Floppy Disk: Apple Floppy Disk.

Vol. 5, No. 4—April 1979

Safeguarding Your Computer: Interpretive Programming: Elements of a Good Computer Game: Music Composition: Marin Computer Center Programs for An Intelligent Calendar, Vertical Graphs and Bar Graphs, Flowers for the PET. Evaluations: Checker Challenger: Video Checkers, Checkbook Maintenance System: Whatsit Data Base Management Program.

Vol. 5, No. 5—May 1979

Word Processing Systems: Pilot Tutorial: Writing User-Oriented Programs: Amortization Schedules, Reading and Comprehension Exams: Hiding Your Basic Program: Cribbage and Mille Bornes Game Programs. Evaluations: WP Daisy Word Processing: Word master Text Editor: PDI IQ Builder: Malibu 160 Line Printer

Vol. 5, No. 6—June 1979

Eight Articles on Computer Graphics and Plotting: Using Basic Strings: Microcomputers in the Hospital: Billing Program for the Sorcerer, Inkblot and Greed Game Programs. Evaluations: TRS-80 Voice Synthesizer, HIPLOT Digital Plotter: Structured Systems. Name and Address Program. ALF Apple Music Synthesizer.

Vol. 5, No. 7—July 1979

Four features on Sorting, Files and Data Bases: Creativity Test: World Power Systems: Personal Finance Model: Two Ecological Simulations: Programs for an Ecological Game Niche, Brain Teaser, and Zone X. Evaluations: BrighterWriter, SWTPC CT-82 Graphics Terminal: API PeCo One Heuristic Speechlab: Micro Pro Super Sort: Diagnostic Programs for the Pet.

Vol. 5, No. 8—August 1979

Can Computers Think? 5 Basic Language Programming Techniques: The Law and Your Computer, muMath, Image Processing, Manipulating Pencil Files: Adventure, a new type of computer game simulation. The Games HYOLT and FORT. Evaluations: Texas Instruments 99/4, Radio Shack TRS-80 Model II, SWTPC PR-40 for the Pet, IMSAI VIO.

Vol. 5, No. 11—November 1979

Adventure: Complete Listing in Basic. Controlling Household Devices: Car Pooling: Mumps Language: Computer Art Exhibition: Build Your Own Joysticks: Telephone Dialer for TRS-80 or Northstar: Teacher-Made Tests: Evaluations: Comparison Chart of 6 Popular Personal Computers: Comparison of 26 Single Board Computers: Electronic Games & Toys: Quick Printer II: Interact Computer: User-Definable Character Generators: TRS-80 Level III Basic: Pet Software from Creative Software: Word Processor: Introl X-10 Home Control System.

Vol. 5, No. 12—December 1979

Controlling Household Devices: Part 2: LOGO: Computerized Biofeedback: Computers at the Rodeo: Creating Digitized Video Images: Programs for using the Microcomputer as an Investment Tool: Animation on the Apple: Magic Tricks: "Turn-Key" CP/M System. Evaluations: More Electronics Games: Language Translators: APF MP1000 Video Game System: 6 Word Processing Printers: Satellite Tracking Software: SysKit for the 8080: Assemblers: CP/M vs. TSC: Statistics for the TRS-80.

Vol. 6, No. 1—January 1980

Interviews with Donald E. Knuth and William Wulf: Six Features on Artificial Intelligence: Air Traffic Controller: Computerized Resume: GROW: A Program that Learns: Evaluations: Six Basics: NEWDOS and TRSDOS: Auto Scribe: Micro Music.

Vol. 6, No. 2—February 1980

Six Articles on Investment Analysis: David Levy: Intelligent Computer Games: Programs: Genealogy: Graphing: Genetics: Evaluations: Word Star vs Electric Pencil: Pascal for the TRS-80: Micro Composer: Data Dubber: Sorcerer Word Processing Pac: Trivia Contest Results.

Vol. 6, No. 3—March 1980

Networks for Personal Computers: Artificial Intelligence: How to Make a Basic Tree: Interview with Joel Birnbaum: Three Mile Island Game: Extended Precision Computation: 'Rolodex' Data Base Program: Photographing Your Computer System. Evaluations: TI 99/4: Modems: Cobol: Tinyc: 10 Software Packages.

Vol. 6, No. 4—April 1980

Dr. KiloBYTE's Creative Popular Personal Recreational Micro Computer Data Interface World Journal—the Famous 73 page April Fool parady: 8 Articles on Reading and Language: Interview with Gordon Bell: Evaluations: Heath WH-89: Atari 800 vs PET: Chatworth Mark Sense Card Reader: Adventure.

Vol. 6, No. 5—May 1980

Seven Features on Saving Money with your Computer: Analysis of Stock Options: Budgeting Model: Shopping Lists: Home Inventory: Home Purchase: Retirement Planning: Computer-Aided Model Rocket Design: Two Natural Language Systems: Evaluations: PET 2022 Line Printer: APF Imagination Machine: Personal Software's Desktop Plan: Universal Data Entry System.

Vol. 6, No. 6—June 1980

Fourteen Graphics Articles: Polar Plots: 3D Graphics: Animation: Graphic Mazes: Motion Simulation: Inside Space Invaders: 7 Music Articles: Digital Audio: Computer-Aided Sight Reading: Design of a Synthesizer: Digital Enhancement of Old Recordings: Comparison of Printers: Evaluations: The Atari Machine: Neelco's Music Box for the PET: HeathKit-Thomas Electronic Organ Kit.

Vol. 6, No. 7—July 1980

Four Articles on Adventure Games: Dragon, Dungeon: How to Fit a Large Program into a Small Machine: How to Write an Adventure: 6 Simulation Features: Genetics: Electric Management: Medical: Ecological: Sports: Self-Reproducing Programs: Man-Machine Dialogs: Selecting a Computer Dealer: Evaluations: Super-Text vs. Easy Writer: Mountain Hardware ROM PLUS+: Toolkit for the Pet: Chart Comparing Basics of 8 Popular Computers.

Vol. 6, No. 8—August 1980

Games Features: Computer Bismarck: Knight's Tour: Guess My Animal: Turnablock Game: Fifteen and Hot: Mind Exerciser: Marketing Your Own Program: Computer Graphic Designs: Robotics Conference: Insertion Sort: Stocks and Listed Options: Evaluations: Magic Wand: VisiCalc: Beta-80: Asteroids in Space.

Vol. 6, No. 9—September 1980

Twenty Educational Applications and Features: Language Arts: CAI Development: Grading Program: Computers in the Classroom: Asimov: Point of View: How to Heapsort: New Consumer Electronic Products: TRS-80 Shopping List for Schools: Evaluations: Milliken Math Sequences: Exatron Strings Floppy: EDS Videotape Series: 'Little Computers: See How They Run': 8 Apple II Software Packages: Educational Packages.

Vol. 6, No. 10—October 1980

Symposium on Actor Languages and Smalltalk: Linked Merge Sort: How to Solve It: 9 New Applications and Games: Election Prediction: The Presidential Campaign: Computer Division Evaluations: OSI C2-4P Computer: TRS-80 Voshex: Two Text Editors: Five Music Systems: 15 Software Packages: BASEX.

Vol. 6, No. 11—November 1980

Actor Languages and Smalltalk—Part 2: Effective Documentation: Bomb-proof Data Entry: Interactive Systems and Virtuality: Fast Sorting: Controlled Input in Basic: Loosening Packed Basic: Future of Small Business Computing: Planning Your Diet: Evaluations: Electronic Games: Computer Ambush: TR Copy.

Vol. 6, No. 12—December 1980

A Comparison of Basic Systems: Busing Guides to Personal Computers and Electronic Toys and Games: Legal Protection of Computer Programs: Nuclear Power Plant Simulation: Superman Game: Logic Problem Solver: Interview with the inventor of the ZX80: Clive Sinclair: Alvin Toffler: The Electronic Cottage: Evaluations: Sinclair ZX80: Atari: Apple Pascal: CBM2022 Smart Printer: Pearl, Apple II and Apple II Plus: Pet: TRS-80.

Vol. 7, No. 1—January 1981

Graphics and Animation: Printing Without Quotes: Apple Lo-Res Shape Tables: Sorcerer Hi and Lo-Res Graphics: Spirograph: TRS-80 Color Computer: New PETs: Intelligent Videodiscs: A Library of Sound: Dithering: Educational Software and Books: Music Synthesizers: Graphics Hardware: Atari Music Composer.

Vol. 7, No. 2— Febuary 1981

Comparison of Music Editors: Artificial Intelligence: Are Computers Alive?: Genetics Simulation for the Pascal: National Programming Contest: Monster Combat: Introduction to Computer Control.

Vol. 7, No. 3— March 1981

Education: MECC In-Depth: Selecting a Computer: CAI: Prize-Winning Simulation: Commercial Software Evaluations: Fantasy Games: Show and Spell: Cutting Your Taxes: PET Word Processor: Space Invaders Championship: Microcomputers and Hyperactive Children: Realistic Simulations: 25 New Products.

Vol. 7, No. 4—April 1981

Networks and Telecommunication: Home Banking: Osborne I: ABM: New Horizons for the Apple: Column Board Comparison: Computerized Writer: Space Games: Small Computers in Big Business.

Vol. 7, No. 5—May 1981

Buyer's Guide to Small Business Computers: Bomb-proof Data Entry: Personal Finance: Home Accounting: Programs for the Investor: Financial Programming: Language: Short-Range Forecasting: Fuel Economy Comparison Program: Music Synthesis Past and Future.

Vol. 7, No. 6—June 1981

Graphics and Animation: Interview With Leo Christopherson: Alien: OSI: Computers of Hollywood: Colored Tapestries: Computer Warfare: Digital Music Synthesis: Hi-Res Graphics for the TRS-80: Fantasy Games Old and New: Funny Numbers: Spiderman.

e cart...apple cart...apple c

Chuck Carpenter

Correspondence is always welcome and a response will be made to those accompanied by a SASE. Send your letters to: Chuck Carpenter, 2228 Montclair Pl., Carrollton, TX 75006.

Since there are many newcomers to the world of Apple II, in this month's column I will share some thoughts about getting started with an Apple. Also, as I mentioned in the July '81 column, the mini-assembler will be discussed.

Getting Started

The Apple II is one of the most versatile of all personal computers. The reasons for this versatility are many:

• Ease of expansion. Sockets for RAM (Random Access-Read/Write Memory) are built-in—so are the sockets for up to seven peripherals. There is a socket for language expansion too.

• Capacity for up to 14 disk drives. If you only want to store data you can use all seven peripheral slots for disk drives.

• Color graphics. You can choose lo-res in 16 colors or hi-res in seven colors. The commands to manipulate graphics are built into the programming languages.

• Programmable sound. Music synthesis and special effects are possible. Out of one little speaker you can produce the sounds of space war or symphonies (with a little imagination).

• Game paddle I/O. This is more than just a game paddle connector. You can program three inputs for such things as sensing switches. There are four output bits that can be turned on and off under program control. A program is included in Listing 1 to let you drive a printer from one of these bits. Four analog inputs are available for game paddle controls. These inputs can be used for measuring any low speed device. Or, you can use them to make temperature measurement.

• Power supply. To power all of these things there is a high-quality switching power supply. This supply, of modern design technology, will provide all the power needed to run a fully loaded Apple II. There is no need to buy another supply for most of the available add-ons.

• Languages. The standard machine (Apple II Plus) comes with Applesoft Basic in ROM (Random Access—Read Only Memory). The language is always there when you turn the machine on. You can get the very fast Apple Integer Basic too. If you want UCSD Pascal or a version of Fortran 77, these are also available. The Apple Language System supports both of these languages.

With all this flexibility, it is no wonder that so many software packages and peripherals are available for the Apple II.

Software

Software packages are available to cover most any requirement. Apple supplies several, but many, many more are available from independent sources. There is so much software, in fact, that space is not available here to list it.

One way to see some of the software packages is to visit several computer stores. Visit as many as possible because none of them carry exactly the same ones. For those of you that have to shop by mail, the ads in magazines will be helpful. Another source of software information is catalogs. One such catalog is *The Apple Software Directory* from WIDL Video, 5245 West Diversity, Chicago, IL 60639, (312) 622-9606.

Once you find some interesting software, how do you know it's any good? If you buy at a store, ask to try it. If you buy by mail, you can't do that, but most reputable companies exchange defective software.

Reviews are a good source of information. Many magazines, such as *Creative Computing*, have regular reviews of Apple software. One magazine is devoted to Apple software reviews; it is called *Peelings II*, and you can get a subscription for $15 per year by writing to POB 188, Las Cruces, NM 88004. Or, you can phone (505) 526-8364. Some back issues are available.

Hardware

Hardware accessories range from disk drives to modems for communications to printers that permanently capture the electronic word. Each requires some type of interface between the computer and the peripheral device. Again, a search through the magazines will turn-up most of the possibilities.

Disk drive controllers are the usual first hardware option. The Apple II uses its own special controller. By doing this, Apple was able to use their own format and get more data on a diskette than most other systems. The disk drives are modified Shugart SA400s. I believe they are called an SA385 since they are stripped-down somewhat. You can't use the SA400, in any event. The Apple disk system puts 143K bytes on a single sided diskette. Most other systems only allow about 80 to 90K bytes. Several companies are now making more storage capacity available.

One company, Sorento Valley Associates (SVA), makes an Apple compatible controller that lets you use 8" drives. The capacity of a standard 8" disk is 250K

5 Ways To
PASCAL POWER
FOR YOUR APPLE PASCAL™ SYSTEM

Sales Info . . . (213)453-1851

1 LinkVideo™

REDUCE SCREEN I/O PROGRAMMING 90%

- creates terminal independent programs
- safeguards programs from user error
- validates, filters and prompts input
- gives programs that professional look
- includes source and P-code
- simplifies screen handling

$54.95

2 LinkSampler™ I

LEARN PASCAL THE ACTIVE WAY

- 21 teaching programs
- games and personal finance
- 68 page easy reading manual
- Pascal techniques illustrated

$59.95

3 LinkDisk™

GET FOUR FUNCTION DISK CONTROL

- converts Dos 3.3 text/binary to Pascal
- guarantees correct readable copies
- examines disks in ASCII, HEX or mixed
- changes individual nibbles
- sophisticated screen-oriented editor
- selective print-out of text files

$69.95

4 NEW DataLink™

COMMUNICATE LIKE MAINFRAMES

- accurate transmission up to 4800 baud
- automatic error-checking and retry
- single key control of entire session
- on-line print control
- sends 128 ASCII characters from Apple
- saves communications dialogue

$99.95

5 NEW LinkIndex™

USE THE FASTEST KEY RETRIEVAL SYSTEM

- sophisticated B-tree indexing method
- faster than ISAM
- mathmatically optimized
- maintains sorted order
- supports duplicate keys
- easy to use Pascal unit

$150.00

☐ Please send more information
☐ I am a Dealer

Company_____
Name_____
Address_____
City_____
State_____ Zip_____

LINKO SYSTEMS™ CORP.
1655 26th St., Santa Monica, CA 90404

CIRCLE 274 ON READER SERVICE CARD

PRICE BREAKTHROUGH
16K RAM BOARDS FOR APPLE JUST $129.95

HAVE YOU BEEN WAITING FOR THE COST OF EXPANSION BOARDS TO COME DOWN? YOUR WAIT IS OVER. UP UNTIL NOW RAM EXPANSION HAS COST AS MUCH AS $195.00. NOW **OMEGA MICROWARE** IS PROUD TO ANNOUNCE THE ARRIVAL OF A TRULY AFFORDABLE EXPANSION CARD.

NOW YOU CAN RUN **PASCAL, FORTRAN, 56K CPM** WITH A **Z80, SOFTCARD, INTEGER BASIC, APPLESOFT AND OTHER LANGUAGES** ON YOUR **APPLE**. NOW YOU CAN **INCREASE USUABLE MEMORY** FOR **VISICALC**. NOW YOU DON'T HAVE TO PAY A FORTUNE TO HAVE ALL THIS.

AT $129.95, **OMEGAS RAMEX 16** IS THE LOWEST PRICED CARD AVAILABLE TODAY.

WHAT DO YOU GIVE UP WHEN YOU PURCHASE THIS FIRST REALLY AFFORDABLE **RAM** EXPANSION CARD? WELL, YOU GIVE UP HAVING TO REMOVE ONE RAM CHIP FROM THE MOTHERBOARD OF YOUR **APPLE**. YOU GIVE UP HAVING TO STRAP A CABLE FROM THE CARD TO YOUR MOTHER BOARD. THAT'S IT. WHAT YOU GET IS A SIMPLE, RELIABLE, BOARD THAT JUST PLUGS IN. MEMORY REFRESH IS ACCOMPLISHED ON THE BOARD ITSELF.

THE **RAMEX 16** IS GUARANTEED NOT JUST FOR 90 DAYS, NOT EVEN 6 MONTHS, OUR **WARRANTY** IS FOR **ONE FULL YEAR** FROM DATE OF PURCHASE. WE WILL REPAIR OR REPLACE ANY BOARD THAT IS DEFECTIVE THROUGH MANUFACTURE FOR A PERIOD OF ONE YEAR AFTER PURCHASE PROVIDED THIS DAMAGE IS NOT USER INFLICTED.

ORDER YOUR **RAMEX 16** NOW BY CALLING **TOLL FREE** 1-800-835-2246. **KANSAS RESIDENTS CALL** 1-800-362-2421. MASTERCARD OR VISA ACCEPTED OR SEND $129.95. ILLINOIS RESIDENTS ADD $7.80 SALES TAX.

ANOTHER QUALITY PRODUCT FROM
OMEGA MICROWARE, INC.
FORMERLY OMEGA SOFTWARE PRODUCTS, INC.
222 SO. RIVERSIDE PLAZA
CHICAGO, IL 60606
PHONE 312-648-1944

©**OMEGA MICROWARE, INC.**

APPLE AND APPLESOFT ARE REGISTERED TRADEMARKS OF APPLE COMPUTER INC. PASCAL IS A REGISTERED TRADEMARK OF THE REGENTS OF THE UNIV. OF CA. SAN DIEGO. VISICALC IS A REGISTERED TRADEMARK OF PERSONAL SOFTWARE. CPM IS A REGISTERED TRADEMARK OF DIGITAL RESEARCH INC. Z80 IS A REGISTERED TRADMARK OF ZILOG INC. SOFTCARD IS A REGISTERED TRADMARK OF MICROSOFT

CIRCLE 202 ON READER SERVICE CARD

Why would anyone spend $59.95 for a joystick?

Super Joystick

Star Wars. Played with paddles, it's difficult at best and frustrating at worst. But with a joystick it becomes an entirely new experience. It's still challenging. It's also fun. And very addictive.

Have you ever used a drawing program in which one paddle controls the horizontal movement of the "brush" and the other paddle the vertical? It's slow, tedious work. But with a joystick, drawing is an absolute joy.

Exceptional Precision

The Apple high-resolution screen is divided into a matrix of 160 by 280 pixels. To do precise work on this screen, you need a precise device. Most potentiometers used in paddle controls are not quite linear. If you rotate a paddle control at a constant speed, you'll notice that the cursor speeds up slightly at the beginning and end of the paddle rotation.

The Super Joystick has a pure resistive circuit which is absolutely linear within one tenth of one percent. In other words it would give you precise control over an image of 1000 by 1000 pixels, were such resolution available. Thus it is suitable for high precision professional applications as well as educational and hobbyist ones.

Matched to your application

The Super Joystick also has two external trim adjustments, one for each direction. This allows you to perfectly match the unit to your application and computer. Say you want to work in a square area instead of the rectangular screen. Just reduce the horizontal size with the trim control.

How many times have you played Space Invader and had your thumb ache for hours from the repeated button pressing? This won't happen with the Super Joystick. It's two pushbuttons are big. Moreover, they use massive contact surfaces with a life of well over 1,000,000 contacts. A few games of Super Invader using these big buttons will justify the purchase of the Super Joystick.

The Super Joystick is self-centering in both directions. That means when you take your hand off it, the control will return to the center. However, if you want it to stay where you leave it, self-centering may be easily disabled.

The Super Joystick plugs right into the paddle control socket and doesn't require an I/O slot.

High-quality construction

The sturdy high-impact molded plastic case of the Super Joystick matches that of the Apple computer. Every component used is the very highest quality available.

We invite your comparison of the Super Joystick with any other unit available. Order it and use it for 30 days. If you're not completely satisfied, return it for a prompt and courteous refund plus your return postage. You can't lose.

By removing two springs, self-centering can be defeated.

The Super Joystick consists of a self-centering, linear joystick, two trim controls, and two pushbuttons mounted in an attractive case. It comes complete with instructions and a 90-day limited warranty. Cost is $59.95.

Order Today

To order the Super Joystick send $59.95 plus $2.00 postage and handling (NJ residents add $3.00 sales tax) to our address below.

Experience the joys of using the world's finest joystick. Order your Super Joystick at no obligation today.

Peripherals Plus

39 East Hanover Ave.
Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)

CIRCLE 239 ON READER SERVICE CARD

Apple Cart, continued...

bytes per side. There are other companies now offering more capacity in 5 1/4" drives too—these are the newer drives that use more than 35 tracks for storage. Some drives use 40 tracks, some use 70 tracks, and some now use 80 tracks. The 40-track drives from Shugart are modified SA400s. The track-per-inch density is still the same. The 80-track drives use higher track density and require special head positioning mechanisms. Consequently, the cost of these drives is much higher. You will be seeing many new controllers and drives with much higher capacity over the next year or so, and it won't be long before some company will offer a 5 1/4" rigid that will store 6 to 10 Megabytes. It might even be Apple.

Compatibility with the Apple Disk Operating System (DOS) is always a question. The only way to know for sure is to try your software on one of these systems. Most of the people that I know who have the SVA system, for instance, have had good luck with it. It's been around the longest. Check out the system of interest first. If the company has been in business for a couple of years they are probably doing a good job.

Printers

One peripheral that always causes confusion is the printer. There are so many types and sizes now that it is difficult to know where to start. Some of the options are: parallel or serial interface, dot matrix print font or formed character font, friction feed or tractor feed, upper case characters only or lower case with descenders. And, the list goes on and on.

Parallel interface printers send the character from the computer to the printer as a complete character. Serial printers send the character as a stream of data one element of the character at a time. Parallel printers require interface control called handshaking. Handshaking signals are used to tell the computer that the printer can accept characters into its input buffer. When the buffer is full, the computer is signaled to stop sending. The printer then prints out the characters and signals the computer that it is ready for more characters. The data can be transmitted to the printer as fast as the computer can send it.

Note that it is of no use to send the data faster than the printer can print it. An operating system that allows "spooling" or the equivalent is needed. Spooling is a technique for dumping the output to be printed into a special buffer storage area. The printing is done from the buffer while the computer goes off and does other things for the operator. The Apple operating system is not that sophisticated. You must wait for printing to be completed before you can do another task.

Here's the KEY to your Apple®!



Computer Station's Programmers Handbook for the Apple®

Retail Price 29.95

Indexed Looseleaf notebook (7½" x 9") containing all the reference material found in our popular Programmers Guide to the Apple II.®

Plus . . .

- Applesoft* & Integer
- CP/M Digital Research, Inc.
- Basic-80 Microsoft
- Pascal
- 6502 Assembly Language
- DOS 3.3
- DOS Tool Kit
- Monitor

Including Command References for

- Applewriter*
- Visicalc* Personal Software
- Macro-Sced

Hardware Configurations & Software Commands for

- Spinwriter
- PaperTiger
- Silentype
- Special ROMs

Two diskette pockets in front & back. Notebook format allows user to add personal comments. A must for every Apple® owner. Available from your local Apple® Dealer or from

Computer Station
11610 Page Service Dr.
St. Louis, MO. 63141
(314) 432-7019

Direct order will incur a $2.00 shipping/handling charge plus sales tax where applicable

Apple, Apple II and Applesoft are the registered trademarks of Apple Computer, Inc.

CIRCLE 149 ON READER SERVICE CARD

MicroStand®

Standard in Microcomputing Products

AT YOUR LOCAL DEALER

MS-II Let MicroStand's sturdy steel shelf organize your Apple[1] II hardware. Professionally constructed, colored and textured to match your Apple[1], and now with new ventilation slots. MicroStand will enhance your home or office microcomputing system, and is available at microcomputer stores across the nation.

CS-I Sturdy steel Apple[1] beige copy holder for ease in typing from books, magazines, etc...

MS-II $39.95 plus $5.00 shipping and handling
CS-I $15.95 plus $3.00 shipping and handling

VISA

MicroStand
P.O. Box 96
Tolovana Park, OR 97145
1 (503) 436-1429

MasterCard

1. TM of Apple Computers, Inc.

CIRCLE 211 ON READER SERVICE CARD

World War II rages across Europe. Castle Wolfenstein is occupied by the army of the Reich and converted into battle-front headquarters. You have been captured and brought to the Castle for interrogation by the dreaded SS. From a hiding place behind the stones of the dungeon a dying cellmate produces a Mauser M-98 pistol fully loaded with ten bullets and gives it to you. Your new mission: Find the Nazi war plans and escape Castle Wolfenstein alive.

Castle Wolfenstein™ is an action adventure game from MUSE demanding fast thinking and quick manual response. Use game paddles, joystick, or your computer keyboard. Castle Wolfenstein™ generates an unlimited variety of castle layouts, each more difficult to escape than the last.

For the Apple II and Apple II Plus with 48K. $29.95

CASTLE WOLFENSTEIN™
by Silas S. Warner

MUSE SOFTWARE

330 N. CHARLES STREET
BALTIMORE, MD. 21201
(301) 659-7212

CIRCLE 226 READER SERVICE CARD

Apple Cart, continued...

```
]ASM
                  1000 ****************************
                  1010 * PRINTER DRIVER ROUTINE *
                  1020 * BY: CHUCK CARPENTER    *
                  1030 ****************************
                  1040
                  1050 * TOGGLES TTL AN0-PIN 15
                  1060
                  1070          .OR $0360
                  1080
0035-             1090 YSAV1  .EQ $35      SAVE Y
0036-             1100 PRINTL .EQ $36      USER PORT L
0037-             1110 PRINTH .EQ $37      USER PORT H
C058-             1120 MARK   .EQ $C058    AN0 SET HIGH
C059-             1130 SPACE  .EQ $C059    AN0 SET LOW
FDF0-             1140 CHROUT .EQ $FDF0    PRINT A CHAR.
FCA8-             1150 DELAY  .EQ $FCA8    DELAY ROUTINE
03EA-             1160 PRTOOS .EQ $03EA    OOS DRIVER HK
                  1170
                  1180 *    MAIN PROGRAM
                  1190
0360- 84 35       1200 PRINTR STY YSAV1    CONTENTS OF Y
0362- 48          1210        PHA
0363- 20 7C 03    1220        JSR TOGGLE
0366- 68          1230        PLA
0367- C9 8D       1240        CMP #$8D     CARRIAGE RET.
0369- D0 0C       1250        BNE COUT
036B- A9 8A       1260        LDA #$8A     LINE FEED
036D- 20 7C 03    1270        JSR TOGGLE
0370- A9 58       1280        LDA #$58
0372- 20 A8 FC    1290        JSR DELAY    DELAY SOME
0375- A9 8D       1300        LDA #$8D     CARRIAGE RET.
0377- A4 35       1310 COUT   LDY YSAV1    GET Y VALUE
0379- 4C F0 FD    1320        JMP CHROUT   PRINT CHAR.
037C- A0 0E       1330 TOGGLE LDY #$0E
037E- 18          1340        CLC
037F- 48          1350 PUSH   PHA
0380- B0 05       1360        BCS TOGGL1
0382- AD 58 C0    1370        LDA MARK     MARK OUT
0385- 90 03       1380        BCC KATE
0387- AD 59 C0    1390 TOGGL1 LDA SPACE    SPACE OUT
038A- A9 03       1400 KATE   LDA #$D3     BAUD RATE
                  1410
                  1420 * $D3=110  $4D=300
                  1430
038C- 48          1440 PUSH1  PHA
038D- A9 20       1450        LDA #$20
038F- 4A          1460 SHIFT  LSR
0390- 90 FD       1470        BCC SHIFT
0392- 68          1480        PLA
0393- E9 01       1490        SBC #$01
0395- D0 F5       1500        BNE PUSH1
0397- 68          1510        PLA
0398- 6A          1520        ROR
0399- 88          1530        DEY
039A- D0 E3       1540        BNE PUSH
039C- 60          1550        RTS
                  1560
                  1570 * START PRINTER
                  1580
039D- A9 60       1590 PRTON  LDA #PRINTR
039F- 85 36       1600        STA PRINTL
03A1- A9 03       1610        LDA /PRINTR
03A3- 85 37       1620        STA PRINTH
03A5- 4C EA 03    1630        JMP PRTOOS
                  1640
                  1650        .EN
SYMBOL TABLE
FDF0- CHROUT
0377- COUT
FCA8- DELAY
C058- MARK
0037- PRINTH
0036- PRINTL
0360  PRINTR
03EA- PRTOOS
039D- PRTON
037F- PUSH
038C- PUSH1
03BA- RATE
038F- SHIFT
C059- SPACE
0387- TOGGL1
037C- TOGGLE
0035- YSAV1
:
```

Hex Code

Listing 1. Assembly of printer drive program in the format of the S-C ASSEMBLER II. Enter the hex code starting at address $0360 and ending at address $03A7. For some printers the mark and space addresses at $C058 and $C059 may need to be reversed. Load the program using APPLE Monitor commands. Run it with a 39DG from the monitor or a CALL 925 from a Basic program. Change the baud rate as shown in Line 1400 for 110 or 300 baud.



Figure 1. Connections from the 16 pin Apple game I/O connector to a TTL compatible serial printer. Use the program in Listing 1 to drive a printer connected as shown.

Serial printers are usually described as having an RS-232 interface. This interface defines the characteristics of the signals and the pins used for the signal and handshaking lines. Connectors for RS-232 compatible signals and handshaking are usually the 25-pin D type. Most printers use this configuration but not all. Serial printers often do not require handshaking to print. The electronics and printing mechanisms are designed to allow printing at some maximum speed. The head will actually move faster but the speed is controlled to allow for carriage returns without buffer overflow. If this were not done, some characters would be lost during the carriage return time. If you want to run the serial printer at maximum speed, handshaking is required. Typical speed of current printers is 30 to 45 characters per second. This is often translated as 300 to 450 baud. A baud is a transmission rate of so many bits of serial data in a given time period. Current use of the more or less outdated term is 10 bits per character.

Often too, the serial printer will allow simple interfacing to the computer. Many times, I have used a simple driver program to drive my DEC LA-34 from the game paddle connector. If the printer input uses modern electronics, it is often what is called TTL (Transistor Transistor Logic) compatible. These are the output voltages available from the game paddle I/O (input-

Apple II sensational software

creative computing software



Trucker and Streets of the City

CS 4710 Applesoft Disk (32K) $24 95

Trucker

This program simulates coast-to-coast trips by an independent trucker hauling various cargos The user may haul oranges, freight or U.S. mail All have different risks and rewards Maximum profit comes from prudent risk-taking

If all goes well, you can obey the speed limits, stop for eight hours of sleep each night and still meet the schedule Bad weather, road construction or flat tires may put you behind schedule You may try to increase your profit by skimping on sleep, driving fast or carrying an overweight load.

Other factors are choice of routes, truck payments, fuel, food, tolls and fines The simulation is engrossing and informative

Streets of the City

This simulation is modeled on Grand Rapids, Michigan, a metropolitan area with a population of 550,000 The budgeting, cost and work standard bases are derived from actual experiences of the city over the past five years The objective of the simulation is to complete a ten-year plan of street and transit improvements while retaining the support of a majority of the City Commission.

During your tenure, you must construct streets and Interstate highways, repair existing streets, and improve traffic safety. For the Transit Authority you have to upgrade and replace a delapidated bus fleet, increase ridership, reduce maintenance downtime and improve on-shedule performance

Other factors to be considered are operating tax levies, construction bonding and labor negotiations The simulation provides a substantial challenge and it is both educational and entertaining

Super Invasion

Disk CS-4505 (16K) $19 95
Cassette CS-4006 (16K) $19 95

This original invasion game features superb high resolution graphics, nail biting tension and hilarious antics by the moon creatures Fifty-five aliens whiz across the screen, quickening their descent, challenging you to come out from behind your blockades and pick them off with your lasers A self-running attract mode makes it easy to learn and demonstrate the game Game paddles are required

Milestones

Disk CS-4515 (48K) $19 95
Cassette CS-4015 (48K) $11 95

The object of Milestones is to complete a 700-mile auto trip before your opponent. the computer You must deal with hazards of the roads stop lights flat tires speed limits accidents and gas shortages Spectacular high-resolution color graphics



Action and Bumping Games

Disk CS-4516 (16K) $24 95

Action Games Cassette CS-4017 (16K) $11 95
Bumping Games Cassette CS-4070 (16K) $11 95

Hustle Earn points by chasing and tagging the elusive colored blocks

Cycle Jump Try to jump over rows of cars, buses and trucks

Road Machine Drive over a curving, mountain road as fast as possible Eight skill levels

Mine Rover Use your rover to cross a mine field with moving miners

Bumper Blocks An absorbing game of evasion and collision Five skill levels

Obstacle Course This multi-level course includes hurdles, ladders, tires and penalty areas Different every time

Stock & Options Analysis

Disk CS-4801, $99 95
Requires 32K Applesoft or Apple II Plus

This is a comprehensive set of four programs for the investment strategy of hedging listed options against common stocks. A complete description is in the TRS-80 section

Apple is the registered trademark of Apple Computer Inc

Advanced Air Traffic Controller

Disk CS-4517 (16K) $19 95
Cassette CS-4008
(16K, regular version) $11 95

In this popular, fast-moving simulation you must successfully control the flight paths of 27 aircraft as they take off, land and fly over your airspace

Order Today

To order any of these software packages send payment plus $2 00 postage and handling per order to Creative Computing Morris Plains NJ 07950 Visa MasterCard and American Express orders may be called in toll-free

Order today at no risk If you are not completely satisfied your money will be promptly and courteously refunded

Creative Computing Software
Morris Plains NJ 07950
Toll-free 800-631-8112
In NJ 201-540-0445

creative computing software

output) pins. Figure 1 shows how to make the connections. A program to drive a serial TTL-compatible printer is shown in Listing 1. With this program, you never have to be concerned with the effect of tabs. Many of the interface boards, including Apple's, have problems with tabs that have to be handled with a special code. This program prints just what is in the code. It can also be used as a slow-list program.

Enter the hex code using the Apple monitor commands. These can be found on pages 40 to 66 of the Apple II Reference Manual. Specifically, use the instructions on pages 43 and 44. The program will run from the monitor using the instruction 39DG (RETURN). From a Basic program use CALL 925. To change the speed of the program, change the byte of data at location $038B. Notice that the value in the program is $D3. (The $ symbol is used to mean a hexadecimal number in 6502 microprocessor notation.) Change this value to $4D if your printer runs at 30 characters per second—or 300 baud. For higher speeds use smaller numbers. (This is the timing loop value for the delay between character elements.)

Other Features

Most of the less expensive printers use what is called a dot matrix. Each character is formed by an arrangement of dots. These dots are in a fixed pattern and are made by individual wires striking the paper through an inked ribbon. The dot matrix is often in a 5 x 7 or 7 x 9 arrangement. There are also special arrangements such as the N x 9 pattern used by my Centronics 737 printer. This arrangement is used for the proportional spacing feature.

Formed characters are found on the more expensive printers. The Xerox, NEC and similar printers are examples. A formed character is like that found on a typewriter. When the hammer strikes the paper a complete character is printed. With the printers mentioned, the characters are on the spokes of a printwheel. These spoked wheels are often called daisy wheels. Hence the term "Daisy Wheel Printers." Printers of the formed character type give much better quality print and are much more expensive. Note that some matrix printers do not have descenders. That is, certain characters do not go below the line. This is done to save the cost of more wires in the print-head. Most of the newer printers now have descenders of sorts. This helps to make the print more readable. Also watch to see if the lower case letters are raised. Some printers do this to give the appearance of descenders. But the character is actually raised above the line to keep it within a smaller matrix.

Printers to be used for graphics almost always have to have tractor feed. Tractor feed is used to maintain the position of the paper in relation to the print head. If you try to do graphics without being able to control the position of the paper, you may get gaps in the graphics being printed. Also, be sure there is software available to drive the printer you chose for graphics. It is not a simple matter of just having a printer with individual dot control. My 737 has that capability. But, as far as I know, there is no software available to let me use it for graphics.

Other considerations to be made include the choice of thermal or regular paper. Thermal paper is used with the Apple Silentype printer, which allows you to use the various plotting programs available. But, you have to use special coated paper. It is expensive and has a finite life. If it is not handled with care, your printed listings may discolor. Any heat will break it down. Plain paper printers, on the other hand, require frequent replacement of the ribbon. If you write for publication, the editors will insist on new ribbons—frequently. If you write only casually, you can get away with a lot of things. If you insist on using the blue thermal paper remember: it is very difficult to read the stuff and it is practically impossible to reproduce it with any optical system such as photography.

Lots More

Whole columns could be devoted to each of the peripheral options available for the Apple. One significant choice would be communications. You have several choices there. One is with the Apple communications card and an acoustic

do you have a hard time tearing yourself away...

...from endless tax tables and computations every time you run your payroll?

Look at these other powerful features!

- COMPUTES all Federal and State Income Taxes, plus other state and local taxes for any and all 50 states and Washington D.C. Tax formulas are built in, no messy entry from tax tables required.
- CAPACITY of 300 employees, 15 Divisions/Stores in multiple states ... any state. Up to 30 additional user defined deduction types.
- PRINTS payroll checks, check register, W-2 forms, all summary and quarterly reports, ethnic distribution, employee lists, and file usage information ... all in the time it takes your printer to print!
- FULL SUPPORT after you make your purchase. Hotline for technical assistance. Payroll tax update service to keep your system current, even with changes in local laws, available at low cost (free for the first year). Your system never becomes obsolete!

Consider the fast and versatile alternative: PAYROLL from Brøderbund Software is written in PASCAL and assembly language so it runs many times faster than Basic, yet it requires no language card or other special hardware! PAYROLL will run on any 48K Apple II with DOS 3.3 and two disk drives.

Ask for a demonstration of the Brøderbund PAYROLL at your authorized Apple dealer.

Coming soon ... PASCAL General Ledger
Accounts Receivable
Accounts Payable

For hard disk users — PAYROLL "HD" has a capacity of 745 employees and 63 Divisions, plus other special features, and requires a Pascal language card system.

Apple II is a trademark of Apple Computer Company.

Brøderbund Software 2 Vista Wood Way San Rafael, CA 94901 [illegible]

CIRCLE 129 ON READER SERVICE CARD

modem. Another is with the Hayes direct coupled modem. Each has its own special features and characteristics. My system uses the Hayes modem. You can do many things, such as dial from the keyboard and have unattended answering. Electronic mail and other technologies are also within the communications realm.

Amateur radio is possible with some of the equipment available. One company offers a card to let you send and receive morse code and teletype. And, how about video monitoring and control. There are peripheral cards to let you control a 3/4" video recorder. The list goes on and on. No brief treatment such as this could cover all the possibilities. Recent issues of some Apple magazines have talked about the use of the Apple computer in the making of major science fiction films, and, the Apple has been used in space exploration applications too.

Information Sources

Softalk magazine is available to all Apple owners in the USA. If you are not getting your complimentary subscription, contact Softalk Publishing Inc., 11021 Magnolia Blvd., North Hollywood, CA 91601. (213) 980-5074.

Other magazines for Apple owners include:

- *Nibble*, Box 325, Lincoln, MA 01773. $17.50 for 8 issues.
- *Call-APPLE*, 304 Main Ave. S., Suite 300, Renton, WA 98055. Membership required, $25 one-time application fee; $15 yearly dues.

Other useful publications about the Apple include:

- *Beneath Apple DOS* by Don Worth and Peter Lechner, Quality Software, 6660 Reseda Blvd., Suite 105, Reseda, CA 91335. (213) 344-6599. An in-depth analysis of Apple DOS. Covers all versions of DOS concentrating on DOS 3.3. Sells for about $22 and is well worth the price.
- *Computer Station's Programmers Handbook to the Apple II*. Complete summary of all Apple commands. Includes DOS, Assembler/Editor, Basics, Pascal, Visicalc, CP/M, Basic-80, and much more. A useful reference for the serious Apple II programmer. About $20.
- *The Apple Monitor Peeled* by William E. Dougherty, 14349 San Jose St., Mission Hills, CA 91345. (213) 896-6553. Covers all the calls and subroutines in the Apple Monitor. Also useful for the serious Apple programmer. Especially if you're interested in assembly/machine language programming. About $10.
- *Apple Machine Language* by Don Inman and Kurt Inman, Reston Publishing Co. Inc., Reston, VA. This book covers the fundamentals of assembly language programming from an Apple point of view. Basic programs are used to explain machine language. The content is specifically Apple and covers the mini-assembler. I got my copy from a local computer store for about $20.

And Lots More

My intent here was to give the newcomer and potential owner some help with sources of Apple information. There was also an attempt to explain some of the more confusing aspects of peripherals. Please write to me if you have any questions. There is so much to be covered that I could not possibly do it here. Perhaps your imagaination has been stimulated though and that's good.

NEXT TIME

Lots of you wrote to me about the space problem with hi-res graphics also mentioned in the May '81 column. There were too many to mention each one. I'll summarize them and give credit to all. A couple responses included elaborate programs for helping to get more space for hi-res programs. But that's enough until next time. □

Worth A Fortune

Past issues of Creative Computing. What are they worth today? It varies. To a collector, Vol. 1, No. 1 is worth $7 or $8. To a scrap dealer, less than two cents.

But we're not selling old back issues. We're all out.

On the other hand, you know that much of the content of Creative Computing is timeless. The Depth Charge program in Vol. 1, No. 1 is just as challenging today as the day it was written. Walter Koetke's series of five articles on using computers in the classrom are as valid today as the day they first ppeared in print. And scores of people have written about obtaining reprints of Don Piele's classic problem-solving series.

Our Mistake

In our early growth years when we had 5,000 and then 10,000 subscribers we couldn't imagine we would ever need more than 1000 extra copies for back issue sales. That's about what we printed extra. However, by the time we were going into Volume 3, we found our stocks of Volume 1 issues virtually depleted.

Our Solution

So we selected the best material from Volume 1, edited it, put it together in book form and sold it for $8.95, about the same as the six individual issues. Nine months later, we did the same with Volume 2. Then a year and a half later we did it again with Volume 3.

Most other magazines in a high technology field like small computers find their contents are quickly out of date. However, because we've concentrated on applications and software, our content retains its value for a much longer time. Our subscribers know this and retain their copies of Creative Computing long after they've disposed of the more hardware-oriented magazines.

Now you can obtain the best material from the first three years of Creative Computing in book form and the next three years (minus four issues) in the original magazine form.

Our Offer

We have a unique special offer, so pay close attention to this paragraph. (Computer types ought to be able to understand this). If you order any one item below, you pay the full price. If you order any two items, take a 5% discount from the total; any three, take a 10% discount; any four, take a 15% discount; any five, take a 20% discount, and on all six take a whopping 25% discount from the total price.

Best of Creative Computing-Vol 1	$8.95
Best of Creative Computing-Vol 2	8.95
Best of Creative Computing-Vol 3	8.95
Volume 4 (Four issues)	6.00
Volume 5 (Ten issues)	15.00
Volume 6 (Twelve issues)	18.00

Less discount (5% for two items, 10% for three, 15% for four, 20% for five, 25% for all six) Shipping ($2.00 USA, $5.00 foreign)

This isn't really an order form. Cut it out or copy the items you want onto a sheet of paper. Send it with your name and address and payment or credit card number and expiration date (Visa, MasterCard or American Express) to Creative Computing, Morris Plains, NJ 07950. Or call toll-free to 800-631-8112 (in NJ, 201-540-0445).

We guarantee you'll never find a better value in computer applications reading matter. On average you're getting 128 pages of solid information for each $1.00. If you're not completely satisfied after you've read them, send the books or magazines back to us and we'll refund your full purchase price plus the return postage.

creative computing

Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)

outpost : atari

David and Sandy Small

Recently I received a letter from a new Atari user. In it, the writer said "Help! My friends with Apples are making fun of me and my 'Aturkey 800,' as they call it. They say it can't display more than five colors onscreen at once and their Apples can. They call me up at 4:00 a.m. to tease me. Can you help?"

Well, I couldn't ignore such a plea. So here it is, the first of a two-part column on making your Atari generate many different shades of color on the same TV frame. Along the way, I'm going to cover very briefly topics that have been covered in previous columns (i.e., what is a display list?). Expect them to be just briefly defined, for there isn't room to cover them again. Rather, I'll concentrate on new topics, in a ground-up approach to color generation on the Atari. Hopefully I'll leave you with a wider knowledge of how the machine generates color, with a few example programs to show you just how much it can do.

The Atari is, in my opinion, far and away the finest graphics machine available for the price. It was designed by the wizards of Atari to be able to create as many TV displays as you can imagine. The designers knew that many new applications would be thought of long after the hardware was designed, and thus made everything as open ended as possible with a great deal of flexibility. (I suspect a stripped-down Atari 800 resides inside many Atari coin-op games.)

"Wait a minute," you say, "what's this about 'flexible' and 'open ended?' The Basic book says, five colors maximum. That's not very flexible."

Let's discuss how the Atari handles color a bit, understand why there's a five color limit, and then get around it using some of the flexibility designed into this machine. One demonstration program will show 128 shades of color on the same screen! This demo has been seen by few people indeed. Along the way, I'll even provide a nifty demonstration program called "Sunset."

Why Five Colors?

When the designers of the Atari worked out the details of its color handling, they decided on a technique which would give the user as much flexibility as possible, rather than locking him into just one method.

Inside the Atari is stored a copy of what's currently going on the TV screen, this is called "display memory." For a given point, or a group of points onscreen, some way of determining the color to be used when plotting must be stored in this memory. In the Atari the color information is stored in a "color register." When in display memory the color of a point is specified, a color register number is stored rather than the actual color code.

In other words, to plot a red point, one tells the display memory that this point will be plotted in the color and brightness stored in (say) color register 1, then one puts color red at some brightness into that color register. See Diagram 1.

```
10 REM PROGRAM #1. COUNTS THROUGH
20 REM ALL POSSIBLE COLORS.
25 POKE 709,14:REM SHADOW REGISTER
30 FOR C=0 TO 255 STEP 2
40 POKE 710,C:REM SHADOW REGISTER
50 PRINT "COLOR REGISTER=";C
60 FOR DELAY=1 TO 100:NEXT DELAY
70 NEXT C
```

Program 1.

There are five available color registers, numbered 0 through 4. Color register 4 is also known as the "background color register." It specifies the color and intensity for any place onscreen where nothing else is written. (In the Graphics modes 3-7, this means the color of the area between any plotted pixels; in mode 0, it means the area around the character display field, not the area "behind" characters. It's the border area.)

This approach may seem more complex than necessary, but it has its advantages. First, it saves memory: only two bits at most are required to specify the color of a pixel in the display memory. Second, it adds flexibility. All we have to do to change the color of every point onscreen using the same color register is modify that register—one POKE. To turn the entire screen red, then black, ("RED ALERT!"), we need only two POKEs. In a machine without the Atari's sophistication, massive and slow rewrites of display memory would be required. See what I mean about leaving the Atari open ended for applications that would be thought of after the machine was designed?

Color registers are one byte long. The upper four bits determine the color (0-15), the lower four specify the brightness. Now only the top three of the four brightness bits are used; hence, there are eight levels of brightness, and 16 colors, or 128 possible total shades of color. Note that in this register, values 0-15 are color 0 in

Value	Color
0	Grey
1	Gold or Light Orange
2	Orange
3	Red-Orange
4	Pink
5	Blue
6	Purple-Blue
7	Blue
8	Blue
9	Light Blue
10	Turquoise
11	Green-Blue
12	Green
13	Yellow-Green
14	Orange-Green
15	Light Orange

Table 1. Color Register Values (as stored in upper 4 bits of color register).

ATARI BOOK SOFTWARE

THIS BK EXTENDED BASIC COLOR COMPUTER SOFTWARE

THIS BK LOGICAL COMPUTER SIMULATOR

FROM SEBREE'S COMPUTING
456 Granite Avenue, Morrovia, Calif., 91016

CIRCLE 229 ON READER SERVICE CARD

Too Much!

How can we tell you about 200 products in one advertisement?

Our new catalog gives detailed descriptions of over 200 peripherals software packages and books We believe that to make an intelligent purchasing decision you need as much information as possible You need more than can fit into a short ad You need screen photos of software not just a glowing description You need technical details about peripherals

You ll find this kind of detail in our new 48-page catalog It s unique in the small computer field Best of all it s **FREE**

Peripherals Plus

319 Maple Ave Morristown NJ 07960

CIRCLE 239 ON READER SERVICE CARD



ATARI

Atari 800 16K	810.00	16K RAM	85.00
Atari 800 48K	950.00	Atari 850 Interface	176.00
Atari 810 Disk	460.00	Atari 830 Modem	156.00
Atari 400 16K	379.00	Microsoft Basic	72.00

TELECOMMUNICATIONS PACKAGES
Base Unit, A850, A830, TeleLink I
with 800: $1150.00 with 400: $710.00
PLUS **FREE** NOVATION SUPERMIKE!

The Bit Bucket is a company made up of computer professionals We are able to provide low prices as well as technical support Give us a call and find out why we consider the Atari the best home computer on the market today You won t be disappointed

The Bit Bucket
Specializing in Atari Home Computers
P O Box 365
Newton Highlands MA 02161
(617) 783 3144

CIRCLE 115 ON READER SERVICE CARD

WANTED

SOFTWARE AUTHORS!

for Apple, Atari, TRS-80, NEC, Hitachi. . . .

Brøderbund Software is looking for new authors to join its international team of programmers. If you have a product for the micro market, let us show you the advantages of working with our team of design, production and distribution specialists.

Call or write for our free Authors Kit today or send us a machine readable copy of your work for prompt review under strictest confidence.

Brøderbund Software

2 Vista Wood Way San Rafael, CA 94901

CIRCLE 264 ON READER SERVICE CARD

MAIL ORDER DISCOUNTS

apple computer
Sales and Service

APPLE II PLUS 48K
$1,099
APPLE II PLUS 16K $1,025

HARDWARE

DISK II DRIVE & INTERFACE	499
DISK II SECOND DRIVE	439
BASF 5¼" DISKETTES (10)	25
LANGUAGE SYSTEM W/PASCAL	379
INTEGER BASIC FIRMWARE CARD	149
APPLESOFT II FIRMWARE CARD	149
CENTRONICS PRINTER INTERFACE CARD	179
HIGH SPEED SERIAL INTERFACE CARD	145
GRAPHICS TABLET	649
APPLE IEEE-488 INTERFACE CARD	339
M&R SUP-R-MOD RF MODULATOR	25
MICROSOFT Z-80 SOFTCARD SYSTEM	299
MICROSOFT 16K RAM CARD	169
VIDEX 80 COLUMN BOARD	295
HAYES MICROMODEM II	299
AMDEX 13" COLOR MONITOR	429
NEC 12" GREEN MONITOR	255
SILENTYPE PRINTER W/INTERFACE	350
EPSON MX-100	829
QUME SPRINT 5/45 PRINTER	2499

SOFTWARE

APPLE DOS TOOLKIT	65
APPLE PILOT	60
TAX PLANNER	99
APPLE FORTRAN	159
APPLE PILOT	119
APPLEWRITER	65
DOW JONES PORTFOLIO EVALUATOR	45
DOW JONES NEWS & QUOTES REPORTER	65
THE CONTROLLER	495
VISICALC (16 SECTOR)	159
VISIPLOT	149
VISITREND/VISIPLOT	215
DESKTOP PLAN II	159
BPI BUSINESS SOFTWARE (EACH)	335
SUPER TEXT II	125
PROGRAMMA APPLE PIE	110
EASYWRITER (80 COLUMNS)	219
D B MASTER	180
WORD STAR	299
MICROSOFT FORTRAN	149

TO ORDER Please send cashier s check, money order or personal check (allow 10 business days to clear) VISA and Master Card credit card service add 3% American Express credit card service add 5% Shipping, handling and insurance in U.S add 3% (minimum $4). California residents add 6% sales tax. Foreign orders add 10% for shipping. Equipment is subject to price change and availability All equipment carries factory warranty Store prices differ from mail order prices TELEX 697120 DATAMAX SDG

800-854-1941 **computer age, inc.** (714) 565-4062
Authorized Apple Dealer & Service Center
4688 CONVOY STREET, SAN DIEGO, CA 92111

different intensities. 16-31 are color 1, and so on; if we just count this register upwards, we'll pass through all 16 colors, each increasing in intensity to the highest level before moving on to the next. If you'll run Program 1, you'll see the screen counted through all the different shades. Table 1 lists the different colors.

How Basic Handles Colors

Up in high memory there's some memory which isn't read-write, regular old RAM. Rather, when one writes or reads from these locations, one is communicating with other chips in the Atari which help support the 6502 (more on this later). (Diagram 2.) Anyway, one chip, called CTIA, handles colors and graphics generation. There are five locations ("hardware color register addresses"), which are the five color registers. Now CTIA looks to these registers to find out the color needed for a given character/point, whenever it plots a new point. During the refresh process of updating the screen, it looks to the registers many, many times, fetching the colors for displayed data.

The operating system maintains five "shadow registers." These are normal RAM memory locations. At the beginning of each screen refresh, these five color shadow registers are copied into the corresponding five hardware locations. Basic deals with these shadow registers. (A list of these also appeared in a previous article.) Why?

One reason for maintaining these shadows is that the CTIA color register locations are "write only"; one cannot read out those locations the color has just written in. Remember, they are not memory locations; they are other chips to which we write by POKEing simulated memory locations. Hence, if we wanted to read a color register and we didn't have it stored somewhere (like a shadow register), we couldn't. Being able to read registers is handy, for example, rotating a color from one register to the next; you use the O.S. shadow registers for this.

Basic's SETCOLOR (color reg number), (col number), (lum number) takes: (16 x color number) + lum and POKES that value into the O.S. shadow register. One sixtieth of a second later, at the beginning of a screen refresh, the O.S. copies this value into the CTIA hardware color registers and begins to use it for plotting data onscreen. Incidentally, a direct POKE to the O.S. shadow locations is equivalent to a setcolor. For example, SETCOLOR 2, 4, 10 is the same as: POKE 710, (4*16)+10.

The designers of Basic also had to come up with some means for the user to specify what color a given point or character should be. For this they have the COLOR



Diagram 1. Specifying a Color Indirectly.



Diagram 2. Atari Memory Layout and Support Chips.

Hardware Registers (CTIA)		O.S. Locations (Shadows)		
D016	(53270)	2C4	(708)	PF0
D017	(53271)	2C5	(709)	PF1
D018	(53272)	2C6	(710)	PF2
D019	(53273)	2C7	(711)	PF3
D01A	(53274)	2C8	(712)	PF4(BACK)

Table 2. Color Registers.

Graphics Mode	Color Register	COLOR(x)
	Character Modes	
0	0 - Unused 1 - Character lum only 2 - Char backgnd color/lum 3 - Unused 4 - Border col/lum	Not used in graphics sense.
1,2	0 - 3: Character 4 - backgnd/border	Not used in graphics sense.
	Graphics Modes	
4,6: One Bit	0: Point color/lum 1, 2, 3: Unused 4: Backgnd	COLOR 1 COLOR 0
3, 5, 7: Two Bit	0: Point color/lum 1: Point color/lum	COLOR 1 COLOR 2

Table 3. COLOR # Values.

(#) statement. It specifies which color register to use when plotting data, and remains in effect until the next COLOR statement.

The argument, unfortunately, is not a color register number. The designers of Basic tried to keep the user away from bits and bytes discussions; hence the COLOR argument at first appears random. Upon closer inspection, I determined what it actually was and the reasons for its arguments.

The argument of the COLOR statement is the data that are written into display memory to specify colors. The Atari has two- and four-color graphics modes, which uses one or two bits to specify color register. For example, COLOR 0 is generally background because of a 00 written into display memory plots nothing, thereby forcing the background color to appear there. Next month we will learn how to get around it. □

Notes:

SETCOLOR (n), color, lum always sets color register n. Hence, the color register number given is equvalent to the SETCOLOR register number.

In chapter modes (0,1,2) more than 1 or 2 bits are written into display memory. Hence the COLOR argument is actually the character byte written in memory.

apple computer
Authorized Dealer

Software!

We Stock It All!!

Games		Business	
Raster Blaster	29.95	Job Cost Accounting	459.95
Micro Chess	25.00	Construction Acct.	549.95
Snoggle	24.95	Visicalc	129.95
Pool 1.5	34.95	Client Billing	250.00
Pustar	29.95	Data Factory	139.00
Orbitron	29.95	Invoice Factory	100.00
Auto Baun	29.95	Tax Planner	120.00
Gamm A Gobling	29.95	Landlord Apartment Management Sys.	795.00
Muse ABM	24.95	Dental Assistant II	600.00
Cyber Strike	39.95	Payroll Management	199.95
Robot War	39.95	Prosoft Medical Billing	1995.00
Dragon Fire	49.95	Magic Window	99.95
Operation Apocalypse	59.95	Gen. Ledger	225.00
Cartels & Cutthroats	39.95		

VISA and MasterCard accepted.

COMPUTER STORE OF GULF BREEZE, INC.
37 Gulf Breeze Pky.
Gulf Breeze, Florida 32561
Call
(904) 932-0660

CIRCLE 199 ON READER SERVICE CARD

SOFTWARE FOR ATARI™

MAZE of DEATH

As a special agent, you try to stop the Cosmitron Device from exploding and destroying the city. The sinister scientist has allowed the device to become critical by removing the radiation control blocks before it is too late. You work against the clock, find your way through laser rooms, mine rooms and other hazards, evade Electrobots and much more. 5 levels of play. All graphics, joystick required. ©1981
In Real Time 16K cassette only $12.95

DRAC IS BACK

An adventure game to test your logic and your tendency towards greed. Battle monsters, werewolves, vampires, speeding demons, the crafty igor and of course the Lord of Evil...Drac. How much gold can you escape with? How much will you spend to stay alive? Your instincts could be wrong. (non-scrolling). ©1981
24K cassette only $14.95

SYNCRO, INC. SOFTWARE DIVISION
3132E VIA COLINAS, SUITE 107
WESTLAKE VILLAGE, CA. 91362

VISA & MASTERCARD ACCEPTED
CALIF. RESIDENTS PLEASE ADD
6% SALES TAX. $1.50 SHIPPING

CIRCLE 246 ON READER SERVICE CARD

rings...trs-80 strings...trs-8

Stephen B. Gray

For the 34th ride on the TRS-80 train, we'll talk about getting started with a TRS-80, look at a benchmark report on the Model II, a cassette that lets you do a print, a plastic video worksheet, a screen-print program, a word-processing program, Radio Shack's Level-I Statistical Analysis package, and a short program that creates an optical illusion.

Getting Started

I've been asked to write a "Getting Started" piece for this column. Although some of the lesser personal computers are fascinating machines, I feel that you're better off with one of the best-sellers, from a company that's had plenty of experience manufacturing and supporting their computers.

If there were no TRS-80 computers, I'd probably have an Apple, mainly because of all the wonderful peripherals available. But in my opinion, the TRS-80 is, and for the foreseeable future will be, the king of the hill in its field. There are many more publications for the TRS-80 than for any other computer, and many more software packages are available for the TRS-80 than for any other. Many of the programs are, admittedly, second- and even third-rate, but even then you have a great many to choose from. Also, if you're on a tight budget, there are more used TRS-80s around than any other machine.

As for which TRS-80 to select, more about that in a moment. As for tape versus disk, tape is cheaper, but the general movement is toward disk, and some software houses will soon, if not already, offer only disk programs. With disk, you load a program in seconds instead of minutes, and you can store much more in less space.

If possible, go into a computer store and try out a machine, or try out a friend's computer. Get the feel of it, try to imagine owning it, make sure you'll get enough out of it to make the investment worthwhile, and also make sure you want to spend that much time alone with a machine.

Which TRS-80 For You?

When you get to the point of selecting a TRS-80, it's not all that complicated. They fall into rather easily defined user slots, so there usually isn't much of a problem deciding which to buy.

Pocket Computer

As I wrote previously (June 1981, p. 196), the TRS-80 Pocket Computer is mainly for the gadgeteer (who wants one because it's such a clever little piece of engineering), the man on the road (who hasn't space for a table-top micro), and the engineering student.

Despite the small keyboard and small, fixed memory, the PC packs a lot of computing power in a small space. One problem: so far, Radio Shack, hasn't provided much software for the PC. And unless the few companies that write programs for the PC generate something other than games and mortgage-payment-type software, you may have to write your own applications software. However, that's the best way to really learn how your PC works and how to use it; you'll be surprised how complex a program you can write if you really have to.

Model II

This is an easy one, because just about everybody who buys a Model II TRS-80 intends to use it for business. That's the way Radio Shack markets it, offering several business-system combination packages, and nothing but "Ready-to-Use Model II Business Software," as the RSC-5 catalog puts it.

Color Computer

The TRS-80 Color Computer seems mainly intended for game players, what with its "instant-load Program Paks"



COLOR COMPUTER

RAMCHARGER 32K UPGRADE

- EXTEND MEMORY FROM 16K to 32K
- 100% Compatible With Extended Basic
- No Soldering Or Modification
- Fits Inside Computer
- $99.95

TRS-80

Space Invaders
Meteoroids
Space War

- The Best Games Available
- High Resolution Graphics
- Fast, Machine Language
- Compatible w/ Ext. Basic
- $21.95 each, $59.95 for all three

EXTENDED BASIC GAMES

- LOTHAR'S LABYRINTH) Word Search Puzzle
- BATTLEFLEET Battleship Search Game (one or two players)
- SPACE TRADERS Galactic trading game

$14.95/ea.

ADVENTURE

Combat the powers of darkenss and evil! Can you recover the treasure of the Golden Sorcerer before his minions overcome you. A adventure for endless hours of fun and excitement. $19.95

THE FACTS

At last, a complete description of the "guts" of the Color Computer. Specs on all the ICs, complete schematics, theory of operation and programming examples. $14.95

UTILITIES

- EDITOR/ASSEMBLER $34.95
- SUPER MONITOR 19.95
- EPROM PROGRAMMER ..... 89.95 (Program your own ROMs for the ROM PAC port)
- MAGIC BOX ..... 24.95 Load MOD I/III Tapes into the color computer

Coming Soon: Software speech synthesis. Improved Videotex with printout and many other features.

SPECTRAL ASSOCIATES

143 Harvard Ave.
Tacoma, Washington 98466
(206) 475-8483

WRITE FOR COMPLETE CATALOG

ADD 3% FOR SHIPPING

VISA OR MASTERCHARGE ACCEPTED

CIRCLE 271 ON READER SERVICE CARD

RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes —

FIELD PROVEN!!
10 MEGABYTES and MORE for the TRS-80* Model II plus SHARED ACCESS to HARD DISK DRIVE

Hard/Soft Disk System (HSDS) Software allows access as single drive. You can have that 10 Megabyte continuous file - that 50,000 name mailist or inventory! Or a directory with 1000 entries! All completely compatible with TRSDOS 2.0 BASIC. You can mix floppy and hard disk drives. Includes special utilities including HPURGE, DCS Directory Catalog System, HZAP, Hard Disk Superzap, and many special formatting options. Three to eight times faster than floppy! RACET quality.

HARD DISK DRIVE & CONTROLLER $5995. Second User $595.
HSDS Software $400. (Note: HSDS now also available for CORVUS drives!!)

INFINITE BASIC (Mod I & III Tape or Disk) **Mod I $50.00, Mod III $60.00**
Extends Level II BASIC with complete MATRIX functions and 50 more string functions. Includes RACET machine language sorts! Sort 1000 elements in 9 seconds!! Select only functions you want to optimize memory usage

INFINITE BUSINESS (Requires Infinite BASIC) **Mod I & III $30.00**
Complete printer pagination controls — auto headers, footers, page numbers. Packed decimal arithmetic — 127 digit accuracy +, —, *, /. Binary search of sorted and unsorted arrays. Hash codes.

BASIC CROSS REFERENCE UTILITY (Mod II 64K) **$50.00**
SEEK and FIND functions for Variables, Line Numbers, Strings, Keywords. All options available for line numbers and variables. Load from BASIC — Call with 'CTRL'R. Output to screen or printer!

OSM **Mod I $75.00, Mod II $150.00, Mod III $90.00**
Disk Sort/Merge for RANDOM files. All machine language stand-alone package for sorting speed. Establish sort specification in simple BASIC command File. Executed from DOS. Only operator action to sort is to change diskettes when requested! Handles multiple diskette files! Super fast sort times — improved disk I/O times make this the fastest Disk Sort/Merge available on your TRS.
(Mod I Min 32K 2-drive system. Mod II 64K 1-drive. Mod III 32K 1-drive)

GSF (Mod I & III Tape or Disk - Specify Memory Size)
Mod I $25; Mod II $50; Mod III $30
Generalized Subroutine Facilities. The STANDARD against which all other sorts are compared! And then compare prices! Machine language — fast and powerful! Multi-key multi-variable and multi-key character string. Zero and move arrays. Mod II includes USR REEKS and POKES. Includes sample programs

DISCAT (32K 1-drive Min) **Mod I, III $50.00**
This comprehensive Diskette Cataloguing/Indexing utility allows the user to keep track of thousands of programs in a categorized library. Machine language program works with all TRSDOS and NEWDOS versions. Files include program names and extensions, program length, diskette numbers, front and back and diskette free space

KFS-80 (1-drive 32K Min — Mod II 64K) **Mod I, III $100.00; Mod II $175.00**
The keyed file system provides keyed and sequential access to multiple files. Provides the programmer with a powerful disk handling facility for development of data base applications. Binary tree index system provides rapid access to file records

MAILLIST (1-drive 32K Min. Mod II 64K) **Mod I, III $50.00; Mod II $150.00**
This ISAM [illegible] no separate sorting. Supports 9-digit zip code and 3-digit [illegible] tributes. Mask and query selection. Record access times under [illegible]

COMPROC (Mod I & Mod III — Disk only) **Mod I $20, Mod III $30**
Command Processor. Auto your disk to perfo[illegible] instructions that you can save from the keyboard. DIR, FREE, [illegible] BASIC. No of FILES [illegible] MEM SIZE. RUN program [illegible] ents, BREAK, return to [illegible] etc. Includes lowercase dr[illegible] screenprint!

UTILITY PACKAGE (Mod I & III) **$150.00**
Important [illegible] alone will pay for the packa[illegible] page manual! XHIT, XGAT[illegible] cover data from bad diskette[illegible] select, absolute sector mode[illegible] any sector on diskette incl[illegible] recovery. DCS directory catalog [illegible] display or listing sorted by disk name or file name plus more. Change Disk ID with DISKID. XCREATE preallocates files and sets 'LOF' to end to speed disk accesses. DEBUGII adds single step, trace, subroutine calling, program looping, dynamic disassembly and more!!

DEVELOPMENT PACKAGE (Mod II 64K) **$125.00**
Includes RACET machine language SUPERZAP, Apparat Disassembler, and Model II interface to the Microsoft Editor Assembler Plus software package including uploading services and patches for Disk I/O

CHECK, VISA, M/C, C.O.D., PURCHASE ORDER
TELEPHONE ORDERS ACCEPTED (714) 997-4950

*TRS-80 IS A REGISTERED TRADEMARK OF TANDY CORPORATION

RACET COMPUTES
1330 N. GLASSELL, SUITE M
ORANGE CA 92667

RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes — RACET SORTS — RACET UTILITIES — RACET computes —

CIRCLE 252 ON READER SERVICE CARD

designed to compete with the load-and-go capability of the Atari and other such machines (Creative, July 1981, p. 208).

Yet the 16K Color Basic provides many functions that go beyond the needs of the graphics enthusiast, who might seem one of the main targets for the high-resolution CC graphics.

The CC's low display-character density, which is only 38 percent that of a black-and-white TRS-80 screen, makes the CC less suitable for business use and for writing long programs.

All in all, the CC seems best suited to graphics, to programmers who want to try out a TRS-80 based on the Motorola 6809E microprocessor, and to writers who want to generate books and programs that go beyond Radio Shack's efforts.

Model III



Ever since Radio Shack stopped manufacturing the Model I (although I've heard it's still being made, for sale outside the U.S.A.), the Model III has become the standard TRS-80, not only for the hobbyist, but for the small-business man who can't afford the Model II, which begins at $3,450.

Although some users might prefer a separate keyboard that can be placed where most comfortable, the Model III's self-contained keyboard and dual disk drives do help reduce costs by cutting down on cabling and cabinetry, plus making it a neater-looking machine.

For those on a tight budget, used Model I TRS-80s are advertised as low as $500 for a 16K Level-II that originally sold for about $850.

Model II Benchmark Report

The Association of Computer Users, founded several years ago by Hillel Segal, is a membership organization offering a monthly *ACU Bulletin*, a bimonthly *Interactive Computer Journal*, and unlimited phone-in reference service, for an annual fee of $50.

The fee also includes membership in one of ACU's seven sections, each of which has its own bimonthly newsletter: Large Computers, Small Computers, Distributed Processing, Word Processing, Midi Computers, Time-Sharing, and Home & Hobbyist.

The fee also includes two free Benchmark Reports, which come in three series: popular computers under $15,000; single-user systems in the $15,000 to $25,000 range; and multiple-user systems.

Reports published in the first series include the Northstar Horizon, Apple II Plus, Pertec PCC 2000, Radio Shack TRS-80 Model II, etc., for a total of twelve.

The report on the TRS-80 Model II, dated July 1980, covers 22 pages, including an overall summary; summary of benchmark results; benchmarks; details on pricing, hardware, software and support; summary of user comments; and conclusions.

The summary says the benchmark tests "place the Model II in the middle of the times recorded for the 18 systems tested in ACU's Series 1 and Series 2 prepared so far." The Line Printer III "was found to be very efficient and convenient."

All the summary comments are laudatory, including "the extensive popularity of the Radio Shack Model I systems seems to be instrumental in getting small users to integrate the Model II into their businesses" and "The Model II can be configured to satisfy a variety of uses, and many cited the ability to gradually expand the Model II system as their needs grow as a strong selling point for the system."

The benchmark tests are meaningful, of course, only when compared with benchmarks run on other computers. The test section takes up eight pages, covering speed tests (both CPU and I/O intensive), "real-life" problems (scientific/engineering, new product planning, accounts receivable), and ease-of-use tests.

Comments on setting up the Model II and running the tests are many and detailed. The setup/initialization procedure was found to be "simplified by the clear step-by-step instructions in the manual" and the "handy, concise and well-organized quick reference card" to be "extremely useful as a check list and reference for the new user."

The Basic Reference Manual "we found to be an excellent guide in making our program modifications" to adapt the benchmark programs to Model II Basic, mainly in the area of input/output.

The report mentions some of the TRS-80 Basic features appreciated by programmers, including direct and sequential access files, and assembly-language subroutine calls.

Radio Shack in-house programmers "streamlined some of the benchmark programs, and their comparative results are shown in this report. Their changes basically consisted of defining variables as integers when possible, and defeating the normally operating verify function."

The ease-of-use test results noted that "Approximately 191 keystrokes were required to edit a nine-record test file" and commented "The line editor was found to be extremely easy to use although somewhat inefficient in terms of required keystrokes."

The next eight pages provide information on pricing or hardware or software, followed by ACU observations and user comments.

A user comment on pricing: "Radio Shack is really going for that small business user. When you compare price, TRS ranks way up there." ACU's observation on Line Printer III is that its "somewhat noisy operation... can be distracting at times," then counters with: "but this minor drawback is easily overshadowed by the printer's other features, such as the software-selectable line and print densities.

An observation on software packages: "Radio Shack is moving towards offering software tailored specifically for multi-drive system configuration."

The Summary of User Comments says, "User acceptance of the [software] packages was uniformly good, particularly considering that they were not custom-designed and occasional minor problems had to be worked out."

The last sentence of the report says: "Overall we feel that Radio Shack, in combining aggressive marketing with a quality, cost-effective product, is successfully competing in the small-computer market."

These are only a very few excerpts from the Benchmark Report, which deserves to be read in full, and compared with Benchmark Reports on other computers you may be considering for business use. The complete Series 1 is $150 for the twelve reports, available individually for $25 each, from the Association of Computer Users, 4800 Riverbend Road, P.O. Box 9003, Boulder, CO 80301.

The ACU report is almost entirely full of praise for the Model II TRS-80, which could mean either that it's a fine computer, or that the ACU's policy is "Be a Booster, Not a Knocker."

Hillel Segal's comment on this is "That's not so! We certainly 'tell it like it is' from a user point of view. In fact, many of our reports contain negative comments—but when we're impressed we say so. In short, we liked the TRS-80 Model II."

3M CRT Filters

Because of a missing line in the item on the two 3M CRT filters in the August column (p. 192), the meaning was garbled. The paragraph should have read:

"The filters advertised in personal-computer magazines cost considerably less than $20.55 each, more like $13.95 or even $7.95. However, the couple I've seen

Super Cassette Sale

Cassettes A thing of the past? You might think so by the number of software houses that have dropped them from their line in the past year or so

However, we have always tried to make our software available on both cassette and disk for as many computers as possible This is a policy we intend to continue

But right now we have so many new software packages coming along that we are consolidating and merging some of the programs from our cassettes into the new lineup As a result we are selling out of some existing cassettes now in stock

All of the cassettes are high quality, durable tape in Norelco-style plastic boxes and are backed by our unconditional guarantee The savings on these cassettes are tremendous! 20 to 45%. So order yours now! At these prices they'll move fast

All orders subject to stock on hand

PET/CBM

Graphic Games-1 cassette includes Escape, Snoopy, Chase, Sweep, and Darts. Top rated by three reviewers! Available in old and new ROM version. CS-1004 regular $11.95, sale price $7.95

Graphic Games-2 cassette includes Checkers, Dodgem, Bounce, Nuclear Reaction, LEM, and Artillery. Our most popular Pet cassette Available in old and new ROM version. CS-1005 regular $11.95, sale price $7.95.

Conversational Games cassette includes Hexletter, Hurkle, Hangman, Haiku, and Eliza Old and new ROM version available CS-1006 regular $11.95, sale price $7.95.

Board Games cassette includes Yahtzee, One-Check, Backgammon, Trek 3, and Blackjack. Old and new ROM available CS-1007 regular $11.95, sale price $7.95.

SUPER PET SALE
Take all four cassettes (21 programs in all!) for only $29.95.



ADVENTURES

Adventureland will excite you as you search for treasures on a deserted island, or so you think! Available for the 16K Apple II or Apple II Plus (CS-4011), or the Sorcerer (CS-5003), list $14.95, sale price $11.95.

Pirate Adventure takes you from your London flat to try to recover Long John Silver's buried treasure Available for the 16K Apple II or the Apple II Plus (CS-4012), TRS-80 (CS-3008) or the Sorcerer (CS-5004) List $14.95, sale price $11.95

Your **Mission Impossible**, if you decide to accept it, is to save the world's first nuclear reactor from doom. Available for the 16K Apple II or the Apple II Plus (CS-4013), or the Sorcerer (CS-5005). List $14.95, sale price $11.95.

Wander through the **Voodoo Castle** in search of the secret of Count Cristo, but beware the Voodoo man Available for the 16K Apple II or the Apple II Plus (CS-4014), TRS-80 (CS-3010) or the Sorcerer (CS-5006) List $14.95, sale price $11.95

Beware **The Count** as you move through the haunted castle looking for clues to allow you to escape unharmed. Available for the 16K TRS-80 (CS-3011), or the Sorcerer (CS-5007). List $14.95, sale price $11.95.

Other suppliers are raising the price on these programs to $19.95. Save 50% with this never-to-be-repeated offer while supplies last!

Apple II
CS-4011 Adventureland
CS-4012 Pirate Adventure
CS-4013 Mission Impossible
CS-4014 Voodoo Castle
Package price $39.95

Sorcerer
CS-5003 Adventureland
CS-5004 Pirate Adventure
CS-5005 Mission Impossible
CS-5006 Voodoo Castle
CS-5007 The Count
Package price $49.95

TRS-80
CS-3008 Pirate Adventure
CS-3010 Voodoo Castle
CS-3011 The Count

Package Price $26.95

TRS-80

Space Games includes Star Lanes, Romulan, Star Wars and Ultra Trek. Cassette (CS-3002) list $11.95, sale price $9.49

Strategy Games includes Evasion, Tunnel Vision, Motor Racing, Jigsaw, and The Masters One of our most popular cassettes! Cassette (CS-3005) list $11.95, sale price $9.49

Battle Games includes Gunner, Sub Hunt, Tank Battle, and Getacross. Rave reviews of this package Cassette (CS-3012) list $11.95, sale price $9.49

Deep Space Games includes three challenging games Space Lifeboat, Asteroids, and Galaxy I Cassette (CS-3013) list $11.95, sale price $9.49

Text Processing is a line-oriented simplified text editor for letters, documents, reports, etc Cassette (CS-3302) list $14.95, sale price $11.95

```
COMMANDS
C    CONTINUE LIST ON SCREEN
D    DELETE LINE
E    EDIT
I    INSERT LINE
K    RESUME EDITING
L    LIST ON SCREEN
P    PRINT HARD COPY
Q    QUIT PROGRAM
T    SAVE ON TAPE

COMMAND?
```

Checking Account is a home budgeting system that keeps track of individual checks, payees, etc Cassette (CS-3304) list $11.95, sale price $9.49

IQ Test is a valid 60 question IQ test with a machine language scoring routine that defies cheating Cassette (CS-3203) list $14.95, sale price $11.95.

TRS-80 Sale
Pick any four packages for $29.95. Take all seven for $49.00

SOL-20

Air Traffic Controller simulates, in real time, the actions and responsibilities of an air traffic controller. Cassette (CS-8001) list $11.95, sale price $9.50.

Space Games includes Asteroids, Lunar, Star Wars, and Romulan. Cassette (CS-8003) list $11.95, sale price $9.50.

Strategy Games includes Wumpus I, Wumpus II, Trap, Race and Kingdom. Our most popular Sol package. Cassette (CS-8004) list $11.95, sale price $9.50.

Reading Comprehension will help students to learn the skills needed to master good reading habits Available in a five-cassette package for $50.00, sale price $39.95.

Game Sale
CS-8001 Air Traffic Controller
CS-8003 Space Games
CS-8004 Strategy Games
Package price $24.95

APPLE Games Sale

Space Games-1 includes four games by Bob Bishop Saucer Invasion, Rocket Pilot, Star Wars, and Dynamic Bouncer Available in Integer and Applesoft version (CS-4001) list $11.95, sale price $9.49

Sports Games-1 includes Baseball, Breakout, Torpedo Alley and Darts Available in Integer version ONLY (CS-4002) list $11.95, sale price $9.49

Strategy Games includes Blockade, UFO, Skunk, Genius and Checkers. Available in Integer version ONLY (CS-4003) list $11.95, sale price $9.49

Brain Games includes Dodgem, Nuclear Reaction, Parrot, Dueling Digits, Midpoints, Lines, and Tones Available in Integer version ONLY (CS-4004) list $11.95, sale price $9.49

Haunted House is a nightmare simulation leaving you only six hours to find the secret passage leading out of the many room mansion. Available in integer version ONLY (CS-4005) list $11.95, sale price $9.49

Space Wars is a version of a classic MIT game redesigned for the Apple. Available in Integer and Applesoft version (CS-4009) list $14.95, sale price $11.95

Outdoor Games includes Forest Fire, Fishing Trip, Treasure Island I and Treasure Island II Available in Integer version ONLY (CS-4010) list $14.95, sale price $11.95.

Know Yourself includes Alcohol, Sex Role, Life Expectancy, Psychotherapy, and Computer Literacy Available in Integer version ONLY (CS-4301) list $11.95, sale price $9.49

INTEGER SALE
Pick any four tapes for $32.95. Pick any six tapes for $44.95. Take all eight cassettes for $54.95.

creative computing software

Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)

at those prices were flat and rectangular. The 3M filters are cut to the 'bulgy rectangle' shape of the screen, with rounded corners, and are also curved convexly to fit as closely as possible to the screen, for maximum legibility."

LPRINT a Picture

A short cassette program from En-Joy Computer Programs (P.O. Box 1535, Goleta, CA 93116) lets you do a screen print with your Model I Level-II disk or tape system.

For $5, you can LPRINT any graphics display on the screen, without the need for a screen printer such as Radio Shack's long-discontinued $599 model.

The program slowly scans the video memory, comparing adjacent pairs of graphics blocks. If both are on, an equal sign is printed. If only one of the pair is on, a single-quote is printed.

Numbers, and signs such as #$%*@, are printed as they appear in the display. The program should also print the alphabet as it appears in the display, but doesn't on my system, probably because of the Radio Shack lower-case modification.

Simply merge the short LPRINT A PICTURE tape program with your Basic graphics program. Then find the last program line used to make the picture, and add a GOSUB 1, to get to the screen-print routine.

Using this program, the small box (Dec. 1980, p. 194) created by the lines

```
110 PRINT @ 412, CHR$(183)
120 PRINT @ 413, CHR$(179)
130 PRINT @ 414, CHR$(179)
140 PRINT @ 415, CHR$(187)
```

is printed out as

```
====
I  I
====
```

which is a long way from the original display: a box of solid graphics blocks. But most printers don't have any characters that look like graphics blocks.

With large pictures, especially those with many diagonal lines, the printout may not look much like the original screen display, but $5 is a lot cheaper than a screen printer.

Video Worksheet

Another useful En-Joy product is the $3.95 video worksheet, similar to the one printed on page E/1 of the Level-II TRS-80 manual, except that this one is on clear plastic.

To the top and side margins have been added the decimal and hex video-memory locations. Also on the same plastic sheet is a chart that gives all 64 combinations of the six blocks making up the graphics characters.

The display area of the video worksheet is 7 1/2" wide, from X=0 to X=127. If your horizontal display measures close to 7 1/2", you can use this plastic worksheet to figure out the exact location of any point on the screen, using SET, PRINT @, or POKE.

On my screen, the width of the display area is only 7 3/16", a shrinkage of about four percent, which also affects the height of the display. This shrinkage is due to the low line voltage—in my case about 110 volts—available in New York City.

Ask for the En-Joy catalog; they have programs that display ukulele, banjo, mandolin or guitar chords in time with the music, to help you play along; a hand-sign display of the alphabet for the deaf; bartender, with 84 drinks; a medical-history program, et al.

Screen Printing

Some printers, such as Radio Shack's Line Printer II, include a black rectangle in their character set. In the case of the Line Printer II, this black block is decimal 127 (hex 7F) in ASCII code.

If you have a Line Printer II, or any other printer with a black rectangle you can call up with an ASCII code, you can do a screen print that looks more like the displayed original than with the En-Joy single-quotes and apostrophes.

Simply edit the En-Joy LPRINT A PICTURE program, changing the

```
LPRINT "="
```

and

```
LPRINT "'"
```

to

```
LPRINT CHR$(127)
```

which will, in the case of the four-line box program mentioned previously, print out

```
▮▮▮▮
▮  ▮
▮▮▮▮
```

The CRT displays a solid rectangle, but the printout isn't solid, because the printed block doesn't take up the full width and height of the printing position.

Note that while the top and bottom lines of the solid box on the screen are eight graphics blocks wide, the printed box is only four blocks wide. This is because the En-Joy program translates *pairs* of graphics blocks into single = or ' signs, which is required because two graphics blocks take up the same horizontal space as one printing character.

If the program didn't translate pairs of blocks into single printing characters, and if you printed out the box using eight black blocks horizontally, the box would take up twice as much space as it should.

Here's a program that will print the rectangular box with eight black boxes across:

```
1 FOR GY=0 TO 47
2 FOR GX=0 TO 127
3 IF GX=0 LPRINT
4 IF POINT(GX,GY)=-1: LPRINT
  CHR$(127);: NEXT GX,GY
5 IF POINT(GX,GY)=0: LPRINT
  " ";: NEXT GX,GY
6 RETURN
```

Merge this with the four-line box program, add

```
150 GOTO 1
```

to call up this brief screen-print routine, and the result will be

```
▮▮▮▮▮▮▮▮
▮      ▮
▮      ▮
▮▮▮▮▮▮▮▮
```

You've got as many horizontal blocks as in the screen original, but if you try to print a whole screenful of graphics, instead of just this small box, you'll run out of horizontal space on your printer.

So it's best to stick to the modified En-Joy LPRINT A PICTURE program.

Simple Word Processor

Thomas R. Walls sent this from Hialeah, Florida:

"I wrote this simple word-processing system for all the people still typing LPRINT.

"After the program is RUN, you select the cursor you prefer. Next you input the number of characters per line and set the margin.

"If your printer has upper/lowercase, you must use the SHIFT key to print in uppercase. An uppercase lock (SHIFT up-arrow) is provided. Press the up-arrow to return to lowercase. If you don't have upper/lowercase, you don't need the shift.

"At any time, you can backspace, or your can press @ to erase the entire line. By pushing SHIFT @ you can reselect your cursor. And by backspacing past the first column, you can reselect the number of characters per line and reset the margin.

"NOTE: SHIFT @ needs to be pressed twice because of the built-in feature: it has to stop program execution.

"P.S. I use a Model I and I don't know how this program will work on a Model III."

I'll bet that four out of five of you who try this program, will find that SHIFT @ doesn't allow you to "reselect your cursor." That's because you (and I) didn't take full notice of the REM on line 350. The @ on this line isn't the same @ as on line 340, because it's a SHIFT @. Gotcha!

Stop playing games and get organized.

You spent up to $2,500 on computer hardware to make your personal life easier. You didn't spend it just for fun.

Now there's GUARDIAN – the first microcomputer software program that can truly organize your life with ultimate ease and speed.

GUARDIAN is the only program that lets you make a single one-line data entry to remind you . . . for the rest of your life . . . of birthdays, oil changes, appointments and any other recurring events. Once an item and its frequency of recurrence is entered, you'll never have to worry about remembering again. Each morning you flip a switch, enter your personal code, and get an instant readout of everything you need to accomplish that day.

Plainly speaking, there's no need for special codes or computer language with GUARDIAN . . . you talk to it, and it talks right back in plain English. GUARDIAN even tells you how to enter data and correct errors with step-by-step on-line instruction through its built-in video display manual. The printed manual that comes with GUARDIAN is also complete and easy-to-understand.

Years Ahead

GUARDIAN lets you organize everything you need to do today for years to come. The single-line entries are easy to make, and can even be set to flag you several days in advance of the event.

Advance To Go

GUARDIAN is programmed to automatically advance and schedule appointments, PTA meetings, vacation schedules, tax deadlines and other activities indefinitely, until you cancel the entry. GUARDIAN's internal calendar adjusts itself from year to year.

GUARDIAN

Protects Your Interests

GUARDIAN is as easy to use as pencil and paper, but its memory can't be lost or erased by accident. System failure and operator error are protected by automatic file closure. Password protection keeps your files confidential.

GUARDIAN's disk has the storage capacity to organize up to 2,000 separate events for 200 people at the same time.

The GUARDIAN program is recommended for use with any soft disk drive system with 48k memory or more, and operates on any CP/M*-based system or the TRS 80** (Model I, II or III). Programs are available on standard 5¼"- or 8-inch disk, with storage sleeve **$119.95.**

GUARDIAN is available directly from Time Management Software, and is not sold through any store, catalog or other source. To order GUARDIAN call one of our toll-free numbers or return the order blank below.

Call now toll free to order (Ask for operator 601)

1-800-824-7888 (nationwide, except California, Alaska and Hawaii)

1-800-852-7777 (in California)

1-800-824-7919 (in Alaska and Hawaii)

VISA



Yes . . . I want to put GUARDIAN to work for me, to receive maximum efficiency and ease in organizing my personal life with my microcomputer

NAME _____

ADDRESS _____

CITY _____ STATE _____ ZIP _____

I have enclosed $119.95 to avoid delays and handling charges.

☐ Check ☐ Money Order Price includes tax, handling and shipping (except C.O.D. Orders)

☐ C.O.D. (If delivery address is different than above, please specify)

_____

Please specify one: ☐ 5¼-inch disk ☐ 8-inch disk **11-F1**

Please specify one: ☐ CP/M* Operating System ☐ TRSDOS** Operating System

TIME MANAGEMENT SOFTWARE™

123 E. Broadway
P.O. Box 727
Cushing, Oklahoma 74023

* Registered Trademark of Digital Research Inc. ** Registered Trademark of Tandy Corp.

CIRCLE 279 ON READER SERVICE CARD

TRS-80, continued...

```
100 CLEAR 500: CLS: PRINT @ 74, "TRS-80 WORD PROCESSOR"
110 PRINT @ 266, "PLEASE SELECT CURSOR:": PRINT
120 PRINT TAB(15) "1 ": PRINT TAB(15) "2 ": PRINT TAB(15) "3 "
130 POKE 15768,31: POKE 15832,30: POKE 15896,143
135 GOTO 180
180 A$=INKEY$: IF A$="" THEN 180
190 IF A$="1" THEN 210
193 IF A$="2" THEN 220
196 IF A$="3" THEN 230
200 GOTO 180
210 CH=95: POKE 19000,95: GOTO 240
220 CH=94: POKE 19000,94: GOTO 240
230 CH=143: POKE 19000,143: GOTO 240
240 CLS: INPUT "MAX PRINTER LINE LENGTH"; L
250 CLS: INPUT "LEFT / RIGHT MARGIN"; M
260 CLS: PRINT "READY": FOR N=1 TO 200: NEXT: CLS
270 C=-1: S=-1: B$="": A$="": CLS
280 CH=PEEK(19000): C=C+1: B$=B$+A$
290 PRINT @ 128, B$; CHR$(CH)
300 PRINT @ 40, "SPACE LEFT"; L-C-M
310 IF C>=L-(2*M) PRINT @ 30, "MARGIN"; ELSE PRINT @ 30, "      ";
320 IF C=L-M THEN 440
330 A$=INKEY$: IF A$="" THEN 330
340 IF A$="@" THEN 270
350 IF A$="@" THEN 100: REM  SHIFT @
360 IF S=1 THEN 380
370 IF (ASC(A$)<91)*(ASC(A$)>63) THEN A$=CHR$(ASC(A$)+32): GOTO 280
380 IF (ASC(A$)<128)*(ASC(A$)>95) THEN A$=CHR$(ASC(A$)-32): GOTO 280
390 IF ASC(A$)=27 PRINT @ 0, "SHIFT";: S=1: A$="": GOTO 330
400 IF ASC(A$)=91 PRINT @ 0, "     ";: S=-1: A$="": GOTO 330
410 IF ASC(A$)=13 THEN 490
420 IF ASC(A$)=8 THEN C=C-2: ON ERROR GOTO 500: Z=LEN(B$)-1: B$=LEFT$(B$,Z): A$=
"": GOTO 280
430 GOTO 280
440 PRINT @ 0, "END OF LINE.   PRINT (P) OR ERASE (E)?"
450 P$=INKEY$: IF P$="" THEN 450
460 IF P$="P" THEN 490
470 IF P$="E" THEN 270
480 GOTO 450
490 LPRINT TAB(M) B$: GOTO 270
500 CLEAR 500: GOTO 240
```

When you've filled a line, you can erase it with an E, or print it with a P. To print a line before filling it completely, just hit ENTER: to erase an incomplete line, hit @.

Because of all the computations and decisions involved between keystrokes, you can't type much faster than about 40 words a minute with this program. Any faster and you'll lose letters.

The original program put a box around the first display, and a smaller box around the three types of cursors. The boxes have been eliminated in this renumbered and slightly reworked version, because they take up a lot of program space, even though they do dress up the display.

However, this is the kind of program that can be expanded in various ways, to add default values for cursor type, printer line length, and margin setting, for example.

Statistical Analysis Level-I

Radio Shack's RSC-5 catalog lists six Model-I Level-I programs, including Statistical Analysis Level-I. There is a Level-II Advanced Statistical Analysis package, but it's on disk. So if your input is limited to cassette and you want to get into statistical analysis, simply run the Level-I program with the Program Conversion tape packed with each Level-II machine.

Load the conversion tape, which will display

LOAD TAPE & PRESS ENTER

so you put the stats tape in the cassette recorder, and the conversion program inputs the tape. When finished, the screen says

PRESS ENTER TO BEGIN

and after a pause, displays

CONVERSION COMPLETE
PRESS ENTER TO CONTINUE

and when you do, you get READY, and you're all set to RUN.

The $29.95 Statistical Analysis system consists of eight programs, loaded in four cassettes and described in a 42-page manual, all packaged in a three-ring binder.

The manual, which takes the user through each program step by step, provides the details of the five programs for describing data sets and conducting data analyses (Descriptive Statistics, Histogram, T-Test, Simple Correlation, Linear Regression), two utility programs for preparing, updating and listing data files stored on tape (Data-File Preparation, Data-File Lister), and a program that helps select data samples (Random Sample).

Appendix A shows that, with 4K of RAM memory, the maximum data-set size is 400 elements for the first three programs, and 200 pairs for the following two. With 16K, the maximum is over 3,400 elements and over 1,700 pairs, respectively.

Although four of the five programs get into areas I don't pretend to understand, the Histogram program is fairly simple. You enter data from a data file on tape, or from the keyboard—and get a BS ERROR on trying to enter the twelfth data value. So you add a DIM statement, and continue.

Several SN errors pop up next, due to semicolons in PRINT @ statements. Change the semicolons to commas, and continue.

The bar-chart display, which is quite elegant, has a couple of odd little glitches, so here's your chance to debug the conversion further, en route to statistical analysis.

Short Program #23: Drunk Snake

Robert Hankins sent a program that "produces an interesting pattern of wavy lines, and which runs on Level I or II":

```
10 FOR X=10 TO 15
20 PRINT TAB(X) "xxx"
30 NEXT X
40 FOR X=15 TO 10 STEP -1
50 PRINT TAB(X) "xxx"
60 NEXT X
70 GOTO 10
```

The three-asterisk-wide pattern seems to weave back and forth like a drunk snake. It's an optical illusion, as you'll find out if you try to increase the number of asterisks; three is just the right number to maintain the illusion.

The illusion is also destroyed if you try to make the "snake" weave over a larger path by significantly increasing the 15 in lines 10 and 40. At 15, the snake really wiggles; at 20, he begins to show he's just a string of diagonal lines.

Bob didn't put his address on his letter. It may have been on the envelope, but sometimes envelopes get discarded when letters are forwarded to me. □

"Do you sell those pocket computers?"

Sourcebook of Ideas

Many mathematics ideas can be better illustrated with a computer than with a text book.



Consider Baseball cards. If there are 50 cards in a set, how many packs of bubble gum must be purchased to obtain a complete set of players? Many students will guess over 1 million packs yet on average it's only 329.

The formula to solve this problem is not easy. The computer simulation is. Yet you as a teacher probably don't have time to devise programs to illustrate concepts like this.

Between grades 1 and 12 there are 142 mathematical concepts in which the computer can play an important role. Things like arithmetic practice, X-Y coordinates, proving geometric theorems, probability, compounding and computation of pi by inscribed polygons.

Endorsed by NCTM

The National Council of Teachers of Mathematics has strongly endorsed the use of computers in the classroom. Unfortunately most textbooks have not yet responded to this endorsement and do not include programs or computer teaching techniques. You probably don't have the time to develop all these ideas either. What to do?

For the past six years, *Creative Computing* magazine has been running two or three articles per issue written by math teachers. These are classroom proven, tested ideas complete with flowcharts, programs and sample runs.

Teachers have been ordering back issues with those applications for years. However, many of these issues are now sold out or in very short supply.

So we took the most popular 134 articles and applications and reprinted them in a giant 224-page book called *Computers in Mathematics: A Sourcebook of Ideas.*

Ready-to-use-material

This book contains pragmatic, ready to use, classroom tested ideas on everything from simply binary counting to advanced techniques like multiple regression analysis and differential equations.

The book includes many activities that don't require a computer. And if you're considering expanding your computer facilities, you'll find a section on how to select a computer complete with an invaluable microcomputer comparison chart.

Another section presents over 250 problems, puzzles, and programming ideas, more than are found in most "problem collection" books.

Computers in Mathematics: A Sourcebook of Ideas is edited by David Ahl, one of the pioneers in computer education and the founder of *Creative Computing.*

The book is not cheap. It costs $15.95. However if you were to order just half of the back issues from which articles were drawn, they would cost you over $30.

Satisfaction Guaranteed

If you are teaching mathematics in any grade between 1 and 12, we're convinced you'll find this book of tremendous value. If, after receiving it and using it for 30 days you do not agree, you may return it for a full refund plus your return postage.

To order, send your check for $15.95 plus $1.00 postage and handling to Creative Computing Press, Morris Plains, NJ 07950. Visa, MasterCard, and American Express orders may be called in toll-free to 800-631-8112 (in NJ 201-540-0445). School purchase orders should add an additional $1.00 billing fee for a total of $17.95.

Don't put it off. Order this valuable sourcebook today.

creative computing

Morris Plains, NJ 07950
Toll-free **800-631-8112**
(In NJ 201-540-0445)
CIRCLE 300 ON READER SERVICE CARD

ns...puzzles & problems...pu

Merlin's first Annual Summer Puzzle Contest is over and the final winners have been selected by our board of judges. As we mentioned back in the June issue each winner will receive an autographed copy of *Merlin's Puzzler, Merlin's Puzzler 2, Merlin's Puzzler 3* and *The Clue Club*, all by yours truly, and a copy of *Computer Coin Games* by Joe Weisbecker.

Congratulations!!! We want to thank everyone that entered the contest. To those of you that did not win, take heart, Merlin may still use your puzzle later on and send you a copy of one of his books. We would also like to thank those of you that have taken the time to tell us how much you enjoy Merlin's puzzle pages each month.

And now, the winning puzzles:

Potted Problem

Our first winner is Mr. Rick Olcott from Memphis, Tennessee. Mr. Olcott wrote a series of puzzles for the house bulletin of the Mid-South Aquarium Society between 1972 and 1977 and he was kind enough to send them along to us. His puzzles all have a fishy flavor to them and we have selected the following "Potted Problem" to receive our award:

"Millard Fillbert bought a set of nesting clay pots for the waterfall rock garden he's installing in his back bedroom, and he told us that all three of the smaller pots together hold exactly as much water as the largest pot by itself. The pots are all square-bottomed, fit exactly together, and have walls and bottoms exactly one inch thick. If the smallest pot has a 6" inside edge, how much water do all the pots hold?



Cornered

Next is an interesting chessboard puzzle from Mr. Max Vrugt of Kingston, N.Y. He writes:

"I have a chessboard and 32 domino pieces. Each domino piece has the size of 2 fields of the chessboard. The 32 pieces will cover the board completely. Now I cut 2 opposite corner fields out of the chessboard. Can I still cover the board completely with 31 domino pieces?



A Punctuation Problem

Another winner is Mr. Ed Konowal of Fort Myers, Florida. You get only one chance at solving it.

"All the following sentence needs is a little punctuation to make it understandable:

THAT THAT IS IS THAT THAT IS NOT IS NOT IS THAT IT THAT IS IT.

A Matchless Puzzle

From across the sea comes our next winner. Mr. Alexander E. Yagupsky of The Hague, Holland has propounded the following puzzle:

"Forty-eight matches are divided into three piles of different amounts. If we take from the first pile the amount of matches that are in the second pile and place them with the second pile, if we then take from the second pile the amount that is in the third pile and add it to the third pile, and if we then take from the third pile the amount of matches that reside in the first pile and place them in the first pile, all three piles will have the same amount of matches; that is, 16 (48/3 = 16).

How many matches were there originally in each of the three piles?"

The Problem of the Burning Candles

Mr. Murray Hayman of Silver Spring, Maryland, is our next winner. He writes:

"There are 2 candles, and one is 1 inch longer than the other. One is lit at 7:30 A.M. and the other at 8:00 A.M. Later, at 12:00 noon, they are both the same size. At 4:30 P.M. the first one goes out and at 6:00 P.M. the second one goes out. How long were the candles before they were lit?"

T	I	M	E
W	A	R	P

The Star Trek Puzzle

Hop into hyperspace with this winner from an old contributor, Mark Kantrowitz of Brookline, Mass. Mark has given us a Change-The-Word-Puzzle to solve. You must change the word TIME to the word WARP in 4 moves. (During each step the puzzler must change *one letter* in the *previous word* so that a new word is formed. Keep the good work, Mark!

Another True or False Puzzle

Yes, Edward Wellen of New Rochelle, New York, has come up with another variation of the popular "Who's telling the truth and who's lying" type of puzzle. Well done Edward. His story goes like this:

"On the island of Ambivia the natives come in two hues — orange and purple. The Oranges always lie, the Purples always tell the truth. At dusk you row towards the beach, where you dimly see three figures. You shout to them: "Are you Orange or Purple?" One answers, but the tropical breeze blows the words away. A second one calls: "He says he's Purple, and he is Purple, and so am I." The third one calls: "He's Orange, but I'm Purple." What's the color of each of the three?"

What Comes Next?

Susan de Guardiola of Dallas, Texas, sends us an interesting "What Comes Next", or, fill in the blank type of puzzle. In this problem the puzzler is given a list of words. After looking the list over you must supply the next logical word that should be added to the end of the list. As always these puzzles teach us to look at a problem in more than one way. Our thanks go out to Susan for sharing this problem with us. The list of words is:

Hard, Soft, Joy, Thin, Grief, Green, Brittle, Humor, Aqua, Sour, Heavy . . .

A Counter Problem

Mr. Sheppard Yarrow of Derwood, Maryland, is our next winner. He tells us about a conversation partly overheard at the counter of a hardware store. The conversation went as follows:

"How much will one cost?"
"Twenty cents," replied the clerk in the hardware store.
"And how much will twelve cost?"
"Forty cents."
"Okay. I'll take nine hundred and twelve."
"That will be sixty cents."

The puzzle is, what was the customer buying?

An Ageless Problem

Our last winner is Scot Shinderman of Commack, New York. Scot sends us a problem involving ages that can be solved with the application of a little simple algebra (those are Scot's words). As Scot tells it:

"Mary is 24. If Mary is twice as old as Ann was, when Mary was as old as Ann, how old is Ann now?"

I hope that you all have enjoyed the puzzles we selected as the winners of "Merlin's First Annual Puzzle Contest". Here's a final puzzle from Merlin called:

A Loopy Problem

You should have a lot of fun with this puzzle. Form a one-inch wide loop of stiff paper. Place this loop on top of an empty milk bottle (or glass jar). On top of the loop, directly over the mouth of the bottle, place a dime. Your problem is to get the dime into the bottle. When doing this you are only allowed to touch the paper loop. You are also only allowed to use one hand while solving this puzzle. Also, you cannot pick the paper loop up with your fingers. (From *Merlin's Puzzler 3* by Charles Barry Townsend, Published by Hammond, Inc.) Answers on p. 286.

Well, that does it for now. I certainly enjoyed putting this issue together. If you have a puzzle or two that you would like to share with us please send it along. If Merlin uses it he will send you one of his puzzle hooks. Just address your letter to Charles Barry Townsend, 32 Hickory Drive, Maplewood, New Jersey 07040.

Until next month, good luck, and, good puzzling.

Charles Barry Townsend

m...software legal forum...s

Barry Bayer

Starting with this month's Forum, there will be several articles written by Barry Bayer from the viewpoint of a software purchaser who has had problems with the product purchased. Mr. Bayer is an attorney who practices general law in the Chicago area. – H.N.

As regular readers of this column are aware, I have long been of the opinion that microcomputer software users often come out on the short end of the stick because of unfair warranty and support policies instituted by software publishers, because of the great distance between the typical user and the typical publisher, and because of the small amount of money involved (relative, at least, to the great cost of retaining an attorney to do anything to enforce your legal rights). It is difficult to do anything about the distance (although a legal gimmick commonly called "long arm jurisdiction" may sometimes help) and next to impossible to do anything about legal fees (although another legal gimmick known as the "class action" may have some applicability).

The purpose of these remarks, therefore, is to define the relationship between the software vendor and the purchaser when there is no signed agreement, and to suggest agreements that software publishers should be expected to offer to customers who, in good faith, spend $25 to $300 for programs to play the latest game, or organize their accounts receivable. I claim no originality for any ideas presented, but readers who have never attended a law school "Contracts" course may consider this of some use.

I will be using some real examples of software advertising and documentation. But because these examples are typical and not unusually evil, it is, perhaps, unfair to single out the specific publisher involved, therefore names will be omitted. It is sufficient to say that any example used will be from a product that has been advertised in these pages, possibly in this very issue.

I will ignore the potential problems that exist because a purchaser will typically deal with a retailer and not the publisher. It will always help to deal with a reputable local retailer who will take back a product that just does not work, notwithstanding the difficulties he might have with his distributor or the publisher. It has been my experience that such retailers do exist, but may be hard to find. With the ground rules out of the way, let's begin.

I walk into a computer store, hand a clerk $100 and walk out with a receipt and a heavily advertised XYZ management and analysis package, with shrink wrap surrounding its rich looking leatherette binder. Although not one word was said about warranties or program performance, a state law, the Uniform Commercial Code, adopted almost everywhere but Louisiana sets out these provisions. (See Appendix.)

Because the product was sold by a merchant, and there was no agreement that the implied warranties would not be included in the transaction, the Seller warranted that the product was "merchantable," that is, that it is of a condition that is considered generally saleable in the business community selling that type of goods. I would think, at a minimum, that this implied warranty would include a warranty that the disk would boot, and that the program would run without crashing under normal circumstances, that it would accept reasonable input, and send reasonable output. You (or a court) might come to a different conclusion.

Let's add some facts. Assume that I walk into the store, and tell the proprietor of my intended application, and ask him to suggest a good program to suit my application. If he, as an expert in the microcomputer field, suggests and sells me the XYZ package, knowing my intended use and that I rely on his expertise, he has made an implied warranty of fitness for a particular purpose, pursuant to Section 2-315 of the UCC.

This warranty means exactly what it says. The Seller is making a statement that the program will do what I told him it would do. This warranty can be much stronger than the implied warranty of merchantability.

Applewriter, for example, is a "merchantable" word processor, but it would not fit for my purpose of writing scholarly articles with footnotes requiring superscripts and would not interface with my printer which uses proportional microspacing. If I had asked the Seller for a word processor that would do all these things, there would be an implied warranty of fitness that the program sold to me would do them.

In order to take advantage of this warranty of fitness for a particular purpose, you should tell the Seller as much as you can about your application, and about the hardware you will run it on. Incidentally, this also happens to be the best way to make the best use of the Seller who knows his stuff.

Let's change the first example just a bit more. Instead of asking the Seller for advice, I carefully studied the advertisements in *Creative Computing*, and went to purchase the program because of the store's advertising that the program would handle 20,000 separate inventory items, and find any one of them in .6 seconds with only one disk drive. A good case can be made that I can take advantage of the store's expressed warranty that the program

Retail Roster



CALIFORNIA

Advance Data Concepts—2280 Diamond Blvd., Concord, 94520; (415) 671-9016. 9-5 Mon-Fri. Vector-Graphic, CP/M Software Headquarters-User's Group.

D.E.S. Data Equipment Supply—8315 Firestone, Downey 90241. (213) 923-9361. 7 days. Commodore PET specialists. Hardware Software, Books, Mags, Supplies, In House Maintenance.

CONNECTICUT

Computerworks—1439 Post Rd., East Westport 06880; (203) 255-9096. 12-6 Tues-Fri, 12-9 Thu, 10-5 Sat.

GEORGIA

Atlanta Computer Mart—5091 Buford Hwy, Atlanta 30340; (404) 455-0647. 10-6 Mon-Sat

ILLINOIS

Computer Land/Downers Grove—136 Ogden Ave., Downers Plaza 60515; (312) 964-7762. 10-6 Mon.-Sat., 10-8 Tue., Thurs. Apple, Atari, Osborne Zerox, Vector.

Data Domain of Schaumburg—1612 E. Algonquin Rd., Schaumburg 60195; (312) 397-8700. 12-9 Tues-Fri, 11-5 Sat. Apple, Alpha Micro, Hewlett-Packard Calculators. Largest book and magazine selection.

Farnsworth Computer Center—1891 N. Farnsworth Ave., Aurora, IL 60505; (312)851-3888. 10-8 Mon-Fri, 10-5 Sat. Apple, Hewlett-Packard series 80 systems, HP Calculators, IDS Printers.

Gavin Computers—5935 W. Addison St., Chicago; (312) 286-4232. Mon.-Thurs. 9-8:30, Tues.-Sat. 9-6. Apple B & H, Atari & Commodore Systems.

Lillipute Computer Mart, Inc.—4446 Oakton, Skokie 60076; (312) 674-1383. M-F 10:30-8 pm, Sat 10-6. We sell Cromemco, Gimix, Bell & Howell, NorthStar and others. Starting our fifth year in business.

To include your store in Creative Computing's *Retail Roster, call the Advertising Department at (201) 540-9168*

Video Etc.—465 Lake Cook Plaza, Deerfield 60015; (312) 498-9669; Open Everyday. Strong software support for Apple, Atari.

The Video Station—872 So. Milwaukee Ave., Libertyville; (312) 367-8600. Open 7 days. Atari Computers, Hardware and Software.

MASSACHUSETTS

Neeco—679 Highland Ave, Needham 02194; (617) 449-1760. 9-5:30 Mon-Fri. Commodore, Apple, Superbrain, Atari

Science Fantasy Bookstore—18 Eliot St., Harvard Sq., Cambridge 02138; (617)547-5917. 11-5 Mon-Sat, 11-8 Thur. Apple & TRS-80 games; Epyx, Microsoft, Creative Computing.

MICHIGAN

Upstate Computer Shop—629 French Rd., Campus Plaza, New Hartford 13413; (315) 733-9139: Mon—Fri 10—6, Sat 11—5. Apple—Commodore—Data General.

Computer Center—Garden City; (313) 425-2470 & West Bloomfield; (313)855-4220; Books, Magazines, Hardware and Software for Apple, Northstar, TRS-80 & PET.

NEVADA

Home Computers—1775 E Tropicana #6, Las Vegas 89109 (702) 798-1022. 10-7 Mon-Sat. Apple, Commodore, Atari, AIM 65. (Books) Sales & Service

NEW JERSEY

Computernook—Rt. 46, Pine Brook Plaza, Pine Brook 07058; (201) 575-9468. 10-6:30 MTWS, 10-8 Thurs., Fri. Apple/Commodore Authorized dealer.

Stonehenge Computer Corp. — 89 Summit Ave., Summit 07901; (201) 277—1020. 10 am— 6 pm Mon.— Fri. Apple/Bell & Howell/Cannon/ Authorized Dealer, Sales and Service.

Software City — Pine Brook, 101 Rt. 46 East, 07058; (201) 575—4574. Bus/Rec Utility/Home Programs for TRS—80, Atari, Apple and PET. 10—25% off list.

Software City — River Edge, 111 Grand Ave., 07661; (201) 342—8788. Bus/Rec/ Utility/Home Programs for TRS—80, Apple, Atari and PET. 10—25%off list.

NEW YORK

Programs Uniimited—20 Jericho Turnpike, Jericho, NY 11753; (516)333-2266. 10-8 Mon-Sat. The largest microcomputer software selection available.

The Computer Center—31 East 31st St., New York 10016; (212)889-8130. 10-7 Mon-Fri, 11-6 Sat, 10-8 Thur.

Upstate Computer Shop—629 French Rd., Campus Plaza, New Hartford 13413; (315)733-9139. 10-6 Mon-Fri, 11-5 Sat. Apple—Commodore—Data General.

OHIO

Abacus II—1417 Bernath Pkwy , Toledo 43615; (419) 865-1009.

Micro Mini Computer World—74 Robinwood Ave., Columbus 43213; (614) 235-5813/6058. 11-7 Tues-Sat. Authorized Apple/Commodore dealer. Sales, Service, Business Software.

North Coast Computers — 626 Dover Center, Bay Village 44140; (216)835—4345; 10—6 Mon.—Fri., 10—8 Tues., Thurs., 9:30—5 Sat. Apple/Atari/Vector Graphics/Data General.

WISCONSIN

Petted—4265 W. Loom's Rd. (I-894-Hwy 36, Milwaukee 53221; (414)282-4181. 12-8 Mon-Fri, 10-4 Sat. Authorized Commodore PET, CBM, VIC dealer. Books, Magazines, Chips, etc.

Forum, continued...

will do exactly what the advertising states. Such an action gives rise to a warranty by description or model, pursuant to Section 2-313 of the Uniform Commercial Code.

So we have three types of warranties that are possible without anyone specifically using the language "I warrant...":

1. Implied warranty of merchantability;
2. Implied warranty of fitness for a particular purpose; and
3. Express warranty arising out of advertising, example or model.

That's good for the purchaser, and I wish I could end this article right here. Unfortunately, I forgot to tell you what actually happened in the first example. The Seller told me that he wasn't sure if the program would work for my purpose. In fact he doubted that it would work at all. Actually, he refused to sell the program to me unless I signed an agreement stating:

"Seller makes no warranties, either express or implied, with respect to the XYZ data package, its quality, performance, merchantability, or fitness for any particular purpose. This software is sold "as is." The entire risk as to its quality and performance is with the buyer. Should the program prove defective following its purchase, the buyer, and not the seller, assumes the entire cost of all necessary servicing, repair, or correction and any incidental or consequential damages. In no event will the seller be liable for direct, indirect, incidental, or consequential damages resulting from any defect in the software, even if seller has been advised of the possibility of such damages. Some states do not allow the exclusion or limitation of implied warranties or liability for incidental or consequential damages, so the above limitation or exclusion may not apply to you."

Now I suggest that you save this paragraph, because it not only seems to take away the implied warranties that were so helpfully supplied by the UCC, but also contains limitations on damages and some language required by federal law called the Magnusson-Moss Consumer Warranty Act. And these are all topics that we will discuss in future columns. At this point I will say nothing more than if I signed the agreement as part of a contract of purchase of the XYZ package, it is very likely that I would be without any recourse if I walked home, and the program didn't boot, or if it booted, but just didn't work the way the advertising said it would. The tough question is: What happens if I never sign the agreement, and never even see the agreement until I get home and cut through the shrink wrap? And that's a very real question, because that paragraph is copied (with only names removed) from the pages of a well known software manual.

Appendix

Excerpted from the Uniform Commercial Code

Sec. 2-313. Express Warranties by Affirmation Promise, Description, Sample.

(1) Express warranties by the seller are created as follows:

a) Any affirmation of fact or promise made by the seller to the buyer which relates to the goods and becomes part of the basis of the bargain creates an express warranty that the goods shall conform to the affirmation or promise.

(b) Any description of the goods which is made part of the basis of the bargain creates an express warranty that the goods shall conform to the description.

(c) Any sample or model which is made part of the basis of the bargain creates an express warranty that the whole of the goods shall conform to the sample or model.

(2) It is not necessary to the creation of an express warranty that the seller use formal words such as "warrant" or "guarantee" or that he have a specific intention to make a warranty, but an affirmation merely of the value of the goods or a statement purporting to be merely the seller's opinion or commendation of the goods does not create a warranty.

Sec. 2-314. Implied Warranty: Merchantability; Usage of Trade.

(1) Unless excluded or modified, a warranty that the goods shall be merchantable is implied in a contract for their sale if the seller is a merchant with respect to goods of that kind. Under this section the serving for value of food or drink to be consumed either on the premises or elsewhere is a sale.

(2) Goods to be merchantable must be at least such as

(a) pass without objection in the trade under the contract description and

(b) are fit for the ordinary purposes for which such goods are used; and

(c) run within the variations permitted by the agreement of even kind, quality and quantity within each unit and among all units involved; and

(d) conform to the promises or affirmations of fact made on the container or label if any.

(3) Unless excluded or modified, other implied warranties may arise from course of dealing or usage of trade.

Sec. 2-315. Implied Warranty: Fitness for Particular Purpose.

Where the seller at the time of contracting has reason to know any particular purpose for which the goods are required and that the buyer is relying on the seller's skill or judgment to select or furnish suitable goods, there is unless excluded or modified under the next section an implied warranty that the goods shall be fit for such purpose. □

Bit Pit

Chas Andres



We dare you.



We dare you to ship out on our tall ships to the Caribbean.

We dare you to take the helm of our 258' Polynesia or our 198' Yankee Clipper. Sleek sailing ships out of another age once owned by Onassis, Vanderbilt, and the Duke of Westminster.

We dare you to set foot on small, far away islands like Saba, Carriacou, Anegada. And we dare you to walk the footsteps of Captain Bligh, Columbus and Nelson on uninhabited tropic beaches.

We dare you to get down to your bikini and shorts and have a love affair with the sun. To take each day as it comes, sip Bloody Marys in the morning and take your ration o' grog when the sun slips down the mast.

We dare you to step out with the moon. Feel the throbbing of the steel drums. We dare you to limbo, calypso and goombay. And we dare you to fall asleep under a star-filled sky.

We dare you to snorkel amidst a rainbow of tropical fish, and to swim in waters so clear you can see 20 feet down.

We dare you to ship out with an adventurous group of guys and gals for 6 or 14 days. Your share from $400.

We dare you to set sail to another time, another land. To do all the things you have always wanted to do.

Then we dare you to tell us that Windjammin' was something besides the greatest vacation in your life.

Windjammer Barefoot Cruises
Post Office Box 120, Miami Beach Florida 33139 | 305 373-2090

Capn Mike
Windjammer Barefoot Cruises
PO Box 120, Dept 199, Miami Beach, Florida 33139
For Reservations Call TOLL FREE 1-800-327-2600

Might take your dare
Send my free full color Great Adventure Booklet on the 6 and 14 day cruises to the Caribbean and West Indies

Name _____ Address _____

City/State/Zip _____



ucts...new products...new

COMPUTERS

DESKTOP COMPUTER FROM IBM

IBM has announced a desktop business computer that combines data processing and word processing in a system designed for first-time users.

IBM System/23 Datamaster can include two computer workstations, which permit two people to use the system simultaneously.

The Basic language used by Datamaster is compatible with the Basic available on IBM's System/34.

The computer's processing unit features single or dual integrated disk drives with storage capacity from 0.3 megabytes to 2.2 megabytes which may be expanded with an optional disk unit to provide maximum storage of up to 4.4 megabytes.

The workstation will display up to 1,920 characters on a 12" screen and has main memory capacity of up to 128K in 32K increments.

A full-function data processing installation, with a single computer workstation and an 80 character-per-second printer, will cost $9,830.

IBM, General Systems Division, Attn: Bob Murphy, 5775 East Glen Ridge Dr., Atlanta, GA 30328.

CIRCLE 351 ON READER SERVICE CARD

PMC-81: TRS-80 "WORK-ALIKE"

Personal Micro Computers has added the PMC-81 to its TRS-80 Model I work-alike product line.

The PMC-81 has 16K of memory, 14K of ROM, uses a Z-80 microprocessor and provides a keyboard, cassette interface and video monitor interface in the unit. It uses the EXP-100 Expander to add interfaces for minifloppy disks, printer, RS-232C and S-100 bus.

The PMC-81 has a complete professional keyboard with lower case letters and true descenders provided as standard, as well as a 15-key numeric pad and four function keys. $939.

Personal Micro Computers, Inc., 475 Ellis St., Mt. View, CA 94043. (415) 962-0220.

CIRCLE 352 ON READER SERVICE CARD

MULTITASKING MICROCOMPUTER

A multi-tasking desktop microcomputer has been introduced by the TRW-Fujitsu Company.

Designated Affinity 16, the computer will operate as a stand-alone unit, on-line to a central computer or in a network environment, and can perform batch, on-line or distributed processing applications.

The central processing unit includes a 16-bit microprocessor and 128K bytes of memory. Two minifloppy disk drives can each record 320K on two dual-sided, double-density disks. Up to 2.5 megabytes of auxiliary disk storage is available with an 8" floppy disk drive unit.

The CRT display features a 12", 1920-character screen, 192 display patterns and versatile display functions. The full ASCII keyboard includes alphanumeric keys, ten-key, and 12 programmable function keys.

Prices will be in the $6,000 to $10,000 range.

The TRW-Fujitsu Company, 9841 Airport Blvd., Suite 620, Los Angeles, CA 90045. (213) 535-3821.

CIRCLE 353 ON READER SERVICE CARD

META TECHNOLOGIES

26111 Brush Avenue, Euclid Ohio 44132
CALL TOLL FREE 1-800-321-3552 TO ORDER
IN OHIO, call (216) 289-7500 (COLLECT)

1001 THINGS TO DO WITH YOUR PERSONAL COMPUTER

BY MARK SAWUSCH

333 pages $7.95

333 pages, written in simple terms, of "what-to-do" and "how-to-do-it". Suitable not only for microcomputers, but for programmable calculators as well. Includes program listings, formulas, a glossary of computer terms and more! Definitely a MUST BUY!

A PARTIAL LIST OF APPLICATIONS

Real Estate Evaluation	Test Your Typing Speed
Astrology	Finances & Investments
Income Tax	Biorythm
Speed Reading	Energy Efficiency
Personality Test	Antenna Design
Statistical Analysis	Letter Writing
Logic Circuit Analysis	Recipe Index/Calculator
Carpenter and Mechanic's Helper	
General Purpose Clock Timer	

"OTHER MYSTERIES" VOLUME III

by Dennis Kitsz

Call now and place your order for this new book, "THE CUSTOM TRS-80™ & OTHER MYSTERIES", from IJG, Inc. More than 300 pages, with over 60 photographs, of projects for the hardware hobbyist. Includes schematics, PC layouts, software driver code, etc. for such do-it-yourself undertakings as high resolution graphics, reverse video, real-time clock/calender, music synthesis, ROM/RAM additions and more!

THE CUSTOM TRS-80™ $29.00
CALL FOR AVAILABILITY

MICROPARAPHERNALIA

NEWDOS by APPARAT

NEWDOS/80 by Apparat $149.95
NEWDOS + to NEWDOS/80 UPGRADE ..... CALL
NEWDOS + with ALL UTILITIES
35-track $69.95
40-track $79.95

BOOKS

TRS-80™ DISK AND OTHER MYSTERIES .. $19.95
MICROSOFT™ BASIC DECODED $29.95

Let your TRS-80™ Teach You

ASSEMBLY LANGUAGE

REMSOFT's unique package, "INTRODUCTION TO TRS-80™ ASSEMBLY PROGRAMMING" includes ten 45-minute lessons on audio cassettes, a display program for each lesson providing illustration & reinforcement, and a text book on TRS-80™ Assembly Language Programming. Includes useful routines to access keyboard, video, printer and ROM. Requires 16K - Level II, Model I.

REMASSEM-1 ..... $69.95
FOR DISK SYSTEMS $74.95

Let your TRS-80™ Teach You

ASSEMBLY LANGUAGE DISK I/O TECHNIQUES

REMSOFT does it again! REMDISK-1 is a concise, capsulated supplement to REMASSEM-1. Package consists of two 45-minute lessons on audio cassettes, and display programs providing illustration and reinforcement. Provides specific track and sector I/O techniques, and sequential and random file access methods and routines.

REMDISK-1 ..... $29.95

Let your TRS-80™ Test Itself With

THE FLOPPY DOCTOR & MEMORY DIAGNOSTIC

by DAVE STAMBAUGH

A complete checkup for your Model I. THE FLOPPY DOCTOR completely checks every sector of 35- or 40-track disk drives. Tests motor speed, head positioning, controller functions, status bits and provides complete error logging. THE MEMORY DIAGNOSTIC checks for proper write/read, refresh, executability and exclusivity of all address locations. Includes both diagnostics and complete instruction manual.

SYSTEM DIAGNOSTICS $19.95

An improved version of the SYSTEM DIAGNOSTICS above. Designed for single or double density, 35-, 40-, 77-, or 80-track disk drives. Includes new and modified tests. Features THE FLOPPY DOCTOR, Version 3.0.

SYSTEM DIAGNOSTICS-V3 .. $24.95

Single Sided, Soft-Sectored 5¼-inch, (for TRS-80™) Mini-floppy

DISKETTES $21.95 box of 10

PLAIN JANE™

These are factory fresh, absolutely first quality (no seconds!) mini-floppies. They are complete with envelopes, labels and write-protect tabs in a shrink-wrapped box.

PLAIN JANE™ Diskettes $21.95
10 boxes of 10 (each box) $21.50

PLAIN JANE™ *Gold*

Introducing MTC's premium generic diskette. Single-Sided, Soft-Sectored, DOUBLE-DENSITY, 5¼-inch diskettes with reinforcing HUB-RINGS. Individually 100% ERROR-FREE certified. Invest in GOLD!

PLAIN JANE™ *Gold* $25.95

VERBATIM'S PREMIUM DISKETTES

DATALIFE™

Seven data-shielding improvements mean greater durability and longer data life. These individually, 100% error-free certified diskettes feature thicker oxide coating, longer-lasting lubricant, improved liner, superior polishing and more! Meets or exceeds IBM, Shugart, ANSI, ECMA and ISO standards.

VERBATIM DATALIFE™ DISKETTES
5¼-inch (box of 10)
MD525-01 $26.95
10 boxes of 10 (each box) $25.95
8-inch FLOPPIES
Double-Density, FD34-8000 . $43.95

'RINGS' & THINGS

HUB RING KIT for 5¼" disks.	$10.95
HUB RING KIT for 8" disks.	$12.95
REFILLS (50 Hub Rings)	$ 5.95
CLEANING KIT for 5¼" drives	$24.95
5¼-inch diskette case	$3.50
8-inch diskette case	$3.95
5 1/4-inch File Box for 50 diskettes	$24.95
8 Inch File Box for 50 diskettes	$29.95

TRS-80 is a trademark of the Radio Shack Division of Tandy Corporation. DATALIFE is a trademark of VERBATIM. PLAIN JANE, AIDS-I, AIDS-III, CALCS-III, CALCS-IV, MERGE-III are trademarks of MTC. © 1981 by Metatechnologies Corporation, Inc.

MOST ORDERS SHIPPED WITHIN ONE BUSINESS DAY

Products damaged in transit will be exchanged

PRICES IN EFFECT Nov. 1, 1981 THRU November 30, 1981.

Prices, Specifications, and Offerings subject to change without notice.

8111

WE ACCEPT
- VISA
- MASTER CHARGE
- CHECKS
- MONEY ORDERS
- C.O.D

- Add $3.00 for shipping & handling
- $3.00 EXTRA for C.O.D.
- Ohio residents add 6½% sales tax.

CIRCLE 228 ON READER SERVICE CARD

PORTABLE WORD PROCESSING COMPUTER

A British-made "computer in a briefcase" contains a word processor, an 8" x 8" viewing screen with a capacity of 480 characters, bubble memory and a telephone coupler.

The Microdata 8400 weighs less than 17 lbs. and has a standard keyboard. The acoustic coupler allows the unit to transmit or receive data or programs over public telephone lines, and it operates on both American and European communications standards.

The 94K bubble memory stores the data and is not erased when the power is switched off.

Microdata Computers, Belvedere Works, Bilton Way, Hayes, Middlesex UB3 3ND England.

TI99/4A HOME COMPUTER CONSOLE

Texas Instruments Incorporated has announced an enhanced version of the TI-99/4 home computer. Designated the TI99/4A, the new console features upper and lower case letters arranged as on a standard typewriter keyboard. The Shift key activates the uppercase letters and can be locked by depressing the Alpha Lock key.

An automatic repeat function has been added, and special keys have been included to simplify access to special computer functions. $525.

Texas Instruments Incorporated, Consumer Relations, P.O. Box 53, Lubbock, TX 79408. (800) 858-4565; in Texas (800) 692-4279.

CIRCLE 355 ON READER SERVICE CARD

INTEGRATED DESKTOP COMPUTER

North Star Computers has introduced an integrated desktop standalone system which offers graphics capabilities, a 12" display, two 5 1/4" high-capacity floppy disk drives, an 87-key Selectric-style keyboard and a choice of optional operating and applications software.

The Advantage is built around a 4-megaHertz Z-80A and has 64K of RAM. It features a 12" bit-mapped CRT display to produce bar charts, pie diagrams, plotted graphics and three-dimensional visuals, driven by an additional 20K of RAM.

In addition to the double-sided, double-density floppy disks, the chassis contains six slots for plug-in option cards such as a parallel interface for either a printer or a hard disk, an RS-232C serial-port board, or North Star's Floating Point Board for performing high-speed floating point arithmetic with up to 14 digit precision.

An operating system called Application Software Program manages the Advantage resources, and provides an Indexed Sequential Access Method and Random File Management system interface for the application software packages which include the Accounting Application Software Package—GeneralLedger, Accounts Receivable, AccountsPayable (Inventory Control, Order Entry/Invoicing); North Word, a word processing package; Mail Manager, a mailing list processor; and InfoManager, a data manager.

Also available is graphics CP/M, a superset of CP/M that allows the user to take advantage of the graphics capabilities of Advantage and also to run all CP/M-compatible software. North Star also offers Fortran and Cobol under CP/M. $3999.

North Star Computers, Inc., 14440 Catalina St., San Leandro, CA 94577. (415) 357-8500.

CIRCLE 356 ON READER SERVICE CARD

COMPUTERS BY MAIL

P.O. Box 1805 Hawthorne, CA 90250

PRINTER AND INTERFACES	
ANADEX 9500/132 COL	1345.00
ANADEX 9501 132 COL	1345.00
EPSON MX80 PIN FEED	585.00
EPSON MX80 TRACTOR/FRICTION	675.00
EPSON MX70 PIN FEED	405.00
EPSON PARALLEL CARD	65.95
EPSON SERIAL ADAPTOR BOARD	61.95
EPSON CARTRIDGE RIBBON	13.00
EPSON PARALLEL INTERFACE CABLE	21.95
TRENDCOM 200 80 COL	540.00
CENTRONICS 7721 W/O CABLE	95.95
CENTRONICS 7728 W/O CABLE	95.95
CALIFORNIA COMPUTER SYSTEMS	
ASYNCHRONOUS SERIAL	125.95
SYNCHRONOUS SERIAL	139.95
PARALLEL	95.95
MONITORS	
AMDEK 13" COLOR	420.00
AMDEK 12" B & W	150.00
AMDEK 13" 100 GREEN	175.00
SANYO 9" B & W	169.00
SANYO 12" HI-RES B&W	255.00
SANYO 13" COLOR	475.00
SANYO 12" HI-RES GREEN	270.00
NEC 12" COLOR	450.00
MODEMS	
HAYES MICROMODEM II (APPLE II)	299.00
HAYES MICROMODEM 100 (S-100)	325.00
HAYES STACK (RS-232)	245.00
SOUTHEASTERN DATA CAPTURE 4.0	44.95
DISK DRIVES	
MICRO-SCI 40 TRACK W/CONT	460.00
MICRO-SCI 40 TRACK W/O CONT	395.00
MICRO-SCI 70 TRACK W/CONT	575.00
MICRO-SCI 70 TRACK W/O CONT	435.00
EDUCATIONAL SOFTWARE	
EDUWARE	
STATISTICS	24.95
EDU - PAK I	32.95
STORY TELLER	18.95
ALGEBRA I	32.95
UNI - SOLVE	19.95
COMPU - MATH ARITH SKILL	32.95
COMPU - MATH FRACTIONS	32.95
COMPU - MATH DECIMALS	32.95
COMPU - SPELL (REQ DATA DISK)	24.95
SPACE	24.95
SPACE II	19.95
NETWORK	16.95
TERRORIST	24.95
WINDFALL	16.95
PRISONER	24.95
MICROSOFT TYPING TUTOR	18.95
SUB - LOGIC FLIGHT SIMULATOR	29.95
SYNERGESTIC STAR GAZERS GUIDE	25.95
ACCESSORIES	
DANATRONICS COOLING FAN	39.95
T.G. JOYSTIK	44.95
GAME PADDLES	32.95
80 COLUMN SYSTEMS	
M + R SUPERTERM	24.95
APPLE DOUBLE VISION	235.00
APPLE II 80 COL VIDEO CARD	315.00
VIDEX VIDEO TERM CARD 80 COL	295.00

★ APPLE II 48K + APPLE DISC II DRIVE W/CONT. + 3.3	$1299.00
★ XEROX SAM MICROCOMPUTER	590.00
★ MICROPRO WORDSTAR	2595.00
★ MICROSOFT Z 80 CARD	249.95
★ MICROSOFT 16K RAM BOARD	259.95
★ DANATRONICS 16K RAM BOARD	149.95
★ MOUNTAIN CPS MULTIFUNCTION CRD	175.00
MISC HARDWARE	
VIDEX SWITCHPLATE	18.95
KEYBOARD DISPLAY ENHANCER	99.95
ADVANCE BUSINESS TECHNOLOGY	
10 KEY PAD (OLD OR NEW)	99.95
APPLE CLOCK	239.95
100,000 DAY CLOCK	319.00
SUPERTALKER	254.00
ROMPLUS	132.00
ROMWRITER	150.00
INTROLINK CONTROLLER CARD ONLY	170.00
MUSIC SYSTEM W/SOFTWARE	450.00
A/D D/A W/O CABLE	295.00
I/O CABLE ASSEMBLY	42.95
BUSINESS SOFTWARE	
CONTINENTAL SOFTWARE	
HOME MONEY MINDER	28.95
CPA I GENERAL LEDGER	195.00
CPA II ACCTS RECEIVABLE	195.00
CPA III ACCTS PAYABLE	195.00
CPA IV PAYROLL	195.00
MUSE SUPERTEXT II	115.00
ADDRESS BOOK	39.95
FORM LETTER MODULE	85.00
STONEWARE DB MASTER (NEW)	179.95
MISCELLANEOUS SOFTWARE	
PERSONAL SOFTWARE	
VISICALC 3.3	159.95
VISIPLOT	149.95
VISIDEX	159.95
VISITERM	119.95
PROGRAMMA INTERNATIONAL	
APPLE PI (SMARTERM)	105.95
APPLE PI (SUPERTERM)	105.95
APPLE PI (VIDEX)	105.95
APPLE PI (OTHER 80)	105.95
ON-LINE EXPEDITER II	79.95
HAYDEN APPLESOFT COMPILER	159.95
HIGH TECH APPLE JUICE ONE HOUR	245.00
LAZER LOWER CASE ADAPTER	59.95
PAYMAR CHECK PRINTER REV 7/LATER	39.95
SOLID STATE MUSIC	
A/D SERIAL PARALLEL CARD	160.00
S-100 SYSTEMS	
CALIFORNIA COMPUTER SYSTEMS	
32K STATIC RAM MODULE	650.00
64K STATIC RAM MODULE	560.00
INTEGRATED SYSTEM W/MAINFRAME	2195.00
DISK CONTROLLER	300.00
MOTHER BOARD	105.95
4 PORT SERIAL I/O INTERFACE	250.00
Z-80 CPU	259.95

INCLUDE NAME, ADDRESS, PHONE NUMBER. ADD 3% FRT/HANDLING. CALIF. RESIDENTS ADD 6% SALES TAX. ALL MFRS. WARRANTIES APPLY. ALL PRODUCTS IN STOCK! VISA/MC ADD 3%. — INCL. EXP. DATE. PRICES SUBJECT TO CHANGE. CBM P.O. BOX 1805, HAWTHORNE CA 90250 (213) 533-4071.

CIRCLE 108 ON READER SERVICE CARD

Creative Computing Gift Certificate

Here is the perfect gift for the person who has almost everything: A *Creative Computing* Gift Certificate.

Having a difficult time selecting a gift for someone? Don't know what books or software they have now? Then give a *Creative Computing* Gift Certificate. Here's how it works. You send us a check for the amount you'd like the certificate to equal, along with the recipient's name and address. We'll send them a *Creative Computing* Gift Certificate from you for the amount specified. We'll also send them a 48-page catalog from which they can select their gift. Sounds simple? It is. And it's convenient for you. Get one today. Creative Computing Gift Certificates are available for whatever amount you wish to give.

Stock Market

See Wolf

NEW! ASCII
for the TRS-80*

Every month you receive a certified ASCII C-20 cassette
containing: a cover page with a directory of programs
4 original programs
an information packed newsletter
and information on ASCII funded contests

Rates: 1 year [12 issues] $40.00
6 months [6 issues] $25.00
Sample issue $ 5.00

Write For Overseas Rates
To subscribe, write to: ASCII
P.O. Box 516, Valley Stream, N.Y. 11582
Or call: 516-791-4890

Level II/16K Required

*TRS-80 is a product of Tandy Corp.

Makes A Great Gift

CIRCLE 116 ON READER SERVICE CARD

COMPUTER EQUIPMENT & SOFTWARE BARGAINS

EVERY MONTH

BUY, SELL OR TRADE ALL TYPES OF COMPUTER EQUIPMENT AND SOFTWARE (pre-owned and new) among 20,000 readers nationwide.

FEATURES:

- Low classified ad rates - 10¢ a word
- Hundreds of ads from individuals
- Categorized ads so you can find them instantly
- Large (11 by 14") easy to read pages

Subscribe now for $10 and receive 13 issues/year (one FREE plus 12 regular issues). After receiving your first issue if you're not completely satisfied you may have a 100% refund and you still keep the first issue free. Bank cards accepted.

BONUS: *If you have something to advertise (pre-owned or software) send in a classified ad with your subscription and we'll run it FREE.*

The Nationwide Marketplace for Computer Equipment
COMPUTER SHOPPER
P.O. BOX F 7 • TITUSVILLE, FL 32780 • 305-269-3211

MasterCard & VISA subscriptions only, call TOLL FREE 1-800-327-9920

CIRCLE 128 ON READER SERVICE CARD

Special editions for Apple, Atari and TRS-80 Computers.

Programming is Child's Play

Hey kids, are the folks out of the room? Good, 'cause I've got a secret to tell you. You know that computer they fuss over? Well, kid, between you and me, this whole programming thing is a lot simpler than they realize.

What's that? Sure, you can learn. Just get a copy of **Computers For Kids**. It's a super book, and it tells you everything you need to know. Huh? You have an Apple? No problem. There's a version just for the Apple. One for the TRS-80 and one for the Atari too, with complete instructions for operating and programming.

The book will take you through everything programmers learn. Its easy to understand and the large type makes it easy to read. You'll find out how to put together a flowchart, and how to get your computer to do what you want it to do. There's a lot to learn, but **Computers For Kids** has 12 chapters full of information. You'll even learn how to write your own games and draw pictures that move.

Just so the folks and your teachers won't feel left out, there's a special section for them. It gives detailed lesson ideas and tells them how to fix a lot of the small problems that might pop up. Hey, this book is just right for you. But you don't have to take my word on that. Just listen to what these top educators have to say about it:

Donald T. Piele, Professor of Mathematics at the University of Wisconsin-Parkside says, "**Computers For Kids** is the best material available for introducing students to their new computer. It is a perfect tool for teachers who are learning about computers and programming *with* their students. Highly recommended."

Robert Taylor, Director of the Program in Computing and Education at Teachers College, Columbia University states, "it's a good idea to have a book *for chidren*."

Not bad, huh? Okay, you can let the adults back in the room. Don't forget to tell them **Computers For Kids** by Sally Greenwood Larsen cost only $3.95. And tell them you might share it with them, if they're good. Specify edition on your order: TRS-80 (12H); Apple (12G); Atari (12J).

Your local computer shop should carry **Computers For Kids**. If they don't ask them to get it or order by mail. Send $3.95 payment plus $2.00 for one, $3.00 for two or more for shipping and handling to Creative Computing Press, P.O. Box 789-M, Morristown, NJ 07960.

creative computing press

CIRCLE 350 ON READER SERVICE CARD

New Products, continued...

SYSTEM SUPPORTS 255 USERS

Molecular Logic Corporation has announced the DIRAC computer system.

The system can support up to 255 independent users with virtually no impact on system throughput. This is accomplished by providing each user with a complete 64K microprocessor module which can access a common data base.

The DIRAC system features two microprocessor module types; one for disk storage management and the other dedicated to each individual user. Also included are 30Mb of disk storage and a standard 8" floppy disk drive for software interchange and data backup.

The system is based on the Z-80A microprocessor and features the CP/M operating system.

The basic DIRAC system sells for $9000. Additional processor modules are priced at $1250.

Molecular Logic Corporation, 10311 S. DeAnza Blvd., Suite 4A, Cupertino, CA 95014, (408) 446-9077.

CIRCLE 357 ON READER SERVICE CARD

COMPUTHINK EAGLE 32

Computhink has announced the Eagle 32 family of microcomputer systems. The two new systems are based on the Motorola 68000, 16/32 bit, microprocessor chip.

The two systems, Model 10 and 20, are similar except for quantity of mass storage available standard with the system. Each has a 128K byte main memory. The Eagle 32 Model 10 ($6650) has a 1.6 megabyte storage capacity expandable to 3.2 megabytes on 5 1/4" floppy disk as compared with 2.4 megabyte storage capacity, expandable to 4.8 megabytes for the Eagle 32 Model 20 ($7650).

Both systems are expandable to one megabyte of main memory. All of memory is directly addressable by the computer allowing large application programs to be executed.

The Eagle 32 is essentially a dedicated commercial or scientific application system. Initial deliveries will include a batch operating system, Basic+, Forth+, and Tiny Fortran.

Computhink, 965 West Maude Ave., Sunnyvale, CA 94086, (408) 245-4033.

CIRCLE 358 ON READER SERVICE CARD

the CP/M* and S-100 user's journal

MICROSYSTEMS

TM

Finally, there's a magazine with up-to-date, informative articles for the serious microcomputer user! MICROSYSTEMS focuses on CP/M*, Pascal, and related software, on North Star and S-100 bus hardware (including 16-bit systems). You,ll find applications, tutorials, hardware and software reviews, and a software directory. No longer will you have to hunt through magazines to find the articles you,ve been waiting for. Now you can find them all in MICROSYSTEMS!

Keep up with the latest developments in the S100 and CP/M world with MICROSYSTEMS!

MICROSYSTEMS, 39 E. Hanover Ave., Morris Plains, NJ 07950

☐ Sign me up!

☐ Send a sample copy ($2 enclosed)

Name _____

Address _____

City _____

State/Zip _____

Term	USA	Canada, Mexico	Foreign (Air)
3YR(18 issues)	☐ $24	☐ $38	☐ $69
2YR(12 issues)	☐ $18	☐ $27	☐ $48
1YR(6 issues)	☐ $10	☐ $15	☐ $25

☐ Payment enclosed ☐ Bill me ($1 charge)

☐ Visa ☐ Master Card ☐ American Express Exp. Date: ____

Card Number: _____

Signature: _____

*TMK Digital Research



Edited by Sol Libes

Published every other month

CIRCLE 247 ON READER SERVICE CARD

The only thing you can do with a baked Apple is eat it.

The more you stuff your Apple II™ with plug-in boards, the more of a chance it has to overheat.

And once that happens, it won't do anybody any good. Your program bombs and you start losing time and money.

The solution? Simple. Take two minutes to install the Dana Industries fan in the back of your Apple, and you'll practically never have to worry about overheating again.

So pick up the Dana Industries fan at your local computer store. And your Apple will have a long and fruitful life.

™Apple II is a trademark of Apple Computer, Inc.

CIRCLE 195 ON READER SERVICE CARD

dy/an

Dysan

CORPORATION

Solve your disc problems, buy 100% surface tested Dysan diskettes. All orders shipped from stock, within 24 hours. Call toll FREE (800) 235-4137 for prices and information. Visa and Master Card accepted. All orders sent postage paid.

PACIFIC EXCHANGES
100 Foothill Blvd
San Luis Obispo, CA
93401 (In Cal call
(805) 543-1037)

CIRCLE 189 ON READER SERVICE CARD

we beat the price...

ATARI

800™ $749

ATARI®
Computers
for people.™

ATARI 810 DISC DRIVE



$444

ATARI SOFTWARE

CX404 Word Processor	$119.00
CX405 PILOT	$68.00
CX413 MICROSOFT BASIC	$68.00
CX401 Invitation to Programming 1	$17.00
CX402 Kingdom	$13.00
CX403 Statistics	$17.00
CX404 Mailing List	$17.00
CX405 Blackjack	$13.00
CX406 Invitation to Programming 2	$20.00
CX407 Biorhythm	$13.00
CX408 Hangman	$13.00
CX409 Graph It	$17.00
CX410 Touch Typing	$20.00
CX411 Space Invaders	$17.00
CX412 States & Capitals	$13.00
CX414 European Countries & Capitals	$13.00
CX415 Mortgage & Loan Analysis	$13.00
CX416 Personal Fitness Prog	$59.00
CX417 Invitation to Programming 3	$20.00
CX418 Conversational French	$45.00
CX419 Conversational German	$45.00
CX420 Conversational Spanish	$45.00
CX421 Energy Czar	$13.00
CX425 Conversational Italian	$45.00
CX6001 U.S. History	$23.00
CX6002 U.S. Government	$23.00
CX6003 Supervisory Skills	$23.00
CX6004 World History	$23.00
CX6005 Basic Sociology	$23.00
CX6006 Counseling Proced	$23.00
CX6007 Principal of Act	$23.00
CX6008 Physics	$23.00
CX6009 Great Classics	$23.00
CX6010 Business Comm	$23.00
CX6011 Basic Psychology	$23.00
CX6012 Effective Writing	$23.00
CX6014 Principals of Econ	$23.00
CX6015 Spelling	$23.00
CX6016 Basic Electricity	$23.00
CX6017 Basic Algebra	$23.00
CX8106 Bond Analysis	$20.00
CX8107 Stock Analysis	$20.00
CX8108 Stock Charting	$20.00
CXL4001 Education System Master	$21.00
CXL4002 Basic Computing Language	$46.00
CXL4003 Assembler Editor	$46.00
CXL4004 Basketball	$24.00
CXL4005 Video Easel	$24.00
CXL4006 Super Breakout	$30.00
CXL4007 Music Composer	$45.00
CXL4009 Chess	$30.00
CXL4010 3 D Tic Tac Toe	$24.00
CXL4011 Star Raiders	$39.00
CXL4012 Missile Command	$32.00
CXL4013 Asteroids	$32.00
CXL4015 TeleLink	$20.00
Computhome	$74.95
Visicalc	$149.00
Letter Perfect (Word Processor)	$119.00
Source	$89.00

Atari® Peripherals:

400 16K	$329.00
410 Recorder	$59.00
822 Printer	$359.00
825 Printer	$CALL
830 Modem	$159.00
850 Interface	$ CALL

Atari® Accessories

New DOS 2 System	$21.00
CX70 Light Pen	$64.00
CX30 Paddle	$18.00
CX40 Joy Stick	$18.00
CX853 16K RAM	$89.00
Microtek 16K RAM	$75.00
Microtek 32K RAM	$169.00

CBM 8032 $1099

4016	$799.00
4032	$999.99
8096	$1795.00
CBM4022 Printer	$629.00
Tally 8024	$1699.00
CBM C2N Cassette Drive	$69.00
CBM4040 Dual Disk Drive	$999.00
CBM8050 Dual Disk Drive	$1349.00

commodore



VIC 20 $259

Vic-TV Modual	$19.00
Vic Cassette	$69.00
Vic Disk Drive	$ Call
Vic 6 Pack program	$44.00

CBM Software

WordPro3 Plus	$199.00
WordPro4 Plus	$299.00
Commodore Tax Package	$399.00
Visicalc	$149.00
BPI General Ledger	$329.00
OZZ Information System	$129.00
Dow Jones Portfolio	$239.00
Pascal	$449.00
Legal Time Accounting	$289.00
World Cretit 80	$180.00
Word Check	$239.00
Create A Base	$89.00
Power	$20.00
Socket 2 Me	Call
Jinsam	

Disks

CX8100 Blank Disk (5)	$22.00
Sycom Blank Disk (10)	$29.00
Maxell Blank Disk (10)	$36.00
Maxell Blank Disk (10)	$46.00

Printers

Call for prices on the new NEC models

Epson MX 70	Call for Prices
Epson MX 80	
Epson MX 80 FT	
Diablo 630	
TEC 1500 Starwriter 25cps	$1495.00
TEC 1500 Starwriter 45cps	$1795.00

No Risk, No Deposit On Phone Orders, COD or Credit Card, Shipped Same Day You Call *

* on all in stock units

IN PA. CALL (717) 327-9575

(800) 233-8950

To Order

Phone orders invited (800 number is for order desk only). Or send check or money order and receive free shipping. Pennsylvania residents add 6% sales tax. Allow 2 weeks for Visa or M.C. Equipment is subject to price change and availability without notice. Please call between 11 AM & 6 PM

COMPUTER MAIL ORDER
501 E. 3RD ST., WILLIAMSPORT, PA 17701

CIRCLE 148 ON READER SERVICE CARD

SMALL BUSINESS COMPUTER

The Datamac 1255 is a self-contained, portable computer system which packages a Z-80 processor, 64K bytes of RAM, I/O ports, keyboard, CRT, and two 5 1/4" double-sided, double-density mini-floppies in a cabinet no bigger than a normal CRT terminal.

The industry standard CP/M operating system is offered along with software, including Basic, Fortran, Cobol, Pascal, Forth, macroassemblers, business packages, text editors, word processors, and utilities.

A unique feature of the Datamac 1200 series is the ability to add on external floppy drives of any configuration—5 1/4" or 8", single or double density, single or double sided, 48 or 96 tracks per inch.

List prices of the 1200 series range from $2995 to $4995 depending on floppy disk configuration.

Datamac Computer Systems, 3333-F Octavius Dr., Santa Clara, CA 95051. (408) 727-0561.

CIRCLE 359 ON READER SERVICE CARD

1 TO 20 MEGABYTE SYSTEM

Tarbell Electronics announces the Empire Series System, which includes a Z-80 4 Mhz CPU with memory management timer and full interrupt capability, two RS-232 serial ports with handshaking, 64K bytes of RAM (expandable to 256K), double-density floppy disk interface, two double-density floppy disk drives, cabinet, power supply and cables.

The systems software includes: the Digital Research CP/M 2.2 disk operating system, Tarbell Disk Basic, Tarbell Database System, and all manuals and documentation.

The applications software available includes word processing, inventory control with bill of materials, mailing lists, general ledger, payables, receivables, payroll with cost accounting and order entry.

Tarbell also offers the Digital Research MP/M Multi-User Operating System and four additional RS-232 serial ports.

Tarbell Electronics, 950 Dovlen Pl., Suite B, Carson, CA 90746. (213) 538-4251.

CIRCLE 360 ON READER SERVICE CARD

GUIDELINES FOR EVALUATING COMPUTERIZED INSTRUCTIONAL MATERIALS

- for users and creators of educational software
- with sample evaluation instruments
- by an international organization dedicated to the improvement of mathematics instruction

1981 ISBN 0-87353-176-0 #122 $3 75

National Council of Teachers of Mathematics
1906 Association Drive, Reston, Virginia 22091

Prepay, save shipping and handling. MasterCard and VISA orders 703-620-9840
Minimum billed order $20 Virginia residents add 4% sales tax

THEME ISSUE.....MICROCOMPUTERS
MATHEMATICS TEACHER 11/81 #203 $3.50

CIRCLE 220 ON READER SERVICE CARD

Software Breakthrough!

THE WORD HANDLER

BY SILICON VALLEY

THE ONLY WORD PROCESSOR IN THE WORLD FOR THE APPLE THAT:

- **Gives you full line capability on the screen, no boards nec.**
- **Two character formats to choose from at all times!**

RUNS WITHOUT ANY HARDWARE MODIFICATIONS!

HIGH POWER
Simplicity of Operation

LARGE SCALE
Direct to disk.
All functions seen on the screen.

- Lower and upper case
- Underlining
- Superscript, bold, and unlimited tabs
- Even and normal justification
- Other functions seen on turnkey systems in the $13–$20,000 range

DEALER INQUIRIES INVITED

652 BAIR ISLAND ROAD
REDWOOD CITY, CA 94063
(415) 361-1818

CIRCLE 253 ON READER SERVICE CARD

TERMINALS & I/O

PRINTER/CASSETTE INTERFACE FOR POCKET COMPUTER

Radio Shack offers a printer and cassette interface for the TRS-80 Pocket Computer. The combined printer and cassette interface unit (26-3505) comes complete with rechargeable batteries, an AC adapter/charger cassette recorder connecting cable, replaceable printer ribbon cartridge, three rolls of paper and an owner's manual.



Utilizing the pocket computer's "PRINT" and "LIST" commands, the printer provides a legible 16-column alphanumeric printout of programs, data, instructions and results on ordinary electronic cash register type paper.

The dot matrix printer mechanism prints approximately one line per second, about 8000 lines per battery charge. $149.95.

Available at Radio Shack stores and Computer Centers.

NORTH STAR BUSINESS SOFTWARE

Our catalog lists over 20 business and utility programs for use on the North Star computer. We have the finest collection of business programs available. No games are included. All programs are professionally written by experienced programmers and come with complete documentation.

If you use your North Star for business purposes, you should have our free catalog. Drop us a card or call.

Omni SOFTWARE SYSTEMS INC. 1800 N. ELDRIDGE PARKWAY HOUSTON, TEXAS 77077 (AC 219) 924-3522

CIRCLE 174 ON READER SERVICE CARD

SOFTWARE FOR OSI

VIDEO GAMES 3 .... NEW! $14.95
Three games. Meteor Mission is an asteroids game. Space Wars is a battle between two starships. Meteor Wars is a combination of the two above games. All three are in machine language with fast real time action and super graphics.

ADVENTURE: IMMORTALITY NEW! $11.95
You are an intrepid explorer searching for the fabled Dust of Immortality. This is the largest adventure yet available for 8K OSI hobbyist room load so you can't cheat.

SUPER BUG! $6.95
Here's a super-fast BASIC Machine language hybrid race game. Ten levels of difficulty and a infinately changing track will keep you challenged.

STARGATE MERCHANT $9.95
You are a trader in the distant future. Traveling through stargates to get to various star systems. Part video game part board game always challenging.

DISASSEMBLER $11.95
Use this to look at the ROMs in your machine to see what makes BASIC tick. Reconstruct the assembler source code of machine language programs to understand how they work. Our disassembler outputs unique suffixes which identify the addressing mode being used no other program has this.

MAROONED IN SPACE .. $11.95
An adventure that runs in 8K! Save your ship and yourself from destruction.

SUPER! BIORHYTHMS .. $14.95
A unique sophisticated biorhythm program.

DUNGEON CHASE $9.95
real time video game where you explore a dungeon.

Write for FREE catalog

ORION SOFTWARE
147 Main St. Ossining, NY 10562

CIRCLE 289 ON READER SERVICE CARD

PUT YOUR TRS-80® TO WORK---
managing your film orders! Our data-base film library program manages more than 250 titles on TRS-80® L1 W1 or M3 16K. Based upon—with memory to spare!—Written to be used.

Cassette manual ordered—$ 15.00

ATLANTA CREATED ENTERPRISES
P O Box 2727
Cocoa, Florida 32922

TRS-80 is a registered trade mark of Tandy Corp.

CIRCLE 256 ON READER SERVICE CARD

"Attention Computer Owners"

If you own a mini or micro...you could be on your way to fantastic riches. Put your computer to a new use by monitoring these investments. Set up your own office in your home...never work for the other guy again. It is the most ingenious method ever devised. Make six digits annually.

First time offered. Complete package $25.00. We pay postage & handling. Send check or M.O. to:

C.B.A.S.
P.O. Box 163
Ontario, OH 44862

CIRCLE 203 ON READER SERVICE CARD

ATTENTION TEACHERS!

At last! An end to the busy work of preparing math problems. Let the computer and printer do the busy work.

RELL offers you 25 math programs printed in BASIC for the line printer—all whole number and decimal operations (+ - × ÷), equations and proportions... all for hard copy. Each program produces a new and different set of drill and practice problems, with answers, each time it is run off on the line printer. In seconds you have individualized math problems on a ditto master, ready for duplication.

Order complete set now and receive a bonus of 2 free measurement programs covering English and Metric systems. Send for free brochure.

25 printed program listings $119.95
25 programs on cassette with printed listings $169.95

Send check or money order to:
RELL, 1125 Stanford Avenue
Redondo Beach, Calif. 90278

CIRCLE 223 ON READER SERVICE CARD

Save On TRS-80™ Computers

For the best deals on TRS-80 Computers we have SPECIAL DISCOUNTS, FREE SHIPPING and a TOLL FREE ORDER NUMBER

Pan American Electronics

Dept 22 • 1117 Conway • Mission, TX 78572
Telex Number 767339
Toll Free Order Number 800/531-7466
Texas & Principal Number 512/581-2766
TM Trademark of Tandy Corporation

CIRCLE 186 ON READER SERVICE CARD

Perfect Gift for Computer Enthusiasts



It's not easy to find a suitable gift for someone interested in computers and electronic games. Creative Computing magazine is aimed at both students and relaxing professionals. Every issue is packed with in-depth reviews of the latest computers, software and games along with scores of applications for home computers. The down-to-earth style of the magazine encourages readers to have fun while learning. A dramatic computer graphic announces your gift. Only $20/year. Write Hazel at Creative Computing, Morristown, NJ 07960.

CIRCLE 350 ON READER SERVICE CARD

Complete 6-year Index

Find it Fast!

Our new 6-year cumulative index lists every article, program and review that has appeared in Creative Computing from its inception in November 1974 to December 1980. The index lists not only the issue in which an article appeared but a cross reference to The Best of Creative Computing, Volumes 1, 2 and 3. It also lists all the articles in ROM magazine.

Articles are classified by subject area and listed by title and author. Over 3500 separate items are included. Note: the index does not include a cross reference to author.

Looking for information on computers in education? You'll find 76 articles and 155 application programs. How about art and graphics? You'll find 44 entries. In the market for a computer? You find 82 hardware evaluations and 94 of software.

Price of this huge index is just $2.00. Even if you've been a reader for only a year or two you'll find the index of great value. Orders yours today.

creative computing

Morris Plains, NJ 07950

CIRCLE 350 ON READER SERVICE CARD

MEMOREX DISKETTES & CARTRIDGES

for your computer or word processor

BUY THE BEST FOR LESS. Lowest prices. **WE WILL NOT BE UNDERSOLD!!** Buy any quantity 1 - 1000. Visa, Mastercharge accepted. Call free (800) 235-4137 for prices and information. All orders sent postage paid.

PACIFIC EXCHANGES
100 Foothill Blvd.
San Luis Obispo, CA
93401. (In Cal. call
(805) 543-1037.)

CIRCLE 169 ON READER SERVICE CARD

COTTAGE SOFTWARE

PACKER Machine language program that edits all or part of your Basic program to run faster, save memory, or ease editing. The 5 options include UNPACK—unpacks multiple statement lines into single statements maintaining logic inserts spaces and renumbers lines SHORT—deletes unnecessary words, spaces, and REM statements. PACK—packs lines into maximum multiple statement lines, maintaining program logic. RENUM—renumbers lines, including all branches. MOVE—moves line or blocks of lines to any new location in program. On 2 cassettes for 16K, 32K, & 48K For TRS-80™ Mod I or III Level II or Disk Basic $20.95

SYSTEM TAPE DUPLICATOR Copy your SYSTEM format tapes. Includes verify routines. The Model III version allows use of both 500 and 1500 baud cassette speeds

For TRS-80™ Model I or III Level II $15.95

CASSETTE LABEL MAKER A mini word processor to print cassette labels on a line printer. Includes 50 peel-and-stick labels on tractor feed paper

For TRS-80™ Model I or III Level II & Printer $17.95

PRINT TO LPRINT TO PRINT Edits your Basic program in seconds to change all Prints to LPrints (except Print# or Print#) or LPrints to Prints. Save edited version

For TRS-80™ Model I or III Level II $12.95

FAST SORTING ROUTINES For use with Radio Shack's Accounts Receivable, Inventory Control I, and Disk Mailing List Systems for Model I Level II Sorts in SECONDS! You'll be amazed at the time they can save. Supplied on data diskette with complete instructions

FAST SORT for Accounts Receivable	$19.95
FAST SORT for Inventory Control I	$19.95
FAST SORT for Disk Mailing List (specify data diskette: cassette for 1 drive system)	$14.95
ALL THREE ROUTINES	$44.95

Prices subject to change without notice. Call or write for complete catalog. Dealer inquiries invited. VISA and MasterCard accepted. Foreign orders in US currency only. Kansas residents add 3% sales tax. On-line catalog on Wichita FORUM-80 316-682-2113. Or call our 24 hour phone 316-683-4811 or write

COTTAGE SOFTWARE
614 N. Harding Wichita, KS 67208
TRS-80 is a trademark of Tandy Corporation

CIRCLE 161 ON READER SERVICE CARD

CAPTIVITY

the most advanced maze game available to the ATARI® owner

A new game by Craig Patchett which uses machine language routines, 5-color, high-resolution graphics and sound effects.

The player's goal is to guide an imaginary robot through and out of a 3-dimensional maze.

20 game variations insure countless hours of enjoyment.

CAPTIVITY can be used with any **ATARI®** computer with at least 24K. It is available in cassette format only. Price is $24.95 plus $2.00 shipping and handling.

Available at fine computer stores or write us directly.

Program Design, Inc. 11 Idar Court Greenwich, CT 06830
203-661-8799

ATARI® is the registered trademark of **ATARI**, Inc.

CIRCLE 297 ON READER SERVICE CARD

DON'T MISS PCAS-81

PHILADELPHIA AREA COMPUTER SHOW

Sponsored by Philadelphia Area Computer Society

NOVEMBER 12-14
Philadelphia Sheraton Hotel
17th & J. F. Kennedy Boulevard

Featuring Applications of Computers in

- **EDUCATION**
- **BUSINESS**
- **LEISURE ACTIVITIES**

PACS-81 covers a broad spectrum of interest among computer USERS.
A special area of the Exhibit Hall will be reserved for

APPLICATIONS IN EDUCATION
and Computer Assisted Instruction
The most comprehensive educational exhibit to date.

BUSINESS AND HOBBY
application will also be exhibited
Commercial and Proprietary Software and Hardware will be on display including Special Exhibits on

COMPUTER MUSIC AND ROBOTICS.

CONFERENCE:
November 12-14
(Thurs., Fri., Sat.)
Speakers, Workshops and Seminars

EXHIBITS:
November 13
(Fri.) 11-9
November 14
(Sat.) 10-6

ADMISSION: $5

EXHIBITOR BOOTHS AVAILABLE
CONTACT:
HOWARD LUBERT
Exhibit Coordinator
5127 Windward Lane
Bensalem, Pa 19020
(215) 245-0544

CIRCLE 248 ON READER SERVICE CARD

new friends for your child...



Katie and the Computer

Fred D'Ignazio and Stan Gilliam have created a delightful picture book adventure that explains how a computer works to a child. Katie "falls" into the imaginary land of Cybernia inside her Daddy's home computer. Her journey parallels the path of a simple command through the stages of processing in a computer, thus explaining the fundamentals of computer operation to 4 to 10 year olds. Supplemental explanatory information on computers, bytes, hardware and software is contained in the front and back end papers.

Thrill with your children as they join the Flower Bytes on a bobsled race to the CPU. Share Katie's excitement as she encounters the multi-legged and mean Bug who lassoes her plane and spins her into a terrifying loop. Laugh at the madcap race she takes with the Flower Painters by bus to the CRT.

"Towards a higher goal, the book teaches the rewards of absorbing the carefully-written word and anticipating the next page with enthusiasm..."

The Leader

"Children might not suspect at first there's a method to all this madness—a lesson about how computers work. It does its job well."

The Charlotte Observer

"...the book is both entertaining and educational."

Infosystems

The book has received wide acclaim and rave reviews. A few comments are:

"Lively cartoon characters guide readers through the inner chamber of the computer."

School Library Journal

"...an imaginative and beautifully conceived children's story that introduces two characters—the Colonel and the Bug—who already seem to have been classic children's story book characters for generations."

The Chapel Hill Newspaper

Written by Fred D'Ignazio and Illustrated in full color by Stan Gilliam. 42 pages, casebound, $6.95. (12A)

A t-shirt with the Program Bug is available in a deep purple design on a beige shirt. Adult size S, M, L, XL. Children's size S, M, L. $5.00.

To order, send a check for books plus $2.00 shipping and handling per order to Creative Computing, P.O. Box 789-M, Morristown, NJ 07960. NJ residents add 5% sales tax. Visa, MasterCard, and American Express orders are welcomed. For faster service, call in your bank card order toll free to 800-631-8112 (in NJ call 201-540-0445). Or use the handy order form bound into this magazine. CIRCLE 350 ON READER SERVICE CARD

puzzle answers

Potted Problem: The volume of each pot is its inside depth times its inside base area. The smallest pot is a six-inch square on the inside (36 square inches) but we don't know its depth. Call the depth of this pot X so the volume is 36X cubic inches. The next pot is 8 by 8 by (X + 1) or 64X + 64) cubic inches. The second largest pot is 10 by 10 by (X + 2) or (100X + 200) cubic inches, and the largest is 12 by 12 by (X + 3) or (144X + 432) cubic inches. We're told that the three smaller pots together have the same volume as the largest one alone, so

36X + 64X + 64 + 100X + 200 = 144X + 432

56X = 168 inches

X = 3 inches.

The four pots hold: 36X = 108 cubic inches

64X + 64 = 256

100X + 200 = 500

144X + 432 = 864

1728 cubic inches = 1.0 cubic foot or very nearly 7½ gallons.

Cornered: No. The board consists of 32 black and 32 white fields. Every domino piece will cover a white and a black field together. However the two corner fields which I cut out of the board are both white, leaving 32 fields of one color and 30 fields of the other color, making it impossible to cover the board with 31 domino pieces.

A Punctuation Problem: THAT THAT IS, IS. THAT THAT IS NOT, IS NOT. IS THAT IT? THAT IS IT.

A Matchless Puzzle: This problem is solved by doing the operations backwards. We start with three piles of 16 matches.

The third operation consisted of doubling the first pile and removing that amount from the third pile.

1: 16 ÷ 2 = 8 2 : 16 3 : 16 + 8 = 24

Applying this to the second operation we get:

1 : 8 2 : 16 + 12 = 28 3 : 24 + 2 = 12

Doing this once more:

1 : 8 + 14 = 22 2 : 28 ÷ 2 = 14 3 : 12

Therefore, we started out with 22, 14 and 12.

The Problem of the Burning Candles: It takes 6 hours for the second candle to burn the same amount as the first candle burns in 4½ hours. Therefore the rate of the second candle is only ⅔ times that of the first candle.

rate = distance/time

let x = length of first candle

then x − 1 = length of second candle

⅔ times the rate of the first = rate of the second

⅔ times x/9 = (x − 1)/10 which resolves x being equal to 6.

So one candle is 6 inches and the other candle is 5 inches.

The Star Trek Puzzle: TIME, TAME, TARE, WARE, WARP.

Another True or False Puzzle: If Orange, the first would have lied and answered "I'm Purple." If Purple, he would have said so. Either way, the windblown words were "I'm Purple." It follows that the second person is Purple because he reported truly the first's reply. Since the first two are Purple, the third is lying and has to be Orange.

What Comes Next?: The next word must denote an emotion not already used in the list, (we used Joy, Grief, Humor, etc. You might try Sad or Happy). The list is a concepts progression. (It goes A, then AB, then ABC, then ABCD.) The concepts are: A = physical properties; B = emotions; C = colors; D = tastes.

A Counter Problem: House numbers.

An Ageless Problem: Ann is 18.

A Loopy Problem: Place your forefinger inside the loop and give the loop a quick sidewise blow. It must be a sharp blow and you must follow through sweeping the loop out from under the dime. The dime will then fall straight down and into the bottle.

INVALUABLE

It's hard to put a price on the kind of knowledge InfoWorld gives you. The software and hardware analyses, news stories and interviews contained in this very successful microcomputer newspaper will assist you in all your buying decisions—an you'll be up to date on new developments every other week.

Keep up with the industry. Subscribe to InfoWorld, the microcomputer newsweekly.

Mail this form or facsimile to:
InfoWorld, 375 Cochituate Road,
Framingham, Mass. 01701
Or call (617) 879-0700
Outside MA (800) 343-6474

InfoWorld

Please start my subscription to InfoWorld, the microcomputer newsweekly.

☐ $25 one year
☐ $35 one year Canada & Mexico
☐ $116 Airmail to Rest of World

☐ My check is enclosed
Charge my: ☐ Mastercharge ☐ BankAmericard/Visa ☐ American Express

MC only list 4 digits above your name _____

Card No. _____ Exp. Date _____

Signature _____ Date _____

First Initial _____ **Middle Initial** _____ **Surname** _____

Company Name _____

Address _____

City _____ **State** _____ **Zip Code** _____

InfoWorld, 375 Cochituate Road, Framingham, Mass. 01701
Or call (617) 879-0700 Outside Mass. (800) 343-6474

index to advertisers

Reader Service	Advertiser	Page
112	Aardvark 80	213
102	Aardvark Technical	101
105	ABM Products	172
101	Acorn Software	95
148	Advanced Computer Products	109
114	Advanced Operating Systems	121
103	Adwar Video Corp.	118
104	Adwar Video Corp.	183
*	All Products	217
170	Alpha Byte Stores	88
159	Alpha Byte Stores	136,137
117	Amdek	15
255	Analog	195
118	Apparat Inc.	80
121	Applied Analytic Inc.	47
109	ASAP Computer Products Inc.	111
118	ASCII	279
282	Aspen Software	107
287	Atari	99
123	Atari	25
256	Atlantis Creative	284
107	Aurora Systems	211
124	Aurora Systems	221
110	Automated Simulations	113
*	Big Five Software	Cover 3
115	The Bit Bucket	259
322	Broderbund Software	93
264	Broderbund Software	259
129	Broderbund Software	256
125	Bytes & Pieces	239
258	CAMI	217
203	CBAS	284
133	Charles Mann & Assoc.	221
111	Cload Magazine	128
113	Cload Magazine	166
134	The Comm Center	166
126	Comm Data Systems	225
120	Commodore Business Mach.	Cover 2
	Computer Age	259
108	Computers By Mail	278
288	Compusoft	153
*	Computer Age	259
281	Computer Case	225
217	Computer Consultants of Iowa	48,49
141	Computer Exchange	104,105
122	Computer Information Exchange	247
148	Computer Mail Order	282
180	Computer Plus	204
222	Computer Products Int'l	115
128	Computer Shopper	279
145	Computer Specialties	147
149	Computer Station	253
132	Computerville	225
127	Computer's Voice	217
130	Computer Wholesale	202
138	Computronics	154
137	Computronics	155
139	Computronics	157
140	Consumer Computer Mail	117
319	Context Systems	18
231	Continental Adventures	217
181	Cottage Software	285
164	Cove View Press	229
171	CPU Shop	149
241	Creative Software	233
185	Crystal Computer	41
119	C & S Electronics	235
135	Cybersoft	129
150	Designer Software	119
169	DFS Computer Forms	114
173	Digibyte Systems	28,29
158	Discount Data Products	151
131	Discount Software Group	22
136	Dynacomp	66,67
154	Ecosoft	211
106	Eduware Services Inc.	97
	80 US Journal	206
142	Electronic Specialists	219
254	Electronic Systems Furniture	85
177	Exidy Systems Inc.	131
179	Farnsworth Computer Center	219
178	Frederick Computer Products	153
199	Gulf Breeze Computer Store	261
180	Happy Hands	242
205	Hayden Book Co.	185
*	Heath Co.	8,9
257	H & H Trading	229
259	Highland Computer Services	139
183	Horizon Simulations	213
190	Howard Industries	171
144	Huntington Computing	21
280	Huntington Computing	169
*	H.W. Electronics	219
147	IDSI	187
188	IMB	246
151	Information Unltd Software	43
273	Information Unltd Software	208
*	Info World	287
152	Insoft Corp.	87
192	Interface Technology	245
198	Jem Research	221
178	Kogyoeda Co. Ltd.	230
219	Krell Software	35
182	Leading Edge	2
218	Lifeboat Associates	11
274	Link Systems	251
184	Little Genius	123
278	L.N.W. Research	55
208	L.I. Computer General Store	231
162	Magnolia Microsystems	246
320	Manhattan Software	234
207	Mannfred Electronics	231
208	McGraw Hill	235
228	Meta Technologies	277
187	Micro Ap	45
197	Micro Architect	248
195	Micro Distributors	281
209	Micro Focus Inc.	125
155	Micro Lab	189
156	Micro Lab	191
153	Micro Lab	195
143	Micro Lab	197
185	Micro Learningware	68
210	Micro Mail	233
163	Micro Management	209
166	Microsoft Consumer Products	7
172	Microsoft Consumer Products	57
211	Micro Stand	253
247	Microsystems	281
224	Micro Technology Unltd.	207
212	Microworks	231
157	Mini Micro Mart	5
166	Minnesota Software	33
191	Mountain Computer	1
244	Mountain Software	51
225	Muse Software	233
226	Muse Software	253
220	NCTM	283
221	NEC America	18,17
285	Neeco	205
196	Net Profit Computers	229
288	NRI Schools/Elec. Div.	37
201	Omega Microware	230
213	Omega Sales	203
200	Omega Software	197
202	Omega Software	251
243	Omni Resources	159
174	Omni Software Systems	284
265	Omnitec Data	244
232	Optimized Systems Software	235
250	Orange Micro	181
289	Orion Software	284
169	Pacific Exchanges	61
169	Pacific Exchanges	245
169	Pacific Exchanges	281
169	Pacific Exchanges	285
186	Pan American Electronics	284
292	Pegasys Systems	244
235	Perry Oil & Gas	243
239	Peripherals Plus	79
239	Peripherals Plus	83
239	Peripherals Plus	252
280	Personal Computing	77
246	Phila. Area Computer Show	265
	Pocketbooks	187
296	Poly Paks, Inc.	243
*	Professional Software	81
251	Professional Software	133
297	Program Design Inc.	285
175	Program Store	179
282	Promethews Products Inc.	63
298	QT Computer Store	164,165
194	Quality Software	Cover 4
275	Quality Software	10
252	Racet Computes	263
	Rainbow Computing	85
299	Reliance Plastics	52
223	Rell	284
303	River Bank Software	91
229	Sebree's Computing	259
*	Retail Roster	273
230	Sentient Software	32
253	Silcon Valley Systems	263
263	Simutek Computer	53
238	Sirius Software	89–75
290	Small Business Computer	19
266	Software Connection	242
*	Software Arts	13
266	Software Connection	242
269	Software Publishing	31
234	Software Street	239
236	Software Technology	23
271	Spectral Assoc.	263
233	The Stocking Source	141
245	Strategic Simulations	59
268	Street Electronics	191
267	Sturges Engineering Software	208
187	Sublogic	39
272	Supersoft	241
*	Sybex	223
215	Sync	177
246	Syncro Inc	261
277	Systems Plus	175
276	Systems Plus of MD	208
218	Tampco Labs. Inc.	239
279	Time Management Software	267
193	Total Information Service	195
181	Trans Net Corp.	213
237	Triangle Systems	158
240	Videx	199
*	Vodex	127
*	Windjammer Cruises	275
283	York 10 Computerware	211
284	Zeitgeist	135

Creative Computing

300	Apple Software	201
300	Apple Blister Ball	237
350	Back Issues	248,249
350	Basic Computer Games	215
350	Best of Creative Computing	257
350	Cassettes Closeout	265
350	Computers For Kids	280
350	Computers In Mathematics	269
350	Computer Rage	173
350	Creative Computing Index	285
*	Gift Certificate	279
350	Katie and the Computer	286
300	Mixed Products	193
*	Subscriptions	284
*	Subscriptions	145
300	TRS-80 Software	183
350	T-Shirts	143

*Write Advertiser Directly

FAMILY RECREATION

CREATIVE COMPUTING

SUBSCRIPTIONS TO CREATIVE COMPUTING

Term	USA	Canada and Foreign surface	Foreign air
3 yrs (36 issues)	☐ $53	☐ $80	☐ $143
2 yrs (24 issues)	☐ $37	☐ $60	☐ $107
1 yr (12 issues)	☐ $20	☐ $29	☐ $50

☐ New ☐ Renewal

For a change of address, please attach old label.

BOOKS, POSTERS, RECORDS, GAMES

Quan.	Cat.	Title	List Price	Total
	3G	Binary Dice	$ 1.25	
	6A	Best of Creative Computing-Vol 1	8.95	
	6B	Best of Creative Computing-Vol 2	8.95	
	12C	Best of Creative Computing-Vol 3	8.95	
	6C	Basic Computer Games	7.95	
	6C2	More Basic Computer Games	7.95	
	6C4	More Basic Games-TRS-80	7.95	
	6C5	Colossal Computer Cartoon Book	1.95	
	6G	Cheapskate Games	4.95	
	6H	Be A Computer Literate	3.95	
	8Z	Computer Rage Game	8.95	
	9Y	Problems for Computer Solution	9.95	
	9Z	Teacher's Edition Problems for Computer Solution	4.95	
	10R	Computer Coin Games	3.95	
	12A	Kattie and the Computer	6.95	
	12D	Computers in Mathematics-A Sourcebook of Ideas	15.95	
	12E	Intuitive Computer Society and Ethics Bibliography	17.95	
	12B	Tales of the Marvelous Machine	7.95	
	12G	Computers for Kids-Apple	3.95	
	12H	Computers for Kids-TRS-80	3.95	
	12J	Computers for Kids-Atari	3.95	
	CR101	Computer Music Record	8.00	
		SUBTOTAL		

SOFTWARE T-SHIRTS BACK ISSUES

Quan.	Cat.#	Title	Price	Total

Books, Records, Games
$3 USA, $6 Foreign Shipping Charge
NJ residents add 5% sales tax
Magazine subscriptions
TOTAL

☐ Check or Money order enclosed (U.S. funds only)
☐ VISA ☐ MasterCard ☐ American Express

Card number

Expiration Date

Signature

Name

Address

City State Zip

CCLH

November, 1981 • Expires February 1, 1982

creative computing

(Please Print)

Name

Title

Address

City

State Zip

Please take a minute to answer the following questions. Your answers will help us make *Creative Computing* even better.

1. Are you a member of an amateur computer club?
☐ A. Yes ☐ B. No

2. Are you a member of a scientific, engineering or computer professional society?
☐ A. Yes ☐ No

3. Do you own a home video recorder?
☐ A. Yes ☐ B. No

4. Which of the following best describes your involvement with small computers?
☐ A. Hobby only
☐ B. Professional or business only
☐ C. Hobby and professional or business
☐ D. Educational purposes
☐ E. Research and development
☐ F. Other

November, 1981 • Expires February 1, 1982

creative computing

(Please Print)

Name

Title

Address

City

State Zip

Please take a minute to answer the following questions. Your answers will help us make *Creative Computing* even better.

1. Are you a member of an amateur computer club?
☐ A. Yes ☐ B. No

2. Are you a member of a scientific, engineering or computer professional society?
☐ A. Yes ☐ No

3. Do you own a home video recorder?
☐ A. Yes ☐ B. No

4. Which of the following best describes your involvement with small computers?
☐ A. Hobby only
☐ B. Professional or business only
☐ C. Hobby and professional or business
☐ D. Educational purposes
☐ E. Research and development
☐ F. Other

creative computing
P.O. Box 2976
Clinton, Iowa 52735

Place
Stamp
Here

creative computing
P.O. Box 2976
Clinton, Iowa 52735

Place
Stamp
Here

Place
Stamp
Here

creative computing
P.O. Box 789-M
Morristown, N.J. 07960

The Newest & Most Astounding Arcade Game that TALKS has Just Reached Planet Earth:

ROBOT ATTACK

BIG FIVE SOFTWARE

Ordering info for all games:

Super Nova, Galaxy Invasion Attack Force, Cosmic Fighter, Meteor Mission 2 and Robot Attack

our first name is Quality

Our popular space game, *Asteroids in Space*, is now *Meteoroids in Space*, with hyperspace, autobrake, and autofire. This exciting arcade game can be played with or without game paddles. Diskette $19.95.

Beneath Apple DOS

This best-selling 170 page technical manual tells you everything you want to know about Apple's Disk Operating System. Book $19.95.

Beginners and experts both enjoy this Othello* playing game that outplays Hayden's *Reversal*. Yet *QS Reversi* has features that *Reversal* doesn't have and costs less. Diskette $29.95.

LINKER
Links and relocates assembled machine language programs. Works with any assembler. Diskette $49.95.

FASTGAMMON
Known for outstanding graphics and speed of play, this popular program is the standard to which other computer backgammon games are compared. Cassette $19.95. Diskette $24.95.

CR

CROSS-REF
Prints out a cross-reference of the variables in your Applesoft program. Options include changing the name of a variable. *Cross-Ref* resides passively in memory with your Applesoft program. Cassette $22.95. Diskette $24.95.

FRACAS
A fantastic adventure game like no other. Up to eight players can journey in the land of Faroph at the same time, searching for hidden treasure and fending off monsters. Cassette $19.95. Diskette $24.95.

BABBLE
This amazing and amusing program will entertain you by twisting your stories around in a most delightful way. *Babble* also works with music and sound. It's a language all its own! Cassette $19.95. Diskette $24.95.

BENEATH APPLE MANOR
The original dungeon game for the Apple computer is still one of the best. Descend into a dangerous maze of underground corridors. See if you can find the Golden Apple. Cassette $14.95. Diskette $19.95.

BATTLESHIP COMMANDER
A superb version of the traditional battleship strategy game. Cartoons and sound effects help make this game fun for everyone. Cassette $14.95. Diskette $19.95.

ASTROAPPLE
Your computer becomes your astrologer, generating horoscopes and forecasts based on the computed positions of the heavenly bodies. Cassette $14.95. Diskette $19.95.

*Othello is a trademark of Gabriel Industries

6660 Reseda Blvd., Suite 105, Reseda, CA 91335
(213) 344-6599

CIRCLE 194 ON READER SERVICE CARD

QS
QUALITY SOFTWARE

ASK FOR QUALITY SOFTWARE products at your favorite computer store. If necessary you may order directly from us. MasterCard and Visa cardholders may place orders by calling us at (213) 344-6599. Or mail your check or bankcard number to the address above. California residents add 6% sales tax. *Shipping Charges:* Within North America orders must include $1.50 for shipping and handling. Outside North America the charge for airmail shipping and handling is $5.00. Pay in U.S. currency.